

SPRING SALE

The Outstanding Tape Recorder Value of the Year!

New LAFAYETTE 2-SPEED TAPE RECORDER
 FEATURES 4-TRACK MONAURAL RECORD PLAYBACK
 WITH 4-TRACK STEREO PLAYBACK*

Contains Every Quality
 Tape Recorder Feature

- Two Speeds—3 3/4 & 7 1/2 ips • Sensitive Hand-Held Dynamic Microphone with Swivel Desk Stand • Pause Lever Provides Instant Stop For Editing
- Record-Erase Safety Switch • Fast, Rugged Shift Lever Control • Extension Speaker Jack • High Impedance Monitoring Jack • VU Meter Recording Level Indicator • Electronic Track Selector Switch • Specially Designed Heavy Duty 6x4 PM Speaker • Separate Erase and Record Heads.

We've tested, we've compared and Lafayette's engineers have certified this new RK-137 Tape Recorder as containing one of the finest, quality constructed, smoothest performing tape mechanisms available. And, at its remarkably low price, the RK-137 must be ranked near the top in Lafayette's long history of best buys. Engineered to provide virtually every wanted tape recorder feature, the RK-137 performs brilliantly, with facilities for 4-track monaural record/playback and 4-track stereo playback. (When used with a second channel containing a tape head input such as found in a component Hi-Fi system) Controls are completely functional and are designed and arranged to make the RK-137 a genuine pleasure to use.

Features include: a rugged, easy to use shift lever for fast rewind, fast forward, play and record functions; a special push-button safety record switch assures against accidental erasure of tapes; velvet-smooth volume and on-off tone controls; a pause lever instantly stops tape in motion, especially useful for editing; track switch provides fast, dependable electronic switching between tape tracks 1-4 and 3-2. In addition a VU recording level meter has been incorporated to indicate correct volume-setting for recording. Speeds are adjustable from 3 3/4 to 7 1/2 inches per second by means of a simple capstan adjustment. Tape economy is unmatched—from a standard 7 1/2" 1200 ft. reel the RK-137 provides over 2 hours monaural record/playback time at 7 1/2 ips and over 4 hours at 3 3/4 ips. Jacks are furnished for microphone input, High-impedance Radio-Phono Input, Extension Speaker Output, Monitor Output and Stereo Head Output for a playback of 2nd stereo channel. RK-137WX Shpg. wt., 22 lbs. Net 89.50

ACCEPTS FULL 7" REEL OF TAPE



89.50

NO MONEY DOWN

INCLUDES
 LIGHTWEIGHT
 CARRYING CASE

LEVER
 ACTION
 CONTROL



RK-137

COMPLETE with MIKE, SHIELDED
 PATCH CORDS, EMPTY 7" REEL
 and 7" REEL RECORDING TAPE.

Response: 40-15,000 cps at 7 1/2 ips. 40-9,000 cps at 3 3/4 ips. Signal-to-Noise Ratio: 42db. Wow & Flutter: less than 0.3%. Interchannel separation. Complete in attractive vinyl covered two-tone case and equipped with a dynamic mike, cable assembly for recording from your phono or radio, stereo head input cable for stereo playback, 1200 ft. 7" Reel recording tape with a 7" take up reel. Size: 13 1/2 W x 6 1/2 H x 10 3/4 D. For 110-120 VAC 60 cycles operation.

SPEECHES
 PUBLIC MEETINGS



SCHOOL WORK
 VOICE TRAINING



TAPE
 FM
 BROADCASTS

NEW! LAFAYETTE MULTIPLEX ADAPTER KIT MODEL KT-220



Quality Stereo FM Multiplex
 At minimum cost

ONLY **19.50**

- Separation 30db at 400 cycles
- Self-powered • Ideal for Lafayette tuners with or without MPX output Jacks

Enjoy thrilling FM Stereophonic sound from any recent Lafayette Tuner or any other quality wide-band FM or FM-AM tuner with or without multiplex jacks. Hear the full range of audio frequencies in all the realism and magnificence of stereo sound by simply adding this low-cost Lafayette Multiplex adaptor kit. Engineered for anyone to build and operate, the KT-220 is easily connected to your tuners built-in multiplex output and special instructions are provided for connection to tuners without MPX output jacks. Coils are pre-aligned and only minimum adjustments are necessary. Self-powered, the unit may be hidden out of sight or installed remotely from your tuner.

The specifications speak for themselves: Separation—30db at 400CPS; Distortion—below 1%, noise filter controls: on-off with pilot light, Separation control, Tubes: 12AU7, 6BN8, 12AX7 plus a silicon rectifier.

The KT-220 Multiplex adapter is supplied complete with shielded cable for input and output connections; metal case and all parts plus the famous Lafayette detailed kit instruction manual. Front panel is finished in beige and ivory trim with contrasting beige and brown cabinet. Size 8 1/2 W x 4 3/4 D x 4 3/4 H" for 110-125 volts, 60 cycle AC. KT-220 Shpg. wt., 4 lbs. Net 19.50



WAS **54.50**

NOW

49.95

NO MONEY DOWN!

LOW COST 4-BAND SHORTWAVE BROADCAST RECEIVER

- Electrical Bandsread • Built-in "S" Meter • 3 Short-Wave Bands, 1 BC Band
 - AVC — Noiselimiter • Big 5 Inch Speaker • BFO • Phone Jack
- IN A SMARTLY STYLED DURABLE METAL CABINET

Now, you can tune in the world with this fabulous, new Lafayette HE-40 BC-SW receiver. Keep up to date with on the spot news coverage. Power packed superheterodyne circuit covers the broadcast band (550-1600KC) and shortwave from 1600 KC to 30 MC in four bands. The perfect radio for shortwave listeners. Features a precision electrical bandsread with slide rule bandsread dial, 0-100 logging scale for easy self-calibration. Separate bandsread tuning condenser and calibrated "S" meter for accurate tuning. Meter can be electrically adjusted by rear panel control. Sensitive circuit features AVC (Automatic Volume Control) to minimize blasting and/or fade out; Automatic noise limiter to reduce annoying interference. Includes convenient front panel B.F.O./selectivity control to allow for reception of CW (telegraphy). Also has convenient front panel headphone jack

which automatically disconnects speaker. Jack can be used to drive an external speaker. Built-in 5" PM speaker provides big, clear sound on all stations. Useful tone switch is included to vary sound to suit conditions, or taste. Three antennas (ferrite loop for broadcast band, adjustable 58" whip for short wave and wire antenna) provide high sensitivity and flexibility for best reception. Low impedance phones are recommended for use with this unit. Evenly illuminated dial for night-time tuning. Attractively styled steel cabinet with silver trim. Powered by 4 tubes plus a selenium rectifier. 1—12BE6; Converter, 1—12BA6; IF Amplifier, B.F.O., 1—12AU6; Audio Amplifier AVC detector; 1—50C5; Audio output. Operates on 105-125V; 50/60 cycle AC/DC. Size 13 1/2 W x 5 7/8 H x 8 3/4 D. Shpg. wt., 12 lbs. Net 49.95

NOW! NO MONEY DOWN when you use Lafayette's NEW EASY-PAY PLAN!

LAFAYETTE RADIO

NEW MAIL ORDER and SALES CENTER
 111 JERICHO TURNPIKE

Open Mon., Thurs., and
 Fri., 'til 8:45 p.m.

SHOP BY PHONE DEPT. WALNUT 1-7500
 ALL DEPARTMENTS WALNUT 1-7700

SYOSSET, L.I., N.Y.

JAMAICA	NEW YORK	BRONX	NEWARK	PLAINFIELD	PARAMUS	BOSTON
165-08 Liberty Ave. Jamaica 33, N. Y. AXtel 1-7000	100 6th Avenue New York 13, N.Y. WOrth 6-5300	542 E. Fordham Rd. Bronx 58, N. Y. FOrdham 7-8813	24 Central Avenue Newark 2, N. J. MArkett 2-1661	139 W. 2nd Street Plainfield, N. J. PLainfield 6-4718	182 Route 17 Paramus, N. J. COlfax 1-8800	110 Federal Street Boston 10, Mass. HUBbard 2-7850
Open MON. and FRI., 'til 8:45 P.M.	Open THUR. 'til 8:45 P.M.	Open THUR. 'til 8:45 P.M.	Open WED. 'til 8:45 P.M.	Open THUR. 'til 8:45 P.M.	Open MON., WED. & FRI. 'til 8:45 P.M.	Open MON., WED. 'til 8:45 P.M.

• ASSOCIATE STORES — SEE REAR COVER •

LAFAYETTE 7-Transistor Marine & Broadcast 2-Band Radio



Reg.
29.50

22.50

NO DOWN MONEY

9 SECTION
ANTENNA EXTENDED

EARPHONE

Carrying
Case


A MUST for Marine Enthusiasts

- Covers AM Broadcast Plus 1.6-4.8 MC. Marine Band
- Sensitive Receiver Uses 7 Transistors, 2-Diodes, And 1-Thermistor
- 2 Built-in Antennas, Including 9 Section Telescoping Antenna for Marine Band
- Operates on 2 Inexpensive Penlight Batteries
- Complete With Carrying Case, Batteries, and External Earphone
- A Must For Marine Enthusiasts
- Compact and Light-Weight

With this new sensitive transistorized radio, Lafayette answers the needs of the marine enthusiast. Designed to be used by the week-end sailor as well as the serious yachtsman, the FS-223 is a power-packed, 7 Transistor, superheterodyne receiver. It receives both the standard AM broadcast band and the Marine Band (1.6-4.8 MC). A built-in antenna is used for the broadcast band and a 9 section telescoping antenna for the marine band. The telescoping antenna is readily detachable and may be carried in the same manner as a pocket pen. The receiver circuitry utilizes 7 transistors, 2 diodes and 1 thermistor for power-packed performance. Simple selector switch allows choice of Broadcast or Marine Bands and a clearly marked slide dial makes tuning simple. The built-in speaker can be shut-off by inserting an external earphone (supplied) for personal listening. Operates on 2 inexpensive Z cells giving up to 3 times longer life than ordinary 9 volt batteries. Comes complete with 9 section telescoping antenna, carrying case and earphone. Measures only 5 7/8 x 3 1/2 x 1 1/2". Shpg. wt., 2 lbs.

FS-223L Net 22.50
Replacement batteries for FS-223 7 Transistor radio, 2 required. Net each .095
BA-155 Z Cells

NEW FAMOUS BRAND 19 INCH PORTABLE TV



A handsome contemporary styled portable with a full size 19" screen. Features built-in telescoping unipole antenna which gives excellent performance in most locations. Beautiful Beige and white vinyl case blends in with any decor. All most used controls are top and side mounted. Includes AGC


control to adjust picture contrast to optimum in weak or strong signal locations. Provisions for external antenna. For 117V AC only. Dimensions: 20 1/2 x 15 1/2 x 11 1/2" D. Shpg. wt., 60 lbs. FS-500WX

Net 127.50

Only
127.50
No Money Down

- BUILT-IN TELESCOPING ANTENNA
- THIN-LINE STYLING
- BIG 19" SCREEN

LAFAYETTE 9-TRANSISTOR PORTABLE 3-BAND RECEIVER



WAS 49.95

NO MONEY DOWN

NOW
39.95

- Three Bands Long Wave Weather Band 190-400 KC Broadcast—540-1600 KC Short Wave Marine Band 1.6—5 MC
- Built-In Quality Speaker
- Telescoping 9 Section Antenna
- Earphone With Cord, Plug, and Leather Case
- Sensitivity Control
- Tone Control
- Powered by 4 Inexpensive 1.5V Batteries
- An Outstanding Value At Any Price
- Compact, Lightweight, Self-Contained
- Jack For External Speaker
- Microphone Adapter for P.A. Use

A mighty-mite in any class, the Lafayette 3 band portable outperforms many home radios. Combining extremely sensitive receiver circuitry with compact design, this receiver is the answer to many boatmen, aviators, weather observers, and outdoorsmen. Giving versatility rarely obtainable in other portable receivers, this unit covers Long Wave, Broadcast, and Shortwave Marine Bands. It can be used to receive Weather, Broadcast, Marine, Aviation, Beacon, and Ham Stations. Features a handsome cabinet with clearly marked slide-rule dial, Nine Transistors, 2 diodes, and 1 thermistor. Built for years of trouble-free operation. SPECIFICATIONS: BANDS—190-400 KC, 540-1600 KC, 1.6-5MC. CONTROLS—ON-OFF Switch, Volume, Tuning, Sensitivity, Tone, and Band Switch. Two antennas—A 9-section telescoping antenna for long and short waves and a powerful built-in ferrite antenna for Broadcast stations. PUSH-PULL AUDIO POWER OUTPUT STAGE. OUTPUTS—2 Phone jacks, phono. This compact, highly sensitive receiver comes complete with a handsome leather carrying case, earphone, plug, earphone case, cord, shoulder strap, battery and adapter for an external speaker. Size—8 1/2 x 4 7/8 x 1 1/2". Carrying weight—less than 3 lbs. Shpg. wt., 4 1/2 lbs. FS-93L Replacement battery for above receiver (Four Required). BA-156

Net 39.95

Net each .13

WEATHER, AVIATION, BEACON, MARINE, AND STANDARD BROADCAST BANDS

EMPLOYS 9 TRANSISTORS, 2 DIODES, PLUS A THERMISTOR FOR HIGH GAIN PERFORMANCE

For The First Time A Radio That Receives 190-400 KC Weather, Airplane and Direction Beacon Band Plus 1.6-5 MC Marine Band Plus Broadcast Band

For Planes

For Boats

Weather Reports



- Adapter for External Speaker
- Earphones with Cord, Plug and Case
- PRECISION DESIGN FOR TOP PERFORMANCE


LAFAYETTE "MINI" 6 TRANSISTOR RADIO

ONLY 13.98

- 6 Transistors Plus Germanium Diode and Thermistor
- Vest Pocket Size—Only 3 1/2" H x 2 1/2" W x 1" D.
- Weighs only 7 ounces with batteries
- Night Powered For Economy—Long Life
- Earphone Jack Built-in For Private Listening
- Rich Tone Dynamic Speaker
- Trouble-Free Printed Circuit
- Built-in Ferrite Bar Antenna
- Superheterodyne Circuit

A truly remarkable radio, the "MINI" 6 is so compact and lightweight (just 7 oz.) you hardly know you're carrying it—turn it on and get the biggest, clearest sound yet, from a pocket 6 transistor set. Precision engineered—true superheterodyne printed circuit board assures long trouble-free operation. Push-pull audio output, 6 transistors, one diode and one thermistor are utilized to obtain really phenomenal reception across the entire broadcast band. Only 2 two inexpensive penlight cells are required. This cuts down battery drain and lengthens playing time considerably over ordinary single cell radios. 'Jewel' black and gold case of durable plastic and soft attractive black leather carrying case with attached earphone pouch complete this smart set. Includes 2 batteries, carrying case and matched earphone for personal listening. All at our low, low price. Shpg. wt., 1.5 lbs.

FS-235L "MINI" 6 transistor Radio Net 13.98
Extra batteries for FS-235L Type Z (2 required). Shpg. wt., 4 oz. Net ea. .095
BA-155



CARRYING CASE

EARPHONE

BATTERIES

NEW! LAFAYETTE FM TUNER

FULLY WIRED — NOT A KIT


Only

16.95

- SLIDE RULE TUNING DIAL
- SIMPLEST OPERATION

- CONNECTS TO HI-FI, TV or RECORDER

MULTIPLEX OUTPUT JACK



A Lafayette low cost exclusive! The Model FS-234 Tuner is a real compact beauty. Ideal for use as a "second" FM Tuner—perfect for Students and Teenagers. Just one cable connects it to your Hi-Fi amplifier, TV or tape recorder input to give you static free FM listening enjoyment. Features a built-in multiplex jack for future adaptor installation if desired. Complete with 1 connecting cable. Most radios, TV sets, phonographs, and tape recorders have phono input jacks to take the shield-plug connection

from the tuner. For equipment not provided with input jack, the necessary connections can easily be made by any serviceman. SPECIFICATIONS: Tuning Range: FM 88 to 108 MC. Controls on/off—volume, Tuning Antenna: Provision for external twin lead antenna. Power: 110-125 VAC, 30 watts. Tubes: (2) 12BA6 12DT8, 12AL5. Size: 6 1/2 x 4 1/4 x 5 1/4" D. Shpg. wt., 4 lbs.


FS-234

Net 16.95

7 TUBE AM/FM TABLE RADIO

NEW!

- 7 tubes, Selenium Rectifier
- Quality 4" PM Speaker
- 2 Built-in Antennas
- Terminals for Remote Speaker and Tape Recorder Input
- Pilot Light



Just Compare

24.50


NO MONEY DOWN

Styled beautifully to grace any decor this set has all the power to play well even on weak stations. 2 bands provide standard AM broadcasts and static-free FM. Large easy-to-read slide rule dial with big clear numerals make tuning easy. Jeweled pilot light indicates when set is turned on. For those who desire remote reception, an external speaker jack is provided on the rear. Tape recording enthusiasts will enjoy the handy input for tape recorders. For better FM fringe area reception provision has been made for adding an external FM antenna. For normal use in strong signal areas a built-in wire antenna is used for FM and a high gain Ferrite-core for AM. Tube complement: 12DT8, 12BE6, (2) 12BA6, 12AV6, 12AL5, 35C5 plus selenium rectifier. For 117V 60 cycle AC. Size: 12 1/2" W x 5 1/2" H x 6 3/4" D. Shpg. wt., 7 lbs.

FS-126 Ebony Net 24.50
FS-127 Ivory Net 24.50

NEW!

LAFAYETTE AM/FM CLOCK RADIO



39.95

- Sleep-Switch - Lulls You To Sleep
- Completely Automatic
- AC Appliance Outlet
- Big Set Tone

NO MONEY DOWN

The FS-239 combines a fully automatic Telechron clock movement with a superb AM-FM broadcast radio. Handy sleep-switch permits you to slowly drift-off to dreamland while the radio 'shuts itself off' at a preset time. A buzzer alarm is included. In addition to a standard AM broadcast radio, a quality FM radio will expand your listening pleasure plus a 600 watt appliance outlet — useful to turn on the coffee pot, light etc. Slide rule dial for easier tuning. Beautiful low boy plastic cabinet in antique white with gold trim. Tubes: 50C5, 12AU6, 12AL5, 12BA6, 12BE6, 17EW8 plus a selenium rectifier. Size: 14 3/4" x 6 1/2" x 6". Imported
FS-239 Shpg. wt., 8 lbs. Net 39.95

NEW! FM-AM DELUXE TABLE RADIO

WITH DUAL SPEAKERS



39.50

NO MONEY DOWN

- 7 Tubes plus 1 Selenium Rectifier
- Your Choice of Rich Walnut or Mahogany Wood Cabinets
- Two 4" Speakers
- Built-In Ferrite Core Antenna
- Provision For Remote Speakers & Tape Recorder

Sound, performance and features that are astounding in table model radio at this low Lafayette price. Powerful 7 tube plus rectifier FM-AM circuit pulls in stations loud and clear with an absolute minimum of distortion. Two high-quality 4 inch speakers assures you of full fidelity on both FM and AM. Controls include: Power Switch—Tone Control, Volume Control, FM-AM Band Selector and Tuning Control. Output terminals located at the rear provide for the addition of a remote speaker or for recording with your tape re-

recorder. Cabinets are beautifully crafted and finished in your choice of rich walnut or mahogany woods. Beautifully styled to fit with virtually any decor. Supplied complete with wire antenna for FM. Covers 88 mc - 108 mc on FM; 5.3 to 10 Kc on AM. Size: 17 1/2" W x 7 1/4" H x 5 3/4" D. For 117V AC 60 cycle operation. Imported.

FS-123 Mahogany Cabinet Net 39.50
FS-125 Walnut Cabinet Net 39.50

LAFAYETTE QUALITY RADIOS AT SENSIBLE PRICES

9 TRANSISTOR FM/AM PORTABLE RADIO



- FM BAND 88-108MC
- AM BAND 530-1600KC
- BIG TONE PM SPEAKER
- PUSH BUTTON CONTROLS
- 3 ANTENNAS


49.95

NO MONEY DOWN

This superb Lafayette radio will recreate for you all the glorious tones of thrilling, static-free FM programming as well as standard AM broadcast. Styled for tomorrow, the FS-245 features a beautiful black plastic case with carrying handle. Off, FM and AM modes are selected by positive push-buttons. A precision slide rule dial with high gear ratio tuning makes this set one of the easiest to tune. Two 22" telescoping antennas pull in most FM stations with ease while the large 3x5" PM dynamic speaker assures you of glorious tone. Other features include, built-in ferrite rod antenna for AM, tone control and 2 earphone output jacks. Sensitive circuit incorporates 9 transistors, 4 diodes 1 varistor, automatic gain control. Four inexpensive "C" type cells power the unit. Complete with batteries and earphone. Size: 9 1/2" W x 5 3/4" H x 2 1/2" D.
FS-245L Shpg. wt., 4.5 lbs. Net 49.95
BA-156 Extra Batteries for above. 4 Required Net ea. .13



LAFAYETTE "LONG DISTANCE" AM-SHORTWAVE TABLE RADIO



SW VALUE of The Year

26.50


NO MONEY DOWN

- Attractive Decorator Cabinet
- Power Packed 7 Tube Performance—5 Tubes (2 dual purpose)
- Large Slide Rule Tuning Dial with Automatic Indicator Lights
- Provision For External Phonograph • "Big Speaker" Sound

A smart new way to enjoy yourself—listen to short-wave radio! Never before has a SW receiver of this quality been offered at such a low, low price. Beautifully styled to fit into any room, the 231 features 7 tube performance from 5 tubes (2 dual purpose) for maximum station "pulling" power. Separate SW antenna terminal to permit antenna selection suitable for location. Large PM speaker and 3-step tone control enhance your audio pleasure. Extremely legible slide-rule dial has separate pilot lights of different color which automatically switch-on to quickly identify band in use. In addition a phono jack is provided in the rear of the set for connecting any external phonograph. Covers the entire broadcast band and SW band from 3.8—12 MC. Tubes: 6BE6, 6BD6, 6AV6, 6AR5, 6X4. For 117 V, 60 cycles AC. Size 16Wx5 1/4 Dx 5 1/2" H. Shpg. wt., 10 1/2 lbs. Imported
FS-231 Net 26.50

PACKED WITH POWER!

LATEST FM-AM PORTABLE RADIO FEATURES 14 TRANSISTORS PLUS 4 DIODES



- Drift-Free Non-Directional FM Tuning
- Precision Slide Rule Tuning
- External Hi-Fi Amplifier Jack
- Powerful FM Telescopic Antenna
- Automatic Frequency Control

54.88

NO MONEY DOWN

All the quality and performance of a high-fidelity AM-FM tuner in an easy to use portable radio you can carry anywhere. Two completely separate AM and FM sections employ 14 transistors plus 4 diodes for unmatched sensitivity and stability. Automatic Frequency Control together with a specially designed di-pole telescopic antenna provides drift-free FM reception. Additional features include: easy slide rule tuning; tone control knob, external hi-fi amplifier jack, earphone jack, built-in ferrite bar antenna and specially developed 3 1/2 inch speaker designed to provide exceptional tone quality even at the highest volumes. Operates on 4 low cost flashlight batteries—low drain provides up to 400 hours of operation from one set of batteries. Supplied with carrying case, but with earphone and batteries. Covers FM band range: 88 mc - 108 mc; AM: 535 Kc - 1600 Kc. Size: 9 1/4 x 7 1/2 x 2 3/4".
FS-119L Shpg. wt., 4 1/4 lbs. Imported. Net 54.88
Attractive leather carrying case for FS-119L above Net 3.95
FS-121L ea. Net .13
BA-156 Extra Burgess No. 1 Battery

New! LAFAYETTE EXECUTIVE DESK SET



19.50

- It's a 7-Transistor Radio!
- It's a Cigarette Box!
- It's a Pen Holder!
- Handsome Black Case with Gold Trim!
- Perfect Gift For The Man On The Way Up!

NO MONEY DOWN

Now a Three-in-one desk set. A powerful 7 transistor AM broadcast radio specially designed to harmonize with the entire unit. Radio operates on four economical penlight cells to give long dependable service. The dial face is tilted and tuning knobs top mounted for maximum legibility and accessibility. Includes Earphone too for private listening! Right hand portion holds an extra large compartment useful for cigarettes or paper clips, etc. Two convenient penholders complete the set (Pens are not included). Beautiful black and gold finish make a most attractive addition to a desk. The ideal gift. Complete with 4 penlight cells and earphone. Size: 11 1/4 W x 2 3/4 H x 6" D.
FS-238L Shpg. wt., 6 lbs. Net 19.50
Extra "Z" batteries, 4 required. Net ea. .095; 2 for .19
BA-155

BIG SAVINGS VALUES

Transistor™

SUPER BUY 5-TUBE AC/DC TABLE RADIO



8.95

- "Easy-Tune" Dial
- Attractive Decorator Cabinet
- For Home, Store, Office; Wherever Radio Pleasure is desired

This Lafayette SUPER-BUY features 5 tubes (2 Dual Purpose) giving peak performance for clear, steady sound. A sturdy 3 1/2" Alnico PM Speaker gives fine tone response. An unusual "Easy-Tune" dial makes station selection simple. The built-in antenna brings stations in loud and clear. Covers the entire broadcast band from 530 to 1600 KC. Tubes: 1-12BE6, 1-12BD6, 1-12AV6, 1-50C5, 1-35W4. Will operate on 105-125 volts AC or DC. Dimensions 4 1/2" high, 6 3/4" wide, 3 1/4" deep. Shpg. wt., 3 lbs. Net 8.95 FS-240

"CONTEMPORARY" AC/DC RADIO


- Styled For Any Decor!
- Priced For Every Pocket!
- Put One In Every Room!
- 5 Tubes For Peak Performance!
- Swivel Base

10.99



A "better" 5 tube radio — engineered and styled to last. Petite, contemporary design maintains clean, good looks and peak performance. 5 tubes (2 dual purpose), plus a Mi-Q ferrite rod antenna pulls in more distant AM stations. 3 1/2" P.M. speaker, properly baffled in a sturdy, vented cabinet for clear tonal quality. Muted colors to match any color-scheme; gold trim. Pedestal base swivels for sound and reception directivity. Cabinet measures 8 1/2" x 4 1/2" x 4" overall. Tubes: 35W4, 50C5, 12AV6, 12BA6, 12BE6. For 117 V. A.C./DC. Shpg. wt., 3 lbs. Net 10.99 FS-233

NEW! HOUSE N' CAR RADIO



18.66

- Plays in Any 12V. Car or Boat or on 117V AC/DC
- No Installation — Just Plug in Lighter
- Needs No Outside Antenna
- Complete With Generator Condenser and Noise Suppressor

Play this radio anywhere! In the home — car — boat — trailer! Any place you can obtain a 12V D.C. or 117 V AC/DC supply! The radio (our FS-233) and the new Dynamo inverter form a customized package to suit a wealth of needs. You can even run your shaver in your car or boat! Shpg., wt., 5 lbs. Net 18.66 SP-229

NEW 9 TRANSISTOR 3 BAND PORTABLE RADIO

- Receives Standard AM Broadcasts, International and Marine on 3 Bands.
- Three Built-in Antennas—30 Inch SW Telescoping whip; 2 Ferrite Rod Antennas for BC Band and Long wave.
- AGC For Steady Reception
- Variable Tone Control
- Earphone For Private Listening
- Hi-impact plastic Case
- Combination Handle and Easel Stand



27.95
NO MONEY DOWN

- 9 TRANSISTORS, 1 Diode plus one Thermistor for powerful reception
- Includes short wave Listening chart • with carrying case, earphone and batteries


You'll get tremendous listening pleasure from this smart looking all-transistor portable. Three separate bands will afford the utmost in varied listening. The Standard AM broadcast band includes markings of two conrad stations for quick easy location on the dial. The long wave band between 130 and 400 KC provides Marine, Aeronautical and FAA weather broadcasts and the 4 to 12 MC Shortwave band enables you to hear International and Ham Stations. Truly a unique opportunity to explore the world's airwaves. Precision engineered the FS-128L features high sensitivity and selectivity with separate mixer and RF oscillator Stages. Self-compensating AVC avoids sudden blasts of volume and an AGC Transistorized Stage prevents sound Fade-out when the radio is repositioned. A

true-tone 2 1/2" Alnico Speaker and push-pull output Stage provide the finest audio reproduction. Other features at no extra cost include three separate built-in antennas for each band including a 30" telescoping whip for better short wave reception; precision tuning on an indirect slide views dial; variable tone control; separate battery compartment to minimize damage from leaky batteries; high impact plastic case, resists breakage and chipping and a combination handle and back easel stand for easy placement on table or desk. Operates on 4 inexpensive penlight cells for long life. With leather carrying case, strap, earphone and set of 4 batteries; Size: 6 1/4" x 4 1/2" x 1 1/4". Shpg. wt., 1 1/2 lbs. Net 27.95 FS-128L
BA-155 Replacement Batteries Net ea. .095


AUTOMATIC 6-TRANSISTOR CLOCK-RADIO with 7-JEWEL PRECISION ALARM-WATCH

- 7-Jewel, 11 Ligne, One-Day Alarm Movement
- Automatically Turns Radio On or Off
- Superhet Circuit — 6 Transistors, 1 Diode, 1 Thermistor
- Pocket Size — 4 3/4" x 3 1/4" x 3/4"
- Complete With Earphone, Batteries and Handsome Gift Case

29.95
NO MONEY DOWN




More than just a clock-radio, the FS-124 is an all-transistor clock-radio featuring a patented 7-jewel watch movement with a 11 ligne one-day alarm . . . automatically turns the radio on at a preset time or lets you go to sleep to music and automatically shuts off. The superhet circuit uses 6 transistors, one diode and one thermistor for more power and better sensitivity. Other advanced engineering features include AVC, push-pull output stage, ferrite rod antenna, 2" speaker, gear vernier tuning. Magnifying optic glass over dial plate for easier selectivity. Operates on 3 inexpensive penlight batteries. High-impact plastic case resists breaking and chipping. Complete with earphone for private listening, batteries, gift case. Shpg. wt., 2 lbs. Net 29.95 FS-124L



Extra penlight batteries for above. Net ea. .095 BA-155

NEW GRANCO STEREO MULTIPLEX RADIOS



38.95

NO MONEY DOWN



28.95

23.95

STEREO FM/AM RADIO

Compact, smartly styled table radio plays AF, FM and FM stereo multiplex with the SC-3 Speaker-Amplifier companion. Exclusive "Auto-G-Tuner" assures sensitive, drift free performance. Built-in Linetenna requires no installation. Phono input jack. High power 6 tube chassis provides 8 tube performance. Easy-view window dial and vernier tuning. Cabinet is completely enclosed. Attractive gray with white grill. 9 1/2" x 4 1/2" x 5 1/2" H. Shpg. wt., 7 lbs. Net 38.95 DR-17 Granco 703

attaches the SC-3—no installation necessary. Powerful speaker and amplifier. Volume control and function selector switch. For quality stereo at a modest price. Available in Grey. Size: 9 1/2" x 4 1/2" x 5 1/2" H. Shpg. wt., 5 lbs. Net 23.95 DR-18 Granco SC-3

Acoustically Matched Stereo Pair Models 703G & SC-3. Shpg. wt., 12 lbs. Net 58.95 DR-19

Low Cost Stereo FM Radio

Super powered, high sensitivity 5 tube chassis provides 7 tube performance. New hand wired detector circuit offers hi-fi and stereo-multiplex at exceptionally low cost with the use of the SC-3, matching FM multiplex speaker/amplifier unit. Other features includes new auto-G-tuner for drift free performance, easy-view window dial with vernier tuning, phono input jack and built-in antenna. Decorator cabinet encloses entire set. Gray only. Shpg. wt., 6 lbs. Net 28.95 DR-20 Granco Model 603G

STEREO COMPANION FOR GRANCO FM RADIOS

- Acoustically Matched
 - Plugs in—No Attachments Necessary
 - Doubles your Sound
- Specifically designed to match Granco radios 603 and 703 both acoustically and aesthetically. For perfect stereo FM reception, an interconnecting plug-in cable

Combination of Model 603 FM Radio and SC-3G Stereo Companion. Shpg. wt., 12 lbs. Net 51.50 DR-21

ULTRA-MINIATURE 3 TRANSISTOR HEARING AID



29.50
with Battery

- Extremely Light In Weight - Less Than One Ounce
- Extremely Compact; Dimensions: 2 3/8" Long, 3/4" Wide and 3/16" Thick
- Uses Inexpensive, Long Lasting Mercury Cell

Only 2 3/8" x 3/4" x 3/16" — almost as small as a tie clasp, this precision unit employs an advanced 3 transistor circuit powered by a tiny inexpensive mercury cell. A 180° rotating volume control provides exactly the amount of amplification necessary, while a MIC provides sensitivity for telephone use. Supplied with 3 ft. TEL lever readjusts sensitivity for telephone use. Supplied with 3 ft. Fresh-tinted cord, earpiece, velvet lined leather carrying case. Mercury cell and instructions. Shpg. wt., 1 lb. Net 29.50 F-758L
BA-523 Extra Battery (Mallory RM 625R) Net .30

SUB-MINIATURE 4-TRANSISTOR HEARING AID

- Lightweight—Weighs Less than 2 oz. Including Battery
- Small Enough To Be Carried in Breastpocket
- 4-Position Tone Control
- Unique Telephone Switch Allows Telephone Conversation
- Latest Electro-Magnetic Earphone and Miniature Crystal Microphone
- Utilizes Economical Penlight Battery

ONLY 2 1/2" LONG x 1 3/4" WIDE
22.50 x 3/8" THICK

Features an extremely advanced circuit with 4 transistors, a high performance crystal microphone, 3 ft. thin plug-in, colorless flexible cord and a unique magnetic earphone providing the clearest reception and sound reproduction yet achieved. Supplied with leather carrying case, earphone and battery. Shpg. wt., 1 lb. Net 22.50 F-480L
BA-153 Extra Battery (1 required) Burgess NE type. Net .08
F-567 Extra Plug-in Cord For F-480 Net .55
F-568 Extra Earphone For F-480 Net 1.59



LAFAYETTE SPECIAL PHONOGRAPH SALE

with **FREE DIAMOND STYLUS**

NO MONEY DOWN
49.95



LAFAYETTE AUTOMATIC STEREO PHONOGRAPH
Compatible—Plays Both Stereo and Monaural Records • 4-Speed British Changer

New, attractively styled automatic stereophonic phonograph featuring the latest Monarch 4-speed automatic intermix record changer. Complete with stereo crystal turnover cartridge with dual sapphire stylus. Plays both stereo and monaural records. Among many features are automatic record intermix mechanism, automatic motor shut-off at the end of last record, automatic arm return, free floating motorboard eliminating acoustic feedback. Careful design assures long life and freedom from trouble. Takes all record sizes, and plays all 4 speeds: 16 2/3, 33 1/3, 45 and 78 RPM. Controls include separate volume controls for each channel and dual channel tone control. Built-in Alnico 5 PM speaker provide clean, balanced sound. Second Alnico 5 PM speaker is housed in the removable phonograph cover. 8 ft. cable supplied, permits placement of second speaker for optimum stereo effect. Covered in charcoal linen leatherette with oyster white trim. Tubes 2-50C5, 1-12AX7 and 35W4 rectifier. Size: 19 1/2 x 15 1/2 x 8 1/4". Shpg. wt., 23 lbs. Net 49.95

NO MONEY DOWN
62.95



LAFAYETTE Deluxe AUTOMATIC STEREO PHONOGRAPH
• 3 Speaker System • 4-Speed V-M Changer • Plays Both Stereo and Monaural Records

New Lafayette deluxe automatic stereophonic phonograph features the famous 4 speed V-M changer. Plays all speeds: 16 2/3, 33 1/3, 45 and 78 RPM. Plays all sizes: 7", 10" and 12" records. Has such features as 4-pole motor, automatic shut-off after last record, etc. Supplied with turnover cartridge. Separate volume controls adjust optimum balance for perfect stereo realism. Separate bass and treble controls permit tonal adjustment of both channels. Has 3 Alnico V PM speakers: 1 in main case and 1 in each wing. Wings may be left in position or can be detached from the sides and placed apart for individual stereo requirement. Tubes: 2-35C5, 1-12AX7, 1-50EH5, 1-35W4 rectifier. Attractive black gold branch leatherette case. Size: 20x15 1/2x9". Shpg. wt., 29 lbs. Net 62.95


WITH FREE DIAMOND STYLUS



LAFAYETTE AUTOMATIC MONAURAL PORTABLE PHONOGRAPH
• Alnico V PM Speaker • Plays 4 Standard Record Speeds • Complete With Crystal Turnover Cartridge

New, attractively styled automatic monaural portable phonograph featuring 4 speed, 16 2/3, 33 1/3, 45, 78 RPM. Consists of the latest famous British-made Monarch automatic record changer. High-quality Alnico V PM speaker. Uses heavy-duty 4-pole induction type motor for constant speed and minimum "wow". Automatically plays all speeds, and takes all record sizes—7", 10", 12" Intermixed in any order. Plays 12" records with lid closed. Arm automatically returns to the rest position and motor shuts off after last record. Lightweight pickup arm has high output crystal turnover cartridge with sapphire stylus. Controls: Tone, Off-On Volume. Durable and attractive cabinet covered in fine leatherette, black with white trim. For 110-120 volts, 60 cycles, A.C. Size 15 1/2 x 16 1/2 x 8 1/4". Shpg. wt., 20 lbs. Net 39.75

NO MONEY DOWN
39.75



You get **BOTH** sapphire and diamond styli at no extra cost!
FREE DIAMOND NEEDLE OFFER EXPIRES APRIL 30th, 1962

MONAURAL RECORD PLAYERS



13.95

"LEADER" 4-SPEED MANUAL
Plays up to 12" monaural records at 16 2/3, 33 1/3, 45 or 78 RPM. A single lever selects any speed. The lightweight pickup arm is equipped with a single all-purpose needle for all records. Has volume control with on-off switch. Fine quality Alnico 5 PM speaker. Attractive leatherette covered case. For 110-120 volts, 60 cycles. Size 11 1/2 x 10 1/2 x 5". Shpg. wt., 9 lbs. Net 13.95



18.45

STANDARD 4-SPEED MANUAL
With this portable phonograph you can play any record up to 12" size at 33 1/3, 45 or 78 rpm, or at the new "Talking Book" speed of 16 2/3 rpm. A single lever selects any speed. The lightweight pickup arm is equipped with a turnover cartridge with dual sapphire stylus. Has both tone control and volume control with on-off switch. Fine quality Alnico 5 PM speaker. Attractive 2-tone leatherette covered case. For 110-120 volts, 60 cps. AC. Dimensions 14x11 3/4x6 1/4". Shpg. wt., 10 lbs. Net 18.45


OUR finest PORTABLE PHONO!

With FREE Diamond Stylus

NO MONEY DOWN!

89.50

- FULLY AUTOMATIC GARRARD CHANGER
- TWO POWERFUL 10 WATT AMPLIFIERS
- SECOND SPEAKER EASILY DETACHED
- 3 SPEAKERS



Plays Both Stereo and Monaural!

A complete portable and compact stereo phonograph in one convenient case. System uses the well-known Garrard High-Fi 4-speed stereo changer which features true intermix of 12" and 10" records in any order with instant selection of either automatic or full manual operation. Uses a stereo turnover cartridge to play all your records—whether monaural or stereo. Two powerful 10 watt amplifiers provide a frequency response of 50 to 12,000 cps. Controls included: Master Volume; Remote

speaker volume; Master treble; Master bass. Detachable front speaker cabinet houses a 6" x 9" speaker with 9 ft. extension cord. Main unit houses two speakers—one 6" x 9" woofer and one 4" tweeter. Phonograph has easy-grip handle on attractive smart-looking Pyroxylin covered case. Size: 23x16x9 1/4". Shpg. wt., 40 lbs. Available in choice of 2 attractive coverings. Net 89.50

LAFAYETTE Exclusive 4-TRACK STEREO TAPE

By special arrangement with one of America's finest recording companies, Lafayette presents its own superbly recorded stereo tape. They're complete—about 45 minutes playing time on a 7" reel. Shpg. wt., 1 lb. per tape.

349



BIG SAVINGS

STRAUSS WALTZES IN HI-FI. Its a festival of Strauss' Viennese waltzes with the Vienna Festival Orchestra, Rudolph Langer conducting. Old favorites include Emperor Waltz, Gypsy Baron Overture, On the Beautiful Blue Danube, others. STOCK NO. RM-19

THE TOMMY DORSEY STORY. It's the great all-time hits of the fabulous Tommy Dorsey in the great Dorsey style. Top favorites include Boogie Woogie, Song of India, Marie, others. STOCK NO. RM-23.

DYORAK: Symphony No. 5 in E Minor, "From The New World." A vibrant performance of Dvorak's classical favorite, by the Prague Symphony Orchestra, conducted by Ladislav Kiras. STOCK NO. RM-70

THE ROMANTIC THEMES OF TSCHAIKOVSKY. From the great pen of the master, music filled with melody and tenderness. The Rome Symphony Orchestra in excerpts from Capriccio Italian, Violin Concerto in D, and other Tschaikevsky favorites. STOCK NO. RM-72

MOONLIT MOODS. The best of American popular music, played in superbly sophisticated arrangements featuring the lush strings of Donatoni, Stardust, Star Eyes, How High the Moon, etc. STOCK NO. RM-74

EVERYBODY LOVES A BAND. One of the great bands of Europe, the Royal Artillery Band, in a rousing Salute to America. Thrill to the sound of Anchors Aweigh, El Capitlan, Stars and Stripes Forever, and many more. STOCK NO. RM-76

DIXIE. The wonderful sound of Dixieland jazz played by the Empire City Six. Top hits include Limehouse Blues, Muskrat Ramble, Black and Blue, Wolverine, and others. STOCK NO. RM-22.

DANCE TIME U.S.A. Memories are made of these great hits, set to dance time by Raymond Porter and The Sheridan Society Orchestra. The pulsating tunes include Somebody Loves Me, Birth of the Blues, Flying Home, and more. STOCK NO. RM-24.

CHA CHA CHA and MERENGUES: Pupi Campo's great band recreates a dozen authentic Cha-Chas and Merengues for your listening and dancing pleasure. Quiereme, Tea for Two Cha Cha, etc. STOCK NO. RM-71.

BEETHOVEN: Symphony No. 6 in F Minor, "Pastoral." A magnificent interpretation of Beethoven's classic "Pastoral." Rudolph Langer conducts the Frankfurt Symphony Orchestra. STOCK NO. RM-73

FAVORITES FROM FAR AWAY. A collection of the most beloved songs from all over the world, played in beautiful arrangements by Mat Matthews and his orchestra. Dark Eyes, Lili Marlene, Greensleeves, and more. STOCK NO. RM-75

NEW! 4-TRACK FULL STEREO TAPE

Famous popular selections on 300-ft., 3" reels. 3 1/2 IPS, 4 selections per reel, 15 minutes playing time. Splicing labels, title tabs and instructions with each reel.

CONTINENTAL MUSIC • LATIN MUSIC • FAMOUS POPULAR SELECTIONS on 300 ft., 3" REELS • MOOD MUSIC • SHOW TUNES



LAFAYETTE SPECIAL PRICE 1.69

Majorca; Brasillia; Mexican Nights; Bygone Times. STOCK NO. RM-35.
Mi Cha Cha Cha; No Me Digas Que No; Manzanillo; Ay Manita. STOCK NO. RM-36.
Starlight Mambo; Silbando; Mambo at the Zenda; Ana Morena. STOCK NO. RM-37.
April in Paris; Mon Coeur est un Violin; The Continental; Monte Carlo Melody. STOCK NO. RM-38.
Old Black Magic; Sleepy Lagoon; I Gave My Heart; Petticoats of Portugal. STOCK NO. RM-40.
Baubles, Bangles and Beads; Two Faces in the Dark; A Certain Smile; Arriverderci Roma. STOCK NO. RM-41.
Spanish Fiesta; La Macarena; La Corrida; Andalucia. STOCK NO. RM-39.

Merry Widow Waltz; Three Coins in the Fountain; September Song; Gigi. STOCK NO. RM-42.
Bess, You is My Woman; Just for Once; Tammy; Que Sera, Sera. STOCK NO. RM-43.
Look Who's in Love; It's Not for Me to Say; I'll Never Stop Loving You; Sweet Sue, Just You. STOCK NO. RM-44.
Blue Waltz; Good Morning, Cindy; Tarantella; Terrible Infant. STOCK NO. RM-45.
Beer Garden Polka; Britta Polka; Petite Polka Parisienne; Amanda Polka. STOCK NO. RM-46.
Magician's Wedding Dinner Polka; Slap Happy; Paganini Polka; Bird Polka. STOCK NO. RM-47.
Look for the Silver Lining; A Fine Romance; Make Believe; Why Do I Love You. STOCK NO. RM-48.
Miss Otis Regrets; In the Still of the Night; Don't Fence Me In; Just One of Those Things. STOCK NO. RM-49.

With a Song in My Heart; Manhattan; It Might as Well Be Spring; This Can't Be Love. STOCK NO. RM-50.
Georgia on My Mind; Blue Orchids; Stardust; Two Sleepy People. STOCK NO. RM-51.
Around the World; Love Letters in the Sand; Gondoliere; Dinah. STOCK NO. RM-52.
You Belong to My Heart; Symphony; Twelfth Street Rag; Picnic. STOCK NO. RM-53.
You Made Me Love You; Happy Days are Here Again; Carolina Moon; Sunshine Serenade. STOCK NO. RM-54.
If You Knew Susie; Almost Like Being in Love; Over the Rainbow; Side by Side. STOCK NO. RM-55.
Crazy Feelin'; Take it Easy Boy; Jive After Five; Walking My Baby Back Home. STOCK NO. RM-56.
Lover Come Back to Me; Short Cut; Love Walked In; Ain't She Sweet. STOCK NO. RM-57.



NEW! LAFAYETTE HE-20B CLASS D Deluxe CITIZENS BAND TRANSCEIVER



LAFAYETTE'S SENSATIONAL CITIZENS BAND TRANSCEIVER—NOW WITH THESE ADDED DELUXE FEATURES!

- 8 Crystal Receive Positions
- 8 Crystal Transmit Positions
- Built-in 6 or 12 Volt Power Supply
- Pi-Network gives optimum line and antenna matching for greater power output.
- Improved Series Gate Noise Limiter

Not A Kit!
COMPLETELY WIRED!

109⁵⁰

NO MONEY DOWN

WITH Foolproof Dependable Relay Switching As Found In Most Expensive Equipment. NOT Electrical Switching With It's Voltage Hazards. NOT Electronic Switching With Inefficiency Due To Tube and Parts Deterioration.


Quality engineering, design, and features give this Deluxe transceiver a place all-its-own in the Citizens Band Field. Operating within the limits prescribed by the FCC, the HE-20B supplies you with a highly efficient 2-way radio-telephone communications system from your office, truck, auto, boat, store, home, etc. Two or more will serve as an effective communications system over a distance of up to 20 miles or more, depending on the terrain and the height of the antenna.

3 dual function tubes, 1-Quadri-purpose tube, 3 tubes, and 2 Silicon rectifiers give 14 tube performance. The transmitter section features precision engineering to insure power-packed communications. The 5 watt-input crystal-controlled transmitter may be operated on any 8 of the 23 channels assigned by the FCC. The operating channel can be selected by a knob on the front panel (transceiver comes with pair of crystals for channel 9). The receiver circuits provide for 8 crystal controlled receiving channels plus a tuneable superheterodyne receiver that covers all 23 assigned channels, with a sensitivity of 1 microvolt. Effective built-in Squelch circuit quiets the receiver when no signal is being received. Series Gate Noise Limiter materially reduces ignition noise and other unwanted interference. An illuminated dial with planetary vernier tuning is clearly marked with channel numbers and lights up when tuned to any channel. New tuneable or fixed receiver switch permits selection of tuneable and fixed receive operation. The receiver terminates in 4" speaker amply supplied by a 2-watt audio power output section. The unit

comes complete with a push-to-talk ceramic microphone that is conveniently mounted to the side of the transceiver. Push-to-Talk operation is accomplished with a sturdy, dependable relay. An "S" meter calibrated in S units 1-9 and to 30 db. above S-9, allows measurement of incoming signal strength. The meter is wired with a switch to enable monitoring of final amplifier wattage. Incorporates Pi-network for optimum matching to 30-100 ohm antenna for high signal output. A low-loss antenna jack is mounted at the rear of the cabinet to accept the popular PL-259 connector used with dipole, ground plane, rod, and direct mounting (Lafayette HE-19) Antennas. Rugged, low silhouette case with a bracket handle for installation at any location and in any position. Tube line up 1-6AW8A, Oscillator/Amplifier; 1-6BA6, RF Amplifier and 1st Audio Amplifier; 1-6A05 Audio Output/Modulator; 1-6T8, ANL, Detector, AGC, Squelch Clamp and 2nd Audio Amplifier. Size 12x5x8 1/2"D. With 115 Volts AC/12 Volts DC or 115 Volts AC/6 Volts DC Power supply. Shpg. wt., 14 lbs.

HE-20BWX 115 AC/12 Volts DC	Net 109.50
HE-43BWX 115 Volts AC/6 Volts DC	Net 109.50
HE-830L Transmit Crystal (Specify Channel or Frequency)	Net 2.25
HE-22L Receive Crystal (Specify Channel)	Net 2.25
Direct plug in antenna for short distance communications.	
HE-19 Shpg. wt., 1 lb.	Net 3.95

EXCELLENT FOR BUSINESS, FARM, INDUSTRY, CAR, BOAT, PERSONAL AND SPORTS USE



LOOK AT THESE QUALITY FEATURES

- 1 14 Tube Performance, 3 Diodes
- 2 8 Crystal-Controlled Transmit Positions
- 3 8 Crystal-Controlled Receive Positions
- 3 Tuneable Receiver over all 23 channels
- 4 Calibrated "S" Meter with Switch To Measure Signal Strength and To Check on Wattage Input to Final
- 5 Dependable Push-To-Talk Ceramic Microphone & Relay
- 6 Adjustable Squelch Control
- 7 Receive Tuneable or Fixed Crystal Selector Switch
- 8 Illuminated Dial
- 9 Highly Effective Automatic Series Gate Noise Limiter
- 10 Built-in 12 or 6 volt Power Supply for Mobile Use





NEW! LAFAYETTE HE-15B SUPERHET CITIZENS BAND TRANSCEIVER!



MADE IN U.S.A.



Completely Wired - NOT A KIT!



Outstanding Performance, Design, and Ease-Of-Operation. Meets All FCC Requirements

ONLY **59.50** NO MONEY DOWN

THE GREATEST VALUE
in the CITIZENS BAND FIELD

NEW!
8 Crystal Transmit Positions
Increased Selectivity in IF's
Attractive Modern Styling

COMPLETE 2-WAY COMMUNICATIONS FOR BUSINESS, HOME, FARM, BOAT, AND SPORTS
Not Superregenerative but SUPERHET!
NOW WITH ADDED FEATURES

- 8 Crystal-Controlled Transmitting Positions
- Effective Full-Wave Variable Noise Limiter
- RF Jack on Front Panel
- Ceramic Temperature-Free Microphone
- Improved Selectivity and Power Output
- Superheterodyne Tuneable Receiver Over Full 23 Channels
- 4 Dual Function Tubes, plus 2 Single Function Tubes, plus 2 Rectifiers for 12 Tube Performance
- Planetary Vernier Tuning
- Complete with Transmitting Crystal for Channel 9

The Lafayette HE-15B Superheterodyne Transceiver is both a compact precision transmitter and receiver designed to operate on the new class D "Citizens Band." Two or more of these units furnish your own communications system covering up to a 20 mile or more radius depending on antenna height and terrain. The Transceiver features 8 crystal controlled transmitting channels operating at a maximum legal power input of 5 watts fully modulated, RF stage in both transmitter and receiver. The 8 position crystal selector on the front panel selects any one of 8 transmitting frequencies. These 8 crystals are readily accessible by means of a removable front plate. The superheterodyne receiver is tuneable over the full 23 channel band with 3 watts audio output, AVC, and an amazingly effective Full-Wave Variable Noise Limiter. The Noise Limiter is continuously variable from the front panel for diminishing ignition and other unwanted noise pickup.

RF jack on the front panel may be used to monitor the current in the final tube using external meter. Controls include a 3 position function switch (transmit, receive, and transmit with spring return), planetary vernier tuning plus variable noise limiter. Output impedance matches 52 and 72 ohm antenna with Amphenol type coax connector. Has large PM speaker; input jack for crystal or ceramic microphone; power receptacle in rear

for AC line and 6 or 12 volt external power supply. Supplied with single transmitting crystal for channel 9, high output ceramic microphone, and brackets for easy mounting of units in auto, boat, etc. Operates on 115 volts AC. Addition of 6 or 12 volt power supply (separately supplied) adapts transceiver for mobile operation. Size 10 1/4"Wx5 1/2"Hx6 3/4"D. Tube complement: 2-6U8A/6EA8, 1-6AL5, 1-6V6, 1-12AX7, 1-6AW8. HE-15BWX Shpg. wt., 11 lbs. Net 59.50

POWER SUPPLY: Adapts HE-15B for mobile operation. Complete with cable, 6 or 12 volt vibrator and mounting flanges. Completely enclosed. Size 4 1/4"Dx6"Wx4"H. Shpg. wt., 4 lbs.

HE-16W For 12 Volts Net 10.95

HE-18W For 6 Volts Net 10.95

ANTENNA: Base loaded telescoping whip antenna with PL259 coax connector. Mounts directly on rear of cabinet. Telescopes to only 15". For short distances.

HE-19 Shpg. wt., 2 lbs. Net 3.95

TRANSMITTING CRYSTALS: For any of the 23 channels. Specify channel or frequency. Net 2.25

HE-830L Net 2.25

CITIZENS BAND—The New Two-Way Personal Communications Method for Everyone—Fill out the FCC form enclosed with each Lafayette Transceiver. No examination or technical knowledge required—Any citizen 18 years or older is eligible for a license.

Lafayette OUTSTANDING VALUES FOR CITIZENS BAND ANTENNAS & ACCESSORIES

NEW ALL STAINLESS STEEL CITIZEN BAND MOBILE ANTENNA

OUTSTANDING FEATURES

- 102 1/2" Stainless Steel Whip For Optimum 11 Meter Performance
- Heavy-Duty Chrome Plated Stainless Steel Spring
- Chrome Plated Swivel Ball Jointed Mount Base

6.95


Chrome plated swivel ball mount base designed to be mounted on any surface. Stainless steel spring holds rod in properly adjusted position and prevents rod damage from shocks and blows. Stainless steel whip for maximum resiliency and strength. Shpg. wt., 4 lbs. Has lug terminals for HP-52 cable assembly. Net 6.95



20 FT. RF COAXIAL CABLE ASSEMBLIES FOR CITIZENS BAND EQUIPMENT

A 2.95

B 2.45




These cable assemblies are necessary for connection between Citizens Band Transceiver and Antenna. TYPE A—Consists of 20 ft. RG-58/U cable with PL-259 plus UG-175/U on both ends. Required for Ground Plane and Coaxial and Mobile Antennas terminating in a coaxial jack. Shpg. wt., 8 oz. Net 2.95
TYPE B—Same as type A except one end is terminated with PL-259 plus UG-175/U and other end with universal ring type terminal lugs for mobile antennas. Shpg. wt., 8 oz. RECOMMENDED FOR USE WITH HE-800WX MOBILE ANTENNA. Net 2.45

MOSLEY A-311 3-ELEMENT CITIZEN'S BAND BEAM ANTENNA

36.75

NO MONEY DOWN

- Durable Light Weight Aluminum
- Delivers the Equivalent Power Input of 40-Watts from your 5-Watt Citizen's Band Transmitter



Unequaled point-to-point communications for Citizens Band operators. 9.3 db gain over dipole means the effective radiated power is multiplied by 8. This means your 5 watt Citizen's Band Transmitter can actually achieve a legal effective power input of 40 watts. Boom is 12' long with maximum turning ratio of 9.5 ft. Requires 1 1/4" mast and RG-8/U or R9-58/U Cable. Lugs are supplied for the other end. Shpg. wt., 30 lbs. AN-57WX Net 36.75

COR AR-22 AUTOMATIC ROTOR FOR CITIZENS BEAM

This heavy-duty rotor unit will handle antennas up to 150 lbs. Simply set the control unit pointer to the desired direction, and the antenna will automatically rotate to this position and stop. Perfect for TV, Ham or Citizen Band application. Rotor unit employs 12 heavy duty ball bearings in two 6 1/2" races. Weather-proof motor reverses instantly and is factory lubricated for life. Reversible clamps on rotor will take masts from 3/4" to 2". O.D. Control unit is marked in compass points, N.S.E.W. NW, NE, SW, and SE. Housed in attractive brown plastic cabinet with rubber feet. Complete with rotor, control unit and instructions. For 110-120 volts 50-60 cps AC. Requires 4 conductor cable. Net 32.77

4-Conductor cable for HE-476WX rotor WR-24 ea. ft. Net .03; 100 foot length Net 2.39



MARK MOBILE HELIWHIP & MOUNT



The HW-11-4 "Heliwhip" is a fiberglass molded, continuously loaded whip antenna, four feet in length for the 11 meter Citizen Band. The HW-11-4 mounts in a HWM-1 molded mount or can be used with any good commercial mobile ball mount which will accept the 3/8" - 24 thread HE-895-WX HW-11-4 Fiberglass Antenna. Shpg. wt., 3 lbs. Net 9.95
HE-895 HWM-1 Antenna Mount for HW-11-4 Shpg. wt., 2 lbs. Net 7.50

NEW! LAFAYETTE "DUMMY" ANTENNA LOAD FOR CB TRANSCEIVERS

A 52 ohm non-inductive load for testing and tuning-up Citizens Band transmitters up to 5 watts. It permits tune-up into a non-radiating element instead of into antenna - in compliance with F.C.C. regulations. Built-in PL-259 coaxial plug is easily connected and disconnected from equipment. Shpg. wt., 1 lb. Net .98



LAFAYETTE TELESCOPIC CITIZEN'S BAND WHIP ANTENNA

SENSATIONAL VALUE IN A DIRECT MOUNTING CITIZENS ANTENNA

3.95



Sturdy, attractive chrome plated whip antenna that telescopes from approx. 45" fully extended to only 15" to facilitate portability and storage. Ideal for shorter distances up to several miles. Has enclosed base loading coil for proper impedance matching. Complete with removable PL-259 connector that permits direct top, side or rear mounting to transceiver. Shpg. wt., 1 lb. HE-19 Net 3.95

LAFAYETTE 27MC WALKIE-TALKIE TELESCOPING ANTENNA Attractive and highly efficient 12 section chrome plated brass telescoping antenna for "walkie talkie" transceivers. Measures 52" fully extended and 5 1/2" retracted. Has #8-32 threaded stud and nut at bottom for easy mounting, and soldering lug for electrical connection. F-703 wt., 10 oz. Net 1.95

LAFAYETTE CITIZENS BAND 27MC. COLLAPSIBLE ANTENNA

.79



Ideal for mobile or fixed transceivers, miniature portable and pocket transistor radios, and a host of similar applications. The 4 section antenna is made of chrome-plated brass and plugs into a jack. Measures 48" fully extended and retracted is 11" to facilitate carrying in pocket. Complete with a flexible plastic case and slip-under protecting flap. Shpg. wt., 8 oz. Net .79

ANTENNA SPECIALISTS

MAGNUM-27 1/2 WAVE 27MC ANTENNA

Compact vertical radiator with an actual 6 DB gain over any single element omni-directional antenna. Constructed of rigid aluminum and cadmium plated steel, it is corrosion resistant, waterproof and fits on most masts or directly into wooden areas. Hi-Q phasing transformer provides proper resonance over entire CB band. Direct ground lightning protection. 50 ohm feed. Total height is only 18" 2" (17" 3" radiator, 4-54" radials. Shpg. wt., 12 lbs. HE-487WX Net 27.88

ANTENNA SPECIALISTS

GROUND PLANE ANTENNA

Solid aluminum 108 inch heat-treated radials and radiator. Elements supplied in two 54 inch lengths joined by threading coupling nuts. Radials drop for 50 ohm match. Accepts 1 1/4 inch tubing RG-58/U cable and PL-259 connector. Shpg. wt., 4 lbs. HE-661WX Net 15.63

ANTENNA SPECIALISTS M-38 ANTENNA ISOLATING SKIRT

Improves Performance Of All Citizen Band Ground Plane Antennas
Isolating skirt for use with Citizen's Band Ground Plane Antennas. Mounts 9 feet (3/4 wave length) below ground plane (i.e. 27 MC). Lowers angle of radiation and minimizes effect of mounting structure. Improves performance of ground plane. Clamps to 1 1/4 inch tubing or 1 inch pipe. Shpg. wt., 4 lbs. HE-881WX Net 11.14

NEW! HY-GAIN CLR COLINEAR GROUND PLANE ANTENNA

A new concept in CB antenna design. Achieves gain through colinear action which concentrates more power at lower angles to the horizon. Performs equally well receiving or transmitting, greatly increasing the range of consistent CB communications. Precision tuned and matched for 52-ohm coaxial cable, either RG-8/U or RG-58/U. Overall only 20-ft. high; radiator is 1 1/4" O.D. to 3/8" O.D. heavy wall heat-treated aluminum tubing. 9-ft. long radials of 3/8" D.D. aluminum tubing. Accepts all masts up to 1 1/2" diameter. Complete with matching stub and complete assembly instructions. Shpg. wt., 10 lbs. HE-773WX Net 29.37

29.37
NO MONEY DOWN

NEW UNIVERSAL LAFAYETTE CITIZENS BAND AMATEUR SPRING AND SWIVEL BALL-MOUNT BASE

- Heavy-Duty Chrome Plated Stainless Steel Spring



New universal Lafayette HE-53 chrome plated swivel ball mount base with lug terminals for use with mobile antennas. Exclusive Lafayette design provides easy adjustment and at the same time prevents loosening by vibration or shock. Can be mounted vertically or horizontally on any surface. With lug terminals for use with mobile antennas. Net 1.95

New Universal Lafayette HE-54 Heavy duty chrome plated stainless steel spring. Provide maximum support for long whips and heavy center-loaded whips. HE-54 Net 2.89

NEW LAFAYETTE 12 POSITION CRYSTAL SELECTOR

Houses and selects up to 12 crystals - increases channel coverage. Chassis has 12 ceramic crystal sockets, wired to a 12 position, no stop selector switch. Long reach shaft permits practical mounting. Chassis size: 2 1/4" D x 2 1/4" W x 2 1/4" H. Shpg. wt., 1 lb. HP-201 Net 6.50

NEW! LAFAYETTE BROADCAST TO CITIZEN BAND COUPLER

Specially designed network permits any Citizen's band mobile antenna to be used also for broadcast reception. No switching necessary. With SO-239 antenna receptacle, 2 ft. lead with coaxial auto plug for broadcast radio connection and 2 ft. lead with PL-259 coaxial plug for transceiver connection. Shpg. wt., 1/4 lb. HP-202 Net 6.95

LAFAYETTE GENERATOR NOISE FILTER

- Frequency Range 3-30 mcs
- Maximum Current 25 Amps
- Adjustable
- Simple to install

Eliminates whining and grinding noises created from generator brushes. Enables quiet receiver operation for Citizens Band, Amateur and industrial frequencies. Standard frequency range 3-30 mcs. Maximum current 25 amps. Installs quickly and easily. CF-135 Shpg. wt. 1 lb. Net 2.49

NEW! LAFAYETTE AUTO-MARINE ENGINE NOISE SUPPRESSOR KIT

- A Must For Mobile CB & Ham Operators
- 14 Components Plus Hook-Up Wire

This easily installed kit will effectively suppress ignition, generator and voltage regulator noise. Consists of 8 spark plug suppressors; 1 distributor suppressor, 1 voltage regulator suppressor; 4 coaxial capacitor shielded cable and braid for wiring filter system. All necessary hardware and instructions for installation are included. Shpg. wt., 2 lbs. HP-204 Net 9.45

GENERATOR/REGULATOR FEED-THRU NOISE SUPPRESSORS

These 3-terminal network feed-thru capacitors act as extremely effective R.F. filters above 2 MC. Eliminates and suppresses the majority of noises due to regulators and generators interfering with 27MC citizens band frequencies. Rated .1 MFD/600 Volts DC 20 Amps.

Feed-Thru Suppressor (Screw Terminals) 1/2" Diam. x 1 1/4" length. Shpg. wt., 4 oz. SP-221 Net .95
Feed-Thru Suppressor 1/2" Diam. x 1 1/4" length. Shpg. wt., 4 oz. SP-222 Net .95

RF COAXIAL CONNECTORS

Stock No.	Type	Description	Net
SP-174	PL-259	Male conn. For direct connection into transceiver or antenna	.59
SP-175	UG-175/U	Reducer—Adapts PL-259 to RG-58/U Diam.	.16
SP-176	PL-258	Junction Adapter—Accepts PL-259 on both ends for cable extension	.89

CITIZENS BAND CONNECTOR ADAPTERS

29-786 ADAPTER
Adapts an SO-239 Socket to a Standard auto radio (Motorola type) socket. Av. Shpg. wt., 2 oz. HP-53 Net .44

29-782 ADAPTER
Adapts a PL-259 Plug to a standard auto radio (Motorola type) plug. Avg. shpg. wt., 4 oz. HP-54 Net .54

RG COAXIAL CABLES

These high quality coaxial cables are branded with RG type standard type numbers. Meets specifications outlined by U. S. Government Qualified Products List. R.G. 52-ohm cable is required for Ham and Citizens Band hook-up from the transceiver to antenna.

Stock No.	Type	Impedance	Net Per Ft.
WR-143	RG-8/U	52-ohms	.11
WR-144	RG-58/U	52-ohms	.05
WR-145	RG-59/U	72-ohms	.05

NEW! LAFAYETTE CHROME PLATED MOBILE BUMPER MOUNT WITH STAINLESS STEEL STRAP

- Completely Adjustable For Use With Most Types of Automobile Bumpers
- Highly Reliable and Durable!

An outstanding new Lafayette mobile bumper mount featuring chrome plated mount and stainless steel strap which is completely adjustable for vertical mounting on most type of automobile bumpers. Eliminates need of cumbersome link type chain mounts. Shpg. wt., 1 1/2 lbs. HE-33 Net 3.95

NEW LAFAYETTE "SQUELCHER"

- PROVIDES FULL SQUELCH AND NOISE LIMITING TO ANY SUPERHETERODYNE TRANSCIEVER OR RECEIVER
- VASTLY IMPROVES MOBILE TRANSCIEVERS WHEN VEHICLE IS IN TRAFFIC
- REDUCES NOISE FROM IGNITION SYSTEMS AND OTHER SOURCES

The Lafayette "Squelcher" noise eliminator and squelch was designed to improve reception and reliability in all superheterodyne transceivers or receivers including the Lafayette HE-15A, HE-15B, HE-20A, HE-20B, HE-30, HE-45, HE-50, and KT-320. Reduces noise from ignition systems and other sources. Quiets receiver when no signal is received. Vastly improves sensitivity of mobile transceiver when operating in traffic. Complete with 2 tubes (6AL5 and 12AX7), instructions for easy installation in any receiver. In Satin aluminum with blue gray perforated cover. Furnished with cable. Size 2-3/10x3 1/4x4 1/4" HE-55 Shpg. wt., 1 1/4 lbs. Net 10.95

B and W 424 LOW PASS FILTER FOR CB AND LOW POWER TRANSMITTING EQUIPMENT

Designed to effectively reduce TVI—Radiated spurious and other undesirable signals higher than 35 MC are attenuated by at least 60db. It may also be used between a low power exciter unit and a high power amplifier to reduce spurious frequencies entering the grid circuit of the final. SPEC: Power rating—100 watts Max. Frequency Range—1.5 to 30 MC. Impedance 50/75 ohms (reversible), two UHF type connectors. Size: 5x2x1 3/4". Shpg. wt., 1.5 lbs. HE-304 Net 8.65

BLITZ BUG LIGHTNING PROTECTOR

Designed to fit any standard coaxial cable, the "Blitz Bug" employs the spark gap principle to eliminate static build up on coaxial cables. Provides a constant drain off, reducing chances of a direct lightning strike and in many cases eliminating noise problems. Constructed of 3/4" O.D. brass by 2 1/4" long. Employs one PL-259 plug and one DKCB connector (takes PL-259 plug.) Shpg. wt., 1 lb. HP-50 Net 3.95

NEW! HY-GAIN UNIVERSAL BUMPER MOUNT with STRAP

- Chrome-Plated Mount
- Stainless Steel Strap

6.44

An attractive new bumper mount, heavily chrome-plated and attaches easily and quickly to most auto bumpers. Stainless steel mounting strap replaces the old-fashioned bulky bumper chain. Fully adjustable for vertical alignment. Shpg. wt., 1 1/2 lbs. HE-774 Net 6.44

NEW! "NOISTOP" IGNITION NOISE ELIMINATOR

Effective as both a noise limiter and a positive squelch the "Noistop" improves reliability and operating pleasure, when vehicle is in traffic. Measures only 1 1/2 x 2 1/2 x 4". Complete with tubes (6AL5 and 12AX7) and instructions for easy installation in most available transceivers. For use with superheterodyne type transceivers. Furnished with cable and gold anodized cabinet with black perforated cover. Mounts in any position. Shpg. wt., 10 oz. HE-902 Net 16.61

CITIZENS BAND RADIO MANUAL 160 PAGES 8 1/2 x 11"

Up-to-date list of "Q" calls, special do-it-yourself section and 16 page CB equipment directory. Also lists CB clubs in U.S. and includes a log section. BK-331 Net 2.95

1962 CITIZENS BAND CALL-BOOK

HANDBOOK H. W. SAMS
Includes PHOTOFACT® schematics, chassis photos, parts lists, etc., for 46 1960-61 CB Transceiver models. Special features on servicing CB equipment. BK-1323 Net 3.95

RIEERS CITIZEN BAND HANDBOOK No. 273

By Allan Lytel. Written for the user, prospective buyer and the service technician. Describes historical development, applications, classifications, and types of available equipment. Design features of different types of equipment are compared and analyzed in detail. The various elements of a CB station, and their maintenance, are all thoroughly treated. Includes a discussion of relevant FCC regulations. Soft cover. 160 pages. 5 1/2 x 8 1/2". BK-741 Postpaid in U.S.A. Net 3.87

MOTOROLA RADIOS for FOREIGN & DOMESTIC CARS

ALL NEW TRANSISTORIZED AUTOMOBILE RADIOS Complete with Mounting Kit 5-TRANSISTOR MANUAL CAR RADIO



39⁹⁵

• **In-dash or Under-dash Mounting**
A tremendous value in an all-transistor car radio. Hand-wired chassis with 5 transistors, 2 diodes, 1 thermistor. Built-in Golden-Voice hi-fi speaker. Set plays as soon as you turn it on—no warm-up time required. Custom fits most cars, sport cars, trucks and boats—in-dash or under-dash installation. Low battery drain. Features

• **All-Transistor, Hand-Wired Chassis**
full variable tone control, cool chassis operation, band pass circuit, automatic gain control. For 12-volt cars, reverse polarity. Size: 6⁷/₈Wx2¹/₂Hx7¹/₄"D. Shpg. wt., 7 lbs.
CR-128 Model 320T Net 39.95



51⁹⁵

• **Custom Fits "Difficult to Fit" Cars**
A flexible car radio with movable control shafts to accommodate the most difficult-to-fit cars. Push/Pull audio system gives smooth high-fidelity sound and delivers a full 12 watts of peak power output. Employs 6 transistors, 2 diodes and 1 thermistor in a hand-wired chassis. Low battery drain of only .5 amp. Features

• **Push/Pull Audio System for Hi-Fi Sound**
tunes Golden-Voice hi-fi speaker. full variable tone control, automatic gain control. Plays as soon as you turn it on—no warm-up needed. 12-volt cars, negative ground. Size: 7⁵/₈Wx2¹/₂Hx5"D. Shpg. wt., 7 lbs.
CR-129 Model 2MT Net 51.95

ALL-TRANSISTOR PUSHBUTTON CAR RADIO FOR FOREIGN CARS




54⁹⁵

• **Pushbutton Convenience** • **5 Transistors, 2 Diodes, 1 Thermistor**
Simple, pushbutton convenience with all-transistor power and dependability. Hand-wired, transistor chassis means instant play without warm-up, cool chassis operation, and 64% less battery drain, only .7 amp. Full variable tone control, automatic gain control, band

pass circuit, plus the exclusive Golden-Voice hi-fi speaker. For 12-volt cars, reversible polarity. Size: 6⁷/₈Wx2¹/₂Hx7¹/₄"D. Shpg. wt., 8 lbs.
CR-130 Model 520T Net 54.95

6-TRANSISTOR PUSHBUTTON CAR RADIO For Domestic Cars



59⁹⁵

• **6 Transistors, 2 Diodes, 1 Thermistor**
A new, all-transistor car radio designed to custom fit most domestic cars on the road. The push/pull audio principle results in smooth, uninterrupted sound. Delivers 12 watts of peak power output. Features 30% cooler chassis operation; 64% less

• **Push-Pull Audio System for Hi-Fi Sound**
battery drain; instant play no warm-up; full variable tone control; automatic gain control. Exclusive Golden Voice 6x9" speaker. Size: 9¹/₄Wx3Hx7"D. For 12 volt cars, negative ground.
CR-131 Model 12AT-2 Shpg. wt., 9 lbs. Net 59.95

MODEL 406 — TUBE & TRANSISTOR AUTO RADIO



39⁹⁵

• **For 6-Volt System**
Compact radio set that is ideal for custom underdash or in-dash installation. "Golden Transistor" circuit employs 2 transistors and 4 tubes. "Volumatic" constant level output eliminates

fading and distortion. Antenna band pass filter. Reverse polarity. Size: 6⁷/₈Wx2¹/₂Hx7¹/₄"D. Shpg. wt., 6 lbs.
CR-28 Model 406 Net 39.95

Full 1-year warranty on all parts and labor. Manufacturer's guarantee covers free exchange or repair of any component power defective in normal use. Removal and re-installation labor extra. Arranged through your local service dealer.

Consult This Chart To Determine Which Sets Fit American Cars, Sports Cars and Foreign Cars.

The below chart shows the make and model of cars which use the above Motorola Car Radios. The "Use-Set" column indicates the stock number of the radio or radios which can be used with the different types of automobiles. Use this stock number when ordering. Also list make, model and year of your car.

MAKE, MODEL AND YEAR	USE SET	MAKE, MODEL AND YEAR	USE SET	MAKE, MODEL AND YEAR	USE SET
Austin Healy 1957-62	CR-128	Falcon 1960-62	CR-128, CR-129, CR-131	Plymouth 1956-62	CR-128, CR-129, CR-131
Borgward 1957-62	CR-28	Fiat 600-1100 1957-62	CR-128	Rambler 1959-62	CR-128, CR-129
Buick 1954-62	CR-128, CR-129	Ford 1957-62	CR-128, CR-131	Rambler-American 1960-62	CR-128, CR-129, CR-131
Buick Special (Compact) 1961-62	CR-128, CR-129, CR-131	Hillman Minx 1957-62	CR-128	Renault Dauphine 6 Volt 1955-58	CR-28
Chevrolet 1958-60	CR-128	Karmann-Ghia (V.W.) 58-62	CR-28	Renault Dauphine 12 Volt 1958-62	CR-128
Chevrolet 1961-62	CR-128, CR-129	Mercedes Benz 1958-62	CR-128, CR-130	Studebaker Lark 1959-62	CR-128, CR-129, CR-131
Citroen 1D-19, DS-19 6 Volt	CR-28	M. G. Magnette MGA 1957-62	CR-128, CR-130	Sunbeam Rapier 1957-62	CR-128
Citroen 1958 62 12 Volt	CR-28	Morris Minor 1957-62	CR-128, CR-130	Taunus 1958-62	CR-28
Comet, 1960-62	CR-128, CR-129, CR-131	Oldsmobile F-85 1961-62	CR-128, CR-129, CR-131	Triumph TR-3 1958-62	CR-128, CR-130
Corvaire 1960-62	CR-128, CR-129	Opel 1957-62	CR-28	Valiant 1960-62	CR-128, CR-131
Dodge Dart 1957-62	CR-129, CR-131	Peugeot 1958-62	CR-128, CR-130	Volkswagen 1952-62	CR-28
Dodge Lancer 1961-62	CR-128, CR-129	Pontiac Tempest 1961-62	CR-128, CR-129, CR-131	Volkswagen Bus 1952-62	CR-28
English Ford 1957-62	CR-128, CR-130	Porsche 1957-62	CR-28	Volvo PV-444, PV-544 1957-62	CR-28
				Volvo 12 Volt	CR-128

GRANCO FM CAR CONVERTER



Only **39⁵⁰**

Add Hi-Fi to Your Present Car Radio

- Exclusive "Auto-G" Coaxial Tuner
- Automatic Frequency Control
- Quick, Under-Dash Installation

Get added pleasure from your auto radio listening with the new Granco FM car converter—lets the incomparable richness of High Fidelity FM travel with you. Features the exclusive "Auto-G" coaxial tuner for highest sensitivity and selectivity. Automatic frequency control locks in stations. Economical to operate too—uses the existing car radio antenna and circuits. Complete 12-volt battery operation. Compact design—book size, 1¹/₄" thick. Stays in place with just 2 screws, 1 wire and antenna plug-in.
(In lots of 6, Each 36.50)
CR-105 Shpg. wt., 10 lbs. Net 39.50

AUTOMOBILE ANTI-THEFT PROTECTOR



Protects Your Car from Being Stolen **6.98**
• Protects Your Car by Sounding An Alarm
• Prevents Ignition Switch from being Jumped
• Prevents Car's Lights and Accessories from Working
• Easy to Install

Here is the ideal auto protection for salesmen, servicemen, delivery vans... all motorists. Not only will it prevent your parked car from being stolen, but will also safeguard valuables in the trunk as well as parts under the hood. Sounds an alarm in case of attempted theft and completely immobilizes the car—ignition can't be jumped, lights and accessories will not operate. Instructions included for easy installation. AA-111 Shpg. wt., 1¹/₂ lbs. Net 6.98


NEW! RADIO TRANSVERTER



Converts Transistor Radio to Car Radio **Only 1.47**
• For all 9-Volt Transistor Radios
• Plugs into Cigarette Lighter
• Fits all Cars

Now you can avoid the expense of buying a car radio with this new radio transverter. Simple to operate—remove 9-volt battery from your transistor radio, connect contacts from transverter to battery contacts in the radio, and then plug into the cigarette lighter. Fits all cars. Shpg. wt., 6 ozs.
AA-102 For 12-volt Cars Net 1.47
AA-103 For 6-volt Cars Net 1.47

CARDIO-MASTER



Convert your Transistor Radio into a Car Radio
• For all Makes of Cars — Cabs — Trucks **2.98**

Cardio master is a magnetic device designed to hold a portable transistor radio in the area of a car's windshield to make it operate as an auto radio. Car's owner can remove a radio from the Cardio master for use as portable or to avoid theft while the car is parked. Fits any "pocket" transistor radio. Will not come loose in the bumpiest roads. Includes magnetic base, brackets, hardware, adjustable band and complete, illustrated instructions.
AA-45 Shpg. wt., 2 lbs. Net 2.98


NEW! POCKET TIMER



Set It and Forget It **2.95**
• Set Timer Up to 60 Minutes
• Swiss Precision Watch Movement
• Hairline Accuracy
• Hundreds of Uses

The new pocket timer is an invaluable aid for most anyone, anywhere. With its 60 minute time set, it can be used as a reminder when parking meter time runs out, for appointments, take pills or medicines, etc. Also use as a timer on phone calls, cooking, photography, etc. Shpg. wt., 1/2 lb.
MS-888L Net 2.95

REAR SEAT AUTO SPEAKER KITS



6" x 9" KIT WITH CHROME OR GOLD GRILLE
Complete kit for adding second speaker in rear of your car. Includes a 6x9" PM speaker, 3-position selector switch for cutting in front, rear, or both speakers; dial plate with mounting bracket, knob, and hardware; chrome or gold grille; wire; and wiring instructions. Simple to install. Shpg. wt., 5 lbs.
SK-94 Speaker kit chrome grille Net 3.45
SK-196 With gold grille Net 3.45


DELUXE 6"x9" KIT with 2.15 oz. ALNICO V MAGNET
Same as above but with deluxe speaker with extra-heavy Alnico V magnet (2.15 oz.). This is same speaker used in kits selling at twice the price. Shpg. wt., 5 lbs.
SK-37 Speaker kit chrome grille Net 4.65
SK-197 WR6 gold grille Net 4.65

5" x 7" KIT
Same as SK-94 but with 5x7" speaker and grille. 5 lbs.
SK-42 Chrome grille Net 3.05
SK-198 With gold grille Net 3.05

FADER TYPE AUTO KITS
Rear-seat speaker kits identical to those above except with fader-type controls to cut either speaker in or out or balance both. Shpg. wt., 5 lbs.
SK-55 5x7" kit. Same as SK-42 but with fader control. Chrome grille Net 3.29
SK-199 With gold grille Net 3.29
SK-95 6x9" kit. Same as SK-94 but with fader control. Chrome grille Net 3.69
SK-200 With gold grille Net 3.69

DELUXE 6" x 9" FADER KIT
Deluxe kit with extra-heavy-magnet 6x9" speaker, plus fader control. Shpg. wt., 5 lbs.
SK-56 6x9" kit. Same as SK-37 but with fader. Chrome grille Net 4.89
SK-201 With gold grille Net 4.89

HI-FI REAR SEAT AUTO SPEAKER KITS



• **ADD HI-FI LISTENING TO YOUR CAR**
• **FEATURING 6x9 COAXIAL SPEAKER WITH TWIN TWEETERS**
Identical to SK-37 auto speaker kit shown on this page except has hi-fi 6x9" coax speaker instead of single-cone unit. Excellent for music lover who wants quality reproduction. Shpg. wt., 6 lbs.
SK-77 With Chrome Grille Net 8.80
SK-202 With Gold Grille Net 8.80

FADER TYPE AUTO KIT
Coaxial speaker kit (same as SK-77) with fader for flexible control of both front seat and rear speakers and sound balancing. Shpg. wt., 6 lbs.
SK-78 With Chrome Grille Net 9.00
SK-203 With Gold Grille Net 9.00

INSTANT FLAT TIRE REPAIR

• **No Jacks, No Tools, No Removing Tires**
• **Seals and Inflates Tires in ONLY 2 MINUTES**
• **For Tube-Type and Tubeless Tires**
You'll never change a punctured flat on the road again. Just attach the valve of any tube or tubeless tire and the amazing sealant instantly plugs the puncture as the tire is inflated to a satisfactory driving pressure. Will not affect wheel balance. No tools needed, no removing tires, no dirty hands—any woman can use it too. Road tested for performance. Shpg. wt., 3 lbs.
AA-84 Net 2.59

3-WAY PUSH-BUTTON SWITCH



Just push a button to select either front speaker alone, rear speaker alone or both together. Comes completely assembled on black & silver metal plate with cable, hardware and simple instructions. Imported. Shpg. wt., 1/2 lb.
MS-890 Lots of 3, ea. .75 singly, each .89

MAGNETIC UTILITY LIGHT



High intensity trouble lamp for car or boat. Powerful magnetic base holds easily to metal surface. Double ball joint for use at every possible angle. Folds down to an "egg" sized unit. Long life, horizontal filament lamp, gives more light than conventional types. Heavy chrome plate over brass plated steel for exceptional corrosion resistance. 15 ft. cord gives plenty of leeway in positioning. Includes red filter for use as a warning light, lighter plug and vinyl case for storage. For 12V. DC only. Shpg. wt., 1 lb.
F-631 Net 4.95
Spare Bulb for F-631 Net .28
F-632 Shpg. wt., 2 oz. Net .28

NYLON "BULLDOG" 10 FT. TOW CABLE

• **100% DuPont Nylon** • **10-ft. Long**
• **Guaranteed 5,000 lb. Test Strength**
• **Attaches Instantly to Any Bumper**
The perfect cable for towing ANYTHING UP TO 5,000 LBS. Constructed of heavy-duty, 1" wide, DuPont Nylon webbing that stretches 25% to take up shocks for smooth, safe towing. Oil, grease and water resistant too! Dual, self-aligning clip attaches to any bumper. Shpg. wt., 3 lbs.
AA-57 Net 3.75

NEW! Lafayette ELECTRONIC AUTO TESTER

COMPLETELY ASSEMBLED

NOT A KIT!

A TRUE VTVM IGNITION ANALYZER

Compact Combination Automobile Test Instrument

CHECK ✓ Power ✓ Performance ✓ Economy



39⁹⁵

NO MONEY DOWN

- No Complex "Curves" • "Scope" Type Indications are converted into Direct Meter Readings • Check Your Car's Ignition System—Plugs, Coils, Condenser, Points, Wiring • Special Capacitive Clip Prevents Overloads and Shocks Even when Ignition System is Operating • Large, Easy-to-Read Dial Face • Operates from 12-Volt Car Battery

The new Lafayette Electronic Auto Analyzer will pinpoint auto ignition trouble quickly and accurately without confusing curves or complicated interpretations. As accurate as an expensive oscilloscope, the TE-40 incorporates a highly sensitive VTVM to locate troubles in coils, plugs, points, condensers, etc. without any circuit drain. The large, easy-to-read multi-colored meter eliminates complicated curves and scope interpretations—you get direct, simple readings.

Featured is a variable resistance loading circuit which simulates a heavy engine load such as driving at high speed or hill climbing—you test under conditions simulating actual driving. The TE-40 also has a special capacitance clip which enables you to make high voltage measurements, including surges, without danger of shock. Operates on 12-volt auto batteries. Complete, ready-to-use with detailed operating instructions. Shpg. wt., 16 lbs.

TE-40 Net 39.95

THE GAUGES DETROIT LEFT OUT!

LAFAYETTE AMMETER & OIL PRESSURE GAUGES

4⁴⁹



DON'T trust flashing indicator lights—a burned out bulb can ruin your motor or strand you with a dead battery. All cars with warning lights for oil and battery need these precision gauges. Lights only indicate when oil pressure falls below 15 lbs. or whether or not the generator is working. These Lafayette gauges will replace your panel lights (or if you wish to use both lights and gauges, buy the Tee fitting listed below). Keep a constant check on the condition and performance of your car's electrical and oil pressure systems. The ammeter calibrated in a 60-0-60 scale measures the actual rate of current flow... helps prevent generators from burning out and overcharging or discharging the battery. Exact oil pressure from 0 to 80 lbs. is indicated. Easily installs in any 6 or 12 volt car below the dash, without drilling or can be mounted right in the dash. Both meters are mounted in an attractive chrome panel. Easy to read meters feature 1 3/4" diam. black dial faces with calibrations in white. Size: 5 1/4" x 2 7/8" x 2 1/4" D. Supplied with all necessary fittings plus full instructions.

MS-788 Shpg. wt., 1 1/4 lbs. Net 4.49
MS-912 Tee fitting Net .49

ILLUMINATED TYPE

Same as above, but gauges are illuminated. Supplied with lamp sockets and both 6 and 12 volt bulbs. MS-792 Shpg. wt., 1 1/2 lbs. Net 6.49

PROFESSIONAL BATTERY CHARGER 8.95

- 3 Amp Tapering Charge
- For Both 6 and 12 Volts
- Positive Automatic Overload Protection



A professional type 6 - 12 volt battery charger with reset circuit breaker. Indicator light flashes on when circuit breaker trips. Front panel switch for change-over from 6 to 12 volts. Delivers a tapering charge starting at 3 amps for 6 volts. Noiseless, aircooled construction. Oversized components and vented case for troublefree operation. Runs cool even under constant use. 4 1/2 ft. charging cables with heavy duty. 25 amp battery clips. Measures 5x3 1/2 x 3". For 105-125 volt, 50-60 cycle A.C. Shpg. wt., 5 lbs. Net 8.95

CV-50

CHARGER PLUG: Permits charger to be plugged into lighter receptacle. Shpg. wt., 8 oz. MS-707 For 6V Cars Net 1.15
MS-708 For 12V Cars Net 1.15

2-IN-1 BATTERY CHARGER 4.95




- Full 1 Amp Charge Rate on 6 or 12 Volt Batteries
- Automatic Taper Rate—Can't Overcharge
- Manual Reset Circuit Breaker

End dead battery trouble in your car, boat, truck or tractor. This powerhouse battery charger keeps all 6 and 12 volt batteries fully charged for peak performance even at 40° below freezing. Full 1 amp. "safe" charge rate prevents flacking and plate buckling—same method used by storage battery dealers. Easy to use—plug the line cord into any 110V outlet, connect the two terminals and forget it. Warning trouble light indicates incorrect terminal connection. Can't overcharge—automatically tapers off. Welded constructed steel. Shpg. wt., 3 1/2 lbs. Net 4.95

CV-56

AUTOMOTIVE TESTING EQUIPMENT



(A) MOTOR ANALYZER

All the advantages of a well-equipped service shop in a light, hand-held package. Ideal for do-it-yourselfers, sports car Rallyers, etc. The Analyzer enables you to test ignition coil output, spark plugs, insulation breakdowns; locates poorly adjusted carburetor, sticky or burnt valves, weak valve springs; checks valve timing, choke, muffler, vacuum tank, manifold, fuel pump vacuum and pressure and vacuum operated equipment. 14Wx7 3/4 x 3 1/2" D. Shpg. wt., 5 1/2 lbs. Net 15.95

AA-49

(B) REMOTE STARTER SWITCH

Eliminates the need of a second man when making compression, fuel pump, generator, starter, and electrical tests. Permits the mechanic to crank the engine from any position. Shpg. wt., 1/2 lb. Net 2.59

AA-50

(C) MOTOR GUIDE-VACUUM FUEL PUMP TESTER

Combination motor guide, vacuum and fuel pump tester, 4 color zones: Economy Driving, Fast Pick-up, Coasting and Idle. Promotes good driving habits and economical gas-mileage. Warns when tuneups are necessary. Shpg. wt., 12 oz. Net 3.75

AA-51

(D) COMPRESSION TESTER

Gives quick, accurate readings of compression pressure. Merely unscrew the spark plug, plug tester into spark plug hole and read pressure. 2 1/2" dial reads to 300 lbs. Stem is offset 15° for reaching back cylinders. Complete with instructions. Shpg. wt., 12 oz. Net 3.75

AA-52

(E) STANDARD TIMING LIGHT

Employs the stroboscopic principle of light synchronized with motion for adjustment and setting of ignition timing under actual operating conditions. Shpg. wt., 1 lb. Net 3.25

AA-53

(F) TACHOMETER

Here's the instrument for the most important check of an engine's performance: the RPM test. Tests 4, 6 and 8 cylinder engines with both 6 and 12-volt systems. Operated by two inexpensive penlight batteries which last about a year. Large dial reads 0-1000 and 0-5000 RPM. Shpg. wt., 2 1/2 lbs. Net 28.50

AA-54

CAM-DWELL INDICATOR 3.95

A high quality instrument for solving all CAM-DWELL problems. Checks the number of degrees a distributor can rotate while the breaker points remain closed. Too much rotation means points are set too close, too little means breaker points are not closed long enough for adequate build up of the magnetic field in primary coil, permitting arcing across points. Requires no electrical outlet. Distributor need not be removed. Compact, portable. Complete with case and includes chart showing specifications for all popular cars. Shpg. wt., 2 lbs. Net 3.95

AA-98

EMERGENCY BLINKER 1.49


- MAGNETIC BASE
- VISIBLE FOR 1000 FEET
- OPERATES ON 2 FLASHLIGHT BATTERIES

Every motorist needs it. Bulb flashes 60 times a minute. Stands by itself on road; has hanger or magnetic base which holds it firmly to any metal surface. Rugged plastic dome. 5 3/8" diam. x 3 3/4" high. Shpg. wt., 2 lbs. With spare, non-blinking bulb for steady light, less batteries. Net 1.49

AA-99

BA-157 #2 batteries (2 needed) ea. Net .13

MOTOROLA ALL-ELECTRONIC ALTERNATOR SYSTEM



Always Charges Battery Even at "Idle" Speed

- All-Transistor Voltage Regulator and Advanced New 7-Diode Alternator
- Extends Battery Life
- Reduces Maintenance Cost Caused by Generator and Regulator Failures
- Fits 12-Volt Cars with Negative Ground

• GUARANTEED FOR 3 YEARS (OR 30,000 MILES)*

Tired of replacing expensive car batteries? Frustrated by stalling cars and costly towing? Now you can save time, money and trouble with Motorola's all-electronic alternator system. This is the low cost solution to the heavy demands made by your car on its electrical system... heaters, radios, defrosters, air conditioners, power seats and windows. The new Motorola alternator eliminates all the fuss and expense caused by chronic run-down battery due to generator and voltage regulator failures. Unlike D.C. generators, it supplies a charge at idle speeds and keeps the battery at a uniform high level of charge. The all-transistor voltage regulator has no contact points to stick or burn... nothing but trouble-free transistors and diodes that virtually never wear out. So reliable it's sealed for life and is not affected by shock, vibration, moisture or dust. The alternator is 50% smaller than a generator and weighs 50% less. Guaranteed for 3 years or 30,000 miles.*

Motorola's advanced new alternator fits all domestic cars with 12-volt, negative ground electrical systems. Available in 2 sizes: 30-amp for autos and light trucks; 45-amp for police cars, taxis, and heavy duty use. The complete system includes: alternator (with standard-size pulley); all-transistor regulator (with all connecting wires); universal mounting bracket; instructions for installation in less than 1 hour.

AA-109 30-Amp (shpg. wt., 11 1/2 lbs.) Net 59.95
AA-110 45-Amp (shpg. wt., 13 1/4 lbs.) Net 74.95

*Manufacturer's guarantee covers repair or replacement of parts within 3 years or 30,000 miles (whichever occurs first).



Lafayette HOT CAR-GO Starts Your Car INSTANTLY

OUR LOWEST PRICE EVER!

- Starts Wet or Cold Motors Instantly
- Saves Battery and Gasoline
- Installs Easily and Quickly
- 6 and 12 Volt Cars

2.95

Avoid excess wear and tear on your motor and battery—install Lafayette's Hot Car-Go. Provides 5 times the normal spark for fast starting in any weather, and automatically disconnects when engine is running. Will not damage plugs or distributor. Simple to install—instructions included. Shpg. wt., 1 lb. Imported MS-784

Net 2.95

NEW! DO-IT-YOURSELF PLATING KIT

Tune Up Your Chrome—Plate or Replate Most Metal Surfaces



- Fast-Easy-Inexpensive
- Non-Electric
- For Use in Home, Car, Boat, Office

3.98

Combination of Cadmium, Nickel, Chromium Now you can replating worn, rusted or pitted iron, steel, copper or brass—even metal parts that have never been plated before. Your finished plating is a combination of cadmium for rust-proofing, nickel for protection and luster, chromium for hardness and brilliance. Ideal for car, plumbing fixtures, door hardware, and most any metal surface except aluminum. Kit consists of 4 oz. copper chelate, 4 oz. chrome chelate, 1/2 pint plating sealer, sponge, catalizer wool, 1" brush, sandpaper, steel wool, 4 oz. rust remover. Shpg. wt., 2 lbs. Net 3.98

AA-106

SUPER PLATING KIT

Similar to above but in larger quantities. 12 oz. copper chelate, 12 oz. chrome chelate, 12 oz. spray can of plating sealer (no brush needed), 12 oz. rust remover, sponges, catalizer wool, sandpaper, steel wool. Shpg. wt., 4 lbs. Net 9.98

AA-107

"RUSTY" RUST REMOVER 86c

- Dissolves Rust from Iron and Steel
- Cleans Stains from Porcelain, Cement, Tile
- Frees Frozen Nuts and Bolts

A few drops of Rusty and rust dissolves without affecting the sound metal. No more heat or torches necessary; no more long waits. Use for car or home—any corrosion, stained porcelain and cement. Frees frozen nuts and bolts; loosens frozen pipe joints. Non-flammable; safe to use. Shpg. wt., 8 oz. Net .86

AA-108

TIMING & OCTANE SELECTOR 4.54

- Advances or Retards Spark As you Drive
- Spark Indicator Light Shows Engine Load
- Gives Longer Engine Life
- Premium Performance on Regular Gas

Increases Gas Mileage & Horsepower

and power your car is now wasting with this Timing and Octane Selector. Enables you to dial-in the most effective spark timing from the dash, as you drive. Harmful ping and spark knock are eliminated—you get premium performance from regular gas. Will not interfere with your distributor's advance mechanism. Mounts on your dash. Simple, do-it-yourself installation instructions—no tools needed. Shpg. wt., 1 1/4 lbs. Net 4.54


AA-112

LAFAYETTE'S SPECIAL AUTOMOTIVE ACCESSORIES

New! LAFAYETTE TRANSISTORIZED TACHOMETER

- Accurate 0-8,000 RPM Scale
- Adjustable Shift Point Indicator
- Economy Range-Finder
- Easy to Install

19.95



Here is the modern electronic guide to big gas savings, full power and longer engine life. The Lafayette Tach helps you shift right... tune right... drive right. Features an "Adjustable Speed Shift Indicator" that shows exact shift points for fastest acceleration, and "Economy Range-Finder" that indicates engine's safest,

most economical operating range. Handsome 3-color illuminated dial has accurate 0 to 8,000 RPM scale. Dependable transistor design; self-contained with chrome head. Easy 5-minute installation on any car. Shpg. wt., 1 lb.

NEW! RADAR SENTRY warns of radar traffic zones

- Dual Band Circuit Detects Radar Beams on Both "S" and "X" Frequencies
- Gives Advance Warning Within 1/2 Mile Range
- Miniature and Completely Transistorized
- No Wires or Antennas Needed



39.95 NO MONEY DOWN


Radar Sentry, the miniature electronic detector, warns you of radar traffic zones in advance—up to 1/2 mile away. The Dual-Band circuit detects all commonly used police radar speed meters and traffic control devices to promote safer driving. Miniaturized and completely transistorized, Radar Sentry does not require wires or antennas. Constructed of top quality components; printed wiring; 8 transistors; two 1,000 hour mercury cell,

self-testing batteries (equivalent to 35,000 miles of driving at 35 M.P.H.). Magnesium case eliminates radio, TV and other interference. Weighs only 13 ozs., measures 3 3/8" x 2 1/4" x 3 1/4" D; clips to sunvisor. Complete with batteries, sunvisor clip, magnetic base for dashboard use. Instructions included. Shpg. wt., 1 1/2 lbs. AA-104 Net 39.95

Car Model	Year	Cylinders	Stock No.	Car Model	Year	Cylinders	Stock No.
Bergward*	All	4	AA-116	Edsel	1958-60	8	AA-114
Buick	1953-61	8	AA-114	Plymouth	1956-61	8	AA-115
Buick Special	1961	8	AA-114	Ply. Valiant	1960-61	6	AA-115
Cadillac	1953-61	8	AA-114	Pontiac	1955-61	8	AA-114
Chevrolet	1955-61	8	AA-114	Pontiac Tempest	1960-61	6	AA-115
	1955-61	6	AA-115	Rambler	1956-61	8	AA-114
Corvair	1960-61	6	AA-115		1956-61	6	AA-115
Chrysler	1956-61	6	AA-115	Renault*	All	4	AA-116
	1956-61	8	AA-114	Studebaker	1956-61	8	AA-114
Crown Imp; 200	1956-61	8	AA-114		1956-61	6	AA-115
DeSoto	1956-61	8	AA-114	Volvo*	All	4	AA-116
	1956-61	6	AA-115	V.W.*	All	4	AA-116
Dodge	1956-61	8	AA-114	Willlys*	1940-59	4	AA-116
	1956-61	6	AA-115				
Dodge Dart	1961	8	AA-114	AA-114 For 8-Cylinder Cars			Net 19.95
	1961	6	AA-115	AA-115 For 6-Cylinder Cars			Net 19.95
Dodge Lancer	1961	6	AA-115	AA-114 For 4-Cylinder Cars			Net 19.95

*6-Volt Negative Ground

COMPLETE 120-PIECE SOCKET WRENCH and TOOL SET



Compare— Piece for Piece! Quality for Quality! Price for Price! YOU'LL NEVER FIND A BETTER BUY!!

- 120 Pieces—All Top Quality Chrome Alloy Steel
- 1/2", 3/8" and 1/4" Square Drive Sockets All in the SAME SET
- 12 Sets in One; A Lifetime Selection!

HERE'S WHAT YOU GET:

- 1—Heavy Duty Tool Box
- 1—Removable Tray
- 8—1/2" Square Drive Sockets: 3/16", 1/8", 3/16", 1/4", 5/16", 3/8", 7/16", 1/2" Openings
- 3—1/2" Drive Attachments: Extension, Hex Handle Ratchet
- 7—3/8" Square Drive Sockets: 3/16", 1/8", 1/4", 5/16", 3/8", 7/16", 1/2" Openings
- 3—3/8" Square Drive Attachments: Reversible Ratchet, 3" Extension, Pouch
- 8—1/4" Square Drive Sockets: 3/16", 1/8", 1/4", 5/16", 3/8", 7/16", 1/2" Openings
- 3—1/4" Drive Attachments: Hinge Handle, Cross Bar, Metal Box
- 6—Open End Wrenches: 1/2"x3/4", 3/8"x1/2", 1/2"x3/4", 5/8"x3/4", 3/4"x1/2" openings, Metal Clip
- 1—Combination Plier

- 7-Pc. Nut Driver Set; 2-Pc. Hacksaw and Blade; 12 Blades; 10-Pc. Screwdriver Set; 14-Pc. Twist Drill Set; 6-Pc. Screw Extractor Set; 12-Pc. Hex Key Set; 7-Pc. File Set; 9-Pc. Combination Wrench Set.

The best tool value Lafayette has ever offered—120 top quality pieces guaranteed against defects in workmanship and materials by the world's finest hand tool manufacturers. It's the most complete selection of sockets available at the price. Where else could you find 1/2", 3/8" and 1/4" sockets in the same set. Dependable and durable on any job from the kitchen to the car. Shpg. wt., 25 lbs. HD-978WX Net 32.50

32.50 NO MONEY DOWN

PLUS ALL THIS!

SAMPSON JR. LOAD-HELPER 5.85 SPRINGS

- Increases Load Capacity 750-1000 lbs.
- Assembled—Easy-to-Install in Only 15 Minutes
- Heavy-Duty Base—Special Tempered Steel Cord
- Fits Most Cars 1940-59 with Elliptical Springs



SAMPSON DE LUXE 6.95 SHOCK SPRINGS

- Custom Engineered for Ride Control

Eliminate drag, sag and car bottoming with these shock springs—get more road clearance EVEN WITH OVERLOADS. Can be installed on your present shock absorber—no replacement needed. Provides a level, cushioned ride, stabilizes car for easier steering and greater safety. Fits rear of cars listed below. Shpg. wt., 7 lbs.

Car	Year	Car	Year
BUICK	1956-60	MERCURY	1949-60
CADILLAC	1950-60	(Except '55 and '56 Series and Park Lane)	
CHEVROLET	1949-60	METROPOLITAN	1954-60
DART	1960	OLDSMOBILE	1951-57
DeSOTO	1938-60	PACKARD	1940-56
DODGE	1939-60	(Except '55 Series 60-80-88 and '56 Series 40-60-80-88)	
FALCON	1960	PLYMOUTH	1939-60
FORD	1947-60	PONTIAC	1937-60
(Except Thunderbird)		RAMBLER	Late 1952-60
HUDSON	1940-54	STUDEBAKER	1950-60
IMPERIAL	1955-60	VALIANT	1960
KAISER, HENRY J.	1947-54	WILLYS	1941-60
LINCOLN	1949-51		
	1956-58		

S.O.S. Magnetic WARNING SIGNAL 1.59

- 4" TWOFACED PARABOLIC REFLECTOR
 - NEW SUPER REFLECTIVE SURFACE
 - NO MOVING PARTS — BULBS — WIRES
- The simplest, most dependable and practical safety device to protect you in emergencies. No moving parts—no wires or bulbs. Use on or off the car. Holds magnetically to car in any position at any angle! Warns traffic in both directions! Parabolic reflector is highly visible from front or rear! Ideal for hand signaling! Makes a perfect road "flare"! Stand it on the metal plate furnished and position it on curved roads! It can't tip or slide! Completely effective in case of tail-light failure! The sway of the arm keeps it in continuous motion to insure pedestrian protection. HD-677 Shpg. wt., 1 lb. Net 1.59

100% AUTOMATIC SPARK PLUGS

- Precision made replacement for all ordinary SPARK PLUGS
- Reacts AUTOMATICALLY to all engine temperature changes
- Up to 40% greater voltage & increased power
- A "must" for foreign and compact cars

Stock No.	Type	Description	Net
AA-92	9C	Set of 6	6.90
AA-93	9C	Set of 8	9.20
AA-94	22C	Set of 6	6.90
AA-95	22C	Set of 8	9.20
AA-96	45C	Set of 6	8.90
AA-97	45C	Set of 8	9.20

Use This Chart To Select Proper Type for Your Car

MAKE	YEAR	TYPE	MAKE	YEAR	TYPE	MAKE	YEAR	TYPE
Buick	53-61	9C	Chrysler	54-58 N. York		Mercury	55-61	45C
Cadillac	53-61	9C	and Imp V8	22C	Olds.	50-61	9C	Studeb.
Chevrolet	58-61 "W"		Chrysler	59-61	9C	Opel	All	9C
			Ser V8	22C	Corvette	All	9C	Plymouth
								46-61
								9C
Chevrolet	53-61 (others)	9C	Dodge	50-61	9C	Plym, 6 Cyl.	60-61	22C
Chrysler	46-54	9C	Ford	46-54	9C	Pontiac	50-61	9C
Chrysler	54 Wind V8	22C	Ford	55-61	45C	Rambler	All	9C
Chrysler	55-58 Wind V8	9C	Mercury	46-54	9C	Renault	All	9C

SPARK PLUG WRENCH AND GAP GAUGE SET .77

For removal of most spark plugs and adjustment of spark gap. Gauge provides 6 different gaps. With wrench handle. Shpg. wt., 1 lb. HD-898 Net .77

Ignition TUNE UP KITS As Low as 1.10

- Preassembled-Matched — Ventilated Points
- Precision Engineered For YOUR Car
- Heavy Duty — Longer Operating Life
- Install Quickly, Easily — No Special Tools Required

Replace worn ignition parts for increased performance—easy starting—more gas economy. Needs no special tools. Factory assembled, perfectly matched and aligned, heavy duty points. Ventilated for cooling and self-cleaning action. Hi-dielectric rotor won't leak impulses. Moisture proof condenser. Complete set installs quickly and easily—in minutes. Shpg. wt., 10 ozs.

Car Model	Year	Stock #	Net, ea.	57	AA-65	1.55
Ambassador	56-59	AA-73	2.55	58-61	AA-80	1.70
	60-61	AA-80	1.70	(Advtr.) 60-61	AA-81	2.69
Buick	53-56	AA-70	1.60	Dodge 16 cyl.	50-60	AA-63
	57-61	AA-74	2.35	(CC Dist.) 5 cyl.	60-61	AA-79
Cadillac	51-55	AA-68	1.70	8 cyl.	53-55	AA-64
	56-57	AA-73	2.55	8 cyl.	56	AA-66
	58-61	AA-74	2.35	78 cyl.	57-60	AA-65
Chow, 6 cyl.	53-60	AA-69	1.35	(CC Dist.) 8 cyl.	60	AA-80
8 cyl.	55-56	AA-71	1.60	(D-500) 8 cyl.	60	AA-81
8 cyl.	57-60	AA-74	2.35	Edsel, 6 cyl.	59-60	AA-76
Chrysler, 6 cyl.	50-54	AA-63	1.45	8 cyl.	58-59	AA-78
8 cyl.	51-55	AA-64	2.35	8 cyl.	60	AA-83
*8 cyl.	56	AA-66	1.53	Falcon	60	AA-76
*8 cyl.	57-59	AA-65	1.55	Ford, 6 cyl.	49-61	AA-76
*8 cyl.	60-61	AA-80	1.70	8 cyl.	49-53	AA-76
††8 cyl.	60-61	AA-81	2.69	8 cyl.	54-56	AA-77
Comet	60-61	AA-76	1.10	8 cyl.	57-59	AA-78
Continental	56	AA-77	1.10	8 cyl.	60	AA-83
	58-59	AA-78	1.35	Lincoln	52-56	AA-77
	60-61	AA-83	1.55		58-59	AA-78
Corvair	60-61	AA-82	1.85		60-61	AA-83
Corvette	55	AA-70	1.60	Mercury	49-53	AA-77
	56-57	AA-72	1.60		54-56	AA-77
	58-61	AA-74	2.35		57-59	AA-78
DeSoto	56	AA-66	1.53			

PRIMETTA "RADAR" NIGHT GLASSES

- Increases Vision and Reduces Fatigue while Driving
- Reduces Glare from Headlights
- Excludes all Ultra Violet Rays
- Suede-Lined Leather Case
- See More Accurately in Comfort



2.69

Night driving is safer and easier with Primetta Radar Night Glasses. Scientifically designed to protect the eye from the glare of headlights, street lights, etc. without materially reducing vision. Ideal while driving at night in the rain, fog and snow. The filter lens excludes all ultra violet rays. Designed for 20-20 vision. With heavy, suede-lined leather case. Shpg. wt., 6 oz. AA-113L Net 2.69

NEW! DIMMER SWITCH EXTENSION

- Designed with You in Mind — No Installation Necessary
- Locates Dimmer Switch Where You Want It

Eliminate danger and accidents due to bright lights with the new dimmer switch extension. No more groping for that tiny dimmer switch. Easy-to-install, fits most cars since 1940. Ideal for women drivers with high-heeled shoes. Can be changed from car to car. Shpg. wt., 6 ozs. AA-85 Net .69



AUTO BUTLER—SWING-AWAY LITTER CONTAINER

- Fits Every Car
- Swings Away Out of Sight
- Removable Washable Container

Keep your car clean with this easy-to-install Auto Butler. Swings under the dash, keeps litter out of sight. Washable, heavy-duty vinyl container has 125 cubic-inch capacity. Every car should have one. Shpg. wt., 12 ozs. AA-91 Net .89

LAFAYETTE RADIO

ENGINEERED FOR SUPREMACY



99⁵⁰

NO MONEY DOWN

Made in U.S.A.



"Let Your Own Ears be the Judge"

LAFAYETTE 50-WATT STEREO AMPLIFIER Model LA-250 A

*Impressive Performance... Handsome Styling
... Another Unbeatable Lafayette Value!*

The Stereo 250A... a completely new stereo high fidelity amplifier with a high quality of reproduction, remarkable versatility and new distinctive styling—worthy of a place in the finest stereo hi-fi music system. A full range of controls enables you to enjoy the utmost in listening pleasure in any situation. A unique "blend" control which provides continuously variable channel separation—from full monaural to full stereo—may be used to eliminate the exaggerated channel separation found in some stereo source material. Included is a clutch-type Volume Balance control for independent or simultaneous control of both channels, concentric Bass and Treble controls which provide independent tonal control of each channel and a 4-position switch which selects phono, tuner, auxiliary or tape head stereo inputs. Simple slide switches provide channel reversal and phase reversal—or you can reproduce either channel through both amplifiers. A loudness switch permits the volume balance control to function as a compensated loudness control. The LA-250A also features a 3rd channel output which may be used to feed a 3rd single channel amplifier and speaker to provide a wider sound spread, a Tape Output jack for recording purposes, plus dual terminations for 4, 8 or 16 ohm speakers. Advanced circuitry includes DC operated preamp and tone control tube filaments for hum-free operation, 6CW5/EL86 push-pull output tubes, individual bias and balance adjustments on each channel and a hum balance control.

SPECIFICATIONS:
POWER OUTPUT & DISTORTION: 50 watts—25 per channel ± 1 db at less than 1% Total Harmonic Distortion at 1 KC. Less than 0.25% Total Harmonic Distortion at 1 KC at normal listening level (1 watt); less than 0.5% 1M distortion at normal listening level. FREQUENCY RESPONSE: 15-40,000 cps ± 0.5 db at normal listening level. HUM & NOISE: 70 db below rated output at max. volume (high level inputs). SENSITIVITY: For full output high level inputs 0.5V; Mag. Phono 3.5 MV at 1 KC. CHANNEL SEPARATION: Greater than 55 db at 1 KC; greater than 45 db from 20-20,000 cps. IMPEDANCE: 4, 8 and 16 ohms per channel. POWER: 200 watts; 110-125V AC 50-60 cycles.
Attractive beige vinyl laminated steel case. Handsomely designed three color brass etched front panel. Sienna brown molded legs and matching knobs with polished brass inserts. Dimensions with legs and knobs. 14 $\frac{1}{2}$ "x12 $\frac{3}{4}$ "x5 $\frac{1}{2}$ "H. Shpg. wt., 28 lbs.
LA-250AWX Net 99.50


**brehtaking performance
at a price only LAFAYETTE can offer.**



Clutch-Type Volume-Balance Control — Provides precise effective means of controlling volume and balancing stereo channels.



Dual Pre-amplifier Section — Inputs have been provided for every stereo-monaural function.



- 50 WATTS MONAURAL—25 WATTS EACH STEREO CHANNEL
- RESPONSE 15-40,000 CPS $\pm .5$ DB (at normal listening level)
- UNIQUE "BLEND" CONTROL
- PREMIUM EL86 OUTPUT TUBES
- SEPARATE BASS & TREBLE CONTROLS
- CLUTCH-TYPE VOLUME-BALANCE CONTROL
- 3RD CHANNEL OUTPUT

Outstanding New STEREO HI-FI Components

McIntosh

STEREO MULTIPLEX TUNER & PRE AMP

Combines the famous McIntosh Pre Amplifier and FM Tuner circuitry into a single outstanding component, equipped with facilities for FM stereo multiplex reception. Completely flexible, with individual Bass and Treble controls for each channel; Input Selector, Mode Selector Variable Channel Balance, Volume control, has switches for Muting, Loudness, Tape Comp., 0°-180° phase, LF and HF Filters. Tuner section employs a heavy flywheel tuning control. Frequency Response: $\pm 1/2$ db 20 to 20,000 CPS. Distortion: Less than 2% at rated output. Hum and Noise: 80db below rated output. Multiplex section features a front panel stereo indicator light. Hum Level is better than 60db below 100% stereo modulation with distortion less than 0.3%. Pilot carrier Suppression (18KC and 38KC) is greater than 40db below 100% modulation. For 117V 50/60 CPS AC. Size: 5 $\frac{1}{4}$ "x15 $\frac{1}{2}$ "x12 $\frac{1}{2}$ "D. Shpg. wt., 29 $\frac{1}{4}$ lbs.
G-343WX Net 374.50
Model L66 oiled walnut cabinet Net 25.00
G-178WX

NATIONALLY ADVERTISED FAMOUS BRAND STEREO MULTIPLEX ADAPTOR

Reg. Price 39.15
Lafayette Price 28.88

Many FM tuners are now equipped with an output jack wired to provide an external multiplex adaptor with the electrical information necessary for stereophonic reception. This adaptor is designed to operate in conjunction with FM tuners to provide two stereophonic audio channels which may be connected to the inputs of a stereo amplifying system. Since this adaptor is completely self-contained and self-powered, the only required connections to the existing audio system are those to the separate inputs of the stereo amplifier system. Frequency response of the adaptor is ± 3 db from 50 to 15,000 cycles. Hum and noise down 60 db. Mounting base is 10Lx2 $\frac{1}{4}$ "W, with mounting holes spaced 2 $\frac{1}{4}$ " Clearance of 3" required for tubes and capacitor.
G-336 Shpg. wt., 3 lbs. Net 28.88

H.H. SCOTT

MODEL 299C NEW SCOTT 72 WATT STEREO AMPLIFIER

A superb unit designed to accommodate every existing signal source. Aluminum chassis and D.C. heated pre-amp filaments for low hum. Uses 4-7591 Output tubes and rectifier.
FRONT PANEL CONTROLS: Input selector: 6 Mike, NAB tape head, RIAA record equalization, tuner tuner, extra. Selector Balance A, B, Monophonic Records; Stereo; Reverse stereo; Channel A, B; Tone Controls; Channels A, B, Stereo Balance; Derived Center channel Level Control; Loudness/Push-pull on/off; Pickup Selector; Tape Monitor; Scratch and rumble filters; Phase reverse; Loudness Compensation. Low impedance Stereo headphone output on front panel; High Impedance Stereo headphone output on rear. Dimensions in accessory case 15 $\frac{1}{2}$ "x5 $\frac{1}{4}$ "x13 $\frac{3}{4}$ "D. Shpg. wt., 28 lbs.
G-635WX (less case) Net 224.95
Leather finish steel case for above. Net 12.95
G-147W

WIDE-BAND FM MULTIPLEX TUNER

19995 NO MONEY DOWN

Moderately priced, this outstanding FM-multiplex stereo tuner provides the performance you can obtain only from WIDE-BAND design. Its wide-band design gives unparalleled frequency and dynamic ranges with low distortion and noise, even with weak signals. The 350 uses silver plated front end and is absolutely drift free without AFC. Main FM carrier circuit features 150 KC IF bandpass and 2 full stages of limiting. Usable (IHF) sensitivity 2.5 microvolts, low hum and noise and sensitivity 1 microvolt for 20db quieting using balanced 72 ohm antenna. Stereo outputs to amplifier and tape recorder. Dimensions in accessory case: 15 $\frac{1}{2}$ "x5 $\frac{1}{4}$ "x13 $\frac{3}{4}$ "D.
G-630WX (less case) Shpg. wt., 10 lbs. Net 199.95
G-147W Leather Finish steel case for 350 Net 12.95

THE FISHER

MPX-200 UNIVERSAL STEREO MULTIPLEX ADAPTOR

Self powered, compact and designed for easy connection, with placement up to three feet from the tuner, this new Multiplex adaptor provides high quality FM tuners and receivers, regardless of make. Two controls are provided to assure identical output levels from both channels. SPECIFICATIONS: Frequency Response: 20-15,000 CPS ± 1 db Separation: 35db (at 1KC) Gain: 16db. Hum and Noise: better than -70db; Tube Complement: Total of four tubes plus selenium rectifier plus eight diodes. For 105-120 volts 50/60 cycles AC operation. Size: 12Wx4Hx3 $\frac{1}{2}$ "D. Shpg. wt., 3 $\frac{1}{2}$ lbs.
G-669WX Net 79.50
New Model MPX-50 plug in stereo multiplex adaptor designed for use with the following Fisher tuners and consoles: FM100, 100-T, 202-T, Coronet (model 808), Coronet II (models C-55, and C-55A), Statesman (model 1010), and Statesman II (model S-70) No soldering needed, MPX-50 fits directly onto area provided on chassis. Shpg. wt., 1 lb. Not illustrated Net 59.50
G-668

Bell

FM-AM MULTIPLEX RECEIVER

235.15 NO MONEY DOWN

Consists of a 50 watt stereo amplifier (15 watts each channel), a versatile stereo preamplifier, an AM-FM tuner with built in multiplex facilities—a complete stereo electronic center in one compact convenient unit that equips you to play every type of stereo program material. Controls include: Dual Bass and Treble, Balance, OFF-ON Volume, AM tuning, FM Tuning, Monaural-Stereo Selector and AFC, AFC defeat. SPECIFICATIONS: 15 watts each channel, Total 30 watts (HF Method) Frequency Response—20-20,000 CPS ± 2 db; Distortion: Less than 2% @ 1KC; Hum and Noise: 66db below 15-watts; FM Sensitivity 2.5 μ v for 30db quieting, Selectivity: 6db down @ 240KC. Image Rejection: 38db. AM Sensitivity 6 μ v for 20db signal-to-noise ratio, Selectivity: 6db bandwidth @ 8KC. Finished in Satin black and brushed aluminum with walnut grain vinyl steel enclosure. For 117V 60 cycle AC. Size: 5 $\frac{1}{4}$ "x17 $\frac{1}{2}$ "x13 $\frac{3}{4}$ "D. Shpg. wt., 30 lbs.
G-354WX Net 235.15

THE FISHER

500-B 65 WATT FM MULTIPLEX STEREO RECEIVER

The new 500-B receiver has 18 controls and switches for flexible control of its wideband FM multiplex tuner, dual channel preamplifier and dual channel 65 watt power amplifier. Front panel controls are: FM tuning; MPX filter, dual volume, dual bass, dual treble, high filter, low filter, tape monitor, dual selector, mono-stereo, channel reverse, balance, loudness, FM circuit has 4 IF stages, advanced multiplex design, special switchable noise filter and "Stereo Beam" tuning indicator. SPECIFICATIONS: Amplifier distortion less than 0.5%; Overall frequency response 25-25,000 cps ± 1.5 db; FM sensitivity 0.7 μ v into 72 ohm load; IHFM sensitivity 2.2 μ v; signal/noise & hum 70 db. IF bandwidth 190 KC, channel selectivity 52 db; FM response (after deemphasis) 30-15,000 cps; Tubes: 4-ECC85, 6-6AU6, 4-12AX7, 2-7591, 2-EM84A, 1N-542, plus special multiplex tubes. Size: 17 $\frac{1}{2}$ "x5 $\frac{3}{4}$ "x13 $\frac{3}{4}$ " deep. G-640WX Less cabinet. Shpg. wt., 35 lbs. Net 359.50
FISHER 30-U Oiled Walnut Cabinet for 500-B. G-404W Shpg. wt., 6 lbs. Net 24.95

harman kardon

AWARD TA500X

50 WATT AM/FM STEREO RECEIVER

A complete stereo control center consisting of a sensitive, distortion-free AM/FM Tuner with built-in FM multiplex facilities, 50-watt stereo amplifier (25-watts each channel) plus a versatile stereo preamplifier. All components have been engineered into a single compact unit only 13 $\frac{1}{2}$ inches deep—small enough to place on a bookshelf. The TA-500X features a full range of controls for every stereo function including separate Bass and Treble controls for each channel plus Blend, Balance, Loudness and Function controls. Slide switches provide for Stereo Reverse, Equalization, Contour plus Hi-cut and Lo-cut filters. Front panel contains a Stereo Headphone Receptacle plus a front panel tuning meter allows precise visual tuning. Size: 16"Wx10 $\frac{1}{4}$ "x13 $\frac{1}{2}$ "D. Shpg. wt., 40 lbs.
G-656WX Net 299.95
G-657WX CX-80 Metal Case Shpg. wt., 5 lbs. Net 12.95
G-658W WW-80 Walnut Case. Shpg. wt., 5 lbs. Net 29.95

A COMPLETE STEREO SYSTEM BASED ON THE SUPERB LA-250A

brehtaking performance at a price only LAFAYETTE can offer.


THE SMART WAY TO BUY HI-FI!
Lafayette's Most Popular Stereo Phono System



LAFAYETTE LA-250A
50-WATT STEREO AMPLIFIER



CRITERION
EQUIPMENT CABINET
AVAILABLE FOR
84.50




CHOICE OF CARTRIDGE

"LISTEN AT HOME GUARANTEE"
Prove to yourself in your own living room, that the hi-fi system you select sounds as good at home as it does in our showroom.
LISTEN at HOME and BE SURE!
With Lafayette's Famous 30 Day FREE Trial if not completely satisfied with your purchase once you get it home, you can return it within 30 days and get your Full Purchase Price returned to you, less only transportation charges.



(OPTIONAL)
2 LAFAYETTE ELIPTOFLEX SERIES
BOOKSHELF ENCLOSURES



MATCHED COMPONENTS

- Lafayette LA-250A 50-Watt Stereo Amplifier 99.50
- Glaser-Steers GS-77 4-Speed Record Changer 59.50
- Lafayette Wood Changer Base 3.95
- Audio Empire S108 Diamond Needle Stereo Cartridge 35.00
- 2-Lafayette SK-58 Famous Free Edge 12" Coaxial Speakers @ 29.50 Each 59.00

Regular Catalog Price ~~256.95~~

LAFAYETTE SYSTEM PRICE 199.50
You Save 57.45
NO MONEY DOWN


LAFAYETTE MATCHED STEREOPHONIC SYSTEMS
*Make Certain to Indicate Your Choice of either Empire S108, Pickering 380C, Shure M7D or GE VR-1000-7 Diamond Needle Cartridge.

System No.	Amplifier	Changer	Cart	Base†	Speaker	Shpg. Wt.	Net
LS-251WX	LA-250A	GS-77	CHOICE OF	†	2 ea SK-58	67 lbs.	199.50
LS-252WX	LA-250A	AT-6	Audio	†	2 ea SK-58	67 lbs.	199.50
LS-253WX	LA-250A	GS-77	Empire S108	†	2 ea SK-58	2 ea Eliptoflex 143 lbs.	265.50
LS-254WX	LA-250A	AT-6	or	†	2 ea SK-180	67 lbs.	203.50
LS-255WX	LA-250A	GS-77	Pickering 380C	†	2 ea SK-180	2 ea Eliptoflex 143 lbs.	269.50
LS-256WX	LA-250A	AT-6	or	†	2 ea SK-180	2 ea Eliptoflex 143 lbs.	269.50
LS-257WX	LA-250A	GS-77	Shure M7D	†	2 ea SK-210	70 lbs.	233.50
LS-258WX	LA-250A	AT-6	or	†	2 ea SK-210	2 ea Eliptoflex 146 lbs.	299.50
LS-259WX	LA-250A	GS-77	GE VR 1000-7	†	2 ea SK-210	2 ea Eliptoflex 146 lbs.	299.50
LS-260WX	LA-250A	AT-6		†	2 ea SK-210	2 ea Eliptoflex 146 lbs.	299.50
LS-261WX	LA-250A	GS-77		†	2 ea SK-58	70 lbs.	219.50
LS-262WX	LA-250A	AT-6		†			
LS-263WX	LA-250A	Model A		†			

Any of above systems with addition of Lafayette LT-700 WX Multiplex Stereo Tuner (described on other pages) add \$114.50 to system price. When ordering add the letter T to the prefix.
Example: LS-251WX system with LT-700WX tuner is ordered as LST-251WX.
Eliptoflex—12" shelf type speaker enclosure.
†—Specify Mahogany, Walnut or Blonde Base.
*—Specify Walnut, Oiled Walnut, Mahogany or Blonde.
**—Specify Walnut, Oiled Walnut, Mahogany or Blonde.
AT-6—Garrard 4-Speed Record Changer. Model A—Garrard 4-Speed Record Changer.




GARRARD AT6



LAFAYETTE SK-180
"TRIMELIX" SPEAKERS

NEW LAFAYETTE CRITERION Hi-Fi CABINETRY... to decorate your home with music



Lafayette's Criterion Line — the standard of construction and design by which all others are judged.


The Criterion Stereo Furniture Ensemble

The Technical Know-How of Lafayette's Audio Engineers Combined with that of America's Finest Furniture Craftsman, bring to you the new Lafayette Criterion Line of Acoustically Correct Hi-Fi Furniture.

Now your high fidelity listening area can look as good as it sounds. Add the elegance, grace and timeless styling of this decorator inspired furniture grouping to your home music center, but lose nothing in performance. Painstaking acoustical design by Lafayette's audio engi-

neers provides the best possible relationship between equipment and furniture. The meticulous custom craftsmanship, rich, matched, natural wood veneers and custom hand-rubbed finishes of these fine cabinets are bound to please the most discerning taste.

THE CRITERION EQUIPMENT CABINET



84.50

"Component Engineered" by Lafayette's audio experts to provide ample, convenient, well-ventilated accommodations for all of your components. When matched with its companion Criterion Eliptoflex speaker enclosure (described on the right) it forms a complete music center. Cabinets employ rigid tongue and groove construction of 3/4" lumber core woods throughout, with matched veneers inside as well as out. Swinging doors with brass pulls and magnetic catches. Smartly styled with tapered legs and gold side trim. Overall Dimensions: 40Wx18Dx32 1/2"H including legs. Shpg. wt., 70 lbs.

THE CRITERION ELIPTOFLEX SPEAKER CABINET

The same graceful styling and fine construction as the CRITERION equipment cabinet, which it matches. Designed to accommodate any 12" speaker, this enclosure incorporates the inner construction and acoustic principles of the famous Lafayette "Eliptoflex" enclosure. A specially designed elliptical port with diffracting ring broadens frequency response. This results in natural smoothness and unequalled performance in the low ranges. Constructed of 3/4" lumber core woods with hand-rubbed natural wood veneers. Smartly styled with matching grille cloth, gold trim and tapered legs. Overall Dimensions: 32 1/2 H x 18 D x 16 W. Shpg. wt., 50 lbs.

55.50
NO MONEY DOWN



**LOW COST
HIGH VALUE!**

COMPLETE 24-WATT MATCHED COMPONENT STEREO PHONO MUSIC SYSTEM



LA-212 24 Watt Stereo Amplifier

CHOICE OF CARTRIDGE



Garrard Autoslim Changer

Wood Base



G-542WX



Lafayette SK-124
2-Way Speaker Systems

**INCREDIBLY
PRICED
AT ONLY**

128.45

NO MONEY DOWN

Dollar For Dollar—Decible For Decible . . . Any Way You Measure It This Is The Greatest Stereo High Fidelity Music System Value Available Today.

**THESE COMPONENTS
MATCHED FOR VALUE
AND PERFORMANCE**

Lafayette LA-212 24-Watt Stereo Amplifier	49.95
Garrard Autoslim 4 Speed Stereo Record Changer	39.50
Woodbase for Changer (Specify Walnut, Mahogany or Blonde)	3.95
Audio Empire S108 Diamond Needle Stereo cartridge	35.00
2-Lafayette SK-124 Ultra-Compliance 2-Way Speaker Systems (Specify Walnut or Mahogany)	34.00
Your Regular Catalog Price Would Be	162.40
At Lafayette's Low System Price You Save	33.95
Your Total Cost Is	128.45

Incredible Price—Incredible Value—Incredible Performance . . . A complete stereo phono system selected and matched by Lafayette's audio experts for outstanding value and performance.

Heart of the system is the new LA-212 24-Watt Stereo Amplifier. This attractive low silhouette component contains dual 12 watt stereo amplifier and preamplifier with a full array of inputs and controls. The Garrard Autoslim 4-speed record changer is equipped with handsome woodbase and your choice of stereo cartridges. This precision unit features separate manual and automatic controls and intermixes all size records.

Two Lafayette SK-124 Ultra-Compliance 2-Way Speaker

System especially designed for stereo complete the system and provide a purity of sound and musical quality you'd expect from stereo components many times Lafayette's low price. Finished on 4 sides in your choice of mahogany or walnut. The SK-124 may be placed horizontally or vertically.

Complete stereo system as listed above with your choice of either the Audio Empire S108, Pickering 380C, Shure M7D or GE VR1000-7 diamond needle stereo cartridges.

LS-312WX Shpg. wt., 65 lbs. Net 128.45

Same as LS-312WX listed above plus the G-542WX FM-AM Stereo Multiplex Tuner. LS-313WX Shpg. wt., 75 lbs. Net 202.95



NEW 24-WATT STEREO AMPLIFIER

MADE IN U. S. A.

ONLY 49.95

No Money Down

SPECIFICATIONS:

Power Output: 24 watts RMS (12 watts each channel). Frequency Response: ± 1 db, 20 to 20,000 cps at 1 watt; Harmonic Distortion—Less than .5% (1000 cps); Intermodulation Distortion — 2% at 10 watts; Damping Factor 4.5; Input Sensitivity: Aux. Tuner—.7 volt, Mag phono—.0055 volt, Tape Head—.0075 volt and Crystal phono—.35 volt for rated output (1000 cps); Hum and Noise 72 db Tuner input and 52 db phono input below rated output; Tubes 4-6EU7, 4-6BQ5 and EZ81/6CA4.


OUTSTANDING PERFORMANCE AND VALUE!!

HARMONIC DISTORTION LESS THAN .5% (at 1,000 cps)
IM DISTORTION LESS THAN 2%

- Frequency Response 20-20,000 cps ± 1 db
- Individual Bass and Treble Controls For Each Channel
- Variable Balance Control

All the quality and performance you could ask for in a stereophonic amplifier, and Lafayette brings it to you at a budget price. Every outstanding stereophonic amplifier feature has been incorporated—complete versatility allows using this instrument as a dual 12-watt stereo amplifier or as a single 24-watt monophonic unit. Additional features include: separate Bass and Treble control to provide independent tone control of each channel; easy-to-use master loudness control; Balance Control allows proper balance of each stereo channel too, individual room acoustics and speaker placement; three slide switches furnish fast easy switching between 12 watt per channel stereo operation or 24 watt monophonic operation, phono or tuner sources, and magnetic or crystal cartridges. Dual rear panel inputs are provided for magnetic phono, crystal phono, tuner, auxiliary, tape (high impedance). Speaker outputs allow use with 4, 8 or 16 ohm speakers. Attractively styled with a rich brown low silhouette enclosure and contrasting brushed aluminum front panel. Size: $\frac{1}{2}$ Hx9Dx14"W. For 110-120V 60 cycle AC.

LA-212WX Shpg. wt., 21 lbs. Net 49.95



A FABULOUS BUY!

NEW KORDEX AM-FM STEREO MULTIPLEX TUNER

- Foster Seeley discriminator
- AFC (plus AFC Defeat Switch) Locks In Stations—Prevents Drifting
- Stereo Separation Control
- Four FM IF Stages plus 2 AM IF Stages
- Flywheel Tuning
- 4 μ v Sensitivity For 30db Quieting
- Dual Channel Cathode Follower Output
- FM Frequency Response—1db 20-20,000

ALL THE QUALITY, FEATURES AND PERFORMANCE YOU'D EXPECT FROM TUNERS MANY TIMES THIS LOW LAFAYETTE PRICE.

ONLY 74.50

NO MONEY DOWN

SPECIFICATIONS: Sensitivity: FM 4 microvolts for 30db quieting, AM 75 Microvolts loop sensitivity; Frequency Response: FM—1db 20-20,000 CPS; AM—2db 20-5000 CPS; Selectivity—FM 250 KC bandwidth, 6db down, AM 7KC Bandwidth 6db down; Hum Level—70db below 1 volt. Tubes: Total of Ten—6U8, 12AT7, 6BEG, 6BAG, 2-6AUG, 6A15, 6C4, 2-12AU7, plus 2 matched diode detectors.

An excellent performer with outstanding features and at Lafayette's low price a truly fabulous buy. Engineered to provide the widest possible range of tuner flexibility it's capabilities include—Sparkling clear AM reception, highest fidelity FM reception and most important FM multiplex stereo reception. Front panel controls provide complete tuner flexibility with smooth action AM-FM flywheel tuning, Selector Switch (Off-On, FM, FM with AFC, AM), Monaural-Stereo Multiplex Switch, and a Calibrated Stereo Separation Control. The Automatic Frequency Control virtually locks in stations and prevents drift while the AFC defeat position allows easy tuning of weaker or distant FM station adjacent to stronger stations on the tuning dial. A Stereo Separation Control allow precise channel separation according to individual acoustic requirements during FM stereo multiplex

operation. Quality FM circuitry features a Foster Seeley Discriminator with 4 IF stages including discriminator, an R.F. Input stage plus Dual Channel Cathode follower output. The FM stereo MPX section utilizes an ASC-Doubler with 2 Diode Detectors plus a Dual Channel Cathode Follower Output. AM circuit feature two IF Stages plus OSC/Mixer and Diode Detector with a Dual Channel Cathode Follower Output. In addition an Automatic Volume Control (AVC) insures a constant output in tuning from station to station. Attractive low silhouette styling features brushed brass front panel with contrasting ebony finished steel enclosure. Size: 13 $\frac{1}{2}$ Lx 4 $\frac{1}{8}$ Hx11 $\frac{1}{2}$ D. Equipped with AM ferrite rod antenna plus FM line cord antenna. For 110-120V 60 cycle AC. G-542WX Shpg. wt., 10 lbs. Net 74.50

JUST OUT! FM-AM TUNER Superior Quality and VALUE!



Made in U.S.A.

49.95

Receive FM and AM broadcasts with this "best value" tuner. Delivers the same fine performance and value as the (G-542WX) Kordex Tuner described above, but it is equipped with a multiplex output jack that will allow you to add multiplex later at your convenience with one of Lafayette's Kit or factory wired low cost multiplex adaptors. Front panel controls include: Selector Switch for OFF, FM and FM AFC positions plus flywheel tuning control for velvet smooth tuning. For 110-120V 60 cycle AC operation. Finished in attractive brushed brass with matching ebony enclosure. Size: 13x4 $\frac{1}{2}$ x9". G-541WX Shpg. wt., 10 lbs. Net 49.95



LAFAYETTE 40-WATT ALL TRANSISTOR STEREO AMPLIFIER LA-440



99⁵⁰
NO MONEY DOWN

STUDY & COMPARE THESE SPECIFICATIONS

I.H.F.M. Music Power Output: 40 watts (20 watts per channel) based on 4-ohm load impedance. Frequency Response ± 0.5 db 20 to 20,000 cps measured according to IHFM standards. Intermodulation Distortion: 0.9% to 1 db below clipping 60 and 6,000 cps. Harmonic Distortion: 0.5% at 1 db below clipping. Hum and Noise: Completely inaudible at all playing levels. Phono Input: -72 db Tuner Input: -85 db. Output Impedance: May be used with 4, 8, 16 ohm loud-speakers. Power Requirements: 105-120 volts AC, 50-60 cps. 12 to 28 volts DC for battery operation.

• Dual Concentric Bass & Treble Controls • Brilliant Design & Performance • Frequency Response — ± 0.5 db 20 to 20,000 cps • Instantaneous Operation — No Warm-Up Required • Hum, Noise & Microphonics Virtually Eliminated • Place Anywhere — Does Not Require Ventilation as No Heat Is Generated.

NEW!

- 20 Transistors plus
- 4 Germanium Diodes plus
- 3 Silicon Diodes plus
- 2 Thermistors



Made In U.S.A.

Now Lafayette applies space-age electronics to high-fidelity design to bring you this superb new 40-watt stereo amplifier (20-watts each channel). Utilizing the most advanced transistor circuitry, the LA-440 completely eliminates tubes and output transformers; substituting in their place a total of 29 solid state devices to provide an unmatched level of stereo high-fidelity performance. Here is an amplifier that: **GENERATES NO HEAT**—no need to worry about ventilation, you can place it anywhere and current drain is so low, it will operate efficiently not only at 110 V AC, but even from 12 to 28 volt batteries. **REQUIRES A MINIMUM OF MAINTENANCE**—since transistors last indefinitely maintenance problems are virtually a thing of the past and performance will not deteriorate, **VIRTUALLY ELIMINATES HUM, NOISE AND MICROPHONICS**—performance can best be described as transparent, the only sound you hear is that of the music. **PRO-**

VIDES INSTANTANEOUS OPERATION, no need to wait for warm-up, the LA-440 plays as soon as it is turned on.

Controls are provided for every possible stereo, hi-fi function: Front panel contains dual concentric Bass and Treble controls, Volume control, Balance control and Selector switch for Phono, Tuner, Tape, Aux 1 and Aux 2 with corresponding inputs provided on the rear panel. In addition, slide switches are provided for Mono A—Stereo—Mono B, Loudness, Scratch Filter and Rumble Filter. Rear panel contains 2—switched AC outlets plus 3 tape outputs for recording stereo or mono (Tape A, Tape B, A & B).

Superbly styled, the LA-440 measures only 3Hx10Wx8 1/2"D and is finished in a brushed gold front panel, gold finished aluminum knobs and is complete with matching enclosure. Shpg. wt., 10 lbs. **LA-440WX** Net 99.50

NEW! LAFAYETTE ALL-TRANSISTOR FM-MULTIPLEX STEREO TUNER WITH BUILT IN MULTIPLEX

Runs Cool
Place It Anywhere!

- 20 Transistors — 9 Diodes Includes 8 Transistor Automatic Multiplex Section • Built-In Tuning Meter • Frequency Response 20-20,000 Cps ± 1 db • Automatic Frequency Control • Interstation Muting • Unmatched Reception of FM and FM Stereo Broadcasts

Years of Trouble free listening are yours with the Lafayette LT-300 all transistor multiplex tuner. A perfect match for the LA-440 amplifier both in appearance and performance. The tuner eliminates hum, heat or microphonics, problems associated with tube units. Super powered transistor circuit provides dazzling reception of FM and Stereophonic FM Multiplex Broadcasts. Wide band design with AFC assures greater selectivity, high sensitivity and an amazingly low signal-to-noise ratio. The built-in multiplex section is completely automatic... no controls to set. Synchronous—gate separation


of channels from composite signal reproduces all the audio information with low distortion. Advanced design keeps circuit exceptionally stable with no adjustments needed. Deluxe signal-strength meter indicates perfect reception at all times. Interstation muting avoids annoying FM hiss and pops found between stations.

Power requirements are very small, consumes only 4 watts at 105-120V AC. Brushed brass panel, tan covers — matches companion amplifier LA-440. Size: 3Hx10Wx8 1/2"D. Shpg. wt., 8 lbs. **LT-300WX** Net 149.95

Built-In
Tuning
Meter

149⁹⁵

Regularly 209.95
NO MONEY DOWN




SPECIFICATIONS:

Sensitivity: 1.8 microvolts for 20db quieting. Selectivity (IF bandwidth) 270 KC at -6 db points. Discriminator Peak-to-Peak separation 1 megacycles. Noise level: 66db below 100% modulation. Antenna Input Impedance 300 ohms.

Made in U.S.A.

40-WATT ALL TRANSISTOR LA-440 AMPLIFIER IN MATCHED STEREO SYSTEMS



MADE IN U.S.A.



194⁵⁰
NO MONEY DOWN



LAFAYETTE SK-58 12" COAXIAL SPEAKERS



CHANGER BASE

LESA CD2/21



GARRARD "AUTOSLIM" (ALTERNATE CHANGER)



SK-100 TRIMMER SPEAKERS

ELIPTOFLEX

LAFAYETTE 40-WATT ALL TRANSISTOR AMPLIFIER IN MATCHED STEREO SYSTEMS		
Lafayette LA-440 40-Watt All-Transistor Stereo Amp.		99.50
Lesla CD 2/21 4-Speed Record Changer		44.50
Wood Base for Changer (Specify Walnut, Mahog. or Blonde)		4.75
Audio Empire S108 Diamond Needle Cartridge		35.00
2-Lafayette SK-58 Free Edge 12" Coaxial Speaker @ 29.50 each		59.00
LAFAYETTE SYSTEM PRICE	194.50	REGULAR CATALOG PRICE 242.75
		YOU SAVE 48.25

System No.	Amplifier	Changer	Cart*	Base	Speaker	Speaker Cabinet**	Shpg. Wt. Lbs.
LS-441WX	LA-440	Lesla	CD 2/21	+	2 ea. SK-58		48 194.50
LS-442WX	LA-440	Garrard	Autoslim	+	2 ea. SK-58		48 194.50
LS-443WX	LA-440	Lesla	CD 2/21	+	2 ea. SK-58	2 ea. Eliptoflex	96 260.50
LS-444WX	LA-440	Garrard	Autoslim	+	2 ea. SK-58	2 ea. Eliptoflex	96 260.50
LS-445WX	LA-440	Lesla	CD 2/21	+	2 ea. SK-180		45 198.50
LS-446WX	LA-440	Garrard	Autoslim	+	2 ea. SK-180		45 198.50
LS-447WX	LA-440	Lesla	CD 2/21	+	2 ea. SK-180	2 ea. Eliptoflex	93 264.50
LS-448WX	LA-440	Garrard	Autoslim	+	2 ea. SK-180	2 ea. Eliptoflex	93 264.50

Any of above systems with addition of Lafayette LT-300 All-Transistor Multiplex Stereo Tuner (described above), specify System Stock No. plus LT-300 Tuner and add 134.95 to system price.

* Be Sure To Specify Choice of Empire S108, Pickering 380C, Shure M7D or GE-VR1000-7 Cartridge.

LAFAYETTE 40-WATT ALL-TRANSISTOR TUNER AMPLIFIER RECEIVER SYSTEM

LA-440 All-Transistor 40-Watt Amplifier	99.50
LT-300 Transistor FM Multiplex Tuner	149.95
Walnut Enclosure	19.50
Catalog Price	268.95



YOU SAVE 9.50

Lafayette Complete Receiver Price **SPECIAL 259.45**

MADE IN U.S.A.

COMPACT SPACE SAVING COMBINATION OF ULTRA-MODERN DESIGN

Space age electronics has developed this compact system. Small size and no heat generation enable this smart looking ensemble to be placed anywhere in your home. The all-transistor LA-440 amplifier and LT-300 tuner complement each other perfectly for outstanding performance of musical material via records, tape or

FM stereophonic multiplex programs. A beautifully finished walnut cabinet completely encloses the top and sides of the units giving them a "custom built" look. Front panels of brushed brass with black knobs and white switches. **LA-445WX** Net 259.45

NEW! TEC S-25 68 WATT ALL-TRANSISTOR STEREO PREAMP-AMPLIFIER



MADE IN U.S.A.

Acclaimed by Audio Magazine

- 34 WATTS EACH CHANNEL*
- NO HEAT, NO HUM, NO TUBES
- 16 INPUTS
- GUARANTEED TWO-YEARS

174.50

Now from transistronics, recognized specialists in the transistor field comes the powerful model S-25. Using precision transistors, it is a combination stereo audio control center, preamplifier and power amplifier on one compact chassis. Provides 34 watts of music power output on each channel with a full frequency response of 20-20,000 CPS. Superior sound is evident due to low (0.72%) harmonic distortion and intermodulation distortion of only 0.9 percent. Direct coupling to power output transistors is achieved through an auto-transformer for extended bass response. A wide variety of combinations is possible with 16 inputs; switch for High Level phono; NARTB Tape equalization playback, low level microphone, 3 high level Tuner, and one-high level auxiliary input. Includes 4, 8 and 16 ohm outputs for each channel, tape recorder outputs

for each channel and mixed A+B output for third channel operation. In addition remote volume and balance control operation is possible through an accessory outlet jack on the rear of the unit. Among the other features of the TEC-25 are Baxandall tone controls for natural sound, 2 level controls, rumble filter, phase reversal switch, and 3 AC switched receptacles. Low power consumption 70 watts max. at full output less than 15 watts at normal listening levels, and it may also be operated from 12 to 18 volts off car battery if desired. Full wave power supply is transformer operated. Finished in handsome black and satin aluminum panel with a black cover and walnut end pieces. Power requirements: 117 V.A.C. or 12-18 V.D.C. Size 14 3/4x4 1/4x14 3/4"D. Shpg. wt., 34 lbs. **G-564WX** Net 174.50

the ULTIMATE FM MULTIPLEX STEREO TUNER

the new...

Now! from the
LAFAYETTE
HIGH-FIDELITY
RESEARCH
LABORATORIES



124.50
NO MONEY DOWN!

Criterion™

FM LT-700 STEREO MULTIPLEX TUNER



MADE IN U.S.A.

FREE! LAFAYETTE FM STEREO
MULTIPLEX BROCHURE

Lafayette has prepared an informative, fact-filled brochure describing FM stereo Multiplex Broadcasting. Write for your free copy of brochure BK-50, "Facts About FM Stereo Broadcasting."



- Virtually Distortionless Performance — Less than 0.15% Distortion at 100% Modulation, Monaurally • Low Noise Front End With Triode Grounded Grid Amplifier and Triode Mixer • Electronic Bar Tuning Indicator
- Double-Tuned Dual Limiters and Foster Sealey Discriminator • Stereo Separation: 35 db at 400 cps. • Frequency Response $\pm \frac{1}{2}$ db 15-35,000 cps, Monaurally • Variable AFC Literally "Locks In" Stations • Sensitivity 1.25 μ V for 20 db of Quieting • 3 Gang Tuning Condenser

The LT-700 is another impressive example of Lafayette's engineering leadership. For here is a tuner that achieves a level of distortionless performance and flexibility that sets the standard for professional FM multiplex reception. Its superb circuitry features a low noise front end with triode mixer, double-tuned dual limiters and wide band Foster Sealey discriminator. Distortion has virtually been eliminated with less than 0.15% distortion at 100% modulation (monaurally). Sensitivity of the LT-700 is such that in many areas the only antenna needed will be a short piece of wire, except of course in remote locations. Plate follower outputs permit using the tuner up to 50 feet from the amplifier. Designed for maximum versatility, the LT-700 features a convenient front panel volume control for precision adjustment of tuner output level. In addition a

variable AFC (automatic frequency control) is provided. Once properly tuned, the AFC literally "locks in" the station and is adjustable for tuning weak stations adjacent to strong stations. Pinpoint tuning accuracy is assured by a special electronic bar tuning indicator that indicates maximum closure at the point of best tuning. Multiplex operation is achieved by a simple front panel switch. This also activates a stereo light when the station tuned to starts broadcasting stereo. Every LT-700 is individually aligned and tested to meet or exceed Lafayette's specifications. Attractively styled with a cream and brushed brass front panel set in a beige finished vinyl enclosure. Size 13 $\frac{3}{4}$ "x10 $\frac{1}{2}$ "x4 $\frac{1}{2}$ "H. For 117V. 50-60 cycle AC. LT-700WX Shpg. wt., 16 lbs. Net 124.50

TECHNICAL SPECIFICATIONS

Sensitivity: 1.25 μ V for 20 db of quieting. Harmonic Distortion: 0.15% at 1Kc 100% modulation. Signal-to-Noise Ratio: Better than 57 db. Freq. Response: $\pm \frac{1}{2}$ db 15-35,000 cps monaurally. Image Rejection: -50db. Stereo Separation: Built-in MPX section provides 35db separation at 400 cps. Discriminator Linearity: 600 Kc. Audio output: 1.75v at 75 Kc deviation (100% modulation). Tubes: Simple manual switching for FM multiplex operation. Anode follower for low impedance 2-No. 47 Pilot Lights. Automatic FM stereo indicator light. 2-6BA6, 2-7543, 6AL5, E2-81 rectifier, 2 matched diodes plus EM-84 tuning eye.

LOOK at THESE QUALITY LT-700 FEATURES!

- 1 Simple Front Panel Switch for Mono or Stereo Multiplex
- 2 Variable AFC "Locks In" Stations

THE REMARKABLE

KT-650 FM TUNER KIT

MADE IN U.S.A.



- Low Noise Front End With Triode Grounded Grid Amplifier and Triode Mixer • Double Tuned Dual Limiters and Foster Sealey Discriminator • Sensitivity 1.25uv For 20 db of Quieting
- Variable AFC Literally "Lock In" Stations • Frequency Response $\pm \frac{1}{2}$ db 15-35,000 cps • Multiplex Output For Stereo FM • Easy-to-Build Printed Circuits • Electronic Bar Tuning Indicator Tube • Pre-Aligned IF and Discriminator Coils • 3 Gang Tuning Condenser • Virtually Distortionless Performance—Less than .15% Distortion at 100% Modulation.

NO MONEY DOWN

KT-650 in KIT FORM

54.50

LT-650 Factory
Wired & Tested

79.95

READY FOR MULTIPLEX!

The KT-650 incorporates every desirable FM Tuner feature. A Multiplex jack provides for addition of a Multiplex Adapter for FM Stereo Reception. Flywheel weighted tuning enables effortless station-to-station tuning. Pinpoint tuning accuracy by a special electronic bar tuning indicator tube. A variable AFC (Automatic Frequency Control) is featured—literally "locks in" the station and is adjustable for tuning weak stations adjacent to strong stations. The Tuner Level Control allows precise adjustment of the Tuner output level. Superb circuitry features a low noise front end with triode mixer plus double tuned dual limiters and wide band Foster-Sealey discriminator. Sensitivity is such that in many areas the only antenna needed will be a short piece of wire, except in remote locations. Plate follower outputs permit using the tuner up to 50 feet from the amplifier. Time-saving printed circuit boards are utilized to make wiring errors almost nonexistent.

IF and discriminator coils have been carefully factory prealigned—permits you to play the tuner as soon as assembled.

The superbly styled low silhouette enclosure will do justice to any decor. Beige cover is set off by a Cream and Sienna Brown etched panel and knobs with contrasting Black Dial Face. Complete with cage, legs, interconnecting cables with plugs, indoor folded dipole antenna and alignment tool. Overall Dimensions: 14x5 $\frac{1}{2}$ x11"D. For 117V, 50-60 cycle AC. Power consumption 40 watts. Shpg. wt., 13 $\frac{1}{2}$ lbs.

KT-650WX FM Tuner Kit	Net 54.50
HTA-14WX Combination of KT-650 and LT-200 FM Multiplex Adapter. You Save 5.00	Net 104.00
LT-650WX Factory Wired & Tested	Net 79.95
HTA-15WX Combination of LT-650 and LT-200 FM Multiplex Adapter. You Save 5.00	Net 129.45

COMPARE THESE SPECIFICATIONS:

Sensitivity: 1.25 microvolts for 20 db of quieting. Image Rejection: 66 db. AM Suppression: 48 db. Discriminator Linearity 600 kc. Distortion and Noise: Better than 57 db below 1.5 volts at 100% modulation. Frequency Response: $\pm \frac{1}{2}$ db from 15 to 35,000 cps with a standard 75 microsecond de-emphasis network. Audio Output: 1.75 volts at 75 Kc deviation (100% modulation). Antenna Input: 300 ohm. Controls: Tuning; Level; AFC Control and Power Switch. Outputs: (2) Multiplex Adapter; Amplifier. Tube Complement: ECC85, 6BK7B, 6AL5, 2-7543, 2-6BA6, 6AV6, EM84 Electronic Bar Tuning Indicator Tube and a silicon diode rectifier.

The Most Flexible Tuner Ever Designed LAFAYETTE STEREO TUNER KT-500A



MADE IN U.S.A.

KT-500A
74.50

NO MONEY DOWN
IN KIT FORM

LT-50A

124.50
NO MONEY DOWN

COMPLETELY WIRED AND TESTED

- MULTIPLEX OUTPUT FOR NEW STEREO FM • TWO PRINTED CIRCUIT BOARDS AND PREALIGNED IF'S • FM AFC AND AFC DEF
- 17 TUBE PERFORMANCE—11 Tubes (4 dual-purpose) + Tuning Eye & Selenium Rectifier • ARMSTRONG CIRCUIT WITH DUAL LIMITERS AND FOSTER-SEELEY DISCRIMINATOR • 12 TUNED CIRCUITS AND DUAL CATHODE FOLLOWER OUTPUTS • EXTREME SENSITIVITY AND WIDE FREQUENCY RESPONSE

The KT-500A will receive simultaneous FM and AM stereo broadcasts or may be utilized for normal FM or AM reception. Provides an output for the new multiplex FM stereophonic reception. Apart from its unique flexibility, the KT-500A offers noise-free, drift-free, distortion-free performance. Each FM & AM section is tuned with its own 3-gang tuning capacitor and is provided with individual cathode follower outputs. Also, separate volume controls are provided for each channel so that when used for stereophonic reception, a proper balance between channels can be achieved. Convenient front panel switch changes from stereo to monaural use. Simplified accurate knife-edge tuning is provided by magic eye which operates independently on FM and AM. Automatic frequency control "locks in" FM signal permanently. Ferrite rod antenna with loading ring is supplied to bring in weak AM stations. Designed for easy assembly, the kit is built around two printed circuit boards and prealigned IF's insuring fast accurate construction even for the beginner. Employs a cream and brushed brass front panel plus matching brown knobs with copper inserts set in a beige finished vinyl enclosure.

KT-500AWX Stereo Tuner Kit	Net 74.50
HTA-12WX Combination of KT-500A and LT-200 Multiplex Adaptor	You Save 5.00 Net 124.00
LT-50AWX Same as KT-500AWX, completely wired and tested	Net 124.50
HTA-13WX Combination of LT-50A and LT-200 Multiplex Adaptor	You Save 5.00 Net 174.00

SPECIFICATIONS

FM CIRCUIT: Armstrong, low noise front end with triode grounded grid amplifier and triode mixer. Double tuned dual limiters, Foster-Sealey discriminator, AFC and AFC defeat. AM CIRCUIT: Superhet with 3 stages AVC, 10kc whistle filter, ferrite antenna. DISTORTION: Under 1% harmonic on FM; under 1% on AM for up to 80% modulation. HUM LEVEL: 60 db below 100% modulation. SENSITIVITY: FM—full limiting on signals as low as 1 μ V, 2 μ V for 30 db quieting; AM Terminal Sensitivity 5 μ V. SELECTIVITY: FM 200 kc bandwidth; 6 db down, AM 8kc BW; 6 db down. FREQUENCY RESPONSE: FM 20-20,000 cps $\pm \frac{1}{2}$ db, AM 20-5,000 \pm 3 db. IMAGE REJECTION: FM 40 db; AM 30 db. I. F. REJECTION: FM 70 db, AM 50 db. CONTROLS: 5 controls; FM VOL, AM VOL, FM Tuning, AM Tuning, and five position function selector switch. TUBES: 3-6BA6, 2-6AU6, 1 each 6BK7B, ECC85, 6AL5, 6BE6, 12AU7 and 6U5 tuning eye. Selenium rectifier. OUTPUT IMPEDANCE: Low impedances cathode follower. Output jacks for FM, AM or Stereo. ANTENNA INPUT: 300 ohms. Size 13 $\frac{3}{4}$ "x10 $\frac{1}{2}$ "x4 $\frac{1}{2}$ "H. Shpg. wt., 18 lbs. Kit comes complete with all parts and metal cover, a ctan-hv-step instruction manual, schematic and pictorial diagrams.

ASSURANCE OF COMPONENT QUALITY
ONE YEAR PARTS GUARANTEE
All components in this unit are conservatively engineered to operate well within their performance capabilities. As assurance of this quality, Lafayette guarantees all parts including tubes for one year.

"I congratulate you people on the tremendous job you have done with this FM tuner."
Donald MacKenzie
Marlboro, Mass.


"The KT-650 performed as beautifully as it went together."
Curtis Frets,
Ontario, Calif.

"In this era of loose claims by many reputable manufacturers, you may feel a deep sense of pride in producing this kit. Every claim you made is true."
George F. Schaefer
Ramsey, N. J.

Some Letters
Out of
THOUSANDS

"A pleasure to build."
Francis J. Crowley
Hempstead, N. Y.

USE AS TWO INDIVIDUAL TUNERS
Use as a FM-AM Stereophonic Tuner for simulcast stereo or with a multiplex adapter for FM stereo reception
FM IN ONE ROOM . . . AM IN THE OTHER



"... this kit is excellent all the way around. It would be difficult to improve upon."
Robert Meier
Washington, D.C.

"Instructions were very good. Performance is wonderful. Best all around design."
S. B. Heberlik
Glendora, New Jersey

LAFAYETTE Criterion STEREO COMPONENTS

LAFAYETTE KT-600A STEREO PRE-AMPLIFIER MASTER CONTROL CENTER

MODEL KT-600A
79.50
 IN EASY-TO-BUILD KIT FORM
 COMPLETELY WIRED AND TESTED
 LA-600A
134.50
 NO MONEY DOWN!




MADE IN U.S.A.

The KT-600A represents a brilliant stereo achievement. This "no-compromise" stereo pre-amplifier and control unit offers unlimited versatility, includes every feature necessary for the finest reproduction. It has a total of 12 input jacks (6 stereo pairs) for program sources of any type and level—all of which may be selected by front panel control. Separate turnover and roll-off switches provide 24 positions of correct equalization—Independent for each channel. Dual concentric stereo function selector for maximum flexibility in controlling selected program sources. A unique Bridge Control provides continuously variable channel separation from full mono to full stereo, or it can optionally be used to regulate the 3rd channel output. A clutch-operated Volume Balance Control provides independent or simultaneous level adjustment of channels. Low impedance Plate Follower outputs are used, and a host of many other professional type features.

KT-600AWX Stereo Pre-amplifier Kit No Money Down Net 79.50
 LA-600AWX Stereo Pre-amplifier, wired and tested No Money Down Net 134.50

SPECIFICATIONS

FREQUENCY RESPONSE: 5-40,000 cps \pm 1 db. DISTORTION: Less than 0.05% IM at 2 volts out; Less than 0.1% Harmonic, at 2 volts out. SENSITIVITY: Low Level 2.2 mv for 1 volt out; high level 94 mv for 1 volt out; Tape Head inputs 1.8 mv for 1 volts out. HUM AND NOISE: High level inputs better than 80 db below 2.0 volts; low inputs better than 62 db below 2.0 volts. INPUT IMPEDANCES: High level—250K ohms; Mid—96K ohms; Ceramic—96K ohms. In series with 68 uuf; Tape Head—470K ohms. OUTPUT IMPEDANCES: Main Outputs—1500 ohms; Tape Outputs—2700 ohms; Bridged Output—1100 ohms. TONE CONTROL RANGE: Bass \pm 15 db at 30 cps; Treble \pm 15 db at 10Kc. RUMBLE FILTER: 12 db/octave slope, down 15 db at 30 cps. SCRATCH FILTER: 12 db/octave slope, down 15 db at 15 Kc. CROSSTALK: Greater than 55 db separation between channels. AUXILIARY AC OUTLETS: 4, 1 unswitched. TUBES: 7-7025, 2-Selenium Rectifiers. POWER REQUIREMENTS: 35 Watts, 105-125 volts AC, 50/60 cycles. SIZE: 14Wx4 $\frac{1}{2}$ Hx11 $\frac{1}{2}$ D, not including projections. Shpg. wt., 16 lbs.



PATENTS APPLIED FOR ON BRIDGE AND NULL BALANCE CIRCUITRY.

The KT-600A Solves every Stereo-Monaural problem

- RESPONSE 5-40,000 CPS • AMAZING BRIDGE CONTROL PROVIDES VARIABLE 3rd CHANNEL OUTPUT FOR 3-SPEAKER STEREO
- HIGHLY PRECISE "NULL" BALANCING & CALIBRATION—MORE ACCURATE THAN METERS • TAPE HEAD PLAYBACK EQUALIZATION FOR NEW 4-TRACK STEREO • 4-AUXILIARY AC OUTLETS

"LABORATORY STANDARD"

IN EASY TO BUILD KIT FORM

MODEL KT-550

134.50

MODEL LA-550

184.50

COMPLETELY WIRED AND TESTED
 NO MONEY DOWN




the KT-550 100 WATT BASIC STEREO AMPLIFIER KIT

- 50 Watts—per channel—100 watts for monophonic use. Frequency response from 2-100,000 cps, \pm 0, \pm 1 db at 1 watt • Unmeasurable Distortion • Hum and Noise Better Than 90 db Below 50 watts • Multiple Feedback Loop Design (over 50 db) Lowers Distortion Without Sacrificing Stability • Metered Control Panel With D.C. Bias and AC Balance Potentiometer • High Power 7027A Output Tubes • Massive Grain oriented steel transformers.

TECHNICAL SPECIFICATIONS

Power Output: 50-watts per channel continuous RMS from 20-20,000 cps; 100-watts monophonic operation. Total Harmonic Distortion: Less than .15% at 1,000 cycles at 50 watts each channel, 0.75% from 20-20,000 cps at 50 watts each channel. Intermodulation Distortion: Less than 0.5% at 50-watts equivalent sine wave power, 60 & 7,000 cps 4:1 ratio. 0.15% at 10-watts equivalent sine wave. Frequency Response: \pm 1-45,000 cps, 0 \pm 1db at 50-watts; 2-100,000 cps, \pm 0 \pm 1db at 1 watt. Sensitivity: 1.0 volt RMS input for 50-watts output. Damping Factor: 15 at 1 kc—16 ohms. Feedback: Over 50db in six multiple loops. Hum and Noise: Better than 90 db below 50-watts. Output Impedance: 4, 8 and 16-ohms. Convenience Outlet: Single A.C. convenience outlet. Fuse: Externally accessible fuse. Controls: 4 Bias Controls, 2 AC Balance Controls, Meter Selector Switch and Power On/Off Switch. Tube Complement: (Total of 10) 4-7027A, 4-6CL6, 2-6BR8A plus 5 Silicon Diodes. Power Consumption: 350-watts.



COMPARE PERFORMANCE

These performance curves demonstrate the ability of the KT-550 to provide high power output with extremely flat response at both ends of the frequency spectrum—Furnishes phenomenal reproduction even at low listening levels and is perfect for today's low-efficiency speakers.

Lafayette introduces the KT-550 "Laboratory Standard" Dual 50-watt Stereo Amplifier Kit—the finest instrument possible to design and produce regardless of price. Advanced engineering concepts in audio design were used to achieve flawless performance at an output of up to 50 watts per channel for stereo operation or 100 watts combined for monaural. The sound reproducing capabilities of the KT-550 are in excess of the audible range . . . \pm 0, \pm 1 db from 2 to 100,000 cps without evidence of ringing or instability. Perfect for low efficiency speaker systems. "Multiple loop" feedback design achieves very low distortion and high stability, with an absence of listening fatigue. Highest quality components were used throughout such as special massively designed output transformers, telephone grade electrolytics, and Corn-

ing deposited metal film glass case resistors. The 7027A output tubes are conservatively rated in the KT-550 to insure long life at lowest distortion levels. A well regulated power supply employing 4 silicon diode rectifiers is used. Engineered for the kit builder, two printed circuit boards virtually eliminate any possibility of error. Lafayette's famous step-by-step instruction manuals plus large pictorials provide ease of assembly equal to factory built units. Handsomely finished in contrasting brown and beige; control panel finished in brass. Complete with cover. Size: 17Wx12 $\frac{1}{2}$ Dx8 $\frac{1}{2}$ H 105-120 V, AC 50-60 cycles Shpg. wt., 60 lbs.

KT-550WX No Money Down Net 134.50
 Dual 50-watt stereo amplifier as above wired and tested.
 LA-550WX No Money Down Net 184.50

NOW YOU CAN AFFORD The Very Finest LAFAYETTE BUILD-IT-YOURSELF PROFESSIONAL 100 WATT STEREO SYSTEM

COMPONENTS




MATCHED COMPONENTS		
Lafayette KT600A Stereo Pre-amplifier Kit		79.50
Lafayette KT-550 Dual 50-Watt Basic Stereo Amplifier Kit (with enclosure)		134.50
2-Lafayette SK-115A 15" 3 Way Speakers @	79.50	159.00
Garrard Model A Record Changer (less base)		79.50
Base for Model A Changer (Specify Finish)		3.95
Audio Empire S108 Diamond Needle Stereo Cartridge		35.00
Regular Catalog Price		491.45

LAFAYETTE KIT SYSTEM PRICE YOU SAVE

437.⁷⁵ NO MONEY DOWN
53.70

ALTERNATES



LAFAYETTE 100 WATT MATCHED DE LUXE STEREO KIT SYSTEMS

*Be sure to specify Audio Empire S108, Pickering 380C, Shure M7D or GE VR-1000-7 Cartridge.

System	Amp. Kit	Preamp Kit	Changer	Cartridge*	Changer Tuner Base† Kit	Spkr.	Spkr. Cabinet	Shpg. Wt.	Net
LSK-551WX	KT-550	KT-600A	Garrard Model A	Choice of	Laff	—	2 SK-115A	—	175 lbs. 437.75
LSK-552WX	KT-550	KT-600A	Garrard Model A	Empire S108,	Laff	—	2 SK-115A	2 CK-10	283 lbs. 491.75
LSK-553WX	KT-550	KT-600A	Garrard Model A		Laff	—	2 SK-210	—	135 lbs. 381.75
LSK-554WX	KT-550	KT-600A	Garrard Model A	Pickering 380C,	Laff	—	2 SK-210	CK-14A	183 lbs. 422.75
LSK-555WX	KT-550	KT-600A	Garrard Model A		Laff	KT-500A	2 SK-115A	—	193 lbs. 512.25
LSK-556WX	KT-550	KT-600A	Garrard Model A	Shure M7D, Or GE VR-1000-7	Laff	KT-500A	2 SK-115A	2 CK-10	301 lbs. 566.25
LSK-557WX	KT-550	KT-600A	Garrard Model A		Laff	KT-500A	2 SK-210	—	153 lbs. 456.25
LSK-558WX	KT-550	KT-600A	Garrard Model A	Laff	KT-500A	2 SK-210	CK-14A	201 lbs. 497.25	

Any of above systems with addition of Lafayette LT-700WX Multiplex Stereo Tuner add \$114.50 to system price. When ordering add T to prefix. Example: LSK-551WX system with LT-700WX tuner is ordered as LSKT-551WX. †: Specify Mahogany, Walnut or Blonde Base.
 KT-500A AM-FM Stereo Tuner Kit. SK-210 12" 3 Way Speaker. CK-10 Base Reflex Unfinished Speaker Enclosure Kit for 12" or 15" Speakers. CK-14A Famous Lafayette Bookshelf Enclosure Kit for 12" Speaker.

THE OUTSTANDING

"Stereo 250A" KIT

ASSURANCE OF COMPONENT QUALITY
ONE YEAR PARTS GUARANTEE

All components in this unit are conservatively engineered to operate well within their performance capabilities. As assurance of this quality, Lafayette guarantees all parts including tubes for one year.

50 WATT INTEGRATED STEREO AMPLIFIER KIT

- DC applied to all preamplifier and tone control tube heaters for hum-free operation
- RIAA equalization on phono inputs
- NARTB tape equalization on tape head inputs
- Individual bias and balance controls
- Hum balance Control
- Excellent DC power supply regulation provided by silicon diodes
- Total of 9 tubes, plus 3 silicon diodes—uses premium 6CW5/EL86 output tubes.

Made in U.S.A.

IN EASY-TO-BUILD KIT FORM

74.50

NO MONEY DOWN



SPECIFICATIONS

POWER OUTPUT: 50 watts (100 watts peak) 25 watts per channel ± 1 db. DISTORTION: Total Harmonic Distortion ± 1 db at less than 1% at 1KC at normal listening level (1 watt); I.M. Distortion less than 0.5% at normal listening level. FREQUENCY RESPONSE: 15-40,000 cps ± 0.5 db at normal listening level, 20-50,000 cps ± 1 db at rated output. HUM & NOISE: Zero volume hum 77 db below rated output; max volume hum high level inputs 70 db below rated output; Mag. phono inputs 50 db below rated output. Sensitivity: For full output high level inputs 0.5V; Mag. phono 3.5 MV at 1KC. CHANNEL SEPARATION: Greater than 55 db at 1KC; greater than 45 db from 20-20,000 cps. SPEAKER AUXILIARY OUTPUT: 1 switched. TUBE COMPONENT: 4-6CW5/EL86, 2-7199, 3-12AX7, 3 Silicon diodes. IMPEDANCE: 4, 8 and 16 ohms per channel. POWER: 200 watts; 110-125V AC 50-60 cps. MODEL KT-250AWX Net 74.50

THE new Lafayette KT-250A offers remarkable versatility, high quality of reproduction and new distinctive styling in one convenient low-cost unit. Designed and engineered for ease of assembly, the KT-250A is a fine stereo preamplifier and 50 watt stereo amplifier combined — with all the controls and features to enable you to enjoy the utmost in listening pleasure in any situation. Whether you use it as a stereo amplifier delivering 25 watts per channel or as a powerful 50 watt monophonic amplifier, you are assured of true high fidelity reproduction — free from hum, noise and distortion.

DELUXE FEATURES

- Unique Separation Control—A new stereo control which provides continuously variable channel separation—from full monophonic to full stereo. Lets you select the amount of separation you want.
- Clutch-Operated Volume Balance Control—Gives you a choice of independent or simultaneous control of both channels—you can use it as a master volume control without disturbing previously selected settings on each channel.
- 4 Independent Tone Controls—Independent Bass and Treble adjustment for each channel. Concentric mounting for convenience—inner knob controls one channel, outer the other channel.
- Mode Switching—Two slide switches provide Normal Stereo—Reverse Channel—Mon A (Channel A reproduced through both channels)—Mon B (Channel B reproduced through both channels).
- Input Selector—4-position switch lets you select instantly any one of your connected monophonic or stereo sources—special non-shorting arrangement on one position permits recording and playback using a permanently connected tape recorder.

Loudness Switch—Provides the frequency response changes required by the ear at low listening levels and permits the Volume-Balance control to function as a compensated loudness control.

Phase Switch—Reverses the phase of one channel electrically—corrects for speakers connected out of phase or for reversed phase recordings sometimes found commercially.

3 Pairs of High Level Inputs—For connection of Crystal or Ceramic phono, Tuner, and auxiliary equipment.

2 Pairs of High Level Inputs—For connection of magnetic phono and Tape Head.

Main Speaker Outputs—Dual 4, 8 and 16 ohm terminals may be paralleled for 4 or 8 ohm operation at 50 watts.

Tape Output—Provides an output for Tape recording—unaffected by Volume and Tone Controls.

Bridged Output—A monophonic blend of both channels which can be fed to a third single channel power amplifier and speaker for a greater sound spread in stereo. May also be used for listening in another room.



NO TECHNICAL SKILL REQUIRED

Designed for ease of construction, the KT-250A can be assembled in a minimum of time. Assembly manual contains detailed step-by-step instructions... guides you every step of the way. Large full-scale pictorials show you where every wire and component goes.



Made in U.S.A.

NO MONEY DOWN

59.50

Lafayette 36 watt stereo amplifier

Fine wide-range stereo reproduction can be yours when you build this easily constructed 36 watt stereo amplifier (18 watts each channel). The KT-236A provides all the necessary inputs—lets you connect your stereo or monophonic sources permanently, with instant selection provided by the turn of a switch. Has built-in dual preamps for low level phono inputs—RIAA equalized for flat response. It includes a unique "Blend" control which provides continuously variable channel separation from full monophonic to full stereo—you select the exact degree of separation you want. Other features are: Concentric clutch-operated Volume control for independent or simultaneous level adjustment of both channels; Dual concentric Bass and Treble controls—give you 4 independent tonal adjustments; 3-position Selector Switch—Aux-Tuner-Phono; Mode (2 Slide Switches) provide Normal Stereo, Reverse channel, Mon A and Mon B; Phase switch—makes up for reversed-phase recordings sometimes found commercially and also corrects for speakers connected out of phase.

SPECIFICATIONS: POWER OUTPUT: 36 watts—18 watts per channel ± 1 db. Institute of High Fidelity Manufacturers Rating (72 watt peak). FREQUENCY RESPONSE: 15-30,000 cps ± 1 db at normal listening levels. SENSITIVITY: For full output; High level inputs 0.5V; Mag. Phono 3 mv. DISTORTION: Harmonic, less than 0.15% at normal listening level; IM, less than .3%. HUM AND NOISE: (At full volume) High level inputs 70 db below rated output; Mag. phono 53 db below rated output. CHANNEL SEPARATION: Better than 50 db. SPEAKER OUTPUT IMPEDANCE: 8 and 16 ohms. INPUTS: (Total 8) Dual Aux, dual Tuner, dual Tuner, dual Crystal Phono, dual Mag. Phono. OUTPUTS: (Total 4) Dual main speaker output, dual Tape out jacks. TUBE COMPONENT: 4-EL84, 2-7199, 3-12AX7 plus 2 silicon diodes. Attractive beige vinyl laminated steel cabinet. Handsomely designed brass anodized aluminum front panel. Sienna brown molded legs, matching knobs with polished brass inserts. 14% wide x 11 1/2" deep x 5 3/4" high (with legs and knobs) Shpg. wt. 24 lbs. 36 watt integrated Stereo Amplifier Kit, complete with deluxe cabinet and legs, all necessary parts and detailed assembly. MODEL KT-236AWX Net 59.50


THE AMAZING "STEREO 236" KIT

A NEW LOW-COST STEREO AMPLIFIER ANYONE CAN BUILD



Easy to Build!

Anyone can build these superb Lafayette stereo kits—no special skill is needed. Assembly manuals contain clearly worded step-by-step instructions which guide you all the way. Large full-scale pictorials illustrate every stage of assembly—show you exactly where every part goes. Join the thousands who have already discovered this easy low-cost way of owning the finest audio equipment.



Deluxe Stereo Controls

- 1 3-position Selector switch
- 2 Dual concentric Bass control
- 3 Dual concentric Treble control
- 4 Concentric clutch-operated Volume control
- 5 Unique "Blend" control
- 6 Phase reverse switch
- 7 Mode switches



DO-IT-YOURSELF and SAVE with LAFAYETTE HI-FI STEREO KIT SYSTEMS

BUILD THIS 36-WATT STEREO KIT SYSTEM

COMPONENTS		
Lafayette KT-236A 36 Watt Stereo Amplifier Kit		59.50
Lesa CD2/21 4-Speed Stereo Record Changer (less base)		44.50
Base for Record Changer (Specify Finish)		4.50
Audio Empire S108 Diamond Needle Stereo Cartridge		35.00
2 Lafayette SK-128 8" Ultra-Linear Bi-axial Speakers @ 19.50		39.00
	Regular Catalog Price	182.50

ONLY 142.50

YOU SAVE 40.00

LAFAYETTE MATCHED 36-WATT STEREO KIT SYSTEMS

*Be sure to Specify Choice of Audio Empire S108, Pickering 380C, Shure M7D or GE VR-1000-7 Diamond Needle Cartridges.

System	Amp. Kit	Changer	Cartridge*	Spkr. Base†	Spkr. Or Tuner	Cab. Shpg. Wt.	Net
LSK-231WX	KT-236A	Lesa CD2/21	Choice of Audio Empire S108, Pickering 380C, Garrard M7D,	Lesa† 2 SK-128	—	50 lbs.	142.50
LSK-232WX	KT-236A	Autoslym	—	Laf† 2 SK-128	—	48 lbs.	142.50
LSK-233WX	KT-236A	Lesa CD2/21	—	Lesa† 2 SK-128	2 Mini-Duct†	93 lbs.	185.50
LSK-234WX	KT-236A	Autoslym	—	Laf† 2 SK-128	2 Mini-Duct†	91 lbs.	185.50
LSK-235WX	KT-236A	Lesa CD2/21	—	Laf† 2 SK-58	—	61 lbs.	162.50
LSK-236WX	KT-236A	Autoslym	—	Lesa† 2 SK-58	2 CK-14	109 lbs.	203.50
LSK-237WX	KT-236A	Lesa CD2/21	—	Laf† 2 SK-58	2 CK-14	107 lbs.	203.50
LSK-238WX	KT-236A	Autoslym	—	Lesa† 2 SK-128	KT-650	64 lbs.	192.00
LSK-239WX	KT-236A	Lesa CD2/21	—	Laf† 2 SK-128	KT-650	62 lbs.	192.00
LSK-240WX	KT-236A	Autoslym	—	Laf† 2 SK-128	KT-650	62 lbs.	192.00

Any of above systems with addition of Lafayette LT-700WX, Multiplex Stereo Tuner, add \$114.50 to system price. When ordering add T to prefix. Example: LSK-231WX system with LT-700WX tuner is ordered as LSKT-231WX.
† Specify Mahogany, Walnut or Blonde Base. Mini-Duct: 8" Speaker Bookshelf Enclosure. CK-14: Eliptoflex 12" Speaker Enclosure Kit. Unfinished. KT-650: FM Tuner Kit.

CHOICE OF ONE



LESAs CD 2/21

CHANGER BASE

SK-128W SPEAKERS

OPTIONAL



KT-650



"MINI-DUCT" ENCLOSURES

"ELIPTOFLEX" ENCLOSURES

ALTERNATES



SK-58 SPEAKERS



GARRARD AUTOSLYM

CHOICE OF ONE



AUDIO EMPIRE S108

PICKERING 380C

SHURE M7D

GE VR1000-7

GLASER-STEERS GS-77

SK-58 SPEAKERS

OPTIONAL



KT-650 FM TUNER



"ELIPTOFLEX" ENCLOSURES

ALTERNATES



SK-180



GARRARD AT-6

Deluxe 50-WATT DO-IT-YOURSELF STEREO KIT SYSTEM

MATCHED COMPONENTS		
Lafayette KT-250A 50 Watt Stereo Amplifier		74.50
Glaser-Steers GS-77 4-Speed Record Changer (less base)		59.50
Base for Changer (Specify Finish)		3.95
Audio Empire S108 Diamond Stereo Cartridge		35.00
2-Lafayette SK-58 12" Coaxial Speakers @ 29.50		59.00
	REGULAR CATALOG PRICE	231.95

ONLY 184.75

YOU SAVE 47.20

LAFAYETTE MATCHED 50-WATT STEREO KIT SYSTEMS


*Be Sure to Specify Choice of Audio Empire S108, Pickering 380C, Shure M7D or GE VR-1000-7 Stereo Cartridges.

System	Amp. Kit	Changer	Cartridge*	Changer Base†	Spkr. Cabinet	Spkr. Wt.	Net
LSK-351WX	KT-250A	Glaser-Steers GS-77	Choice of Audio Empire S108,	Laf†	2 SK-58	—	80 184.75
LSK-352WX	KT-250A	Garrard AT-6	—	Laf†	2 SK-58	—	80 184.75
LSK-353WX	KT-250A	Glaser-Steers GS-77	—	Laf†	2 SK-58	2 CK-14	128 225.75
LSK-354WX	KT-250A	AT-6	—	Laf†	2 SK-58	2 CK-14	128 225.75
LSK-355WX	KT-250A	Glaser-Steers GS-77	—	Laf†	2 SK-180	—	74 188.75
LSK-356WX	KT-250A	Garrard AT-6	—	Laf†	2 SK-180	—	74 188.75
LSK-357WX	KT-250A	Glaser-Steers GS-77	—	Laf†	2 SK-180	2 CK-14	122 229.75
LSK-358WX	KT-250A	Garrard AT-6	—	Laf†	2 SK-180	2 CK-14	122 229.75

Any of above systems with addition of Lafayette LT-700WX, Multiplex Stereo Tuner, add \$114.50 to system price. When ordering add T to prefix. Example: LSK-351WX system with LT-700WX tuner is ordered as LSKT-351WX.

† Specify Mahogany, Walnut or Blonde Base. SK-180: "Trihelix" 10" 3-way speakers. AT-6: GARRARD 4-Speed Record Changer. CK-14: Eliptoflex Bookshelf Speaker Enclosure in Kit form, unfinished.

LAFAYETTE UNIVERSAL MULTIPLEX ADAPTER



New!

Now Enjoy All The Quality & Dynamic Brilliance of Stereo Through Your FM Tuner

COMPARE THESE QUALITY FEATURES

- 35 DB STEREO SEPARATION (AT 400 CPS)
- MATCHES WITH VIRTUALLY ALL RECENT MODEL WIDE BAND TUNERS EQUIPPED WITH MPX OUTPUT JACKS
- LESS THAN 1% DISTORTION FROM 50-15,000 CPS
- PLATE FOLLOWER OUTPUT PROVIDES FOR REMOTE AMPLIFIER CONNECTION
- SELF POWERED
- COMPLETE WITH ENCLOSURE & ALL NECESSARY CONNECTING CABLES

ONLY 54.50
No Money Down

- 35 DB Stereo Separation (at 400 cps)

Here's the easiest, most inexpensive way for you to enjoy stereo—not records, not tapes, but stereo with all the fidelity and convenience that only FM can provide. Add this exciting new method of stereo reproduction to your component High-Fidelity system with this brilliant new stereo multiplex adapter. Performs beautifully with virtually any late model, wide band tuner equipped with a multiplex output jack and delivering a mpx output signal from 1.5 to 2 volts. Requires no special knowledge or tools to hook up—as simple and easy to connect as were your original components. Supplied with all necessary audio cables. All that's required is to merely plug the unit into your tuner, amplifier and AC outlet. Engineered for simplicity of operation, a selector switch conveniently located on the front panel provides for ON-OFF, Mono-FM and Stereo-FM. Individual pilot lights indicate when power is on and when adapter is

operating stereophonically. Beautifully styled to match any decor in textured beige finish cover and smart brushed brass anodized aluminum front panel. **TECHNICAL SPECIFICATIONS:** Separation: (at 400 cps) 35db; Harmonic Distortion: Less than 1% from 50 to 15,000 cps; Frequency Response: ± 1 db 50-15,000 cps. Multiplex Input Signal: .15 volts to 2V; Gain: 15 db; Output Impedance: 8000 ohms; Hum: at 60 cps for 1 volt signal input better than 60db; Rejection to 67KC; at least 50db; Rejection to 38 KC; at least 40 db. Four tubes (2 dual purpose) 12AX7, 6CA, 12BZ7, EZ80. Features notch filter for 38KC; low impedance plate follower output (for remote amplifier connection); matched diodes for optimum separation. Supplied with a special low capacitance input cable for optimum separation. Measures 4 $\frac{3}{4}$ "x5 $\frac{3}{4}$ "x10 $\frac{7}{8}$ "D. For 110-120V, 60 cycle AC. LT-200 WX Shpg. wt., 8 lbs. Net 54.50

THE NEW LAFAYETTE LA-240 40-WATT STEREO AMPLIFIER


LAFAYETTE 40 WATT RECOMMENDED MATCHED STEREO SYSTEM

- Concentric Volume Balance Control
- Less Than 1% Harmonic Distortion at Rated Output
- Hum & Noise 80 db Below Rated Output
- Frequency Response: 12-100,000 cps ± 1 db at 1 Watt
- Variable Separation Control Eliminates Exaggerated Channel Separation
- Dual Concentric Bass & Treble Controls
- High Sensitivity Allows Use With All Stereo Cartridges



LAFAYETTE 40 WATT RECOMMENDED MATCHED STEREO SYSTEM

CHOICE OF ONE



COMPONENTS

LAFAYETTE LA-240 40-watt Stereo Amplifier	79.95
GARRARD AUTOSLIM 4-Speed Record Changer	39.50
WOOD BASE FOR CHANGER (Specify Walnut, Mahog. or Blonde)	3.95
AUDIO EMPIRE S108 Diamond Needle Cartridge	35.00
2-LAFAYETTE SK-58 Free Edge 12" Coaxial Speakers @ 29.50 each	59.00
REGULAR CATALOG PRICE	217.40

YOU SAVE 34.45

LAFAYETTE SPECIAL SYSTEM PRICE **182.95**

Complete system as above with choice of Audio Empire S108, Pickering 380C, Shure M7D or GE VR1000-7 Diamond Needle Stereo Cartridge. Net 182.95
 LS-350WX Shpg. wt., 58 lbs.
 Same as LS-350WX plus 2 Lafayette Famous Eliptoflex speaker enclosures. Net 248.95
 LS-352WX Shpg. wt., 106 lbs.
 Same as LS-350WX but with 2 Lafayette SK-180 Trihelix Speakers instead of the SK-58 speakers. Net 186.95
 LS-346WX Shpg. wt., 55 lbs.
 Same as LS-346WX plus 2 Lafayette Famous Eliptoflex speaker enclosures. Net 252.95
 LS-348WX Shpg. wt., 103 lbs.
 Above systems with addition of Lafayette LT-700WX multiplex Stereo Tuner (described elsewhere) add 114.50 to system price and add letter T to the stock number. Example LS-350WX system with LT-700WX tuner is ordered as LST-350WX.

COMPARE THESE QUALITY FEATURES

Quality, Design and Performance That Are Remarkable—The Lafayette LA-240 represents the highest standards of stereophonic amplifier design—literally creating a new meaning for excellence. Use of the most advanced engineering techniques and finest components have resulted in a powerful 40-watt stereo amplifier incorporating two 20-watt power channels and dual preamplifier. A level of flexibility and performance have been achieved that can only be compared with units twice the price.
Separation Control—Provides continuously variable channel separation from full stereo to full monaural, thus insuring the correct degree of stereo separation for individual listening tastes and room acoustics.
Independent Tone Controls—Centrally mounted bass and treble controls for each channel.
Volume—Balance Control—Individual level controls for each channel.
Loudness Switch—Allows the volume controls to function as compensated loudness controls and provides the frequency response changes required by the ear at low distortion levels.
Rumble Filter—Reduces rumble from a noisy turntable with a minimum effect on program material.
Mode Switching—Ch A and Ch B slide switches provide for normal stereo, reverse channel, monophonic A or monophonic B.
Selector Switch—Instant selection of Aux, Tuner, Phono or Tape Head Inputs—non-shorting position permits recording and playback using a permanently connected tape recorder.
Hum Balance Controls—Individual hum balance controls for each channel located at the rear for fast, easy minimum hum adjustment.
Full Range of Inputs & Outputs—Inputs: (5 stereo pairs) Dual Aux—Dual Tuner—Dual Ceramic Phono—Dual Mag. Phono—Dual Tape Head; Outputs: Dual Tape Out—Dual 8 and 16 ohm speaker terminals.
Superb Low Silhouette Styling makes the LA-240 an amplifier you'll be proud to display. Gold finish cover is set off by an ivory and gold front panel with gold metal knobs. Complete with cage and legs. Overall Dimensions: 14 $\frac{1}{2}$ "x10 $\frac{1}{2}$ "x5 $\frac{3}{4}$ "H. For 115V AC operation. Power consumption 185 watts. Net 79.95
 LA-240WX Shpg. wt., 25 lbs.

79.95
NO MONEY DOWN

SPECIFICATIONS

Power Output and Distortion—20 watts per channel at less than 1% total harmonic distortion at 1 Kc. Less than 0.25% total harmonic distortion at 14 watts; less than 0.12% at 1 watt. Intermodulation Distortion: .075% at 1 watt; .34% at 10 watts. Frequency Response: 12 to 10,000 cps ± 1 db at 1 watt. 50 to 70,000 cps ± 1 db at full output. Sensitivity: For full output: High Level inputs 0.75v Mag. inputs 5.5 Mv at 1 Kc. Tone Control Range: Treble: 12 db boost or cut at 10 Kc. Bass: 15 db boost or cut at 50 cps. Hum and Noise: Zero volume hum: 80 db below rated output. Maximum volume hum: High level inputs, 78 db below rated output; Mag. Phono inputs, 50 db below rated output. Outputs: Dual 8 and 16 ohm impedance speaker outputs, Dual Tape outputs. Tube Complement: 4—6BQ5/EL84, 2—6BL8/ECF80, 3—12AX7/ECC83, 1—GZ34/SAR4.

LAFAYETTE LA-55 15-WATT MONAURAL AMPLIFIER

The most extraordinary Hi-Fi value ever offered



LAFAYETTE LA-55



SK-124



LESA CD2/21



CHOICE OF ONE

- Frequency Response: 15-30,000 CPS
- Hum 65 Db Below Rated Output
- Power Output 15 Watts
- Harmonic Distortion Less Than .3%
- Sensitivity: 3 MV Mag. Phono
- 5 Input Channels
- Rumble Filter
- EL84 Output Tubes in Push-Pull
- Beautifully Styled

44.50 NO MONEY DOWN

LA-55WX Shpg. wt., 20 lbs. Net 44.50

LAFAYETTE SUPER-VALUE Hi-Fi PHONO SYSTEM

PLAY STEREO & MONAURAL RECORDS MONAURALLY NOW — ADD COMPLETE STEREO LATER. This economical high-fidelity system is the performance value of the year. Designed for ruggedness as well as beauty, these components will satisfy even the most critical music listener.

COMPONENTS

LAFAYETTE LA-55 15 Watt Complete Amp.	44.50
LESA CD 2/21 4 Speed Record Changer	44.50
WOOD BASE FOR CHANGER (Specify Walnut, Mahog. or Blonde)	4.75
AUDIO EMPIRE S108 Diamond Needle Cartridge	35.00
LAFAYETTE SK-124 Ultra Compliance 2 Way Speaker System	17.50
REGULAR CATALOG PRICE	146.25

YOU SAVE 38.75

SPECIAL LAFAYETTE SYSTEM PRICE **107.50**

Complete System as above with choice of Audio Empire S108, Pickering 380C, Shure M7D or GE VR1000-7 Diamond Needle Stereo Cartridge. Net 107.50
 LS-59WX Shpg. wt., 39 lbs.

MODEL LT-80B FM TUNER



READY FOR MULTIPLEX!

ONLY 49.50

NO MONEY DOWN


• ARMSTRONG CIRCUIT FOSTER-SEELEY DISCRIMINATOR AND DUAL TUNED LIMITERS • AFC • AFC OEFEEAT • EXTREMELY SENSITIVE—1.5 UV FOR 20 DB QUIETING • 10-TUBE PERFORMANCE—8 TUBES (2-DUAL PURPOSE) • 20-20,000 CYCLES $\pm 1/2$ DB • SUPERB LOW SILHOUETTE STYLING • 3 GANG TUNING CONDENSER • TUNED GROUNDED GRID RF STAGE

COMPARE FEATURE FOR FEATURE WITH THE MOST EXPENSIVE TUNERS

Remarkable... Quality, performance and styling that is in every respect the equal and in many instances superior to tuners priced far above the modest cost of this instrument. Designed and constructed of the finest components, with jewel like precision (each unit is hand wired). Engineered to provide maximum FM versatility, the LT-80B is provided

with a multiplex output, designed to accept a stereo FM multiplex adapter. Flywheel action tuning control. Tube complement consists of 2-6AQ8, 2-6BA6, 2-6AU6, 1 each 6AL5 and 6X4. Handsome low silhouette enclosure will do justice to any decor. Beautifully finished in gold and white with contrasting black dial face. Complete with cage and legs. Dimensions: 11 $\frac{3}{4}$ "x8 $\frac{1}{2}$ "x4 $\frac{1}{2}$ "H.
 LT-80B FM Stereo Tuner Net 49.50
 NTA-11WX Combination of LT-80B and LT-200 FM Multiplex Adapter. Net 99.00
 You Save 5.00

QUALITY STEREO LOW COST COMPONENTS



MODEL LT-78
Delivery JUNE 15, 1962

LAFAYETTE FM-AM STEREO TUNER WITH BUILT-IN MULTIPLEX
QUALITY STEREO RECEPTION AT A FANTASTIC LOW PRICE.

A LAFAYETTE SPECIAL VALUE. Compare These Features Against Higher Priced Stereo Tuners.

- 16 Tube Performance—12 Tubes & 5 Diodes & Tuning Meter • MPX Separation 30 db @ 400 CPS. Less than 1% Distortion • Armstrong Circuit with Dual Tuned Limiters and Foster-Seeley Discriminator • Automatic Frequency Response
- Tuned Grounded Grid R.F. Stage on AM & FM
- Flywheel Tuning • Broadband I.F. for AM
- Noise Filter Slide Switch • AM Level Control
- Stereo Dimension Control • Illuminated Multiplex Indicator

89.50


NO MONEY DOWN

SIMPLICITY, FLEXIBILITY AND SUPERB STYLING have been carefully integrated in this quality instrument. Offering unlimited versatility, the LT-78 features separate AM, FM and FM MULTIPLEX Reception for your listening pleasure. A complete set of controls provide for every tuner faction on the front panel there is a mode selection switch with a choice of AM, FM or FM stereo, a power on/off slide switch; Variable AFC adjustable for tuning in weak stations adjacent to strong stations; Flywheel tuning for smooth rapid station selection, tuning meter for pinpointing your station to the strongest signal; a noise filter slide switch for weak stations and an illuminated multiplex indicator which shows you are in the FM stereo mode. On the rear panel there is an AM level control and a stereo dimension control to provide the right separation for your systems. Plate follower output permits using the tuner up to 50 ft. from an amplifier. FM circuitry features armstrong grounded grid low noise front end and Foster-Seeley discriminator. Superheterodyne AM circuit

with 3 stages, AVC and ferrite loopstick antenna. Specifications: Selectivity FM 200 KC band width, 6db down; AM 8 KC bandwidth, 6db down; Frequency Response: FM 20-20,000 CPS \pm 2db; Stereo Separation 30 db @ 400 cycles less than 1% distortion; Harmonic distortion less than 1% on AM to 80% modulation; HUM Level—60db; Image rejection, FM Better than 40 db. AM 70 db; I.F. Rejection, FM 70 db AM 50 db; Meets FCC RF Radiation requirements. Tubes: 12AX7, 12AU7, 6BE6, (3) 6AU6, (3) 6BA6, (2) 6AQ8, 6x4 plus 5 germanium diodes. Antenna Input: 300 ohms, dual stereo outlets. Each unit has been hand wired and individually tested at the factory. Superbly styled low silhouette enclosure finished in gold and white with an easy to read black dial face. Complete with case and legs. Dimensions: 15Wx9½Dx5"H. Legs add ¾" to height. Shpg. wt., 16½ lbs.

LT-78WX AM-FM MULTIPLEX TUNER

Net 89.50



Delivery April 30, 1962

MODEL LT-81
FM STEREO
TUNER

LAFAYETTE FM TUNER WITH BUILT-IN MULTIPLEX

- Built-In Multiplex Circuit With 30 db Separation @ 400 CPS • Foster-Seeley Discriminator and Dual Tuned Limiters • AFC • AFC Off
- Extremely Sensitive—2.0 μ V for 20 db Quieting 12 Tube Performance 10 Tubes (2-dual purpose) • Freq. Response 20-20,000 CPS \pm 2 db • Low Silhouette Styling • 3 Gang Tuning Condenser • Tuned Grounded Grid RF Stage.

76.50


NO MONEY DOWN

TRULY remarkable, quality performance and styling that is in every respect the equal to and often superior to FM Stereo tuners priced far above the modest cost of this fine instrument. Designed and constructed of the finest components with jewel like precision (each unit has been hand wired and individually tested at the factory) in order to insure that each tuner will maintain its excellence year after year with a minimum of maintenance. Engineered to provide high quality FM and FM stereo multiplex broadcasts the LT-81 has an Armstrong circuit and a Foster-Seeley discriminator with dual tuned limiters. The multiplex circuit provides a stereo separation of 30 db at 400 cycles with less than 1% distortion. Controls consist of power on/off selector switch for FM, Stereo MULTIPLEX, noise filter; AFC slide switch with off position, tuning Meter. Stereo dimensions control to custom blend stereo reception and Flywheel action tuning control gives velvet smooth tuning action. Pilot light goes on in stereo position. Two stereo output jacks on rear panel. Tube Complement: (2) 12AX7, (3) 6AU6, (2) 6BA6, (2) 6AQ8, 6X4 and 4 germanium diodes. Handsome low silhouette enclosure looks good in any room setting. Beautifully finished in gold and white with a contrasting black dial face. Complete with cage and legs. Dimensions: 5½Hx13½Wx9¼"D.

LT-81WX

Shpg. wt., 12 lbs.

Net 76.50



NEW! LAFAYETTE 40 WATT STEREO FM MULTIPLEX RECEIVER-AN OUTSTANDING VALUE!



Delivery JUNE 30, 1962

A MATCHED AM-FM TUNER PLUS BUILT-IN MULTIPLEX PLUS A 40-WATT STEREO AMPLIFIER (20-WATTS EACH CHANNEL) AT LAFAYETTE'S AMAZING LOW PRICE!

- AM/FM Tuner with Multiplex
- Complete Stereo Preamp Facilities
- 15 Front Panel Controls
- 20 Tubes—7 Diodes
- JUST ADD A TURNTABLE AND SPEAKERS FOR A COMPLETE STEREO SYSTEM

189.95

NO MONEY DOWN

The Lafayette LA-226 is a self-contained instrument designed for the control and reproduction of all stereophonic and monophonic sources featuring a new built-in FM multiplex circuit. The receiver section consists of an AM/FM tuner with built-in multiplex which provides more than 30 db separation @ 400 cycles. Precision tuning meter and flywheel tuning for precise station selection. Multiplex pilot light indicates set is tuned to MPX. A sensitivity of 2 μ V for 20 db of quieting is achieved by the FM circuit with AFC and AFC defeat assuring reception of even the weakest signals. FM noise & filter slide switch cuts out unwanted station noise. The AM section features a superheterodyne circuit with AVC, and built-in ferrite loop antenna. The 40-watt amplifier section features large power transformers and a frequency response of 20-20,000 CFS \pm 2 db. Less than 1.5% harmonic distortion on all modes. Complete stereo preamp facilities provide dual concentric front panel controls for bass and treble, Volume control balance, blend for variable channel separation from 5-position selection stereo to mono, switch (AM, FM, FM Stereo, phono, AUX) 4-Position Amplifier mode switch (A, B, AB, REV), rumble filter slide switch, loudness slide switch, and on-off power switch. Rear controls include: Speaker phase switch, 8-16 ohm impedance selector switch, dimension control adjustment, speaker on/off switch, jack for stereo headphones, AC outlet, fuse and stereo tape outputs. Complete with a handsome enclosure in contrasting brown and brass—overall size: 17½Wx15Dx5¼"H.


LA-226WX

Shpg. wt., 45 lbs.


Net 189.95

SPECIFICATIONS

TUNER: HARMONIC DISTORTION: .7 on FM for 100% modulation; FM Freq.-response: 20-20,000 CPS \pm ½ db FM Sensitivity: 2 μ V for 20 db quieting; MPX Separation: 30 db @ 400 CPS. Hum level: 60 db, Image rejection: FM—50 db. AMPLIFIER: 65 db below full output for low level—75 db for high level. Power Output: 20 watts per channel. Sensitivity: mag phono 2 mv at full output, crystal input 30 mv at full output. Tone Control: \pm 12 db @ 50 CPS (bass), \pm 9 db @ 10 KC (treble) 20-20,000 CPS \pm 2 db. Output Impedance: 8 & 16 ohm, switch selected. Input Impedance: 47 K phono; 22 meg (high level) Rumble Filter —8 db @ 50 db. Phono Equalization: RIAA.



LAFAYETTE STEREO AMPLIFIER TRIUMPH! NEW! LA-224 24-WATT STEREO AMPLIFIER



Dual 12-Watt Stereo Amplifier Coupled With a Versatile Stereo Preamplifier . . . Performance The Equal of Units 2 & 3 Times Its Power & Price.



Delivery April 30, 1962

CHECK THESE QUALITY FEATURES

- ✓ Stereo Headphone Jack
- ✓ Independent Concentric Bass & Treble Controls For Each Channel
- ✓ Concentric Volume Balance Control
- ✓ Frequency Response: 20-100,000 CPS \pm 1db at 1 Watt
- ✓ Hum & Noise—73 db Below Rated Output
- ✓ High Sensitivity Allows Use With All Stereo Cartridges



49.95

No Money Down

SPECIFICATIONS

Power Output: 12 watts per channel stereo. 24-watts monaural operation. Frequency Response: 20-100,000 CPS \pm 1db at 1 watt, 50-50,000 CPS \pm 1db at 12 watts. Hum and Noise: Mag Phone — 56 db below rated output, Tuner — 73 db below rated output. Distortion: less than 1% total harmonic distortion at 12 watts (IKC), less than .25% total harmonic distortion at 1 watt (IKC), Sensitivity: Low Level (Mag Input) 5mv at full output, High Level .6v at full output. Outputs: Dual 8 and 16 ohm impedance speaker outputs. Dual Tape outputs, Tube Complement: Total of 8, 3-12AX7, 4-6GW8, 1-5AR4.

FIRST RATE—make no mistake, don't be misled by Lafayette's low price. This is a Brilliant Stereo Performer . . . an amplifier with the wide-range frequency response, low distortion, low hum and noise characteristics you'd expect of amplifiers 2, even 3 times its power rating and many times its price. A full range of control facilities have been provided to assure complete Stereo capability and flexibility. Two dual concentric Bass and Treble controls provide separate and individual tone controls for each channel. A dual concentric volume Control acts as an independent level control for each channel and allows precise channel balancing. Fast, easy operation between Stereo, Reverse Stereo, Monophonic Left channel and Monophonic Right channel is furnished by a Mode switch. A selector Switch furnishes switching from Aux, Tuner or Phono music sources. In addition slide switches are

included for: Rumble Filter (off-on) Phase (normal-reverse) and to take full advantage of the front panel Headphone jack a switch is provided for speaker or phone operation. Paired inputs located on the rear panel accommodate any of the ordinary stereo sound sources —inputs are included for magnetic, crystal or ceramic cartridges; Tuner, tape or auxiliary (high output) plus Tape Out jacks for recording through your tape recorder. Beautifully styled in a low silhouette enclosure, color keyed to do justice to any decor, ivory and gold front panel is contrasted by gold metal knobs and enclosure. Complete with cage and legs. Size: 5 $\frac{1}{2}$ "x13 $\frac{1}{2}$ "x8 $\frac{1}{2}$ "D. For 115V 60 cycle AC operation. Shpg. wt., 20 lbs. LA-224WX Net 49.95

New! *TruTest*™ STEREO / 5 AMPLIFIER



- Individual Stereo Volume-Balance Controls
- For Both Stereo and Monaural
- Fully Wired—Ready For Stereo

Only 9.95

One of the finest stereo values we have ever offered. This rugged, precision made dual channel stereo amplifier will amaze you with its fine quality . . . Ideal for that low cost stereo system you're planning for your home or business. Perfect for converting your present console or portable to stereo. Controls include separate left channel and right channel volume controls, stereo-


monaural mode switch, tone control switch and on-off switch. Provision for crystal or ceramic cartridge, 4 ohm output terminals accept most speakers. Tube complement: 2-35C5, 1-35W4 and 1-12AX4. Size: 4 $\frac{1}{2}$ "x5 $\frac{1}{2}$ "x4 $\frac{1}{2}$ "D. 115 volt 60 cycles. Shpg. wt., 5 lbs.

PK-441W Net 9.95

COMPLETE STEREO *TruTest*™ PHONO SYSTEM

44.50

No Money Down



PK-605W



SK-228

Now you can have genuine component stereophonic sound at the lowest price ever. Complete in every detail this system consists of: The TruTest Stereo/5 Amplifier, Lafayette AUTOMATIC 4 Speed Stereo Record Changer that plays Stereo, LP and 78 RPM records and features quality Ronette Ceramic Stereo Cartridge, Automatic 3-way Shut-off, Record Intermitter, heavy precision balanced turntable and

constant speed motor; and 2 Lafayette SK-228 "Music Mite" Speakers in attractive Mahogany. Each speaker system is supplied with 25 feet of hook-up cable and measures only 9 $\frac{1}{4}$ "x5 $\frac{1}{4}$ "x4 $\frac{1}{4}$ "D. Shpg. wt., 20 lbs. Less Changer Base. PK-627WX Net 44.50 PK-607W Mahogany Base for Changer Net 3.95 PK-609 45 RPM Spindle for Changer Net 1.49

NEW! *pioneer* MODEL SE-1 STEREO HEADPHONES


- Actually 2 High Fidelity Dynamic Speakers
- Frequency Response 25 to 15,000 Cycles
- Soft Foam Rubber Ear Pads

F-770 **19.95**

- Frequency Response 25 to 15,000 Cycles
- Actually 2 High Fidelity Dynamic Speakers
- Soft Foam Rubber Ear Pads

For the audio connoisseur who demands the finest in stereophonic headphone performance, the Pioneer Stereophones combine broad frequency response and faithful reproduction with comfort-oriented design, to fulfill the most exacting requirements. The Stereophones are actually two 2 $\frac{1}{2}$ " high fidelity dynamic speakers with a frequency response range of 25 to 15,000 cycles. Perfect for stereo and monaural operation, the headphones are rated at $\frac{1}{2}$ watt maximum input; impedance, 8 ohms per phone. The soft foam rubber ear pads provide extremely comfortable listening, help to keep out noise and maintain an excellent bass response. Imported F-770 Shpg. wt., 2 lbs. Net 19.95 Model SE-2 resistor box for SE-1. Permits flexible one-switch changeover from speakers to Stereophones. F-800 Net 4.95 Model SE-3 "Y" connector for connecting 2 or more sets of headphones to a single source. F-801 Net 2.45 Model SE-4 12' extension cord for SE-1 phones F-802 Net 2.95

NEW! REVOLUTIONARY *pioneer* STEREOSCOPE! NOW! PLAY YOUR STEREO RECORDS ON ANY TURN-TABLE WITHOUT AN AMPLIFIER OR SPEAKERS.



- Attaches in Minutes
- Frequency Response—30-15,000 CPS
- Comes complete with one head set—up to 4 people can listen by adding accessory earphones!

Original Price 29.95

Only **9.95**

Listen to your stereo records as you've never heard them before—without amplifier or speaker—no electronic devices of any sort between your ear and the record . . . a range of distortion free, full-bodied sound that will amaze you. These headphones are driven by variations in pressure transmitted by the specially designed pickup arm. The sound is then transmitted by a set of pipes to the specially designed earphones. A handy, easily adjusted control unit inserted in the pipe provides a separate volume control for each channel and a mixing control to govern channel separation (from full stereo to monaural operation).

Frequency Response 30 to 15,000 CPS. Tracking force for pickup, 3-6 grams. Accessory earphone kits permit as many as 4 persons to enjoy the same recording. Easily mounted on virtually any turntable. Complete with special pick-up-arm, sapphire needle, mounting base, suction base, volume control unit, connecting tubes, earphones and mounting hardware. Shpg. wt., 4 lbs. PK-596 SH-100 Stereoscope Net 9.95 PK-597 SH-101 Additional earphone Kit Net 2.95 PS-97L NSH Diamond replacement needle Net 3.49

JUST OUT!! LAFAYETTE SK-228 "MUSIC MITE" SPEAKER




8.25

- AMAZING TONAL QUALITY
- CONTAINS SPECIAL 6x4" OVAL SPEAKER
- HANDSOME MAHOGANY FINISHED WOOD ENCLOSURE
- EQUIPPED WITH 25 FT. OF EXTENSION CABLE

Truly amazing tonal quality—Utilizing a specially designed 6x4" oval speaker in a rigid rear vented wood enclosure this new speaker unit delivers a quality of reproduction out of all proportion to its small size. It measures only 9 $\frac{1}{4}$ "x5 $\frac{1}{4}$ "x4 $\frac{1}{4}$ "D. Ideal for that inexpensive music and/or paging installation you've wanted for your store, office, den or kitchen. Use two for stereo. May be connected to either 8 or 40 ohm amplifier outputs. Supplied with 25 ft. of extension cable. Cabinet is attractively finished in mahogany. Shpg. wt., 6 lbs. Net 8.25

AMAZING NEW OUTDOOR WEATHER-PROOF SPEAKER

The Same Indestructible Speaker Specified By The Navy For Our Atomic Submarines!!




5.75

- Frequency Response: 100 to 10,000 CPS
- Compact — Measures Only 3 $\frac{3}{4}$ "x2 $\frac{1}{2}$ "D
- Completely Weatherproof & Dust-proof
- Enclosed In A Cadmium Plated 20 Gauge Steel Case
- Specially Designed Plastic Impregnated Cloth Speaker Cone

Compact, Weatherproof, Dustproof . . . virtually indestructible. What's more you'll be amazed at its sound. Frequency Response is 100 to 10,000 CPS. So rugged it will withstand immersion in boiling water, and is impervious to salt spray. And no wonder, this is the same speaker specified by the Navy for our Atomic Submarines. The Speaker utilizes a plastic impregnated cloth cone, spider and dust cap material with an aluminum voice coil and zinc plated frame. The rugged enclosure is constructed of 20 gauge cadmium plated steel with 2 coats of baked electrostatic enamel. Enclosure is equipped with an RCA Type Phone Jack, Key slot mounting hole plus a mounting cutout to accept a volume control, on-off or push-to-talk switch. Ideal for outdoor extensions, patios, pools, skating rinks, barns, grain elevators, open fields, paging. Use in industrial plants where corrosive atmosphere destroys other speakers. SPECIFICATIONS: Response: 100 to 10,000 CPS. Shock Test: withstands up to 50 G's. Voltage: withstands up to 100 volts RMS. Temperature Extremes: from -80°F to 160°F. Size: 3 $\frac{3}{4}$ "x2 $\frac{1}{2}$ "x2 $\frac{1}{2}$ "D. Shpg. wt., 5 lbs. SK-209 Net 5.75

LAFAYETTE MINIATURE HI-FI SPEAKER and ENCLOSURE



6.95

- ATTRACTIVE MAHOGANY FINISHED WOOD CABINET
- COMPLETE WITH 25 FEET OF CABLE

Enjoy music everywhere in your home with this amazing Lafayette miniature speaker system. Perfect as an extension speaker for your den, basement, kitchen or bedroom. Use two as extension speaker units for stereo or with your TV and Radio. Housed in a beautiful mahogany finished wood cabinet with ventilated back cover, the 5-watt 4x6" speaker is designed to work from either 4 or 8 ohm outputs. System is supplied with 25 feet of cable which should meet any hook up requirement. Over-all size: 9 $\frac{1}{4}$ "x7 $\frac{1}{4}$ " (inc. feet) x 3 $\frac{1}{4}$ "D. Shpg. wt., 5 lbs. SK-109 Miniature Speaker System Net 6.95

build your own HI-FI KITS

H.H. SCOTT



**NEW MODEL LT-110
WIDE-BAND FM
STEREO MULTIPLEX
TUNER KIT**

- First Kit With Built-In Multiplex
- Prealigned Multiplex Section

FM multiplex tuner in kit form. Both the multiplex section and silver plated front end are factory preassembled and prealigned. You need only align the tuner's wide-bandpass IF's and detector using the meter on the tuner itself. Special shielding protects against interaction of tuner and multiplex sections. Unique circuitry eliminates multiplex interference with bias oscillator of any stereo tape recorder. Features stereo Noise Filter, Vernier Tuning; Front panel tuning meter; and Stereo Tape recorder output. IHFM usable sensitivity 2.2 microvolts. 10 Tubes, 11 diodes. Shpg. wt., 20 lbs. 15 1/2" x 5 1/4" x 13 1/4" D.

G-633WX (less case) Net 159.95
Leatherette metal case C for LT-110. Shpg. wt., 5 lbs.
G-147W Net 13.95



**MODEL LK-72
72-WATT STEREO
AMPLIFIER KIT**

The LK-72 has the same output circuitry as the 299C wired stereo amplifier. Aluminum chassis and D.C. heated preamp filaments give low —80 db hum and noise. Frequency response 20 to 20KC ± 1 db; harmonic distortion at full output 0.8%. IM distortion 9.3% (CCIF); IHFM power bandwidth 21 to 20 KC; speaker output impedances 4, 8, 16 ohms. Front panel controls: Input selector (phono or tape head, Tuner, Extra); Equalization (NAB tape head or RIAA record equalization), Stereo Selector Switch; separate tone controls for channels A & B Stereo Balance; Derived Center Channel Level Control; Loudness On-Off; Scratch Filter; Tape Monitor; Loudness Compensation, 15 1/2" x 5 1/4" x 13 1/4" D.

G-625WX (less case) Shpg. wt., 35 lbs. Net 159.95
Leatherette metal case for LK-72 kit.
G-147W Shpg. wt. 5 lbs. Net 13.95

PACO STEREO COMPONENTS

NEW PACO ST-35MX FM STEREO



**TUNER KIT
MULTIPLEX**

A superb FM Tuner with built-in pre-aligned multiplex circuitry. Outstanding features and specifications include dual limiters; Foster-Seeley discriminator; wide bandwidth of 200 KC; less than 1% harmonic distortion; push-button controlled AFC with indicating pilot light. Three-gang tuning condenser pulls in stations even in fringe areas. Easy to tune with wide-visibility tuning eye. Finished in Black and gold. Size: 15 1/2" x 11 1/4" x 5 1/2" D.

G-595WX ST-35MX Kit Net 99.95
G-596WX ST-35MXWired Net 139.95



**PACO SA-40
40-WATT STEREO
AMPLIFIER KIT**

The SA-40 combines dual 20 watt amplifiers plus versatile preamplifiers in one easy to build kit. Front panel switch converts SA-40 into a 40-watt monaural unit. Frequency Response — 30-90,000 cps ± 1 db. Distortion — Less 0.2% harmonic and 1% intermodulation per channel. Hum and Noise Level: Up to 80 db below rated output. Controls: Equalization, Mode Selector, Speaker Selector, Input Selector, Balance, Loudness/Volume, Bass, Treble and Monaural Operation. 9 Tubes, plus 2 silicon and 1 selenium rectifiers. For 117v. 50-60 cycles AC. Gold and satin black hooded case. 15 1/2" x 11 1/4" x 5 1/2" D. Shpg. wt., 23 lbs. Complete with case and step-by-step assembly manual.

G-590WX 5.00 Down Net 79.95
G-591WX SA-40 Factory Wired 5.00 Down Net 129.95

FAIRCHILD RECORDING EQUIPMENT



**2-SPEED
MODEL 440
TURNTABLE KIT**

A high fidelity turntable kit. 2-speed operation (33 1/3 and 45 rpm), single belt drive, Speed Sentinel control varies turntable speed ± 1 1/2%, highly styled and precision turntable platter. Strobe disc included to determine correct speed. Size: 19 1/2" x 10". Complete with unfinished mounting board, but less base, 19 1/2" x 10", 60 cycle, AC. Requires 1 1/4" clearance above turntable, 3 1/2" below. GR-276W Shpg. wt., 21 lbs. Net 58.00
Same as above but completely wired and assembled. Net 69.95
MODEL 440CBW. Base for above. Includes walnut mounting board, walnut wraparound. 19 1/2" x 8". Shpg. wt., 12 lbs. Net 18.95
GR-275W



REKO KUT 2 SPEED TURNTABLE KIT

K-34H TWO SPEED STEREO TABLE KIT. The same high quality and performance of the N-33H (described above) but with two speeds. Motor: Lifetime lubricated hysteresis—synchronous. Speeds: 33 1/3 and 45 RPM. Noise Level: 57 db. Wow and Flutter 0-15%. Chassis Deck: 12 1/2" x 19". Shpg. wt., 17 lbs. Net 69.95
GR-260WX
KB Walnut finish woodbase for K-34H turntable. Net 14.95
GR-262W Shpg. wt. 8 lbs.



**Jensen
57.75 KTF-3 SPEAKER KIT**

Provides the necessary speaker components for TF-3 performance in a home-built or separately bought cabinet. Kit includes the woofer, two midrange units and tweeter of the TF-3 system. Includes M-1/M-F balance control, crossover network, wiring cable, enclosure vent tube and full instructions for enclosure construction. SPECIFICATIONS: Frequency Range: 25 cps to beyond audibility. Crossovers: 2,000 and 10,000 cps. Speaker System Power Rating: 25 watts. Impedance 8 ohms. GS-313 Shpg. wt., 11 1/2 lbs. Net 57.75

NEW FISHER HI-FI KITS



**THE FISHER KX-200 80
WATT STEREO CONTROL
AMPLIFIER KIT
169.50**

Fisher engineers have developed a new concept of kit design known as Stratakit. Major components are pre-mounted and wires are pre-cut. The KX-200 amplifier/preamp specifications are: 80 watts IHFM music power output; (35 watts RMS each channel) Harmonic distortion (at rated output) 0.4%; IM Distortion (SMPT), at rated output 0.8%; Frequency response (overall) 20-20,000 cps ± 1 db—total hum and noise 80 db (450mv rep); Channel Separation at 1 KC better than 50 db. Tubes: 6 ECC83, 4-7591, 2-SD95A, 2-SD91A. Built-in D'Arsonval calibration meter. For 117V, 60 cycles AC. Size: 15 1/2" x 12 1/2" x 5 1/4" H. Shpg. wt., 30 lbs.

G-666WX KX-200 Amplifier, less case Net 169.50
G-109W MC-2 Metal Cabinet for KX-200. Shpg. wt., 9 lbs. Net 15.95



**NEW FISHER KM-60
FM STEREO TUNER KIT**

A high quality FM Stereo multiplex tuner kit with famous Fisher features. Ultra-Sensitive Golden Cascade Front-End provides clear reception even from distant stations, exclusive Stereo Beam instantly indicates whether or not a station is broadcasting in stereo, precision D'Arsonval tuning meter which is also used in alignment of IF and ratio detector sections; pre-aligned front-end and multiplex section. 4 IF stages and 2 limiters. SPECS: Sensitivity 0.6 microvolts at 20db quieting, Signal-to-noise ratio 70db at 100% mod., Freq. response — ± 1db 20-15,000 CPS. 11 Tubes 12 Diodes, Selenium rectifier. Complete with illustrated manual. Size: 15 1/2" x 4 1/2" x 13 1/4" D. Shpg. wt., 18 lbs. Less cabinet.

G-667WX Net 169.50
MC-2 Metal cabinet for KM-60 Net 15.95
G-109W Shpg. wt., 9 lbs.



**FISHER SLIM-LINE SPEAKER
SYSTEM KITS MODEL KS-1**

The Fisher KS-1 Slim-line Loudspeaker System lends itself to virtually any type of installation. It can be wall mounted, placed on the floor or in a bookshelf. Composed of a 10-inch free-piston woofer with 30 CPS free-air resonance and 4-lb. magnet; 5-inch AcoustiGlas packed midrange unit. LC type B-way crossover network. 8-ohm impedance. Supplied complete with cabinet; grille cloth, AcoustiGlas padding and instructions. Size: 18 1/2" x 24 1/2" x 5 1/4" D. Shpg. wt., 26 lbs.

GB-464WX KS-1B Speaker System Kit, Unfinished Net 59.50
GB-465WX KS-1W Speaker System Kit, Walnut Net 64.50
GB-462WX KS-1AB As above, Factory Assembled, Unfinished Net 84.50
GB-463WX KS-1AW As above, Factory Assembled, Walnut Net 89.50

FAIRCHILD COMPANDER KIT

Automatic Sensing Device
The Fairchild Compander is a deluxe automatic sensing device that allows recreation of original performance dynamics in existing playback equipment for discs, tape or FM. The Compander is not an amplifier. It does not introduce distortion or require a 110 V AC power supply. The Compander is inserted between the output program source: pickup, tape unit, or FM and the input of preamp, or integrated amp. By deriving and analyzing a signal from the existing amplifier — the Compander automatically increases your amplifier gain to allow dynamic expansion of high level signals to compensate for the controls placed on the original recording. Surface noise; turnable and system noises are minimized. Right or left information is displayed giving insight into original studio mike placement. Dynamically expands signals—increases separation effects of signal. Also can be used as signal compressor for background music control. Specifications: Input Imp. 47 K ohms both channels. Output Imp. 47 K ohms. Control circuit imp. 4-16 ohms; Min. Control Circuit volt. 25V AC. Expansion 8 db max/channel. Compression 20 db max. channel. Distortion—none. Freq. response — Flat through entire audio range. AC Power Requirements — none. Dim.: 8 1/2" x 5 1/2" x 2 1/2" D. Shpg. wt., 6 lbs. G-676WX Compander kit Net 59.95
G-675WX Compander Factory Wired and Assembled Net 75.00



CITATION STEREO KITS




**CITATION IIIX
FM STEREO TUNER KIT**

Famous Citation III now has built-in multiplex. Outstanding sensitivity is featured with a completely assembled and prealigned FM cartridge. Maximum selectivity is assured by Nuvistor Front end followed by three wide band IF stages. Sensitivity 0.65 microvolts for 20db quieting. Frequency response ± 0.5db, 1-52,000 CPS, (mono) 10-15,000 CPS (stereo); Dual cascaded gated beam limiters; Foster-Seeley discriminator. Hum: 65db below 100% modulation. Stereo Separation, —30db at 10-15,000 CPS. 6x1 1/4" x 12 1/4" D. For 110-120V AC. Shpg. wt., 33 lbs.

G-364WX Citation IIIX Stereo Tuner Kit Net 219.95
G-374WX Citation IIIX Stereo Tuner wired Net 299.95
G-365WX Citation III FM Tuner Kit with multiplex output jack. Shpg. wt., 32 lbs. Net 149.95
G-366WX Citation III wired with Multiplex output jack Net 229.95
G-232W WC1 walnut enclosure for Citation III and IIIX Net 29.95
G-373WX Citation III MA FM Stereo Adapter wired. Shpg. wt., 3 lbs. Net 79.95


CITATION HI-FI EQUIPMENT



**CITATION I KIT
Stereo Preamplifier Control Center**

A high quality stereo-monaural preamp-control unit. Inputs: 12 (six pairs) — Aux, Tape Amp, Tuner, low-level phono, high-level phono. Outputs: 5-Two main preamp outputs plus a third channel output, two tape outputs for recording. Mode selector chooses output types: stereo, Blend A + B, Channel A, Channel B, Stereo Reverse. IM DISTORTION: Less than 0.05% at 2 volts. RESPONSE: to ± 5 db 5-80,000 cps. Tubes: 9-ECC83/12AX7 plus silicon rect. POWER REQUIREMENTS: 110V AC, SIZE: 14 1/2" x 12 1/4" x 6 1/2" H. Shpg. wt., 20 lbs. Gold & Charcoal brown finish.

G-230WX Kit Net 159.95
G-231WX Wired Net 249.95
G-232W Walnut Enclosure Net 29.95



**CITATION II KIT
120 Watt Stereophonic Hi-Fi Power Amplifier**

Two ultra-linear type amplifiers deliver 60 watts each channel or a total of 120 monaural. Frequency Response: 18-40,000 cps ± 0 to —1.0 db @ 60 watts. 2-80,000 cps ± 0 —1.0 db @ 1 watt; IM Distortion: Less than .5% @ 60 watts. Harmonic Distortion: Less than 0.5%, 20-20,000 cps @ 60 watts, Output 4, 8, 16 ohms. Tubes: 6-12BV7, 4-KT88, plus 4-Silicon Diodes & 1 Selenium rect. Dimensions: 16 1/2" x 9 1/2" x 11 1/2" D. Charcoal Brown & Gold Finish. Shpg. wt., 60 lbs.

G-233WX Kit Net 159.95
G-234WX Wired Net 229.95
G-235W Charcoal Brown Metal Enclosure Net 7.95

dynakit STEREO KITS



DYNAKIT PAS-2 STEREO PREAMPLIFIER KIT

Includes two independent high gain, low noise preamplifier-control channels. Inputs: 3 stereo low level and 4 stereo high level. Frequency response: ± 0.5 db 6-60,000 cps. Distortion: less than .05%. Noise: less than 3 uv. equivalent noise input on RIAA. Gain: 60 db at 1000 cps on RIAA, 20 db on high level. Tubes: 4-12AX7/ECC-83, 6X4, selenium rectifier. Textured vinyl finish. Size: 13 1/2" x 4". Shpg. wt., 11 lbs.

G-453WX Kit Net 59.95
Dynakit PAS-2 Stereo Preamp. Same as above, but completely wired. Shpg. wt., 11 lbs. Net 99.95
G-454WX
Model PM-3 Panel mounting kit for PAS-2. Shpg. wt., 3 lbs. Net 4.95
G-468



**DYNAKIT STEREO 70
70-WATT STEREO AMPLIFIER KIT**

The stereo 70 is rated at 35 watts channel or 70 watts for monophonic. Frequency response: ± 0.5 db 10-40,000 cps. IM distortion: less than 1% at 35 watts. Sensitivity: 1.3 volts rms input for 35 watts output. Output impedance: 4, 8, 16 ohms. Minimum channel separation: 55 db. Size: 13 1/2" x 9 1/2" x 6 1/2" D. Shpg. wt., 32 lbs.

G-455WX Kit Net 99.95
Dynakit Stereo 70 Stereo Amplifier. Same as above, but completely wired. Net 129.95
G-456WX

VEICO HI-FIDELITY COMPONENTS • Kits and Wired



**NEW! EICO ST-84
STEREO PREAMPLIFIER**

A comprehensive self-powered stereo preamplifier which features 0.05% distortion or less on all basic functions (mag phono, tuner, tape). Input and mode selectors each have seven positions each for maximum flexibility. Independent bass and treble controls provide true variable crossover control to boost or cut. Tape recorder outputs are not affected by controls. Has high and low frequency filtering, Tape Speed equalization and monitor switches for top tape control flexibility. Also includes level, and balance controls and a loudness switch. Frequency Response is 0.3 db from 5 to 25,000 CPS. Hum and noise is a 65db for low level inputs and —75db for high level inputs. RIAA phono equalization and NARTB for Tape. Tube Complement five 12AX7/ECC83 plus one 6X4. Metal cover is included. Finished in brush gold aluminum faceplate with brown accenting band. Size: 5 1/2" x 15 1/2" x 8 3/4" D.

G-523WX ST-84 Kit Net 59.95
G-524WX ST-84 Wired Net 89.95

NEW! MODEL MX-99 FM MULTIPLEX ADAPTER



NEW! MODEL MX-99 FM MULTIPLEX ADAPTER

The EICO MX-99 is a self-powered multiplex adapter. It is free of phase distorting filters and meets or exceeds the required suppression of all spurious signals including the SCA (67KC) background music carrier, reinserted (38KC) sub-carrier, the (19KC) pilot carrier and all harmonics thereof. This factor is very important for high quality stereo tape recording. This adapter will synchronize with any usable output from the FM tuner. Provides automatic stereo-monophonic operation and includes low impedance cathode follower outputs. An indicator lamp turns on when a station is broadcasting multiplex stereo. It can achieve channel separation of 35db. The MX-99 is designed for all EICO FM equipment (HFT-90, HFT-92, ST-96), and any other component quality ratio detector FM tuners provided with a multiplex output. Size: 9 1/2" x 6 1/2" x 3 1/4" H. Shpg. wt., 7 lbs. Less metal enclosure.

G-442 Kit 39.95
G-443 Factory wired and tested 64.95
G-522 E-9 metal enclosure for MX-99. Shpg. wt., 2 lbs. Net 2.95



EICO MODEL HFT 90K FM TUNER KIT

Factory pre-wired and pre-aligned front end. Pre-wired tuning eye assembly. Stereo FM Multiplex reception with adaptor, "traveling" tuning indicator, fly-wheel tuning and AGC. SENSITIVITY: 1.5 uv for 20 db quieting; 2.5 uv for 30db quieting; full limiting from 25 uv. INPUT: 300 ohm balanced. OUTPUTS: Cathode follower and multiplier. TUBES: 1-ECC85/40 watts at 110-120 volts AC, 50-60 cycles. Complete with instructions. 12 1/2" x 4 1/2" x 3 1/4" D. Shpg. wt., 10 lbs.

G-422 Kit Net 39.95
G-423 HFT-90 Same as above, but factory wired Net 65.95
G-431 E-3 Cover for HFT-90. Shpg. wt., 3 lbs. Net 3.95



**EICO ST-40K 40-WATT STEREO
INTEGRATED AMPLIFIER KIT**

The ST-40 contains 2 twenty watt amplifiers and a complete stereophonic hi-fi control center on one chassis. FEATURES: Switched sets of stereo inputs including magnetic phono (2), tape head, preamplified tape, FM-AM stereo tuner, FM-FM Multiplex, and Auxiliary. Balance Check switch. Loudness/level switch. Bass and treble controls. Other controls include: Six position mode selector, tape monitor, scratch and rumble. Output 4, 8, and 16 ohm. Third channel speaker connection. Specifications: IM distortion—2% at 40 watts; Harmonic Distortion—1/2% at 40 watts; Frequency response—± 1/2 db. 20-20,000 cps. Shpg. wt., 27 lbs.


G-520WX Net 79.95
G-521WX Same as above, but wired. Net 129.95



**EICO ST-70K 70 WATT STEREO
INTEGRATED AMPLIFIER KIT**

Consists of 2-35 watt amplifiers and a complete stereophonic hi-fi control center on one chassis. Stereo inputs in switched sets including: 2 magnetic phono (one for turntable, one for changer); tape head, preamplified tape, FM-AM stereo tuner, FM-FM Multiplex, and Auxiliary. Controls: Level with balance check switch and loudness/level switch; bass, treble, six-position mode selector, blend, tape speed, tape monitor, scratch, and rumble. Output: 4, 8, and 16 ohm speaker. Third channel output available. Specifications: IM distortion — 2% at 70-watts. Harmonic Distortion — 1/2% at 70 watts. Frequency response — ± 1/2 db. 20-20,000 cps. Shpg. wt., 35 lbs.

G-518WX Net 94.95
G-519WX As above, but factory wired. Net 149.95



**NEW! EICO RP-100K
TAPE DECK KIT**

A new, precision stereo/monaural tape deck, the RP-100 provides stereo/mono 1/4 track erase, record, and playback; plus 1/2 track stereo/mono playback. Separate record and playback heads and preamps permit simultaneous stereo playback from tape while recording. Sound-on-sound recordings can be obtained without changing any connections. Features: Dual meters for monitoring stereo record levels and separate line and mic. (dynamic) mixing controls for each channel; SPECIFICATIONS: Tape speed—7 1/2 or 3 1/2 ips; up to 7" reel size; Flutter and Wow —0.2% at 7 1/2 ips, 0.25% at 3 1/2 ips; Frequency response: 30-17,000 cps at 7 1/2 ips, 40-15,000 cps at 3 1/2 ips; Signal-to-Noise ratio — 53 db, or better. Timing accuracy—0.3%. Dimensions: 15 1/4" wide, 13 3/4" front-to-back, 7" deep. Shpg. wt., 28 lbs.

RP-100K semikit; includes transport completely assembled and tested with 3 heads; stereo record, and stereo playback preamps in kit form.
RK-275WX Net 299.95
RP-100W wired and tested with 3 heads, stereo record, playback preamplifiers. Net 309.95
RK-276WX
Model CC-2 Luggage Type Carrying Case with detachable cover. For RP-100 Net 29.95
RK-277W Shpg. wt., 13 lbs.

GARRARD • GLASER-STEERS • LESA • MIRACORD

PICKERING 380C DIAMOND STEREO CARTRIDGE, SHURE M7D DIAMOND STEREO CARTRIDGE, GE VR-1000-7 DIAMOND STEREO CARTRIDGE OR AUDIO EMPIRE S108 DIAMOND STEREO CARTRIDGE FOR ONLY . . .

1/2 SALE!

when you purchase any changer shown below



NEW! GARRARD AUTOSLIM AUTOMATIC INTERMIX CHANGER • 4 Speed
Wired for Stereo and Monaural
39.51
PLUS PICKERING, SHURE, AUDIO EMPIRE OR GE CARTRIDGE

An ultra-compact, automatic-manual changer at a remarkably low price. Only 6 1/4" overall height. Intermixes all records, i.e. records of different sizes can be stacked in any sequence. Separate manual and automatic controls—featuring Garrard's new center-changing mechanism. The Autoslim employs a new type of a turntable and a 4-pole shaded motor, achieving balance and quiet turning. Faun-colored unit plate with white trim. Dimensions: 14 1/4" left to right; 12 1/2" front to rear; 4 1/4" above top of motor-board, 2 3/8" below. For 100-130 VAC, 60 cycles. Imported from England.
GR-168W Less cartridge. Shpg. wt., 9 lbs. Net 39.50
Garrard "Autoslim" plus Pickering 380C Diamond Stereo Cartridge. PK-556W Shpg. wt., 9 lbs. Net 39.51
Garrard "Autoslim" plus Empire 108 Diamond Stereo Cartridge. PK-557W Shpg. wt., 9 lbs. Net 39.51
Garrard "Autoslim" plus Shure M7D Diamond Stereo Cartridge. PK-558W Shpg. wt., 9 lbs. Net 39.51
Garrard "Autoslim" plus GE VR1000-7 Diamond Stereo Cartridge. PK-559W Shpg. wt., 9 lbs. Net 39.51



GARRARD RC88 "MARK II" RECORD CHANGER
Plus PICKERING, SHURE, GE OR AUDIO EMPIRE CARTRIDGE
ONLY 59.51

The Garrard RC88 is a deluxe auto-manual changer wired for stereo and monaural use. Plays all 4 speeds (16, 33 1/3, 45 and 78 RPM). An outstanding performer in an attractive style. Complete with line cord, pickup lead, plug-in shell, mounting hardware, standard and manual spindles, and 45 RPM adaptor. Shpg. wt., 16 lbs. Net 59.50
Garrard RC88 Changer PLUS Pickering 380C Diamond Stereo Cartridge. PK-526W Shpg. wt., 16 lbs. Net 59.51
Garrard RC88 Changer PLUS Shure M7D Diamond Stereo Cartridge. PK-527W Shpg. wt., 16 lbs. Net 59.51
Garrard RC88 Changer PLUS GE VR1000-7 Diamond Stereo Cartridge. PK-604W Shpg. wt., 16 lbs. Net 59.51
GARRARD RC 88 PLUS Audio Empire S108 Diamond Stereo Cartridge. PK-547W Net 59.51



LESA CD 2/21 AUTOMATIC CHANGER
Plus PICKERING, SHURE, GE OR AUDIO EMPIRE CARTRIDGE
only 44.51

Fully automatic jam-proof Lesa changer plays up to eight records of any size, with automatic intermix. Easy to operate—only two controls for all cycles, speed selection, start, stop and reject. Shpg. wt., 17 lbs. GR-195W Lesa changer, less base & cartridge. Net 44.50
LESA CD 2/21 PLUS Pickering 380C Diamond Stereo Cartridge. PK-506W Shpg. wt., 17 lbs. Net 44.51
LESA CD 2/21 PLUS Audio Empire S-108 Diamond Stereo Cartridge. PK-507W Shpg. wt., 17 lbs. Net 44.51
LESA CD 2/21 PLUS GE VR1000-7 Diamond Stereo Cartridge. PK-562W Shpg. wt., 17 lbs. Net 44.51
LESA CD 2/21 PLUS SHURE M7D Diamond Stereo Cartridge. PK-538W Shpg. wt., 17 lbs. Net 44.51
GR-197 Automatic 45 RPM Spindle. Net 3.75
Base for changer—specify mahogany, walnut or blonde. GR-196W Shpg. wt., 3 lbs. Net 4.75



GARRARD MODEL "A" AUTOMATIC TURNTABLE
Plus PICKERING, SHURE, GE OR AUDIO EMPIRE CARTRIDGE
ONLY 79.51

The Garrard Model "A" is a precision turntable and tone arm with the convenience of automatic record changing. Plays all 4 speeds and is wired for stereo and monaural use. Features a built-in stylus pressure gauge. Complete with line cord, pick-up leads, plug-in shell, mounting hardware, standard and manual spindles, 45 RPM adaptor. Shpg. wt., 19 lbs. GR-166WX Garrard Model "A" Net 79.50
Garrard Model "A" plus Pickering 380C Diamond Stereo Cartridge. PK-523WX Shpg. wt., 19 lbs. Net 79.51
Garrard Model "A" plus Shure M7D Diamond Stereo Cartridge. PK-524WX Shpg. wt., 19 lbs. Net 79.51
Garrard Model "A" plus GE VR1000-7 Diamond Stereo Cartridge. PK-551WX Shpg. wt., 19 lbs. Net 79.51
GARRARD Model "A" plus Audio Empire S108 Diamond Stereo Cartridge. PK-548WX Net 79.51



GLASER-STEERS GS-77 RECORD CHANGER
Plus PICKERING, SHURE, GE OR AUDIO EMPIRE CARTRIDGE
ONLY 59.51

Fully automatic, 4-speed stereo record changer. Transcription-type tone arm; inaudible wow, rumble and flutter. 4 pole motor. Shpg. wt., 13 lbs. GR-50W Changer only, less base, cart. Net 59.50
GS-77 PLUS PICKERING 380C Diamond Stereo Cartridge, less base. PK-540W Shpg. wt., 13 lbs. Net 59.51
GS-77 PLUS Shure M7D Diamond Stereo Cartridge, less base. PK-541W Shpg. wt., 13 lbs. Net 59.51
GS-77 PLUS GE VR1000-7 Diamond Stereo Cartridge, less base. PK-564W Shpg. wt., 13 lbs. Net 59.51
GS-77 plus Audio Empire S108 Diamond Stereo Cartridge. PK-550W Net 59.51
Wood base for changer. Ebony with gold trim. Shpg. wt., 5 lbs. PK-350W Net 9.60
PK-352 Automatic 45 RPM Spindle. Shpg. wt., 1 1/2 lbs. Net 2.95



MIRACORD "STUDIO" MODEL AUTOMATIC TURNTABLE
Plus PICKERING, SHURE, GE OR AUDIO EMPIRE CARTRIDGE
79.96

Pushbuttons select automatic or manual operation at any of 4 speeds. Specially designed, heavy-duty 4-pole induction motor. Jam-proof, counter-balance tone arm; famous "Magic Wand" spindle. GR-351WX Less Base and Cartridge. Net 79.95
Miracord "Studio" PLUS Pickering 380C Diamond Stereo Cartridge. PK-574WX Net 79.96
Miracord "Studio" PLUS Audio Empire S108 Diamond Stereo Cartridge. PK-573WX Net 79.96
Miracord "Studio" PLUS Shure M7D Diamond Stereo Cartridge. PK-575WX Net 79.96
Miracord "Studio" PLUS GE VR-1000-7 Diamond Stereo Cartridge. PK-576WX Net 79.96
GR-352W Oil Walnut Wood Base. Net 9.95
GR-354W Automatic 45 RPM Spindle. Net 5.00

PICKERING 380C stereo cartridge with .7 mil diamond stylus with exclusive "V-Guard." Shpg. wt., 5 oz. GD-214L Net 29.85

SHURE M7D moving magnet stereo cartridge with .7 mil diamond stylus. Shpg. wt., 5 oz. GD-273L Net 23.52

GE VR1000-7 magnetic, variable reluctance cartridge with .7 mil diamond stylus. Shpg. wt., 6 oz. GD-144L Net 24.45

AUDIO EMPIRE S108 stereo cartridge with .7 mil diamond stylus. Shpg. wt., 7 oz. GD-315L Net 35.00

NEW!



LAFAYETTE STEREO-MATIC 4-SPEED RECORD CHANGER

RONETTE CERAMIC CARTRIDGE

LESS BASE
ONLY 22.35

NO MONEY DOWN

MADE IN U. S. A.

• Plays Stereo, LP and 78 RPM

• Quality Ronette Ceramic Cartridge • Automatic 3-Way Shut-Off • Intermixes Records of Same Speed • Heavy Duty-Constant Speed Motor

Feature for Feature, the Lafayette Stereo-matic record changer matches or exceeds costlier units. Built for compatibility with both stereophonic and monaural records, this changer offers superior performance for budget-sparing music systems. The balanced featherweight tone arm operates at only 5-7 grams of needle pressure to minimize record wear. Flip-type, Ronette ceramic stereo cartridge is unaffected by heat and humidity. Heavy precision-balanced turntable and constant speed motor insure smooth rotation without hum rumble or "wow". Plays all 4 record speeds—automatically changes up to fourteen 7", twelve 10" or 12" records. Intermixes 10" and 12" records of same speed. Plays records manually if desired. 45 r.p.m. spindle optional. Automatic 3-way shut-off after last record (returns tone arm to rest, stops

turntable motor, turns set off.) neutral position disengages turntable drive wheel when not in use—prevents rumble producing flat spots. 117 volts AC, 60 cycles. Compact and exceptionally functional, only 13 1/2 x 12 7/2 x 3 1/2" below and 5 1/2" above mounting board. Beautiful brown and gold finish. Shpg. wt., 12 lbs. PK-605W No Money Down Net 22.35
PK-606W Walnut Base Net 4.50
PK-607W Mahogany Base Net 3.95
PK-608W Mounting Board Net 1.10
PK-609 45 R.P.M. Spindle Net 1.49

LAFAYETTE'S PANASONIC



TURNTABLE WILL TRACK AT ANGLES IN EXCESS OF 45°
SALE PRICE 19.95 REG. 32.50
• Distortion Free From 20-16,000 cps • Flat Frequency Response 20-15,000 cps • Feather Light Stylus Pressure—Individually Adjusted For 3-Grams • Hum Free—Entire Arm & Cartridge Case Shielded with Mu Metal
Tone arm resonance is minimized by use of specially designed counter weight, sub weight and lateral damping mechanism. The arm counter balance is floated on a damped suspension bar. Precision bearings assure minimum lateral and vertical friction. Overall height of arm adjusts from 1 3/4" to 2 1/8". Signal to noise level of well over 100 db. Stylus replacement requires only a few seconds, pull out the old stylus and plug in the new. The diamond stylus is capable of supplying up to 2,000 hours of playing time. With .7 mil diamond stylus, mounting instructions, stylus cleaning brush, all hardware. Shpg. wt., 3 lbs. PK-448 Net 19.95
Complete .7 Mil Diamond Stylus Assembly for PK-448 Lafayette Panasonic Tone Arm. Shpg. wt., 1/4 lb. PK-452 Net 7.95
TECHNICAL INFORMATION
Output Voltage . . . 5 millivolts • Channel Separation . . . More than 25 db • S/N Level . . . Over 100 db • Compliance . . . 5x10—6 cm/dyne • Suggested Load Impedance . . . 50,000 ohms • D. C. Resistance . . . 420 ohms • Tracking Force . . . 3 grams • Stylus . . . 7 mil • Frequency Response . . . Distortion free: 20-16,000 cps Flat. ± 2 db 20-15,000 cps • Overall Length . . . 11 1/2"

Lafayette TRADE 'N' SAVE SALE!

united Audio

the TOP RATED DUAL 1006 STEREO TURNTABLE/CHANGER with the STEREO CARTRIDGE of your choice
Trade-In Your Old Phono Cartridge & Save Up to **49.95**

ORDER TODAY—LAFAYETTE WILL SHIP YOUR DUAL 1006 and CARTRIDGE IMMEDIATELY SEND US YOUR TRADE-IN CARTRIDGE LATER



LAFAYETTE'S LOW-LOW TRADE-IN PRICE IS ONLY 65.00
No Money Down

PICKERING	SHURE	EMPIRE
380C	M7D	S-108
GD-214L	GD-273L	GD-315L
Reg Catalog Price	Reg Catalog Price	Reg Catalog Price
29.85	23.52	35.00

Here's one of the top buys LAFAYETTE has ever offered! Send LAFAYETTE your old phonograph cartridge (regardless of make or condition) and purchase the top-rated Dual stereo record changer with your choice of any one of the famous diamond-needle stereo cartridges shown here, AT AN UNPRECEDENTED TRADE-IN SAVING.
Combining the flexibility of a changer with performance of a transcription turntable, the Dual 1006 features a completely free-floating tone-arm with built-in stylus pressure gauge plus a 3 1/2 lb. turntable, laminated and girded for rigidity. Powerful motor reaches full speed under load in 1/2 sec. "Rigid equispaced" motor suspension, 4-speed control system with separate drive gears for each speed prevents flat-spot thumping. Simplified push button controls. Stereo-Mono switch removes vertical noise often picked up while playing monaural records. "Elevator action" isolates

bottom record on the spindle from rest of stack assuring protection of record grooves and centers. Intermix mechanism handles up to 10 records.
Complete with 2 cartridge holders, single play spindle, changer spindle and 45 adaptor disc. For 110/120V 60 cycle AC. Chassis 10 3/4 x 13 1" requires 3" clearance below 6" above. Shpg. wt., 20 lbs. Address your orders and cartridge trade-ins to Trade-In Department.
PK-611WX Dual 1006 with Pickering 380C Net 65.00
PK-612WX Dual 1006 with Shure M7D Net 65.00
PK-613WX Dual 1006 with Audio Empire S-108 Net 65.00
Wooden Base for dual 1006. Specify Mahogany or Walnut GR-188W Net 6.95
Dual AS-4 Automatic 45 RPM Record Changer Spindle PK-392 Net 4.80
Dual 1006 Changer without Trade-In & Less Cartridge GR-186WX Net 79.95

NEW 3-IN-1 EASY-PAY-PLAN—NO MONEY DOWN, UP TO 24 MONTHS TO PAY. SEE PAGE 54



NEW LAFAYETTE 4 TRANSISTOR PUSH-BUTTON TAPE RECORDER



Miniature
Only
8x3 1/2 x 7 3/8" D

NO MONEY DOWN

29⁹⁵

Complete with Microphone, Earphone 3" Reel of Tape, Empty Reel, Batteries

FOR HOME, SCHOOL, OFFICE

• Lightweight—A mere 2 1/4 lbs. • Records and plays up to 20 minutes with 1 Standard 3" Reel • Pushbutton Play, Rewind, Off • Battery operated • Completely Portable—Take it with you Anywhere

A real triumph in miniature recorders. Space age printed circuitry using a 4 transistor push-pull amplifier and built-in oval 2 1/2 x 4" PM Speaker provides quality sound. Light weight makes it ideal for travel, business use. Has all the most wanted features. Convenient push-button fast Rewind, Off and Play controls. Record safety interlock prevents accidental erasure of tape; volume control is independent of Off switch; erases automatically in record position. No need for AC adapter; operates on 2 inexpensive batteries. Inputs for microphone and earphone for private playback. Designed for maximum tape economy, the RK-133 employs a half-track tape head—upper half is recorded first and turning over tape records lower half. Plays 10 minutes per side with standard tape—more

with 1/2 mil Long play tape. The handsome two-tone plastic case features a sloping speaker grille which faces front for optimum sound and a snap open top for fast, easy tape loading. Power is supplied by 1 standard 1.5v standard flashlight cell and one 9v transistor battery. Supplied with crystal label microphone, magnetic earphone, batteries, 200 ft. 3" reel of tape and an empty reel. Dimensions: 8Wx3 1/2 Hx7 3/8" D. Shpg. wt., 4 lbs.

RK-133L	Net 29.95
REPLACEMENT BATTERIES FOR RK-133	
BA-2 9 volt transistor battery	ea. Net .39
BA-157 1.5 volt	ea. Net .13

LAFAYETTE RK-138 2-SPEED 4-TRACK TAPE RECORDER SECOND PREAMP for STEREO PLAYBACK

SPECIFICATIONS:
Response: 50-10,000 cps. Wow & Flutter: less than 0.3%. Signal-to-Noise Ratio: 40db. Outputs: Include 2 output jacks — 1) second-channel external amplifier. 2) external speaker.

NO MONEY DOWN **99⁹⁵**

- Plays Back 4-Track Stereo & Records Dual Track Monophonically • Two Speeds—7 1/2 ips & 3 3/4 ips
- Accepts Up To 7" Reel • Has 2 Playback Preamplifiers
- Neon Recording Level Indicator

Loaded with features, precision engineered and built to last, the new Lafayette tape recorder must be classified a best-buy by any standards. Designed for complete flexibility, the RK-138 offers both stereo and monophonic facilities. In addition to being able to record and play back 2-track monaural material, through its own speaker and amplifier, you can use the RK-138 for 4-track playback of the latest stereo tapes through your own component stereo system. Or, if you wish, use its self contained 6-watt amplifier and speakers (5" woofer, 4" tweeter with electronic crossover) as a second stereo channel in association with your monaural hi-fi system, radio, T.V., or with RK-139 matching speaker/amplifier with patch cord for radio, T.V., or tuner input.


Functional design utilizes a single, easy-to-use lever to select "Play-Idle-Record" positions. A special safety interlock in record position insures against accidental erasure of tapes. Fast rewind is accomplished by means of a lock-in lever control with tone and loudness adjusted by a concentric front panel control. Equipped with sensitive microphone, 7" reel of tape with 7" take up reel and patch cord. For 110-120V, 60 cycle AC operation.



MADE IN U.S.A.

Net 99.95

MATCHING AMPLIFIER SPEAKER COMBINATION FOR STEREO PLAYBACK



MADE IN U.S.A. **24⁵⁰**

8 FOOT HOOK-UP CABLE

This attractive speaker/amplifier is style matched and electronically balanced to provide a second stereo channel for the RK-138 Tape Recorder described. Contains 6-watt amplifier, 5" woofer and 4" tweeter. Supplied with 8 ft. hook up cable. Shpg. wt., 6 lbs.

RK-139W Net 24.50

LAFAYETTE VALUE COMBINATION



BOTH THE RK-138 TAPE RECORDER AND THE RK-139 AMPLIFIER/SPEAKER COMPLETELY EQUIPPED WITH EVERYTHING YOU NEED FOR FULL TAPE RECORDER ENJOYMENT

124⁴⁵

NO MONEY DOWN

A complete portable tape recorder and stereo playback system which in addition to the regularly supplied equipment contains 3 7" reels of tape, 12 tape storage cans, storage chest plus tape splicer and roll of splicing tape. Shpg. wt., 32 lbs.

RKS-16WX Net 124.45

Award-Winning TAPE RECORDER

Lafayette SCOOPS the TAPE RECORDER INDUSTRY

Music at Home at the Office



Never Before Such Exceptional Quality and Value!

Voice Recording parties — dancing

ONLY **49.50**

• Completely Portable—Carry it Anywhere! • Two Speeds—3 3/4" or 7 1/2" Per Second • Uses Standard 5" Reel • Frequency Response 60-8,500 C.P.S.

Perfect for home, school or office. At home, the RK-400 proves ideal for parties or recording your favorite musical performance. Handy fool-proof operation has been provided by a single rugged function control (reverse, stop, play and record) and separate on/off volume control. Speeds are adjustable from 3 3/4" to 7 1/2" per second by a simple capstan adjustment. At 3 3/4" ips the RK-400 provides up to one hour of recording time on a standard 600 ft. 5" reel of tape. Special 5" heavy duty permanent magnet speaker furnishes an exceptionally fine tonal quality. Record level indicator light facilitates recording by showing you when volume control is correctly set. Jacks are provided for microphone, phono and extension speaker (special alligator clip cord is supplied). Complete with sensitive crystal microphone. Finished in attractive scuff resistant pyroxylin material. Dimensions: 11 1/4 x 9 3/4 x 7 1/4". For 110 volts 50-60 cycles. Shpg. wt., 20 lbs.

RK-400W Net 49.50
LAFAYETTE ACETATE BASE RECORDING TAPE. Features noise-free reproduction, low abrasion, uniform output. 1 1/2-mil thickness; 5" reel; 600-ft. Shpg. wt., 1/2 lb.
RT-17 lots of 1-4, Net ea. .99
lots of 5-24, Net ea. .90 lots of 25 up, Net ea. .85

LAFAYETTE KT-91
PUSH-PULL AMPLIFIER



10-WATT
HI-FI AMPLIFIER KIT
24⁵⁰
NO MONEY DOWN



LAFAYETTE SK-124
ULTRA-COMPLIANCE
SPEAKER SYSTEM

MADE IN U.S.A.



TELEFUNKEN
AUTOMATIC
RECORD CHANGER

10 WATT PUSH PULL HI-FI AMPLIFIER KIT

• BUILT-IN PREAMPLIFIER • SELECTOR SWITCHES PERMIT CHOICE OF THREE INPUTS • SEPARATE BASS AND TREBLE CONTROLS • 4, 8 AND 16 OHM OUTPUTS • EASY-TO-FOLLOW INSTRUCTIONS

This new, economy hi-fi amplifier has many deluxe features for exceptional performance. The three inputs are radio/crystal phono pickup, magnetic phono pickup and microphone. A selector switches the input from radio/crystal to microphone or magnetic pickup, depending upon the position of a rear apron slide switch. OUTPUT—Rated 10 watts, peak 18. FREQUENCY RESPONSE—± 1 db 30-15,000 cps. DISTORTION—1.5% harmonic, 4% intermodulation at 8 watts. 4 CONTROLS—Input Selector; Volume; Treble; Power-On-Off-Bass. TREBLE CONTROL—Flat response up to 18 db cut. BASS CONTROL—Flat response up to 15 db boost. OUTPUT IMPEDANCES—4, 8 and 16 ohms. TUBES—6SC7, 6SL7GT, 2-6V6GT and 5Y3GT rectifier. AUXILIARY AC OUTLET—Distinctive Hammett finish. SIZE—10 1/2 x 6 1/4 x 5 1/4" WEIGHT—8 1/2 lbs. For 110-120 volts. Complete kit with coded wire, highest grade solder and detailed instruction manual.

Net 24.50

MONAURAL HI-FI PHONO SYSTEM KIT

Have FUN—SAVE MONEY by assembling this top-value system yourself! Features Lafayette KT-91 10-watt amplifier kit; famous Telefunken 4 speed automatic record changer with intermixing, jam proof operation, and automatic shut off features, crystal turnover cartridge with dual sapphire styli for stereo and monaural records, and 45 rpm automatic spindle adapter plus amazing Lafayette SK-124 Ultra-Compliance 2 way speaker system in mahogany or walnut (specify finish). Tuner can be added at any time for radio program reception. Less changer base. Shpg. wt., 34 lbs.

PK-600WX	Net 62.50
PK-341W Mahogany base for changer	Net 3.95
PK-342W Walnut base for changer	Net 4.50
Unfinished mounting board cut for changer	Net .95
PK-343W	Net .95

LAFAYETTE - TAPE RECORDERS FOR EVERY NEED!

Technicorder

MINIATURE TRANSISTORIZED TWO-SPEED TAPE RECORDER

Employs 6 Transistors, plus a Thermistor for high gain performance



Ideal For Office Dictation



Now A Tape Recorder You Can Carry Anywhere—Precision Design And Construction Providing Professional Quality, Features & Performance.

SUPPLIED COMPLETE WITH



- Weighs Only 6 lbs. With Batteries
- Fully Transistorized—6 Transistors plus 1 Thermistor
- Records & Plays Up to 64 Minutes
- Dual Track
- Two Speeds—3 3/4 ips & 1 7/8 ips
- Push Button Controls
- Built-In Speaker
- Use Anywhere—Powered By 4 Inexpensive Flashlight Batteries
- Rugged Dynamic Microphone
- Special Synchro-rod Synchronized Tape Speed With Your 8mm Home Movies



NO MONEY DOWN

79.50

Lafayette proudly presents the RK-126 Technicorder—6 lbs. of precision tape recorder you can carry anywhere, use everywhere. Measuring only 9 1/2 x 7 1/2 x 3 1/2", and as easy to carry as a camera, the Technicorder operates in any position—even while walking. This remarkable new miniature recorder is perfect for both business and pleasure—record conferences, interviews, dictation, lectures, telephone conversations or use at home for parties and recording important occasions, even adding sound to your home movies. Employing the most advanced transistor circuitry (6 transistors plus 1 thermistor) and constructed with the care and precision of a fine watch, the RK-126 provides a level of quality and performance never before achieved in a unit this size and price. Operation is accomplished entirely by push-button with rewind, stop, play and record functions furnished by 3 simple push-button controls. In addition as a safety feature, a special record button is provided to prevent accidental erasure. The correct reading level and battery condition is given by a VU meter located on the front panel. Convenient volume control adjustment with jacks external speaker and microphone are easily accessible at the side. For home movie fans a specially designed Synchro-rod is provided, which, when screwed into the capstan allows synchronizing the speed of the RK-126 with that of your 8mm projector. Two speeds, 3 3/4 and 1 7/8 are provided, with speed changes easily accomplished by means of a simple capstan adjustment. Designed for maximum tape economy, the Technicorder utilizes precision dual track heads (1 erase plus 1 record/playback) to provide record/playback time at 3 3/4 ips for 16 minutes per single track and 32 minutes per dual track; at 1 7/8 ips time is

extended to 32 minutes per single track and 64 minutes per dual track. Exceptional fidelity and sound quality are achieved by means of a specially developed 2 3/4 x 8 1/4" oval speaker and AC recording bias system, with a signal-to-noise ratio of -49 db. Housed in an attractive tan and black hi-impact poly-vinyl case, the Technicorder features a handy snap-open plexiglass top for fast, efficient tape loading. Supplied complete with shoulder strap, vinyl carrying case, dynamic microphone and case, 3" reel of tape and empty reel, batteries, splicing tape and extension speaker cord. Size: 3 1/2 x 9 1/2 x 7 3/4" D. Shpg. wt., 8 lbs.

RK-126L Net 79.50

TECHNICORDER ACCESSORIES

- AC Adaptor—Permits operation of the RK-126 Technicorder on 115V, 60 cycles AC. Net 17.95
- RK-216 Shpg. wt., 3 lbs.
- Telephone Pickup—Attaches to telephone for recording telephone conversations. Net 3.95
- RK-128 Shpg. wt., 1/2 lb.
- Foot Switch—Perfect for dictation—starts and stops RK-126 instantly. Net 4.95
- RK-129 Shpg. wt., 1 1/2 lbs.
- RK-131 Mike w/Remote Switch for RK-126 Technicorder Net 7.95
- RT-20 Tape—3" reel of 300 ft. 1/2 mil nylon tape. Shpg. wt., 1/2 lb. Net .69
- BA-157 Replacement Batteries for RK-126, 4 reqd. Shpg. wt., 4 ozs. Net ea. .13

NEW!


RK-115WX STEREO TAPE DECK

199.45

- Record & Playback 4-Track & 2-Track Stereo & Monaural
- Separate Playback and Record Preamplifiers

Completely self-contained the RK-115 combines a precision tape and stereo recording and playback pre-amplifier in one compact portable unit. 1/4 track stereo erase and record/playback heads are laminate triple mu-metal shielded professional type, providing a frequency response of 30-16,000 cps ± 2db at 7 1/2 ips or 40-12,500 cps ± 3db at 3 3/4 ips. Crosstalk rejection is better than 55db. Wow & Flutter: less than .18% at 7 1/2 ips, less than .25% at 3 3/4 ips. Switches and Controls: Transport Mechanism Selector Control provides forward-stop-rewind; Fast forward lever; Record safety switch to prevent accidental erasure; Speed selector for 7 1/2 ips and 3 3/4 ips; Socket for electromagnetic remote control. Stereo Record/Playback Amplifier Controls: Channel selector for stereo, monaural 1-4 and 2-3 channels, Equalization selector; Recording/Playback selector for each channel; Volume control for each channel. Outputs: Cathode follower outputs for external stereo amplifier; Monitoring output jacks for hi-impedance or crystal earphones. Accepts up to 7" reel of tape. Complete with attractive vinyl covered carrying case. Size: 15 1/2 x 11 x 6" H. Shpg. wt., 60 lbs. For 60 cycles 110-120 volts AC.

RK-115WX Net 199.45
Stereo Tape deck, same as RK-115WX above, but without case or electronics (preamps).
RK-118WX Net 89.50



BOOK SIZE only 7 1/2" W x 5 3/4" D x 2 1/2" H

REMOTE CONTROL SWITCH

79.95

NO MONEY DOWN

NEW! LAFAYETTE Transistorized Professional MINIATURE TAPE RECORDER

- Two Speeds—3 3/4 & 1 7/8 IPS
- Fully Transistorized—5 Transistors, 1 Thermistor
- Complete With New Dynamic Microphone
- Includes Carrying Case
- Portable—Only 4 lbs.
- Remote Control Mike Switch

Ideal for use everywhere (travel, sales meetings, club functions, parties, etc.)—self-contained with built-in speaker and amplifier, 5 transistors and 1 thermistor with precision printed circuitry and quality PM speaker you would expect from units three and four times this price. Single function lever operation for Rewind, Stop, Play and Record; special safety record button prevents accidental erasure. Built-in level meter shows battery condition and correct recording level. New rugged, sensitive dynamic microphone with desk stand. Convenient volume control adjustment plus jacks for earphones, radio and microphone are accessible from the front. Inputs at rear for AC power supply and remote control foot switch. Microphone equipped with remote control switch for starting and stopping recorder instantly, providing true one-hand operation. Sturdy metal case has snap-open top for easy tape loading and features a calibrated plexiglass insert for viewing tape motion and estimating playing time. Precision heads (1 erase 1 record/playback) are half-track—upper half is recorded first and tape is then turned over to record on lower half. Records and plays up to 68 minutes at 1 7/8 ips; 34 minutes at 3 3/4 ips. Powered by 6 inexpensive standard penlight cells (included). Supplied with dynamic microphone with remote control switch, crystal earphone, 3" reel of tape with 300 ft. of tape, empty reel and leather carrying case. Shpg. wt., 8 lbs.

RK-135WX Net 79.95

COMPLETE RANGE OF ACCESSORIES

- AC ADAPTOR—Allows switching the RK-135 from battery operation to 115 v, 60 cycle AC. Has on/off switch plus pilot light. Shpg. wt., 2 1/2 lbs. Imported Net 9.95
- RK-136 REMOTE CONTROL FOOT SWITCH—Starts and stops RK-135 instantly. Ideal for dictation. Net 4.75
- RK-122A Shpg. wt., 1 1/2 lbs.
- TELEPHONE PICK-UP COIL—For recording telephone conversations. Net 2.95
- RK-121 Shpg. wt., 1 lb.
- PATCH CORD—Allows recording from radio, TV, phono, speaker. Net .85
- RK-124 Shpg. wt., 1/2 lb.
- 3" REEL 300 Ft. 1/2 Mil Mylar Tape. Shpg. wt., 1/2 lb. Net .69
- RT-20 BATTERIES—The RK-135 requires 6 standard "Z" cells. Shpg. wt., 4 oz. Net ea. .095
- BA-155

NEW BELL PROFESSIONAL STEREO TAPE DECK MODEL T-337



Features Built-in Stereo Record / Playback Pre-Amplifier

- 4 TRACK STEREO RECORD/PLAYBACK
- 2 TRACK STEREO PLAYBACK
- PUSH-BUTTON OPERATION

An extremely versatile tape deck with facilities for making 2-track and 4-track stereo tapes, off-the-air stereo recordings, copy stereo tapes and discs etc. Professional features include 3 heavy-duty 4-pole motors. Wow and flutter less than 0.2%. Frequency response of 18-16,500 CPS ± 3 db @ 7 1/2 CPS & 18-15,000 CPS ± 3 db @ 3 3/4 IPS (overall record-playback). Playback only extends to 20,000 cps. Signal-to-noise ratio—better than 50 db. Maximum reel size 7". Preamp has 4 inputs—2 high impedances for mikes; 2 high impedance for amps, tuners, etc. 4 outputs and 6 tubes. Has front panel mike jacks, pushbutton speed, off and pause selection. Index counter, 2 VU meters. Mounts anywhere, plays in any position. Wood grain finish. Size 15 1/4 x 13 1/2" front-to-back; 5" below mounting surface. 2" above mounting surface (Includes Preamp). RK-271WX Shpg. wt., 23 lbs. Net 293.95

Wollensak TAPE RECORDERS

AT PRICES YOU CAN AFFORD



LAFAYETTE PRICES
T-1500 148.50
T-1515-4 167.50

AWARD WINNING TAPE RECORDER VALUES

MODEL T-1500 HI-FI TAPE RECORDER

• 10 WATTS PUSH-PULL OUTPUT! • RESPONSE 40-15,000 CPS ± 3 DB AT 7 1/2 IPS! • DISTORTION LESS THAN 0.8%! • WOW AND FLUTTER BELOW 0.3%! • SIMPLIFIED KEYBOARD CONTROL! • WEIGHS ONLY 18 LBS.! A really precision portable high fidelity recorder made by a famous manufacturer of precision optics. This latest model T-1500 is made available, for the FIRST TIME AT THIS PRICE, BY LAFAYETTE! Dual speed (3.75 and 7.5 inches per second), dual track—provides up to 4 hrs. of record or playback time. Utilizes miniaturized components and all-metal airplane-type construction to achieve real portability—weighs only 18 lbs., measures 6 1/2 x 10 1/4 x 11 3/4". Takes reels up to 7". Additional features of this outstanding recorder include: signal-to-noise ratio 48 db; 2 special hum balance controls: "Balanced Tone" high fidelity; exclusive high speed rewind lever; 2-level recording indicator; precision index counter. Supplied complete with ceramic wide-range microphone, 1 reel of tape, 1 empty takeup reel, radio-tv attachment cord and hi-fi cable. For 110-120 volts, 60 cycles AC. RK-405WX Shpg. wt., 21 lbs. Net 148.50

MODEL T-1515-4 FOUR TRACK STEREO HI-FI TAPE RECORDER

The Hi-Fi enthusiast's dream in a compact portable tape recorder for true stereo performance. Has all the styling and superb features of the famous monaural T-1550, plus stereo head and built-in second preamplifier. Plays 2 and 4 track monaural and 2 and 4 track stereo. Records up to 4 separate monaural tracks on single roll of tape. RK-417WX 6 1/2 x 10 1/4 x 11 3/4". Shpg. wt., 24 lbs. Net 167.50



Norelco
289.95
NO MONEY DOWN

CONTINENTAL '400' 4 TRACK STEREO RECORDER

The new "400" model stereo tape recorder, guild-crafted by Philips of the Netherlands, reflects professional quality at a modest price. Four track stereophonic recording and playback with dual stacked heads plus 4 track monophonic operation. Three tape speeds: 7 1/2, 3 3/4, and 1 7/8 ips. FREQUENCY RESPONSE: 60-18,000 cps at 7 1/2 ips, 50-14,000 cps at 3 3/4 ips, 50-7,000 cps at 1 7/8 ips. Signal-to-Noise ratio 55 db or below. Cross-talk 55 db down. Instantaneous locking device for pauses in recording or listening. Wow and flutter less than 0.3% at 3 3/4 ips. Dubbing facilities for producing sound-on-sound. Self-contained record and playback amplifiers including dual hi-fi preamps. SPECIAL CONTROLS: For recording—ganged mike volume, and ganged radio/phono

volume. For playback—2 channel tone (individual concentric controls but friction ganged); ganged volume and ganged channel balance. INPUTS: One 2-channel input for stereo microphone; two 2-channel inputs for stereo tuners or phonos. OUTPUTS: For extension speakers (2); for external amplifiers (2); for stereo headphones (1). MIXING CONTROL for electronic mixing of phono and mike inputs. TUBES—2-EF86, 3-ECC83, 2-EL84, 1-EM84. For 117 volts, 60 cps. AC. Size: 18 1/2 x 15 1/2 x 11 1/2". Includes a Norelco professional fidelity, dual element dynamic microphone for both stereo and monaural recording.

RK-398WX Shpg. wt., 55 lbs. Net 289.95

NEW! LAFAYETTE 4 TRANSISTOR PORTABLE TAPE RECORDER with BUILT IN SPEAKER



NO MONEY DOWN

24.95

4-TRANSISTOR TAPE RECORDER

Complete with TELEPHONE PICK-UP, EARPHONE, PATCH CORD, MICROPHONE, 3" REEL OF TAPE, EMPTY REEL, BATTERIES

- Camera Size—Only 6"Dx8 1/4"Wx2 3/4"H.
- Weighs a Mere 2 1/2 lbs. • Fully Transistorized
- Records and Plays Up To 20 Minutes with 1 Standard 3" Reel
- Built-in Speaker and 4-Transistor Amplifier With Push-Pull Output
- Record, Rewind, Playback and Erase
- Powered By 3 Inexpensive Batteries
- 1/2 Track Head Provides Maximum Tape Economy

This is a precision, full function miniature tape recorder perfect for home, office or travel; weighs only 2 1/2 lbs. and slips easily into a briefcase or handbag. Utilizing sophisticated transistor circuitry with 4 transistors, the RK-125AL contains its own 2" x 3" PM speaker and amplifier with push-pull output stage. Engineered for ease of operation, with all controls readily accessible from the front panel. A single function control provides for Rewind, Stop and Forward with a second control furnishing variable Volume. Play or Record functions are chosen by a simple slide switch. In addition microphone and earphone jacks are located on front panel. Designed for maximum tape economy the RK-125 employs a half track tape head—upper half is recorded first and tape is turned over to record on lower half. . . records and plays up to 20 minutes on a 300 ft. 1/2 mil 3 inch reel of tape.

The attractive two-tone plastic and metal case features a carrying handle and snap open top for fast, easy tape loading. Power is supplied by 2 standard 1.5v flashlight cells and one 9v transistor battery. Complete with crystal laval microphone, magnetic earphone, batteries, 100 ft. 3" reel of tape and an empty reel. Measures only 6Dx8 1/4Wx2 3/4"H. Shpg. wt., 5 lbs.

RK-125AL	Net 24.95
RT-20 3" REEL 300 Ft. 1/2 MIL MYLAR TAPE. Shpg. wt., 1/4 lb.	Net .69
BA-2 9V TRANSISTOR BATTERY. Shpg. wt., 2 oz.	Net .39
BA-156 1.5V BATTERY (2 required). Shpg. wt., 2 oz.	Net .13

LUXOR MP-410A 4-TRACK STEREO TAPE RECORDER

279.00



No Money Down

Superb Swedish Craftsmanship

- 40-17,000 C.P.S. at 7 1/2 IPS • Two & Four Track Stereo & Monaural Record & Playback • 3 Speeds 7 1/2—3 3/4—1 1/2 IPS • Completely Self Contained with Built-In Speakers and Amplifiers

Superb performance, virtually unlimited versatility plus flawless Swedish precision construction makes this one of the finest instruments we've ever offered. A completely self contained stereo tape unit, the Luxor is equipped with its own built-in speakers and amplifiers for record/playback of both stereo and monaural two and four track tapes. In addition to use as a high performance portable, the Luxor is ideal for utilization with your component stereo system as a tape deck. Fast forward, fast reverse and play are controlled by a single, 3 position, positive shift lever. Record control is furnished with an interlock. Separate gain controls for the two built in stereo speakers. Additional features include: magic eye recording level indicators for each channel and digital tape counter. Frequency Response: 40-17,000 cps @ 7 1/2 ips; 40-14,000 cps @ 3 3/4 ips; 80-8,000 cps @ 1 1/2 ips; Flutter & Wow: ± .09 RMS @ 7 1/2 ips; ± 18% RMS @ 3 3/4 ips. ± .25% RMS @ 1 1/2 ips. Stereo Channel Separation better than 35 db. Supplied with patch cord to assure easy use with all U.S. made components. Size: 14 1/2Lx11 1/2Wx6 1/2"H. Shpg. wt., 30 lbs. For 117 Volts, 60 cycle AC. RK-477WX Net 279.00

NEW! LAFAYETTE DELUXE DUAL SPEED TAPE RECORDER MODEL RK-130

PLAYS BOTH 7" and 5" REELS

- Two Speeds 3 3/4 and 7 1/2 I.P.S.
- Plays Both 7" and 5" Reels
- Built-in Speaker and Amplifier
- Complete with Dynamic Microphone

NO MONEY DOWN

79.95

The perfect companion for language work, voice and instrument study, personal and family use, office work—a worthwhile investment for any classroom. This rugged tape recorder plays both 7" and 5" reels at speeds of 3 3/4 and 7 1/2 inches per second. Consists of a double track, high frequency bias recording system with a frequency response range of 80 to 10,000 cycles, and a high frequency erase system. Internal amplifier provides 1.5 watts audio output to a built-in 4 3/4" speaker. An additional speaker may be plugged into the output jack. The RK-130 features simplicity of operation for quick stopping, playing, recording, fast forward winding or rewinding. Two input jacks are provided to permit simultaneous recording from a radio or record player and a microphone. Dynamic microphone is included with the unit. Both volume and tone are adjustable, and a neon tube recording level indicator is provided to facilitate correct settings. A switch allows the user to hear the playback either through the speaker or through a set of headphones (not supplied). A 7" tape reel played on both tracks will last for 120 minutes at 3 3/4 i.p.s., or for 60 minutes at 7 1/2 i.p.s. A 5" reel will last 60 minutes at 3 3/4 i.p.s., or 30 minutes at 7 1/2 i.p.s. Internal amplifier tube complement: 1—12AD7, 1—6BM8, 1—6AR5, plus 1—6X4 rectifier. For 117 VAC, 60 cps. Recorder dimensions: 16.4x12.4x8". Complete with 7" empty reel, dynamic microphone, patch cord, instructions, and large, removable strap for easy carrying. Shpg. wt., 28 lbs..

RK-130WX	Net 79.95
7" reel with 1200 ft. of recording tape. Shpg. wt., 1 lb.	
RT-10	Net 1.59



NEW! RK-116WX 4-TRACK STEREO TAPE RECORDER

- Professional Quality Laminated Record/Playback Heads • Records Sound-On-Sound
- 5-Watt Hi-Fi Quality Amplifier • Electromatic Remote Control
- Response 40-15,000 cps • 7 1/2 & 3 3/4 ips



149.50 NO MONEY DOWN

Performance and value make this a best buy in stereo tape recorders. Designed for stereo record and playback when used with the RK-117. Speaker/Amplifier as well as monaural record/playback when used singly. Features include special mu-metal shielded professional type laminated record/playback heads; beltless drive mechanism, magic-eye recording level indicator, electromatic remote control plus self-contained 5 watt amplifier and speaker. Frequency Response: 40-15,000 cps at 7 1/2 ips, 40-10,000 cps at 3 3/4 ips. Wow & Flutter less than .20% at 7 1/2 ips. Controls: Dual type volume control allows adjusting recording and playback level individually for left and right channels and tone control. Accepts up to 7" reel of tape. Complete with dynamic microphone, recording patch cord, monitoring earphone and attractive vinyl covered Philippine mahogany carrying case. For 60 cycles—110-120 volts AC. Shpg. wt., 26 lbs.

RK-116WX	Net 149.50
----------	------------

COMPANION RK-117WX SPEAKER/AMPLIFIER



Identical in appearance to the RK-116. Contains its own 5-watt power amplifier and speaker to operate as a second channel power amplifier and speaker for the RK-116. Also functions as a second channel recording amplifier for making live stereo recordings or recording directly from radio or stereo records. For 60 cycles 110-120 volts AC.

RK-117WX Shpg. wt., 12 lbs.	Net 59.00
-----------------------------	-----------

LAFAYETTE COMBINATION SPECIAL!

The RK-116WX and RK-117WX combined to make a complete stereo portable tape system and to save you money at this special combination price. SP-247WX Net 199.50

SAVE 9.00

SONY MODEL 101 TRANSISTORIZED DUAL-TRACK TAPE RECORDER

- 2-Speed 7 1/2 & 3 3/4 ips
- Fast Forward & Rewind
- Lightweight

Only **97.50** NO MONEY DOWN

An AC powered bantam weight dual track tape recorder which incorporates the latest design in transistor circuitry. Ideal for those who require a low cost, high fidelity reproduction, the model 101 records and plays back monophonic 2-track tape with a frequency response of 50-12,000 cps at 7 1/2 ips and 50-8,000 cps at 3 3/4 ips. Flutter & wow, less than 0.25% at 7 1/2

ips. Imposing features include: a Vu meter and volume control; inputs for mike and auxiliary units; external speaker output, tape lifters and built-in AC power supply. Plugs directly into wall outlet. Complete with 7" reel, dynamic mike, speaker and case. Size 12Wx10Dx 6 1/2"H. RK-288WX Shpg. wt., 20 lbs. Net 97.50



SONY MODEL 464-D STERECORDER



199.50

- 4 TRACK STEREO & MONO RECORD PLAY
- BUILT-IN RECORD-PLAY PREAMPS
- 2 SPEEDS — 7 1/2 & 3 3/4 ips
- REMOTE CHANNEL INTEGRATOR CONTROL UNIT
- SOUND-ON SOUND

NO MONEY DOWN

The compact 464-D is a 2-speed 4-track stereo and monophonic record/play tape recorder designed for custom installation. Contains built-in record and play pre-amplifiers with frequency response of 40-15,000 CPS @ 7 1/2, 40-10,000 @ 3 3/4 ips and bias frequency of 60 KC. Features include: beltless drive mechanism, sound-on-sound and sound-with-sound switch, push-button mode selector for stereo or 4 tr. mono record and playback. Signal-to-noise ratio better than 50 db. Special compact accessory panel permits easy accessibility to microphone inputs and sound-on-sound switching — Less case. Size: 13 1/4Wx11 3/4Dx6"H. RK-286WX Shpg. wt., 23 lbs. Net 199.50

SONY MODEL 262-D TAPE DECK



87.70

NO MONEY DOWN

- 4-Track Stereo Record/Playback & Erase Heads
- 7 1/2 & 3 3/4 ips Tape Speeds
- 30-18,000 cps Response
- Full 7" Diam. Reel Capacity

High quality at a truly economical price make this unit an unbeatable value. Plays back through your Hi-Fi system Amplifier must be added to record. For 117 VAC. Size: 13Wx10Dx5 1/2"H. Shpg. wt., 15 lbs. RK-282WX Sony 262-D Tape Deck Net 87.70 RK-284W Walnut base for 262-D Net 12.95 RK-287WX Sony Recording Amplifier for above Net 89.50

AMPEX THE FINE LINE 1200 SERIES

NEW MODEL 1260 Portable 2-Speed Tape Recorder



545.00

NO MONEY DOWN

- RECORDS: 4-Track Stereophonic 4-Track Monophonic
- PLAYS: 4-Track Stereophonic 2-Track Stereophonic 4-Track Monophonic

Offers superior recording facilities with preamplifier included. Features separate erase, record and playback heads; automatic tape take-up, built-in mixer; 4 inputs; recording level meter and exclusive "Auto-Set" shutoff which operates for either unattended recording or playback. Specs: Freq. response 50-15,000 cps ±2db @ 7 1/2 ips; 50-8,000 cps ±2db, 3 3/4 ips; S-N ratio: Better than 55 db @ 7 1/2 ips. Size in case, 9x15x17 1/2". For 117V AC, 60 cps. RK-303WX Shpg. wt., 38 lbs. Net 545.00 MODEL 1250 DECK Same as Model 1260 but less case. Size: 13Wx6 1/2Dx11 1/2" above top plate. Net 449.50 RK-305WX MODEL 1270 Same as 1250 but with matched pair of speakers and case. Size: 9Hx25 1/2Wx15"D. Net 645.00 RK-304WX Shpg. wt., 46 lbs.



LAFAYETTE TOP QUALITY RECORDING TAPE

LAFAYETTE RECORDING TAPES

LAFAYETTE QUALITY IS BACKED BY OUR MONEY-BACK GUARANTEE



LAFAYETTE'S FAMOUS MONEY-BACK GUARANTEE

Lafayette's tape is made by outstanding nationally known manufacturers. It is first quality, splice free, red oxide coated, with full frequency response, uniform output and no "drop-outs". Resistant to moisture, heat, cold and abrasion. We guarantee absolute satisfaction or your money back. If you do not find it equal to tapes costing up to twice the price, if for any reason you are dissatisfied, return the tape in 30 days and we will refund your money. You are the sole judge.

LAFAYETTE MYLAR BASE RECORDING TAPE

AS LOW AS **1.42** RT-19 900 ft. 25 & up

Mylar base is especially strong, durable and break resistant, and is virtually impervious to heat, cold or humidity. All in clear plastic reels, individually boxed.

Stock No.	Feet	Reel	Mils	WL Lbs.	1-4	5-24	25 Up
RT-19	900	5"	1	3/4	1.75	1.58	1.42
RT-12	1800	7"	1	1 1/4	2.50	2.25	2.13
RT-13	2400	7"	1/2	1 1/4	3.69	3.39	3.22

Tensitized Mylar
Prestretched, super-strong mylar base.
RT-16 2400 7" 3/4 1 1/2 4.95 4.45 4.23

3" REEL 300-ft. 1/2 mil Mylar tape. AS **.63**
Shpg. wt., 1/2 lb.
RT-20 Net ea. 1-4, .69; 5-24, .63

YOU BE THE JUDGE!

LAFAYETTE ACETATE BASE RECORDING TAPE

AS LOW AS **85^c** RT-17 600 ft. 25 & up

Acetate base magnetic recording tape with uniform standard red oxide coating provides wide range high fidelity response over the audio spectrum. Features noise free reproduction, low abrasion and uniform output. In 1 mil and 1 1/2 mil thickness.

Stock No.	Feet	Reel	Mils	Wt. Lbs.	1-4	5-24	25 Up
RT-17	600	5"	1 1/2	3/2	.99	.90	.85
RT-18	900	5"	1	3/4	1.35	1.20	1.08
RT-10	1200	7"	1 1/2	1	1.59	1.49	1.35
RT-11	1800	7"	1	1 1/4	1.98	1.88	1.79

LAFAYETTE BULK TAPE ERASER AND DEMAGNETIZER

PROFESSIONAL MODEL

- Erases 1/2" Tapes in One Operation—No Reversing
- For 3", 5", 7" or 10 1/2" Reels
- Completely Erases Tapes
- Two Erasing Coils
- Erases up to 1" Tape

18.95




A carefully designed and precisely manufactured tape "degausser" for complete erasing of tapes. Just place the tape reel on spindle of demagnetizer, slowly rotate 2 or 3 turns, take off, and that's all. Reduce tape hiss to the level of new "virgin" tape. Two completely separate coils are used for doubly-effective erasures, even of large, 10 1/2" reels. Will erase 1" wide tape. An extra powerful unit for heavy-duty use—draws over 9 amperes. Can be used to demagnetize tape, magnetically stripped film, plus tools and watches. Has a heavy, custom finished case, a rugged non-magnetic top, heavy duty on-off switch and power cord. Has built-in fuse. Pilot light prevents accidentally leaving it turned on. Size 6 1/4 x 7 7/8 x 3 1/2". Shpg. wt., 14 lbs.

ML-120 Net 18.95

STANDARD MODEL

- Takes Reels Up To 10 1/2"
- Reduces Noise Level
- Top Value

12⁵⁰



A bulk tape demagnetizer that erases existing recorded signals and noise from magnetic tapes quickly and efficiently. Also capable of demagnetizing metal parts and work tools. Ideal for the recording enthusiast desiring clean, noise-free tapes. Simply rotate reel of tape several turns over unit, turn over and repeat once. Has two spindle positions: Inner position for tape reel sizes up to 7" in diameter, and the outer one for 10 1/2" reels. Push button energizes the coil, and a pilot light installed on top of the unit indicates unit in operation. Non-magnetic bakelite plate for tape reel rest. One powerful coil is used for effective erasure of all quarter-inch tapes. Current consumption—5 amps. Heavy duty, rugged gauge metal case. Attractive finish. For 105-125 volts, 60 cycles. Size 7 1/2 x 4 3/4 x 3 1/2". Shpg. wt., 9 lbs.

ML-176 Net 12.50

LAFAYETTE MYLAR SPECIAL

THE RECORDING TAPE BUY OF THE YEAR—YOU BE THE JUDGE! 1200 FT. 1 1/2 MIL SPLICE-FREE LIFETIME MYLAR BASE RECORDING TAPE



AS LOW AS **1.25** RT-22 5 and up

Sensational buy by Lafayette brings you this 1 1/2 mil splice-free mylar base lifetime recording tape at an unbelievable low price. This 1 1/2 mil mylar tape features unprecedented recording tape strength as well as exceptional resistance to heat, cold, humidity and abrasion. 7" reel. Shpg. wt., 1 lb.

RT-22 Each Net 1.49
5 and up Each Net 1.25

NEW! Lafayette RECORD, PLAYBACK and ERASE HEADS

3.95 per set



- Ideal for Experimenters
- Half-Track Recording Playback and Erase

A Lafayette special—ideal for the experimenter interested in tape recorders. Recording head has impedance of 9K ohm at 1,000 cps, DC resistance 130 ohms, reproduction level—40, recording at—10db. Bias frequency 30KC, bias 10MA. Frequency 60-12,000 cps ± 5db. SN ratio—40db. Erasing head: DC resistance 10 ohms, erasing current 15-20 milliam. AC bias, DC erase systems. Record head 7/8 x 1 1/4 x 3/4"; erase head 3/8 x 1 3/8". Shpg. wt., 8 oz. 5-687 Net 3.95

LAFAYETTE TAPE HEAD DEMAGNETIZER

3.95 • REMOVABLE POLEPIECES • EXTRA CONVENIENT



Lafayette Tape Head Demagnetizer uses removable polepieces. Three complete sets are furnished: straight, 45° and 90° (right angle), permitting quick and easy use with any tape head. Far from being a luxury, a tape head demagnetizer is necessary for best tape recorder performance. Although unmagnetized when new, tape heads gradually become magnetized by sharp switching pulses occurring while switching the recorder from play to record or vice versa. The solution is to use a demagnetizer to remove this permanent magnetism from the head, thus reducing the noise level. Periodic head demagnetization is required for all tape recorders to insure optimum signal-to-noise ratio. Now Lafayette enables anyone with even the most modest budget to perform this necessary demagnetization with a minimum of effort. For 110 volts 60 cycles. Shpg. wt., 1 lb. PK-238 Tape Head Demagnetizer 3.95

CLEAR PLASTIC REELS

.26



IN LOTS OF 6

Individually boxed plastic reels for recording tape. Av. shpg. wt., 4 oz. singly.
MS-692 5" reel. In lots of 6, Ea. .26 Singly, Ea. .29
MS-267. 7" reel. In lots of 6, Ea. .38 Singly, Ea. .45

LAFAYETTE SPECIAL

3.95 per set

Size: 1/2 W x 3/2 D x 3/4" H.




RECORD PLAYBACK and ERASE HEADS for MINIATURE TRANSISTORIZED TAPE RECORDERS

A two-piece set consisting of one record/playback and one erase tape head. Designed for use in dual track miniature tape recorder. These units will replace the heads in most Japanese-built recorders, and are also excellent for the experimenter. Record/playback head specifications: impedance 2.2K at 1 KC; DC resistance: 160 ohms; reproduction level: —45db (recording at —10db); bias frequency: 35KC; bias current: 400ma; voice current: 100ma; response: 100-7000 cps ± 5db; S/N ratio: better than 45db; bias system: AC & DC reproduction: gap: .00024 in. (-.006mm); dimensions: approx. 1/2 W x 3/2 D x 3/4" H. Erase head same dimensions. Total shpg. wt., 3 oz. F-432 Net 3.95

MAGNETIC TAPE SPLICER

1.47



- Cut Both Ends Simultaneously
- Easy to Operate
- Durable & Sturdy

An excellent accessory that splices tapes accurately and eliminates joint noise. Both ends cut simultaneously. Nickle-plated brass finish. Shpg. wt., 1 lb. MS-289 Net 1.47

NEW!

NEW! STROB-LOOP RECORDER TEST TAPE

CHECKS: • SPEED • TIMING • WOW • FLUTTER
Accurate within 1/10 of One Percent!

For 7.5 I.P.S. Shpg. wt., 6 oz. MS-914

Net **.98**



REEL LOCKS

59c Set of Two

Holds tape recorder reel in place by locking spindle to reel. Especially useful if recorder is in vertical position. Will not interfere with normal operation of reels. Easily removable. Shpg. wt., 6 oz. MS-564 Set of two .59

TAPE CLEANER

1.49



Simple, unique recorder head cleaner. Tape is impregnated with special formula cleaner. Simply run through like regular roll of tape. Entire job done in 2 minutes. Can be reused many times. 100' roll on plastic reel. Shpg. wt., 8 oz. PK-283 Net 1.49

NEW TELEPHONE PICKUP COIL




1.89

This telephone pick-up coil is designed to feed into the microphone input of either a tape recorder or any high gain amplifier. The pick up can be easily attached to the telephone by the use of a rubber suction type attachment. The coil is electrostatically shielded to minimize hum pick-up. When properly positioned on telephone handset, the output of this device is more than adequate for a fully modulated tape recording. Complete with 5' shielded cable. Shpg. wt., 6 oz. MS-693 Net 1.89



METAL TAPE STORAGE CHEST

STANDARD CASE: Sturdy all steel carrying case. Holds 12 7" or 5" reels and cons. Twin snap locks for positive closure; perfect portability. Guards against exposure and accidental erase. Platinum gray hammerloid finish. Metal separators between reels. Includes index cords. Shpg. wt., 5 lbs. ML-60 Net 2.99



(A) ROBINS "GIBSON GIRL" SPLICER


Cuts 2 rounded indentations in the tape splice, leaving the edges of the tape which contact parts of the recorder entirely free of adhesive. Adhesive deposited on initial parts of recorder is a frequent cause of wow and flutter. As little as 1/4" tape need be removed. Shpg. wt., 1/2 lb. MS-288 Net 6.25

(B) EDITALL TAPE EDITING KIT

This kit has all the equipment required to execute a complete editing job on a professional basis. The cutting block supplied is simple to operate but is precise in its application; made of duraluminum precisely machined and polished (makes straight or diagonal cut). All accessories such as grease pencil, blades, splicing tape (66 ft. roll of 1/2") supplied. Comes with instruction booklet—in a smart metal case. Shpg. wt., 1 lb. MS-474 EDITALL KIT Net 8.82

BUY 12 TWIST LOCK TAPE CANS

NEW! FOR ONLY 4.95



AND GET STORAGE CHEST FREE!

12 dust-free, moisture-proof unbreakable styrene tape cans in storage chest. Can has foolproof twist lock feature and is ribbed for convenient stacking. Center locking stud prevents reel movement on all 7" reels and most 3" and 5" reels. Shpg. wt., 6 lbs. ML-302 Net 4.95

Pressure sensitive for editing and splicing. Shpg. wt., 3 oz. RT-265 Type 515C1 1/4" x 100" Net .17
RT-267 Type 511C1 1/2" x 100" Net .22
RT-268 Type 512C1 1/2" x 150" Net .30
RT-269 Type 513C1 3/4" x 100" Net .32
RT-270 Type 514C1 3/4" x 150" Net .39

RCA SPLICING TAPES

Convenient press-on adhesive labels for positive identification of tape reels. Easy to apply or remove. Shpg. wt., 5 oz. MS-292 Pkg. of 30 .13

ADHESIVE REEL LABELS

Convenient press-on adhesive labels for positive identification of tape reels. Easy to apply or remove. Shpg. wt., 5 oz. MS-292 Pkg. of 30 .13



METAL STORAGE CANS

Your best protection for valuable recorded tapes and movie film. Cans are ribbed for easy storage. Precision fit makes opening and closing easy. Attractively finished in grey. 3 sizes to choose from to fit any size reel. Av. shpg. wt., 8 ozs.

ML-154 3" Can. lots of 6, Ea. .18 Singly, Ea. .20
ML-155 5" Can. lots of 6, Ea. .27 Singly, Ea. .30
ML-61 7" Can. lots of 6, Ea. .36 Singly, Ea. .39



(A) ROBINS TAPE THREADER

No more awkward fumbling while threading a reel. Just place the tape against the reel, slip your Robins Threader over the capstan shaft and over the empty reel. Tip of threader holds the tape firmly against the reel. A few turns on the crank and you're ready to play or record. Saves time and tape. Shpg. wt., 2 oz. MS-222 .79

(B) TAPE THREADER

For quick and simple tape reel threading. Simply clip on and start recorder. Works on all size reels. Handsome chrome finish. In plastic case. Shpg. wt., 6 oz. MS-374 TAPE THREADER List 2.50 Net 1.47



SAVE WITH EXCLUSIVE LAFAYETTE HI-FI

now from Great Britain... **LAFAYETTE**
PERFORMANCE, DESIGN & VALUE


THE LAFAYETTE SOVEREIGN 12 . . .

3-Way High Performance

High-Fidelity Speaker



49⁵⁰
 NO MONEY DOWN



LAFAYETTE'S FINEST 12" SPEAKER

Constructed by master English craftsmen to Lafayette's rigid specifications, the "Lafayette SK-210 Sovereign 12" must be considered among the very finest 12" speakers available. Engineered to satisfy the most discriminating listener, the SK-210 achieves full 3 speaker performance through its advanced triaxial design. Woofer, midrange radiator and tweeter are all axially mounted within a single rigid, unitized die cast frame, to provide an integrated, efficient wide range speaker system. Construction features incorporate a 3 inch voice coil with an exclusive "Rigidflex" cone-bonding and cone-edge treatment process to form a virtually free-edged cone suspen-

sion. All irregularities of the audible frequency spectrum are smoothed out with standing waves and surround resonances eliminated. High efficiency and low distortion are further assured by use of a specially designed 2 1/4 lb. ceramic magnet. The quality of the Sovereign 12" is immediately evident in its uncompromising performance. Frequency response is 30-20,000 cps with a free-air woofer cone resonance of 35 cps. Bass response is tight and solid without boom or hangover to achieve a phenomenal realism. At 2000 cps, frequencies are channeled into a stiff-coned mid-frequency radiator by means of a smooth mechanical

crossover. High frequencies are reproduced with a silkiness and naturalness to beyond the limits of human hearing by means of a compression driver tweeter. This superb new tweeter incorporates a rigid, die cast, flared, hyperelliptical horn, a 1" diameter aluminum voice coil and diaphragm in a self-aligning assembly with air chamber and phase equalizer. A built-in crossover allows the tweeter to take over at 5,000 cps and is provided with a high-frequency L-pad level control with attractive escutcheon and knob. Shpg. wt., 15 lbs. Recommended with Elliptoflex® enclosures. SK-210 Net 49.50



ROYAL DANISH 12" DUAL CONE SPEAKER

• HIGH FLUX DENSITY

7.95

Lafayette brings you this fine imported high fidelity speaker at a fraction of the price you would expect to pay for so much quality. Two cones are mounted on a single axis, and provide remarkable wide range frequency response from 45 to 14,000 cps. Reproduction of program material is exceptionally lifelike throughout the entire range. An exclusive, special formula cone rim treatment eliminates cone rim resonance and distortion. Also, the damping effect improves transient response and prevents "hangover." Overall depth, 5 1/4". Completely enclosed. 1" diameter voice coil with an impedance of 6 ohms. Shpg. wt., 6 lbs. SK-86. 12" Dual Cone Hi-Fi Speaker Net 7.95

the Revolutionary LAFAYETTE

Sphericon



SK-146

22⁵⁰

HIGH FREQUENCY SUPER TWEETER


- Frequency response from 3,000 cps to beyond 40,000 cps
- Uniform dispersion over 120 degrees in all directions
- High sensitivity allows use with any 4-16 ohm speaker
- Requires no high voltage or power supply
- Built-in 3,000 cycle crossover network

Achieve unequalled brilliance and musical warmth from your present speaker system or the system you're now planning. The Lafayette's Sphericon is an entirely new concept in tweeter design. Equipped with a built-in 3,000 cycle crossover network and featuring a specially designed domed phenolic diaphragm with spherical diffractor. The Sphericon produces a virtually linear response from 3,000 cps to beyond 40,000 cps, ± 2 db. to 22,000 cps. High frequencies are radiated in a 120° pattern in all directions, vertically as well as horizontally—with absolutely no trace of stridency or harshness. Unlike electrostatic tweeters the "Sphericon" is highly efficient and may easily be matched with any speaker or speaker systems . . . especially the low efficiency high compliance type. Precise matching of the "Sphericon" with today's low and medium efficiency speaker is accomplished by means of a special built-in attenuator designed not to affect or lower the efficiency of the woofer. As a result less amplification is needed assuring lower distortion. Power capacity is 30 watts. May be employed with any 4-16 ohm speaker. Beautifully styled with an acoustically designed gold anodized grill set in a sturdy satin black plastic case. Dimensions: 9x4x2 1/2" D. SK-146 Shpg. wt., 4 lbs. Net 22.50

NOW FROM LAFAYETTE... THE "BIG 8"

34.95

NO MONEY DOWN



ONLY 8" SPEAKER WITH 1 1/4 LB. MAGNET

THE LAFAYETTE SK-212 . . . A new 8-Inch 3-Way High-Fidelity Speaker with Performance and Capabilities of a 12-Inch Speaker

ONLY 8", BUT LOOK AT THESE SPECIFICATIONS AND PERFORMANCE:

- FREQUENCY RESPONSE: 35-20,000 CPS
- CONE RESONANCE: 45 CPS
- MAGNET: 1 1/4 LB. ALCOMAX
- VOICE COIL: 3" DIAM.
- FLUX DENSITY: 175,000 GAUSS
- IMPEDANCE: 16-OHMS
- POWER HANDLING CAPACITY: 25-WATTS
- 2,000 CPS MECHANICAL CROSSOVER 5000 CPS ELECTRONIC
- CROSSOVER WITH BUILT-IN BRILLIANCE CONTROL
- SPECIALLY DEVELOPED "RIGIDFLEX" FREE EDGE CONE SUSPENSION
- DIE-CAST FRAME
- NEW COMPRESSION-DRIVER TWEETER

LAFAYETTE'S "BIG 8"—The remarkable quality and performance of this new speaker provide it with the largest 8" of sound we've ever heard! With almost uncanny ability, the SK-212 easily re-creates the entire musical spectrum from 35 to 40,000 cps; achieving a standard of natural balance distortionless performance and superb transient response normally associated with larger costlier speakers. Every musical tone is there—from powerful orchestral passages and deepest organ tones to the most delicate of solos. Precision engineered to meet Lafayette's uncompromising specifications and constructed by master English craftsmen, the SK-212 incorporates the design and construction features you'd expect to find in the finest speakers. This excellence of design is best demonstrated by its 3 inch voice coil, 1 1/4 lb. Alcomax magnet, and special "rigidflex" free edge cone suspension. Woofer, midrange radiator and tweeter are axially mounted to provide wide range speaker performance. A mechanical crossover separates bass and midrange frequencies at 2,000 cycles while 5,000 cycle electrical crossover provides a smooth transition from midrange to a newly developed compression driver tweeter. A high frequency level control allows matching of sound to individual taste and room acoustics. Recommended with Elliptoflex® enclosures. SK-212W Shpg. wt., 11 1/2 lbs. Net 34.95


LAFAYETTE SK-130 8" WIDE-RANGE HI-FI SPEAKER

Check These Phenomenal Specifications

- ✓ Frequency Response: 40-18,000 cps
- ✓ Magnet Weight: 1 lb. High Efficiency Alcomax Magnet
- ✓ Flux Density: 13,500 Maxwells
- ✓ Power Handling Capacity: 15 Watts
- ✓ Cone Resonance: 55 cps
- ✓ Voice Coil: 1 Inch
- ✓ Impedance: 16 Ohms

ASTONISHING FIDELITY from a speaker of this size and modest price. Designed and finished with typical British craftsmanship, the SK-130 features an especially designed hyperbolic cone with a plastic surround suspension for wide compliance performance. Bass response is robust and full bodied, while the mid-range and highs are virtually transparent, with never a trace of shrillness or harshness.

The excellent wide-range response of the SK-130 make it ideal for stereo when used in pairs or perfect for use as a high quality extension speaker. Overall Diam. 8 1/4" x 4" Deep. Baffle cut-out 7 1/2". Rigid vibration-free frame is equipped with screw type terminals. See Elliptoflex® enclosures recommended for this speaker elsewhere in catalog. SK-130 Shpg. wt., 3 lbs. Net 12.95



NEW!

12⁹⁵



HK-3

CONE TYPE METAL-CASED HI-FI TWEETER

5.95

- FREQUENCY RESPONSE 2,000-16,000 CPS
 - HANDLES 20 WATTS • IMPORTED TO SAVE YOU MONEY
- Without doubt one of the finest cone type high frequency tweeters we have ever tested, and is exceeded in performance only by diaphragm type tweeters. It is particularly efficient in the higher end of the audio spectrum where ordinary cone tweeters tend to lose clarity and volume. With this tweeter added to your present system, you will be able to hear all the fine transients and high notes of the upper register as they were actually recorded. Entirely enclosed in metal case with base for standing by itself, or mounting on a flat surface. Bracket is supplied for mounting on panel or in cabinet. Requires crossover network such as Lafayette LN-2. Diameter 3". Depth 2 1/2". Voice coil impedance 8-16 ohms. HK-3 Hi-Fi Tweeter—Shpg. wt., 4 lbs. Net 5.95



SK-121 SK-122

NEW! METAL CASED TWEETER

2.95

- FREQUENCY RESPONSE 3,000-16,000 CPS
- HANDLES 20 WATTS OF POWER • CHOICE OF 8 OR 16 OHM IMPEDANCE

The modest price of this tweeter gives no indication as to its high quality. Smooth, silky reproduction of the high frequencies along with an even sound dispersion is insured by the use of the round cone. The tweeter assembly is protected by a heavy wire mesh screen and completely encased in an attractive Satin Gold metal. As a result of the rear casing on the tweeter, speaker interaction between speakers has been eliminated allowing for the placement of the tweeter in the same enclosure with the woofer and mid-range speakers. Supplied with sturdy attached mounting stand and 2 1/2 ft. hook-up cord. Size 2 1/2" diam. x 2" deep. SK-121 8 ohm Tweeter. Shpg. wt., 2 1/2 lbs. Net 2.95 SK-122 16 ohm Tweeter Net 2.95

SPEAKER AND ENCLOSURE COMBINATIONS

NEW! 12" WIDE-RANGE

HI-POWER
HI-FI SPEAKER


- 21.5 OZ. ALNICO 5 MAGNET • RATED AT 30 WATTS
- RESPONSE 20-14,000 CPS • SEAMLESS CONE • SPECIAL HEAVY-DUTY CONSTRUCTION

ONLY 14.95



Tweeter with baffle

Polyester resin treated tweeter edge



TWEETER BAFFLE


CONICAL STIFFENER

CROSSOVER NETWORK

Incorporating a full 21.5 oz. magnet of high-flux density Alnico 5, this new wide-range 12" PM high fidelity speaker is rated at 30 watts and is excellent for use with any hi-fi system. With proper baffling, frequency response is 20 to 14,000 cps. Special constructional features include a 1 1/2" voice coil; epoxy bonding of the voice coil to the seamless cone; completely dust-proof enclosed magnet structure; fibre-to-metal bonds made with heat under extreme pressure; heavy cast-metal frame; metal parts heavily cadmium-plated, with exposed surfaces covered with a handsome mar-resistant hammerloid finish. Voice coil impedance 8 ohms. Outside diameter 12 3/4", mounting diameter 11 1/2", depth 6 3/4". Color-coded 4-way binding-post terminals.

SK-137 Shpg. wt., 7 lbs. Net 14.95

NOW FROM LAFAYETTE
ADD-ON REVERBERATION



Works With Phono, TV
Radio or Tape Recorder

Converts Your
Living Room Sound
to that of Concert
Hall Grandeur


69.95

- Marvelous For Existing Monaural Systems
- Enriches Your Present Stereo Systems
- Adds A Delightful Dimension to Sound Without Effecting Fidelity
- Completely Self-Contained, Has Own Amplifier and Speaker

Changes the acoustic dimensions of your room. A self-contained reverberation speaker-and-amplifier with its own internal power supply, that hooks into any existing stereo or monophone component sound system, FM and AM radio, Tape Recorder, T.V. set, or Electric Organ. More than just a simple "echo device," the "Reverb-Control" takes part of the original signal from a speaker system and feeds this signal through a carefully tuned device which delays the sound for 1/30th of a second. This delayed sound blends with the original sound to add acoustic dimension to your room. Uses 8" Dual diameter speaker. Power output of amplifier 3 watts R.M.S. (will work excellently with systems having up to 60 watt amplifiers). 2 sets of inputs—high level and low level (left and right)—use only one input for monaural. Comes supplied with 2 cables, 15' each with standard phono plugs on one end. Power requirement 110V to 120V AC. Cabinet size 10x20x10 1/2" deep. Available in walnut and mahogany. Shpg. wt., 22 lbs. SK-204WX Walnut Finish Net 69.95 SK-205WX Mahogany Finish Net 69.95

SENSATIONAL SPEAKER SYSTEM

JENSEN speakers + UNIVERSAL
WOODCRAFTERS cabinets +
LAFAYETTE low prices



38.95

- Heavy 7-Ply Furniture Veneer Cabinets
- Fiberglass-loaded Cabinet for Better Bass Response
- Jensen 12" Woofer, 8" Midrange Driver, 3 1/2" Enclosed Tweeter

Now you can get unparalleled speaker performance at a low, low Lafayette price—the most outstanding value of its kind in the industry. The Uni-Voice hi-fi speaker system is a thrilling blend of fully integrated, unified 3-speaker systems engineered by Jensen with specially developed Jensen components, with cabinetry by Universal Woodcrafters. Contains special 12" woofer; 8" midrange driver independently pneumatically damped in its own hermetically enclosed acoustic surroundings, completely separated from woofer cavity; 3 1/2" fully enclosed, independently baffled tweeter. Woofer electric crossover at 600 cycles, midrange electric crossover at 2000 cycles. Impedance 8 ohms. Response: 35-18,000 cycles. MODEL UV-30. Bookshelf enclosure finished on 4 sides. Speaker grille completely framed with brass inlay. 24Wx14 1/4Hx13"D. SK-185WX Walnut finish. Shpg. wt. 32 lbs. Net 38.95


Lafayette presents

THE NEW ULTRA-LINEAR SK-128™ full range 8 inch
biaxial speaker with newly developed
tweeter baffle design.

19⁵⁰

- 20 TO 20,000 CPS (40 TO 16,000 CPS ± 3 DB) ■ HIGH EFFICIENCY
- HIGH EXCURSION WOOFER WITH UNIQUE "CONICAL STIFFENER"
- HANDLES HEAVY BASS PASSAGES WITHOUT "DOUBLING"

*Eccentric Tweeter Mounting & Unique Elliptical Baffle
Completely Eliminates Interaction Between Woofer & Tweeter*



The SK-128 combines the best features of a multiple speaker system in one compact and economical unit. It offers full, even coverage of the entire audible range, with no distortion or coloration to mar your listening pleasure. The specially treated woofer cone has a unique "Conical Stiffener" at the apex which, coupled with its high compliance, enables the cone to operate in a piston-like manner—delivering a clean, powerful bass response. The 2-inch tweeter has its own voice coil and magnetic field. Special treatment of cone and cone edge provides even distribution of the high frequencies, with no peaks or resonances. The unusual off-center mounting of the tweeter and its elliptical baffle minimizes interaction between tweeter and woofer and insures an overall response free of intermodulation distortion. Electrical crossover from the woofer cone to the tweeter unit is provided by a built-in network. An adjustable brilliance control permits matching of sound to room acoustics. Efficiency of the speaker is such that it will operate from any amplifier with an output of 1 watt or more. Installed in a bass-reflex type of enclosure, it performs outstandingly, and is recommended for all high-quality music systems—whether monaural or stereophonic. SPECIFICATIONS: Overall Response: 20-20,000 cps (40-16,000 cps ± 3 db). Free air Resonance: 45-65 cps. Impedance: 8 ohms. Power Rating: 20 watts Integrated Program Material. Crossover: 2,500 cps. Overall Diam. 8 3/4". Overall Depth: 5 1/2". Baffle cut-out: 7 1/2". Rugged, vibration-free speaker frame with color-coded screw-type terminals for quick, easy connection of amplifier leads. Shpg. wt., 5 lbs. SK-128 Full Range 8" Biaxial Speaker..... Net 19.50

LAFAYETTE MINI-DUCT BOOKSHELF ENCLOSURE
WITH SK-128 8" ULTRA-LINEAR SPEAKER

The perfect answer for those who demand realistic sound reproduction even where space is limited. Two of these systems are ideal for stereo. Shpg. wt., 28 lbs.

- | | |
|---|-----------|
| SY-343WX Speaker System in Walnut | Net 39.50 |
| SY-344WX Speaker System in Mahogany | Net 39.50 |
| SY-345WX Speaker System in Blonde | Net 39.50 |
| SY-346WX Speaker System in Oiled Walnut | Net 39.50 |
| SY-347WX Speaker System in Unfinished Birch | Net 37.50 |

SK-128 SPEAKER & MINI-DUCT FINISHED ON 4 SIDES

- | | |
|-------------------|-----------|
| SY-403WX MAHOGANY | NET 41.95 |
| SY-404WX WALNUT | NET 41.95 |




LAFAYETTE MINI-DUCT™ BOOKSHELF ENCLOSURE
WITH SK-212 3-WAY SPEAKER

A perfect match: The "Mini-Duct" enclosure and the remarkable Lafayette SK-212 3-way High Fidelity speaker. Reproduces the entire audio spectrum with a marvelous smoothness. Styled in attractive furniture finishes. Shpg. wt., 35 1/2 lbs.

- | | |
|---|-----------|
| SK-212 SPEAKER AND MINIDUCT ENCLOSURE FINISHED ON 3 SIDES | |
| SY-431WX UNFINISHED | Net 52.45 |
| SY-432WX MAHOGANY | Net 54.95 |
| SY-433WX WALNUT | Net 54.95 |
| SY-434WX OILED WALNUT | Net 54.95 |
| SY-435WX BLONDE | Net 54.95 |

SK-212 SPEAKER AND MINI-DUCT FINISHED ON ALL 4 SIDES

- | | |
|-------------------|-----------|
| SY-436WX MAHOGANY | Net 56.40 |
| SY-437WX WALNUT | Net 56.40 |




FAMOUS LAFAYETTE MINI-DUCT™ BOOKSHELF ENCLOSURE
WITH SK-130 8" WIDE-RANGE SPEAKER

As Low As 33.95

A combination that rivals the performance of much larger speaker systems. This fine enclosure assures optimum performance from the SK-130. Only 23" W x 11 1/2" H x 11 1/4" D—ideal for mounting in a bookcase or record shelf. Finished on 3 sides in a variety of fine furniture finishes. Shpg. wt., 27 lbs.

- | | |
|---|-----------|
| SK-130 SPEAKER & MINI-DUCT ENCLOSURE COMBINATIONS | |
| SY-415WX Unfinished | Net 33.95 |
| SY-416WX Mahogany | Net 35.95 |
| SY-417WX Walnut | Net 35.95 |
| SY-418WX Oiled Walnut | Net 35.95 |
| SY-419WX Blonde | Net 35.95 |

- | | |
|--|-----------|
| SK-130 SPEAKER & MINI-DUCT FINISHED ON 4 SIDES | |
| SY-420WX Mahogany | Net 36.95 |
| SY-421WX Walnut | Net 36.95 |



SK-130

YOUR ORDER IS SHIPPED AT THE CURRENT PRICE SO YOU BENEFIT FROM ANY PRICE REDUCTION

Lafayette Catalog No. 624 Page 29

THE FAMOUS LAFAYETTE ELIPTOFLEX




SK-58

FINISHED ON 4 SIDES

Adapts to any room arrangement. Place horizontally on shelves or vertically on the floor.

64.50 NO MONEY DOWN

PHENOMENAL ELIPTOFLEX PERFORMANCE



PERFORMANCE EXPLANATION

The loudspeaker is mounted on a baffle recessed in the cabinet shell with the front-plate extending partially across the front surface of the baffle forming ducts or tubes from the port openings to the outside air. The elliptical cutout changes the effective length of the duct across its area. This variation in path lengths provide an extremely smooth transition from duct to free air; broadens the frequency response and provide better transient response. A triangular shaped diffracting ring mounted on the front of the baffle board virtually eliminates undesirable cancellation effects normally produced by close coupling of front and rear cone radiation. This results in a "lens" effect, changing relative particle velocities and consequently, phase relationships so as to produce a smooth transition from front to rear radiation. Comparative laboratory and listening tests indicate that "Eliptoflex" performance is demonstratively superior throughout the audio spectrum.

Patents applied for in United States, England and Canada

ELIPTOFLEX® COMPLETE SPEAKER SYSTEM with ENCLOSURE

NOW IT IS POSSIBLE TO HAVE THE ADVANTAGES OF A HIGH EFFICIENCY 12" SPEAKER IN A BOOKSHELF SIZE ENCLOSURE.

SPECIALLY DESIGNED 12" COAXIAL SPEAKER WITH SHEEPSKIN CONE EDGE SUSPENSION AND 1 1/4 LB. MAGNET PROVIDE A RESPONSE FROM BELOW 30 TO 15,000 CPS.

ENCLOSURE BEAUTIFULLY FINISHED ON FOUR SIDES IN HAND RUBBED VENEERS.

The "Eliptoflex" is the result of an intensive research program whose 3-fold purpose was to:

Develop a speaker system that would meet space requirements of stereo.

Utilize the full advantages of efficient 12" speaker performance.

Provide optimum performance without use of large wattage expensive amplifiers.

The Results Were Remarkable . . . The Eliptoflex utilizes a unique elliptical port which broadens frequency response and provides better transient response. A specially engineered diffracting ring eliminates cancellation effects between front and rear radiation. These engineering advances are coupled with the famous Lafayette free edge SK-58 12" coaxial speaker 3" conetype tweeter, 1 1/4 lb. TSK-5 high flux density magnet and special 3/4" wide sheepskin cone-edge suspension and built-in crossover network level control.

"Eliptoflex" achieves a degree of natural smoothness, low-distortion and rich robust bass hitherto found only in large enclosure speaker systems or inefficient bookshelf speakers many times its price requiring high powered amplifiers. Due to its highly efficient design characteristics the "Eliptoflex" does not require costly high wattage amplification.

The "Eliptoflex" speaker system is beautifully finished on 4 sides in a variety of hardwood veneers for attractive room placement either horizontally or vertically. Dimensions are 14"Hx23-7/16"Wx13-5/16"D. Shpg. wt., 35 lbs.

SY-381WX "Eliptoflex" Speaker System Mahogany	Net 64.50
SY-382WX "Eliptoflex" Speaker System Walnut	Net 64.50
SY-383WX "Eliptoflex" Speaker System Blonde	Net 64.50
SY-384WX "Eliptoflex" Speaker System Oiled Walnut	Net 64.50
SY-392WX "Eliptoflex" Speaker System Unfinished furniture grade birch	Net 59.50

ELIPTOFLEX ENCLOSURE LESS SPEAKER—FINISHED ON 4 SIDES

CAB- 83WX "Eliptoflex" Enclosure—Mahogany	Net 36.50
CAB- 84WX "Eliptoflex" Enclosure—Walnut	Net 36.50
CAB- 85WX "Eliptoflex" Enclosure—Blonde	Net 36.50
CAB- 86WX "Eliptoflex" Enclosure—Oiled Walnut	Net 36.50
CAB-124WX "Eliptoflex" Enclosure—Unfinished Birch	Net 29.50

SPECIAL KIT VALUE Lafayette ELIPTOFLEX in KIT FORM

PRICED EXTRA LOW!
COMPARE FOR VALUE


- Easy To Assemble
- 3 Sides Ready To Finish For Horizontal Placement

- 3/4" Furniture Quality Birch
- Decorative Acoustic Grille
- Interior Acoustic Padding

21.50
NO MONEY DOWN

CK-14AWX Ready-To-Finish "Eliptoflex" Speaker Cabinet Kit in Birch	Net 21.50
CK-34WX Ready-to-finish Kit with Walnut veneer	Net 24.50

LAFAYETTE ELIPTOFLEX® BOOKSHELF ENCLOSURE WITH SK-180 10" TRIHELIX 3-WAY SPEAKER



66.50

An ideal combination of speaker and enclosure that furnishes optimum 3-way speaker performance. Eliptoflex enclosures are finished on all four sides for vertical or horizontal placement. Shpg. wt., 32 lbs.

SY-398WX Mahogany	Net 66.50
SY-399WX Walnut	Net 66.50
SY-400WX Blond	Net 66.50
SY-401WX Oiled Walnut	Net 66.50

VALUE COMBINATION! LAFAYETTE SK-211 CAVALIER 12" 3-WAY SPEAKER WITH 1 1/4 LB. MAGNET AND FAMOUS ELIPTOFLEX ENCLOSURE



74.50
NO MONEY DOWN

Get the most in both value and performance with these speaker/cabinet combinations. Lafayette's famous Eliptoflex bookshef enclosure, assures you of top performance for your SK-211 "Cavalier 12" speaker. Enclosures finished on all four sides for vertical or horizontal placement. Your choice of fine finishes. Size: 14Hx23 1/2 Wx 13-5/16 D. Shpg. wt., 34 lbs.


SY-410WX SK-211 & Eliptoflex in Mahogany	Net 74.50
SY-411WX SK-211 & Eliptoflex in Walnut	Net 74.50
SY-412WX SK-211 & Eliptoflex in Blonde	Net 74.50
SY-413WX SK-211 & Eliptoflex in Oiled Walnut	Net 74.50
SY-414WX SK-211 & Eliptoflex in Unfinished furniture grade birch	Net 67.50

FAMOUS LAFAYETTE ELIPTOFLEX ENCLOSURE AND SK-210 SOVEREIGN 12" 3-WAY SPEAKER WITH 2 1/4 LB. MAGNET

PERFORMANCE MATCHED—Lafayette's famous Eliptoflex bookshef enclosure matched with the exceptional SK-210 Sovereign 12" 3-way speaker. Finished on four sides in your choice of decorator finishes. Size: 14Hx23 1/2 Wx13 1/2 D. Shpg. wt., 39 lbs.

SY-405WX SK-210 & Eliptoflex in Mahogany	Net 82.50
SY-406WX SK-210 & Eliptoflex in Walnut	Net 82.50
SY-407WX SK-210 & Eliptoflex in Blonde	Net 82.50
SY-408WX SK-210 & Eliptoflex in Oiled Walnut	Net 82.50
SY-409WX SK-210 & Eliptoflex in Unfinished furniture grade birch	Net 75.50

82.50
NO MONEY DOWN



HI-FIDELITY WOOFERS



SK-67W*

SK-68

23.95

15.50

15" HI-FI WOOFER*

- 2 LB. ALNICO MAGNET
- 20 TO 5000 CYCLES—35 WATTS

This efficient 15" low frequency woofer incorporates many exclusive features. For original equipment or replacement, it provides highly efficient extended low-frequency response. Ideal for assembling 2- and 3-way speaker systems. Handles 35 watts of audio power. Frequency response ± 2 db 20 CPS to 1000 CPS, and ± 5 db from 20 CPS to 5,000 CPS with proper baffling. Voice coil dia. 2", impedance 8 ohms, 31.5 oz. Alnico V magnet. Finished in beautiful brown enamel. Cone is seamless type, permanently bound to voice coil. Has 4-way binding posts. Shpg. wt., 13 1/4 lbs. Cone Resonance 45 cycles

Net 23.95

12" HI-FI WOOFER

- 21.5 OZ. ALNICO V MAGNET—25 WATT

Provides efficient, extended low-frequency response of ± 5 db from 35 to 8000 CPS, and features 25 watts of power handling capacity. Perfect for high-fidelity installations or for modernization of older equipment. Ideal for assembling 2- and 3-way speaker systems at a budget price. Enclosed magnet structure—completely dust-proof. Compliance of outer cone and inner spider carefully calculated for best bass response. 21.5 oz. Alnico V magnet, 1 1/2" dia. voice coil, 8 ohm impedance. All exposed surfaces are finished in beautiful brown enamel. Has 4-Way binding posts. Cone Resonance 50 cycles. Shpg. wt., 8 lbs.

Net 15.50

NEW! 2- and 3-way L/C CROSSOVER NETWORK



NETWORK

- 4 CROSSOVER FREQUENCIES: 350, 700, 2000-3000, 5000 CYCLES
- 6 CROSSOVER COMBINATIONS
- 2 OR 3 WAY CROSSOVER
- ATTRACTIVE METAL CASE
- BUILT-IN BRILLIANCE & PRESENT CONTROLS

This versatile unit can be used either as a 2-way or 3-way 6 db per octave network. You can use this network for a 2-way system now, easily and quickly convert to 3-way later. Six crossover combinations are available—2-way crossover with 2000-3000 cycle or 5000 cycle crossover, and 3-way with crossover frequencies of 350 and 5000, 350 and 2000-3000, 700 and 2000-3000 or 700 and 5000 cycles—a total of four different crossover frequencies! Suitable for 8-16 ohm speakers. The network is housed in an attractive metal case, suitable for mounting inside enclosure or leaving out in the open. Two level controls—Brilliance and Presence controls—are mounted on the front panel. If desired, these level controls may be removed, along with the beautiful gleaming copper escutcheon plate, for external mounting; controls are wired with 3-foot long leads. High quality components are used for long life and top performance. Shpg. wt., 6 lbs.

LN-5 Lafayette L/C Crossover Net 14.95

2 OR 3 WAY CROSSOVER NETWORK



- 4 CROSSOVER FREQUENCIES
- L PAD BALANCE CONTROLS
- EASY TO USE
- IMPEDANCE 16-OHMS

The LN-7 Crossover Network combines quality performance, beauty and versatility at an unbeatable price. It can be used in a two-way system by crossing over at 500 cps or 3300 cps, and in a three-way system by utilizing the two simultaneously. The change from a two-way to a 3-way 6 db per octave network may be accomplished easily. Two level balance controls. Size 5 1/2"x2 1/2"x2 5/8". Shpg. wt., 2 1/2 lbs.

Net 8.75

HIGH FREQUENCY TWEETER WITH ACOUSTIC LENS

DIRECT IMPORTATION MAKES THIS PRICE POSSIBLE!
• FREQUENCY RESPONSE FROM 2000 CPS TO BEYOND AUDIBILITY
• LOUVERED ACOUSTIC LENS FOR UNIFORM SOUND DISPERSION
• HANDLES 25 WATTS OF POWER
• PRICED EXCEPTIONALLY LOW

New high frequency tweeter featuring a louvered acoustic lens for uniform sound dispersion and capable of handling up to 25 watts of distortion-free power. The directional tendency of high frequency notes is overcome by the natural wide dispersion angle of the short horn and acoustic lens which disperses and radiates the high notes smoothly throughout the entire listening area. The lens is detachable for panel mounting, with a separate base for the tweeter furnished for external mounting where desired. Aluminum voice coil has 16 ohms impedance. Size 4 1/4" long x 3" diameter, lens extends 2 1/2". Requires a crossover network, preferably one with a level control, such as the LN-2. With full instructions. Shpg. wt., 5 lbs.

HW-7 Net 14.95

**WORLD-RENOWNED
LAFAYETTE SK-115A 3-WAY 15"
HIGH FIDELITY SPEAKER**

Custom Built in England
to Lafayette's Rigid
Specifications



79⁵⁰

**MONEY BACK
GUARANTEE**

YOU BE THE JUDGE

Try the SK-115A for 30 days.
If not completely satisfied,
return it for full refund.
* 1 Year Service Guarantee

**NO MONEY
DOWN**

- Massive 5 lb. Magloy Magnet—The Most Efficient Magnetic Material Available
- Free-Edged Cone Suspension
- 3 Inch Long Main Voice Coil
- 12 DB/Octave Crossover Network with High Frequency Level Control
- Precision Pressure Driven Horn Loaded Tweeter with Aluminum Diaphragm & Coil

SUPERB PERFORMANCE—The finest British craftsmanship and advanced acoustic design, combined by Lafayette to bring you this outstanding 3-way 15" speaker. Designed and constructed to the most exacting laboratory standards, the SK-115A features a patented concentric twin gap magnetic system with a massive 5 lb. Magloy magnet. Woofer, mid-range radiator and speaker are axially mounted to achieve unexcelled, efficient, wide-range speaker performance. The woofer section with a cone resonance of 25 cps is vacuum constructed by an exclusive process. The cone rolls and edges are bombarded with minute particles of specially-blended plastic materials, to form a virtually free-edged cone suspension that eliminates standing waves and surround resonances. An automatic mechanical crossover separates bass and mid-range frequencies at 2,000 cps to a high stability mid-range radiator. A 12 db per octave LC crossover network provides smooth transition at 5,000 cps from mid-range to a precision pressure driven horn loaded tweeter employing an aluminum diaphragm and coil in a self aligning assembly with air chamber and phase equalizer. This crossover is provided with a high frequency level control for matching of sound to room acoustics and individual listening tastes. Dimensions: 8 3/4" Overall depth; 15 3/8" diam. Shpg. wt., 40 lbs.

SK-115AWX Net 79.50

*Repairs which become necessary due to manufacturing defects will be made by Lafayette at no charge during the Guarantee period.

COMPARE THESE SPECIFICATIONS

- Cone Resonance: 25 cps. • Overall Frequency Response: 20-20,000 cps. • Magnet: 5 lb. Magloy Permanent Magnet • Magnetic Flux Density: 306,000 Maxwells
- Crossover: 12db/Octave Twin 1/2 Section LC Network
- Power Capacity: 50-watts • Woofer Voice Coil Diameter: 3 Inches • Tweeter Voice Coil Diameter: 1 inch
- Impedance: 16 ohms

LAFAYETTE "MINUETTE" HIGH-FIDELITY SPEAKER SYSTEM

Room Filling Music
Everywhere in Your Home!



TWO FOR STEREO 23⁵⁰ SINGLY 12.50

- Shelf Size — 8 1/4 x 15 3/4 x 5 7/8" H
- Use Two For Stereo—Perfect For the Small Apartment or Listening Area
- Genuine Walnut Finish on 4 Sides
- Complete with 6' Extension Cable and Phone Plug

An exceptional speaker value... the Lafayette "Minuette" Hi-Fi Speaker System will bring music to any room in your home... and for a remarkably low cost. Designed for use where space is at a premium... ideal for the small apartment or listening area. Expand your stereo system to other areas of your home... easily used in the den, kitchen, patio or bedroom. Employs a specially designed 5x7" speaker in a rear loaded reflex type enclosure. Provides an exceptionally fine musical quality yet measures only 8 1/4 x 15 3/4 x 5 7/8" — small enough to fit anywhere. Superb Walnut finish on 4 sides allows placing speaker horizontally or vertically. Frequency Response 100-12,000 cps. Impedance 8 ohms. Rated at 10 watts. Supplied with 6 ft. of extension cable and phone plug. Shpg. wt., 5 1/2 lbs.

SK-181 Net 12.50

Save — Buy two for stereo. Shpg. wt., 11 lbs. Net 23.50

**THE WIDELY ACCLAIMED LAFAYETTE
SK-58 12" COAXIAL SPEAKER**
Now Offered Exclusively By Lafayette At
Tremendous Savings


**SUPERB PERFORMANCE GUARANTEED
—OR YOUR MONEY BACK!**

**THE WORLD-RENOWNED
ORIGINAL LAFAYETTE SK-58[®]**

- RESPONSE 30-15,000 CPS
- SHEEPSKIN "FREE EDGE" CONE MOUNTING
- 1 1/4 LB MAGNET WEIGHT
- 3" COAXIALLY MOUNTED TWEETER
- BUILT-IN LC NETWORK
- RATED AT 20 WATTS CONTINUOUS POWER

29.50

**NO MONEY
DOWN**



Lafayette's exclusive 12" coaxial is a precision-made high fidelity loudspeaker, universally acclaimed by music lovers, hi-fi enthusiasts and professional experts alike as the greatest performance-value on the hi-fi market. It provides a truly faithful reproduction of sound without any "coloration" or distortion, its excellence being responsible for its use in innumerable high fidelity music systems today. The SK-58 incorporates such features as heavy, high flux density TSK-5 magnets for high efficiency; 3/4" wide sheepskin cone-edge suspension and special composition fibre cone material, specially treated for ultra-linear, distortion-free response; heavy rugged cast metal frame for freedom from resonances and for greater rigidity.

The coaxially-mounted 3" cone-type tweeter has a bell shaped mounting for maximum dispersion of high frequencies with no back radiation. With the built-in 3000 cps crossover network it contributes its share to the smooth delivery of the overall wide range response of 30-15,000 cps. Woofer resonance in free air is 40 cps. Speaker power handling capacity is 20 watts continuous sine wave, 35 watts peak program material. Impedance of the voice coil is 8 ohms, connections being made to chrome-plated screw terminals. Finished in gray-brown opalescent enamel, the speaker is supplied complete with "brilliance" level control. Shpg. wt., 11 lbs. SK-58W 12" COAXIAL SPEAKER Net 29.50

THE LAFAYETTE TRIHELIX[®]

Recreates The Entire Audio Spectrum With Concert Hall Faithfulness—The Lafayette "Trihelix" represents a major breakthrough in three way speaker design. Fresh engineering concepts have resulted in a single 10-inch speaker designed expressly for use in bookshelf size enclosures, that delivers a quality of performance with the unmistakable feel, presence and clarity of a 3-way speaker system. The "Trihelix" is in effect a complete three-way high-fidelity speaker system, with three mechanically and electronically independent speakers mounted within a single 10-inch frame. Although they are individual units the 2-inch tweeter and 5-inch midrange speakers have been especially designed to compliment the woofer. Special treatment of the cones and cone edges with polyester resins provides an even distribution of mid and high frequencies without peaks or resonances. To minimize interaction between the three cones both the midrange and tweeter units are mounted eccentrically or off center in relation to the woofer. In addition the midrange and tweeter are completely enclosed by a specially designed baffle. These unusual design features result in effectively eliminating intermodulation distortion due to interaction between woofer, midrange and tweeter cones—a common fault in conventionally designed 3-way speakers.

The specially treated woofer cone employs a revolutionary "conical stiffener" located at the apex of the cone in order to stiffen the diaphragm and eliminate "breakup," thus providing a true piston action. This carefully designed cone-stiffening procedure, in addition to its very high compliance, enables the woofer to deliver a smooth, crisp, solid bass that balances naturally against a crystal clear midrange and natural treble. A built-in electrical crossover network with crossover points at 1500 cps and 5000 cps, allows each speaker to reproduce its portion of the audio range smoothly and efficiently. An adjustable brilliance control permits matching of sound to room acoustics. SPECIFICATIONS: Overall Response 20-20,000 cps (30 to 18,000 cps ± 3 db). Free Air Resonance 35-55 cps. Impedance 16 ohms. Power Rating: 20 watts Average Program Material. Crossover Points: 1500 & 5000 cps. Overall Diam: 10". Overall Depth: 7". Baffle cut-out: 8 7/8". Screw type terminals are color coded for quick easy connection of amplifier leads. Shpg. wt., 8 lbs.


SK-180 10" Lafayette "Trihelix" Net 32.50
SB-62W Adaptor Board To Fit SK-180 To 12" Cutout Net .89

32.50

NO MONEY DOWN


**3 Completely Independent
Speakers With 3 Separate
Voice Coils in a Single
Compact Unit**

- Frequency Response 20 to 20,000 cps (30-18,000 cps ± 3 db)
- Revolutionary "Conical Stiffener"
- Eccentric Baffle Mounting of Midrange & Tweeter Eliminates Interaction Between Speaker Cones
- Built-in Crossover Network and Brilliance Control
- Extremely Efficient
- High Excursion Woofer
- Ideal For Stereo



**3-WAY CROSSOVER
NETWORK**

**MIDRANGE &
TWEETER
BAFFLES**



**CONICAL
STIFFENER**

**THE LAFAYETTE CAVALIER 12"
High-Fidelity 3-Way Speaker**

- 1 1/4 lb. High-Efficiency "Alcomax" Magnet
- Special Design For Distortionless Performance From 30-20,000 cps.
- 1 3/4" Voice Coil
- Handles 25 Watts of Power
- Non-Resonant Rigid Frame Construction
- Crossover Complete With Brilliance Control

39⁹⁵

NO MONEY DOWN




AN OUTSTANDING PERFORMANCE VALUE . . .

This new Lafayette Cavalier 12 integrates the finest acoustic design with precise British craftsmanship. It's advanced 3-way design with woofer, mid-range radiator and tweeter axially mounted within a specially engineered non-resonant rigid frame is capable of faithfully reproducing the complete audio spectrum from 30-20,000 cps. The most violent crescendos are easily handled without tone coloration or distortion, with superior bass response achieved even at the lowest volumes. Construction features include a 1 1/4 lb. high efficiency "Alcomax" magnet, an especially engineered "Rigidflex" cone-bonding and cone edge treatment process for a virtually free-edged cone suspension, 1 3/4 inch voice coil

plus a stiff-coned midrange radiator with a 2,000 cps mechanical crossover. A 5,000 cps LC crossover equipped with brilliance control channels high frequencies into a compression-driver tweeter, incorporating a rigid die cast flared hyperelliptical horn, a 1" diameter aluminum voice coil and diaphragm in a self-aligning assembly with air chamber and phase equalizer. SPECIFICATIONS: Frequency Response: 30-20,000 cps, Fundamental Cone Resonance: 35 cps, Power Handling Capability: 25 watts, Magnet: 1 1/4" lb. "Alcomax," Voice Coil: 1 3/4" diameter; Crossover: Mechanical at 2,000 cps. Electrical at 5,000 cps; Impedance: 16 ohms. Shpg. wt., 10 lbs.

SK-211 Lafayette Cavalier 12 Net 39.95



BUILD-YOUR-OWN SPEAKER ENCLOSURES

EASY-TO-ASSEMBLE HI-FI ENCLOSURE KITS and COMPLETE SPEAKER SYSTEMS

LAFAYETTE UNIVERSAL HI-FI BASS REFLEX ENCLOSURE KITS

Entire Cabinet 3/4" Plywood
Heavier Construction—Fully-Cured 3/4" Plywood
Smoothly Sanded Ready for a Fine Finish
Picture Frame Moulding Built-In
Tweeter adapter
Pre-Cut for Most Tweeters Or No Tweeter, If Desired
Pre-fab 3/4" Baffle for any Lafayette And Almost Any Other Speaker System
For 8 1/2", 8" or 5" Mid-range Or No Mid-range, If Desired
Pre-Cut for 15" Woofer With Adapter for 12"
Acoustic Grille of Decorative Plastic
Precision Design—Parts Fit Air-tight
Supplied With Interior Acoustic Padding
Carefully Designed Bass Reflex Port

HIGHBOY
LOWBOY

AT TREMENDOUS SAVINGS TO YOU!

A LAFAYETTE BEST BUY AT ONLY 29.95

NO MONEY DOWN

- EASIEST TO ASSEMBLE—ALL YOU NEED IS A SCREWDRIVER!
- 3/4" WHITE BIRCH
- PRECISION-CUT—FITS TOGETHER SMOOTHLY
- PERFECT FOR SINGLE WIDE RANGE, 2-WAY OR 3-WAY SPEAKER SYSTEMS
- HIGHBOY OR LOWBOY STYLE

All pieces of these carefully designed bass reflex high fidelity speaker enclosures are accurately precut of 3/4" Plywood to fit snugly together and eliminate spurious resonances. Surface is white birch veneer. Front panels have picture-frame moulding and plastic acoustic grilles to blend with any finish and room decor. Tapered offset legs are protected by brass ferrules. Acoustic lining material prevents reverberation and cabinet resonance. Cutouts are provided for 15" speaker plus adapter for 12" 8 1/2" or 8" midrange plus adapter for 5" and blank wood block if no midrange speaker is used; cutout with adapter horn tweeters plus blank block if no tweeter used. Thus, any single wide-range 12" or 15" speaker may be used, or any Lafayette 2- or 3-way speaker system, or almost any other combination of speakers. Kits are supplied unfinished, smoothly sanded and ready for finishing. The lowboy-style cabinet dimensions are (less legs) 28 7/8x23 1/2x16 3/4" D; legs are 7" high. Highboy has same dimensions with height and width interchanged. Instructions, all parts, hardware, and grille are included. Shpg. wt., 54 lbs.

CK-10WX Unfinished Highboy Enclosure Kit Net 29.95
CK-11WX Unfinished Lowboy Enclosure Kit Net 29.95

LAFAYETTE OILED WALNUT FINISHING KIT

AT TREMENDOUS SAVINGS TO YOU!



2.69

Use this professional walnut oiling kit to achieve a beautiful oil finish on all unfinished walnut furniture. Materials are identical to those used by professional finishers; kit contains walnut oiling mixture, walnut paste wax, sandpaper and instructions. Shpg. wt., 2 lbs.

MS-592 Net 2.69

LAFAYETTE HI-FI SPEAKERS AT POCKETBOOK PRICES

SK-183 11.95
SK-138* 5.25

12" THREE-WAY HI-FI SPEAKER

This new 3-way speaker answers the needs of many hi-fi enthusiasts. Featuring an 8 oz. dual-diameter magnet it has a frequency response of 35-17,500 cps. The elliptical tweeter gives improved sound dispersion over cylindrical types. Voice coil: diam-1 1/4", Impedance-8 Ω. Plated steel frame finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 6 1/2 lbs.

SK-183 Net 11.95

6" MID-RANGE SPEAKER

An excellent mid-range direct-radiator type speaker for installation in 3-way or 4-way speaker systems. Gives clean, distortion-free reproduction at rated power. Features closed back to eliminate interaction with sound waves generated from other speakers in the same enclosure. Rated power handling capacity: 10 watts. Frequency response from 700 to 7000 cps. Magnet weight: 3.16 oz. Voice coil impedance: 8 ohms. Plated steel frame finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 3 lbs.

SK-138* Net 5.25

SK-106 4.95
SK-93W* 8.75

LAFAYETTE 8" EXTENDED RANGE SPEAKER

- 45 to 13,000 cps
- SKIVER ROLLED CONE FOR SMOOTH RESPONSE
- 3.16 OZ. NEW TYPE MAGNET

Here is a price buster for the budget-wise hi-fi music lover. This is an extended range domestic speaker whose high sensitivity is achieved through a new hi-efficiency magnetic circuit. Ideally suited for medium and low level monaural or stereo reproduction. It has a 1" voice coil with 8 ohms impedance and will handle musical peaks of 10 watts. Size: O.D. 8 3/4"; Mtg. hole dimensions 7 1/4"; 3 1/2" deep; Brown enamel over heavily plated steel. 4-way binding posts. Shpg. wt., 2 lbs.

SK-106 Net 4.95

12" COAXIAL HI-FI SPEAKER

12" Alnico V PM with 1" voice coil and heavy one-piece cone. Specially designed 3" Alnico V PM tweeter completes this combination speaker. Range 40 to 15,000 cps. Built-in high pass filter. Power rating: 12 watts. 6.8 oz. Alnico V magnet. Impedance 8 ohms. Shpg. wt., 8 lbs.

SK-93W* Net 8.75

SK-69 6.25
SK-164 10.95

8" HI-FI WIDE RANGE SPEAKER

50-13,000 CPS

Answers the need for a good quality but moderately priced speaker with a range of 50-13,000 cycles. An extremely smooth single cone reproducer — ideally suited for Hi-Fi systems. Excellent for limited space—good overall balance—power handling capacity: 10 watts—6.8 oz. Alnico V magnet—frequency response: 50-13,000 CPS when properly baffled. Rim treatment on cone minimizes possibility of diaphragm distortion. Voice coil impedance: 8 ohms. Cone Resonance 85 cycles. Plated steel frame finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 4 lbs.

SK-69 Net 6.25

LAFAYETTE 8" WOOFER

- Rated 20 watts • Free edge cone
- 14.7 oz. alnico V magnet
- High Compliance • 35 to 7500 cps

Ideal for 2 or 3 way systems where space is at a premium, this 8" woofer provides coverage from 35 to 7500 cps. The 14.7 oz. magnet is extraordinarily heavy for this size speaker insuring the efficiency needed for good clean response. Other features include free edge, high compliance cone, 20 watt power dissipation, voice coil dust cover. Cone resonance 50 cycles, 8 ohm V.C. Has 4-way binding posts. Shpg. wt., 4 1/2 lbs.

SK-164 Net 10.95

8" MID-RANGE SPEAKER


Ideal for use with tweeter and crossover networks to make up a 2- or 3-way system. This 8" mid-range speaker is capable of producing undistorted response down to 350 cps, the crossover frequency. Back is enclosed. Power handling capacity: 25 watts. Frequency response 350-13,500 cycles. Recommended to crossover at 5000 cycles to a tweeter. Cone resonance 150 cycles. Impedance: 8 ohms. Plated steel framed finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 4 lbs.

SK-74 Net 6.50

NEW! LAFAYETTE 8" 3-WAY HI-FI SPEAKER

MADE IN ENGLAND TO OUR SPECS!

For Stereophonic and Monophonic Systems



- Frequency Range: 40-20,000 cps
- Magnet System: 1 lb.
- Voice Coil: Aluminum
- Impedance 16 Ohms
- Power Handling Capacity: 20 Watts

PAY LESS FOR HIGHER QUALITY-PERFORMANCE

24.50

NO MONEY DOWN

- 3-Concentric Radiators • Unique Wide-Angle Compression Lens Tweeter
- Special "Rigidflex" Free Edge Woofer Cone • Built-in Brilliance Control • Die-Cast Frame

The Lafayette SK-213 has been specially designed for us in England to reproduce sound with true fidelity without compromise. It is a complete 3-way system, composed of 3 concentric radiators. The "Rigidflex" bass and midrange radiators accurately reproduce frequencies of from 40 to 5,000 cps. The new wide-angle compressor lens tweeter extends the frequency range from 5,000 on up to 20,000 cycles. Here is a speaker capable of a standard of performance previously associated with much larger and more elaborate loudspeaker equipment. Deluxe features such as an aluminum voice coil, heavy 1 lb ceramic magnet system and rigid nonresonant die-cast frame demonstrate the unique mating of Lafayette custom specifications with quality English craftsmanship. Small size makes it an ideal choice for mounting in the famous Lafayette "Mini-duct" bookshelf enclosure. Use it in pairs for finer stereo reproduction anywhere in your home. A built-in bass-treble attenuator makes it possible to "customize" the SK-213's sound to your individual requirements. Baffle Hole dia., 7"; Front to back dimension, 3 3/4".

SK-213 Shpg. wt., 6 lbs. Net 24.50
SK-213 3-WAY SYSTEM with MATCHING "MINI-DUCT" ENCLOSURES FINISHED ON ALL 4-SIDES
SY-438WX Mahogany Net 46.95
SY-439WX Walnut Net 46.95

LAFAYETTE'S Amazing New! MINI-DUCT

A universal ducted-port bookshelf enclosure engineered for use with 1, 2 or 3-way speaker systems.

SOLIDLY CONSTRUCTED OF 3/4" WOODS START WITH A SINGLE SPEAKER AND BUILD INTO A 2- OR 3-WAY SYSTEM LATER ACOUSTICALLY LINED THROUGHOUT AVAILABLE IN A VARIETY OF FINISHES

23.50
NO MONEY DOWN



Mounting boards accept all types of tweeters

MINI-DUCT BOOKSHELF ENCLOSURE

33.25
NO MONEY DOWN

SK-98

Now limited space need not necessarily mean limited sound. The Lafayette Mini-Duct is acoustically designed to achieve smooth, distortion-free reproduction with a remarkably full, clean extended bass response that gives no indication as to its small size. Reducing boards are supplied so that the Mini-Duct will accept an 8" Woofer, 6" Mid-Range and a variety of tweeters. This versatility makes it possible to start with an 8" speaker and eventually build into a 2-way or 3-way speaker system. Solidly constructed of 3/4" woods the Mini-Duct is beautifully finished in a variety of fine veneers on 3 sides. Designed for attractive placement anywhere in your home with dimensions 23Wx11 1/2Hx11 1/4"D. Shpg. wt., 23 3/4 lbs.

CAB-47WX MINI-DUCT IN WALNUT	Net 23.50
CAB-48WX MINI-DUCT IN MAHOGANY	Net 23.50
CAB-49WX MINI-DUCT IN BLDNDE	Net 23.50
CAB-50WX MINI-DUCT IN OILED WALNUT	Net 23.50
CAB-51WX MINI-DUCT UNFINISHED BIRCH	Net 21.50
Mini-Duct Enclosure finished on 4 sides for attractive horizontal or vertical placement. Choice of mahogany or walnut.	
CAB-105WX Mahogany	Net 24.95
CAB-106WX Walnut	Net 24.95

SPEAKER AND ENCLOSURE COMBINATIONS

A PERFECT COMBINATION: The "Mini-Duct" enclosure and the famous Lafayette SK-98 8" mechanical 2-way speaker with patented dual cone construction. This speaker combined with the Lafayette "Mini-Duct" enclosure will give the same wide-range frequency response (40-16,000 cps) normally found only in the coaxial speakers or multiple speaker systems. Shpg. wt., 29 1/2 lbs.



COMBINATION UNFINISHED "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER SY-348WX	Net 31.25
COMBINATION MAHOGANY "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER SY-349WX	Net 33.25
COMBINATION WALNUT "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER SY-350WX	Net 33.25
COMBINATION OILED WALNUT "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER SY-351WX	Net 33.25
COMBINATION BLONDE "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER SY-352WX	Net 33.25
SK-98 SPEAKER AND MINI-DUCT FINISHED ON 4 SIDES	
SY-377WX MAHOGANY	Net 34.25
SY-378WX WALNUT	Net 34.25

Decorator Inspired!!

NEW LAFAYETTE HI-FI COMPONENT SHELF/CONSOLE

Group your Components Into A Distinctive, Custom Home Entertainment Center.



OILED WALNUT FINISH. **52.95**
NO MONEY DOWN
UNFINISHED. ONLY **28.95**



- ROOM FOR ALL YOUR COMPONENTS.
- STURDY 3/4" WOOD NON-WARP CONSTRUCTION
- HOLDS OVER 150 RECORDS
- AN ATTRACTIVE ADDITION TO ANY HOME - PLACE ALONG A WALL OR USE AS A ROOM-DIVIDER.

As functional as it is beautiful, this new Lafayette Shelf Console combines the beauty and compact all-in-one convenience of a console with the versatility of a shelf arrangement: The ideal answer to your Hi-Fi Stereo component placement problems—measures 66 1/2" long, yet holds over 150 records with more than enough room for your amplifier, turntable or record changer, tape deck and stereo speakers. Available in both finished and unfinished versions. Both feature 3/4" warp-proof construction. Top shelf measures 11x31 1/2x16"D. Lower shelf is 15 1/4x16Dx3 1/2"W and to protect your records contains a veneered rear panel, finished on both sides to allow placement of the unit as a room divider. Speaker compartments are 27x16Dx14 3/4"W—Large enough to accept virtually all of today's popular bookshelf size units and are spaced far enough apart to provide proper separation for stereo. Overall dimensions: 66 1/2x16Dx33 3/4"H including 5" legs. Shipped knocked down—Assembles in minutes. Shpg. wt., 65 lbs.
CK-37WX Oiled Walnut Finish Net 52.95
CK-36WX Unfinished Chip Board Net 28.95

NEW! LAFAYETTE RECORD STORAGE CABINETS



IN KIT OR ASSEMBLED FORM

... TO COMPLEMENT ANY ROOM OR SETTING.

- ROOM FOR OVER 300 RECORDS
- QUALITY 3/4" WOOD WARP-PROOF CONSTRUCTION

As Low as **29.50** NO MONEY DOWN

Tasteful, functional styling at its best—you'll be proud to add this distinctive record storage cabinet to your present room arrangement. The double tier design equipped with dividers easily accommodates over 300 records in their jackets. Solid 3/4" wood warp-proof construction. Available in two basic styles, both identical in size and design. One with easy-glide sliding doors and the other without doors. In addition, the cabinet less doors is available in easy-to-assemble Kit form of ready to finish birch veneer (all that's needed is an evening of your time and a simple screwdriver). Size: 16Dx30Wx33 3/4"H overall including 5" legs. Each shelf is 13"H.

IN EASY TO BUILD KIT FORM. Shpg. wt., 55 lbs.
CK-38WX without sliding doors (Unfinished Walnut) Net 34.95
CK-39WX without sliding doors (Unfinished Birch) Net 29.50
COMPLETELY ASSEMBLED. Shpg. wt., 55 lbs.
CAB-149WX without sliding doors (Finished in Oiled Walnut) Net 44.95
CAB-150WX without sliding doors (Unfinished Birch) Net 34.95
CAB-147WX with sliding doors (Finished in Oiled Walnut) Net 52.95
CAB-148WX with sliding doors (Unfinished Birch) Net 41.95

NEW! LAFAYETTE CUSTOM CRAFTED EQUIPMENT CABINET

BEAUTIFUL CABINETRY DESIGNED TO ENCLOSE YOUR COMPONENTS.




As Low as **42.50** NO MONEY DOWN

- Available In A Variety Of Fine Finishes.
- Rigid 3/4" Wood Warp-Proof Construction
- "Component Engineered" To Provide Adequate Circulation For Your Equipment

A magnificent example of contemporary furniture design—it's slender, graceful styling is sure to win approval in virtually every fine music room/living room arrangement. Features rigid 3/4" wood warp-proof construction with two adjustable center shelves to accommodate virtually any amplifier and tuner. The bottom section is equipped with a pull out drawer to provide easy access to your record changer. Proper circulation

of air around components is maintained by use of a perforated rear panel. Precision fitted swing-out front doors are equipped with magnetic latches. Size: 33 1/2"H overall (including 5" legs) x 18Dx20"W.
CAB-151WX Oiled Walnut Net 52.50
CAB-152WX Walnut Net 52.50
CAB-153WX Mahogany Net 52.50
CAB-154WX Unfinished Birch Net 42.50


COMPLETE all-in-one STEREO CABINETS by Casard



Your Choice of Contemporary, French Provincial or Italian Provincial Styling
No Money Down **88.95**

- Ample Space For Your Components including Stereo Speakers
- Luxurious Hand Rubbed Veneers
- Contains Two Sealed Bass-Reflex Ducted-Port Enclosures
- Your choice of Contemporary, French Provincial or Italian Provincial Styling

Here's period styling and furniture craftsmanship in the old world tradition. And, at Lafayette's low, low price these new all-in-one stereo cabinets represent a superb value. Hand crafted in luxurious 3/4" woods and veneers. Cabinets have been acoustically designed to showcase your component stereo systems to its best advantage. Enclosure is structurally reinforced to eliminate cabinet resonance. Speaker sections are acoustically insulated with fiber glass and utilize a sealed, bass-reflex, ducted port construction designed to accept either an 8" or 12" full-range speaker or a two or 3 way speaker system. Speaker enclosure section measures 17x13 1/2x15 1/2". The center or component section is protected by two sliding front panels and features a removable shelf. Lower compartment contains a pull-out mounting base which will accept a turntable or record changer (mounting base requirements are 3" below and 6 1/2" above mounting board). Upper compartment provides ample room for a tuner-amplifier combination (receiver) or a separate tuner and amplifier. Compartments measure: Upper—8 1/2x17 1/4x15 1/2"D; Lower—9 3/4x17 1/4x15 1/2". Available in three superb styles—Contemporary, in your choice of fine Oiled Walnut or Mahogany finishes plus Italian Provincial and French Provincial, both finished in Fruitwood. Special plastic cane grill cloth is matched to each style and finish. Overall Size: 48x18x28"H. Shpg. wt., 90 lbs.



(A) CONTEMPORARY STYLE	
CAB-143WX Oiled Walnut	Net 88.95
CAB-144WX Mahogany	Net 88.95
(B) FRENCH PROVINCIAL	
CAB-146WX Fruitwood	Net 88.95
ITALIAN PROVINCIAL STYLE (Not Illustrated)	
CAB-145WX Fruitwood	Net 88.95

DIAMOND STYLI AT LOWEST PRICES ANYWHERE

LAFAYETTE DIAMOND and DIAMOND-SAPPHIRE STYLI

MADE FOR LAFAYETTE BY THE FOREMOST AMERICAN MANUFACTURERS

KEY TO POINT CODES HOW TO ORDER

The symbols in the column headed "PT SIZE" are explained in the table below.

LP = SINGLE 1 MIL MICRO-GROOVE FOR 33 1/3 AND 45 RPM

COMB = DUAL 1 MIL DIAMOND AND 3 MIL SAPPHIRE

Identify your needle by cartridge number and illustration and order by stock no. Note that all needles listed here are for monaural cartridges.

ALL DIAMOND STYLI ARE NOT ALIKE
MADE FROM WHOLE DIAMONDS • PRECISION GROUND AND POLISHED • VERTICALLY AND EDGEWISE GRAIN ORIENTED • SHADOWGRAPHED




Each Lafayette's diamond stylus is made from individual diamond, properly oriented and ground to close tolerance; shadowgraph tested to give you less wear per play and long service life.

The synthetic sapphire used in these styli are of the same fine quality used in precision watch bearings.

FULL 1 YEAR REPLACEMENT GUARANTEE AGAINST DEFECTS IN WORKMANSHIP AND MATERIAL ON ALL DIAMOND STYLI

1.69

ANY DIAMOND or DIAMOND-SAPPHIRE NEEDLE IN THIS LISTING



DIAMOND NEEDLES

Stock No.	Size Pt.	Fig.	Cartridge	REPLACES JENSEN NO.	Stock No.	Size Pt.	Fig.	Cartridge	REPLACES JENSEN NO.	Stock No.	Size Pt.	Fig.	Cartridge	REPLACES JENSEN NO.										
FOR ADMIRAL CARTRIDGES																								
PS-16L	LP	1	409A11, 409A300, 98A54-1	JPS-30LPD	PS-35L	LP	54	560176, 560180	CRA-55LPD	PS-35L	LP	53	TO-200, TO-222, TO-284, or TO-400 series, RA284, DT60 series.	CRA-55LPD										
PS-16L	COMB	6	409B21	JPS-35SD	PS-70L	COMB	51	560161	S-66SD	PS-69L	LP	38	TX88, A	CRA-56LPD										
PS-17L	LP	7	409A30	A81LPD	FOR PHILCO CARTRIDGES																			
FOR ASTATIC CARTRIDGES																								
PS-20L	LP	3	AC Series, 40T, 41T, 40-1, 41-1, 42-1, 90T series, 10-L-3, 11L-3	A-75LPD	PS-56L	COMB	43	45-9612, 76-4649, 425-0016	PH-13SD	PS-56L	COMB	43	45-0009, 425-0011, 425-0014	PH-13SD										
PS-23L	LP	12	408	M-70LPD	FOR PERPETUUM EBNER CARTRIDGES																			
PS-25L	COMB	14	GCD, 409, 55-T, 55TJ, 55TM	A-71SD	PS-64L	COMB	47	P12/RG	RX550SD	PS-16L	COMB	6	WC10, WC10D, PC2 series, PC3 series, PC4 series, PC5 series	JPS-35SD										
PS-23L	LP	12	410	M-70LPD	PS-65L	COMB	48	PE-8, PE10	RX551SD	PS-10L	LP	1	P-72, P-73, P-73R, P-75, P-76, P-77, P-80, W-21, W-21AR, W-22A, WC-24, WC-25 Series	JPS-30LPD										
PS-17L	LP	7	CAC, CQ, CQ-1, LQD, LQD-1, QT, QT-33, 44-T, 46-1, 48-1, 166T Series	A-81LPD	PS-66L	LP	22	P7000 (MJ, MD) (LP only)	RX552LPD	FOR SONOTONE CARTRIDGES														
PS-35L	LP	54	118, 120, 124 series, 310T, 312T, 420, 422, 424TS series, 310-1, 310-TB, TS, 312-TB, TS, 414-1	CRA-55LPD	FOR R.C.A. CARTRIDGES																			
FOR MAGNAVOX CARTRIDGES																								
PS-51L	COMB	37	560176, 560180, 560133, 560151, 560169-1, 560170	M-50SD	PS-23L	LP	12	74067	M-70LPD	PS-70L	COMB	51	1P-LB-1D, 2TD, 2TS, 2T-SD, 2T-LB-D, 2T-LB-S, 2T-LB-SD, 9980-S, 9980-SD, 9980D, 5T, 57-LB-S, 57-LB-SD	S-66SD										
FOR WEBSTER ELECTRIC CARTRIDGES																								
PS-17L	LP	7			PS-20L	LP	3	76257, (988370-2)	A-75LPD	PS-32L	COMB	51	3T, 3TS, 3TD	S-61SD										
PS-10L	LP	1			PS-70L	COMB	51	78748, 79807, 100653	S-66SD	PS-17L	LP	7	BX	A-811LPD										
					PS-25L	COMB	14	100329	A-71SD	PS-10L	LP	1	F11	JPS-30LPD										

REPLACEMENT STYLI FOR GE CARTRIDGES

FOR GE VR II CARTRIDGES (FIG. 35)
Direct replacements for clip-in styli in GE VR II series models 4G-050, 4G-052, 4G-053, 4G-040, 4G-041, 4G-063, 4G-061 cartridges. Avg. shpg. wt., 2 oz.
PS-48L 1 mil diamond LP clip-in stylus. Replaces GE 4G-01D Net 1.69
PS-546 1 mil sapphire LP clip-in stylus. Replaces GE 4G-01S Net .69
PS-548 3 mil sapphire 78 clip-in stylus. Replaces GE 4G-03S Net .69

MODERNIZATION ASSEMBLIES (FIG. 33)
Modernize your old triple-play cartridge. These assemblies replace both the old and new series "A." Once installed, you can replace one point at a time.
DIAMOND SAPPHIRE. Replaces old RPJ-013 and new RPJ-013A. Avg. wt., 2 oz. Net 1.69
DUAL DIAMOND. Replaces old GE RPJ-012 and new RPJ-012A. Net 3.90
DUAL SAPPHIRE. Replaces old GE RPJ-010 and new RPJ-010A. Net .99

STYLI FOR OLD TYPE GE CARTRIDGES (FIG. 32)
Exact replacement for all old type single needle GE cartridges. Avg. wt., 2 oz.
PS-45L Diamond 1 mil (LP) replaces GE RPJ-004 Net 1.69
PS-541 Sapphire 1 mil (LP) replaces GE RPJ-005 Net .69
PS-540 Sapphire 3 mil (78) replaces GE RPJ-001 Net .69

FOR GE SERIES A CARTRIDGES (FIG. 34)
Individual styli replacements that clip in to all GE "A" series. Avg. wt., 2 oz.
PS-47L Diamond 1 mil (LP) replaces GE RPJ-01D Net 1.69
PS-543 Sapphire 1 mil (LP) replaces GE RPJ-01S Net .69
PS-542 Sapphire 3 mil (78) replaces GE RPJ-03S Net .69

DIAMOND STYLI FOR G.E.

AS LOW AS 1.69



MULTILINGUAL LANGUAGE COURSE

GERMAN SPANISH
FRENCH ITALIAN

You can now learn to speak French, Italian, German or Spanish easily and pleasantly in your own home and progress at your own speed. Features the new simplified participation method that helps you to learn the lessons faster and retain them longer. It is a complete language course with 48 lessons on two 12" hi-fi long playing records. You learn with native speakers! The recorded lessons are printed in an illustrated conversation manual. Also included is a combination of grammar and dictionary book. When ordering, please specify the language desired. Shpg. wt., 4 lbs.

SPECIAL VALUE! INCLUDES RUSSIAN
5 language combination course. French, Italian, German, Spanish, and Russian. 9-12" LP records, 216 lessons, 2 books. Shpg. wt., 10 lbs. Net 9.50

4 SPEED PHONO MOTOR WITH TURNTABLE

Quiet, dependable A-C operation assured by rubber shock-mounted friction drive motor. Speed change control through idler driving an 8" turntable. Mounting centers 4 1/2 x 3 3/4"; 2 1/2" depth below base plate. Shpg. wt., 3 1/2 lbs.
ML-24 Phono and turntable Net 5.35
PK-149 Mounting board for motor Net .95

5.35



STATI-CLEAN .88

Sprays a fine mist which keeps your record clear of surface noise created by static (common to all vinyl records) and clean of dust attracted by the static charge. Prevents groove and needle wear caused by static-dust and keeps records lustrous. Extends their life. Two applications a year is sufficient. Enough for hundreds of records. Shpg. wt., 8 oz. Net .88

LAFAYETTE RECORD CLEANING KIT

Clean your valuable records the professional way with this Lafayette Kit. Contains a non-gumming anti-static detergent in polyethylene bottle. Squeeze to apply for complete elimination of static in the record grooves. Supplied with special velvet applicator in plastic pouch. Shpg. wt., 10 oz. Net 1.29



1.95 TONE ARM CONTROL

An absolutely essential addition for every Hi-Fi enthusiast. Ends groove and stylus damage caused by accidental dropping of tone arm onto record, greatly extending record life. Accurately and smoothly lowers tone arm into run-in groove and lifts arm off record at end of play. Ideal for "cueing." Designed to fit practically every known turntable arm as well as record changer with manual features. Supplied with adhesive mounting base to keep unit in position and with both wood and metal mounting screws for permanent installation. Shpg. wt., 6 oz. MS-785 Net 1.95


NEW! EXCLUSIVE LAFAYETTE STYLOCHRON



PROTECT YOUR PRECIOUS RECORDINGS.
NO MORE GUESS WORK KEEPS AN ACCURATE RECORD OF NEEDLE USE.

More precious recordings are ruined by tardy replacement of the needle than by any other cause. Now, there is no need to let this happen, especially to your doubly precious stereo recordings. Lafayette Stylochron lets you know just how long your needle has been in use so that you can replace the worn needle at the proper time, before it can do damage to your records. The Stylochron is quickly and easily mounted on your motor board or other convenient place. The moment your record changer or turntable starts, the Stylochron begins to register. It stops when the turntable stops. The 1000 hour dial will tell you at any time how long you have been using the needle. Dial is marked off in 50 hour units. You can remove your stylus for inspection at any predetermined number of hours. Diameter of the face plate is 2 3/8". Extends 1 7/8" below or behind panel. Complete with instructions. Shpg. wt., 2 lbs. Net 4.95

STEREO DIAMOND STYLI AT LAFAYETTE'S 1.69 Low Prices!



Stylus Stock No. Fig. For Cartridges

PS-88L	G	ACOS 73	.7 mil diamond and 3 mil sapphire stylus No. 73-1
ADMIRAL CARTRIDGES			
PS-80L	C	409B33-1-1(2-1)	
PS-81L	B	409C37-1	
ASTATIC CARTRIDGES			
PS-92L	N	17, 17D	
COLUMBIA CARTRIDGES			
PS-84L	J	SC-1-2-7-8	
ELECTROVOIC CARTRIDGES			
PS-80L	C	21 and 26 Series	
EUPHONIC CARTRIDGES			
PS-93L	K	E-1-3	
GENERAL ELECTRIC CARTRIDGES			
PS-87L	A	GC7	
PS-89L	A	VR27	
MAGNAVOX CARTRIDGES			
PS-80L	C	560233-3-4	
PS-94L	D	560280-1	
MONARCH (BSR)			
PS-86L	F	TC8S, TC-8SH	
MOTOROLA CARTRIDGE			
PS-80L	C	59K643335	
PS-81L	B	59B645397	
PERPETUUM-EBNER			
PS-81L	B	PE90 (M, N)	
PHILCO CARTRIDGES			
PS-80L	C	35-2809-1, 35-2824-1, 325-8047, 35-2825-1, 325-8036	
PS-81L	B	35-2820-1, 35-2826-1, 325-8048, 325-8049	
PS-86L	F	35-2827-1, 35-2829-1, 325-8051, 325-8052	
RCA CARTRIDGES			
PS-81L	B	T, T-1	
PS-85L	E	106770-1, 106690, 108213, 108718	
PS-86L	L		
SONOTONE CARTRIDGES			
PS-81L	B	0V, 0V1, T1 Single BF40, 105, 105-1 (2,3,4), 106-1(2,3,4)	
SONOTONE CARTRIDGE			
PS-82L	D	Combination .7 Mil (stereo) diamond and 3 mil (78RPM) sapphire for 8T and 8TA	
PS-95L	L	Same as above but for 9T Series	
PS-96L	M	Same as above but for 12T Series	
SONOTONE			
PS-83L	D	Same as above but with .7 mil (stereo diamond and 1 mil (monaural LP) sapphire	
TELEFUNKEN CARTRIDGE			
PS-90L	H	T20-2	
VM CARTRIDGES			
PS-80L	C	16707-A	
PS-82L	D	16708-F	
WEGCOR CARTRIDGES			
PS-80L	C	21P573	
PS-81L	B	21P596, 21P598	
PS-82L	D	21P700-1-2-3-4	
ZENITH CARTRIDGES			
PS-81L	B	142-99B	

NEW! .7 MIL DIAMOND STYLUS FOR SHURE M7D STEREO CARTRIDGE

PS-91L Net 4.50

ELECTROSONIC LAB "DUST BUG"



5.63

Automatically removes dirt and dust on each playing. Light plastic arm mounts by suction cup. Can be permanently mounted by rubber cement. The bottle of anti-static cleaning fluid has a built-in wick for application to a brush and pad at the end of arm. Shpg. wt., 6 oz. PK-156 Standard model (A) Net 5.63

ESL CHANGER DUST BUG (B). The tuft and pad assembly clips onto arm of changer. Performs the same as the standard model. Shpg. wt., 4 oz. PK-246 Changer model (B) Net 4.65

DISPENSER OF ACTIVATING FLUID. For Dust Bugs. PK-247 Net 1.22
PK-173 Replacement plush pad Net .78
PK-174 Replacement nylon brush Net .98

Sensational Values In Lafayette Communication Receivers!

LAFAYETTE AMATEUR COMMUNICATIONS RECEIVER

**SUPERHETERODYNE CIRCUIT UTILIZING
8 TUBES & RECTIFIER TUBE**



**KT-200
SEMI-KIT**

64.50

**HE-10
WIRED**

79.95

- BAND SPREAD FOR EASY TUNING • BUILT-IN "S" METER WITH ADJUSTMENT CONTROL • EXCELLENT SELECTIVITY • ACCESSORY POWER SOCKET PROVIDED • ALL TRIMMERS PRE-ALIGNED • COVERS 550KC. TO 31MC. IN FOUR BANDS • VARIABLE BFO AND AF + IF GAIN CONTROLS • SWITCHABLE AVC & AUTOMATIC NOISE LIMITER • ALL MAJOR COMPONENTS PRE-MOUNTED • DUAL 4 AND 8 OHM OUTPUT IMPEDANCES • 1 RF + 2 IF STAGES FOR HIGH GAIN RECEPTION

The KT-200 represents a significant departure from usual kit designs. As soon as it is unpacked, it is already half finished. All of the mechanical mounting is completed. Tube sockets, transformers, main tuning capacitor, filter capacitor, controls, even knobs and pilot lamps are all in place. The tuning assembly is installed and operative. Most important of all, the complex coil assembly and alignment capacitors for the oscillator, mixer and rf amplifier stages are factory mounted and pre-aligned. Thus only a slight touch up will be required to achieve maximum sensitivity and selectivity. Features such as built-in "S" meter with

adjustment control, switchable AVC and automatic noise limiter make the KT-200 worth many times its low price. Supplied with all components.

KT-200WX Net 64.50

HE-10WX Same as above, factory wired & Tested Net 79.95

The HE-48 speaker is handsomely styled to enhance your KT-200 or HE-30. Special 3 x 5 speakers gives distortion free response. 8 ohm impedance. Size: 7 3/4 H x 3 1/2 W x 5" D. Shpg. wt., 4 lbs. HE-48 Net 7.95


SPECIFICATIONS:

AM, 80-40-20-15-10 meter bands. Pre-calibrated band spread. Sensitivity: 1.25 mv for 10 db Signal-to-noise ratio. Selectivity: ± 10 KC, -60db (at 1 MC). Audio Output: 1.5 watts. Tubes: 3-6BD6, 2-6BE6, 2-6AV6, 1-6AR5, 1-5Y3. Power: 100-125 V AC 50/60 cps. Size: 15 1/2 L x 8 1/4 H x 12" D. Shpg. wt., 22 lbs.

**ELECTRONICS
ILLUSTRATED**

"... even the most inexperienced constructor should have no trouble."
"Sensitivity was so great the IF gain had to be turned all the way down to prevent overloading."

15
73
"... excellent value"
"... rugged, well made, and uses good components."



**RECEIVER
SPEAKER-MATE**

HE-48

7.95

DELIVERY APRIL 15, 1962



NEW! LAFAYETTE Professional QUALITY AMATEUR COMMUNICATIONS RECEIVER

HE-30 WIRED

**99.95 NO MONEY
DOWN**

**DESIGNED for TODAY'S
CROWDED AMATEUR BANDS**

**FEATURE FOR FEATURE, SIGNAL FOR SIGNAL
MATCHES RECEIVERS SELLING FOR ALMOST TWICE THE PRICE**

**KT-320
SEMI-KIT
79.95**

Designed for today's crowded amateur bands and the discerning Short Wave Listener, the new Lafayette HE-30 offers features and performance previously unheard of at this price. Outstanding Bandspread, Selectivity with a built-in Q-multiplier, and sensitivity combine to make the HE-30 one of the "hottest" general coverage bandspread receivers ever priced below \$200. For the crowded amateur bands—illuminated Slide Rule Dial, bandspread with markings every 5 KCS on 80 and 40 meters (IT TAKES 16 REVOLUTIONS OF THE BANDSPREAD DIAL TO COVER EACH OF THESE BANDS), every 20 KCS on 20 and 15 meters, and every 50 KCS on 10 meters, plus an edgewise S-meter. For the SWL—a 0-100 logging scale for "instant reset" to a desired station plus coverage from 0.55-30 MCS. The 8 tube (plus a husky 5Y3 Rectifier) circuit provides an RF stage with an antenna trimmer for peak performance PLUS 2 IF stages for improved selectivity. Far from an "empty shell" receiver, the HE-30 utilizes a 5Y3 tube in a transformer Full Wave rectifier power supply. This suppresses ripple and hum that often produces poor CW and SSB reception in "stripped down" receivers. Receiver sensitivity—that important difference between hearing and not hearing

stations—1.0 microvolts for 10db Signal-to-Noise Ratio. The Built-in BFO can be used to separate CW stations by means of the pitch control, while the Q-multiplier adds the selectivity needed for crowded phone band operation. The front panel controls speak for themselves—FUNCTION SWITCH, AUDIO GAIN, SELECTIVITY (Q-Multiplier), FREQUENCY (BFO), BAND SELECTOR, IF GAIN, TRIMMER, AVC-MVC SWITCH, ANL SWITCH, MAIN TUNING BANDSPREAD TUNING, and headphone jack. We invite comparison. Selectivity—60db at 10KC, 0.8 KC @ 6db (with Q-multiplier), IF—455KCS. Speaker-External PM type (not supplied), 4 or 8 ohms impedance. Audio Output—1.5 watts. Tubes—6BA6—RF Amplifier, 6BE6 Mixer, 6BE6—Oscillator, 6AV6-Q-Multiplier—BFO, 2-6BA6—IF Amplifier, 6AV6—Detector—AF Amplifier—ANL 6AQ5—Audio Output, 5Y3—Rectifier. Size—7 H x 15 W x 10" D. For 105-120. 60 cps AC. 50 watts.

HE-30WX Shpg. wt., 25 lbs. Net 99.95

NEW! KT-320 SEMI-KIT

This receiver is also available in kit form with all major components and front end pre-mounted and pre-calibrated. All other components supplied for easy mounting.

KT-320 Semi Kit Net 79.95



**SUPERHETERODYNE
CIRCUIT UTILIZING
8 TUBES &
RECTIFIER TUBE**

**HE-48
7.95**
**RECEIVER
SPEAKER-MATE**
Delivery April 15, 1962



- 8 TUBES PLUS RECTIFIER TUBE
- 1 RF + 2 IF STAGES FOR HIGH GAIN RECEPTION
- EASY-TO-READ, ILLUMINATED, SLIDE RULE DIAL
- BUILT-IN Q-MULTIPLIER FOR CROWDED PHONE OPERATION
- ANTENNA TRIMMER FOR OPTIMUM PERFORMANCE ON ALL BANDS
- CALIBRATED ELECTRICAL BANDSPREAD ON AMATEUR BANDS 80 THRU 10 METERS
- 0-100 LOGGING SCALE FOR SWL'S
- EFFECTIVE AUTOMATIC NOISE LIMITER
- AVC-MVC SELECTOR ON FRONT PANEL
- STABLE OSCILLATOR AND BFO FOR CLEAR CW AND SSB RECEPTION
- BUILT-IN EDGEWISE S-METER

NEW! TRANSISTORIZED 100 KC CRYSTAL CALIBRATOR MODEL TE-29



**ONLY
11.95**

- Generates Useful 100 Kc Harmonics Up To 54 Mc
- Transistorized, Self-Powered and Self-Contained
- Completely Wired — Not a Kit

The TE-29 is a transistorized 100 Kc oscillator with an output of high harmonic content. It will provide accurate markings every 100 Kc up to 54 Mc. Can be used to calibrate receivers and VFO's, or to mark band edges to insure in-band operation. The TE-29 may also be used as a constant signal source of accurately determined frequency, to which the receiver can be tuned for alignment purposes. The presence of the many harmonics, evenly spaced throughout each receiver's tuning range makes it easy to check tracking across a band without the nuisance of constantly returning a signal generator. The calibrator is activated by an on/off switch on the front panel, and the output is taken from one binding post on the side. The output may be coupled to the receiver directly. Can be tuned to WWV signals for accurate frequency calibration and the coil can be peaked for optimum output. These points are easily accessible from the bottom of the unit. Powered by a small 9 volt battery, the transistor oscillator is completely self-contained—requires no "digging" into the receiver for power. Housed in a 5Wx2 3/8 Dx 2 1/2" H sturdy metal box. Complete with battery. TE-29 Shpg. wt., 1 1/2 lbs. BA-3 Replacement battery for above Net 11.95 Net .49

NEW! TRANSISTORIZED 100 KC & 1 MC MARKER CALIBRATOR



**ONLY
17.95**

- Gives Markers Every 1 Mc, or Every 100 Kc, at the Flick of a Switch
- Fully Transistorized, Self-Contained and Self-Powered
- Completely Wired — Not a Kit

Here is a unique marker calibrator offering all the features of a conventional calibrator plus many unusual advantages. It consists of two crystal controlled transistor oscillators running at 100 Kc and 1 Mc, respectively. The function switch on the front panel has 3 positions: Off, 1 Mc, and 100 Kc. When the switch is in the 1 Mc position, the 1 Mc are useful in locating amateur band edges up through 6 meters, and for rough calibration of general coverage receivers. Since they are farther apart, they are easier to identify in frequency than the 100 Kc markers, so that they may be used as starting points in calibration. Once the 1 Mc intervals are established and identified, the switch may be thrown to the 100 Kc up to 54 Mc, so that the calibration may be refined to intervals of tenths of a megacycle. Each 100 Kc harmonic may be identified in frequency by counting up or down from the nearest integral megacycle marker below or above. Can be tuned to WWV signals for accurate frequency calibration and the coil can be peaked for optimum output. These points are easily accessible from the bottom of the unit. Completely self-contained and powered by a small 9 volt battery. Output is taken from one binding post, on the side. Housed in a 5Wx2 3/8 Dx 2 1/2" H sturdy metal box. With battery. TE-27 Net 17.95 Net .49 BA-3 Replacement Battery for above


NEW! LAFAYETTE 6 and 10 METER TRANSCEIVERS

NEW! LAFAYETTE Deluxe 6 METER TRANSCEIVER MODEL HE-45

- Highly Sensitive Superheterodyne Receiver Section for 50-54 Mc
- Effective Series Gate Noise Limiter
- 3-Stage, 12-Watt Transmitter with 2E26 Final
- Built-in 117 VAC and 12 VDC Power Supplies
- Pi-Network Transmitter Output
- Illuminated Panel Meter for Plate Current and "S" Readings
- Complete With Push-To-Talk Ceramic Microphone

Now, for 6 meters, Lafayette offers a deluxe transmitter-receiver in a single package, with features which make the low price hard to believe. Provides maximum convenience and flexibility in either mobile or fixed operation. The superheterodyne receiver section employs an RF stage with peaking control on front panel, and two i.f. stages at 1650 Kc. for 1 μ v sensitivity and 35 db image rejection. Tunes the entire 6 meter band from 50 to 54 Mc, with calibrated illuminated vernier tuning dial. Features an adjustable series gate noise limiter, built-in speaker. Illuminated panel meter serves as an "S" meter when meter function switch is set to the proper position. Transmitter section employs a 6U8 oscillator and buffer/multiplier, driving a 2E26 final with a plate input of approximately 12 watts on AM. Pi-network coaxial output is adjustable for matching a wide range of antenna impedances. Sockets for five 8 Mc fundamental crystals plus an input for external VFO on the front panel, with corresponding 6-position selector switch. A spotting switch is provided for zero beating or for locating the transmitting frequency in the receiver. Panel meter reads plate current when switch is set to proper position. A dual power supply for 117 VAC and 12 VDC is built in, making the HE-45 perfect for mobile operation. Push-to-talk operation provided. Tube complement: 12-BA6 RF amplifier, 1-6U8/6EA8 osc./mixer, 12-BA6 1st i.f. amp., 1-6U8/6EA8 2nd i.f. amp./1st audio, 1-6CN7 detector/noise limiter, 1-6AQ5 audio output and transmitter modulator, 1-6U8/6EA8 transmitter oscillator and buffer/multiplier, and 1-2E26 transmitter final amplifier. Housed in a rugged, low-silhouetted case with attractive, metal panel, the HE-45 comes complete with push-to-talk ceramic microphone, crystal for 50.12 Mc, detachable mounting bracket, and all power cables. Only 12x5x8 1/2" D. Shpg. wt., 15 lbs. HE-45WX

109⁵⁰
NO MONEY DOWN



MADE IN U.S.A.

NEW! LAFAYETTE 6 METER VFO

19.95

NEW LAFAYETTE V.F.O. FOR 6 METER TRANSMITTERS AND TRANSCEIVERS



Made in U.S.A. HE-61

- HIGHLY STABLE OSCILLATOR CIRCUIT
- FULLY WIRED—NOT A KIT

A deluxe 6 meter variable Frequency Oscillator designed for high stability and versatility. Completely shielded, the tuning components are isolated from direct heat of components. A High-Q Clapp oscillator circuit assures drift-free performance. An OA2 VR tube further eliminates any effects due to line voltage variation. Operating in the 4 to 4 1/2 Megacycle range, the output frequency is 8 MC. Ferrite tuned coil output is approximately 10 volts. The HE-61 can be used with any transceiver which has a standard 8 MC crystal. Cable with 5-prong power plug for units equipped

with VFO 5-prong power jack input. Instructions supplied for units not equipped with 5-prong VFO jack. Also supplied with cable and standard crystal plug for VFO input. The dial is calibrated from 50-54 megacycles and is illuminated for your tuning convenience. Precision planetary drive mechanism with single knob control of 180° rotation. Tube complement consists of one 12BA6 oscillator and an OA2 Voltage regulator. Furnished complete with cable and instructions. Size 3 3/4 x 4 3/4 x 1 1/4" D. Shpg. wt., 3 lbs. HE-61

Net 19.95


NEW! LAFAYETTE 10 METER TRANSCEIVER MODEL HE-50

- Effective Series Gate Noise Limiter
- With Push-To-Talk Ceramic Microphone
- 12-Watt Transmitter with Pi-Network Output
- Built-in Dual Power Supply for 117 VAC and 12 VDC—Ideal for Mobile or Fixed Operation
- Superhet Receiver Tunes 10 Meter Phone Band from 28 to 30 Mc

109⁵⁰
NO MONEY DOWN

Here is a new transceiver with the deluxe mechanical and electrical features of the HE-45, applied to the 10 meter amateur phone band. Receiver has 1 μ v sensitivity. The i.f. of 1650 Kc results in a 45 db image rejection on 10 meters. Includes automatic series gate noise limiter. Transmitter runs 12 watts input to a 2E26 final, with pi-network coax output to match any antenna. Uses 7 Mc fundamental crystals or external VFO. Sockets for 5 crystals plus VFO input, with corresponding 6-position selector switch, located on front panel. Physical layout is identical to that of the HE-45. Includes big illuminated tuning dial and illuminated panel meter which serves as "S" meter and final plate current meter. Built-in dual power supply for 117 VAC and 12VDC make the HE-50 the ideal solution to the problem of finding a compact, completely self-contained 10 meter rig which can be operated mobile or used at home without modification. The many transmitter and receiver features which are combined in this single package make it a value that is hard to beat, at a price designed for the conservative budget. Tube complement: 1-6BA6 RF amplifier, 1-6U8/6EA8 osc./mixer, 1-6BA6 1st i.f. amp., 1-6U8/6EA8 2nd i.f. amp 1st audio, 1-6CN7 detector/noise limiter, 1-6AQ5 audio output and transmitter modulator, 1-6U8/6EA8 transmitter oscillator and buffer/multiplier, and 1-2E26 transmitter final amplifier. Housed in a rugged, low-silhouetted case with attractive, metal panel, the HE-50 comes complete with push-to-talk ceramic microphone, crystal for 28.30Mc, detachable mounting bracket, and all power cables. Only 12x5x8 1/2" D. Shpg. wt., 15 lbs. HE-50WX

Net 109.50



MADE IN U.S.A.

NEW! LAFAYETTE 6 METER TRANSCEIVER

SMALL, COMPACT COMPLETE 6 METER STATION—TAKE IT WITH YOU ANYWHERE!

57.50
NO MONEY DOWN

- Ceramic Temperature-Free Microphone

- Superhet Receiver Tunes Entire Band (50-54 mc)
- Efficient Adjustable Noise Limiter
- 7 Watts Input to 6CX8 Pentode Final
- New Efficient Pi-Network Output with Hi-"Q" Tuned Circuit
- Separate Oscillator—Final Stage
- Accessible Front Panel Socket With Crystal For 50.2 MC Output

Meet the enjoyable challenge of 6 meter operation efficiently and economically with the Lafayette HE-35 6 meter transceiver. This small, compact transceiver features a transmitter with 7 watts input to a 6CX8 pentode final high quality plate modulation, built-in adjustable TVF filter, and antenna matching network for 30 to 100 ohm antenna; Superheterodyne receiver tunes entire 6 meter band (50-54 mc) and includes variable noise limiter. The transmitter uses a 3rd overtone crystal in easily accessible socket located on front panel; has RF output and modulation indicator. Low-loss 50-239 coaxial antenna output jack. Complete with attractive high output ceramic

microphone, crystal for 50.2 Mc, and mounting brackets for mobile mtg. 6 or 12 volt power supply separately available for mobile operation. Built-in power supply operates on 110-120 volts, 60 cycle. 10 5/8 x 5 1/2 x 6 3/4" D. Tubes: 2-6U8A/6EA8, 6AL5, 12AX7, 6V6GT, 6CX8. Shpg. wt., 11 lbs. HE-35 AWX

MOBILE POWER SUPPLIES
5 3/8 x 4 3/4 x 2 1/4" Shpg. wt., 4 lbs. Net 10.95
HE-16W 12 Volts Net 10.95
HE-16V 6 Volts Net 10.95
Additional Crystals—Specify Frequency
HE-36L Shpg. wt., 4 oz. Delivery 3 wks. Net 4.95



MADE IN U.S.A.

AMATEUR SHORTWAVE EQUIPMENT and ACCESSORIES

hallicrafter



NEW! HALLICRAFTER S-120 RECEIVER

Covers Broadcast Band 550-1600 KC plus 3 Short Wave Bands 1800 Kc to 30 Mc. 3 Antennas, Slide Rule Bandspread Dial, New Compact Styling.

This new precision built receiver features electrical bandspread with slide rule bandspread dial and separate bandspread tuning condenser. Front panel head-phone jack which automatically disconnects self-contained speaker may be used to drive remote 8 ohm speaker. Has 3 antennas (ferrite loop for broadcast band; adjustable whip for short wave; wire antenna).

Tube complement: 12BE6 Converter, 12BA6 I-F amplifier, B.F.O., 12AV6 Audio amplifier, AVC detector, 50C5 Audio, plus Selenium Rectifier, 455KC IF. Attractive gray steel cabinet with silver trim. 13 1/2" x 5 1/2" x 8 3/4" D. (U/L Approved). Operates on 105-125V 50/60 cycles AC/OC.

HE-127 Shpg. wt., 12 lbs. Net 69.95

24 HOUR ELECTRIC WORLD CLOCK

8" Overall diameter • Adjustable for Various Time Zones • South Polar Projection

Self starting, accurate electric clock. Tells world-wide and local time. Calibrated in hours—1 to 24, minutes and seconds—1 to 60. Black dial with white graduation. 2-257 Hallicrafters S120 plus famous name electric world clock. Net 69.96

ANOTHER OUTSTANDING LAFAYETTE AMATEUR SALE



SPECIAL 1c SALE

HALLICRAFTER S120 RECEIVER PLUS FAMOUS NAME ELECTRIC WORLD CLOCK ONLY 69.96

SENSATIONAL LAFAYETTE ANTENNA PACKAGE FOR AMATEURS YOU SAVE 24.83

Reg. Price 144.78 Lafayette Price 119.95

ON SYSTEM CONSISTING OF:

- CDR AR22 Heavy Duty Automatic Rotar
- My-Gain TH-3 3 Element Antenna
- 100' RG-8/U Cable • 100' Rotor Cable

CDR AR-22 AUTOMATIC ROTOR



This heavy-duty rotor unit will handle antennas up to 150 lbs. Simply set the control unit pointer to the desired direction, and the antenna will automatically rotate to this position and stop. Perfect for TV, Ham or Citizen Band application. Rotor unit employs 12 heavy duty ball bearings in two 6 1/2" races. Weather-proof motor reverses instantly and is factory lubricated for life. Reversible clamps on rotor will take masts from 7/8" to 2". O.D. Control unit is marked in compass points. N.S.E.W. NW, NE, SW, and SE. Housed in attractive brown plastic cabinet with rubber feet. Complete with rotor, control unit and instructions. For 110-120 volts 50-60 cps AC. Requires 4 conductor cable. HE-478WX Net 32.77

NEW! My-Gain TH-3 3-ELEMENT ANTENNA



The finest 3-element trap tribander for amateur communications on 10, 15 and 20 meters. All-aluminum construction of 2" OD beams and 1 1/4" telescoping to 3/4" OD elements. Plastic and steel gusset bracket assemblies; all steel fixtures and hardware, 100% rust proof. Less than 2 to 1 SWR on all bands. New "solid state" slim traps (1 1/2" in diam.) Withstand 1000 watts CW or AM and 2000 watts SSB. Overall beam length 14 ft., longest element 26 ft. Shpg. wt., 29 lbs.

HE-773WX Net 99.95
WR-131 100-Ft. RG-8/U Coaxial Cable Net 9.87
WR-151 100-Ft. 4 Cond. Rotor Cable Net 2.39

SPECIAL LAFAYETTE PACKAGE

Includes: AR-22 Rotor; TH-3 3 Element antenna; 100' RG-8/U; 100' 4 Cond. Rotor Cable. SP-228WX Shpg. wt., 61 lbs. Net 119.95

BRAND NEW LAFAYETTE

HE-48 SPEAKER


DESIGNED TO GIVE SUPERIOR VOICE REPRODUCTION FOR SSB, AM, CW AND OTHER VOICE APPLICATIONS.

The HE-48 speaker is handsomely styled to enhance your present facilities. Special 3 x 5 speakers gives distortion free response. 8 ohm impedance.



HE-48 Net 7.95 Delivery April 15, 1962

LAFAYETTE MODEL HE-11 SPEAKER FOR AMATEUR AND SHORT WAVE RECEIVERS 7.95



Efficient and attractive speaker especially designed as ideal mate for communications receivers. 4" speaker housed in handsome, tapered, grey metal cabinet reduces QRN and peaks voice frequencies. Impedance 8 ohms. 7 3/8" x 5 1/4" x 4 1/2". HE-11 Shpg. wt., 4 lbs. Net 7.95 HE-14 As above, except 4 ohms impedance Net 7.95

NEW DRAKE 2B RECEIVER FOR SSB AM & CW



Top performance on SSB, AM and CW. The 2B is a highly sensitive, triple conversion receiver with 60 db image rejection. Covers 3.5 - 4.1 Mc, 6.9 - 7.5 Mc, 13.9 - 14.5 Mc, 20.9 - 21.5 Mc, 28.5 - 29.1 Mc, with a crystal controlled high frequency oscillator (crystals supplied). Highly stable variable oscillator. Sensitivity: 0.5 microvolt for 10 db S/N ratio. 50 Kc last i.f.—selectivity of 2.4 Kc at 6 db down. Receiver has 7" slide-rule dial with markings every 10 Kc and a vernier with markings every 1 Kc. Additional features: slow or fast AVC action, accurate "S" meter, distortion-free product detector. For 110-120V., 60 cps. Size: 12" x 7" x 9" D. Shpg. wt., 15 lbs. HE-180WX Net 279.95

Model 28a Q-multiplier and deluxe speaker. For 2B receivers. Net 34.95

HE-181 Net 34.95

HE-182-2AC crystal calibrator for 2B (not illus.) Net 16.95

New! National 105

A new general coverage receiver which features remarkable performance for the amateur, shortwave listener and hi-fi enthusiast. An efficient fixed tuned peaking type Q multiplier provides continuously variable IF selectivity to meet any listening requirement—from 7 KC for full fidelity music reception to 500 cycles for crowded CW Band conditions. Large edge-type illuminated S-meter operates during AM, SSB and code reception for accurate measurement and logging of signal strength. Separate combination BFO/product detector assures maximum performance during SSB and CW reception. Calibration charts are provided for all popular amateur and foreign broadcast bands. Exclusive tuner output permits detector to be fed into hi-fi amplifier for quality reception for taping SW. Tunes 550K to 30MC in four bands. Available in either a functional steel cabinet or custom oiled walnut enclosure. Dimensions (in steel cabinet) 7 1/2" x 13 1/2" x 8 1/2" D. For 105-125 A.C., 60/60 cycles. Shpg. wt., 27 lbs. HE-222WX Steel Cabinet Net 119.95 HE-223WX Oiled Walnut Cabinet Net 139.95

B&W 550A COAXIAL SWITCH



An inexpensive multi-position coaxial switch that eliminates the annoyance of changing coaxial connections. Permits you to instantly select any one of five r-f generating devices using 52 or 75 ohm line. The switch handles up to 1 kw of modulated power with a maximum cross-talk of -45db at 30mc. MP-91 Shpg. wt., 2 lbs. Net 8.25

NEW GONSET GR-212 DUAL CONVERSION RECEIVER



- RECEIVERS FM, SSB, DSB, CW
- ELECTRICAL BANDS SPREAD OF THE AMATEUR BANDS

A newly designed dual conversion receiver for general coverage from standard broadcast through 34 MC band including WWV, U.S. Bureau of Standards Time Signals and Shortwave. Provides the novice with superb performance at modest cost. Specifications: Frequency Range: 550 KC to 30 MC continuous in 6 bands, with electrical bandspread of amateur bands. Sensitivity: 1.0 microvolt 30% mod @ 400 CPS. Selectivity: 5 KC at 6db points. Audio Output: 3 watts. Receives AM, SSB, DSB, CW. Tubes: 6AU8, (2) 6BA6, 6AL5, 6AQ5, 6BE6, 12AX7 plus 2 Silicon diode rectifiers. Size: 8 1/2" x 16 1/4" x 10 1/2" D. Shpg. wt., 23 lbs. HE-953WX GR-112 Net 110.00

NEW GONSET GR-211 ALL-BAND RECEIVER

A highly sensitive all-band receiver which places the world at your fingertips. Hear Shortwave, WWV, standard Broadcast and Amateur bands. Range: 550 KC to 34 MC in 4 bands with electrical bandspread on Amateur bands. Sensitivity 1 microvolt, 30% mod. Size: 8 1/2" x 16 1/4" x 10 1/2" D. Shpg. wt., 22 lbs. HE-952WX (not illus.) Net 73.50

NEW! HE-34 SWR AND FORWARD POWER METER



16.95

- Reads SWR and Relative Power Output Up To 1 KW
- For Continuous Use in 52 Ohm Lines
- Highly Compact — Only 2 1/2" x 2 1/2"
- Switch Selects SWR or Forward Power — No Reversing Necessary

A compact SWR and relative power meter which can be permanently inserted into a 52 ohm coaxial line to monitor transmitter and antenna performance. The ideal aid in adjusting beams, trap antennas, matching networks, etc., or for tuning transmitters for maximum output. Designed for the frequency range from 3 to 200 mc, and for powers from 25 watts to a full kilowatt. Above 7 Mc, as little as 10 watts will provide adequate sampling; above 100 Mc, as little as 5 watts. The unit is installed by means of a standard coaxial connector on each side, and becomes part of the 52 ohm line. Insertion loss is negligible. Once installed the unit need never be reversed. A switch on the front panel is set to SWR SET for relative forward power readings up to 1 KW on a scale calibrated from 0 to 10, and for adjustment of the sensitivity control for SWR readings. The switch is set to SWR for measurement of reflected power, on an SWR scale calibrated from 1:1 to 100:1. The HE-34 measures only 2 1/2" x 5 1/2", excluding coax connectors. Imported. HE-34 Shpg. wt., 1 1/4 lbs. Net 16.95

National 60 SPECIAL "B" RECEIVER



National's new all-wave low-priced receiver which features continuous coverage of AM Broadcast, Amateur and World Wide Short Wave Bands; brilliantly styled by Peter Quay Yang for easy operation, ready reading and attractive decor. Features include: 4 separate bands—540 Kc-1600 Kc; 1.6-4.5 Mc; 4-12 Mc; 10.5-31 Mc with police, CD, marine, aircraft, amateur, etc. stations clearly marked; plus 0-100 logging and bandspread scale. Bandspread operative on all bands. Audio section drives built-in speaker or front panel phone jack. Has AM, CW switch, standby-receive switch, 2 degrees of selectivity, complement of 4 tubes plus rectifier, superheterodyne circuit. Finish is two tone black and gray enamel. Size: 7 3/8" x 8 3/8" x 13 1/2". Shpg. wt., 15 lbs. HE-200WX Net 55.95

FREE WITH PURCHASE OF NC-60 SPECIAL "B"

KT-77 Shortwave Antenna Kit. Shpg. wt., 1 1/2 lbs. Net 1.05
ME-42 Headset. Shpg. wt., 1 1/2 lbs. Net 2.35
REGULAR PRICE 3.40
SPECIAL LAFAYETTE OFFER
HE-200WX plus KT-77 plus ME-42. Shpg. wt., 18 lbs. Net 59.95
SP-128WX

NEW! TM-58 SWR BRIDGE & RF POWER METER

- Measures RF output Power Into Built-in 52 Ohm Dummy Load, Up to 15 Watts
- Measures SWR and Relative Power Up To 1 KW
- Can be Used in 52 and 75 Ohm Coaxial Lines

Here is a quality instrument which will give highly accurate SWR and direct power readings up to 50 Mc. The unit may be permanently inserted in the transmission line for SWR and relative power monitoring. When the 3-position selector switch is set to POWER, the meter will indicate the RF power up to 15 watts, into a built-in 52 ohm resistive load employing quality non-inductive resistors. Full scale accuracy is 10%. The selector switch is set to SWR SET to read relative forward power up to 1 KW and to adjust the sensitivity control for SWR measurements. For direct SWR measurements from 1:1 to 4:1 with powers up to a kilowatt, the selector switch is set to SWR. Unit is inserted into the transmission line by means of two standard coax connectors, and 2 slide switches are set to 52 or 75 to correspond with line impedances of 52 or 75 ohms, respectively. Insertion loss is negligible. Meter has 50 uA movement; calibrated directly in watts from 0-15, and in SWR from 1 to 4 (reads infinity at full scale). Housed in an attractive grey metal cabinet, 3 1/2" x 7 1/4" x 2 3/4". Sits on 4 rubber feet. TM-58 Shpg. wt., 1 lbs. Net 27.95

NEW! LAFAYETTE TM-26 ILLUMINATED COMMUNICATIONS 2 3/8" "S" METER



Only 3.95

- Replaces Many Communications Receiver "S" Meters
 - 2 Jewel Movement • Clear Plastic Front
 - Calibrated to S9 + 40 db
 - BIG BROTHER TO THE LAFAYETTE TM-11
- A new signal strength meter (basic 1 ma, 2 jewel movement) designed to replace many "S" meters used in communications receivers. Clear plastic front measures 2 3/8" square and meter fits standard 2 1/2" round hole. Perfect for the experimenter and amateur. Complete with mounting screws, instructions for installation and use. For 6 volt or 12 volt operation. Zero adjustment control on front panel. Imported. Shpg. wt., 1 lb. TM-26 Net 3.95



24.50

NEW LAFAYETTE HE-26 HYBRID PHONE PATCH

Enjoy the pleasure of handling phone patch traffic with this deluxe hybrid patch. Hybrid circuit permits use of AM or SSB with voice control by effectively isolating the receiver audio output from the transmitter audio input. Provides an accurate balance between 500 ohm line and station equipment—with negligible insertion loss. Four connections on rear for receiver output (voice coil, 3-4 ohms), transmitter input, Station microphone, and telephone. Easy to operate after a few preliminary adjustments, all from the front panel. Null and balance controls are adjusted, with the aid of readings on the edgewise panel VU

meter, for balance and maximum receiver-transmitter isolation. Thus the receiver audio signal, which would ordinarily trip the VOX circuit, is balanced out from the transmitter audio section. The gain control is adjusted for proper transmitter and receiver audio level. VU meter continuously monitors line level. The patch can be switched in and out by means of a front panel switch, so that it may be permanently installed. Compact, sloping cabinet will fit into any station arrangement. Sits on 4 non-slip rubber feet. Size: 3 1/2" x 5 1/2" x 4" D. HE-26 Shpg. wt., 3 lbs. Net 24.50

TOP QUALITY Marine and

AMATEUR EQUIPMENT

FM-AM COMMUNICATION RECEIVERS

NEW! LAFAYETTE FM AM 10 TUBE 145-175 MC POLICE RECEIVER MODEL HE-52



LAFAYETTE FM/AM 10 TUBE 30-50 MC POLICE RECEIVER MODEL HE-51

NO MONEY DOWN **52.50**

- Crystal Controlled And Tuneable
- Built-in 4" PM Speaker

Now you can listen in on all the exciting action of police, fire department, answering services, civil defense and many other municipal activities right in your own home. Keep alert to emergencies at any hour. Quality built, it is safe to say that a better communications receiver could not be found at twice its price. Look at these features. Powerful 10 tube performance, even a short length of wire will suffice to bring in strong local signals; 3 IF stages; Crystal controlled the HE-51 can be accurately tuned to a pre-selected frequency for long periods of time. Critical tuning and drift problems are virtually eliminated. The crystals for fixed frequency operation can be ordered separately—See below. Though most sig-

nals in the 30-50 MC range will be FM, some transmissions are AM and a handy front panel FM-AM slide is provided. Built-in squelch circuit reduces background noise, without adversely affecting its sensitivity. The built-in 4" speaker can be cut-out for headphone operation with a panel mounted slide switch. Either high or low impedance phones may be used. Provision has been made for connection of a larger external amplifier if desired. Tube complement: 6AQ8, 6BC5, 6UB, (3) 6AU6, 6AL5, 12AX7, 6AQ5, 6X4 for 105-120 VAC. Size: 12½x4½x6½". Shpg. wt., 14 lbs.

HE-51WX Crystal Controlled and Tuneable Net 52.50

Crystal for Fixed Freq. operation—30-50 MC. Please specify exact operating freq.—supplied within .005%. Allow 30 days for delivery.

HE-759L

Net 5.95



52.50
NO MONEY DOWN

- EASY-VISION SLIDE RULE DIAL
- DRIFT-COMPENSATED
- BUILT-IN 4" PM SPEAKER

Now you too can "listen-in" to police, fire, forestry, civil defense, marine and other important municipal and industrial activities right in your own home. Keep yourself constantly alert to emergencies at any hour. Quality built, the HE-52 offers powerful 10 tube performance at a low, low Lafayette price. Look at these features. Sensitive RF stage for maximum low noise amplification—even a short length of wire (2½ to 5 ft.) will suffice to bring in sufficiently powerful signals. Provision has been made for connection of more elaborate 75 or 300 ohm antennas if needed. 3 IF stages; built-in squelch circuit func-

tions without reducing the receiver's sensitivity to information-bearing signals. The built-in 4" speaker may be turned off when switching to phone operation. Either high or low impedance earphones may be used if they are terminated by phone tips. An amplifier jack is provided on the rear of the unit to enable connection of a larger external amplifier if desired. Tube Complement: 6C4, 6AQ8, (3) 6AU6, 6AL5, 12AX7, 6AQ5, 6X4. For 105-120VAC. Dimensions: 12½x4½x6½". Shpg. wt., 14 lbs.

HE-52WX Tuneable only Net 52.50

LAFAYETTE SCOOPS THE ENTIRE RADIO MARINE INDUSTRY Famous Name Nationally Advertised 30 Watt Marine Radio Telephone

COMPLETELY TRANSISTORIZED FOR RELIABILITY AND MINIMUM VOLTAGE DRAIN

Lafayette Price **189.50**

Reg. Price 279.95 NO MONEY DOWN

- 5 Crystal Controlled Channels Plus Standard Broadcast Band
- Equipped With 2 Crystals 2638 KC Ship To Ship 2182 KC Coast Guard • FCC Type Accepted

A truly unique marine radio telephone design. The separate portable transistor radio is easily removable to permit marine and standard broadcast reception. You can even "self-check" your own transmitter. The unit uses an adjustable gimbal permitting installation on any surface. Exceptionally low power requirements due to advanced transistor circuitry. Uses only .190 amperes (equivalent to a small pilot lamp in receive

mode) and 1.5 amps. on standby to transmit. Will tune to existing boat antenna. Antenna booster provides ideal match. Modulator is fully transistorized with automatic limiting. Frequency Range of transmitter and receiver: 2-3 MC. 5 Crystal channels. Input Voltage 12 volts dc. Complete with press-to-talk hand held carbon microphone. Size: 11½x9" D. HE-915WX Shpg. wt., 16 lbs. Net 189.50


MODEL ASP-194—center loaded vertical whip antenna for the marine frequency range of 2000 to 2830 KC for use with above radio Marine telephone. Overall height is 12"9" including stainless steel whip. 21" loading coil covered with epoxy resin to insure long life and trouble free performance—Mast is 6' long made of 1" O.D. heavy gauge anodized aluminum tubing. Shpg. wt., 6 lbs.

HE-957WX

Net 33.42



ONLY 10.99 BRAND NEW! TRANSISTORIZED "BULL HORN"



HUNTERS BOATING CAMPERS SPORTS

- Weighs only 2½ lbs.
- Range up to 2,000 ft.
- Completely Transistorized • Can be Used as Long-Range Listening Device

Considered the most modern development in bull horns because it is completely transistorized—instantly operates on 6 standard 1½V. "C" flashlight batteries (not incl.). With its range up to 2,000 ft., it is ideal for all outdoorsmen, for work or sports. Trigger switch is simple to operate—just press to talk. May be used as a sound detector and amplifier as well as a voice amplifier. Shpg. wt., 3 lbs.

PA-271 Net 10.99
BA-274 1.5 Volt Batteries (6 req.) Net ea., .16

NEW ALL STAINLESS 6 METER MOBILE ANTENNA 6.95

OUTSTANDING FEATURES

- 58 in. Stainless Steel Whip For Optimum 6 Meter Performance
- Heavy-Duty Chrome Plated Stainless Steel Spring
- Chrome Plated Swivel Ball Jointed Mount Base

Chrome swivel ball mount base designed to be mounted on any surface. Stainless steel spring holds rod in properly adjusted position and prevents rod damage from shocks and blows. Stainless steel whip for maximum resiliency and strength. Shpg. wt., 4 lbs.



HE-49W

Net 6.95

THE AMAZING NEW Spacephone KIT

TWO WAY 3 TRANSISTOR CITIZENS BAND TRANSCEIVER ONLY **16.95**

- SAVE ALMOST 50% • NO LICENSES, TESTS OR AGE LIMITS • TRANSMITS AND RECEIVES UP TO ½ MILE • JUST 5 INCHES HIGH

Now Lafayette brings you the amazing Spacephone in new, economical kit form. Save almost 50%. You'll find hundreds of uses for hunting, fishing, boating, around the plant, in the home or fire and police work. Utilizing advanced Space-age printed circuitry, the 3 transistor Spacephone can be built in a few hours of spare time. Self-contained with its own speaker/microphone, it weighs a mere 8 oz. and measures only 2½x5" H, small enough to fit in the palm of your hand. Powerful enough to communicate up to ½ mile. Complete with all parts, 40" telescoping antenna, battery, crystal for channel 14 and instructions.

HE-699 Net 16.95
Set of 2 Net 29.95

Same as above but wired and tested. Less Battery.

HE-698L Shpg. wt., 1½ lbs. Net 23.98
Set of 2 Net 42.95

BA-2 9 volt battery (1 required) Net .39



hallicrafters HAMMARLUND

NEW! S-119 RECEIVER

A low cost superheterodyne receiver kit covering the standard broadcast band plus two short wave bands: 2 Mc to 5.5 Mc and 6 Mc to 16.5 Mc. This range includes the 80, 40 and 20 meter amateur bands. The power supply utilizes a selenium rectifier, and is transformer operated! Tuning dial has 4 to 1 reduction. Receiver includes built-in speaker, headphone tip jacks, AM/CW switch. Designed for Powerful performance. Tube comp: 6BE6 oscillator/mixer, 6BA6 i.f. amplifier/BFO, 6CM8 first and second audio amplifier and output. The detector is a 1N295. Cabinet size: 10½x5x5H7½"D. Shpg. wt., 9 lbs.

HE-135 S119 Factory Wired & Tested Net 49.95
HE-136 S119K Receiver Kit Net 39.95

NEW! CODOME AUTOMATIC MORSE CODE INSTRUCTION MACHINE FOR THE NOVICE

The CODOME and its accompanying manual provide all the materials necessary to prepare the beginner for his Novice class amateur license examination. The machine itself sends groups of letters and numbers automatically, in random order. Built-in key permits the student to develop his sending technique in step with his receiving technique. As each group of characters is being practiced, the student is introduced, by means of the accompanying manual, to the basic concepts of electricity and radio, and to the FCC regulations pertinent to amateur communications. Each code group has a corresponding lesson in the manual, with exam-type questions and answers. Once the code and theory are mastered, the student should have no difficulty in fulfilling the Novice requirements. For 117 VAC. 2¼x5¼x6¾". HE-696 Shpg. wt., 2½ lbs. Net 17.95

NEW HAMMARLUND HK-1B ELECTRONIC KEYS

A compact, fully transistorized code generator that combines all of the desirable features of electronic sending with distinctive dot/dash control to give messages your "personal touch." Uses simplified transistorized circuitry and operates on standard 22½ volt battery. Keying relay prevents polarity reversal and transistor damage. Less battery.

HE-147 Net 39.95
BA-270 22½ Volt battery for above Net 1.61

E. F. JOHNSON 1 WATT PERSONAL MESSENGER

The new 1 watt personal Messenger is another outstanding achievement from E. F. Johnson engineers. Identical in appearance to the highly successful 100 milliwatt Johnson Personal Messenger, this 1 watt unit employs 11 transistors, 4 diodes, and uses heavy duty components, consequently you get improved performance from the 1 watt unit. Handy to use the 1 watt personal Messenger, a citizens band license is necessary. Super-het receiver with tuned RF stage; automatic noise limiter; AVC; squelch; push-pull audio output; powerful 2 stage transmitter. Includes night light cell battery compartment. Battery compartment with rechargeable nickel-cadmium available as an accessory. Built-in telescoping antenna. Supplied with crystals for CB channel 11.

HE-623L Shpg. wt., 2 lbs. Net 129.50
BA-155 Type Z penlight cells (8 req.) Shpg. wt., 6 oz. Net ea. .095

Leather carrying case for transceiver. Shpg. wt., 1 lb. HE-753L Net 8.50

Rechargeable nickel cadmium battery mounted in sealed plug-in compartment for recharging at 115 VAC. 50-60 CPS. HE-754L Shpg. wt., 8 oz. Net 19.55

LAFAYETTE NEW UNIVERSAL 6 METER AND BROADCAST MOBILE ANTENNA

ONE ANTENNA FOR BROADCAST AND 6 METERS! AT A SENSATIONALLY LOW PRICE OF

4.75

Here is a highly efficient 6 meter antenna that replaces your Auto radio antenna for operation on both 6 meters and for regular AM broadcast reception. 59" stainless steel mast, all chrome ball type base adjustable to 180° for front rear or side mount. Complete with 54" lead. Highly versatile and durable. Shpg. wt., 4 lbs.

HE-801WX

Net 4.75

Hi-Par "SATURN 6" MOBILEER

A compact, horizontally polarized mobile antenna for 6 meters. It is essentially an end-loaded folded dipole with 3 ring design, approximately 20" in diameter, 5" high. Design center is 50.5 Mc but resonant frequency may be varied between 50.5 and 53.0 Mc. Easily fed with RG58/U coax. Rigid aluminum construction; net weight under 2 lbs. Easily supported on pipe, tubing or stiff rod.

Model S-1—"Saturn 6" Antenna, 2-piece adjustable aluminum mast, mast bracket, universal bumper hitch. No holes to drill. Less coax feed line. Shpg. wt., 5 lbs.

HE-805W Net 16.59

5 ELEMENT 6 METER BEAM

A rugged, Full size 6 meter beam constructed of ¾" 0.050 wall aluminum tubing with hardwood dowling at high stress points. Boom is 0.058 wall drawn aluminum. Driven element is concentric gamma matched for direct coax feed. Light enough for any heavy duty TV rotator. Turning radius — 7'6"; Forward Gain — 9.5 db; F/B ratio — 29 db. Comes with all parts marked for quick, neat assembly and center band operation. Shpg. wt., 15 lbs.

HE-746WX

Net 19.50

LAFAYETTE 6 METER HALO ANTENNA



7.95

Single halo, horizontal, polarized, provides extreme broadband coverage without the use of bulky wave traps. Loop weight only 1 lb. Standing wave ratio is 1:1 at frequency. 5-15 DB gain over vertical whip types when working Fixed stations with arrays. Includes 3 section, 9 ft. telescoping aluminum mast to fit any standard mobile mount.

HE-46W Shpg. wt., 4 lbs.

Net 7.95

MARK MOBILE HELIWHIP ANTENNAS FOR 6 & 10 METERS

9.95

Fiberglass molded continuously loaded whip antennas designed to replace conventional stainless steel ¼ wave whips. The Heliwhip can be positioned on the upper portion of the vehicle such as trunk lid, cowl, fender or hood without danger of shorting to power lines. Offers superior performance on 49-55 KC bandwidth (6 meters) plus blends in with auto styling. Produces 50 ohm match at resonant frequency. Shpg. wt., 1 lb.

HE-740W 6 meter Heliwhip Net 9.95
HE-739W 10 Meter Heliwhip Net 9.95
HE-896 HWM-1 Antenna Mount for above. Shpg. wt., 2 lbs. Net 7.50

SAVE! BATTERIES, CHARGERS, "HAM" CODE EQUIPMENT

LAFAYETTE BATTERIES AT TREMENDOUS SAVINGS



These popular batteries are for Portable and Transistor radios, R/C equipment, experimenters, labs, and hobbyists, etc.

FRESH STOCK — BRAND NEW GUARANTEED

Here are six of the most popular types used and at **RIDICULOUSLY LOW PRICES**

Stock No.	Voltage	Singly	Lots 10 Each	RCA	REPLACEMENTS FOR Burgess Eveready	Others
BA-1	67 1/2	1.59	1.49	VS215 VS216 VS218	P45 P45M	477 BL-M145
BA-2	9	.39	.35	VS312 VS323	2U6	216 BL-006F
BA-3	9	.49	.44	VS300A VS314	P6 P6M	226 BL-M106
BA-5	67 1/2	1.29	1.19	VS318	UX45	416 BL-045
BA-6	67 1/2	1.45	1.35	VS016	XX45	467 BL-145
BA-7	9	.59	.53	VS309A	YL-6 E-177	TR-177

LAFAYETTE PHOTOFLASH, BC AND HEARING AID BATTERIES

Stock No.	V.	Singly	Lots 10 Ea.	Fig.	Replacements for Burgess Eveready	RCA	Shpg. Wt.
BA-11	15	.49	.44	A	Y10	504	3 oz.
BA-14	22 1/2	.59	.53	A	Y15	505	3 oz.
BA-12	22 1/2	.59	.53	B	U15	412 VS084	3 oz.
BA-16	45	1.98	1.83	C	M30	482 VS013	2 lb.
BA-15	90	2.36	2.12	E	N60	490 VS090	1 lb.
BA-13	240	4.50	—	E	U160	491	1 lb.

PORTABLE A TYPES

Lafayette Stock No.	"Eveready" No.	Burgess	R.C.A.	Voltage	Shpg. Wt. Lbs.	Net
BA-100	A100	230	VS336	1 1/2	1/4	\$.16
BA-101	720	2D	VS069	1 1/2	3/8	.84
BA-104	964	21R	VS236	1 1/2	3/8	.32
BA-109	724	Z4	VS068	1 1/2	1/8	.70
BA-112	713	B5	VS129	7/8	3/8	1.92
BA-113	717	C5	VS065	7/8	1/2	1.15

PORTABLE B TYPES

BA	No.	U10	VS083	15	1/4	\$.81
BA-114	411	U10	VS083	15	1/4	\$.81
BA-115	417	K10	—	15	1/4	.16
BA-116	504	Y10	—	15	1/4	.81
BA-117	412	U15	VS084	22 1/2	1/8	1.05
BA-118	420	K15	—	22 1/2	1/8	1.23
BA-119	505	Y15	—	22 1/2	1/8	1.05
BA-120	413	U20	VS085	30	1/8	1.23
BA-122	506	Y20	—	30	1/8	1.30
BA-123	507	Y20S	—	30	1/8	1.30
BA-124	415	U30	VS086	45	1/8	1.75
BA-125	455	XX30	VS055	45	1/2	2.08
BA-126	482	M30	VS013	45	1	2.70
BA-130	416	UX45	VS318	67 1/2	1/4	2.07
BA-131	457	K45	VS082	67 1/2	1/2	2.42
BA-132	467	XX45	VS016	67 1/2	1/2	2.45
BA-133	477	P45	VS018	67 1/2	1/2	2.27

PORTABLE A-B TYPES

BA	No.	4T260	VS064	1 1/2, 90	2 1/2	\$4.38
BA-143	729	4T260	VS064	1 1/2, 90	2 1/2	\$4.38
BA-146	755	T5250	VS050	6, 7 1/2, 75	3 1/2	5.08
BA-149	756	T6260	VS057W	7 1/2, 9, 90	—	4.87
BA-151	752	G6B60	VS047	9	2 1/2	5.78

ELECTRONIC PHOTOFLASH AND HIGH VOLTAGE TYPES

BA-226	497	U320	—	510	1 1/2	\$11.16
--------	-----	------	---	-----	-------	---------

MERCURY ENERGIZERS

Lafayette Stock No.	"Eveready" No.	Mallory	R.C.A.	Voltage	Shpg. Weight Lbs.	Net
BA-227	E 1	RM-1R	VS143	1.35	0.43	.36
BA-230	E 9	ZM-9	VS313	1.40	1.05	.51
BA-231	E 9N	DM-9N	—	1.40	1.05	.54
BA-232	E 12	RM-12R	VS144	1.35	1.4	.75
BA-233	E 132	TR-132R	VS148	2.70	0.9	.92
BA-234	E 133	TR-133R	VS149	4.05	1.4	1.00
BA-235	E 134	TR-134R	—	5.40	1.9	1.53
BA-236	E 146	TR-146R	VS312	8.40	1.6	1.37
BA-237	E 233	TR-233R	VS400	4.20	1.8	1.80
BA-238	E 400	RM-400R	VS145	1.35	0.04	.24
BA-239	E 401	RM-401R	—	1.35	0.04	.33
BA-240	E 502	RM-502R	—	1.35	1.05	.62
BA-241	E 625	RM-625R	—	1.35	0.14	.34
BA-242	E 630	RM-630R	—	1.35	0.17	.28

FLASHLIGHT, LANTERN BATTERIES

BA	No.	7	VS074	1 1/2	1/4	.10
BA-154	912	7	VS074	1 1/2	1/4	.10
BA-155	915	Z	VS034	1 1/2	2 1/2	.095
BA-156	935	1	VS035	1 1/2	1/4	.13
BA-157	950	2	VS036	1 1/2	1/4	.13
BA-158	D-99	—	—	1 1/2	1/4	.16
BA-159	735	4FH	VS106	1 1/2	1 1/4	.84
BA-160	±6 lgn.	6 lgn.	VS006S	1 1/2	2 1/4	.84
BA-161	509	F4H	VS040C	6	1 1/4	.79
BA-162	510S	F4BP	VS040S	6	1 1/4	.79
BA-163	731	TW1	VS317	6	3 1/4	1.83
BA-164	706	4F4H	VS103	6	5 1/4	4.01
PA-309	904	NE	VS073	1 1/2	1	.08
BA-311	715	4F5H	VS139	7 1/2	8 1/2	4.86



"B" BATTERY ELIMINATOR and CHARGER 2.45

Replaces Eveready 416, Burgess UX-45, and RCA VS 318 67 1/2V B batteries used in Radio Control units and many portables. Just plug in the AC cord and you can save your battery for outdoor use. Also recharges your battery. 110 volts. 3 1/2 x 1 1/2". Shpg. wt., 7 oz. Net 2.45

NEW! "STORAGE CELL" for TRANSISTOR RADIOS!

ONE CHARGEABLE BATTERY OUTLASTS 100 CONVENTIONAL BATTERIES **2.69**

- Replaces 2U6, 216, BL-006P and BA-2
- Fluid Storage Type—Can't Leak Out
- Plays About 15 Hours on One Charging
- Battery Recharges Overnight
- Battery Can Be Used Over and Over Again
- Complete—Battery Plus Charger

The next best thing to a battery that will last a lifetime—this battery can be used for 100 to 1500 hours of playing time, AND MORE, its long life is based on 2 new features: 1. A fine storage battery that cannot have fluid leakage; 2. Recharges Overnight—just plug the battery into the charger, let charge for 10-12 hours it cannot burn out on recharge. After charging, the battery is good for about 15 hours of playing time. When the battery runs down, just charge it up and it's ready to play. Will outlast more than 100 conventional batteries. 9V Battery complete with charger. Battery 1 7/8 x 1 1/8", charger 3 3/4 x 1 1/4 x 7/8". F-619 Battery and Charger. Shpg. wt., 6 oz. Net 2.69

BA-8 Battery Replacement for above Net 1.48

LAFAYETTE "B" BATTERY ELIMINATOR and CHARGER for TRANSISTOR RADIOS 2.95

This simple "B" battery and eliminator has provision for replacing snap terminals on all 9-volt transistor batteries. Now when indoors you can operate your portable transistor set on regular 110V AC house current without using up your expensive "B" battery. Best of all you may also recharge your used "B" battery for many extra hours of use. Complete with AC cord and assorted snap terminals to fit all 9-volt transistor batteries. Size: 3 1/2 x 3 3/8 x 2 1/2" D. Shpg. wt., 1 lb. Net 2.95

ECONOMY ALL-PURPOSE DYNAMIC EARPHONE

- For Transistor and Subminiature Receivers
- For Silent Radio and TV Listening

A sensitive all-purpose earphone designed with both your listening pleasure and pocket-book in mind. Extensive range and excellent tone combine, to provide excellent reproduction. Lightweight, equipped with a practically invisible ear support, that slips comfortably over either ear, from which the earphone can't slip out or fall. Ideal for use with TV and radio sets, amplifiers, miniature and transistor receivers, etc. Attractive unit with shiny chrome finish. Complete with a 3 ft. cord. A super value at this price. Shpg. wt., 5 oz. 6 ohm impedance, with subminiature phone plug. MS-591 Net .79

ONLY 79c


SEMI-AUTOMATIC "BUG"



Fully the equal of keys selling at almost twice the price! 7 adjustments for speed and comfort. Precision-tooled, anti-rust nickel-plated brass and stainless steel operating parts. Speed adjustable 10 wpm to as high as desired. 1/2" silver contacts; weight scale for reproducible speed settings. A real bargain for radio amateurs and professional CW operators! 6 3/4 x 3 x 2 1/4" H. exclusive of knobs and feet. Shpg. wt., 3 1/2 lbs. Net 9.95

9.95

CODE PRACTICE SET



A budget item for the beginning amateur and code practice groups. Key has adjustable spring tension, and adjustable contact clearance. High frequency buzzer has frequency, and tension adjustment with lock nuts to assure constant frequency. There is provision for insertion of head set by means of binding posts with knurled tightening screws. For individual, group or remote listening. Uses Burgess #2 1 1/2 Volt battery. Base 6 3/4 x 2 3/4 x 1 3/8" D. overall length 8 1/2" Shpg. wt., 2 lbs. (less battery). Net 1.79

MS-438—Code practice set Net 1.79
BA-157—Burgess #2 Net .13
MS-369—Stethoscope Headset Net 1.39

1.79

SAVE ON NEW TELEGRAPH KEY



Economical key for beginning amateurs. Solid, heavily chrome and nickel plated metal parts, molded phenolic base. Adjustable spring tension and adjustable metal parts, molded phenolic base. Adjustable spring tension and adjustable contact clearance. 2 mounting holes in base. Base 3 1/4 x 1 1/4 x 1 3/8" W. Overall length 5"; height 1 3/8". Shpg. wt., 12 oz. Net .69

MS-319—Telegraph Key Net .69

69c

LAFAYETTE "BRASS-POUNDER'S" KEY




- WITH BALL-BEARING PIVOTS
- SOLID POLISHED-BRASS BASE

A better quality precision-made key designed for hard usage. Spring tension and contact clearance adjustments; 3/4" silver contacts; adjustable ball-bearing pivots; Circuit closing switch. Base 3 x 2"; overall size 5 x 2 3/8 x 1 1/4". Shpg. wt., 1 1/2 lbs. Net 1.95

MS-428—Telegraph Key Net 1.95

1.95

HIGH FREQUENCY CODE PRACTICE BUZZER



Adjustable frequency buzzer ideal for individual or group code practice. Perfect code item for the ham shack. Black molded phenolic housing. Works with 1 1/2 volt battery. Screw adjustment for changing tone. 1 1/8" diam. x 1 1/4" high. Shpg. wt., 6 oz. Net .79

MS-436—Buzzer Net .79

79c

TELEGRAPH TRANSMITTER



And Code Practice Oscillator **Only 2.95 2 for 4.90 4 for 8.75**

- Send and receive for miles on one wire!
- Ideal for Network Practice
- For Individuals, Group, Classrooms, Hams, etc.

An ideal communications instrument that can be set up, with others, for network practice in classrooms, groups, house to house, etc. Adjustable spring tension and contact clearance. Crystal earphone—high output—lightweight. Molded Bakelite base. Lightweight, only 6 oz., yet designed to give good stability while in use. Complete with 50 ft. of wire on reel, ground spike, ground wire, earphone and Morse code sheet. Uses 1.5V battery (not included). Overall 4 1/4 x 4 1/2" high. Shpg. wt., 1 lb. Net 2.95

F-552 Telegraph Transmitter Net 2.95
BA-157 Battery for above Net .13

TAPEDCODE



Prerecorded magnetic tapes containing a complete course in the International Morse Code. The tapes are 7 1/2" long and can be played on any standard tape recorder. Playing time 2 hours per tape. Shpg. wt., 1 1/2 lbs. Net 8.35

NOVICE Basic instructions & code 4-8 WPM. RT-14 Net 8.35
ADVANCED Code at 9-18 WPM. RT-15 Net 5.39

TRANSISTORIZED CODE PRACTICE OSCILLATOR




- MINIATURE-PORTABLE
- SELF CONTAINED BATTERY POWER SUPPLY
- PRODUCES CLEAR, CRISP, CW NOTE

Here is an ideal, inexpensive code practice oscillator for the amateur radio enthusiast. Long 38 inch wire from oscillator to earpiece, allows two persons to practice without interference. The unit is completely portable, and weighs only 6 oz. Tone produced is clear and crisp, similar to that received during F.C.C. licensing examinations. Low voltage transistorized circuit utilize 1.5 volt penlight type battery which completely eliminates any possible shock hazard. Earpiece is crystal type, and housed in sanitary plastic. Shpg. wt., 5 oz. Net 2.29

F-429 Oscillator only Net 2.29

CODE PRACTICE OSCILLATOR WITH KEY



Above oscillator plus adjustable telegraph key (MS-319). Key has spade lug connectors, making it possible to disconnect the key from the oscillator and use it separately if desired. Shpg. wt., 9 oz. Net 2.95

F-479 MS-319 Key and Oscillator Net 2.95

2.29

AMECO RECORD CODE COURSES

Fast, simple way to learn code for commercial and amateur licenses. Junior course designed to take you from start to 18 words per minute; Senior course from 8 to 18 words per minute. Junior set consists of 5 records for 78 and 45 rpm; 1 for 33 1/2 rpm. Senior set consists of 11 records for 78 and 45 rpm; 2 for 33 1/2 rpm. Advanced set consists of 6 records for 78 and 45 rpm; 1 for 33 1/2 rpm. Number in bracket indicates shpg. wt.

Type	Stock No.	33 1/2 RPM Net	45 RPM Stock No. Net	78 RPM Stock No. Net
JR.	PR-47 (1 lb.)	4.95	PR-41 (2 lb.)	5.95
SR.	PR-48 (2 lb.)	9.50	PR-43 (3 lb.)	10.50
ADV.	PR-49 (1 lb.)	4.95	PR-45 (2 lb.)	4.95
			PR-44 (4 lb.)	5.95

LAFAYETTE SPECIAL CODE COURSE



Learn Morse Code the modern practical way. Supplied with 10 lessons and a non-breakable high quality 33 1/2 rpm playing record, recorded with code sound to provide further aid. Perfect for home studying. Speed progresses steadily from 2 to 15 wpm. Complete with sturdy record album and instruction manual. Shpg. wt., 1 1/2 lbs. Net 3.50

PR-13 Lafayette Code Course Net 3.50

3.50

TRANSISTOR CODE PRACTICE OSCILLATOR KIT

3.95

COMPLETE WITH TELEGRAPH KEY & TRANSISTOR

For those interested in mastering the international code, an audio tone oscillator is essential. The circuit of this transistorized feedback oscillator has the simplicity of the neon glow, the signal strength of the vacuum tube, and requires only two penlight cells for weeks of service. It may be used for solo practice, or two may send and receive with the same unit. Kit comes complete with Transistor, Telegraph Key, Resistors, Condensers, Masonite Board, etc., and Schematic Diagram. Net 3.95

KY-72 LESS BATTERY, Shpg. wt., 1 1/2 lbs. Net 1.18
ME-33 Cannon AM-15-1—Single headset Net 1.18
BA-154 Battery Burg. #7 or eq. (2 required) wt., ea. 1/2 oz. Net ea. .10

SAVE

LOWEST PRICES ON YOUR RECEIVING TUBE PURCHASES PLUS FREE VALUABLE GIFTS ON PURCHASE OF 15 OR MORE TUBES



30 WATT SOLDERING PENCIL



Reg. Price **1.79**

FREE with Purchase of 15 Receiving Tubes

TECHNICIAN'S ELECTRIC TOOL KIT



Reg. Price **7.95**

FREE with Purchase of 50 Receiving Tubes

20,000 Ohms-Per-Volt VOM



Reg. Price **13.50**

FREE with Purchase of 100 Receiving Tubes

ALL BRAND NEW — FRESH STOCK — ORIGINAL BOXED TUBES • FULL 12 MONTH GUARANTEE • YOU MAY ASSORT FOR QUANTITY — PRICE SAVINGS!

ALL BRAND NEW—FRESH STOCK—ORIGINAL BOXED TUBES • FULL 12 MONTH GUARANTEE • YOU MAY ASSORT FOR QUANTITY—PRICE SAVINGS!

TUBE TYPE	Mfr. Sugg. List*	NET EACH IN QUANTITIES OF:		
		1 to 5	6 to 49	50 or more
6Z4	2.40	1.27	1.18	1.06
6X6GT	2.90	1.54	1.42	1.26
1RS	2.70	1.43	1.32	1.19
1T4	2.50	1.32	1.22	1.11
1W4	2.50	1.32	1.22	1.11
1U5	2.20	1.17	1.08	.97
12Z2/B	3.20	1.70	1.57	1.41
3BZ6	2.25	1.19	1.10	.99
3CB6	2.25	1.19	1.10	.99
3V4	2.50	1.32	1.22	1.11
5B4GB	2.10	1.11	1.03	.93
5U6	3.30	1.74	1.62	1.46
5Y4GA	3.50	1.85	1.71	1.55
5Z3GT	1.75	.93	.86	.77
6AB4	2.15	1.14	1.05	.94
6AC7	4.85	2.57	2.38	2.14
6AF4A	4.00	2.12	1.96	1.76
6AG5	2.75	1.45	1.35	1.21
6AL5	1.85	.98	.91	.81
6AM6A	3.25	1.71	1.59	1.43
6AN8A	3.70	1.96	1.81	1.55
6AQ5A	2.15	1.14	1.05	.93
6AS5	2.45	1.29	1.20	1.08
6AU6GT	3.55	1.88	1.74	1.57
6AUBA	2.10	1.11	1.03	.93
6AUBA	3.50	1.85	1.71	1.55
6AV6	1.65	.87	.80	.71
6AW6A	3.65	1.93	1.79	1.61
6AX4GT	2.65	1.40	1.30	1.17
6BA6	2.00	1.06	.98	.88
6BC5	2.45	1.29	1.20	1.08
6BE6	2.20	1.17	1.08	.97
6BG6GA	6.50	3.44	3.18	2.86
6BK7B	3.35	1.77	1.64	1.48
6BL7GTA	4.10	2.17	2.01	1.81
6BN6	3.15	1.67	1.54	1.39

Serviceman & Dealer SPECIAL!



LAFAYETTE TUBE TESTER

FREE!

With Purchase of 150 Receiving Tubes

Reg. Price 19.95

Full Size Tube Checker 8 1/2" Dx 9 3/4" W x 2 3/8" H

TUBE TYPE	Mfr. Sugg. List*	NET EACH IN QUANTITIES OF:		
		1 to 5	6 to 49	50 or more
6BZ6	2.25	1.19	1.10	.99
6BQ6GT/6CUG	4.35	2.30	2.13	1.92
6BQ7A	3.95	2.09	1.93	1.74
6BZ7	4.00	2.12	1.96	1.76
6C4	1.85	.98	.91	.81
6CB6A	2.25	1.19	1.10	.99
6CD6CA	5.80	3.07	2.84	2.56
6CE7	2.45	1.29	1.20	1.08
6DE6	2.45	1.29	1.20	1.08
6DQ6B	4.10	2.17	2.01	1.81
6J6	2.80	1.48	1.37	1.23
6K6GT	2.50	1.32	1.22	1.11
6L6GC	4.20	2.22	2.06	1.85

TUBE TYPE	Mfr. Sugg. List*	NET EACH IN QUANTITIES OF:		
		1 to 5	6 to 49	50 or more
6SA4	2.05	1.09	1.00	.90
6SK7	3.55	1.88	1.74	1.57
6SN7GTB	2.60	1.37	1.27	1.14
6SQ7	3.30	1.74	1.62	1.46
6T8A	3.35	1.77	1.64	1.48
6U8A	3.30	1.74	1.62	1.46
6V6GT	2.15	1.14	1.05	.94
6W4GT	2.40	1.27	1.18	1.06
6W6GT	2.80	1.48	1.37	1.23
6X4	1.65	.87	.80	.72
6X5GT	2.05	1.09	1.00	.90
6X8	3.15	1.67	1.54	1.39
12AT6	1.65	.87	.80	.72
12AX7	3.05	1.62	1.49	1.34
12AU6	2.15	1.14	1.05	.94
12AU7A	2.45	1.29	1.20	1.08
12AV6	1.65	.87	.80	.72
12AX4GTB	2.70	1.43	1.32	1.19
12AX7	2.55	1.35	1.25	1.12
12BA6	1.65	.87	.80	.72
12BE6	1.75	.93	.86	.77
12BH7A	3.05	1.62	1.49	1.34
12BY7A	3.20	1.70	1.57	1.41
12SA7	3.90	2.07	1.81	1.72
12SA7GT	3.25	1.71	1.59	1.43
12SK7	3.55	1.88	1.74	1.57
12S8T	3.30	1.74	1.62	1.46
25L6GT	2.30	1.22	1.13	1.02
35C5	2.15	1.14	1.05	.94
35L6GT	2.40	1.27	1.18	1.06
35W4	1.01	.53	.49	.44
35Z5GT	1.85	.98	.91	.81
50B5	2.65	1.40	1.30	1.17
50C5	2.15	1.14	1.05	.94
50L6GT	2.55	1.35	1.25	1.12
117Z3	2.50	1.32	1.22	1.11

* List suggested by mfr. These prices may or may not be adhered to in retail sales.
NOTE: This is a partial listing. This gift offer also applies to your selection from our complete receiving tube listing on Pages 98 and 99, Catalog 620. Your order is shipped at current prices. You benefit from any price reductions during life of this catalog.


LAFAYETTE BUDGET-PRICED TV PICTURE TUBES MONEY SAVING SPECIALS!

FULL 1-YEAR GUARANTEE

Every Lafayette picture tube is top quality—made or entirely new materials except the glass, which is tested and inspected to meet new-glass standards.

Stock No.	Type	NET PRICE	
		Less Ddd	With Ddd
PT-404X	10BP4A††		7.50
PT-405X	12KP4A*	10.33	
PT-350X	12LP4A	9.00	
PT-352X	14C/B/EP4B*	11.50	
PT-351X	14EP4/CP4	10.25	
PT-351X	14QP4A*	12.50	
PT-393X	14RP4*	13.65	12.00
PT-393X	16AP4/AP4A†	15.10	13.45
PT-354X	15GP4†	13.94	13.39
PT-355X	16KP/RP4	9.00	
PT-356X	16KP4A/RP4A/TP4A*	11.50	
PT-394X	17AVP4	15.00	12.80
PT-395X	17AVP4A*	17.20	15.00
PT-357X	17BP4/BP4A	10.77	9.67
PT-358X	17BP4B*	12.53	11.33
PT-396X	17BRP4*	21.18	17.33
PT-406X	17BVP4*	21.18	17.33
PT-407X	17BWP4*	21.18	17.33
PT-408X	17BZP4*	21.18	17.33
PT-359X	17CP4†	16.75	15.25
PT-360X	17GP4/TP4†	17.65	16.00
PT-361X	17HP4/RP4	11.33	
PT-362X	17HP4B/RP4C	12.95	
PT-363X	17LP4/VP4	13.10	12.00
PT-364X	17LP4A/VP4B*	15.50	14.40


A LAFAYETTE Serviceman SPECIAL!



Economy TUBE CADDY
• Holds More Than 150 Tubes
Only **5.95**

Lafayette now offers a tube caddy with a capacity of more than 150 tubes at this low, low price. Sturdily constructed of wood and kraft-board with easy-to-open lid. Overall 17Wx12 1/2Hx 7 3/4"D. Shpg. wt., 8 lbs. Net 5.95

Stock No.	Type	NET PRICE	
		Less Ddd	With Ddd
PT-397X	17QP4/YP4	12.21	11.11
PT-398X	17QP4A/YP4A*	13.77	12.67
PT-366X	19AP4A/AP4B†	17.50	16.95
PT-367X	20CP4A/DP4A	12.50	11.40
PT-368X	20CP4D/DP4C*	14.43	13.33
PT-370X	21ACP4A/AMP4A/BSP4*	17.70	12.75
PT-372X	21ALP4A/B/ATP4A*	17.40	13.00
PT-369X	21AP4†	21.90	17.50
PT-373X	21AU/AVP4	16.95	12.00
PT-374X	21AU/AVP4B*	18.95	14.00
PT-400X	21BTP4/BTP4A*	17.62	12.67
PT-375X	21CBP4A/B/CMP4*	21.15	16.20
PT-409X	21CEP4/DFP4*	21.33	17.33
PT-410X	21CQP4*	21.73	17.33
PT-401X	21DEP4/DAP4/CZP4*	21.33	17.33
PT-376X	21EP4A	14.32	12.67
PT-377X	21EP4B*	16.00	14.35
PT-378X	21FP4A/KP4A	14.32	12.67
PT-379X	21FP4/KP4C*	15.65	14.00
PT-402X	21MP4†	23.40	19.00



RCA ALL AMERICAN 5 TUBE KIT
2.95

Sensational buy by Lafayette brings this RCA All American 5 Tube kit to you at the unusually low price of 2.95. Used in most popular AC-DC Super-heterodyne Radio Receivers. Kit Consists of 1 each: 50C5, 35W4, 12AV6, 12BA6 and 12BE6. SP-258 Net 2.95



NEW! 5U4 PLUG-IN SILICON RECTIFIER REPLACEMENT. 1.75
JUST PLUG IN 5U4 RECTIFIER SOCKET—NO MORE LOSS OF HEIGHT & WIDTH DUE TO 5U4 FAILURE OR WEAKNESS!
RE-75 Net 1.75



Serviceman & Dealer SPECIAL!

INDOOR T.V. ANTENNA

Classic design for any TV set. 3-section telescoping elements. Shpg. wt., 1 lb.

AN-105

85¢ ea.

6 or more **77¢ each**

12 or more **65¢ each**



LAFAYETTE PUBLIC ADDRESS and MUSIC AMPLIFIERS

NEW! LAFAYETTE 40-WATT PUBLIC ADDRESS AMPLIFIER



- Power Output Sufficient to Drive Many Speakers Simultaneously
- Flat Response from 30 Cps to 15 Kc
- Two Microphone Inputs, One Phonograph Input
- Separate Volume Control for Each Input
- Excellent Hum and Noise Suppression
- Attractive New Styling


69⁹⁵

NO MONEY DOWN

Here is a powerful new public address amplifier suitable for use in large department stores, stadiums, amusement parks, industrial plants, summer camps, etc. Power output is a full 40 watts. Three inputs are provided: Two microphone inputs for crystal or dynamic mikes, and one phono input for a crystal or ceramic pickup, a tape recorder, tuner or other high level program source. Frequency response: ± 2 db from 30 cycles to 15 Kc. Input sensitivity: mike inputs, 5 mv for full output; phono 300 mv. Input impedance: mike, 1 megohm; phono, 500,000 ohms. Hum and noise are 64 db below rated output with mike inputs and 74 db below with phono input. Hum balance control provided in rear. Each input has its own volume control to permit proper blending and balance when two or three inputs are in use simultaneously. Separate bass and treble controls. Output impedances: 4, 8, 16 or 250 ohms, taken either from a terminal strip in the rear, or from two 6-prong sockets provided for rapid connection and disconnection. The 250 ohm output is a constant voltage tap for a 70 volt line. Groups of speakers may be connected directly to the amplifier in various series, parallel, and series-parallel configurations. Tube complement: 1-12AX7/ECC83 microphone preamplifier, 1-6AV6 tone control, 2-6AQ8's and 4-6BQ5/EL84 output tubes (two parallel pairs operating push-pull). For 110-120 volts, 50-60 cycles AC. In an unusually attractive metal cabinet with modern black and gray panel, 5 1/4" H x 13 1/4" W x 9 1/4" D. Shpg. wt., 30 lbs. PA-268WX

Net 69.95

NEW! LAFAYETTE MODEL LA-75 20-WATT MUSIC AMPLIFIER



INSTRUMENT CONTROL PANEL RECESSED FOR EASY ACCESSIBILITY

- 20 Watt High-Fidelity Amplifier
- For Presenting Amplified Live Music and Voice to an Audience
- Adjustable Tremolo for "Quivering" Effect
- Built-in 12" Heavy-Duty Hi-Fi Speaker
- Separate Volume and Tone Controls for Instrument and Voice Inputs

69⁵⁰

NO MONEY DOWN

Here is a music amplifier which will deliver 20 watts of clean power, to a built-in 12" heavy-duty 20 watt speaker or to an external 4, 8 or 16 ohm speaker. There are 3 inputs: two instrument inputs and one microphone input for voice. The two instrument inputs have volume and tone controls separate from the corresponding controls on the voice input. Built-in tremolo circuit super-imposes an oscillator signal on the audio signal to create a periodic fluctuation or "quiver" whose frequency and amplitude may be adjusted by the "speed" and "strength" controls, respectively. There is a jack provided for turning the tremolo on and off by means of a foot switch (available as an accessory). Frequency response: ± 3 db from 33 cycles to 20 Kc on voice

input; ± 3 db from 33 cycles to 15 Kc on instrument inputs. Mike input sensitivity is 9 mv RMS; mike jack is shorting type to minimize hum pickup when mike is not plugged in. Tube complement: 2-12AX7's, 1-6AU6, 2-7189 output tubes, 1-6CA4 rectifier. Dimensions: 15 3/4" H (including rubber feet) x 19 1/4" W x 8 1/4" D. With carrying handle. Shpg. wt., 30 lbs.


Net 69.50

LA-75WX FOOT SWITCH to remotely control the tremolo in the LA-75. Equipped with cable terminated in standard phone plug to fit corresponding jack on LA-75. Shpg. wt., 1 1/2 lbs. SW-103

Net 5.95



FOOT PEDAL



LAFAYETTE MODEL PA 62 30 WATT PA AMPLIFIER

PA-62 with PA-63 Phono Top

Less phono-top
52⁵⁰

NO MONEY DOWN

FEATURES: Ideal for use in churches, schools, small theaters, lecture halls and industrial plants. Priced extremely low to give extra profits to rentals and sales. Separate bass and treble tone controls, permits adjustments to meet all acoustic requirements. Two mike inputs; optional 4-speed phono top. 70 volt constant voltage output tap. Provides coverage up to 100,000 square feet when used with trumpet type speakers. Chassis is equipped with 2-speaker plug-in output sockets. Unit is housed in sturdy steel, well-ventilated cabinet. Modern streamlined styling. Fin-

ished in baked hamerloid enamel. Removable escutcheon plate for rack and panel mounting. **SPECIFICATIONS:** TUBES: 3-6EU7, 2-6L6GB, 5U4GB (Rectifier). **POWER OUTPUT:** 30 Watts. **INPUT GAIN:** Microphone 125 db, Phono 80 db. **FREQUENCY RESPONSE:** 30 to 15,000 cps, ± 1 db. **TONE CONTROLS:** Bass ± 15 db at 50 cps; Treble ± 15 db at 10,000 cps. **HUM LEVEL:** 70 db below rated output. **INPUTS:** 3: 2-Microphone and 1-Phono. **CONTROLS:** 6: Microphone-1, Microphone-2, Power off-on, Phono-Bass, Treble, Slide Switch for operating magnetic phono thru channel 2. **OUTPUT IMPEDANCES:** 4, 8, 16, and 250 ohms (70 volt line). High impedance output for coupling booster amplifier. **POWER CONSUMPTION:** 135 Watts, 110/120 V.A.C. 50-60 cycles. **Fused. SIZE:** 14Wx8Dx6"H. **SHIPPING WEIGHT:** 20 lbs. PA-62WX Complete with Tubes

Net 52.50

4-SPEED PHONO TOP

For above amplifier. Fits in place of cover. Plays all speeds—16 2/3, 33 1/3, 45 and 78 rpm. Has constant 4-speed motor, with turnover cartridge, complete with two precious metal needles. Has arm-rest and plug connection; for 110 Volt 60 cycle. Shpg. wt., 10 lbs. PA-65W 4-Speed Phono Top

Net 17.95

NEW! 40 WATT DUAL SPEAKER PA SYSTEMS

- New Lafayette Powerful 40 Watt Public Address Amplifier
- 2 University or Electro-Voice Horns For Outdoor Systems
- 2 25-Watt Speakers & Wall Baffles For Indoor Systems
- Choice of Deluxe Dynamic Mikes
- 70 Ft. of Speaker Cable

Highly efficient permanent sound systems for large halls, department store music and paging systems, railroad stations, restaurant music, etc. The outstanding Lafayette PA-268 40 watt amplifier assures top performance under all operating conditions. For 117 volts, 60 cps AC.

40-WATT PERMANENT INDOOR SYSTEM
Consists of the PA-268 40-watt amplifier, two 12" PM speakers, two attractive walnut wood baffles, two 35' speaker cables with plugs, an Atlas MS-10C floor mike stand and Argonne AR-3 dual impedance dynamic microphone with ball-joint desk stand, for hand-held, desk stand or floor stand use. Shpg. wt., 75 lbs. PA-284WX

Net 125.95

Same as above, except with Electro-Voice 664 mike. In place of AR-3 PA-283WX

Net 149.95

40-WATT OUTDOOR PA SYSTEM
Consists of a PA-268 40-watt amplifier, two Lafayette PA-57 driver units and two University PH trumpets, two 35' speaker cables with plugs, and an Argonne AR-3 dynamic mike with desk stand. Shpg. wt., 75 lbs. PA-282WX

Net 139.45

Same as PA-282WX, except with Electro-Voice 664 dual impedance cardioid dynamic mike and MS-10C floor stand, in place of AR-3 PA-281WX

Net 168.45

Same as PA-282WX except with 2 Electro-Voice 848 projectors in place of PA-57 and University PH. PA-280WX

Net 157.95

Same as PA-280WX with Electro-Voice 664 mike and floor stand, in place of AR-3 PA-279WX

Net 186.95



LAFAYETTE DUAL SPEAKER 20 WATT PERMANENT SYSTEMS




- CHOICE OF CRYSTAL 3-WAY LAVALIER OR DESK-STAND MIKES
 - TWO HEAVY-DUTY 12" SPEAKERS • TWO POLISHED WALNUT WALL BAFFLES
- Excellent for a great many public address, paging and sound reinforcement applications, the Lafayette 20-watt permanent system is an exceptional value. Speakers and paging horns may be added for wider area coverage or for multiple small areas such as offices, loading platforms or stockrooms. Easy to install in small dance halls or dance studios, school auditoriums, Sunday school rooms, mission meeting halls or gymnasiums. Provides excellent coverage for audiences up to 2000 or areas up to 17,000 square ft. THE AMPLIFIER IS UNCONDITIONALLY GUARANTEED FOR ONE FULL YEAR.

THE COMPLETE PERMANENT SYSTEMS INCLUDE: One 20-watt Model PA-61 amplifier, complete with tubes; 2-12" heavy duty PM 15-watt speakers; 2-35' ft. speaker cables and plugs; 2 polished walnut wooden wall baffles; your choice of either the Electro-Voice 727SR Crystal microphone complete with detachable desk stand for desk, table top or hand use, and with on-off switch, or the Lafayette Model PA-31 slim crystal mike with on-off switch, lavalier cord and bracket and complete with 7' cable and connector and removable swivel-type stand adaptor; you also get the popular Atlas MS-10C mike floor stand for a complete, convenient public address "package." For 110-130 volts, 60 cps AC use. Shpg. wt., 57 lbs.

- PA-136WX 20-watt Permanent System, less Phono Top, complete as described with E-V 727SR microphone. Net 76.50
- PA-137WX Same as above, with Lafayette PA-31 Microphone. Avg. shpg. wt., 67 lbs. Net 70.50
- PA-138WX Same as PA-136WX with 4-speed phono top. Net 94.50
- PA-139WX Same as PA-137WX with 4-speed phono top. Avg. shpg. wt., 67 lbs. Net 88.50
- PA-61WX Amplifier only; Shpg. wt., 19 lbs. Net 42.50

DUAL-SPEAKER 30-WATT PORTABLE SYSTEMS



The most popular system for schools, RR waiting rooms, gyms, churches, noisy factories. Ideal for rentals.

110⁵⁰
NO MONEY DOWN

- CHOICE OF DELUXE DYNAMIC MIKES
- TWO 25-WATT SPEAKERS • MONEY-BACK GUARANTEE

This 30-watt system is one of our most popular models. Large enough for the majority of sound system applications — used in thousands of school auditoriums, churches, theatres, dance halls, dance studios and lecture halls. The ideal system for rentals; these systems have been sold to many hundreds of dealers. **AND REMEMBER OUR MONEY-BACK GUARANTEE AND OUR LOW, LOW PRICE! DUAL SPEAKER 30-WATT PORTABLE SYSTEMS INCLUDE:** The outstanding feature-filled Lafayette Model PA-62 30-watt amplifier; 2—25-watt PM speakers; 2—35' speaker cables and plugs; your choice of the popular Argonne AR-3 All-Purpose Dynamic dual-impedance microphone for hand-held, desk stand or floor stand use, with removable ball-joint desk stand and floor stand adaptor and 8' cable; or the deluxe dual-impedance Electro-Voice 664 Cardioid dynamic microphone for use where high-feedback problems exist, with 40-15,000 cps response, on-off switch and 18' cable; the famous Atlas MS-10C floor mike stand; and the handsomely designed split-type portable carrying case covered in high quality dark blue leatherette. Size of case 22 1/2"Hx16 1/2"Wx15"D — provides a secure place for the system components. For 110-130 volts, 60 cps AC operation. Shpg. wt., 75 lbs. less phono; with phono 85 lbs.

PA-232WX 30-watt Portable System, Less Phono Top and less MS-10C floor stand, complete as described with Argonne AR-3 dynamic mike Net 110.50

PA-233WX Same as above, with E-V 664 dynamic microphone and MS-10C floor mike stand Net 140.50


PA-234WX Same as PA-232WX with 4-speed phono top Net 128.50

PA-235WX Same as PA-233WX with 4-speed phono top Net 158.50

LAFAYETTE 10-WATT FIXED P.A. SYSTEMS



- COMPLETE PERMANENT SYSTEM
 - CHOICE OF CRYSTAL OR DYNAMIC MIKE
 - AMPLIFIER HAS LAFAYETTE'S MONEY-BACK GUARANTEE
- High quality, low cost system engineered for smaller permanent installations. For areas up to 5500 sq. ft. For office, store, garage, small factory paging and music systems. **THE COMPLETE SYSTEMS INCLUDE:** The new Lafayette Model PA-60, 10-watt amplifier complete; your choice of either the Electro-Voice 727 crystal microphone complete with detachable desk stand and 5' cable—or the new Lafayette Model PA-29 weatherproof, blast-proof slim dynamic mike complete with high or low impedance selector switch and detachable swivel-type stand adaptor; 8" heavy duty PM speaker; 35' speaker cable and plug; and attractive polished walnut speaker wall baffle. For 110-120 volts, 60 cps AC operation. Shpg. wt., 25 lbs. (Any other microphone may be substituted in all systems at additional cost. See microphones in index.)
- PA-140WX Complete 10-watt Permanent System as described with E-V 727 Crystal Microphone. Shpg. wt., 24 lbs. Net 45.50
 - PA-141WX Same as above, with Lafayette PA-29 dual impedance dynamic microphone. Shpg. wt., 24 lbs. Net 44.00
 - PA-60WX Amplifier only; Shpg. wt., 12 1/2 lbs. Net 29.70



Most Outstanding Values in Wireless History



LAFAYETTE WIRELESS INTERCOM



- Move it from Room to Room—No Wires Needed
- 3-Position Operation Bar-Lever
- Dependable 3" Speaker
- For Home and Office Use
- Add as many Extra Remotes as Desired

2 WIRELESS INTERCOMS
29⁹⁵
NO MONEY DOWN


Lafayette offers the most outstanding intercom value ever! The Lafayette Wireless Intercom offers quality performance at an amazing low price. Features a three-position operation bar-lever: Dictate (for use as 'baby sitter', lengthy talking), Talk (has spring return to Listen position), and Listen. Can be plugged into any 117V outlet—move from room to room, no wires to connect. Front panel has volume control plus easy-to-see pilot light. Rear panel has adjustable squelch control. Dependable 3" speaker. For use in the home and office and use as many remotes as you need. Shpg. wt., 10 lbs.

PA-294 2-Station Intercom
Extra Remote for PA-294. Shpg. wt. 5 lbs.
PA-293

Net 29.95

Net 15.25

EASY-PHONE TELEPHONE AMPLIFIER




with Batteries • Amplifies Telephone To Room Volume
• 4 Transistors + Varistor • No Dangling Wires, Pick-ups To Connect • No Warm-Up, Instant Operation
17.50

The Lafayette Easy-Phone Telephone amplifier amplifies the telephone to room volume, making it ideal for use in the office or at home. Place the telephone receiver on the easy-phone and both hands are free for writing or typing. At home the entire family can listen in on telephone conversations—a great money-saver for long-distance telephone calls. The Easy-Phone is always ready for instant use. A 4-transistor, battery-powered amplifier and inductive pickup, completely installed in an attractive plastic case, compose the Easy-Phone. Completely self-contained without protruding plugs and twisted hook-up cords. Operation is this simple: by placing the tele-

phone receiver on the Easy-Phone you automatically turn on the amplifier, then adjust the volume to the desired level. The volume control is a separate control. Features 4-transistor circuit, with 1 varistor, powered by 4 penlight 1.5V batteries. 3" dynamic speaker is out of view, under the amplifier. Black, heavy Bakelite case with 2 sturdy chrome plated runners. Weighs only 25 ozs. With miniature plug and jack for recorder input. Overall: 8 3/4" L, 3 1/4" W, 2 1/4" H. Shpg. wt., 3 lbs.
F-759 with Batteries Net 17.50
Extra Batteries for Above. Net .095
BA-155 Penlight Battery

FAMOUS BRAND 2-STATION INTERCOM



• SMART STYLING
• ALL-METAL CABINET
• 4" SPEAKERS
• CABLE SUPPLIED
13.95

New! Low cost intercom system that combines smart new styling with quality performance. A Lafayette special, this 2-station intercom is a must for your home, store, or business office. Units come complete with 50 feet of interconnecting cable and will save you thousands of steps and needed energy. An additional remote station may be added if needed at very low cost. The Master unit has its own volume control with "on-off" switch. No switch is necessary on remote. Power consumption is only 29 watts. This set uses a 12A17 Dual-triode amplifier plus a Selenium rectifier. 4" Alnico speakers are used in both Master and Remote. 110 Volts AC or DC. Measures only 6 1/2" x 4 1/2" x 4 3/8". Shpg. wt., 6 lbs.
PA-269 2-Station Intercom complete Net 13.95
PA-270 Extra Remote Station Net 5.83

LAFAYETTE 2 and 3 STATION TRANSISTOR INTERCOM SYSTEM

Formerly ~~24.95~~ **18.95**
Formerly ~~36.50~~ NOW **26.95**

FEATURES: • All-Transistor Printed Circuit • True 3 Station System (PA-265) • Small Size and Lightweight • May Be Wall Mounted

Now have a deluxe 2 or 3 station system which is durable, versatile and attractive too! Easy to operate: with master unit—just push the press-to-talk button to speak and release it to listen. When talk is finished press Wait button. Remote unit to Master—just press Call button. In addition, the PA-265 is a true 3 station system; there is no call interference—each remote may be called separately, thus assuring privacy and less confusion. Three transistors in a rugged printed circuit and 3 1/2" speakers provide ample volume and low drain on 4—1.5 volt size C flashlight batteries (not included). Light in weight, units may be desk or wall mounted as desired. Plastic body is finished in gray and dark blue, styled to match any decor. Shpg. wt., 5 lbs. Size 1 1/4" x 5 1/2" x 3 1/4" D.
PA-264 2-Station Intercom Net 18.95
PA-265 3-Station Intercom Net 26.95
WR-12 100 Ft. 2 conductor wire Net .80
WR-13 250 Ft. 2 conductor wire Net 1.90
BA-156 Batteries for above—4 required Net ea. .10

4j **FOURJAY**

17.05

The Patio Pair consists of a separate loudspeaker baffle with weatherproof speaker, and an attractive patio lamp. Identical in styling in green and white fiberglass with pipe fitting for 1" pipe. Speaker provides even dispersion of sound. Lamp accommodates up to 100-watt bulb.
Model S-DF1 8 WG Speaker Baffle. Includes 10-watt, 8" weatherproof speaker with 40-11,000 cycle range, 8-Ohm voice coil. Shipping weight 6 lbs. less lamp PE160 Net 17.05
Model LMP 60/100 WG Lamp. Includes weatherproof ceramic socket, less bulb. Shipping weight 4 lbs. PE161 Net 10.95

NEW! LAFAYETTE HI-FI "THIN LINE" CEILING & WALL BAFFLE SPEAKER


Absolutely Incredible Sound Quality!
5.95

- Measures Only 2 1/4" Deep • Employs New Inverted Magnet
- Perfect for Hi-Fi Extension Speaker or P.A. Use
- Only 2 1/4" Deep • New Inverted Magnet

Frankly we were amazed at the phenomenal musical quality of this speaker. Never before have we heard a speaker of this size reproduce the true sounds of loud orchestral passages, drums, etc. with such definition and clarity. The perfect speaker to furnish music or paging throughout your home, office or factory. Advanced design employs an inverted magnet, placing the 12 oz. magnetic structure in front of the speaker rather than behind as in conventional speakers. Only 2 1/4" deep with its own metal baffle plate, the SK-175 easily mounts in any wall, ceiling, closet or ordinary wood enclosure. Two are perfect for stereo. Voice coil is 1" Diam. Frequency Response: 90-9,000 cps. Impedance: 8 ohms. Overall Dimensions including metal baffle is 9 1/2". Requires 6 3/8" wall cutout. Shpg. wt., 3 lbs.
SK-175 Net 5.95

FANON 6-STATION ALL-TRANSISTOR INTERCOM

• Ideal for Wall and Door Mount
Transistorized Intercom System ideally suited for home use—for 2-way conversations, monitoring, and door answering service. Will control up to 5 remote stations. Simple hook-up switch conserves battery yet remote can signal master by pressing "Talk-Listen" switch. "Battery-Saver" switch provides limited battery drain for monitoring. Operates from 9 volt battery. Complete with plastic box for mounting. Size: 11 1/2" x 5 1/2". Shpg. wt. 5 lbs.
PA-210 Net 35.25
BC Flush Wall Mount remote for indoor use. Shpg. wt., 1 lb. Net 5.95
PA-197 BJ Same as BC except with phono jack. Net 8.95
BD Flush Wall Mount remote, for outdoor use. Net 5.95
PA-199 Shpg. wt., 1 lb. Net 7.50
BDR Flush Wall Mount remote, for outdoor use, with bell button. Net .75
PA-200 Shpg. wt., 1 lb. Net 2.45
PB plaster box for use with BC, BD, BDR, BJ remotes. Net 1.26
PA-201 Shpg. wt., 1/2 lb.
WIRING REQUIREMENTS
Separate 3 cord wire lead for each remote used.
WR-115 3 cord wire. Net per 100'. Shpg. wt., 1 lb. per 100'
9-Volt Battery for PA-210. Net 1.26
BA-182



TRANSISTOR POWER 'PHONE

2-STATION TELEPHONE SYSTEM
• 125 MILE RANGE ON A SINGLE PAIR OF WIRES! • A COMPLETELY SELF-CONTAINED TRANSISTOR AMPLIFIER & BATTERY! • WORKS WITH STANDARD "PENLIGHT" CELLS
• ANY NUMBER OF HANDSETS MAY BE USED IN A COMMON TALKING SYSTEM!
Quantity LIMITED
Lafayette brings you these unique transistorized telephone handsets at extremely low cost. Each handset is complete with its own transistor amplifier, buzzer, press-to-talk pushbutton switch, buzzer pushbutton switch and shielded coiled cord (extendable to 6') with male and female connectors ready to connect to 2-wire cable. Each handset is handsomely styled in heavy, high impact resistance, moulded plastic. All stations are connected to the same 2-wire cable, and good signals can be received up to 125 miles with #22 wire! Everything is self-contained in each handset, and any number of handsets can be utilized. Burgess "Z" or RCA VS034 battery cell. SHIPPING WEIGHT (PER PAIR)—3 1/2 lbs. Complete with Batteries.
PA-8 2-Station Transistor Telephone System (2 units) Net 19.95
PA-6 Single Transistor Telephone Unit. Shpg. wt., 2 lbs. Net 10.95
BA-155—Burg. Z or equiv. (1 per handset). Shpg. wt., ea. 1 lb. Extra battery Net ea. .055
WR-221 ALPHA 1172 2-wire cable for telephone systems. Shpg. wt., 1 lb. per 100' Net 2.41

WESTERN ELECTRIC TYPE SG-1 SOUND POWERED HANDSETS.



5.98

Simple 2-way communications for miles. No batteries required. Just connect phone clips to two conductor wire. Excellent for Private Intercom System, Construction, TV Installer, Motels, Camps, Farms, Factories, Stores, Homes, Ski Resorts, etc. Any number of handsets can be installed on one line. Complete with retractable cord and alligator clips. Shpg. wt., 4 lbs.
PA-375 Net 5.98
PA-376 Set of two Handsets with 100 ft. of 2 Conductor Inside-Outside Wire Net 12.75

6 PUSH-BUTTON TELEPHONE



16⁹⁵

- 6 Illuminated Type Buttons
- Made by Western Electric
- Complete with Dial and Ringer

Popular cradle-type phone with 6 push-buttons that can be illuminated. Reconditioned like new and guaranteed to work. Ideal for intercom and private phone systems. Size and appearance may vary slightly. Factory packed. Shpg. wt., 10 lbs.
PA-377 Net 16.95

WESTERN ELECTRIC HANDSET

4.25

Dependable, rugged Western Electric F-1 Handset. Has countless valuable applications for intercom, private phone, etc. Reconditioned for fool-proof service. Complete with retractable cord. Shpg. wt., 1 lb.
PA-379 Net 4.25

3 CONDUCTOR COILED CORD

Exceptional value in a tough, 3-conductor coiled cord with strain relief. Excellent for phones in private phone systems, intercoms, etc. Extends to 6'. Shpg. wt., 1/2 lb.
PA-378 Net .89

Lafayette has the RIGHT Microphone at the RIGHT Price!



LAFAYETTE MOBILE COMMUNICATIONS PUSH-TO-TALK DYNAMIC MICROPHONE

2.95

- Compares With Microphones Selling For More Than Twice The Price
- With Bracket For Mounting on Transceiver
- High Impedance 50K Ohms

SPECIAL CLOSEOUT Limited Quantity

This rugged hand held dynamic microphone is perfect for all mobile and industrial applications—amateur ham radio and (citizens band), police, ship to shore, public address and aircraft. Handy slide switch operates microphone and relay circuits for transmit and receive switching. Response 100-9,000 cps. High Impedance—50,000 ohms. Complete with mounting bracket. Attractive impact-resistant polystyrene case with 5 ft. single conductor shielded cable plus two color coded switching conductors in one plastic jacket. Supplied with instructions for hook up of color coded leads. Size 3x1 3/4x1". Shpg. wt., 1 1/2 lbs. PA-77

Net 2.95



NEW! DYNAMIC PUSH-TO-TALK MICROPHONE FOR CITIZENS BAND TRANSCEIVERS

8.95

- Specifically designed For CB Use
- Momentary-on Spring Return Switch
- Lightweight
- Deluxe Styling

Lafayette now offers a new top quality dynamic microphone at an unusually low price. Specifically designed for citizen band and communication transceivers. Attractive design in black and chrome; tapered styling to fit the hand easily. High impedance dynamic transducer will not be adversely affected by heat and smooth frequency response of 100 to 11,000 cycles make it most suitable for communications work—indoors or out. Comes equipped with a momentary push-to-talk switch, coiled rubber cable with a 5 prong plug and a convenient hang up bracket. Shpg. wt., 1 lb. PA-274

Net 8.95

STEREO

DYNAMIC MICROPHONE

Polar Pattern For PA-263

- 2 Separate EXCLUSIVE OMNI-DIRECTIONAL PATTERNS 90° APART GIVING FULL 360° PICK UP.

LAFAYETTE Brings Quality to Stereo Sound Applications AT A PRICE YOU CAN AFFORD With The New Revolutionary STEREO DYNAMIC MICROPHONE


- Outstanding Performance Characteristics Compatible For Both STEREO and MONAURAL Operation.
- IDEAL FOR TAPE RECORDING OF LARGE Orchestras, Band Concerts, Stage Plays, Small Musical Combos, and All Other Microphone Uses.
- Excellent For Use With School Dramatic Groups.
- SEPARATE SWITCH FOR EITHER MONAURAL OR STEREO OPERATION.
- Satin Chrome-Plated, All-Metal Construction.



17.95

Net 17.95

Lafayette offers a new, outstanding flexible stereo dynamic microphone. Designed by leading audio engineers, the PA-263 offers you outstanding performance at a price you can afford. Completely eliminates need for two mikes. Constructed and designed to obtain the optimum in stereo effect and monaural pick up. Also—excellent for pick up of "reverberation" for full dimensional sound. Mounted on top-plee-proof, heavily weighted, all metal base. Uses gland type swivel joint. Also—adaptable to all type floor stand mounts. Frequency response 50-15,000 cps. Practically flat 80-10,000 cps. Impedance 50K ohms. Polar Pattern—2 omni-directional patterns 90° apart. Comes complete with mike cable. Shpg. wt., 6 lbs. PA-263



11.95

NEW! DUAL IMPEDANCE SLIM DYNAMIC MICROPHONE

- RUGGEDLY CONSTRUCTED
- ON-OFF SWITCH
- 600 & 50,000 OHM IMPEDANCES SELECTED BY SIMPLE ROTATION OF PLUG

Beautiful, professional-looking dynamic with solidly-cast, tapered, slim case with satin-chrome finish. Heavy duty slide-type on-off switch. Built-in transformer supplies dual unbalanced impedances—low Z is 600 ohms, high Z is 50,000 Ohms. Swivel mount fits all standard 5/8"-27 threaded stands. Blast filter eliminates unpleasant "pops" with voice use. Omnidirectional when used vertically—cardioid pattern when tilted. Engineering design and finish are of the highest quality, making this microphone excellent for any application. Complete with 5 ft. plug-in cable. Shpg. wt., 2 1/2 lbs. PA-46

Net 11.95

TRANSISTORIZED MIKE MIXER



6.95

- Up to 4 Channels
- Matches Hi Impedance Microphones

A compact microphone mixer capable of providing professional results. Mixer controls from one to four signals from hi-impedance microphones, tuner, phonograph and/or recorder. Permits amplifying or fading of any channel while holding the volume of other channels. Inputs accept standard 2-circuit phone plugs—output jack accepts standard circuit phone pin plugs. Requires single 9-volt battery (not supplied). Size 6x2 1/4x3 1/4"D. Shpg. wt., 1 1/4 lbs. PA-292

Net 6.95

BA-2 Battery for above

ARGONNE ALL-PURPOSE DYNAMIC MICROPHONE

- IDEAL FOR TAPE RECORDING, PAGING, COMMUNICATIONS
- DUAL IMPEDANCE—250 & 50,000 OHMS
- USABLE RESPONSE 50-18,000 CPS
- FOR HAND-HELD, DESK OR FLOOR STAND USE



13.95

Net 13.95

Here is a flexible dynamic microphone with characteristics suitable for almost any application. Ruggedly constructed, with tapered cast-metal body and removable base for desk use. Mounts to the base by means of a 360° swivel adjustable ball joint and fitted with an adapter for standard 5/8"-27 floor stand. SPECIFICATIONS: FREQUENCY RESPONSE—Practically flat 80-10,000 cps; ± 5 db 70-13,000 cps. OUTPUT—70 db below 1 volt/microbar at 1,000 cps. DUAL IMPEDANCE: Low (250 ohms), High (50,000 ohms) unbalanced. Size 9" high (with base), 2" diam. at head, tapering down to 3/4". Base diam. 4 1/4", 1 3/4" high. Shpg. wt., 6 lbs. AR-3 Dynamic microphone, complete with base, floor stand adapter, and 8' cable

HIGH QUALITY TOP NOTCH CRYSTAL MICROPHONE



3.95

PRICED EXTRA LOW! COMPARE FOR VALUE

Lafayette makes history with a high quality CRYSTAL MICROPHONE at a price that is less than any comparable Crystal Microphone on the market today. Excellent for PA systems, home recorders and general applications. Frequency response 30 to 10,000 cycles. Output level—52 db. provides ample output for use with low gain amplifiers. Uses quality moisture sealed crystal; Die cast case in rich green baked enamel finish, with chrome grill. Completely equipped with 5 feet of shielded cable. Mike may be used on any stand with 5/8"-27 thread. Grill diameter 2 3/4", depth 4/4", height 4 1/2". Shpg. wt., 3 1/2 lbs. PA-24

Net 3.95



3 WAY SLIM CRYSTAL MICROPHONE

- May be hand-held, stand mounted or suspended by lavalier cord!
- RESPONSE 60-10,000 CPS
- ON-Off Switch

13.95

A tremendous value! Unique design, only 4 1/2"x1 1/2" diam. Comes complete with swivel adapter to fit all standard mike stands, and lavalier cord and bracket which leaves both hands free. Smooth wide range response. Locking type on-off slide switch. Detachable 7 ft. cable and connector. Shpg. wt., 2 lbs. PA-31

Singly Each

3.95



STUDIO CRYSTAL MICROPHONE

- DUAL CRYSTAL CARTRIDGES
- ALL DIRECTIONAL
- FINE QUALITY
- HIGH OUTPUT

4.95

Here is a microphone with a 360° pickup, and the added power and sensitivity of two individually shock mounted and phased crystal cartridges. This arrangement assures you of maximum pickup from all sides. Swivel mounted to give full flexibility. Case is chrome plated. Standard 5/8"-27 thread. Overall size 7x3 1/2"W complete with 4 ft. cable. Shpg. wt., 4 lbs. PA-17

Net 4.95

PUSH-TO-TALK CARBON MICROPHONE



6.95

- Retractable Coiled Cord
- Shaped to Fit Your Hand
- Convenient Push-To-Talk Switch
- Outstanding Performance at a Low Price

A hand-held microphone ideal for mobile communications. Designed to fit your hand comfortably with easy-to-reach, easy-to-use push-to-talk switch. Furnished with hanging bracket for convenient mounting. Sturdy plastic case. Frequency response: 200-4,000 cps. Low impedance. Shpg. wt., 1 lb. PA-262

Net 6.95

GUITAR MICROPHONE



MAGNETIC TYPE ALNICO V MAGNET **6.95**

FOR GUITAR Complete with Individual Volume Controls

High impedance contact type microphone specially designed for use with guitar. Easily mounted under strings without special attachments. Separate variable tone and volume controls permit wide adjustment to suit personal requirements. While in mounted position, microphone unit can be raised or lowered easily on rod to create varying tonal effects. Supplied with 8 ft. cable and attached standard size phono plug for connection to amplifier. Shpg. wt., 2 1/2 lbs. PA-38

Net 6.95



POPULAR MIKE CONNECTORS

Standard single contact, cord mounted, nickel plated brass, knurl grips, 5/8"-27 thread. Shpg. wt., 3 oz. MS-467 Female connector Fig. A Net .22 MS-468 Male connector Fig. B Net .16


NEW HI-IMPEDANCE CRYSTAL MIKE

- EXCEPTIONAL PERFORMANCE AT AMAZINGLY LOW PRICE
- IDEAL REPLACEMENT MIKE FOR TAPE RECORDERS

2.95

An attractive high quality microphone that is outstanding for tape recorder as well as countless applications requiring a reliable hi-impedance crystal microphone. Has a frequency response of 30-10,000 cps and an output level of -51 db. Can be used as very neat desk microphone or can be conveniently held in hand. Housed in neat plastic case and is supplied with 8 foot flexible, single conductor shielded cable. 3x2 1/4". Shpg. wt., 1 lb. PA-73

Net 2.95



REMOTE MICROPHONE VOLUME CONTROL

1.76

No more running to the P.A. amplifier to adjust volume. Now, control volume output right at the microphone. Attached between the microphone and the cable; Can be used at any desired distance. Fitted on one end with a female mike connector and male mike connector on the opposite end. Shpg. wt., 12 oz. MS-755 Remote Volume Control

Net 1.76

NEW "DYNA-SLIM" MICROPHONE

- HIGH IMPEDANCE—50,000 OHMS
- ON-OFF SWITCH
- "QUICK-SLIP" ADAPTER

6.95

New dynamic, high output microphone with many features of "mikes" sold above Lafayette's price! Output level—55 db. Smooth response from 60 to 10,000 cycles. Omnidirectional head. External on-off switch. Slips on or off stand adapter in a wink. Standard 5/8"-27 adapter permits tilting mike for multi-angle use. Satin black and chrome finish. Complete with detachable cable and connector. 8" long, 1 1/4" max. dia. tapered barrel 7". Shpg. wt., 2 lbs. PA-43

Net 6.95

Lafayette ACCORDION MICROPHONE




5.95

- Supplied with Backstrap
- Easy-to-Install
- Tone and Volume Controls
- Ideal for Beginners and Professionals

Now accordion owners may enjoy all the advantages of electronic amplification previously limited to stringed instruments. The PA-101, coupled with an amplifier-speaker or P.A. system, provides flexibility impossible with an accordion alone. Alone, it provides a direct pickup for tape recording, eliminating the extraneous noise picked up by a conventional microphone. Included are a case-mounted control bracket containing the volume and tone controls, an output jack, a 10 foot connecting cable complete with phone plugs on both ends, and installation instructions. Shpg. wt., 2 lbs. PA-101

Net 5.95

ATLAS MICROPHONE STANDS



1.76

2.94

Model DS-5. "Velvet Action" Desk Stand. Same quality as floor models. Base dia. 6". Finished in gun metal shivel. Fixed ht., 4". Shpg. wt., 2 lbs. MA-23

Net 1.76

Model DS-7. As above but with ht. adj. 8 to 13". Shpg. wt., 3 lbs. MA-24

Net 2.94

BENDIX RADIATION MEASUREMENT SET



CD V-756

Certified by Bendix to Meet or Exceed Office of Civil Defense Mobilization Specifications

- Simple To Use
- Direct Reading
- Pocket Size
- Rugged — Reliable — Portable

24.95
NO MONEY DOWN

Set Includes:

Bendix CD V-736 Ratemeter (0-120 r/hr)—Indicates precisely how much radiation is present at a given moment

Bendix CD V-746 Dosimeter (0-600 r/hr)—Records total radiation exposure

Bendix VD V-756 Charger—Charges and retests the Ratemeter and Dosimeter to zero


The Bendix Radiation Measurement Set is extremely simple to use. To read the calibrated scales just hold them up to a light source. The Charger is used to reset the hairline indicators to zero before new readings are taken. The Ratemeter measures the amount of radiation at a given moment. There are two scales: one calibrated from 0-120 r/hr for reading one minute after exposure; the second calibrated from 0-12 r/hr for reading 10 minutes after exposure should the first reading be below 10 r/hr. The Ratemeter may also be used in industry for determining protection in any isotope program. The Dosimeter records total radiation exposure and is calibrated from 0-600 roentgens.

TE-666 Complete Set, Shpg. wt., 5 lbs. Net 24.95
TE-668 Pocket Dosimeter; shpg. wt., 1 lb. Net 11.25
TE-669 Pocket Ratemeter; shpg. wt., 1 lb. Net 11.25



CD V-746

CD V-736



NEW LAFAYETTE PHOTO-ELECTRONIC RELAY SYSTEM

Includes Photo Cell Receiver Plus Electronically Operated Relay Plus Exciter Lamp
Efficient 2-Unit, 3-Element Design



- Complete — Ready to Operate — NOT A KIT!
- Operates Bells, Buzzers and Counters.
- The Perfect "Guard for Homes, Stores and Industry"
- Removable Infra-Red Filter For "Invisible-Light" Operation

Only 18.95 Per Set

18.95



The Lafayette Photo-Electronic Relay is your key to an inexpensive indoor warning or counting system. Consisting of a rugged exciter and relay unit and operating on 110-120V AC, it can be connected to signal persons entering a room, counting people or merchandise or function as an effective alarm system to warn of intruders. Effective up to 23 feet (without filter, 15 to 18 feet with filter), relay unit has a convenient variable sensitivity control and switch for continuous or intermittent alarm operation. Exciter has removable infrared filter. Mounts easily across area to be supervised. Metal case. Size: 4 1/4" x 3 3/4" x 4 1/2" D. PC-40 Shpg. wt., 6 lbs. Net 18.95

ACCESSORIES FOR ABOVE

EL-85 Electric Bell, 110V AC, Shpg. wt., 2 oz. Net 1.49
EL-86 Electric Buzzer, 110V AC, Shpg. wt., 10 oz. Net 1.29
F-553 6-Digit Electric Counter, Shpg. wt., 1 1/2 lbs. Net 9.95

LAFAYETTE HOME FIRE ALARM



NO MONEY DOWN

29.95

- UL Approved Detectors
- Loud - Clear Alarm
- Complete Signal Unit - 6 Detectors

Sensitive thermostatic detectors—located in every potential fire area—react to heat instantly. The alarm alerts you and your family before flames spread. The system does not depend on house current for operation. Long life, heavy duty battery will last at least one year. System is readily checked by means of a heat button. The push button kept within easy reach of bed, serves as an intruder alarm. Provision is made in the signal unit for attaching another alarm (6 volt bell, buzzer or horn) for outside or remote locations. The signal unit is completely enclosed in a chrome plated steel housing. Measuring only 4 1/2" x 5 1/2" x 3 3/4" overall—can be located in any convenient area. Detectors, only 2" in diameter, are unobtrusive and cover areas up to 400 sq. ft. System includes signal unit with 2 horns and provision for a 3rd 6 thermostatic detector switches (four 135°, two 200°) 150 ft. of 18 gauge twisted pair control wire, test button, 2 boxes of staples, battery and instruction book. Shpg. wt., 8 lbs. Net 29.95

ML-290 Net 29.95
135° Detector Switches, Shpg. wt., 3 ozs. Net ea. 1.95
EL-103 Net ea. 1.95
200° Detector Switches, Shpg. wt., 3 ozs. Net ea. 1.95
EL-104 Net ea. 1.95
Test Button, Shpg. wt., 3 ozs. Net .16
EL-30 Net .16
18 Gauge, twisted pair control wire, Shpg. wt., 3 lbs. per 100 ft. Net 1.65
WR-122 100 ft. Net 1.65
WR-123 500 ft. Net 7.50
Replacement battery, Eveready 509, Shpg. wt., 1 1/4 lbs. Net .79
BA-161 Net .79


NEW! MAGNETIC PROXIMITY SWITCH



1.74

An ingenious little device that has untold uses in the home—in a burglar alarm system, electric trains, "magic tricks," and many more. As the magnet approaches the switch, the circuit closes. Hermetically sealed; precious metal contacts; 1 millisecond actuation. 15 watts resistive max. up to 1 amp to 250 volts. Size: 2 3/4" x 1 1/2" with leads. SW-105 Shpg. wt., 3 ozs. Net 1.74

RESET CIRCUIT BREAKER



Prevent overload, and possible damage, to radios, TV, power tools, etc. This reset, thermal switch circuit breaker opens at 2.5 amps. No need to replace fuses, no fumbling in the dark—just press the button to reset the circuit. Easy to install; safest to operate. For 110-120 volts. Size: 2 3/4" L x 5/8" D. SW-106 Shpg. wt., 5 ozs. Net .72

FALLOUT DETECTION METER Made by VICTOREEN

Largest Maker of Civil Defense Instruments

- Large Easy-to-Read Meter
- Simple One-Switch Operation
- Rugged Metal All-Weather Construction
- Includes Full Survival & Operating Instructions

49.95

Designed especially for use by private citizens, this is a civilian model of the official instrument used by federal agencies. Enclosed in a rugged steel case, this instrument has been designed and constructed to withstand extreme shock and immersion. Transistorized circuit requires virtually no maintenance and operates from two easily obtainable flashlight batteries. Extremely simple to use and understand—a child can be taught to operate it. This instrument is an absolute necessity for schools, fallout shelters, offices and plants. Includes manual with full survival and operating instructions. TE-667 Shpg. wt., 5 lbs. Net 49.95
Replacement Batteries (2 required) 1.5 volts BA-157 Net ea. .13



NO MONEY DOWN

24-HOUR TELECHRON TIMER SWITCH



- Complete 24-Hour Movement • Turns on Appliance at Pre-Set Time • Famous GE Telechron Mechanism • Accurate Time Control

4.89

Automatically turns on any radio, TV or similar electrical appliance at a pre-set time, up to 24 HOURS. Genuine GE Telechron movement is safe and dependable. Gold finish dial with black lettering. On-Off-Auto switch in front; timer sets from rear. Overall size 3 1/2" square; 1 3/4" deep; set shaft extends 5 1/2" to rear. SPST switch; 15 amps @ 115 V. For 110-120 volts, 60 cycle, AC. MS-918 Shpg. wt., 2 lbs. Net 4.89

24-HOUR GMT AIRCRAFT CLOCK



- Shows Greenwich and Local Time Simultaneously
- 24-Hour Dial
- Made in Accordance with USAF Specifications
- 8-Day Clock

47.95

A precision 8-day aircraft clock equipped with additional hand which is set for Greenwich time and moves simultaneously with the regular hour hand. Lightweight, unbreakable, oxidized black aluminum case. Winds and sets from the front. 24-hour, 1 1/4" dial. Shpg. wt., 1 lb. F-828L Net 47.95

TELECHRON TIMER SWITCH

- Radio - TV - Appliance Timer
- 60 Minute Sleep Switch
- Simple Installation
- Rated to Handle 1650 watt load
- Efficient Accurate Time Control

5.40

Automatically turns on radios—TV sets—tape recorders "ham" rigs—electrical appliances—at any preset time in a 12 hour period. "Sleep-Switch" allows up to 60 minutes of continuous run prior to "shut-off." Built in alarm for added convenience of "signaling." As easy to set as any electric clock. All controls on front. On-off-auto, 0 to 60 sleep switch, alarm set and time set. Gold finish dial—black lettering. 3 1/2" square bezel. 1 3/4" deep. SPST rated 15 amps at 115 volts, 1650 watt load capacity. For 110-120V, 60 cy. AC only. Shpg. wt., 2 lbs. MS-794 Net 5.40




AIRCRAFT CLOCKS



- Made to Gov't. Specifications
- Mil-C-7939A, AN-5743-2 and AN-5743-L2
- Exceptionally Accurate, Precision Movement
- Panel Mounts In Lab, Plane, Car, or Rack.

Standard equipment in the better airlines. Made in strict accordance with USAF specification Mil-C-7939A, Type A-11, AN-5743-2 and AN-5743-L2. Exceptionally accurate, dependable, precision movement. Runs 8 days on one winding. Big luminous, hands and numerals (61 green phosphorescent), sweep second hand, 24 hour dial, 1 1/8" diameter. Winds and sets from the front. Readily mounted in rack panels, instrument panels, dash boards. Lightweight, unbreakable, oxidized black aluminum case. Shpg. wt., 1 lb. F-775L Net 27.95

RESET CIRCUIT BREAKER



Prevent overload, and possible damage, to radios, TV, power tools, etc. This reset, thermal switch circuit breaker opens at 2.5 amps. No need to replace fuses, no fumbling in the dark—just press the button to reset the circuit. Easy to install; safest to operate. For 110-120 volts. Size: 2 3/4" L x 5/8" D. SW-106 Shpg. wt., 5 ozs. Net .72



1.74

An ingenious little device that has untold uses in the home—in a burglar alarm system, electric trains, "magic tricks," and many more. As the magnet approaches the switch, the circuit closes. Hermetically sealed; precious metal contacts; 1 millisecond actuation. 15 watts resistive max. up to 1 amp to 250 volts. Size: 2 3/4" x 1 1/2" with leads. SW-105 Shpg. wt., 3 ozs. Net 1.74



TELECHRON TIMER SWITCH

Turn on any Appliance up to 1650 watts.

3.95

Genuine Telechron mechanism. Complete 12 hour movement. Can be set to turn on any radio, TV or similar electrical appliance at any preset time. Gold finish dial—black lettering. Timer sets from rear. On-off-auto switch in front. Size 3 1/2" square. 1 3/4" deep. Set shaft extends 5 1/2" to rear. SPST switch, rated 15 amps at 115 volts. For 110-120V, 60 cy. AC only. Shpg. wt., 2 lbs. MS-793 Net 3.95

ELECTRONIC DIMMER SWITCH

2.95

Electronically controlled dimmer switch replaces any ordinary light switch, fits all standard boxes, any standard switch plate. 100% of illumination in Hi position, 40% in Lo position. Saves money by reducing power consumption. Fused to protect against misuse. Controls light mood without wiring changes. Installs in minutes with a screwdriver. Use for night lighting, TV lighting, standby lighting, dining room, children's room. Increases lamp life up to 10 times on dim position. 300 watt capacity. 117VAC. For incandescent lamps only. Shpg. wt., 6 oz. EL-101 Net, ea. 2.95



LAFAYETTE Amateur, SWL Equipment & Kits



Made in U.S.A. **21.95**

The most sensational shortwave economy receiver kit ever offered. A complete shortwave and standard broadcast set which covers the entire region from 550 kilocycles to 30 megacycles. Four whole bands of fascinating programming unavailable elsewhere. Perfect for language students and radio amateurs. Only a regenerative circuit can offer such amazing performance and yet be so simple to build. Building this fine kit is an absolute pleasure — it's so well designed you can't go wrong. Kit includes all the parts you need, and the detailed step-by-step instruction book with its giant pictorial drawings shows you just how to put them together. One front panel knob does all the bandswitching at the flick of the wrist, immediately taking you from band to band. All coils are prewound for greater accuracy. This kit is so easy to build a child who can read would do it (and many already have!) The chassis is completely isolated from the circuit, so there is no shock hazard.

BUILD YOUR OWN NEW! EXCITING "EXPLOR-AIR" 4 BAND RECEIVER KIT



TUNE IN the WORLD

• 4 Bands for total coverage: • 550-1600 Kc broadcast band • 1.7-5.0 Mc, 5.0-14 Mc, 14-30 Mc. shortwave bands • Complete band-switching from front panel • Built-in Big 4" PM Loudspeaker

This precision radio kit is just full of extra features. Complete 4 band coverage of broadcast stations, international broadcast bands, amateur, maritime, fire and police services, yes, even satellite signals. Big 4" speaker and sensitive circuit with 50C5 output stage, 35W4 rectifier and 12A7 regenerative detector and amplifier stages give you all the volume you want. Phone jack for privacy automatically disconnects speaker. All controls are on the front panel: On-Off Volume, Main Tuning, Band Spread, Bandswitch, Antenna Tuning, and Regeneration. 110 volt 50-60 cycle AC-DC power supply lets you use this fine set anywhere. Size: 10x7x5". Everything needed for unexcelled reception is combined in a compact, economical package.

KT-135 EXPLOR-AIR RECEIVER KIT (Less Cabinet) wt., 5 lbs. Net 21.95
ML-150 Leatherette covered Wooden Cabinet for above, 1 lb. Net 2.75

JUST OUT! LAFAYETTE MICROPHONE KIT

6.88



- Specially Designed Ceramic Element
- Frequency Response: 30-10,000 CPS
- Requires Only 15 Minutes Assembly Time

EQUALS MIKES THREE & FOUR TIMES IT'S PRICE

The ideal microphone for audio enthusiasts, amateurs, education and sound laboratories. Employs an attractive lightweight cast aluminum housing with a specially designed rugged ceramic element which is unaffected by temperature and humidity. Frequency Response is 30-10,000 CPS. Sensitivity at 1000 CPS is — 52db. Assembles easily in only 15 minutes. Complete with 36" cable. Size: 1 1/2 x 4 1/2". Shpg. wt., 1 1/2 lbs. Net 6.88

NEW LAFAYETTE 27.255 MC CITIZENS BAND REMOTE CONTROL TRANSMITTER KIT KT-127A



MADE IN U.S.A.

WITH .005% TOLERANCE CRYSTAL TWICE AS GOOD AS FCC REQUIRES! OVER 1 MILE LINE-OF-SIGHT TRANSMISSION! EXCEPTIONAL STABILITY FOR FOOL-PROOF CONTROL OF MODEL PLANES, BOATS AND CARS.

You'll marvel at the neatness, simplicity and dependability of Lafayette's RC Citizens Band Transmitter. Crystal-controlled with a .005% tolerance crystal for extra frequency stability; exceeds FCC tolerance requirements. Fits comfortably in the palm of your hand, yet is unaffected by hand capacitance or motion. Has new attractive wide scale meter for visually tuning transmitter. Wide, non-critical tuning for optimum foolproof performance. Tuning for proper output and antenna loading easily accessible. Complete with telescoping antenna, meter, tube, crystal, alignment tool, all parts and easy step-by-step instructions. FCC license application forms enclosed. Size 10x4x2 1/2". Shpg. wt., 5 lbs.
KT-127A less batteries Net 17.25
BA-157 Burgess No. 2 battery Net .13
BA-1 BATTERY (2 needed) 1.59 ea.


NEW! ANALOG COMPUTER KIT



9.95

- Ideal Introduction to Basic Elements of Analog Computers
- Work Over 50 Experiments
- Easy-to-Assemble with Screwdriver and Pliers
- Learn the Way to Sound Scientific Knowledge

The latest Analog Computer Kit offering a basic introduction to computer theory—gives accurate answers to practical problems. Perform over 50 experiments—multiplication, division, powers, square roots, rocketry, interest, radioactive decay, light, kinetic energy, etc. Level of accuracy better than 5%. The computer consists of a masonite, solid instrument panel, kits, potentiometers, meter, specially calibrated scales, guide and operating booklet. Easy-to-assemble. Shpg. wt., 6 lbs. Net 9.95



NEW! AC/DC BROADCAST RADIO SEMI-KIT

Only

9.95



- ALL MAJOR COMPONENTS PRE-MOUNTED
- CONTEMPORARY STYLING
- 5 TUBE SUPERHETERODYNE CIRCUIT
- FUSED POWER LINE

Imagine the joy of building your own full size table model radio. The perfect kit for beginners. Everything but tools is included in the kit to build this fine radio. All the major components are pre-mounted on the chassis by the factory. Two clearly marked cards identify the few resistors and capacitors necessary to complete the set. No special tools are required for alignment either. A simple procedure is outlined in the Lafayette illustrated instruction manual which will enable you to achieve excellent reception across the entire broadcast band (540-1600 KC) sounds as good as it looks too. Styled in a beautiful contemporary plastic cabinet with a finished back. Vented back provides proper baffling and ventilation for components. 5 tubes (2 dual purpose) plus a high "Q" ferrite rod antenna for better AM reception. Cabinet measures 8 1/2 x 4 1/4 x 4" overall. Muted colors match any color scheme. Tubes: 35W4, 12AV6, 12BA6, 12BE6 and 50C5. For 117 V AC/DC. Shpg. wt., 3 lbs. Net 9.95

NEW! teleSpan™ CITIZENS BAND

TRANSISTORIZED "WALKIE TALKIE"

15.45 Each
2 FOR 29.95 NO MONEY DOWN



Weighs only 8 oz. with battery and case!



- No License, Test or Age Limit
- Superregen Receiver, Xtal Controlled Transmitter
- Transmits and Receives up to 1/4 Mile . . . More under favorable conditions
- Plastic Carrying Case, Earphone, Battery Included


The Ideal Set For Young People

A compact, portable, low cost transceiver set with truly amazing performance. Simple enough for a child to operate—it requires no licenses or tests of any kind under Federal law. Perfect for camping, sports, etc. Rugged 2 transistor circuit features a powerful super-regenerative receiver with plug-in earphone for private listening. Will receive and transmit up to 1/4 mile under average conditions. Fingertip push-to-talk switch provides instant X-tal controlled transmitter operation. Durable printed circuit and 9-volt battery shock mounted, assure reliable operation. A removable telescoping antenna can be carried separately in the carrying case pouch when not being used. On-off switch is only other control. Complete with carrying cases, earphones, antennas and 1.9V battery. Nothing else to buy!

Size: 5 1/2 x 2 1/4 x 1 1/4" D. Shpg. wt., 3 lbs. Net 29.95
ME-37L Set of 2 Transceivers Net 15.45
ME-38L 1 Transceiver No Money Down Net ea. .39
BA-2 Extra batteries for above.

COMPLETE 5 WATT PHONO SYSTEM KIT

23.75



Everything required for a complete Hi-Fi system in this "easy-to-assemble" package—and Lafayette brings it to you at an unbeatable price. The system is centered about the excellent Lafayette KT-92 5 watt amplifier kit (as described above). The ML-24 4 speed turntable employs a rubber shock-mounted friction drive motor for quiet dependable operation. Tone arm is the Lafayette PK-157 containing turnover crystal cartridge with dual sapphire

styli. Completing the system in the Lafayette SK-109 miniature hi-fi speaker system beautifully finished in mahogany veneers and supplied with 25 feet of hookup cable. Speaker measures only 9 1/2 x 7 3/4 x 3 1/8" D. Shpg. wt., 15 lbs. Net 23.75
PK-333WX Unfinished mounting board for ML-24 turntable. Shpg. wt., 1 lb. Net .95
PK-149W

PHONO AMPLIFIER KITS



LAFAYETTE KT-92 5 WATT PUSH-PULL AMPLIFIER KIT

Made in U.S.A.

10.95

- PUSH-PULL AUDIO OUTPUT STAGE • INVERSE FEEDBACK CIRCUIT
- SEPARATE VOLUME, BASS & TREBLE CONTRLS • AC OR DC OPERATION

Here in kit form is an AC-DC hi-fi amplifier that presents unusual features despite its amazingly low price. The separate bass and treble controls permit adjustment of both low and high frequency response and balance. Works equally well with both crystal or ceramic cartridges. Has a 4-tube line up—a 12AX7 amplifier and phase inverter, a 35W4 rectifier and a pair of 35C5's in

push-pull, having a power-packed low distortion output. The circuit utilizes an inverse feedback loop to reduce the level of hum and distortion. Kit is complete containing all essential parts, tubes and detailed instruction manual showing pictorial and schematic diagrams. Shpg. wt., 4 lbs. Net 10.95

LAFAYETTE—Build Your Own KITS....

NEW!
LAFAYETTE KT-199
2-TRANSISTOR
DIODE BROADCAST
RADIO KIT

Made in U.S.A. + **POWERFUL REFLEX CIRCUIT**

AR-50

- No Soldering—A Child Could Build It!
- Pre-wired Switch and Control
- 50 Mile Range
- Beautifully Styled Cabinet

Absolutely no soldering or hole punching is necessary. All wiring and components are connected to fahnstock clips mounted on a pre-punched board. It is the ideal kit for beginners interested in transistor circuits. The on-off switch and level control are already pre-wired—just clip them in. A clear construction manual is included with simple How-To-Do-It instructions so that a child could build it. And that's not all. Lafayette engineers have designed this transistor radio to have a receiving radius of approximately 50 miles! Only one 9 volt battery powers its 2-transistor reflex circuit. Ferrite core loop antenna and a variable gang tuning condenser insure crisp reception on the entire AM broadcast band from 550-1600KC. Will accept any high impedance earphone for private listening. Size: 5½x2½x4¾"D. 2-2N165 PNP transistors, 1N48A diode. Complete with instruction manual. Shpg. wt., 1½ lbs.

KT-199 Complete 2 transistor kit—less earphone and less battery Net 9.95
 Recommended Earphone Net 1.39
 BA-2 9-volt battery Net .39

New! LAFAYETTE KT-196 2-STATION INTERCOM SYSTEM KIT

Made in U.S.A.

- Attractive, Modern Styling
- Complete—One Master and One Remote Station Plus 50 Ft. of Cable
- Perfect as Baby Sitter or Sickroom Watcher
- 2 Complete Stages of Amplification

14.75

The perfect 2-station intercom kit beautifully styled and engineered by Lafayette's Kit Divisions, it will grace any room in the home, office, shop, school, etc. Consisting of a Master Station and a Remote station, most useful to communicate with the basement, garage, playroom or nursery. The master unit features a highly sensitive 3-tube circuit with 2 complete stages of audio amplification for maximum talk-power and sensitive reception. Makes a marvelous "baby-sitter." Remote unit may be left in permanent "Talk" position. Master Station has a 3-way lever switch which provides Momentary Talk, Listen, and a lock-in talk position to free hands for other duties or for extended conversation. Master station front panel also includes a combined on/off switch, volume control. Only the master unit need be plugged into outlet—remote may be placed anywhere. The system may use up to 3 remotes. Famous Lafayette instruction manual simplifies assembly. Size of each unit: 4Hx8Wx4¾"D. Attractive metal enclosures. Tubes: 36AM3A, 60FX5, 18FV6. Complete with all parts necessary and 50 feet of 3-wire cable. For 105-125V 50-60 cycles AC or DC.

KT-196 2-Station Intercom Kit. Shpg. wt., 7 lbs. Net 14.75
 LA-196 Factory Wired Extra Remote Station Kit—For use with above. Less cable. Net 19.50
 KT-197 Shpg. wt., 2½ lbs. Net 3.45
 LA-197 Factory Wired Remote Net 3.95
 WR-160 Hook-up wire for above. per ft. Net .03

NEW!
LAFAYETTE
KT-195
WIRELESS BROADCAST
AMPLIFIER KIT

Made in U.S.A.

Use it either as a Wireless Broadcaster or AM Audio Amplifier!

- POWERFUL SIGNAL
- PLAYS THROUGH ALL AM RADIOS
- WORKS WITH ALL CRYSTAL AND MAGNETIC MIKES AND PHONO CARTRIDGES

11.95

Treat yourself and your family to hours of fun with this new Lafayette Kit. Make your own radio programs, announcements, etc. through AM radios anywhere in the house, without wires or extra gadgets. Designed for easy construction by youngsters or adults, the KT-195 combines in one compact unit a powerful 3-tube wireless broadcaster and an audio amplifier. Clearly written instruction manual makes it a cinch to build. Operates on any frequency between 900 and 1600 kilocycles on your radio dial. It will accept any crystal or magnetic microphone. In addition, the KT-195 may be used directly as a phono or microphone amplifier. No external preamp is required. Simple slide switch permits either form of operation. Just connect it to a PM speaker (4-16 ohms). No external record broadcasts. Is designed to provide high quality voice of wide high quality voice or record broadcasts. No license or permit is necessary. Complete with crystal clear in-styled metal cabinet suitable for any decor.

KT-195 Shpg. wt., 3 lbs. Net 11.95
 Same as above, but factory wired and tested. Net 14.45
 LA-23 Crystal microphone for above. Desk or hand held. 8 ft. cable. Net 2.95
 PA-73 Shpg. wt., 1 lb. Net 2.95

New! 20-in-1 TRANSISTOR Experimenters KIT
FUN TO BUILD — EDUCATIONAL — and all 20 projects result in a useful working instrument

SUPER-SENSITIVE PHOTOCELL ELECTRONIC RELAY KIT

MADE IN U.S.A.

- WITH CLAIREX CADMIUM SULPHIDE PHOTOCELL • ADJUSTABLE SUPER SENSITIVITY—WORKS WITH JUST A FLASHLIGHT AT 250 FEET!
- NEEDS NO SPECIAL HIGH-INTENSITY LIGHTS • INSTANTANEOUS OR SUSTAINED OPERATION ON THE FLIP OF A SWITCH!

12.95

Ideal for sustained operation required for burglar alarms, door buzzers and for instantaneous on-off operation required for counters, packaging, door opening, motor activation plus many less industrial applications. Switch converts unit from "RESET" switch "on-off" to sustained "on" operation. The unit opens the external circuit and turns off the efficient 5823 neon tube. Operates on 110 volts AC and incorporates the efficient 5823 cold cathode tube. A simple change in wiring (in instructions) as well as convenient input terminals, enable you to supply the external circuit with any desired voltage. Relay contacts rated at 3 amps permitting up to 300 watts external load on 110 Volts AC. Complete with all parts, photocell, tube, chassis, silk-screened metal cabinet and easy-to-follow illustrated instructions. Size: 3x4x5" Net 12.95
 KT-133A Kit, Complete. Shpg. wt., 3 lbs.

PROJECTS YOU BUILD

1. TRANSISTOR TESTER
2. VOICE ACTUATED ALARM
3. PHOTO TIMER
4. AUDIO AMPLIFIER
5. CRYSTAL SET
6. SOLAR RADIO
7. RAIN ALARM
8. TIMER
9. ONE TRANSISTOR RECEIVER
10. CODE PRACTICE OSCILLATOR
11. METRONOME
12. TWO TRANSISTOR RECEIVER
13. ELECTRONIC GAME
14. HOME BROADCASTER
15. PHOTO ELECTRIC RELAY
16. BURGLAR ALARM
17. WIRELESS TRANSMITTER
18. REGENERATIVE RECEIVER
19. CITIZENS BAND MONITOR
20. AUDIO OSCILLATOR

Only 18.95

This new Educational Kit opens the field of transistor-electronics, with all its fascinating circuits and gadgets, in a simple, easy-to-follow manner. Excellent for beginners as well as advanced experimenters, this kit enables you to build and learn about 20 interesting and useful transistor circuits. By utilizing "bread-board" construction, each project can be simply wired and traced. After building the basic circuit, any of the 20 projects can be built by simply inserting a few preassembled component blocks and interconnecting leads between them. A soldering iron is only required for the basic wiring and not for subsequent projects. All wiring is covered in a step-by-step manner by the instruction manual. Each of the 20 projects is clearly presented with step-by-step instructions, large easy-to-read pictorial wiring diagrams, schematic diagrams, and an explanation of the circuit behavior. There are no AC voltages to produce shock hazard. Amaze your friends with a Voice-Actuated Alarm, Rain Alarm, Home Broadcaster, and other projects. Build useful projects for the home—Metronome, Burglar Alarm, and Timer. Learning Morse Code with the Code Practice Oscillator and receiving Short-Wave Citizens Band Stations. The kit is complete with perforated mounting board, 2-transistors, 1-diode, earphone, light sensitive plate, and all other parts required for construction. The detailed 28 page instruction manual contains a wealth of information about each project. Less batteries and tools. Shpg. wt., 6 lbs. Net 18.95
 KT-173 Complete Net .095
 BA-155 2 Cell Battery for Kit projects Net 1.61
 BA-270 22½ Volt Battery for Kit projects

LAFAYETTE STEREO PHONO AMPLIFIER KIT

Made in U.S.A.

- 4 WATTS STEREO OUTPUT
- ISOLATION TRANSFORMER
- SEPARATE VOLUME CONTROLS
- GANGED TONE CONTROLS
- STEREO-MONAUROUS SWITCH

18.95

This is a complete 4-watt hi-fi stereo amplifier having 2 watts output per channel. Features separate volume control for each channel; ganged tone controls; stereo-monoaural switch to feed one channel to both speakers; stereo-monoaural switch for each right for use anywhere a small stereo amplifier is required—ideal for custom mounting in even the tightest locations. Excellent for small apartments. Complete with instructions. For 3.2 or 8 ohm speakers. Tubes: 2-50C5, 2-12AX7 plus selenium rectifier. For 110-120 volts, 60 cycle AC. Net 18.95
 KT-126 Kit, Complete. Shpg. wt., 7 lbs.

LAFAYETTE 10-IN-1 LABORATORY KIT

WITH THIS KIT YOU CAN BUILD

1. RADIO RECEIVER
2. PHONO-MICROPHONE AMPLIFIER
3. PHONO OSCILLATOR
4. BROADCAST STATION
5. CODE PRACTICE OSCILLATOR
6. SIGNAL TRACER
7. CAPACITY OPERATED RELAY
8. ELECTRONIC TIMER
9. ELECTRONIC SWITCH
10. PHOTOCELL RELAY

Here is a new laboratory tested experimenters kit designed to provide maximum instruction and entertainment and which is ideal for both the beginner and advanced experimenter. Features practical and interesting circuits which enable you to do many novel and interesting things while learning how these circuits function. You can broadcast your voice or play a phonograph through your radio from anywhere in the house, send code through a headphone or radio, or use light or body capacitance to activate electrical circuits. Safe, low voltage is utilized. Kit is complete with perforated mounting board, 3 vacuum tubes, microphone and all parts necessary for construction. A detailed 12 page instruction manual contains simple-to-follow pictorial and schematic diagrams for each project. Less headphone, photoelectric cell and socket, wire and solder.

KT-36A Shpg. wt., 5 lbs. Net 15.50
 PHOTOELECTRIC CELL TUBE TYPE 868. Shpg. wt., 8 oz. Net 3.75
 CM-70 AMPHENOL 77M1P4 SOCKET FOR ABOVE. Shpg. wt., 1 oz. Net .13
 ME-33 CANNON AM-15-1 1000 OHM SINGLE HEADPHONE. Shpg. wt., 1 lb. Net 1.18

15.50

COMPLETE STEREO PHONO SYSTEM KIT

NO MONEY DOWN • Save By Building This Excellent Stereo Amplifier • Plays Both Stereo and Monoaural Records

39.95

Enjoy fine stereo performance with this "easy-to-assemble" exclusive Lafayette package. The complete system consists of the Lafayette KT-126 Stereo Phono Amplifier Kit (as described above), Lafayette ML-24 4-speed Turntable for 16½, 33½, 45 and 78 rpm records, Lafayette PK-171 Stereo Tone Arm with the wide range Plug-In Crystal Cartridge and .75 mil sapphire styli for stereo and monoaural records. Completing the system are 2 of Lafayette's amazing SK-109 miniature speaker systems. Housed in attractive mahogany veneer enclosures, each speaker is supplied with 25 feet of hookuo cable and measures only 9½x7¾x3¼"D. PK-454WX Shpg. wt., 22 lbs. Net 39.95
 Unfinished mounting board for ML-24 Turntable. Shpg. wt., 1 lb. Net .95
 PK-149W

NEW! ELECTRONICS EDUCATIONAL KIT

Complete With 116 Page Instruction Manual — Virtually A Textbook & Laboratory Manual

- 194 ILLUSTRATIONS
- INCLUDES QUESTIONS & ANSWERS FOR EACH SECTION
- CLEARLY WORDED STEP-BY-STEP INSTRUCTIONS
- COVERS BOTH AC & DC IN THEIR ENTIRETY
- TEACHES, AS YOU BUILD
- 12 COMPLETE EXPERIMENTS RESULT IN A FINISHED AC & DC TEST INSTRUMENT
- ENABLES REPAIR OF HOUSEHOLD APPLIANCES

The fascinating world of electronics introduced in a simple, easy-to-follow manner through this new Lafayette KT-180 Electronic Educational Kit. Not a toy—this kit is a complete beginners electronics laboratory course featuring an extremely useful AC/DC Multitester.

In the process of constructing this test meter, the fundamental principles of electricity and electronics are introduced in a "learn-by-doing" method. The focus of attention is on the basic sensitive meter for measuring the flow of electrical current. From this simple measurement, the meter is built up to indicative voltage and resistance. The detailed 116 page instruction manual contains 194 illustrations and is written in a simple, easy-to-read, step-by-step manner with questions and answers supplied for each section. Providing a virtual "guided tour" of electrical fundamentals, this kit furnishes a complete course in AC and DC including ohms law, series and parallel connections, making electro-magnets, producing electricity by induction and testing house appliances. The kit is supplied less batteries.

KT-180 Shpg. wt., 5 lbs. Net 24.50
 BA-155 (Burgess Z type battery, 2 required) Net ea. .095

COMPLETE STEREO PHONO SYSTEM KIT

NO MONEY DOWN • Save By Building This Excellent Stereo Amplifier • Plays Both Stereo and Monoaural Records

39.95

Enjoy fine stereo performance with this "easy-to-assemble" exclusive Lafayette package. The complete system consists of the Lafayette KT-126 Stereo Phono Amplifier Kit (as described above), Lafayette ML-24 4-speed Turntable for 16½, 33½, 45 and 78 rpm records, Lafayette PK-171 Stereo Tone Arm with the wide range Plug-In Crystal Cartridge and .75 mil sapphire styli for stereo and monoaural records. Completing the system are 2 of Lafayette's amazing SK-109 miniature speaker systems. Housed in attractive mahogany veneer enclosures, each speaker is supplied with 25 feet of hookuo cable and measures only 9½x7¾x3¼"D. PK-454WX Shpg. wt., 22 lbs. Net 39.95
 Unfinished mounting board for ML-24 Turntable. Shpg. wt., 1 lb. Net .95
 PK-149W

LAFAYETTE SEMICONDUCTOR SPECIALS FOR EXPERIMENTER, KIT BUILDER, HOBBYIST

QUALITY SEMICONDUCTORS AT ECONOMY 'PACKAGE' PRICES

10 GERMANIUM DIODES
 Pkg. of 10 germanium diodes that replace 1N34, 1N34A, 1N46, 1N48, 1N51, 1N60, 1N64, 1N64A, 1N87, 1N105, 1N109, 1N147, 1N267, 1N268, 1N295, etc. Shpg. wt., 6 oz.
 SP-234

10 SILICON DIODES
 Package of 10 silicon diodes. Replaces 1N34, 1N34A, 1N46, 1N48, 1N51, 1N60, 1N64, 1N87, 1N295, etc. Shpg. wt., 4 oz.
 SP-235

TRANSISTOR - DIODE PACKAGE SPECIAL
.79 Pkg.
 3 Pkgs. (can assort.) 2.09

4 PNP GERMANIUM TRANSISTORS
 SP-238
 Package of 4 PNP General Purpose Type Transistors similar in performance to 2N107, 2N218, 2N1265, CK722, GT222, TR722, 2N1191, etc. Shpg. wt., 6 ozs.

.79 per pkg.
 Any 4 Asst. Pkgs.
2.85

2 PNP TRANSISTORS
 SP-237
 Mixer/Oscillator Converter - Replaces 2N112, 2N114, 2N135, 2N136, 2N137, 2N140, 2N219, 2N411, 2N412, 2N414B, 2N415, CK760, CK766, 2S52, etc. Shpg. wt., 4 oz.

5 GENERAL PURPOSE DIODES
 SP-218
 Package of 5 germanium glass diodes similar to 1N34A, 1N60, 1N64, 1N87A, etc.

4 PNP TRANSISTORS
 SP-220
 Package of 4 PNP Audio transistors similar to 2N107. Beta 15 minimum.

2 PNP GERMANIUM TRANSISTORS IF AMPLIFIER
 SP-238
 Pkg. of 2 PNP germanium IF amplifier transistors that replace 2N111, 2N111A, 2N112A, 2N139, 2N218, 2N409, 2N410, 2N413, 2N413A, 2N414, 2N414A, 2N416, GT760, 2S53, etc. Shpg. wt., 4 oz.

2 PNP GERMANIUM TRANSISTORS AF AMPLIFIERS (Up to 12 Volts)
 SP-239
 Pkg. of 2 PNP Germanium AF amplifier transistors that replace 2N133A, 2N138A, 2N138B, 2N151, 2N156A, 2N187A, 2N215, 2N217, 2N319, 2N320, 2N359, 2N360-363, 2N407, 2N408, 2N1008, A, B, GT81R, GT109, 2S56, 2S838, etc. Shpg. wt., 4 oz.

2 NPN TRANSISTORS
 SP-219
 Package of 2 NPN germanium transistors similar to 2N170 for Audio & RF. Beta 20 minimum.

2 GOLD PLATED SILICON RECTIFIERS 500 MIL - 400 PIV
 SP-240
 Pkg. of 2 miniature size exceptional 24 karat gold plated silicon rectifiers rated at 500 milliamperes, 400 PIV. Shpg. wt., 4 oz.

2 TOP HAT SILICON RECTIFIERS 750 MIL - 400 PIV
 SP-241
 Pkg. of 2 top hat type silicon rectifiers rated at 750 milliamperes, 400 PIV. Shpg. wt., 6 oz.

STUD MOUNT SILICON RECTIFIER 2 AMPERE 400 PIV
 SP-242
 Outstanding Buy! 2 amp. 400 Peak Inverse-Volts Silicon Rectifier, stud mounting. $\frac{3}{4}$ " long less lug, $\frac{1}{4}$ " hex nut. Shpg. wt., 6 oz.

2-10 WATT POWER TRANSISTORS
 SP-243
 Package of 2 PNP 10 Watt germanium power transistors in popular TO-3 case. Similar to 2N155, 2N176, 2N235, 2N351, 2N242, 2N257, 2N268, 2N301A, 2N255, 2N554, 2N555, etc. Shpg. wt., 8 oz.

40 WATT HIGH POWER TRANSISTOR
 Amazing value is this 40-Watt high power PNP germanium transistor! Excellent for experimenter, hobbyist and kit builder for power supplies, auto replacement, audio output, etc. Similar to 2N173, CTP1504, SFT266, etc. Bolt mounted. Shpg. wt., 8 oz.
 SP-244

LAFAYETTE SPECIAL 6 TRANSISTOR plus DIODE SUPERHET PACKAGE 2.95
 • 6 Transistors plus Germanium Diode
 • Matched for Superheterodyne Push-Pull Circuit
 • Can Work on 9-Volts with Minimum Battery Drain
 • Highest Quality — All PNP
 Consists of 1 converter, 2 IF's, 1 driver, 2 push-pull output and 1 germanium diode. Packed in handy plastic bag. Shpg. wt., 6 ozs.
 SP-246 Net 2.95

LAFAYETTE SPECIAL SILICON POWER RECTIFIERS
 Top hat lead type silicon rectifiers excellent for TV Radio and power supplies as half-wave, full wave rectifiers and voltage doublers.
 Type A: 750 Ma, 400 PIV @ 25°C.
 500 Ma, 400 PIV @ 90°C.
 SP-196 Shpg. wt., 4 oz. Net .57
 10 for 5.13; 100 for 47.00
 Type B: 750 Ma, 200 PIV @ 25°C.
 500 Ma, 200 PIV @ 90°C.
 SP-197 Shpg. wt., 4 oz. Net .47
 10 for 4.25; 100 for 38.50

LAFAYETTE PNP AUDIO TRANSISTOR SPECIAL! AS LOW AS .31
 General audio type PNP transistor for experimenters and hobbyists, for code practice oscillators and similar small signal devices. In new JETC 30 welded case. Net, singly, each .39
 SP-148 Net, singly, each .39
 10 for 3.69 50 for 18.95, 100 for 31.00

GENERAL PURPOSE DIODES .19
 EXCELLENT DETECTOR FOR TRANSISTOR AND VACUUM TUBE RADIO RECEIVERS
 EQUIVALENT TO: 100 for 16.50
 1N34 1N34A 1N38A
 1N48 1N56 1N69
 SP-148 General Purpose Diode Net .19 each 10 for 1.75

2N1265 PNP TRANSISTOR SPECIAL! They're Hot!
 AS LOW AS .39 ea. LOTS OF 100
 IDEAL FOR: AUDIO — IF's, DRIVERS, AND OUTPUT FOR: OSCILLATORS, MIXERS AND CONVERTERS
 SP-171 Net .49
 10 for 4.65; 50 for 22.05; 100 for 39.00

POWER TRANSISTORS AS LOW AS .59
 EACH UNIT Similar To: 2N256 2N307 2N554
 TESTED TO MEET SPECIFICATIONS
 SP-147 Power Transistor In lots of 100, Each Net 69c
 Net 59c

NEW! ULTRA SUB-MINIATURE TRANSISTOR COIL KIT

345

 • Smallest 2 Gang Variable Ever Made!
 • Size: $\frac{1}{16}$ " Square, $\frac{3}{8}$ " Deep
 • 3 I.F.'s and OSC: $\frac{1}{4}$ " Square, $\frac{3}{8}$ " High
 • Ferrite Loop Antenna

All in one kit—a complete set of matched micro-miniature coils, ferrite loop antenna, ultra-compact 2 gang variable condenser, tuning dial and schematic diagram for building a subminiature 6 transistor radio. Kit includes: Shielded and Impregnated High-Q 455 KC IF transformers and oscillator coil—all slug tuned. Proper impedances are provided for optimum circuit performance. Variable condenser has protective case and rear trimmer adjustment. Flat ferrite loop antenna measures $2\frac{1}{2} \times \frac{1}{2} \times \frac{1}{4}$ " thick. Clearly-printed circuit diagram indicates all parts necessary for a powerful 6 transistor receiver. Tuning dial and knob ($\frac{1}{16}$ " dia.) fits securely on V.C. shaft. The ultra-compactness and quality of these essential components allow you to construct a broadcast radio, miniature by today's standards, at tremendous savings. Shpg. wt. of kit is 1 lb.
 MS-828 Net 3.45

SUBMINIATURE TRANSISTOR AUDIO TRANSFORMERS
 A new series of miniature transformers for transistor and experimental miniature circuits. Ideal for miniature radio receivers, amplifiers, hearing aids, etc., using standard transistors. Incorporate special heat-treated high permeability magnetic cores-treated to resist corrosion. Designed for improved frequency response with low distortion. 3" color-coded leads. Average shpg. wt., 4 oz.
 ONLY 79c
 ONLY $\frac{1}{2}$ " x $\frac{1}{2}$ " x $\frac{1}{2}$ "

Stock No.	Circuit	Impedance	Sec. Ω	D.C. Resistance	Net
			Fri. Ω	Sec. Ω	
TR-97	INPUT	100,000	1000	1000	.79
TR-98	DRIVER	10,000	2000 C.T.	240	60 C.T. .79
TR-99	OUTPUT	500 C.T.	3.2	42 C.T.	0.7 .79
TR-120	INPUT	200,000	1000	1400	50.5 .89
TR-116	OUTPUT	500 C.T.	8	50 C.T.	1.7 .79

GENERAL ELECTRIC 2N107 NOW .55 PNP GENERAL PURPOSE TRANSISTOR
 2N107 Net .55

NEW! PHOTO-MULTIPLIER POWER TRANSISTOR
 A COMPLETE PHOTOELECTRIC SYSTEM IN ONE UNIT
 • PHOTO ELECTRIC CELL
 • POWER TRANSISTOR AMPLIFIER 1.79 EA.
 • ELECTRONIC RELAY
 Complete with Instructions, Data and Diagrams for photo control systems, photo-electronic amplifiers; Relays, Alarms, etc.
 SP-256 Ea. Net 1.79 3 for 4.77

NEW! 4 TRANSISTOR SUBMINIATURE PUSH-PULL AUDIO AMPLIFIER—


OUTPUT 100 MW
4.95
 Size: $3" \times 1\frac{1}{2}" \times \frac{1}{4}"$
 • TERRIFIC FOR THE EXPERIMENTER, HOBBYIST AND KIT BUILDER!
 • COMPLETELY WIRED, NOT A KIT!
 • PRINTED CIRCUIT BOARD
 • COMPLETE WITH TRANSISTORS
 A tiny, transistorized push-pull audio amplifier with a multitude of applications. Only $3" \times 1\frac{1}{2}" \times \frac{1}{4}"$, it can be mounted inside other equipment to serve as a subminiature phono amplifier, tape recorder, amplifier, etc. Can be the complement of a homebuilt project which needs only an audio amplifier to make it complete and self-contained. Two stages of audio are followed by a push-pull output stage designed to deliver 100 mw to an 8-11 ohm impedance. Low impedance input, with a sensitivity of 0.9 mv. Input transformer for matching high impedances to the amplifier available as an accessory (see below). Includes leads for input, speaker, and volume control/on-off switch. Battery clips and leads supplied for 9 volt miniature battery (one required). Shpg. wt., 5 oz.
 PK-543 Net 4.95
ACCESSORIES FOR ABOVE
 BA-2 9 volt battery. Shpg. wt., 2 oz. Net .39
 VC-31 50K ohm volume control w/switch. Shpg. wt., 2 oz. Net .69
 SK-193 8 ohm voice coil speaker. 3" Shpg. wt., 10 oz. Net 1.49
 SK-189 8 ohm voice coil speaker. 2" Shpg. wt., 8 oz. Net 1.49
 SK-191 8 ohm voice coil speaker. $2\frac{1}{2}"$ Shpg. wt., 8 oz. Net 1.49
 Input transformer for matching high impedance (mike, etc.) to amplifier. TR-120 Net .89

NEW! 5 TRANSISTOR PUSH-PULL AUDIO AMPLIFIER

6.95
 • ONLY $3\frac{1}{16}" \times 1\frac{1}{16}" \times \frac{1}{16}"$
 • 360 MW OUTPUT
 • COMPLETELY WIRED
 • DIRECT WIRING
 A more powerful and more sensitive version of the PK-543, this amplifier employs 3 stages of audio driving a push-pull output stage. Power output is 360 mw, designed for speakers with a voice coil impedance of 8-11 ohms. Low impedance input has sensitivity of 300 microvolts. Input transformer for matching high impedance to the amplifier input available as an accessory (see below). Comes with leads for low impedance input, speaker, volume control/on-off switch. Battery clips and leads supplied for 9 volt miniature battery (one required). Shpg. wt., 5 oz.
 PK-544 Net 6.95
ACCESSORIES FOR ABOVE
 BA-2 9 volt battery. Shpg. wt., 2 oz. Net .39
 VC-28 10,000 ohm volume control w/switch. Shpg. wt., 2 oz. Net .69
 SK-193 8 ohm speaker. 3" Shpg. wt., 10 oz. Net 1.49
 SK-189 8 ohm speaker. 2" Shpg. wt., 8 oz. Net 1.49
 SK-191 8 ohm speaker. $2\frac{1}{2}"$ Shpg. wt., 8 oz. Net 1.49
 Input transformer for matching high impedance (mike, etc.) to amplifier. TR-120 Net .89

3 TRANSISTOR SUBMINIATURE AUDIO AMPLIFIER

3.75
 • FOR THE EXPERIMENTER, HOBBYIST, AND KIT BUILDER!
 • PRINTED CIRCUIT
 • COMPLETE WITH TRANSISTORS
 Here is an amazing little audio amplifier with a multitude of challenging applications; i.e., subminiature phono amplifier, tape recorder amplifier, hand-held public address amplifier, telephone pick-up amplifier, etc. Output sufficient for average listening. Has leads for any one of the following inputs: Tape recorder record/playback heads, radio-tuner, crystal or ceramic phono cartridge, and crystal or ceramic microphone. Has lead terminations for ON-OFF switch, Volume Control, 4 to 10 ohm speaker, and leads terminating in clips for a 9 volt miniature battery.
 Size $2\frac{1}{8} \times 1\frac{1}{4} \times \frac{3}{4}"$. Can be readily mounted on chassis. Shpg. wt., 8 oz.
 PK-522 Net 3.75
 BA-2 9 Volt Battery Net .39
 5K ohm Volume Control with SPST Switch and Knob; Shpg. wt., 2 oz. Net .59
 VC-62 Net .59
 Miniature Crystal Microphone $1\frac{1}{8}"$ Diam. x $\frac{3}{8}"$ Deep. Shpg. wt., 6 oz. Net 1.49
 MS-108 Net 1.49
 Miniature Speaker $2\frac{1}{2}"$ Diam. 10 ohms Voice Coil Impedance. Shpg. wt., 8 oz. Net 1.49
 SK-66 Net 1.49



PHOTOCELLS AND PARTS FOR KIT BUILDERS, for Experimenters & Engineers



NEW!

LAFAYETTE AUTOMATIC PHOTO-ELECTRIC 'LUMINATOR




- Automatic Light Switch
- Lights on at sunset—off at sunrise

4.95

New photo-electronic, light sensitive switch turns lights on and off at dusk and dawn. Better than a clock—no setting and re-setting of timer. Variance in "on-off" cycle adds extra protection when away from home. You need never come home to a darkened house. The controlled lamps go on as darkness falls—stay on until sufficient day light returns or until manually turned off. Just plug it in for protection from prowlers—turn on night lights—illuminate outdoor areas—light up brooders—green houses—displays—show windows—any place you require automatic illumination. Mounts most anywhere on rubber suction cup feet. Unobtrusive—measures only 3 1/4 x 2 1/2 x 3/4". Use on 117 volt AC only. Maximum 300 watts lamp load. Instructions included. Shpg. wt., 1 lb.

Net 4.95

NEW! 1/10 WATT SUB-MINIATURE CARBON FILM RESISTORS



± 10% TOLERANCE
• High Quality—Low Cost

- Really Miniature—Only .28" L x .08" D.
- Excellent Stability Characteristics
- Extremely Low Temperature Coefficient

Specifically designed for those applications requiring special synthetic resin insulation, withstand high degrees of heat, humidity and shock. Very low temperature coefficient and noise factor. Imported to sell at these low prices. SPECIFY RESISTANCE VALUE.

MASTER CHART EIA (RETMA) VALUES SPECIFY RESISTANCE WANTED

Ohms	Ohms	Ohms	Ohms	Ohms	Ohms	Ohms	Ohms
5.1	22	91	390	1600	6800	30,000	0.12 meg
5.6	24	100	430	1800	7500	33,000	0.13 meg
6.2	27	110	470	2000	8200	36,000	0.15 meg
6.8	30	120	510	2200	9100	39,000	0.16 meg
7.5	33	130	560	2400	10,000	43,000	0.18 meg
8.2	36	150	620	2700	11,000	47,000	0.20 meg
9.1	39	160	680	3000	12,000	51,000	0.22 meg
10	43	180	750	3300	13,000	56,000	0.24 meg
11	47	200	820	3600	15,000	62,000	0.27 meg
12	51	220	910	3900	16,000	68,000	0.30 meg
13	56	240	1000	4300	18,000	75,000	0.33 meg
15	62	270	1100	4700	20,000	82,000	0.36 meg
16	68	300	1200	5100	22,000	91,000	0.39 meg
18	75	330	1300	5600	24,000	100,000	0.43 meg
20	82	360	1500	6200	27,000	110,000	0.51 meg

RS-250 Please Specify Resistance Net ea. .12

SPECIAL INDUSTRIAL QUANTITY PRICES

5 for .50 — 25 for 1.75 — 100 for 5.00 — 1,000 for 40.00

WRITE OR PHONE FOR QUOTATIONS IN LARGER QUANTITIES

POLARIS "MAJ-I" RESISTOR PHOTOCELL




2.19

A cadmium-sulphide light-dependent resistor used to actuate door openers, burglar alarms, smoke detectors, light controls, production counters, etc. Resistance varies from 200 ohms at approx. 93 foot-candles to over 10 megohms in total darkness. Maximum volts: 110VAC (peak) 110VDC; maximum dissipation: .2 watt @ 40°C, .1 watt @ 50°C, 0 @ 60°C. Capacity approx. 6 mmf. 1/2" diam. x 3/4" thick. Shpg. wt., 3 oz.

Net 2.19

SELF GENERATING PHOTOELECTRIC CELLS



AS LOW AS

BELOW DISTRIBUTOR COST!

.53

- Complete with leads
- No external power needed
- Output in sunlight up to 60 MA

• Up To 750 ua at 100 ft. Candles

Selenium, self-generating photocells convert sunlight or artificial light energy into electrical energy without any auxiliary source of power. Sensitive to a wide spectrum including white, colored or ultra-violet light. All unmounted; complete with leads. Outputs in table below taken at 100 foot candle illumination with 100 ohm load. Higher outputs obtainable with greater light. Shpg. wt., 3 oz.

Stock No.	Out μ a	Size	1-4	5-9	10	Net Each
MS-771	100	1 1/4" x 3/4"	.59	.56	.53	.53
MS-772	250	1 1/2" x 3/4"	.79	.75	.71	.71
MS-773	350	1 3/4" x 3/4"	.89	.85	.80	.80
MS-774	750	1 3/4" x 1 1/4"	3.18	3.03	2.88	2.88

NEW! LAFAYETTE CADMIUM SULPHIDE PHOTOCELL




Only 3/8" D x 1/2" W **.95**

New head-type window cadmium sulphide photocell. Maximum Ratings: 200 volts DC or AC peak. Temperature is -40°C and +60°C; Resistance is over 10 megohms at zero ft. candles, 100,000 ohms to 10 megohms at 1 foot candle, 100,000 to 350,000 ohms at 10 foot candles; Range of sensitive wave length is 4000 to 8000 angstroms. Size: 3/8" diam. x 1/2" L. o/a. Standard screw mount: miniature base.

Net .95

POWERMASTER TYPE CDS-10 CADMIUM SULPHIDE PHOTOCELL



2.50

A miniature crystal photocell that is ideal for actuating, coating, measuring photo-electric control. Acts as a resistor that varies with the intensity of light from over 1 megohm in total darkness to under 1500 ohms at 100 foot candles. Rapid response fast enough to operate relays in 1/10 second. Minimum current output 66 ma at 50 ft. candles at 90 Volts. Output varies with illumination intensity and applied voltage to as low as .08 ma at 1 ft. candle at 6 volts. Power dissipation 1/2 watt continuous. 2 watts for 5 seconds. Usable response to entire visible spectrum with peak sensitivity to blue-green light and good red response. Response to infra-red is low. Size 1 1/4" x 3/4" x 1/4".

Net 2.50

CADMIUM SULPHIDE PHOTOCELL



1.59

- For Sensitive Relay Actuation
- For Photo Electric Control

A neatly constructed crystal photocell that has countless applications in counting, relay actuation, etc. Resistance varies with light from 1 megohm in total darkness to approx. 1500 ohms at 100 foot candles. Responds to entire visible spectrum and has 1/10 sec. response for relay operation. Minimum current output 60 ma at 50 ft. candles at 90 volts. Power dissipation 2 watts for 5 seconds, 1/2 watt continuous. Output as low as .08ma at 1 ft. candle at 6 volts, varying with illumination intensity and applied voltage. Neatly encapsulated for easy mounting with leads for electrical connection. 1 1/4 x 1/2 x 1/4" overall.

Net 1.59

SELENIUM PHOTOCELL

- Excellent for Burglar Alarms
- Door Openers
- Counters

8.75



OPERATES RELAYS DIRECTLY

Barrier layer, self-generating type: light striking upon cell generates current sufficient to operate relays directly without the use of auxiliary power. Lifetime of cell is unlimited. 600 microamperes output at 100 foot candles. 2 inches in diameter. Mounted in a handsome plastic case.

MS-826 PhotoCell, Wt., 8 oz. Net 8.75

CM-70 Socket for MS-826 Net .13

LAFAYETTE SUPER-VALUE SUN BATTERY



1.95

- Excellent for Experimenter, Kit Builder, etc.

Sensational buy enables Lafayette to offer this amazing selenium photocell at a fraction of the price of similar photoelectric cells! Surpasses by far, specifications of cells of equivalent size! Specifications: 0.9 ma Current Output at 100 ft. candles with 100 ohm load; 0.27 ma Current Output at 100 ft. candles with 1000 ohm load. 1 1/2" diameter. With colored pigtail leads.

MS-891

Net 1.95

NEW! SELENIUM PHOTOCELL FOR HEAVY DUTY OPERATION

2.45 • 3/4" Light Area

An efficient selenium photocell utilizing an extremely sensitive film element with 3/4" light area. Ideal for relay operation, use door openers, counters, etc. Rated at 200V; 20 ma; 0.2W power dissipation at 20°C. Sensitivity is 610 ± 50. Resistance Value Characteristics — 0 Ft. Candles: 2M ohms; 0.929 Ft. Candles: 100K ohms; 9.29 Ft. Candles: 25K ohms; 9.29 Ft. Candles: 8K ohms; Size 1 1/4" Diam. x 3/4" depth.

MS-886 Net 2.45

NEW! LAFAYETTE SELENIUM PHOTOCELL

1.95 • 3/8" Light Area

A quality selenium photocell, perfect for transistor and printed circuit use. Employs sensitive film element with 3/8" light area. Rated at 200V; 10ma; 0.1W. power dissipation @ 20°C. Sensitivity is 610 ± 50. Resistance Value Characteristics — 0 Ft. Candles: 2M ohms; 0.929 Ft. Candles: 100K ohms; 9.29 Ft. Candles: 25K ohms; 9.29 Ft. Candles: 8K ohms; Size 3/8" Diam. x 3/4" Depth.

Net 1.95

NEW! LAFAYETTE MINIATURE SILICON RECTIFIER

.49 • ONLY 3/8" D x 1/2" W

Premium quality and small size make this precision rectifier ideal for prototype and miniature applications. Measures 3/8" D x 1/2" W plus 1/4" mounting lip. Rated AC input voltage 100V, DC output current 20ma. Intermittent 40ma. Maximum Input Capacitance 80MF.

MS-887 Net .49

A FABULOUS BUY! GENUINE 10% and ALLEN-BRADLEY Resistor Kit



\$4.50

Lafayette leads the field with a genuine Allen Bradley and IRC 1/2 watt, 10% tolerance, molded resistor kit with a Transparent Plastic Utility Box (built in partitions) size: 8 1/4 x 4 1/4 x 1 3/4". Meet JAN-R-11 specifications. Stock No. KI-23—Total 100 molded resistors with Transparent Plastic Case Net 4.50

100 INSULATED RESISTORS WITH PLASTIC HINGED BOX!

10% TOLERANCE 1/2 WATT RMA Color Coded

Quant.	Ohms	Quant.	Ohms
3	10	10	.1 meg
3	470	4	.15 meg
4	1,000	4	.27 meg
3	2,200	10	.47 meg
4	4,700	10	1 meg
5	10,000	4	2.2 meg
4	22,000		Other
4	27,000	20	popular values
4	33,000		
4	47,000	100	TOTAL

NEW POWER TRANSISTOR AUDIO TRANSFORMERS

- DESIGNED FOR HIGH OUTPUT TRANSISTORS
- USED IN AUTO RADIOS—PA SYSTEMS—INTERCOMS—ETC.



1.75

Rated 6 watts. Frequency response 70 to 20,000 cycles ± 2 db. Primary impedance, 48 ohms center tapped. Secondary, 3.2 ohms; Primary DC resistance 1.1 ohms, secondary 0.3 ohms. Unbalanced primary current 500 ma DC. Size 1 1/4 x 1 1/4 x 1 1/4". Shpg. wt., 1 lb.

AR-503

INPUT TRANSFORMER


Rated 2 watts. Frequency response 70 to 20,000 cps ± 2 db. Primary impedance 100 ohms. Secondary impedance 200 ohms CT. Primary DC resistance 1.8 ohms, secondary 2.7 ohms. Unbalanced primary current, 200 ma DC. Size 1 1/4 x 1 1/4 x 1 1/4". Wt., 1 lb.

AR-504

NEW! UNIVERSAL POWER

TRANSISTOR OUTPUT TRANSFORMER

- DESIGNED FOR THE EXPERIMENTER • RATED 10 WATTS
- PRI. TAPPED AT 8-12-16-24-32 AND 48 OHMS




3.75

Lafayette's latest transistor circuit component. Engineered for construction projects using the increasingly popular power transistors. Will also serve as a general replacement for many transistorized auto radios. Rated at 10 watts for push-pull operation. Primary tapped at 8, 12, 16, 24, 32 and 48 ohms. Secondary tapped at 4, 8 and 16 ohms. Sizes 3 1/4 x 2 1/4 x 2 1/4". Shpg. wt., 3 lbs.

TR-94

NEW! MICRO-PERFORATED BOARDS



- Ideal For Transistor And Subminiature Circuitry
- Copper-Clad For Printed Circuits
- Unclad Type For Wired Circuits

These sturdy, perforated boards are the ideal base for builders, experimenters, and labs to mount miniaturized components. Two types available: either high grade bakelite for wired circuits, or one side copper-clad for "printed" circuitry. Holes are 1/16" diameter with 3/16" between hole centers. All boards are 1/8" thick. For contacts, the MS-263 flea clips listed on this page are ideal. Avg. shpg. wt., 6 oz.

COPPER CLAD BOARDS

Stock No.	Size	Net Each Lots of		
		1	100	250
MS-847	2 1/4" x 3 3/4"	.35	.30	.24
MS-848	3 1/2" x 6 3/4"	.55	.50	.45
MS-849	7 1/4" x 6 3/4"	1.15	.96	.87
MS-850	10 1/2" x 7 3/4"	1.90	1.58	1.42

UNCLAD BOARD

Stock No.	Size	Net Each Lots of		
		1	100	250
MS-304	2 1/4" x 3 3/4"	.25	.20	.18
MS-305	3 1/2" x 6 3/4"	.45	.40	.35
MS-306	7 1/4" x 6 3/4"	.75	.65	.60
MS-846	10 1/2" x 7 3/4"	1.20	1.08	.97

COPPER CLAD LAMINATE AT LAFAYETTE'S LOW PRICES!

NO.	DESCRIPTION	NET
MS-510	XXXX Copper Lam.—1 side—9"x12"	1.50
MS-511	XXXX Copper Lam.—1 side—6"x4 1/2"	.45
MS-512	XXXX Copper Lam.—1 side—3"x4 1/2"	.30
MS-513	XXXX Copper Lam.—1 side—2"x4 1/2"	.25
MS-514	XXXX Copper Lam.—1 side—3"x2 1/2"	.24
MS-515	XXXX Copper Lam.—2 sides—9"x12"	1.95
MS-516	XXXX Copper Lam.—2 sides—6"x4 1/2"	.60
MS-517	XXXX Copper Lam.—2 sides—3"x4 1/2"	.40
MS-518	XXXX Copper Lam.—2 sides—2"x4 1/2"	.30
MS-519	XXXX Copper Lam.—2 sides—3"x2 1/2"	.27



FLEA CLIPS FOR TRANSISTOR AND SUBMINIATURE CONTACTS

"Flea" clips are specially designed for subminiature work. Fit perfectly in holes in perforated copper-clad and unclad boards listed above. Made of beryllium copper, silver plated finish. Simply insert wire thru hole for positive grip contact.

MS-263	Package of 12	Net .25
MS-851	Package of 1000	Net 15.75
MS-852	Package of 5000	Net 76.15
MS-853	Package of 10,000	Net 149.30

NEW!

LAFAYETTE—RF SIGNAL GENERATOR

- Perfect for Engineers, Servicemen, Students and Experimenters
- Quality Assembled Equipment at a **KIT PRICE!**



- **FACTORY CALIBRATED AND TESTED**
- **SIX BANDS: 120 KC - 260 MC**
- **DUAL OUTPUT RF TERMINALS**
- **SEPARATE VARIABLE AUDIO OUTPUT**
- **DIAL CALIBRATION ±2%**
- **ETCHED CIRCULAR DIAL - (Vernier Tuned)**

A stable, wide-range signal generator engineered to fill the need for an accurate low cost service instrument. Saves you time and money compared to spent building a kit of lesser quality. Since the delicate oscillator coils and tuning assembly are factory mounted and adjusted for optimum performance, the TE-20 is ready to go to work for you the instant you unpack it. This top-flight signal generator can be used for IF-RF alignment, audio signal tracing of TV, FM and AM sets, TV linearity checks and 400 cycle audio testing. In addition, it can serve as a marker generator when used with a suitable sweep generator. Look at some of the TE-20's features which make it the service instrument buy of the year. Incorporates a large 4 1/4" etched circular dial for easy, accurate frequency adjustments. Provides a fundamental frequency output of 120 KC to 130 MC in 6 bands plus a calibrated harmonic output of 130 mc to 260 MC. The built-in audio oscillator operates at 400 KC with adjustable output to 8 volts. Continuously variable RF attenuator for proper signal attenuation and two plug-in RF output terminals provide a choice of high and low outputs for maximum flexibility. High output and tuning dial calibration of ± 2% give evidence of features not found elsewhere at twice its price.

Net 27.95

NO MONEY DOWN

27.95

SPECIFICATIONS

Full frequency range: 6 Fundamental bands—120-320 Kc 320-1000 Kc. 1-3.4 MC, 3.2-11 MC, 11-38 MC, 36-130 MC. One harmonic band 130-260 MC.
 Frequency Accuracy: ± 2%. Audio Output: to 8 volts.
 Large 4 1/4" Etched Circular Dial (Vernier tuned)
 High-Low RF Output Terminals.
 Tube Complement: 12BH7A, 6AR5, Selenium Rectifier.
 Power Requirements: 105-125VAC 50/60 Cps., 12 Watts.
 Attractive gray wrinkle steel case with leather carrying handle.
 Complete with test leads.
 Size: 7Hx10 1/2Wx5 3/4"D. Shpg. wt., 9 lbs.

NEW!

LAFAYETTE—SINE SQUARE WAVE AUDIO GENERATOR

- **FACTORY CALIBRATED AND TESTED**
- **LOW DISTORTION**
- **FREQUENCY RANGE - SINE: 20 cps—200 KC IN 4 BANDS; SQUARE WAVE RANGE: 20-25 KC (Vernier Tuned)**
- **ETCHED CIRCULAR DIAL**
- **FREQUENCY RESPONSE - ±1.5DB, 60CPS - 150KC 4 1/2" VERNIER DIAL**



The Lafayette TE-22 is especially designed for radio-TV servicemen, Hi-Fi fans and students who require a dependable sine and square wave generator at low prices. A completely wired and tested instrument, it is equal in quality to higher priced separate generators and far more convenient to use. A terrific buy, this generator will outperform most higher priced kits with ease. Among its many applications are square wave testing of audio amplifiers, determining the frequency and transient response of loudspeakers, TV audio circuit testing and many other uses. Quality features consist of a frequency response of ± 1.5 db from 20 cps to 200,000 cycles in 4 bands. A large easy-to-read etched dial (vernier tuned) adds a professional quality touch. Variable attenuator prevents overloading circuits and permits proper tracking of test response. A full wave power supply is incorporated to provide low distortion and constant output. Factory wiring and calibration insure its accuracy to be within 5%. High output voltage is 7 volts (max.) across a 1 megohm load. A rugged steel cabinet and shock proof mountings protect components, complete with instructions and test leads. A handsome instrument—one which you will be proud to own.

Net 32.50

COMPLETELY WIRED NOT A KIT!

NO MONEY DOWN

32.50

SPECIFICATIONS

Frequency range: Sine wave: 20-200,000 cps in 4 bands. Square wave—20-25,000 cps.
 Output Voltage—Sine: 7V Square: 7V P-P.
 Output Impedance—0-5000 Ohms. Frequency Accuracy: ± 5%.
 Distortion: Less than 2%.
 Tube Complement: 1-6B8, 1-12AT7, 1-6X4
 Power requirements: 117V 50/60 cps. 19W.
 Gray wrinkle steel case with leather carrying handle.
 Complete with a pair of test leads.
 Size: 7Hx10 1/2Wx5 3/4"D. Shpg. wt., 10 lbs.

NEW!

NEW! LAFAYETTE CAPACITANCE-RESISTANCE ANALYZER

- **Factory Wired and Tested**
- **Capacitance Bridge Circuit**
- **Direct Reading Scales for Capacitance and Resistance**
- **"Magic-Eye" Null Indicator and Meter**
- **Checks Opens, Shorts, Leakage and Intermittents**
- **Determines Power Factor of Electrolytics**
- **2 Turns Ratio Scales**
- **Measures Impedance**



Here is a real service value which can do wonders in your shop or lab. The TE-25 is a completely self-contained AC operated, bridge-type capacitance-resistance analyzer which has a number of time saving applications. It is a high caliber, factory built instrument, not a kit. All readings are made directly without complex, time wasting calculations. "Lab" accuracy within ± 5% for values to 200 mfd and ± 5% from 200 mfd up. It measures capacity and resistance in 4 separate ranges—from 1 mmf—5000 Mfd and from 0.5 ohms—500 megohms on a large permanently etched circular metal scale. You will find it invaluable for the following jobs: Measurement of Capacitance for paper, mica, ceramic and electrolytic capacitors. Resistance measurement. Power Factor measurement on electrolytics from 0-55%; shorts, opens and leaky capacitors. Also determines turn and impedance ratio of audio and power transformers. Read insulation resistance of paper, mica and ceramic capacitors directly on meter to 500 megohms. Eliminates guessing with neon lamps. DC voltage may be varied up to 600 volts to find leakage current of electrolytics. Two ranges (0-6) (0-60) ma is directly read on meter. No guesswork is necessary. Ratio scales are provided to measure impedance and turns ratio of power and audio transformers (to 500:1) in 2 ranges. "Magic-Eye" tube shows capacitance null indication—opens, shorts for electrolytics, a calibrated power factor coil is provided to check capacitor efficiency. No service shop or laboratory should be without one. Shpg. wt., 12 lbs.

Net 34.95

COMPLETELY WIRED NOT A KIT!

NO MONEY DOWN

34.95

SPECIFICATIONS

Capacity, 4 Ranges — .00001 mfd — .005 mfd; .001 mfd — .5 mfd; .1 mfd — 50 mfd; 50 mfd — 5000 mfd. Resistance — 4 Ranges — 0.5 ohms — 500 ohms; 50 ohms — 50K ohms; 5K ohms — 5 megohms; 5 megohms — 500 megohms. Transformer Turns Ratio — 1:1 — 10:1; 10:1 — 500:1. Impedance Ratio — 1:1 — 100:1; 100:1 — 250K:1. DC Leakage Test — Voltages: 0-600 Volts DC. Leakage Current — 6MA — 60 MA — 2 Ranges. DC Insulation Test — 600 Volts Constant — 10 megohms — 500 megohms. Tube Complement: — 1-6R4; 1-6E5. Power: — 117V; 50/60 cps AC. Size: 10 1/2Wx7Hx5 1/4"D. Complete with instructions and test leads. Handsome grey wrinkle steel case with leather carrying handle.

EICO MODEL 666K DYNAMIC CONDUCTANCE TUBE AND TRANSISTOR TESTER KIT

An ideal tube tester for color and monochrome TV servicing. Tests all receiving tubes, including 4, 5, 6, 7-pin, octal, loctal, miniature 7 and 9-pin, sub-miniature, 5, 6, 7-pin (in-line base) and 8-pin (circular base) receiving tubes, transmitting and special purpose tubes. TV picture tubes with accessory adaptor. Measures transistor collector current and shows current amplification factor. Measures Gp, Gm and also leakage in ohms. For 105-130 volts, AC 50/60 cps. 12x15x4 1/2".
 TE-151WX Kit Shpg. wt., 18 lbs. Net 69.95
 Model 666. As above, but factory wired and tested. Net 109.95
 TE-152WX



EICO MODEL 680 TRANSISTOR AND CIRCUIT TESTER



Provides accurate measurements of diodes and ICBO and ICED with separate test positions for signal and power transistors, DC Beta and Simulated AC Beta. The VOM includes 5 DC current ranges down to 50 UA full scale, 2 DC volts ranges at 20,000 ohm/volt, and 3 resistance ranges. Mode Switch sets up instrument for PNP, NPN transistors or VOM use. 3 1/2" D'Arsonval meter has 2% accuracy. Self-powered, uses 4 size AA and 1 "C" battery. Includes 3 permanently connected clip-on test leads on a panel socket for transistor connections; 2 banana jacks. Housed in a sturdy bakelite case. Size: 6 3/4Hx5 1/4Wx3 3/4D. Shpg. wt., 3 lbs.
 TE-735 680K Kit Net 25.95
 TE-736 680 Factory wired and tested Net 39.95

TC-101 TUBE AND CIRCUIT TESTER



• **Tube Checker Checks approximately 2000 Tubes**
 • **Handy VOM For Circuit Testing**
 Here is a tester to satisfy your every need—perfect for kit builders, tube caddys. The TC-101 checks approximately 2000 tubes for emission, shorts and leakage. Front panel function switch converts it to a handy volt-ohm meter for circuit testing. Utilizes a 1 milliamp D'Arsonval meter for positive, accurate measurements. Three voltage ranges for fast circuit testing, either AC or DC — 0 to 12V, 0 to 120V, 0 to 1200 volts. Measures resistance up to 5 megohms—completely self-contained. Easy to follow set-up booklet included, clips on back of unit. Measures 7 1/2x9x3 3/4". Shpg. wt., 5 lbs.
 TE-679 Net 29.95

SIMPSON MODEL 260 SERIES III AC-DC V-O-M



43.07 NO MONEY DOWN
 Now offered in a new and improved form. Sensitivity — 20,900 ohms; V.D.C., 5,000 ohms—V.A.C. Ranges: DC: 0-25V, 2.5V, 10V, 50V, 250V, 1000V, 5000V; AC: 0-25V, 10V, 50V, 250V, 1000V, 5000V; AF: 0-2.5V, 10V, 50V, 250V; DB: 20 to +10 db; —8 to +22 db; +6 to 36 db; +20 to +50 db. DC current ranges from 0-50 u amps, 0-1, -10, -100, -500 ma; 0-10 amps, DC resistance from 0-2000 ohms, 0-200,000 ohms, 0-20 megohms. Accuracies: DC volts ±3% F.S.; AC volts ±5% F.S., DC resistance ±3% of arc from absolute value of resistance measured. Meter housed in Bakelite case, measures 5 1/4x7x3 1/4". Comes with battery and test leads. Shpg. wt., 6 lbs.
 TE-31D Net 43.07

EICO MODEL 460K WIDE BAND SCOPE KIT



Excellent Lab precision scope featuring Push-pull direct coupled vertical amplifier with high sensitivity: 25 mv/in. Response flat from DC to 4.5 mc, useful to 10 MC, ideal for reproduction of 3.58 mc color TV sync. burst, 4 step freq.-compensated attenuator in both AC, DC positions. Also internal voltage calibration. Automatic sync. limiter and amplifier. 2X-full screen horizontal positioning. Sweep-freq: 10 to 100K cps with external capacitor for lo-freq. sweeps. Variably lit graphed 5" screen. Complete with all components and instructions for easy assembly. 13x8 1/2x16". For 105-125 vac, 50-60 cycles. Shpg. wt., 30 lbs.
 TE-222WX Kit Net 79.95
 Model 460. As above, but factory wired and tested. Net 129.50
 TE-223WX



SUPERIOR MODEL 70 UTILITY TESTER 15.53
 Test Appliances and Utilities

Appliance and utility tester. Will test toasters, irons, broilers, clocks, fans, fluorescent lamps, auto systems. Measures AC and DC voltages, AC and DC current, resistance, leakage (ohms scale from 0-5 Meg-ohms). Voltage scales 0-150; 0-300. Amps Scales 0-15 amps. Comes with instructions and leads. Shpg. wt., 3 lbs.
 TE-513 Net 15.53
 TE-517 7.5V Battery Pack for Model 70 Net 1.00

NEW SUPERIOR 820 Multi-Socket TUBE TESTER



The model 820 is a fast 3-step tube tester. Use of 26 sockets eliminates element switching common in ordinary tube testers. Just set the filament switch, insert tube and press down quality button. Emission quality is read directly on a 4" bad-good meter scale. Inter-element leakage, if any indicates automatically. Meter features dual scale for testing low current tubes. Tests 024 and other gas filled tubes, NOVARS, NUUVISTORS 10 pins, COMPACTRONS—over 850 tube types. 7 and 9 pin straighteners are panel mounted. Comes complete with tube charts and instructions. Housed in handsome, portable, saddle-stitched Texon Case. Size: 13 3/4x10 1/2x3 1/2"H. Shpg. wt., 7 lbs.
 TE-518 Net 37.73

RCA WV-77E(K) VOLTOHMIST IN KIT FORM



ONLY 29.95 KIT WIRED 43.95
 Its 28 ranges include 70C and 7 rms AC Voltages 0-1.5, 5, 15, 50, 150, 500, 1500; 7 peak-to-peak AC voltages: 0-4, 14, 40, 140, 400, 1400, 4000 volts; 7 overlapping ohms ranges from 0.2 ohms to 1000 megohms with center-scale values of 10, 100, 1000, 10K, 100K, 1 meg, and 10 meg. ohms. Zero-center for discriminator alignment; frequency response of 40 cps to 5mc. flat to within ± 5% on the 1.5 to 15 volt rms and 4 to 40 volt p-to-p ranges; meter electronically protected against burnout. Supplied complete with DC and AC/ohms probes and cables and ground leads, battery, and instruction book.
 TE-141 Shpg. wt., 5 1/2 lbs. Net 29.95
 WV-77E Same, completely wired and factory-calibrated. TE-142 Net 43.95

LAFAYETTE

PEAK-to-PEAK


V.T.V.M. KIT



**An Outstanding Development In V.T.V.M. Design
The Only V.T.V.M. Available With These Features**

NO MONEY DOWN

KT-174 | TE-31
44.50 | **57.00**
IN KIT FORM | COMPLETELY WIRED AND TESTED



MADE IN U.S.A.

- Special Low AC Ranges Provide Noise & Gain Measurements (as low as 1 mv) for Audio & Hi-Fidelity Applications
- Scope Monitor Terminals For Direct Connection To Oscilloscope
- Newly Designed Lafayette Push-Button AC/DC Omni-Probe
- Calibration Controls—Accessible Without Removing Cabinet
- Measures AC Peak-To-Peak, AC RMS, DC Voltage & Resistance
- Direct Reading DB Scale
- Regulated & Balanced Bridge Circuit Provides Unequaled Accuracy & Stability
- Circuit Employs 12AU7 Twin Triode Operating Only Within Its Linear Capabilities • 1% Precision Multiplier Resistors
- Accurate 200 μ a Meter Movement with Large 4 1/2" face

In Every Respect A Professional Test Instrument—Engineered to meet and exceed the rugged standards, accuracy plus required sensitivity demanded in laboratory, industrial and service applications. The KT-174 offers in remarkably easy-to-build kit form, a Vacuum Tube Volt Meter that achieves a level of performance and versatility rivaling factory wired equipment many times its price. Unquestionably The Finest VTVM in its class. Utilizing a printed circuit board, Lafayette's famous step-by-step instructions and huge pictorial diagrams assure ease of assembly. Attractive dark grey front panel is set in a contrasting textured light grey metal case. Complete with tubes, battery and special Lafayette Omni-Probe. Size: 8 1/2x6x5 5/8". For 105-125 volts, 60 cycles AC. Shpg. wt., 8 lbs.

LABORATORY TEST EQUIPMENT IN EASY-TO-BUILD KIT FORM

COMPARE THESE SPECIFICATIONS

DC VOLTMETER—Ranges: 0-1.5, 5, 15, 50, 150, 500, 1500V. Input Resistance: All ranges—11 Megohms. Sensitivity—1.5V Range: 7.3 Megohms/Volt. Accuracy: \pm 2% of full scale at 117VAC—deviation due to line voltage variation between 105-125 volts is negligible. AC VOLTMETER—LOW AC—Ranges: RMS-0 to 50 mv, 0-150 mv, 0-500 mv. Peak-To-Peak—0-140 mv, 0-420 mv, 0-1400 mv. Accuracy: \pm 5% of full scale. Input Impedance: 1 megohm at 1 KC. Freq. Response: \pm 1 db from 20 to 300,000 cps from 600-ohm source. REGULAR AC—Ranges: RMS—0-1.5, 5, 15, 50, 150, 500, 1500 volts. Peak-To-Peak: 0-4.2, 14.0, 42, 140, 420, 1400, 4200V. Accuracy: 3% on all ranges except 5% on 0 to 5V. Freq. Response: \pm 1 db 20 cps to 4 mc from 600-ohm source. Input Impedance at 1 KC: 0-1.5V, 5V, 15, 50-83 Meg. 0-150V, 1.3 meg—0-500V, 1500V—1.5 meg. Db.—10 to +5 OHMMETER—7 Ranges: 0-1000 RX1, RX10, RX100, RX1000, RX10K, RX100K, RX1M using precision 1% dividing resistors. Meter Movement: 200 μ a for full scale deflection. Tubes: 1—6BN8, AC full-wave peak rectifier and low AC amplifier; 1—12AU7 twin triode meter DC amplifier and balanced bridge. Incorporates Half Wave Selenium Rectifier and Well Filtered Fused Power Supply.

KT-174 Kit Form Net 44.50
TE-31 Same as above, wired and tested Net 57.00
KT-205 RF Probe Kit For KT-174 and any Other Net 3.75
11 meg Ohm Impedance VTVM

NEW! LAFAYETTE V.T.V.M. KIT



MADE IN U.S.A.



- Wide Band—AC Measurements on any Waveform from 30 Cycles to Over 5 MC. Without Additional Probes or Accessories
- 11 Megohm Input Resistance—Negligible Loading Effects on DC Circuits
- Direct Reading DB Scale
- Balanced Push-Pull Amplifier—Isolates and Protects Meter
- Etched Circuit Design Simplifies Construction
- Selected 1% Zero Temperature Coefficient Multiplier Resistors for Dependable, Accurate Readings
- Giant 6" Full-View Meter With Easy-To-Read Two-Color Scales

An indispensable test instrument for the service technician, experimenter or hobbyist. The KT-202 is a high quality V.T.V.M. in easy-to-build kit form, which offers features unusual at this low price. It is a highly accurate DC voltmeter, AC voltmeter and ohmmeter employing a giant 6", 400 μ a meter with clear black and red scales. High input impedance of 11 megohms, accurately measure DC voltages up to 1500 volts while presenting a negligible load to the circuit under test. As a wide band AC voltmeter, it will measure AC peak-to-peak voltages up to 2,000 volts on any waveform. All this from 30 cycles to above 5 Mc—without any accessory probes! AC RMS voltages may be read directly up to 1,500 volts if the waveform is sinusoidal. The wide frequency response makes this meter ideal in audio, radio and TV applications. Resistances can be read directly on the Ohms scale from 0.2 ohms to 1,000 megohms. A direct reading decibel scale is calibrated from -10 to +18 db (reference 1.73 volts, 6 mw into 500 ohm line). In addition, zero center measurements can be made. The KT-202 utilizes a 12AU7 balanced push-pull DC amplifier and two 9006 tubes as peak-to-peak voltage rectifiers. The meter is isolated making it virtually impossible to burn it out. Multiplier resistors are 1% zero temperature coefficient types, to assure maximum accuracy and minimum variation due to heat. Front panel controls: Function Selector—selects Pwr. Off, A.C.V./P-PV, D.C.V. Neg., D.C.V. Pos., Ohms; Range Selector—for 7 voltage and resistance ranges; Ohms Adjustment; Balance (zero) Adjustment. There are 3 probes: Common, A.C.V.—Ohms, and a shielded D.C.V. probe with 1

megohm isolating resistor. Printed circuitry makes construction of this kit easy. Selenium rectifier transformer—operated power supply for 110-120 VAC, 60 cps. Dimensions: 7 1/2x6 1/2x5 5/8" overall. Kit comes with 1 1/2 volt battery for ohmmeter circuit and complete instructions. Shpg. wt., 7 lbs.

KT-202 Accessory RF probe for KT-202 or other 11 megohm V.T.V.M. Net 25.95
KT-205 Carrying case for KT-202, complete with handle. Net 3.75
KT-203 Shpg. wt., 1 lb. Net 2.95

MODEL KT 202
25.95
NO MONEY DOWN

SPECIFICATIONS

DC VOLTMETER RANGES: 0-3, 15, 75, 150, 300, 750, 1500 volts. Input resistance: 11 megohms (1 megohm in probe) on all ranges. AC VOLTMETER RMS RANGES: 0-3, 15, 75, 150, 300, 750, 1500 volts. PEAK-TO-PEAK RANGES: 0-8, 40, 200, 400, 800, 2000 volts. DECIBEL RANGES: -10 to +18db, +10 to +38db, +30 to +58db. Response: 30 cycles to above 5 Mc. OHMMETER RANGES: 0-1000, 10,000, 100,000 ohms; 0-1, 10, 100, 1000, megohms. CENTER SCALES: 10, 100, 1000, 10,000, 100,000 ohms, 1 megohm, 10 megohms. TUBES: 1—12AU7 twin triode balanced meter bridge, 2—9006 peak to peak rectifiers, 1 power supply selenium rectifier. POWER: 110-120 VAC, 60 cycles.

NEW! LAFAYETTE COMBINATION SIGNAL GENERATOR AND SIGNAL TRACER KIT

NEW!

MODEL KT-208



MADE IN U.S.A.

Another Outstanding Achievement by Lafayette Test Equipment Engineers

SEMI-KIT CONSTRUCTION!!! This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory.

SIGNAL TRACER

- Hi-gain Cascode Pre-amplifier
- Front Panel Output For VTVM, Scope or Phones
- Low Distortion Triode Output Stage
- 4 1/2" Permanent Magnet Speaker
- Separate R.F. and Audio Signal Probes

SIGNAL GENERATOR

- Covers From 250 KC to 120 MC in 5 Bands
- High Stability Electron Coupled Oscillator
- Attenuator For Both RF and Audio Circuits
- Most Used Frequencies Marked on Panel in Color
- Utilizes New Ruggedized Industrial Type Tubes

Two test instruments in one! And available in easy-to-build kit form. The Signal Generator will serve as a full service instrument and the Signal Tracer will follow any signal whether generated by a broadcasting station or injected by the Signal Generator section of the Model KT-208. When used in combination, with no dependence on outside signals, the compatibility of Model KT-208 provides ideal service, for unlike any standard signal tracer, it first injects its own signal then traces that controllable signal to locate the source by standard signal tracing technique. Designed for use with AM, FM, TV and audio circuitry. Features 5 frequency ranges and an attenuator switch to control both the R.F. signal (either modulated or unmodulated) and the 400 cycle audio tone. Front panel output jacks which can be used for oscilloscope, VTVM or earphone connections. Famous Lafayette kit building manual with large pictorials will make it a pleasure to build. Housed in a beautiful crackle finish steel cabinet with a deep

etched aluminum panel. Dimensions: 7 1/2x9 1/2x5 3/4". Complete with 2 probes. Shpg. wt., 9 lbs.

This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory. All you have to do is wire it up! KT-208 Kit Net 19.95

MADE IN U.S.A.
19.95

SPECIFICATIONS

RANGE: BAND A: 250KC to 250KC; B: 850KC—300MC; C: 3.0MC to 11MC; D: 11MC to 45MC; E: 35MC to 120MC: 400cps audio signal; modulation slide switch, RF/AF attenuator and power switch; Signal output jack; AF input jack, 2 Preamp. output jacks, 4 1/2" alnico 5 speaker. Tubes: 5965, 5687, 6350, 6AG5

NEW! LAFAYETTE TUBE TESTER KIT TESTS TUBES IN SECONDS

NEW!

MODEL KT-209



MADE IN U.S.A.

- Test Over 1,000 Tube Types
- Checks For Shorts and Leakages Between All Elements
- Tests Filament Continuity
- Checks All Modern Tubes
- Five Year Free Tube Data
- 7 and 9 Pin Tube Straighteners
- Rugged, Accurate. Meter Movement With Sealed Air Damping Chamber

Features & Specifications:

The KT-209 is a complete portable tube tester designed to test the modern tubes found in radio, TV and hi-fi amplifier systems. Speedy operation is assured by use of a single rotary switch in place of one-at-a-time slide switches normally used. Just insert tube in one of the seven panel sockets, set filament selector switch and then rotate the Element switch. Shorts show up instantly on the "leakage indicator" lamp. Tube emission quality is indicated on the highly damped meter's calibrated "Good—?—Bad" scale. A two position slide switch for regular or special higher voltage tubes sets up the meter test. 7 and 9 pin straighteners are provided to insure long life for these sockets. Superbly detailed, step-by-step Lafayette instruction manuals with giant diagrams will assure you of factory-type assembly. This unit uses proven semi-kit construction with all

SEMI-KIT CONSTRUCTION
This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory.

major components pre-mounted and tested at the factory. All you have to do is wire it up! American made, and replacement parts are always available if needed. No finer value available anywhere. Housed in a portable leatherette carrying case with removable cover for easy accessibility. This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory. Dimensions: 10 1/2x8 3/4x3 1/2". Shpg. wt., 6 lbs. Net 17.95

MADE IN U.S.A.
17.95



The Sensational LAFAYETTE TE-15 TUBE TESTER

COMPLETELY WIRED — NOT A KIT

- Accurately Checks Over 1000 Different Tubes
- Tests for Cathode Emission, Leakage and Shorts plus Filament Continuity
- Completely Portable—Weights Only 6 lbs.
- Highly Accurate Easy-to-Read Meter with Replace—Good Scale
- Fast-Setting Slide Switches
- Slide Out Tube Chart

LOW, LOW PRICE!
19.95

FULL SIZE
9 3/4" W
x 8 1/8" D
x 2 3/8" H

An accurate, versatile, precision instrument that actually tests over 1000 different tubes. The low cost and superior performance of the Lafayette TE-15 Tube Tester combine to make it the outstanding test instrument value today... the ideal tube tester for any radio-TV serviceman, experimenter, technician, etc.

Highly dependable, the Lafayette TE-15 is equipped to test most of the tube types employed in Radio, Hi-Fi, Monochrome, Color TV, etc. Sockets have been provided for 7-pin miniature, 9-pin miniature, octal base, loctal base, hoval and sub-miniature types. A special alligator clip lead is furnished for testing tubes with top caps. Slide switches are employed to connect the various tube elements to their respective test circuits. A 3-position tube slide switch adjust for checking shorted elements, cathode emission and filament continuity. In conjunction with the leakage-quality switch a leakage indicator light is employed which glows when an interelement short or leakage is present in a tube. A power switch turns the unit on and additionally serves to adjust for various AC line voltages. Large easy-to-read meter calibrated 0-100 has a red-green "Replace—Good" scale, plus a special scale for checking diodes.

A handy slide out metal tray contains tube charts which facilitate rapid selection of test settings. Metal case is attractively finished in cream and steel gray. Completely portable—weights only 6 lbs. and measures 8 1/4" D x 9 3/4" W x 2 3/8" H. Supplied with carrying case. For 105-125 volts, 60 cycle AC. Shpg. wt., 7 lbs.
TE-15 Tube Checker Net 19.95

NEW! POCKET AC-DC VOM

ONLY **5.95**



- Extremely Compact. Measures Only 3 1/2"x2 1/2"x1 1/2". Weighs 5 Ozs.
- 1,000 Ohms Per Volt Sensitivity
- Completely Wired (Not A Kit)
- 1% Precision Resistors
- Reads 0-1000 Volts AC-DC 0-100K Ω , 0-150 MA

Lafayette's new, pocket multitester features small physical size, and a wide selection of useful ranges. It can be used for trouble-shooting any type of electronic circuits or electrical appliances such as irons, lamps, radios, television, hi-fi equipment, etc. It is also useful for testing complex electrical circuits. Extreme portability allows unlimited usage either at home or in the field.

1000 ohms per volt sensitivity, and 1% precision resistor components assure accurate, precise readings. Operation is extremely easy, simply plug the leads into the desired scale, and you are ready to go, no switching or fidgeting required. Ranges Volts: 0-15-150-1000 AC and DC. Ohms: 0-100K MA; 0-150. The VOM comes completely wired and tested, and is enclosed in durable plastic case. All accessories including battery are rubber insulated, color coded, flexible test leads are supplied.
TE-13 AC POCKET VOM Shpg. wt., 1 lb. Net 5.95

NEW! CAPACITANCE SUBSTITUTION BOX

2.95



- 36" Color Coded Test Leads & Clips
- 9 Ranges From .0001 to .22 MFD

A must for the serviceman, experimenter or student. Fast accurate selection of any one of 9 capacitor values from .0001 to 22 MFD. Condensers are porcelain cased tubular type impervious to moisture and are rated at 600 volts working capacity. 9 capacitance ranges are .0001, .0022, .0047, .01, .022, .047, .1 plus 22 MFD. Complete with 36" red and black test leads and alligator clips. Size: 4 1/2"x2 1/2"x1 1/2". Shpg. wt., 1 1/2 lbs.
TE-16 Net 2.95

NEW! RESISTANCE SUBSTITUTION BOX

3.95



- 24 Resistance Ratings
- Two Ranges — Low 15-10K Ohms. High 15K-10 Megohms.
- 36" Red & Black Test Leads with Alligator Clips

Ideal for laboratory or service application. Substitute resistance values fast and accurately in trouble shooting circuits where values may have changed. Easy to find bias resistance in experimental vacuum tube or transistor circuits. Slide switch selects two ranges—Low: 15 ohm—10K ohm (1 watt resistors) High: 15 K ohm—10 Megohms (1/2 watt resistors). Two rotary switches (12 steps each) selects 24 separate resistances. Size: 4 1/2"x2 1/2"x1 1/2". Shpg. wt., 1 1/2 lbs.
TE-17 Net 3.95

SPECIAL

SENIOR V.T.V.M with 6 1/2" METER

Not a Kit... This is a completely wired and calibrated instrument


29.35



- $\pm 3\%$ Accuracy of Full Scale
- Giant 6 1/2" Meter Face
- Direct Reading DB Scale

COMPARE THESE FEATURES
D.C. VOLTMETER. Ranges 0 to 3, 30, 150, 300, 1500 volts. Accuracy $\pm 3\%$ of full scale. Input resistance: 11 megohms. ZERO CENTER VOLTMETER (for discriminator alignment) Ranges 0 to 1.5, 15, 75, 150, 750 volts. Accuracy $\pm 3\%$ of full scale. Input resistance: 11 megohms. AC VOLTMETER. RMS RANGE: 0 to 3, 39, 150, 300, 1500 volts. Peak to Peak Ranges: 0 to 8, 80, 400, 800 volts. Accuracy $\pm 3\%$ of full scale. OHMMETER: Ranges 0 to 1000 megohms (5 overlapping ranges). Center scale values: 10, 100, 1000, 100,000 ohms. 10 megohms. DECIBEL METER (for all audio measurements) Ranges: -10 to +5, +6 to +25, +26 to +45 decibels. All bases on zero Db. at 1.73 volts on 500 ohm line. Pilot light indicates when unit is "on." Complete with D.C. V.T.V.M. probe and cable plus pair of standard test leads. Housed in a rugged grey high-impact case, with color matched etched aluminum panel and portable handle. Size: 5x6 1/2"x7 1/2".
TE-500 Shpg. wt., 6 lbs. Net 29.35

20,000 OHM PER VOLT SEMI-KIT MULTITESTER



A New Kind of Kit
ONLY **11.95**

The semi-kit is a new concept in test equipment kits. All the important or difficult parts are already mounted. All that remains to be done is to mount and wire in a few small parts—a job so simple you'll finish before you realize it, and best of all, you'll have one of the finest high sensitivity multitesters on the market. When used in a circuit, the high input resistance on all DC and AC ranges does away with the highly inaccurate readings common to low resistance testers which load the circuit. Ranges: DC Volts, 0-10-50-250-500-1000; AC Volts, 0-10-50-250-500-1000; DC CURRENT, 0-500 μ a, 0-10-250 ma; OHMS, 0-10K-100K-1 meg; DECIBELS, -20 to +36; PLUS 0-5000 henries and 250 mmf. to .02 mfd. Black case 5 1/2"x 3 1/2"x1 1/2". Complete with test leads, all parts, and instructions and battery. Shpg. wt., 3 lbs.
TK-10 KIT Net 11.95

NEW! 20,000 OHMS PER VOLT MULTITESTER



13.50

- 20,000 OHMS PER VOLT DC—10,000 OHMS PER VOLT AC
- 40 MICROAMPERE 3" D'ARSONVAL METER MOVEMENT
- HIGH INPUT RESISTANCE ON ALL DC AND AC RANGES

This new multitester has extra-luxury features, found in the most costly instruments. Easy visibility is provided by the large 3" meter with two color scales for assistance on all ranges: 20,000 ohms per volt on DC; 10,000 ohms per volt on AC. This plus 1% tolerance resistors all the measuring of voltages without unduly loading the circuit, thus preserving accuracy of readings. Besides the extreme sensitivity and superior versatility of this instrument, it features ranges not found on other, competitively priced VOM's. Measures 0-10-50-0-500-1000 DC volts, 0-10-50-250-500-1000 AC volts, 0-10K-100K-1 meg ohms, 0-500 microamperes, 0-10-250 milliamperes, -20 to +36 decibels, PLUS two special ranges 0-5000 henrys inductance and 250 mmf to .02 mfd capacity. EM-MODEL RW-60 Multimeter. Size 3 1/2"x5 1/4"x1 1/2". Shpg. wt., 3 lbs.
TE-37 Felt-lined carrying case for above instrument Net 13.50

FILAMENT CONTINUITY TUBE CHECKER



1.69

Small and compact as a cigarette box. Quickly checks filament continuity in a matter of seconds. Ideal for the serviceman or the technician working in the field. Tests filaments of radio, TV picture tubes. Also can be used to test many other electrical devices and line cords, fuses, lamps and bulbs. Has sockets for TV picture tube and loctal, octal, 9-pin, as well as 7-pin sockets. Provided with two test leads. Grey hammetone finish. Size: 4x3x1 1/2". Shpg. wt., 12 oz.
TE-11 Net 1.69

NEW! 10,000 OHMS PER VOLT MULTITESTER



OUTPERFORMS INSTRUMENTS MANY TIMES ITS SIZE

9.95

- EXTRA LARGE 3 1/2" METER FACE
- ALL ACCESSORIES INCLUDED

- COMPLETELY WIRED (NOT A KIT)
- FULL SCALE RANGES

DC VOLTS: 0-6; 0-30; 0-120; 0-600; 0-1200; AC VOLTS: 0-6; 0-30; 0-120; 0-600; 0-1200; DC CURRENT: 0-120 μ A; 0-3M; 0-300M RESISTANCE: 0-30K; 0-3 MEG DECIBELS -20 to +63 in 5 scales; Capacity 50 μ F to .01 μ F; and .001 μ F to .15 μ F; OUTPUT RANGES 0-6; 0-30; 0-120; 0-600; 0-1200.
Unbelievable Bargain. Lafayette's new multitester is a complete factory wired and tested instrument (not a kit). It can be conveniently carried in the pocket, and features unusually sensitive 10,000 ohms-per-volt AC-DC meter, 1% precision resistors, and the largest meter ever placed on an instrument of this size. Single easy-to-use range selector switch can be appreciated by the novice and the engineer alike. Case and panel are made of durable bakelite. First capacity range requires 120 volts AC, second range requires 6 volts AC. Probes and flexible leads are plastic coated and color coded. Size: 4 1/2"x3 1/2"x1 1/2". Complete with leads and battery. Shpg. wt., 1 1/2 lbs.
TE-10 Net 9.95
Pigskin carrying case for TE-10. Shpg. wt., 8 ozs. Net 1.95
TE-14

NEW HIGH SENSITIVITY MULTITESTER



- 20,000 OHMS PER VOLT DC
- 10,000 OHMS PER VOLT AC
- RESISTANCE RANGE 0-60 MEGOHMS
- 40 μ A MOVEMENT
- 1% RESISTORS
- 0-0.6 VOLT DC RANGE FOR AUDIO AND TRANSISTOR WORK
- COMPLETELY WIRED
- 28 RANGES

17.95

A new high-quality, low-priced multitester. Its light weight makes it a perfect portable instrument for technicians, servicemen, etc. Rugged design withstands hard use. Features large easy-to-read meter and sensitive 40 microamp meter movement. 1% tolerance resistors provide extreme accuracy of measurements. Housed in rugged bakelite case. Single knob selector and clearly marked positions permit easy operation. Recessed zero-ohms knob adjustment provided. Features sensitivity of 20,000 ohms-volt DC, and 10,000 ohms-volt AC. Ranges—DC volts: 0-0.6, 0-6, 0-30, 0-120, 0-600, 0-1200, 0-3000, 0-6000 volts. AC volts: 0-6, 0-30, 0-120, 0-600, 0-1200 volts. Resistance: RX1, RX100, RX1K, RX10K. DC current: 0-0.06, 0-6, 0-60, 0-600 ma. Decibels: -20 to -17 (0 db - 0.774 V). Capacity: .0001-.01, .005-.20 mfd. Output ranges: 0-6, 0-30, 0-120, 0-600, 0-1200 volts.
Complete with color-coded heavy duty test probes and battery. Size: 6x3 1/2"x1 3/4". Shpg. wt., 1 1/4 lbs.
TE-12 Net 17.95
TE-37 Felt-lined carrying case for above instrument Net 2.95

The NEW LAFAYETTE

CHOOSE THE PLAN THAT SUITS YOU BEST:

- REGULAR PLAN.** Monthly Payments as low as \$5. No Down Payment. (See Easy-Pay Payment Schedule.)
- E-X-T-E-N-D-E-D PLAN.** Up to 24 months to pay. No Down Payment. (See Easy-Pay Payment Schedule.)
- ALTERNATE 60-DAY PLAN** — No Credit Service Charge. Select the Regular or Extended Plan. Remit your payment within 30 days as scheduled. Pay the full balance, if any remains, within 60 days of shipment and you automatically convert to the Alternate 60-Day Plan and **SAVE THE ENTIRE CREDIT SERVICE CHARGE.**

Lafayette's Easy-Pay Plan
Makes It Easier For You To Buy Now . . .

10 TIMES EASIER

- IT'S EASY TO OPEN AN ACCOUNT.** Fill in the agreement on the back of any order blank.
- IT'S EASY TO ORDER.** Use any regular Lafayette order blank. Initial orders may be as low as \$20.
- NO DOWN PAYMENT.** Whether you pay within 60 days, or 24 months, you need pay no money down.
- IT'S EASY TO MAKE "ADD-ON" PURCHASES.** No Money Down on orders over \$20.
- "ADD-ON" PURCHASES AT ANY TIME.** No need to pay the current balance in full before ordering again.
- UP TO 24 MONTHS TO PAY.** There's no need to wait—"buy what you want NOW, up to 24 months to pay.
- LOW CREDIT SERVICE CHARGES.**
- SEND NO MONEY FOR 30 DAYS.** First instalment payment due 30 days after shipment.
- ONE LOW MONTHLY PAYMENT** buys anything Lafayette sells. (Pre-recorded tapes, records, and items intended for resale excepted.)
- NO WAITING FOR MONTHLY STATEMENTS.** You always know the exact amount of your balance.

"DOLLAR POWER PLUS"

You Get "DOLLAR POWER PLUS" with Lafayette's 3-IN-1 Easy-Pay Plan. One Low Monthly Payment Buys More For You.

Monthly Payments FOR ONLY	Unpaid Balance (Total amount less down payment - if any) YOU CAN BUY UP TO
\$ 5	\$100.00
6	120.00
7	140.00
8	160.00
9	180.00
10	200.00
11	225.00
12	250.00
14	275.00
15	300.00
17	350.00
19	400.00
22	450.00
24	500.00

For monthly payments on balances over \$500, please write us.

3-IN-1

easy-1

pay plan

No Money Down

Here's How To Open Your Easy-Pay Account:-

Use the regular Lafayette order blank (more will be supplied upon request). Complete both sides of the form carefully, following the step-by-step instructions and illustration. Accuracy will speed handling of the form from the moment of receipt and permit immediate shipment upon approval of credit. Be sure to sign the agreement and indicate which Easy-Pay Plan you prefer — the liberal Regular or special Extended.

For both Plans, minimum order is \$20 and first instalment is not due until 30 days after shipment.

No Credit Service Charge for the alternate 60-Day Plan. For the Regular and Extended Plans, you are privileged to prepay the balance in full at any time to obtain a partial rebate of normal credit service charges.

Easy-Pay privileges are available to qualifying U.S. citizens or residents of all 50 States, Puerto Rico, Canada; and U.S. territories having comparable postal and express facilities. Any responsible individual over 21 years old with a steady source of income can apply.

RETAIL INSTALLMENT CONTRACT

Buyer's Copy Mailed—Date _____ By _____

(Please Print)
 Name _____
 Present (A) Home Address _____
 City _____ Zone _____ State _____ Telephone _____

To fill in spaces below correctly refer to EASY PAY PLAN Schedule on this sheet and note example.

EXAMPLE—(Standard Plan)

If Item (5) Unpaid Balance = 106.50
 Item (6) Credit Service Charge = 11.00
 Item (7) EASY PAY Balance = 117.50
 Your Monthly Payment (See Schedule) is 10.00
 You will pay \$10.00 for 11 months or 110.00
 And your FINAL Monthly payment will be 7.50

Beginning one month after shipment BUYER AGREES TO PAY \$ _____ per month for _____ months, and a FINAL monthly payment of \$ _____ to the place and/or to any party designated in writing by the Seller.

1. Total Cash Price* _____
 2. Sales Tax (N.Y.C. only) _____
 3. Total (Items 1+2) _____
 4. Down Pay (Altho Not Required Reduces Svce. Chrgs. & Paymts.) _____
 5. Unpaid Balance (item 3 minus item 4) _____
 6. Credit Service Charge (See EASY PAY Schedule) _____
 7. EASY PAY BALANCE (Add items 5+6) _____

Total EASY PAY Price (Add items 3+6) _____
 Do not include shipping charges. Easy Pay orders are sent shipping charges collect, except for PARCEL POST CHARGES which are added to your account.

RETAIL INSTALLMENT CONTRACT (L.S.) DATE _____

Combined Am't. you wish to pay monthly \$ _____

How to convert to Alternate 60-Day Plan. Pay 1st installment within 30 days of shipment. Complete payment of balance, if any remains, within 60 days of shipment and Save Entire Credit Service Charge.

Unpaid Balance Is	Standard Plan Monthly Payment	Extended Plan Monthly Payment	Standard Plan Credit Svce Charge	Extended Plan Credit Svce Charge
225.01 - 250.00	25.00	15.00	25.00	15.00
250.01 - 275.00	27.50	16.00	27.50	16.00
275.01 - 300.00	30.00	17.00	30.00	17.00
300.01 - 350.00	35.00	19.00	35.00	19.00
350.01 - 400.00	40.00	21.00	40.00	21.00
400.01 - 450.00	45.00	23.00	45.00	23.00
450.01 - 500.00	50.00	24.00	50.00	24.00
500.01 - 550.00	55.00	27.00	55.00	27.00
550.01 - 600.00	60.00	30.00	60.00	30.00
600.01 - 650.00	65.00	34.00	65.00	34.00
650.01 - 700.00	70.00	38.00	70.00	38.00
700.01 - 750.00	75.00	42.00	75.00	42.00
750.01 - 800.00	80.00	46.00	80.00	46.00
800.01 - 850.00	85.00	50.00	85.00	50.00
850.01 - 900.00	90.00	54.00	90.00	54.00
900.01 - 1000.00	100.00	58.00	100.00	58.00

On orders over \$500.00 Credit service charge and payments will be in proportion to amount shown on schedule.

NEW "EASY PAY PLAN" PAYMENT SCHEDULE

For purpose of receiving credit for above EASY PAY PLAN purchase, the buyer makes the following representation:

Permanent or previous address if (A) above is temporary or occupied less than two years. (Address) _____

Have you bought from Lafayette before? Yes No On Time Payment? Yes No If yes, please give your Lafayette Time Payment Account Number. No. _____

Permanent or previous address if (A) above is temporary or occupied less than two years. (Address) _____

Have you bought from Lafayette before? Yes No On Time Payment? Yes No If yes, please give your Lafayette Time Payment Account Number. No. _____

Name _____ Address _____ City _____ State _____

Age _____ Single Married Divorced Spouse Employed By _____

Real Estate Holdings—Address _____

Name _____ Address _____ City _____ State _____

Business Address _____

Name _____ Address _____ City _____ State _____

Bank Account With _____ Savings Checking (Address) _____

First Trade Reference _____ (Name) _____ (Address) _____ (City and State) _____

Second Trade Reference _____ (Name) _____ (Address) _____ (City and State) _____

Third Trade Reference _____ (Name) _____ (Address) _____ (City and State) _____

Nearest Relative _____ (Name) _____ (Address) _____ (City and State) _____

Name _____ (DO NOT LIST THOSE WITH WHOM YOU RESIDE) Address _____ Relationship _____

MINIMUM ORDER \$20.00 TOTAL CASH PRICE — NO DOWN PAYMENT

No money down when you buy with Lafayette's new Easy-Pay Plan.

ADDITIONAL PURCHASES: Once you establish credit, you can "add-on" to your account with purchases of \$20.00 or more. No down payment required on "add-ons" or re-opened accounts. Just list the items you want on the order blank, write "add to my account", give your account number, also "indicate" if you want instalment payments combined. Make certain you sign the Easy Payment Agreement.

NOTICE TO THE BUYER: 1. Do not sign this agreement before you read it or if it contains any blank space. 2. You are entitled to a completely filled in copy of this agreement. 3. Under the law, you have the right to pay off in advance the full amount due and under certain conditions to obtain a partial refund of the credit service charge.

LAFAYETTE RADIO ELECTRONICS CORPORATION (SELLER)
 111 JERICHO TURNPIKE, SYOSSET, L. I., N. Y.

hereof to be kept in good repair and unencumbered as described on reverse side address. Seller shall retain title to and right to possession of merchandise until fully paid. The unpaid balance of this order together with applicable credit service charge, may be added to an existing unpaid account, for convenience of both buyer and seller. Should the buyer place subsequent orders, unpaid balances on such orders may be combined with any balance owing on this order together with applicable credit service charge, if buyer so authorizes and seller accepts in appropriate spaces elsewhere in this contract. Upon default of any payment or payments seller may declare entire unpaid balance due at once and may also repossess merchandise retaining previous payments as compensation for the use thereof. If proceeds of resale of merchandise are insufficient to cover buyer's obligation, buyer will pay the deficiency to seller; if proceeds result in overage, seller will pay such overage to buyer. Payments will be made to the place and/or to any party designated by the seller in writing.

LAFAYETTE RADIO ELECTRONICS CORPORATION (SELLER)
 BUYER SIGN HERE Signed

RETAIL INSTALLMENT CONTRACT

Buyer's Copy Mailed—Date _____ By _____

(Please Print)
 Name _____
 Present (A) Home Address _____
 City _____ Zone _____ State _____ Telephone _____

To fill in spaces below correctly refer to EASY PAY PLAN Schedule on this sheet and note example.

EXAMPLE—(Standard Plan)

If Item (5) Unpaid Balance = 106.50
 Item (6) Credit Service Charge = 11.00
 Item (7) EASY PAY Balance = 117.50
 Your Monthly Payment (See Schedule) is 10.00
 You will pay \$10.00 for 11 months or 110.00
 And your FINAL Monthly payment will be 7.50

Beginning one month after shipment BUYER AGREES TO PAY \$ _____ per month for _____ months, and a FINAL monthly payment of \$ _____ to the place and/or to any party designated in writing by the Seller.

1. Total Cash Price* _____
 2. Sales Tax (N.Y.C. only) _____
 3. Total (Items 1+2) _____
 4. Down Pay (Altho Not Required Reduces Svce. Chrgs. & Paymts.) _____
 5. Unpaid Balance (item 3 minus item 4) _____
 6. Credit Service Charge (See EASY PAY Schedule) _____
 7. EASY PAY BALANCE (Add items 5+6) _____

Total EASY PAY Price (Add items 3+6) _____
 Do not include shipping charges. Easy Pay orders are sent shipping charges collect, except for PARCEL POST CHARGES which are added to your account.

RETAIL INSTALLMENT CONTRACT (L.S.) DATE _____

Combined Am't. you wish to pay monthly \$ _____

How to convert to Alternate 60-Day Plan. Pay 1st installment within 30 days of shipment. Complete payment of balance, if any remains, within 60 days of shipment and Save Entire Credit Service Charge.

Unpaid Balance Is	Standard Plan Monthly Payment	Extended Plan Monthly Payment	Standard Plan Credit Svce Charge	Extended Plan Credit Svce Charge
225.01 - 250.00	25.00	15.00	25.00	15.00
250.01 - 275.00	27.50	16.00	27.50	16.00
275.01 - 300.00	30.00	17.00	30.00	17.00
300.01 - 350.00	35.00	19.00	35.00	19.00
350.01 - 400.00	40.00	21.00	40.00	21.00
400.01 - 450.00	45.00	23.00	45.00	23.00
450.01 - 500.00	50.00	24.00	50.00	24.00
500.01 - 550.00	55.00	27.00	55.00	27.00
550.01 - 600.00	60.00	30.00	60.00	30.00
600.01 - 650.00	65.00	34.00	65.00	34.00
650.01 - 700.00	70.00	38.00	70.00	38.00
700.01 - 750.00	75.00	42.00	75.00	42.00
750.01 - 800.00	80.00	46.00	80.00	46.00
800.01 - 850.00	85.00	50.00	85.00	50.00
850.01 - 900.00	90.00	54.00	90.00	54.00
900.01 - 1000.00	100.00	58.00	100.00	58.00

On orders over \$500.00 Credit service charge and payments will be in proportion to amount shown on schedule.

For purpose of receiving credit for above EASY PAY PLAN purchase, the buyer makes the following representation:

Permanent or previous address if (A) above is temporary or occupied less than two years. (Address) _____

Have you bought from Lafayette before? Yes No On Time Payment? Yes No If yes, please give your Lafayette Time Payment Account Number. No. _____

Permanent or previous address if (A) above is temporary or occupied less than two years. (Address) _____

Have you bought from Lafayette before? Yes No On Time Payment? Yes No If yes, please give your Lafayette Time Payment Account Number. No. _____

Name _____ Address _____ City _____ State _____

Age _____ Single Married Divorced Spouse Employed By _____

Real Estate Holdings—Address _____

Name _____ Address _____ City _____ State _____

Business Address _____

Name _____ Address _____ City _____ State _____

Bank Account With _____ Savings Checking (Address) _____

First Trade Reference _____ (Name) _____ (Address) _____ (City and State) _____


Second Trade Reference _____ (Name) _____ (Address) _____ (City and State) _____

Third Trade Reference _____ (Name) _____ (Address) _____ (City and State) _____

Nearest Relative _____ (Name) _____ (Address) _____ (City and State) _____

Name _____ (DO NOT LIST THOSE WITH WHOM YOU RESIDE) Address _____ Relationship _____

LAFAYETTE Where America Shops... and Saves



ELECTRIC POWER PLANT
145.50
NO MONEY DOWN
1000 WATT

- 3-H.P. Engine
- 90-Day Parts Warranty
- Regulating Governor
- Easy-To-Use Rope Starter
- 1000 Watts Continuous - 1250 Watts Intermittent

A compact, rugged direct coupled power plant. Supplies 115 V.A.C., 60 cycles at 1000 watts continuous, 1250 watts intermittent duty. The engine is a 3 h.p., 4 cycle, air cooled Briggs & Stratton. Operates on regular gasoline. Uses standard weight motor oils. Recoil manual start. Drip-proof, continuous duty, self excited, 2 pole, 3600 RPM generator. Features a pre-lubricated, sealed, ball-bearing commutator, mica insulated, 3 cycle maximum frequency variation. $\pm 5\%$ voltage regulation. Gas consumption at 1000 watts; 0.2 gal per hr.; at 1250 watts, 0.39 gal. per hr. Includes instructions, parts lists and 90 day parts warranty. Made in U.S.A. Shpg. wt., 70 lbs. VIA EXPRESS ONLY. ML-266WX Net 145.50

1750 WATT POWER PLANT

A dependable, carefully constructed and fully tested generating plant. Delivers 115 V.A.C., 60 cycles at 1750 watts continuous duty, 2000 watts intermittent duty. Features an air-cooled, 4 H.P., 4 cycle Clinton engine. Recoil type manual start. Uses regular gasoline and standard motor oils. The generator is a drip-proof, continuous duty, DC self excited, 2 pole, 3600 RPM, revolving armature type. Brushes adjustable to take up wear. Pre-lubricated, sealed, ball bearing commutator. Max. frequency variation, 3 cycles; $\pm 5\%$ voltage. Duplex outlet, 0-150 V. A.C. meter. Includes instruction and parts manual and 90 day parts warranty. Made in U.S.A. Shpg. wt., 110 lbs. VIA EXPRESS ONLY. ML-267WX Net 194.50

2500/3000 WATT POWER PLANT

- Built-in Overload Protection
- 5 1/2 H.P. 4-Cycle Engine
- Continuous Duty Generator
- 0-150V AC Voltmeter
- Filtered To Minimize Line Noise

A heavy-duty power plant with all the "extra" features included as standard equipment. Powered by a 5 1/2 H.P., 4 cycle, air-cooled Briggs & Stratton ball bearing engine. Operates on regular gasoline and standard motor oil. Produces 2500 watts, 115 V.A.C., 60 cps, continuous duty; 3000 watts intermittent duty. Gas consumption is 0.65 gal. per hr. at 2500 watts. Fuel Tank holds 6 qts. Continuous duty, drip-proof, D.C. self excited generator. 2 pole, 3600 RPM, revolving armature. Pre-lubricated, sealed, ball bearing construction. Self-cooled via a centrifugal blower. Adjustable copper graphite brushes. Voltage regulation $\pm 5\%$, 3 cycle max. frequency variation. Voltmeter reads 0-150 V.A.C. Includes instructions, parts list and 90 day warranty. Made in U.S.A. Shpg. wt., 156 lbs. VIA EXPRESS ONLY. ML-268WX Net 279.95

BURGESS RADAR-LAMP

SAFE DEPENDABLE LIGHT WHEN YOU NEED IT

Only **5.73**

- Room Filling Light
- Camping
- Corrosion-Proof

Indoors or out, the Radar-Lamp is one of the safest portable lanterns made. Can be used in any position without danger of explosion. Battery power means no heat, no fumes, no matches—even children may operate it with complete safety. Lantern head provides 360° illumination, enough to fill a room with usable light. Convenient too. Long lasting battery gives up to 4x the service of old fashioned lantern batteries. Leakproof, weatherproof, corrosionproof. Separated head and battery design banishes corrosion damage. ML-303 Shpg. wt., (with battery) 4 1/2 lbs. Net 5.73 BA-163 TWI Battery. Shpg. wt., 3/4 lbs. Net 1.83



STEEL FRAME WORK BENCH



Includes Tool Rack, Peg Board Back Panel and Bottom Shelf

- Sturdy, All-Steel Frame
- Large 24x48" Work Top
- A Complete and Serviceable Work Shop

17.75

Tools not included


A new all-steel frame work bench that is the ultimate in convenience and serviceability. The rigid, all-steel frame is the core of this complete workshop that will last for years. Features a big 24" x 48" work top of special, heavy-duty, compressed, high-impact board to withstand the roughest use. Matching bottom shelf offers handy storage space. Convenient tool rack with peg board back panel. Base on each leg gives extra support and can be bolted down if desired. Easy-to-assemble. 34 1/2" high. (Tools not included). ML-298WX Shpg. wt. 60 lbs. Net 17.75

DRY CHEMICAL FIRE EXTINGUISHER

The Most Efficient Fire Extinguisher Ever Made!

- 6 B:C—Highest U.L. Rating for ITS SIZE
- Exceeds I.C.C. & U.S. Coast Guard Requirements
- Safety Zone Pressure Gauge
- 12 Times as Effective as 1 1/2 Quart Carbon Tetrachloride Units
- Twice as Effective as CO₂ Extinguishers of Comparable Size

The most powerful, efficient fire extinguisher of its size. This new Perfection dry chemical extinguisher utilizing a specially developed non-toxic, non-corrosive dry chemical powder is rated 6 B:C by Underwriters' Laboratories. A rating usually found only in 4 lb. and 5 lb. units. Other features include: Extremely fast rate of damp in spraying chemical, non-clogging valve insures perfect closure without leaking, Safety Zone Pressure Gauge shows instantly whether extinguisher is ready for use, reveals tampering or unreported use, plus a forged brass valve body equipped with vehicle mounting bracket locking clamp. Shpg. wt., 7 lbs. HD-987 Net 11.33



11.33

DO-IT-YOURSELF RECHARGE KIT. Contains 2 3/4 lbs. of Dry-Kern-S dry chemical powder. Shpg. wt., 5 lbs. HD-988 Net 1.47

HEAVY DUTY BLOWER

- 3050 RPM—100 Cubic Feet Per Minute
- 4" Intake Diam.—2 1/4" Output Diam.
- Air Rotor 3 1/8" Diam.



6.95


Efficient, quiet, dependable and economical—for use in many applications: air distribution in confined areas, exhausting gas and fumes, etc. Especially suitable for marine, commercial and home ventilation equipment. Shaded-type motor for efficient, quiet operation. Welded pressed steel housing. 3050 RPM; moves 100 C.F.M. For 115 V, 60 cycle. SP-255 Shpg. wt. 6 lbs. Net 6.95

LAFAYETTE STEEL STORAGE UNITS

5.95

- For 4 Shelves 30"x12"x60"
- Triple Bent Shelves
- Heavy Angle Posts
- Shelves Adjustable on 1 1/2" Centers
- Braced on Back & Sides

For stores, offices, garages, basements, pantries, closets—just what you need to solve your storage problems, you'll find dozens of uses for these rugged racks. And now, Lafayette offers them at a bargain price. Available in two sizes to fit virtually anywhere—30Wx12Dx60"H with 4 shelves, or 36Wx12Dx72"H with 5 shelves. Corner post and all edges are rounded and snag proof with back and side braces providing added strength and rigidity. Gray enamel finish. Shipped unassembled with all necessary hardware for fast easy assembly. Size 12x30x60". Shpg. wt., 25 lbs. ML-306WX Net 5.95 Size 12x36x72" Shpg. wt., 33 lbs. ML-305WX Net 6.89



HEAVY-DUTY SUMP PUMP

- Rust-Proof Cast Aluminum Base
- Rust-Proof Seamless Aluminum Column
- 3,920 Gallons-per-Hour to a 10-ft. Head

NO MONEY DOWN **37.50**

A rugged automatic electric pump with a dependable 1/2 HP motor with safety-designed overload protector. Features a plastic float, non-corrosive in any water; extra large separate screen to prevent clogging; vertical 1 1/4" discharge that eliminates base elbow. Lifetime guarantee on all moving parts (1-yr. guarantee on electrical components). Dilute base bearing for long life. Individual pressure plate to assure consistent water flow. Designed to operate at top performance.

Gallons Per Hour	Discharge Height
3,920	10-ft.
3,215	15-ft.
1,600	20-ft.
540	25-ft.

ML-297WX Shpg. wt. 25 lbs. Net 37.50

LAFAYETTE "Sprazon" —



- If It Can Be Painted, You Can Use Lafayette "Sprazon"
- For Indoors and Outdoors
- Dries in Minutes

SPRAY PAINT

Modern fast way to paint. Give a lasting finish to all types of surfaces. Time tested alkyl resin spray enamel base. Made by dependable chemists under the strictest quality control, superior in quality and performance. Can be used on garden tools, furniture, boats, appliances, tools, automobiles, furnaces, kitchen cabinets. Picture frames and etc. 16 oz. can. Shpg. wt., 1 1/2 lbs.

Stock No.	Color	16-oz. can,
P-480	Glossy White	99c ea.
P-481	Flat White	
P-482	Ivory	
P-483	Glossy Black	
P-484	Flat Black	
P-485	Machine Gray	
P-486	Dove Gray	
P-487	Cherry Red	
P-488	Baby Pink	
P-489	Regal Blue	
P-490	Alpine Green	Any 3, 89c ea.
P-491	Hunter Green	
P-492	Mist Green	
P-493	Orange Flame	
P-494	Bright Yellow	
P-495	Pastel Yellow	
P-496	Brown	
P-497	Bright Silver	
P-498	Bright Gold	

CRYSTAL CLEAR PROTECTIVE SPRAY

Forms a clear protective coating on metal, wood, paper, etc. Has high weather proofing qualities. 16 oz. can. Shpg. wt., 1 1/2 lbs. P-499 Net ea. .99 Lots of 3 ea. .89

ALL PURPOSE PRIMER

Provides excellent bond on bare metal surfaces. Available in gray only. 16 oz. can. Shpg. wt., 1 1/2 lbs. P-500 Net ea. .99 Lots of 3 ea. .89



INDOOR-OUTDOOR EXTENSION CORDS

- 2-Wire and 3-Wire, 16 Gauge
- Molded Connectors

Use Indoors and out, with power tools, refrigerators, mowers, fans, etc. All are 16-gauge, U.L. approved. 3 cond. cords have 3 prong plug.

Stock No.	Length	Cond.	Cap	Shpg. Wt.	Net
EL-105	25 ft.	2-wire	10 amp	1 1/4 lbs.	1.57
EL-106	50 ft.	2-wire	7 amp	2 lbs.	2.66
EL-107	100 ft.	2-wire	5 amp	3 lbs.	4.49
EL-108	25 ft.	3-wire	10 amp	1 1/2 lbs.	2.13
EL-109	50 ft.	3-wire	7 amp	2 1/4 lbs.	3.51
EL-110	100 ft.	3-wire	5 amp	3 1/2 lbs.	6.41

GRA-TITE

Multiples Your Strength More Than 20 Times

- Over 2000 Lbs. Capacity
- For Home, Farm, Shop, Autos, Camping, Civil Defense
- Lightweight Sturdy Construction

The Mighty Muscle provides you with tremendous lifting or pulling power with an over 2000 pound capacity. Actually multiplies a man's strength more than 20 times. Note these features: a safety factored panel gives instant release. Cannot be accidentally disengaged. Steel aircraft cable of 3/4" diameter has over 4,000 lbs. test strain. Easy to operate. 8 holes for handle give maximum number of adjustment positions. Lightweight, the complete assembly weighs only 6 lbs. Unconditionally guaranteed against defects by the manufacturer. Complete assembly includes cable, hook and 12" steel handle. Shpg. wt., 7 lbs. HD-989 Net 23.95




23.95

CABLE LOCK — LOCKS ANYTHING, ANYPLACE

- Stainless Steel Construction
- Over 1-Yard Aeroplane Cable
- Compact and Lightweight

ONLY **3.39**



A new type of lock that performs multiple service—luggage, auto, house, bike, sports equipment, etc. Just pull out the flexible cable (tested for strength at 2000 lbs.), stop, and lock it at the length required as it conforms with the shape of the object. Stainless steel construction—locking mechanism cannot rust. Compact in size; weighs only 5 1/2 ozs. HD-997 Shpg. wt. 1 lb. Net 3.39

Famous SMALL FRY Portable Alcohol Stove

- SPILLPROOF
- EFFICIENT • ODORLESS
- ECONOMICAL
- SMOKELESS

3.75

Made of long lasting, light-weight aluminum within ceramic case that completely absorbs the alcohol fuel, this remarkable alcohol stove is so safe you can roll it along the floor while it's burning. Perfect for Civilian defense shelters, for hunters, fishermen, campers and for the patio. Use it to make coffee anywhere, warm the baby bottle or cook a complete meal. Boils water in 12 minutes. Burns 3 hours for 10c of fuel. Weighs only 24 ounces and measures a compact 5 x 5 inches—small enough to fit into most glove compartments. Shpg. wt., 2 lbs. ML-307 Net 3.75



SEE-THRU PLASTIC CABINETS



CABINETS

- Decorator Styled
- 1-Piece Frames
- Divided, Spill-Proof Drawers
- Cabinets Interlock and Stack

3.99

for 21 Drawers




Decorator-styled cabinets for use in any room, for most any storing use—jewelry, sewing, knick-knack, handyman, office, etc. Extra-strong, one-piece high-impact styrene plastic. Spill-proof drawers are divisible by transparent dividers. Cabinets interlock and stack securely for increased utility. MC-46 21 Drawers; Shpg. wt. 4 1/2 lbs. Net 3.99 MC-47 15 Drawers; Shpg. wt. 3 1/2 lbs. Net 2.99 MC-48 9 Drawers; Shpg. wt. 2 1/2 lbs. Net 1.99

NEW! ASTRO-LITE EMERGENCY LIGHT TURNS ITSELF ON WHEN ELECTRICITY FAILS

13.33

A Must For Every Home, Office & Factory—This new development in emergency lighting offers protection in case of electrical failure, windstorm, floods, hurricanes etc. The Astro-Lite turns itself on automatically when power fails. Keep it ready as an emergency light or use it continuously as a night light. Ruggedly constructed, the Astro-Lite utilizes a heavy duty replaceable bulb and lantern type battery that will burn constantly for 25 hours and has a shelf life of 3 years. Decorator designed to provide an attractive wall fixture, the Astro-Lite may be employed as a free standing unit or easily wall mounted. Measures only 6 1/2 x 8". Shpg. wt., 5 lbs. ML-304 Net 13.33



NEW! AERO/MATCH SPRAY BRUSH



only **1.83**

- CAN SPRAY MIXED COLORS
- COMPLETELY PORTABLE—NON-ELECTRIC

Now you spray and match exactly the same paint you buy for brushing. Since you fill the sprayer with your own paint, you can match anything—even multi-colors. The 15 oz. power unit is bigger, more powerful—outlasts about three aerosol paint cans. Operates on a non-toxic, non-inflammable, pressurized gas. Unsurpassed for small or medium paint spraying. Spray brush requires no special skill... easy to use... easy to clean. Precision spray needle is made of metal and set in metal. Not affected by paint solvents. Can spray any liquid paint, insecticide, polish, antiseptic, etc., and many powders. HD-972 Net 1.83 HD-973 Replacement Power Unit Net 1.24

SPECIAL VALUE POWER TOOLS

8" TILT ARBOR "MOTERTOOL" SAW with G.E. 3/4 H.P. MOTOR

- You Also Get All This:
- Rugged All-Steel Stand
 - 2 Cast-Iron Table Extensions
 - 8" Combination Blade
 - Front & Rear Locking Rip Fence
 - Precision Mitre Gauge
 - Rubber Drive Belt
 - Safety Clutch
 - 8-Ft. Cord and Plug

99.95
NO MONEY DOWN

A complete, compact machine with enclosed motor—you just plug it in, flip the switch and it's ready to operate. With this all-in-one package you can add a room, build a garage, make cabinets, build furniture and much more. Does every sawing operation—cross cutting, ripping, beveling, mitering, dadoing, tenoning, sanding, molding, shaping. Table extends to 28 1/2 x 17 1/4" with extensions. Blade guard and motor tilt to 45°. Precision ball bearing arbor unit. HD-975WX Shpg. wt., 90 lbs. Net 99.95
8" MOTERTOOL TILT ARBOR SAW. Same as above, without extensions, blade and stand. Table top 14 1/2 x 17 1/4". Shpg. wt., 58 lbs. HD-891WX Net 78.50
EXTENSIONS, Set of 2 for HD-891WX. Cast iron. Extends work surface to 28 1/2 x 17 1/4". Shpg. wt., 28 lbs. HD-892W Net 16.50
POWER TOOL STAND. Fits HD-891WX. Heavy steel; slotted for adjustments. Length 21"; width 17 1/4"; height adjusts 24-33 1/4". HD-953WX Shpg. wt., 33 lbs. Net 17.13
HD-993 8" Crosscut Blade Net ea., .98
HD-994 8" Rip Blade Net ea., .98
HD-995 8" Combination Blade Net ea., .98



4 1/2" "MOTERTOOL" JOINTER

- Complete with Motor, Cord, Plug, Switch, 2-Way
- Ball-Bearing Construction
- Tilting Fence




With 3/4 H.P. General Electric Motor built right in. This machine is permanently set up to operate. Has exclusive "Parallel Motion" design which assures 3/32" between the cutting knife and table edge at any depth of cut. All Ball Bearing construction. Outfeed as well as infeed table adjustable. Maximum cuts: width 4 1/2", depth 3/8", Rabbet depth 3/8". Over-all length 30 3/4". Cast iron tables and base. Comes complete with built-in 3/4 H.P. Motor, Cord, Plug and Switch, and 2-way Tilting Fence. HD-890WX Shpg. wt., 53 lbs. Net 71.50

POWER TOOL STAND

Overall length 21". Height adjustable, 24-33 1/4". 17 1/4" wide. Heavy steel construction, slotted for adjustments. Shpg. wt., 33 lbs. HD-953WX Net 17.13

UNIMAT MINIATURE MACHINE SHOP

- Tolerances To .0005"
- Only 16" Long, 5" High
- 11 Spindle Speeds




This small scale combination drill press-lathe-grinder finds extensive application in electronic labs, hospitals, government research agencies, as well as in home workshops. Motor directly attached to headstock, may serve as a hand tool. Belt drive adjustable for speeds 225 to 4,000 r.p.m. Headstock rotates 360° for off center operation. Straight and taper turning. Adaptable for threading, milling, sawing. Cast iron lathe bed swing is 2.82"; center to center distance 6.69. "Special" unit includes 1/15 H.P. induction, fan-cooled motor, drill press vert. column and hand lever, face plate, lathe dog, grindstone arbor, tool post, 2 dead centers. Allen wrench, 1 1/4 x 10 1/2 x 5 1/4" wood chest. 32 page manual. Shpg. wt., 28 1/2 lbs. AC/DC 115 V operation. HD-956WX Net 99.50

"Basic" Unit. Same as above but with 3 jaw universal lathe chuck with reversing jaws, 1/4" Jacobs chuck and key. HD-957WX Shpg. wt., 30 lbs. Net 129.50
Universal lathe chuck for "Special" unit. HD-958 Shpg. wt., 2 lbs. Net 23.50
Jacobs drill chuck (1/4") for "Special" unit, key. HD-959 Shpg. wt., 1 lb. Net 9.75

TOOLKRAFT 10" RADIAL-ARM SAW

- Off-Set Motor Shaft Design Enables 3 1/2" Deep Cut With 10" Blade
- Rear Motor Shaft Takes Accessories
- Rotates 360° Horizontally



Among circular saws the radial-arm type offers the most in safety, performance and operating ease. This 10" radial-arm saw permits work to be held firmly where it can't fly-off and allows the least bodily exposure to the blade. GE 1 H.P. motor has "safety slip" clutch to prevent burn-out. Triple point ball bearing motor carriage suspension. Column of 3" diam. heavy-walled steel with 9" travel; rides in 12" cast iron pedestal. All 10 controls are in front for convenience. Recessed safety switch. Exclusive depth scale. Table of laminated maple. Cross-cuts 17 1/2", rips 31 1/2" of saw arbor. 4200 r.p.m. cutting speed. Motor requires 115/230 V. 60 cycles @ 12.4 amps (continuous duty). Ball bearings used throughout. HD-954WX Shpg. wt., 235 lbs. Net 221.30
Floor Stand for Radial-Arm Saw. HD-955WX Shpg. wt., 25 lbs. Net 14.90


FLEXI-SHAFT HOBBY TOOL

- A real hobby work horse
- Powerful—Versatile
- Hi-Speed—Hi Torque



Flexible shaft and motor combination to do all your hobby grinding — polishing — drilling — sawing — buffing — etching — engraving — routing — carving. Husky, 1 amp motor delivers plenty of power for hard, continuous use. Will not stall under normal usage. Lightweight finger tip control—for intricate hobby work. 36", easily handled, shaft is a sealed tamper proof unit. Will not heat up under prolonged use. Chuck accommodates standard 3/32 and 1/8 inch tool shanks. For use on wood—metals—glass and plastics. 110/120V. AC or DC. Shpg. wt., 3 lbs. HD-849 Net 6.60

6 PC. MOUNTED STONE SET



- Ideal Accessory For The Flexi-Shaft Tool

Six assorted grinding stones and wheels. Selected set of mounted grinding points, stones, wheels. For carving—routing—grinding—sharpening—deburring—sawing—buffing—polishing. Mounted on 1/8" and 3/32" shafts. Shpg. wt., 8 oz. HD-920 Net 1.20

SPRAVIT 600 PROFESSIONAL-STYLE SPRAY UNIT

- Integral Compressor-Motor
- All-Aluminum Spray Gun
- Sprays Oil, Paints, Stains

26.21
NO MONEY DOWN



All-purpose spray unit that gives professional results from the start. Adjusts pattern from small-as-a-dime to a fan 10" wide—4 times faster than a brush, and cleans easier too. Easy-to-use 2-finger trigger gun. Never needs lubrication. Air delivery: 1.5-2.0 CFM @ 15-20 lbs. Complete with 6-ft. cord with plug, 8-ft. hose with connections. HD-933 Shpg. wt., 11 lbs. Net 26.21

Stanley 1/4" Power Drill




- APPROVED AND POWERED FOR FULL TIME USE
- 3 AMP—2500 RPM—AC MOTOR
- PRECISION GEARED CHUCK

13.97

The perfect drill for use with drill attachments. Designed for continuous duty—ease of maintenance. Advanced styling for comfort and balance. Dependable bronze bearings—extra long brush life. 2500 RPM no-load speed. 1600 RPM under full load. Capacity 1/4" in steel, 1/2" in hardwood. Trigger switch with locking pin for intermittent or continuous run. Accurately machined precision gears. High speed airflow ventilation. 8 1/2" overall length. Weighs only 3 1/4 lbs. 3 Amps, 115v. AC only. Shpg. wt., 4 1/2 lbs. HD-702 Net 13.97

STANLEY Heavy Duty SABRE SAW



27.97

- CUTS 2" LUMBER—1/2" STEEL BARS
- CUTS FLUSH TO A WALL
- FULL 3/8" STROKE—3300 STROKES PER MINUTE
- ANTI VIBRATION MECHANISM

New Stanley Heavy Duty Sabre Saw—rugged enough to cut 1/2" steel bars. Will do the work of rip, crosscut, band, jig, keyhole and hack saws. Particularly suited for use where it's difficult to use a circular or band saw. Cuts curves, scrolls, pockets, intricate patterns in wood, plastics, veneers. Cuts full 2" lumber—conduit—cable—1/2" steel bar—aluminum—brass. 2 position base plus flush cutting blade allows cuts right up to a wall. Improved chip blower—single screw blade lock—positive slide switch—cool, comfortable handle. 2.5 amp. 115v. AC/DC motor. Includes one each wood—metal—and flush cutting blade. Shpg. wt., 6 1/2 lbs. HD-701 Net 27.97

STANLEY Heavy Duty ROUTER




- HIGH SPEED PRODUCTION ROUTER
- 3/4 HORSEPOWER
- 23,000 RPM MOTOR
- BUILT-IN SPOTLIGHT
- MICROMETER DEPTH ADJUST—TO 4/1000"
- AUTOMATIC SHAFT LOCK—NEEDS ONLY 1 WRENCH

45.47

The most advanced router design in the world. Most perfect balance and control available. Highest safety and performance level. Cuts dovetails—dadoes—tenons mortises—rabbets—beading—molding—joints—grooves—decorative cuts—inlays—cuts soft metals. Built in spot-light increases brightness as work load increases. Recessed switch automatically locks shaft when changing bits. Precision micro-depth adjustment as fine as .004 inch. Cantilevered base and advanced design grips for stability and balance. Clamping lever holds or releases motor with a flip. 6 amp., 23,000 RPM. 115v. AC/DC. Shpg. wt., 9 1/2 lbs. HD-700 Net 45.47
Basic Bit Kit: Includes three most useful router bits 1/4" straight, 3/8" rounding over, 3/8" V grooving. Also includes a Silicon Carbide hone to keep cutting edges keen. Shpg. wt., 1/2 lb. HD-709 Net 6.97


Stanley Heavy Duty Builders Saw



- PERFECTLY BALANCED
- 9.5 AMPS—5000 RPM
- SELF-LUBRICATING BALL AND BRONZE BEARINGS

Power-packed 9.5 amp motor provides high cutting force. Wrought aluminum base connected to motor housing by spring steel beam. Rear position control panel. Rear-position wing-nuts for depth and bevel adjust. "Free Start" ball bearing guard—moves at slightest pressure. Big "window" for wide open view of cut. "Motor Saver" drive protects motor against damage when blade cuts nails or knots. Weighs only 9 3/4 lbs. Cuts 3/4" to 2" at 45°, 3/8" to 2 1/4" at 90°. Blade size 7 x 3/8". 5000 RPM no load speed. Ball and bronze bearings. 9.5 amps. 115/230 volts AC/DC. Shpg. wt., 13 1/2 lbs. HD-938 Net 34.97

GYRO-DRIVE




- Full-Power Full-Speed Drilling Up to 52 Degrees Off Center
- A Must For Electricians, Plumbers, Mechanics, TV Men, Telephone Installers

6.67

Net 6.87

Here is the amazing drive which converts any 1/4" or 1/2" drill into a variable angle tool — drills in the tightest quarters, "around corners." Immediate angular positioning of the bit at angles up to 52°. Can be mounted into any 3/8"-24 male or female drill spindle. Threaded sleeve for 1/4" or 1/2" chuck, (chuck not supplied). May be permanently installed on drill or mounted in drill chuck, with additional chuck added on operating end. Removable hand grip bar for applying vertical pressure when drilling is difficult. Shpg. wt., 1 1/2 lbs. HD-950 Net 6.87

NEW CHASSIS PUNCH SET



- EASY-SMOOTH-HOLES IN SHEET METAL
- 5 SIZES: 1/4", 5/8", 3/4", 1", 1 1/8"

5.49

Five most often needed round hole punches. Do the job in minutes—save hours of tedious hand labor. Cuts smooth accurate holes for sockets—plugs—controls—panel lights—switches—terminals—most radio parts. Works equally well with sheet metal—sheet plastics—composition board, etc. Drive with any wrench—or with T handle included. Punch sizes included are 1/4", 5/8", 3/4", 1" and 1 1/8". Supplied complete with punches, dies, T drive handle, tapered reamer, fitted wooden case and instructions. Shpg. wt., 2 1/2 lbs. HD-471 Net ea., 5.49, Net ea. in lots of 3, 4.94

NEW! SQUARE PUNCH SET



- 3 NEEDED SIZES—1/2" — 5/8" — 1"
- SMOOTH, ACCURATE, EASY TO USE

6.95

Save time—save effort—cutting square holes in chassis—panels—sheet metal up to 1/8". Most often needed sizes for square chassis components. Multiple cuts allow any size square hole. Drive punches with any accurate square holes in metal—bakelite—plastic punches—dies—drive screw, T handle and wooden case. Shpg. wt., 2 lbs. HD-480 Net 6.95

MODEL 4100 VERSAMATIC

11.25



- WITH YANKEE STYLE BIT HOLDER
- TURNS 1/4" DRILL INTO HIGH POWER TOOL
- REVERSES—INCREASES POWER—REDUCES SPEED

Seven to one speed reduction develops tremendous torque! Hand clutch control for easy, instant stop-start action! Look at these fabulous features! Power screw driver—handles largest screws—reverses to extract them! Power drill tapping head! Plenty of power for oversize drilling! Perfect for concrete or any kind of masonry drilling! Low speed and high power for hole saw attachments! A professional tool that anyone can use! Comes complete with screwdriver bit—Phillips bit—1/4 socket set adapter—wrench pin and instruction book. Shpg. wt., 5 lbs. HD-195 Net 11.25

1/2" CHUCK FOR VERSAMATIC

Geared chuck—3/4" to 1/2" capacity—#33 taper to fit Supreme Versamatic. Shpg. wt., 1/2 lb. HD-268 Net 7.38



JACOBS TYPE DRILL CHUCK

Comparable to Jacobs 18 Key type geared tooth chuck. Capacity 0-1/4", thread 3/8x24". Ruggedly constructed. Polished finish. Used as standard equipment on most electric drills. Made to rigid specifications. Compare our really low price. You'll find this same chuck selling for twice as much! HD-186 Shpg. wt., 1 lb. Net 2.98



UNIVERSAL SQUARE

A versatile precision instrument for the workshop, this universal square can be used as a vertical level, horizontal level, 45° level, or as a square and sliding bevel. 7" steel blade is calibrated in inches and centimeters. Can be accurately set at any angle from 0 to 270°. Length is adjustable. Equipped with scriber. HD-967 Shpg. wt., 8 ozs. Net 1.63

ARC JOINT PLIERS

1.89

- Fully Chrome Plated

Heavy duty, slip-groove jointed water pump pliers. Fully chromed and polished. 5 adjustments. 1 1/2" parallel opening. Forged steel. Deep milled jaws. 9 1/2" long overall. Shpg. wt., 1 lb. HD-896 Net 1.89

THE RIGHT TOOLS AT THE RIGHT PRICE

THOR-SPEEDWAY 3/8" ELECTRIC DRILL



64-PIECE PROFESSIONAL POWER WORKSHOP


- A Complete Workshop For Do-It-Yourself Jobs
- Drills, Sands, Grinds, Buffs, Saws • Home, Garage, Shop

Here is the complete electric power workshop at Lafayette's typical low price. You can do almost every at-home job with this versatile 64-piece set. Look what you get: Thor Speedway 3/8" electric drill; 11-pc. power boring set with bits from 1/4" to 1 1/4"; 14-pc. twist drill set with metal index; 12-pc. sanding and polishing set; 7-pc. grind and buff set; 9-pc. 7-size hole saw; 7-pc. countersink and drill saw set; 3-pc. power screwdriver attachment. The Thor-Speedway 3/8" drill has 2.5 amp, 110 V AC motor. No-load speed, 1750 rpm; full load speed, 1150 rpm. Special alloy bearings throughout. U.L. approved. Shpg. wt., 10 lbs. **Net 19.95**

WEN 3 INCH BELT SANDER

- Extra-Duty 4 1/4 Amp Motor

MODEL 910



ONLY **33.05**
NO MONEY DOWN

- Compact, Balanced, Lightweight
- Forced Ventilation—Cools Motor and Removes Dust

Far more efficient than other sanding devices, the Wen Model 910 Belt Sander provides 850 square feet of abrasive material/minute. Its universal self-cooling motor may be used continuously for hours without overheating. Contour grip, 2 position knob, vibration-free bearings, balancing and lightweight (7 lbs.), remove fatigue from sanding. Belt changing in seconds. Flush design for close work. Complete gear drive with sealed bearings. Die cast polished aluminum housing. With 3 belts (coarse, medium, fine) and 6 ft. 3 conductor cord. Size: 5 1/4 Hx5 1/2 Wx10 1/2 L. For 115 V AC. Shpg. wt., 8 3/4 lbs. **Net each 33.05** In lots of 3, Each **29.37**

MO-937	Net	.49
MO-990 Coarse Sanding Belt (60)	Net	.49
MO-991 Med. Sanding Belt (80)	Net	.49
MO-992 Fine Sanding Belt (120)	Net	.49

NEW! FULL POWER 1/4" DRILL

8.88



OUR TOP DRILL VALUE!

- UL APPROVED • GEARED CHUCK AND KEY
- UNIVERSAL 3/8 H.P. MOTOR

Lafayette's top drill value. 1/4" geared chuck drill rated at a full 3/8th horsepower. Universal motor. U.L. approved. 1/4" capacity in steel, 1/2" capacity in hardwood. 1200 to 1500 rpm speed under load, 2000 to 2400 rpm no load speed. Precision anti-friction bearings. Automatic trigger switch. Specially designed gear train for maximum torque transfer. Overall length, 8". For 115 VAC, 25-60 cycles. Shpg. wt., 4 lbs. **Net 8.88**

THOR SPEEDWAY 3/8" DRILL

- UL AND CSA APPROVED
- PRECISION GEARED CHUCK WITH KEY
- HI-TORQUE MOTOR RATED AT FULL 2.5 AMPS



Here is a professional 3/8" electric drill at an amazingly low price. Hi-torque 2.5 amp, 110 VAC motor with 3-conductor lead cord, precision geared 3-jaw chuck with key, all-steel precision hobbled gears and newly developed special alloy bearings throughout. Capacity in steel, 3/8", in hardwood, 1". No load speed, 1750 rpm, full load speed, 1150 rpm. Momentary contact switch with locking pin. Sturdy diecast aluminum alloy housings with attractive silicone bonded finish. Overall length, 8 1/4". Shpg. wt., 5 lbs. **Net 11.95**

Thor-SpeedWay SUPER SANDER

11.89



- 2.75 AMP MOTOR
- MOTOR DRIVEN 3450 RPM
- SANOS—SMOOTHS—BUFFS—POLISHES—RUBS!
- USE SHEET OR FREE (WET) ABRASIVES

Work-saving power for the master craftsman! The top sander with universal electric motor. Rough or finish sanding and buffing are done twice as fast! Hi-speed orbital action produces perfect finish every time. No load speed, 3450 r.p.m. Paper size, 4 1/2 x 6 1/2"; sanding area, 4 1/2" x 5 1/2"; overall length, 8". Sealed ball and oilite bearings. Neoprene ball guide and pad. Two pole induction motor, AC only; standard voltage 115V. 6 ft. 3 conductor UL approved line cord. UL approved push button switch. Shpg. wt., 6 lbs. **Net 11.89**

MO-865 Lambswool Polishing Pad	Net	.79
MO-866 18 Sheets, Ass'td Sandpaper	Net	.98



13.88

Thor-SpeedWay SUPER JIG SAW

- CUTS 2" WOOD—1/4" STEEL
- 3 AMP MOTOR
- 3000 STROKES PER MINUTE

Enjoy a new thrill in sawing! The powerful No. 5 jig saw cuts curves, scrolls, straight cuts and rips. Cuts 45° angle on either side. Cutting capacity: 2" soft wood, 1/4" in steel; length of stroke 3/4". Motor rating, 3 amps, no load speed, 3000 strokes per minute; oilite bearings. Base tilts 45°. Overall length 6 3/4", height 5". Universal series wound motor, AC or DC; positive on-off position, push-through slide switch UL-approved; 6 ft. 3 conductor lead cord UL-approved. One wood cutting jig saw blade and wrench. 115V. AC/DC. Shpg. wt., 5 lbs. **Net 13.88**

MO-439 Pkg. of 5 wood and metal cutting blades **Net .59**

34-PC. 1/4" POWER DRILL KIT




Basic Kit for Home or Shop Drills, Sands, Buffs, Saws **14.95**

A value-packed electric drill kit with accessories for drilling, sanding, buffing, sawing, etc. The 1/4", UL approved, 3-wire drill features 2.9 amp. motor, mirror finish, and multiple thrust ball bearings. No load speed, 2000 rpm; full load, 1200 rpm. 34-piece set also includes: 9 drill bits; 1 drill stand; 10 sanding discs; lamb's wool bonnet; 6-pc. fittings; rubber base plate; buffing wheel; steel case; adaptor for 3-wire cord; 7-pc. countersink and drill saw set. Shpg. wt., 8 1/2 lbs. **Net 14.95**

WEN 'SOUPED UP' SABRE SAW MODEL 909

- HEAVY DUTY—FULL 6 AMP.
- 1/2 H.P. MOTOR—1" STROKE
- LARGEST CUTTING CAPACITY
- 6" 90° CUT • 4" 45° CUT



NO MONEY DOWN
33.05

Bigger — more powerful — more versatile — faster cutting. Super long blade easily cuts through 6x6" lumber. Cuts 4x4" at a 45° angle! Power enough to cut steel plate up to 1/2" thick—iron pipe up to 2" in diameter. Comfortable—conventional saw grip with auxiliary knob for 2 hand control. Saw tilts 45°—sole plate always remains flat. Finger control trigger-switch. Constant air stream flows down from line of cut. 3400 1" strokes per min. Includes seven blades for cutting wood—steel—hardboard—sheet metal—pipe—leather—rubber—formica—etc. Equipped with rip guide and circle cutter guide. 8 ft. 3 cond cord and adapter. 110 watts. 6 amp., AC-DC. 8Lx7Wx7 1/2"H. Shpg. wt., 8 1/4 lbs. **Net 33.05**

MO-466 **Net 29.37**

RAM "88-3" 7" POWER SAW



- HEAVY DUTY, INDUSTRIAL
- 1 1/4 HP MOTOR
- 8 AMPS
- 4500 RPM
- CUTS 2 1/4" DEEP

27.95

Newly designed model features a powerful 1 1/4 horsepower motor with self-lubricating Moly Sulphite bearings. 7" blade diameter, 3/8" round arbor hole. Cuts to a depth of 2 1/4". Angle of cut can be adjusted from 0° to 45°, with depth of cut of 2 1/4" at 45°. No load motor speed 4500 R.P.M. This rugged but lightweight saw is designed for effortless one-handed operation. For 110-120 volts AC/DC. Lustrous mirror finish. Combination rip and cross-cut blade and rip-guide included. Slip clutch. UL approved, 3 conductor cord with 2 prong adaptor. Shpg. wt., 15 lbs. **Net 27.95**

SAW TABLE. Perfect complement to the "88-3" Saw. Allows cutting at any angle between 45° and 90°. Complete with miter gauge and rip fence. Shpg. wt., 12 lbs. **Net 11.65**

COMBINATION OFFER. Consists of the MO-359 saw and MO-360 saw table, at a further saving in price. **Net 36.90**

NEW LAFAYETTE VIBRO-ENGRAVER PROTECTS AGAINST THEFT AND PROPERTY LOSS

- Easy To Use As A Pencil • Writes On Glass, Gold, Silver, Chrome, Wood • Complete—Ready to Use With 2 Hardened Engraving Points and Gold Filler



A handy featherweight marking and engraving tool with a hundred and one applications. Permanent identification—because marks are actually engraved. Can't be erased, wiped off or rubbed out. Ideal for industrial and hobby use to engrave names on tools, name plates, silverware, decorative glass, identify jewelry or radio chassis, etc. In fact you can engrave just about anything with this remarkable tool. Features a pencil-thin plastic body completely enclosing the durable vibro-mechanism; interchangeable tips, speed adjust and a handy AC line cord. On/off switch. Complete with 2 points and gold filler. Shpg. wt., 8 oz. **Net 7.95**

89c UTILITY-SWIVEL MIRROR



- 14" Reach • 2 1/4" Diameter Mirror
- Comfortable-Grip Handle • Swivel-Head

A handy little aid for mechanics at home or in the shop. Large 2 1/4" diameter mirror on a swivel arm enables you to look into hard-to-see places—no need to "work in the dark". Brightly chrome-plated with easy-to-grip plastic handle. Overall 14" long. Shpg. wt., 8 ozs. **Net .89**

THOR SPEEDWAY 1/2" DRILL

- FULL 5.5 AMP POWER RATING
- TWO-POSITION REAR HANDLE
- HEAVY DUTY SEALED THRUST BALL BEARING ON SPINDLE




This high power 1/2" Drill in the low priced field is built to professional standards throughout. Features built-in safety switch with push button lock and removable top handle. The rear grip handle can be revolved to vertical or horizontal position. Specifications: 1/2" capacity in steel; 1" capacity in wood; 5.5 amp rating; 400 r.p.m. full load speed; 1 1/2" spindle offset. Universal series-wound AC-DC motor for 115 volts. Comes with 10 feet 3-wire, type SJ, UL approved lead cord; and 3-jaw geared chuck with key. Overall length with rear handle is 14 1/2". Shpg. wt., 14 lbs. **Net 23.95**

MO-862 **Net 23.95**

ARCO SCREW & NUT DRIVER ELECTRIC DRILL ATTACHMENT

- Complete 15 Piece Screw and Nut Driver



For rapid fastening of both screws (slotted and Phillips) and nuts (hex and square head). Has non-slip industrial type clutch for fast easy driving. Bit holder prevents screw head slippage. Includes flat bits and bit holders for #4-8 and #8-14 screws, #1-2 Phillips head bit, 6 hex socket wrenches (1/4", 3/8", 1/2", 5/8", 3/4", 1 1/4"), 2 sq. socket wrenches (1/4", 3/8") and socket wrench holder with ball lock. **Net 5.84**

MO-944 Shpg. wt., 1 1/2 lbs.

25-PC. DELUXE TOOL KIT



2.79

Hardened, tempered alloy steel tools for handy use in the house or workshop. Kit consists of 1 plastic screwdriver handle with aluminum chuck; 4 screwdriver blades (1/4x4 1/4", 3/8x4 3/8", 1/2x5", 5/8x5 1/2"); 8 open and box end wrenches (1 1/2", 1 3/4", 1 1/2", 1 3/4", 1 1/2", 1 3/4", 1 1/2", 1 3/4"); 2-way flat ratchet handle; 2-way flexible shaft extension; 2-way 1/4" extension bar; 8 steel sockets (3/16, 1/8, 1/4, 3/8, 1/2, 5/8, 3/4, 7/8, 1). All in a convenient nouch with handy pocket for each tool. **Net 2.79**

MO-888 Shpg. wt., 1 1/2 lbs.

LEATHER TOOL HOLSTER

Heavy, pliable, top grain leather. Stitched and riveted. 5 pockets and tape sling. Practical, rugged tool carrier. Overall size 8 1/2x10". Shpg. wt., 1 lb. **Net 1.59**

MO-860 **Net 1.59**

RAM BUFF-'N-SAND



Two Tools in One — A Combination Polisher Buffer & Sander

A rugged all-purpose polishing and sanding tool half the weight of similar units. Perfect for sanding or polishing furniture, cars, floors and walls. Engineered to operate at 500 rpm to avoid hi-speed heat and friction on working surfaces. Universal AC-DC motor employs thrust ball bearings for smooth rotary action. Supplied with heavy duty 3-conductor cord, 7 1/2" O.D. lamb's wool bonnet and 24 sanding discs. Overall length 13 1/2". Shpg. wt., 5 1/2 lbs. **Net 23.73**

MO-931 **Net 23.73**

ZORON ADJUSTABLE Z-SAW HOLE CUTTER




3.88

A quickly adjustable tool for cutting holes 1 1/8" to 2 1/4" in diameter in wood, plastic, aluminum, etc. For use with tools having 1/4" chucks. Only light pressure exerted, less than with a drill. To adjust desired diameter, and lock-nut tightened. Removable combination blades. **Net 3.88**

MO-949 Shpg. wt., 1 1/2 lbs.

NEW! IMPACT DRIVER



Ever have trouble loosening a tightly turned, rusty screw, or a screw with the groove deformed? With this device, a small hammer rap is all that is required to loosen any corroded or rusty fastener. The driver will loosen any corroded or rusty fastener. The driver will loosen any corroded or rusty fastener. The driver will loosen any corroded or rusty fastener. **Net 6.95**

MO-971 **Net 6.95**

DELUXE HOPPY-SPLIT IMAGE TRANSIT

- Low Cost. Precision Level and Incline Measure
- Prism-Like Optical System
- Plate Glass Mirrors
- External Sights



Amazingly accurate instrument that will indicate level and measure a minimum of 1/8" rise or fall at 25'. Makes present day bubble level and string type levels obsolete. It not only indicates level but shows exactly how much correction is needed. One man can perform any leveling or incline measuring job quickly, easily, and accurately. Makes any complicated measuring/leveling job simple. Use it for patio layout, bricklaying, flooring, surveying, terracing, fencing, plumbing, shelving, guttering, drainage, irrigation. Indispensable as a leveling and grading tool for model railway pike. Shpg. wt., 6 lbs. **Net 6.72**

MO-441 case—Shpg. wt., 1 1/2 lbs. **Net 3.20**

TEKNI-TOOL SWIVEL TURRET VISE



5.49

Precision, swivel, turret vise for the machinist—technician—hobbyist. May be clamped-on or bolted to bench top. Twin, smooth faced jaws open to a maximum of 2". One set 1 1/2" wide, the other set 2 3/4" wide. Small, stationary jaw is V-grooved for gripping round stock. Positive lock in both swivels. Shpg. wt., 5 lbs. **Net 5.49**

MO-848 **Net 5.49**

TRY TO BEAT THESE ANTENNA PRICES!

LAFAYETTE ANTENNAS and "U-INSTALL-IT" KITS!

MAXIMUM PERFORMANCE FRINGE ANTENNA

- 21 Active Elements
- Snap Open Design
- Fiberglass Insulators
- Compound Yagi Array

Range to 100 Miles

11.88

NEW!

GOLD ANODIZED

Field proven design for fringe reception. Gold anodized to combat corrosion. Compound yagi array to "sock-in" signals where other designs fail. "Tension-lok" hardware. Heavy wall tubing throughout. Less mast. AN-67WX Gold Anodized. Shpg. wt., 8 1/2 lbs. Net 11.88

ALL CHANNEL'S "RIVIERA"

WORLD'S MOST POWERFUL ULTRA-FRINGE VHF-UHF-FM ANTENNA
GUARANTEED 200 MILE VHF RECEPTION OR YOUR MONEY BACK

- Receives channel 2-83 from all directions without a rotor
- Broadband UHF-VHF and FM, motorless all direction reception
- All aluminum flip-out assembly



Field tests reception on VHF of up to 200 miles has made possible this unprecedented guarantee. Here is an antenna with one transmission line for all UHF, VHF and FM stations in all directions without the use of a rotor. The nine position selector switch connected at the set electronically rotates antenna beam instantly without physically moving the antenna. Gain on channels 2-6 comparable to 4-bay conicals; on channels 7-13 comparable to stacked 10-element single channel yagis; on 14-83 comparable to bow-tie reflector. 1 1/2" doweled aluminum elements are 60 inches long. Complete with switch, coupler, 45" stacking bars and 2 7/8" angle type mast insulators for Polymalene line listed below. AN-135WX Less Mast Shpg. wt., 10 lbs. Net 19.85

The Riviera is ideal for FM Stereo/Multiplex reception. Elements are a full wave length at FM frequencies.


"U-Install-It" Kit. Includes Riviera antenna, chimney mount, two five ft. masts, 100 ft. of Polymalene 4 conductor lead-in wire, 8 stand off insulators and complete instructions. AN-42WX Shpg. wt., 16 lbs. Net 29.95

THE RIVIERA MUST BE USED WITH THE LOW LOSS LEAD IN WIRE LISTED BELOW

Special 4 conductors, matched impedance transmission line. Low loss, mica-filled Polymalene copperweld conductors.

WR-8W 50 ft. length	Net 5.00
WR-9W 75 ft. length	Net 7.50
WR-18W 100 ft. length	Net 8.90

FULL 20 ELEMENT STACKED



- SNAP OPEN CONICAL
- ALL ALUMINUM
- NO LOOSE PARTS
- FASTEST INSTALLATIONS

5.25

singly each

4.95

each, in lots of 3

Best antenna deal yet for servicemen-dealer-and installation specialists. All the most wanted features. Quickest-easiest installation possible. No loose hardware. All elements snap open and lock in without tools. Most efficient conical design for all reception areas. Two complete bays with Q bars, less mast. AN-28WX—Singly, ea. Shpg. wt., 8 lbs. 5.25 Lots of 3, ea. 4.95

LAFAYETTE TV/FM 4-SET POWER BOOSTER



- Boosts Signal For Up To 4 TV Sets
- Ideal for Master "Home" Installation
- Equally Useful In Primary and Fringe Areas

- The MOST Gain for the LEAST money
- Electro-Matched to Lafayette TV-FM Antennas
- Updates and improves any TV/FM antenna installation

Provide a stronger TV or FM signal to up to 4 sets anywhere in the home. Low noise-high output amplifier boosts and distributes the signal over ordinary twin lead. Special isolation circuitry prevents interaction and interference between sets. Provides as much as 7 to 10 db gain on all channels 2 through 13 when used with one TV set. From 2.5 to 5 db when used with 2 sets. Will often supply more gain when used with an indoor antenna than elaborate, unboosted outdoor antenna supply. Requires no tuning. Installs with just a screwdriver. Uses ordinary twin lead to "antenna-matched" terminals. Mounts behind set—or in any convenient location. Measures 5 3/4 x 3 3/8 x 1 1/4". For 117 V. A.C. 60 cycles. TL-75 Shpg. wt., 2 lbs. Net 9.95

"U-INSTALL-IT" KITS



All the items for simple installation. You get an all angle roof mount—lightning arrester—75 feet of 300 ohm twin lead—screw eyes—mast standoffs and 5 ft., 1 1/4" O.D. steel mast.

AM-10W Shpg. wt., 7 lbs.	ea. 2.95
AM-11W with 2-5 ft. masts. Shpg. wt., 10 lbs.	ea. 3.55
AM-12W Same as AM-10W and chimney mount.	ea. 3.25
AM-13W Same as AM-11W with chimney mount.	ea. 3.75
AM-14W Same as AM-10W with aluminum wall bracket.	ea. 2.95
AM-15W Same as AM-11 with aluminum wall bracket.	ea. 3.55

FAMOUS BRAND COLOR 'TENNA

GOLD ANODIZED



- HIGH GAIN ON ALL VHF CHANNELS
- COMPLETELY FACTORY PREASSEMBLED
- ELECTRONIC LENS DESIGN
- HIGHLY DIRECTIONAL—YAGI PERFORMANCE

13.95


Lafayette is the FIRST to offer this nationally tried and proven antenna at more than 25% off the regular dealer price. This is the same fine antenna—with all its exclusive features—that sells for dollars more than our record-breaking price. Check these features: Electronic Focusing—High Gain—all VHF channel coverage—gold anodized quality construction—easiest installation—outstanding fringe area reception—compact design dynamically balanced. All-aluminum construction—automatic hardware. AN-51WX—Shpg. wt., 8 lbs. Net 13.95

Net ea. in lots of 3. 13.25

FAMOUS BRAND SUPER COLOR 'TENNA

18 ELEMENTS—UP TO 125 MILES

- ELECTRONIC LENS DESIGN
- HIGHLY DIRECTIONAL—YAGI ENGINEERED
- COMPLETELY PREASSEMBLED
- MORE GAIN ON ALL VHF CHANNELS



16.98

All the exclusive features that have made this antenna a national favorite for "problem area" reception. Electronic focussing—18 elements for more gain—quality construction—1" square crossarm—1" round driven elements—1" tubing boom brace—easy installation—automatic hardware—all aluminum construction. Dynamically balanced design—outstanding fringe area performance. AN-63WX Shpg. wt., 10 lbs. Net 16.98

NEW LAFAYETTE UNI-TENNA

- RANGE TO 75 MILES
- ONE ARRAY FOR FM & TV
- A MUST FOR MULTIPLEX



A high quality antenna designed for operation in semi-fringe areas. Excellent pattern and high gain provide top reception of color and black-white TV and is ideal for stereo FM multiplex. Uses combination TV and FM antenna on one boom with separate transmission lines. The 5 1/4 ft. boom has square cross sections for added strength and maintains parallel alignment of elements. 4 Element yagi is used for TV, 3 elements yagi for FM, 10 Elements operating on high band as patented calinear yagi. Shpg. wt., 6 lbs. Net 10.55

NEW LAFAYETTE UNI-TENNA

- ONE RIG FOR TV & FM
- METROPOLITAN AND SUBURBAN MODEL

Similar to AN-212 but with less elements and use of omnidirectional FM halo. Designed for local and suburban use. Provides full response operation for TV, FM and Multiplex. Shpg. wt., 3 1/2 lbs. Net 5.85

REMBRANDT

TV DIRECTION FINDER


- Receives Signals From All Directions—Without a Rotator!
- Supercharges Any TV Antenna—Boosts The Pick-Up Power!
- Filters Out Interference
- Rejuvenates TV Antennas
- Amplifies The TV Signal
- No Installation Problem

5.95



The latest television invention! Seeks out—and beams in—TV signals from any channel, in any direction, without a mechanical rotator. Electrically rotates the polar-receiving pattern of your existing antenna and phases the ground wave picked up by the electrical wiring system with the sky wave picked up by the antenna. Improves any existing antenna: indoor, outdoor, master or built-in. Boosts pick-up power of any antenna—old or new. Just a flick of the selector control tunes out ghosts—filters out interference—tunes in those "hard-to-get" problem channels. Automatically amplifies TV signal strength for "snow" free, brighter, clearer pictures. Works on every channel—in any location—with any antenna—for any TV set. No installation problem—simply attach to antenna terminals in back of TV set—and plug into 110V AC/DC socket. Complete satisfaction guaranteed or your money back. AN-140 Shpg. wt., 2 lbs. Net, ea. 5.95 In lots of 6 ea. 5.00

8 ELEMENT CONICAL



2.29

All aluminum 8 element conical. Full sized. Rugged insulator block. Designed for rapid assembly. Fan front of 6 full length elements. Real value. Shpg. wt., 4 lbs.


AN-11W Singly ea.	Net 2.60
Lots of 3 ea.	Net 2.40
"U Install It" Kit includes AN-11 and roof-mount kit	Net 4.95
AM-10 as shown below.	Shpg. wt., 11 lbs.
AM-33W "U Install It" Kit. With chimney mount kit.	AM-12 as below. Shpg. wt., 11 lbs. Net 5.50
AM-44W	Net 5.50

VEE BEAM

Popular primary area antenna. Rugged aluminum construction. Light weight easy to install. Sharply directional. Shpg. wt., 4 lbs.

AN-21W	Net 2.29
AM-20W 2 bays stacked	Net 4.59
"U Install It" Kit. Includes AN-21W and roof mount kit	AM-10, as below. Shpg. wt., 11 lbs. Net 4.70
AM-45W	Net 4.70
"U Install It" Kit. With chimney mount kit.	AM-12 as below. Shpg. wt., 11 lbs. Net 5.29
AM-46W	Net 5.29

NEW "HI-5 FM YAGI"




- DESIGNED EXPRESSLY FOR FM

5.95

High gain antenna designed for the audiophile who seeks perfection in FM reception. Extra elements on this antenna serve to pull in stations where others fail. Trouble free operation even under severe weather conditions. The fully automatic snap-lock brackets insure easy, rapid and secure installation. AN-49WX Shpg. wt., 3 lbs. Net ea. 5.95

"MULTIPLEX 10" EXTENDED RANGE FM ANTENNA



9.88

GOLD ANODIZED

Ideally suited to Multiplex FM reception. Stereo (Multiplex) FM signals, for the average tuner, have a range of approximately half that of ordinary (monaural) FM signals. This 10 element, double driven, yagi array has the necessary added gain, sensitivity and directivity to compensate for the lack of signal strength. Assures full-fidelity reception and highest signal/noise ratio. All aluminum, gold anodized construction. Fibreglass insulators. Torsion lock hardware, sure-lock mast clamp. Broad banded to cover the entire 88 to 108 mc band. Shpg. wt., 7 lbs. Net 9.88

NEW! FM ANTENNA KIT ALL DIRECTIONAL



- GOLD ANODIZED
- FULL SIZED
- READY TO INSTALL
- FULLY ASSEMBLED

2.85 ANTENNA ONLY 3.98 COMPLETE KIT

Provides excellent gain for areas up to 35 miles from the station. Use on existing masts—new installation—or as an attic installation. Gold anodized aluminum for years of trouble free operation. Capable of receiving FM signals from practically all directions with equal efficiency. Complete with 50 ft. of 300 ohm twin lead, mast standoff, screw eye standoffs, mast mount. AK-53 Shpg. wt., 5 lbs. Net 3.98

FM ANTENNA ONLY. Shpg. wt., 3 lbs. Net 2.85

AN-66

NEW LAFAYETTE ULTRA-LITE ALL DIRECTIONAL FM ANTENNA



- Perfect for Indoor Concealed Installations
- Solid Rod Elements.

Here is the FM antenna you have been waiting for. Designed for either outdoor mast or indoor closet/attic installation. Easy to install—no holes to drill. Provides excellent gain for areas up to 35 miles from station. Perfect for multiplex reception. Brings in all stations clearly. Gold anodized finish for weather and corrosion protection. Strong, yet lightweight design. Shpg. wt., 1 lb. Net 2.10

FM Antenna Kit Same as above, but with kit containing 50 ft., 300 ohm line, 3-31 1/2" Stand-offs; 1-7 1/2" stand-off and 1 mast wrap around stand-off. Shpg. wt., 3 lbs. Net 3.23

AN-214

WIZARD 300 MASTER COUPLER

IDEAL FOR UNLIMITED SET COUPLING



Provides for the coupling of any number of TV (color or black and white) and FM sets to one antenna line. The first set is connected directly to the line, and each additional set is connected through a separate WIZARD 300, without the need for an amplifier or booster. Shpg. wt., 3 oz. Net 1.15

In lots of 3 Net ea. 1.03

NEW! REMBRANDT RADAR COIL - X9

- Guaranteed 35 Mile VHF Reception or Your Money Back

6.95



A powerful indoor antenna utilizing 46" long arms to provide efficient reception to 35 miles. 12-position switch helps eliminate ghosts and snow. A real beauty to grace any decor—Brass plated coil and 4 section telescoping arms. Includes 6-foot transmission line. Available in Mahogany, Walnut and Ivory. Shpg. wt., 3 lbs. AN-141 Net 6.95

SPECIAL UHF ANTENNA 4.79

- Highest Gain on 70 UHF Channels
- Completely Preassembled
- Excellent Directivity
- Flat Response Across Each Channel

Four bay, UHF bowtie antenna. Exceptionally high (12db) gain—relatively flat across the entire spectrum. Fully factory assembled. Quickest and easiest to install. High efficiency screen grid reflector boosts front to back ratio. Unique "cross-over" phasing bars—open V elements. Rugged—rigid—corrosion resistant construction. Shpg. wt., 5 lbs. Net 4.79

AN-200WX Net 4.79

UHF "TRANSLATOR" 4-BAY ANTENNA

Four bay bow-tie and screen reflector—tuned to the UHF translator frequencies. Average 16db gain on channels 70-83. Completely preassembled. Net 4.79

AN-201WX Shpg. wt., 5 lbs. Net 4.79

AMPHENOL

Designed for True video fidelity—featuring "slide rule" tuning with inductive reactance network for fine picture adjustment and transformer coupling for strict impedance matching. Elements fold from sight when not in use. Shpg. wt., 2 lbs. Net 2.59

2.59

Was 14.95



TV ACCESSORY

FOR
PORTABLE
or TABLE
MODEL

FOR
CONSOLE

ALLIANCE ANTENNA ROTATORS

Rotator redesigned and restyled to provide faster, smoother, better efficiency. Rotation speed is 1 R.P.M. Magnetic brake affords instantaneous stop. There is full 360° rotation. Factory lubricated for life. Contacts are self wiping. A reinforced zinc die cast housing affords all weather protection.

Model U-98 (1 & 2)—Fully automatic, just set control knob and antenna rotates to desired position and stops automatically. Indicator shows antenna position. Size: Rotator 7 1/4 x 5 1/4 x 8". Control Case 7 x 4 1/2 x 4". 110V. 60 cps AC at 65 watts. Shpg. wt., 12 lbs. Net 25.77

TL-71W
T-12 (1 & 3)—Manually operated with direction indicator. Needle indicates position of antenna on control panel. Has clockwise and counterclockwise revolution. Highly styled decorator case. Size: Rotator 7 1/4 x 5 1/4 x 8". Control Case 6 1/2 x 2 1/2 x 4 1/2". Operates on 110V 60 cps at 30 watts. Shpg. wt. 12 lbs. Net 22.15


Model K-22 (1 & 4)—Economy model—Provides positive instant finger tip control of rotation. Push on one end of bar and antenna turns clockwise. Push down on other end and antenna turns counterclockwise. Center disc automatic signal light indicates when limit of travel has been reached. Size: Rotator 7 1/4 x 5 1/4 x 8". Case 5 x 5 x 4". Shpg. wt., 12 lbs. Net 18.00

TL-73W
TBB THRUST BEARING BRACKET increases stress capacity of Tenna-Rotors up to 300 lbs. Withstands winds up to 90 M.P.H. Prevents buckling and bending. Shpg. wt., 3 lbs. Net 2.91

TI-74
WR-24—4 conductor flat cable for above per ft. .03



NEW! MODEL AB-4 MAST MOUNTED TRANSISTORIZED TV/FM BOOSTER



- For up to 4 TV or FM Sets
- Transistorized Circuit
- Uses Inexpensive Flashlight Batteries

A complete, compact amplifier—distribution system for up to 4 TV or FM sets. Reliable transistor circuit provides low noise and high gain. Stripless 300-ohm terminals on booster, and remote power supply for fast, positive installation. Requires four 1.5 volts flashlight batteries for power. Noise Figure: 4 db avg. High TV gain from 2-17 db and FM 12 db avg. depending on number of sets connected. Shpg. wt., 1 1/2 lbs. Size: AB-4 2 1/4 x 3 1/4 x 1 1/4". RP-3 (power supply) 3W x 7/4 x 1 1/4".

TL-185
BA-157 1.5 volt Battery (4 required) Net 18.62
Shpg. wt., 15 oz. Net .13

TRIO NO STRIP CONNECTOR

SAFEST—MOST POSITIVE—

LEAD IN CONNECTOR

No stripping—no exposed wire—no soldering—no broken leads at the set. Your TV set unplugs with ease—in electrical storms—for moving and cleaning—to add accessories. Safe, positive installation. Stronger than the lead in wire. Fast—easy—just insert the lead in—tighten a single knob.

TS-338 Shpg. wt., 2 oz. Net .50

UHF-VHF LIGHTNING ARRESTER

Special saw-tooth washers grip transmission line securely without stripping or cutting wire. Designed for flat, tubular, oval or open types. Constructed of low-loss material, resulting in less line loading on UHF. With mounting screw and steel strap. U/L approved. Shpg. wt., 10 oz. TS-11—Lots of 10 Each .29

Singly .35

UNIVERSAL TWIN-LEAD CONNECTORS

The plug with 1,000 uses. Fits all transmission line sockets as well as 1/2" crystal holder and octal tube sockets. Solderless.

TS-329 Shpg. wt., 2 oz. Net ea. .10
Net. ea. in lots of 5 .10

Solderless socket for above. Shpg. wt., 2 oz. Net ea. .10
TS-330 Net. ea. in lots of 5 .10

UNIVERSAL TV-FM PLUG & SOCKET

Compact—low loss—300 ohm plug and socket combination. For all TV & FM lead in applications. Surface mounting socket—low loss polystyrene plug. Constant impedance design. Solderless screw terminals. Includes hardware and instructions.

TS-328 Plug & Socket. Shpg. wt., 2 ozs. Net .35

WUERTH TUBE SAVER

LENGTHENS TUBE LIFE — PROTECTS T.V. — HI-FI — P.A. Any Electronic Equipment Up to 450 Watts!

Prolongs life of all electronic tubes including cathode-ray tubes! Protects components and tubes from destructive initial surge currents by "Thermal Cushion Action." Completely automatic. Just plug the "Tube Saver" into the wall, and appliances into it. RATED: 300 watts, 110-120V AC/DC. Measures only 2 1/2 x 1 1/4". TS-315 (Type 150) Shpg. wt., 8 oz. Net 2.91

Same as above except handles up to 450 watts. Suitable for color television. Net 3.50

BLONDER- TONGUE UHF CONVERTER



The only converter with 3 section tuner for "Class A" signals areas with these exclusive features. Tuned input tracks with oscillator, rejects spurious signals, suppresses oscillator radiation. Precise impedance match gives maximum signal conversion—no line ghosts—no picture smear. Drift-free performance is achieved by use of a thermally compensated oscillator circuit. One knob tuner. No VHF channel switching; output on channel 4, 5, or 6. Complete with tubes and instructions. Shpg. wt., 4 lbs. Net 16.41

TL-100

B-T ULTRAVERTER DELUXE UHF-TV CONVERTER



Adds all UHF channels (primary, satellite, and translator) to standard TV sets. Insures finest pix even in weak areas. Features dual-speed channel selection with direct and fine tuning controls; stable, shielded oscillator. Max. signal transfer to channels 5 or 6 of TV; Precise 300 ohm match and triode amplification; Improved tuner design meets new FCC standards; UL approved; Tubes channels 14-83 (470-890 mc); Tubes: 6AF4A and 6ERS; Power: 117 volts at 60 cps AC, 20 w. Size 6 1/4 x 5 1/4 x 4 1/4". Shpg. wt., 4 lbs. Net 27.44

TL-101

TRI-SET COUPLER 2.29



Highly efficient 3 set coupler. For coupling 2 or 3 TV or FM sets to one antenna of any type. No interaction—less than 6 db insertion loss. 40 to 50 db rejection ratio. Shpg. wt., 1 lb. Net 2.29

TS-322

TWO SET COUPLER .39



Uses one antenna for two sets. Compact electronic set coupler assures performance of two TV sets on one installation. Easy to connect. Nothing to go wrong. Shpg. wt., 1 lb. Net .39

TS-326 In lots of 3, Each .39

LO-PASS LINE FILTER 2.49



Exceptionally efficient line noise eliminator. Utilizing dual ferrite core coils, heavily wound. Eliminates line noises caused by motors, industrial RF, neons, appliances, etc. Particularly useful on TV and FM sets, radios, tuners, record players. Automatic attenuation of unwanted disturbances. Shpg. wt., 1 1/4 lbs. Net 2.49

TS-227 Line Filter

TV-FM HI-PASS FILTER



- Eliminates Interference in FM-TV antenna circuits

Hi-pass filter passes all frequencies above 40 mc. Rejects all frequencies below 40 mc. Automatically eliminates electrical disturbances in the antenna circuit. Clears disturbances caused by neon, X-Ray, ignition, appliances, diathermy, short wave, etc. Shpg. wt., 1 lb. Net 2.39

TS-331

Blonder Tongue "IT-3" TRANSISTORIZED 4-Set TV/FM Booster



- Antenna Matched Input
- Highest Gain—Lowest Noise
- Simple "Stripless" Installation

19.40

The highest gain of any home TV booster. Boosts antenna signal up to five times. More power for up to 4 TV or FM sets. The perfect basic unit for a home master TV-FM system. Designed as a rugged, long life unit. Requires almost no maintenance. Draws so little current it need never be turned off—no tubes to replace. Engineered to provide an excellent impedance match and maintain necessary isolation between sets. Can also be used to boost amplification from most mounted boosters or in master systems. Simple "stripless" installation—solid electrical contact with the turn of a screw. Size 6 1/4 x 3 3/4 x 1 1/2". For 117 volts 60 cy. A.C., .01 amp. Shpg. wt., 1 lb. Net 19.40

TL-99

TV TUBE 'BRITENER' .69 EACH in lots of 6



Absolutely no tools or soldering needed for installing this handy inexpensive tube rejuvenator. You simply attach two plugs as directed on the instructions. For magnetic tubes and PARALLEL CIRCUITS only. Renews brightness contrast. Wt., 8 oz. Ea. Net 12. In lots of 6, each .69

MS-12 In lots of 6, each .69

UNIVERSAL 110° CRT REJUVENATOR 2.20



A new Universal picture tube brightener designed for application on 110° picture tubes. A single heavy-duty unit which performs four ways. A simple adjustment adapts it for either series or parallel wired filaments and it can be used on electromagnetic or electrostatic focus tubes. Shpg. wt., 1 lb. Net 2.20

TS-283 For Sylvania Type 110° Tubes Net 2.20
TS-284 For RCA Type 110° Tubes Net 2.20

PEAK ROOF MOUNT



A heavy gauge steel peak roof mount. Heavily plated to resist corrosion. Will accommodate mast, up to 2" in diameter. Fully adjustable. Can be easily rotated. Complete with all necessary hardware. Shpg. wt., 5 lbs. Net 1.10

TS-41

99¢ ECONOMY MOUNT



Can be erected in minutes; without special tools or drilling. Adjustable, two-section design permits unlimited spacing between brackets for maximum support of masts 1/2" to 1 1/2" O.D. Complete with two 12-ft. lengths of 3/4" galvanized steel bands and hardware. Shpg. wt., 3 lbs. Net .99

TS-82 Net Each .99

UNIVERSAL TV TUBE "BRITENER" 1.29 SINGLY EACH In lots of 6 1.39



Restores brightness to dim TV picture tubes. Operates on all types—magnetic or electrostatic—and in all circuits—parallel or series. Shpg. wt., 10 oz. Ea. Net 1.29

TS-170 In lots of 6 each 1.39

Singly each 1.39

TS-282 Shpg. wt., 1/2 lb. Net .99

TS-282 Shpg. wt., 1/2 lb. Net .99

TV PICTURE TUBE SHORT ELIMINATOR .99



Eliminates expensive picture tube repairs. No elaborate equipment needed. Repairs grid and cathode shorts in two minutes—without pulling the chassis! Simple "plug-in, switch-on" operation. Works with any TV picture tube. Net .99

TS-282 Shpg. wt., 1/2 lb. Net .99

HEAVY DUTY 300-OHM LINE

Extra high quality. Heavier gauge wire and thicker insulation. Shpg. wt., 2 1/2 lbs. per 100 ft. Net .025

WR-26 per ft. Net 1.58

WR-152 per 100

BROWN 300 OHM TWIN LEAD

High quality, low-loss lead-in for all TV and FM installations. Polyethylene dielectric—standard copper leads. Shpg. wt., 2 lbs. per 100 ft. Net 1.29

WR-25 100 ft. Net 4.80

WR-146 500 ft. Net 8.95

WR-147 1,000 ft. Net 8.95

U.H.F. TUBULAR AIR-SPACED TWIN LEAD

300 ohm airspaced tubular lead with copperweld conductors. Shpg. wt., 3 lbs. per 100 ft. Net 2.50

WR-46 per 100 ft. Net 2.50

TELESCOPING TV MASTS

Heavy-duty telescoping masts. Hot-dip zinc galvanizing inside and outside. Designed for easy installation and assembly. Husky thumb bolts lock sections automatically. Precision fitting. 18 gauge .003" wall. Supplied complete with all guy rings, clamps and necessary hardware. Total 5 10-ft. sections for height up to 50 ft.; O.D.: #1 (1 1/4"), #2 (1 1/2"), 50-FT. MAST—Consists of all 5 sections #3 (1 3/4"), #4 (2"), #5 (2 1/4"). Shipping express only. Listed above: Nos. 1, 2, 3, 4 and 5. Height 50 feet. Shpg. wt., 39 lbs. Net 13.73

TL-63WX

40-FT. MAST. Consists of 4 sections; Nos. 1, 2, 3 and 4. Height 40 feet. Shpg. wt., 28 lbs. Net 10.05

TL-62WX

30-FT. MAST. Consists of 3 sections. Nos. 1, 2 and 3. Height 30 feet. Shpg. wt., 21 lbs. Net 7.28

TL-61WX

20-FT. MAST. Consists of 2 sections. Nos. 1 and 2. Height 20 feet. Shpg. wt., 14 lbs. Net 4.58

TL-60WX

TV ANTENNA MASTS

STEEL MASTS. New corrosion-resistant 5 ft. steel mast made to fit all antennas. One end is tapered. "Jam Fit" construction with locking key. 1 1/2" O.D. TL-12W 5 ft. Wt., 2 1/2 lbs. .69

TL-13WX 10 ft. Wt., 4 1/2 lbs. 1.29

TL-14WX 10 ft., 16 gauge. Wt., 8 lbs. 1.69

ALUMINUM MASTS. 19 gauge-heavy wall-high tensile strength. Rust and corrosion proof. Swaged for stacking. TL-66W 5 ft. Wt., 1 1/2 lbs. .89

TL-17WX 10 ft. Wt., 2 1/2 lbs. 1.69

10 Ft. Mast shipped via express only.

NEW "BI-MOUNT" ANTENNA MOUNTING KIT

"BI-MOUNT" kit used to mount and support any 5 ft. 1 1/4" mast. Includes collar, support legs, base mount and screws. Shpg. wt., 1 1/2 lbs. Net 1.82


TL-136

SUPER "BI-MOUNT" kit used to mount and support any 10 ft. 1 1/4" mast. Includes 1" dia. support legs, collar adjustable mast mount and all screws. Shpg. wt., 2 1/2 lbs. Net 3.44

TL-137

LAFAYETTE ENGINEERING & DRAFTING SUPPLIES FOR SCIENCE AND TECHNOLOGY

Minivac 601 DIGITAL COMPUTER




Not A Toy — Performs Functions of Full Size Computer — Solves Scientific and Business Problems

The Minivac 601 can be used by anyone with an inquiring mind. Designed to introduce teenagers and adults to the fascinating world of machines that "think". The 601 demonstrates how computers operate, what they can and cannot do by simulating computer applications in business, science and military. It can learn, remember, calculate, and make decisions. Indispensable to teachers, businessmen who need to keep up with modern technology, a first hand opportunity to explore space age techniques and experimentation. A set of six comprehensive manuals are provided with each Minivac 601. These provide step-by-step experiments demonstrating how computers do arithmetic, use logic, provide automatic control, and language translation. It even plays games as an opponent, partner or referee. The Minivac is ready to

- Teaches Basic Concepts of Computer Operation and Technology
- A Product of 2 Years of Research

use the moment you unpack it. Operates on a low 12 volt system—it is as safe to use as an electric train. Minivac consists of a 24" console with 12 indicator lights, 1 circuit breaker; 6 DPDT memory storage relays; 6 secondary memory storage switches; 6 data input push buttons; 16 position switch (motor driven); game matrix; 194 dual terminals and 100 program wires. The console measures 24x13x5½" H. Shpg. wt., 17 lbs. Power input 110 V AC. HE-647W Net 85.00



85⁰⁰

NO MONEY DOWN

NEW! LAFAYETTE VECTORLOG

SLIDE RULE




The Slide Rule for Communications Engineers and Physicists

16.88

- LAMINATED BAMBOO CONSTRUCTION • P, P', AND Q SCALES — FOR DIRECT VECTOR ADDITION • HYPERBOLIC SINE AND TANGENT SCALES • TWO SINE SCALES—ONE MARKED IN DEGREES, ONE MARKED IN RADIAN • 5 LOG LOG SCALES PLUS A VOLTAGE DB SCALE • COMPLETE WITH BELT CARRYING LOOP AND LEATHER CASE

The Lafayette VECTORLOG Slide Rule provides a new concept in scientific calculation, incorporating scales and arrangement designed for quick-easy-manipulation. Twenty-seven (27) scales incorporate the many problems encountered in Electrical Engineering and Physics. The unique P, P', and Q scales allow direct right angle vector addition. No longer are several settings required to obtain right angle vector sums—these scales work in the same manner as the C and D for multiplication. The two Hyperbolic Sine and one Hyperbolic Tangent Scale, the voltage db scale, and the five Log Log scales, provide maximum coverage of these dynamic fields. VECTORLOG is the result of extensive tests for ease of manipulation. Several of these features are: C and D scales on both the front and back of the rule; Sine scales in both degrees and radians, removing the necessity of bothersome conversion of units; A problem-tested location of scales; and adjustment screws to allow variable tension on the slide. Scales include: (FRONT) Tr-1, TR-2, P', P, Q, ST, S-F, S-O, C, D, LLO1, LLO2, LLO3, LL1; (REAR) Sh-1, Sh-2, DF, A, B, CI, CF, Th, C, D, LL3, LL2, db. With instruction book, leather carrying case, and belt carrying loop. F-686 Shpg. wt., 1½ lbs. Net 16.88

LAFAYETTE'S ENGINE DIVIDED IMPORTED SLIDE RULES



10' LOG LOG DUPLI TRIG SLIDE RULE

Laminated Bamboo Warp-free Construction • Complete With Leather Carrying Case

Specially selected, laminated, non-hygroscopic bamboo. Scales machine engraved on white plastic in permanently accurate calibrations. Adjusting screws permit varying tension on slide. 21 scales including C, D and CI on both sides. LLO and LLO0 scales refer to B scale. All other scales coordinate and refer to D scale. Scales are L, LL1, DF, CF, CIF, CI, C, D, LL3, LL2, LLO, LLO0, A, B, K, CI, C, D, S, ST, and T. Scale characteristics permit multiplication, division, proportion, inverse proportion, reciprocals, cotangents, squares, square roots, cubes, cube roots, logarithms, tangents, sines, etc. F-341 Shpg. wt., 1½ lbs. Net 10.45




DELUXE LOG LOG DUPLI DECIMAL TRIGONOMETRIC SLIDE RULE

- 25 Scales with 8 Log Log Scales • Extended Range Avoids "Going Off Scale" • Extra P Scale Simplifies Computations • Two Color Scales

10" log log duplex trig slide rule contains 25 scales including 8 Log Log Scales. Troublesome end-for-end resetting is eliminated by extensions of C and D scales. Twin set of Log Log scales run from 1.001 to 100,000 and .999 to .00001, enlarging the scale by one scale length each compared with ordinary log log slide rules. Extra features include P scale which enables direct "readout" of cosine value. Scales include LLO1, LLO2, LLO3, DF, CF, CIF, CI, C, D, LL3, LL2, LL1, LLO0, L, K, A, B, S, ST, T, C, D, DI, P, and LLO. With instruction book, saddle leather case. Overall length is 14". F-428 Shpg. wt., 1½ lbs. Net 15.95

NEW! DECI-LOG™ DELUXE 5" LOG LOG DUPLI DECIMAL TRIGONOMETRIC SLIDE RULE



- Pocket Version of Lafayette's Most Popular Slide Rule • P Scale (Pythagorean) permits direct "readout" of Cosine Values
- Includes Leather Case with Pocket Clip
- 24 Scales including 8 Log Log Scales

ONLY 6.88


Designed to answer the demand for a pocket version of our 10" Log Dupli Decimal Trigonometric slide rule (F-428). Contains all the scales of the 10" rule except the "ST" scale. Two color scales—positioned for ease in use and rapid calculations. "C" and "D" scales on both sides of the rule. "P" scale for direct, cursor line reading of cosines of angles. Scales included, front face: LL1, LL2, LL3, DF, CF, CIF, CI, C, D, LL3, LL2, LL1. Back face: LLO, L, K, A, B, S, T, C, D, DI, P, LLO. Engine divided rule of laminated, non-hygroscopic bamboo. Complete with instruction book and leather case with pocket clip. Shpg. wt., 8 oz. F-681 Net 6.88



5" POCKET SLIDE RULE

Pocket Slide Rule: Convenient pocket sized slide rule of specially selected and treated bamboo. Will not warp, shrink or lengthen under varying atmospheric conditions. C, B, CI, C, D and K scales engraved on white plastic surface. Reverse side of slide has standard S, L and T scales. The upper beveled edge of the rule is graduated in m/m to 13 cm. Other edge is divided into 5 inches by 32nds. Only 5¼" long over all. Carried easily in any pocket. Shpg. wt., 8 oz. F-340 Net 2.89

8" PROFESSIONAL DIVIDER




IMPORTED FROM GERMANY


4.96

Extremely accurate finely made proportional dividers. Basic equipment for draftsmen—architects—engineers—students. Replaceable steel points—in hard, leather covered, felt lined case. Used for proportional reductions and enlargements, copying drawings in enlarged or reduced scale, dividing lines or circles into equal parts, quick solving of difficult measuring problems, finding distances on maps without scales, etc. Flat form—replaceable steel points. Pressure setting. Graduated for lines from ¼" to 10"—Circles from 6" to 20". Excellent, accurate utility model. Shpg. wt., 8 oz. F-167 net 4.96

ELECTRONIC DRAFTING TEMPLATE



Exceptionally accurate! Made to I.C.C. standards for electronic standards. All elements of electronic and CR tubes are provided for—plus tube bases for 7, 8, and 9 prong tubes. Includes latest symbols—transistors, diodes—rectifiers—plugs, etc. Covers all electronic symbols. Size 7x5". Thickness .030. Shpg. wt., 4 ozs. F-131 Net 2.10




TECHNICAL DRAFTING SET

- Center Wheel Adjustment
- Professional Quality

6.59

A fine set of imported nickel plated brass instruments priced far below the usual price for this quality. Contains 6¼" self-centering compass, one leg knuckle joint with divider, pencil, pen parts and lengthening bar; 6¼" self-centering divider; spring bow divider 4¼", center wheel adjustment with interchangeable needle points; spring bow pencil and spring bow pen, both 4¼" with center wheel adjustment and interchangeable needle point; two 5¼" ruling pens; extra handle for pen and pencil parts; adjustment tool; lead case and leads; and spare parts kit, all in velvet lined snap closing case. Shpg. wt., 1½ lbs. F-85 Net 6.59



CIRCULAR SLIDE RULE

- Continuous Scales
- Sturdy Construction
- Equivalent to a 10" Rule

2.45

A versatile calculating instrument specially constructed with special chemical resistant, ¼" thick, plastic. It will not shrink or expand under varying climatic conditions. 12 scales to solve problems involving multiplication, division, proportions, squares, cubes, and all trigonometric functions. Special scales allow direct conversions of angles from radians to degrees. Ideal for quick calculations. With leatherette case. F-382 Shpg. wt., 4 oz. Net 2.45

PLASTIC T SQUARE



WITH ADJUSTABLE PROTRACTOR HEAD **2.10**

Adjustable protractor head clearly marked to 180° easily set and fastened. Transparent arm gives clear full view of subject matter. All plastic—light weight. Adapted for ink ruling. Head fits snugly against board. Shpg. Wt., ½ lb. F-98—18" long Net 2.10 F-100—24" long Net 2.35

UTILITY DRAFTING SET

- Exceptional Value

Made in Germany of hard rolled, nickel plated brass. All instruments are nested in a fitted, velvet lined case. Contains three side wheel 3¼" bow instruments—one a divider, one a pencil and one a pen. All have reversible needle point. 5¼" compass with pen and pencil parts—and lengthening bar. 5¼" divider with straightening device. 5" ruling pen. Extra handle for use with pen and pencil parts. Capsule with extra leads. Perfect for schools, labs, industrial or wherever precision drawing sets are used. Shpg. wt., 1 lb. F-13 Net 3.10

Net 3.10



PROFESSIONAL GIANT BOW


- 6" Size with Center Wheel Adjustment
- Finely Balanced—Professional Type

Professional quality utility set in a fitted, velvet lined case. Made in Western Germany of nickel plated, hard-rolled brass. 6" giant bow has preferred center wheel adjustment. Makes circles from ¼" to over 10" in diameter. Set includes 6" giant bow, interchangeable pen and pencil parts, extra needle for using bow as divider, handle for use with pen and pencil parts, lead, lead box and repair parts. Shpg. wt., 1 lb. F-44 Net 3.50

SUPER DRAWING KIT

7.95

- COMPARE OUR PRICE!



Contains all the necessary equipment for drafting, mechanical drawing, designing. Sturdy accurate components. Includes 20x24½" drawing board 24" T square, 10" 30°/60° triangle, 8" 45° triangle, french curve, 12" triangular rule, 6" 180° protractor, 4 pencils, pencil pointer, erasing shield, thumb tacks, and art gum eraser. If purchased separately these components would cost many times our low price. An unbeatable value. Shpg. wt., 10 lbs. F-180 Net 7.95

SPECIAL COMBINATION OFFER

Consists of F-65 Technical Drafting Set and F-180 Super drawing outfit. F-181 Shpg. wt., 12 lbs. Net 13.06


NEW PORTABLE DRAWING KIT



ONLY 2.95

An easy to handle folding portfolio which can be conveniently carried or stored in a desk or briefcase. The kit includes a 12 inch T-square, a 180 degree protractor, a 6 inch French curve, a 4 inch 45°/90° and a 4 inch 30°/60°, a 50 sheet drawing pad and drawing pencil. Plastic portfolio is 9x13½x½". All tools are made of crystal clear plastic, which are physically stable and individually housed in separate pockets. Shpg. wt., 3 lbs. F-806 Net 2.95

NEW "draftette" SKETCH KIT




ONLY 7.80

A completely portable drafting drawing machine permanently mounted in a Vinyl binder (self-locking). A weather protected unit, it can be used for sketching, designing, drawing, and drafting. Great for traveling. Contains a precision portable drafting instrument with a 3x5" scale -180 degree protractor, pad of 50 sheets, drawing-tracing paper 8½x11", all in one compact binder. Does not require tape or tacks to hold paper in place for use. Only 9x13x11". F-805 Shpg. wt., 2 lbs. Net 7.80

LAFAYETTE

TELESCOPES are WORTH LOOKING INTO!



269.50
NO MONEY DOWN

Arcturus

• 454x with Barlow Lens

3" EQUATORIAL REFRACTOR

• Ultra Precise Helicoid Focusing • 7 Coated Eyepieces Plus Barlow Lens • 76.2 mm Clear Aperture • Most Advanced Equatorial Mount • 25x, 42 mm Finder Scope

79-mm. hard coated, air-spaced Fraunhofer achromat of 910-mm focal length with 3" clear aperture, focal ratio of f/12 and resolving power of 1.6". Seven coated eyepieces provide magnifications of 227x, 152x, 101x, 73x, 35x, 18x and 25x through viewfinder. Helicoid focusing by means of a massive wheel and helical gear. Finder Scope, with rack and pinion focusing, features a 1.6 inch clear aperture objective of 500-mm focal length. Micro-motion controls with extended flexible shafts and compression locks in all axes. Accessories include three sunglasses, moon-glass, sun diagonal, two star diagonals, sun projection screen, erecting prism, heavy extensible field tripod, brace, accessory shelf, separate wooden cases for telescope and mount. Shpg. wt., 100 lbs. VIA EXPRESS ONLY. F-385WX

Net 269.50

Galactic

• 454x with Barlow Lens

RESEARCH QUALITY 3" EQUATORIAL REFRACTOR

• Viewfinder Scope 25x, 42-mm • 910 mm Focal Length • 76.2 mm Clear Aperture • Micromotion Controls for Declination and Right Ascension • Resolving Power 1.6 • Barlow Lens Included

189.00 No Money Down!

The objective lens is a 79-mm, hard coated, air spaced Fraunhofer achromat with a clear aperture of 76.2 mm (3"). Focal length 910 mm, focal ratio f/12, resolving power 1.6". Seven coated eyepieces provide magnifications of 227x, 152x, 101x, 73x, 45x, 35x plus 25x through the viewfinder. Barlow lens add ranges of 454x, 304x, 202x, 146x, 90x, 70x and 50x. Focusing by means of micro-precise rack and pinion drive. The viewfinder scope has a 42-mm (1.6 in. clear aperture) objective—500-mm focal length—rack and pinion focusing—and will accommodate various eyepieces. Finely calibrated hour and declination circles for rapid finding and setting. Body tube of white enameled aluminum. Accessories include three sunglasses, moon-glass, two star diagonals, sun diagonal, erecting prism, sun projecting screen, extensible field tripod, chain brace, accessory shelf, wooden cabinet. VIA EXPRESS ONLY. F-384WX Shpg. wt., 60 lbs. Net 189.00

Polaris

• 320x with Barlow Lens


2.4" EQUATORIAL REFRACTOR

• Eyepieces for 160x, 88x, 40x, Barlow Lens gives 320x, 176x, 80x • 800 mm. focal length • 62-mm objective • Micromotion adjustments on both axes • Coated optics throughout • Equatorial mount

79.50 No Money Down!

Objective: Fraunhofer-type achromat, hard coated, 62.5-mm., 800-mm. focal length. Collects about 75 times as much light as the naked eye. resolving power 2 seconds, faintest discernible star 10.7 magnitude. Eyepieces are hard-coated Huygenians, 160x (5-mm), 88x (9-mm), 40x (20-mm). Barlow Lens included give ranges of 320x, 176x and 80x. Finder scope is 6x, 30-mm. Tripod head with latitude adjustment. Clamp lever for declination and inclination. Accessories include sunglass, star diagonal, erecting prism, sun projection screen, field tripod, wooden case. Rack-and-pinion focusing. Heavy plating to prevent rusting.

F-342WX Shpg. wt., 30 lbs. Net 79.50
F-391 4-mm. orthoscopic eyepiece for 200x (400x with Barlow Lens) Net 8.95



(A) ZOOM SPOTTING SCOPE

• Any Power from 15X to 30X!
• Ideal for any "Spotting" Need!
• Pan-Head, elevator Tripod

True Zoom action—finger tip control—from 15 power to 30 power. Choose the right power for any "spotting" or viewing need. Brilliant image at any power. 50mm objective, hard coated for maximum light gathering power. Prismatic system greatly reduces length—only 15" overall. Precisely machined, all metal body. Lightweight scope alone weighs only 2 lbs. May be hand held or used with tripod supplied. Precision finger-tip focusing with oversized, milled ring. Aluminum and chrome-brass tripod adjustable from 12" to 18". Locking pan-head swivels and tilts to any angle. Optical train is fully hard coated. Shpg. wt., 5 lbs. F-685 Net 39.95

(B) 30x, 60mm SPOTTING SCOPE

• Coated Optics • Complete With Leather Case
Field of view is 85 feet at 1000 yds. Both front and rear optics are coated. High relative brilliance due to 60mm objective lens. Exceptionally small and light—weighs only 2 lbs. including metal tripod! The perfect companion for shooting—hunting—viewing—naturalists—and hobbyists. Equipped with 11 1/2" tripod and zippered leather carrying case. Shpg. wt., 3 lbs. F-149 Net 16.95

LAFAYETTE BINOCULARS

LOWEST PRICES • HIGHEST QUALITY



17.95

7X 35 CENTER FOCUS



Precise design — quality material — and expert workmanship. All lenses are hard coated — prisms clamped in lightweight alloy frame and body — sealed against dust and moisture — properly collimated and aligned. All are center focus with adjustable right eyepiece. Hard leather case and neckstraps included.

7X35 Popular, versatile, all purpose binoculars. For the sportsmen—hunter—bird watcher—vacationer. High luminosity. Compact design. Shpg. wt., 3 lbs. Net 17.95
F-183
7X35 Wide Angle. Top performance—highest quality. Almost twice the field of view of ordinary 7x35 binoculars. Spots and holds a moving target faster and easier. Oversize oculars and prisms. Shpg. wt., 3 1/2 lbs. Net 27.50
F-184
7X50 Navy style night glasses. Favored for marine use. The choice of professionals because of exceptionally high light gathering power. Superior image brightness. Shpg. wt., 3 1/2 lbs. Net 21.95
F-184
20X50 King of the long range. Hunters, mountain climbers, plane spotters, forest rangers—any long distance viewing and observation requirement. Shpg. wt., 4 1/2 lbs. Net 27.50
F-185
Add 10% Fed. Tax to the above prices.

TRU-ZOOM BINOCULARS



39.95

NO MONEY DOWN

• Not a "Vari-Power"—One Control Zooms both barrels!

• 7X to 12X—or any Power in Between

• Center Focus—right Eye Adjust—Plus Single Synchronous Zoom Control! • The Perfect Power For Any View!

Sensational Zoom action holds even fast-moving subjects in perfect view. Sight in any subject at 7 power—then Zoom up to 12 power (or any four in between) for closeup viewing. Full 40mm, objective lenses, hard coated achromats. Field of view is 290 feet at 1000 yds. at 12 power (5.5°). Prisms clamped in shock-resistant mounts. Lightweight alloy frame and body. Sealed against dust and moisture. Includes plush-lined, hard leather case and straps. Shpg. wt., 5 lbs. F-793 Net 39.95
*Add 10% Fed. Tax

CLINICAL AND ADVANCED ACADEMIC 1500X "MICRO-STANDARD" ADVANCED ACADEMIC MICROSCOPE



• 25X to 1500X IN 11 RANGES
• INTEGRAL MECHANICAL STATE • VARIABLE SUBSTAGE CONDENSER WITH IRIS DIAPHRAGM • FULL RANGE FINE ADJUSTMENT • STANDARD SOCIETY SIZE OPTICS • BOTH OBJECTIVES AND EYEPIECES

89.95
NO MONEY DOWN

OPTICAL SPECIFICATIONS: Three Huygenian eyepieces: 5X, 10X, 15X. Four achromatic objectives: 5X, 10X, 40X, 100X (oil immersion). BODY: Monocular tube 140mm long. STAGE: Square stage 95mm x 95mm. Integral mechanical stage. Adjustable in any direction. FOCUSING: Coarse focus with adjustable tension. Fine focus vernier adjustment. Spring loaded safety device prevents objective from driving through slide. SUBSTAGE: Focusing Condenser with variable iris diaphragm. 41 mm plano/concave mirror. Overall 12 1/2" high, 6 1/2" deep, 5" wide. Includes fitted cabinet with lock and key, specimen slide, blank slide, bottle of cedar oil. Shpg. wt., 11 1/2 lbs. F-602X Net 89.95

"MICRO'DAPTER"



19.75

• Micro-photography • Astro-photography!
• Inexpensive — accurate — easy to use • Use any camera/microscope or camera/telescope setup
• Photo-record your observations.

Permits the use of any camera—even movie cameras—with practically all microscopes and telescopes. No need to remove the camera lens. Cross hairs are superimposed on the image for centering. The image is automatically in focus for the camera when viewed in focus through the MICRO'DAPTER. Accessory sleeves permit the MICRO'DAPTER to be used with other than Society size microscopes. The MICRO'DAPTER may be used with any telescope by attaching to eyepieces of 29mm (1 1/2") maximum diameter. Shpg. wt., 1 1/2 lbs. F-506 Net 19.75

500X "MICRO-MECH" MICROSCOPE

• BUILT-IN MECHANICAL STAGE!
• 100X - 200X - 300X - 500X
• QUADRUPLE REVOLVING TURRET

5.95

For the student — hobbyist — or budding scientist. Featuring a built-in, micro-drive mechanical stage. Permits the micro-movement necessary to properly examine micro objects. Promotes learning through ease of operation. Four achromatic objective lenses giving magnifications of 100X, 200X, 300X and 500X. Complete with wooden carrying case and slides. Shpg. wt., 4 1/2 lbs. F-357 Net 5.95

"MICRO-MECH" LAB KIT: Consists of F-357 500X "Micro-Mech" microscope and F-454 Micro-Lab Kit, with accessories and cabinet plus latest edition of "Hunting with the Microscope." Shpg. wt., 12 lbs. F-622 Net 13.90

NEW! 50X STEREO-SCOPE

• STEREOSCOPE BINOCULAR MICROSCOPE
• WIDE FIELD—3 DIMENSION VIEW
• VERTICALLY ERECT IMAGE

14.95

Indispensable for the examination of surface features of gross objects. Excellent hobby aid for the coin and stamp collector. Prismatic, binocular head with inter-pupillary adjustment. Ground glass stage, 3 1/4 x 2 3/4". Heavy modified horseshoe base. Overall height 8". Complete with wooden carrying case. Shpg. wt., 5 lbs. F-762 Net 14.95

Earth-Science Combination. Includes 50X Stereo-Scope (F-762) and 96 selected specimens, named, tagged and classified. (Vol. I and Vol. II Mineral Teknikits.) Shpg. wt., 8 lbs. F-763 Net 17.76


50X-100X "MAGNI-SCOPE JR."

5.29

Direct viewing "projection" microscope affords viewing ease to small groups. Less tiring than viewing through a conventional microscope. The image is projected onto a self contained translucent glass screen. Finger tip control switches from 50X to 100X. Thumb wheel focus for sharp definition. Projects the full colors present in the slide or specimen. Illumination by means of a battery powered, pre-focused bulb. Requires 2 standard flashlight batteries (not included). Overall size 4 1/2 x 3 1/2". Hooded viewing screen, inclined to 55°, optimum viewing angle. Supplied with bulb and three prepared slides. Shpg. wt., 1 1/2 lbs. F-760 Net 5.29
BA-157 Batteries (2 required) Net ea. .13

LAFAYETTE REFLEX TYPE F/1.8 ZOOM MOVIE CAMERA

WITH **AUTOMATIC ELECTRIC EYE PHOTOMETER**



ONLY **69.95**

NO MONEY DOWN


- SINGLE LENS REFLEX SYSTEM LETS YOU SEE WHAT THE LENS SEES
- ULTRA FAST F/1.8 Lens—ZOOMS from wide angle to Telephoto
- Built-in Coupled Electric Eye Exposure Meter
- 4 Speeds—Including Slow Motion
- Single-Frame (animation) Exposure
- USES ANY FILM—ASA 10-40
- AUTOMATIC FOOTAGE COUNTER
- TRIGGER ACTION PISTOL GRIP

See exactly what the camera lens sees with this true single-lens reflex system. The bright viewfinder shows exactly what will appear on the film. No more parallel errors—no more focusing problems! Fast F/1.8 zoom lens is directly coupled to the electric eye photometer. Simply look through the viewfinder, line up the arrows and shoot! Needle sharp zoom pictures are yours from 10 mm. wide angle through 30 mm. telephoto. Trigger action, pistol grip handle

provides a firm, comfortable grip for smoother, steadier movies. Fast, simple drop-in spool loading. Adjusts for films of ASA 10-40 speed rating. Film footage counter returns to the starting position automatically when roll is finished. Four motor speeds for 12-16-24 and 32 per second plus single frame for animation. Quiet ratchet-wind motor with a 6 ft. run. Die-cast aluminum body. Trigger action pistol grip handle and leather wrist strap included.

F-822L Shpg. wt., 5 lbs. Net 69.95
Zoom Case: Holds camera with pistol grip attached. Room for accessories. Measures 10x8 1/2x3 3/8". F-784 Shpg. wt., 2 lbs. Net 5.79

MANSFIELD "ULTRA" 500 WATT BRILLIANCE 8 mm MOVIE PROJECTOR



- Fast, Easy Loading
- Forward, Still & Reverse
- Self-Contained Carrying Case

52.95

NO MONEY DOWN

The new "Ultra" 8 mm projector features several unusual conveniences to un-complicate movie showing. Has swing-out gate for fast threading. Forward, Still and Reverse positions. Brilliant, new DFA lamp gives uniformly bright picture. Cinepar .750" f/1.6 lens. Self contained carrying case. F-785WX Shpg. wt., 10 lbs. Net 52.95
F-786 Replacement Lamp (DFA) Net 2.70

"HOLIDAY" 500-WATT 8mm PROJECTOR

- High Intensity Blower Cooler!
- 400-ft. Reel Capacity
- Swing-Out Gate—Easy Loading
- Coated 3/4" f1.6 Lens!

37.95

NO MONEY DOWN



Show your movies sharp and clear! Swing-out gate for fast, easy loading. Scientific Marex film extends life of your film with less wear and tear. High intensity blower for cooling. Coated 3/4" f1.6 lens for wide-angle viewing. Separate switches for blower and lamp. Rapid rewind and quick-tilt features for ease of operation. Lifetime lubrication with oil light bearings. All-aluminum, die-cast construction. 500-watt bulb. Lifetime guarantee. F-526WX Shpg. wt., 10 lbs. Net 37.95
F-649 Carrying Case for F-526. Shpg. wt., 2 lbs. Net 6.44
F-746 Replacement Lamp (DAK) Net 1.89

4-LAMP MOVIE "BOUNCE" BAR LIGHT

- For all 8mm & 16mm cameras
- For color or b-&w
- Complete with flood lamps and case

8.95

Trapeze camera mount keeps lamps above camera, eliminating shadows. Swirls 90°. V-case accepts unit while lamps are hot. Exposure guide; on-off switch. 4 lamps and case. F-651 Shpg. wt., 6 lbs. Net 8.95



THE REMARKABLE LAFAYETTE f 1.8 TRIPLE TURRET 8 mm MOVIE CAMERA with Built-In Exposure Meter

Only **39.50**

NO MONEY DOWN


- 3 TURRET INTERCHANGEABLE f 1.8 LENS — Wide Angle — Normal View-Telephoto
- Built-in Wide Scale Electric Eye Exposure Meter With Exposure Guide
- THREE Built-in Filters — For Color, Normal and Bright Scenes
- Pistol Grip With Trigger Release
- "Combo-View" Finder — For Normal, Wide Angle and Telephoto Areas
- Ratchet Spring Wind



Lafayette is proud to offer a modern 8 mm movie camera that is ready for "rapid fire" shooting. A three turret assembly for instant change over to one of three lens, electric eye exposure setting, and pistol grip trigger release are time saving features the serious moviemaker should not overlook. A twist of the turret selects wide angle (f = 6.5 mm), normal (f = 13 mm), or telephoto (f = 25 mm), f 1.8 coated and color corrected lens. Turret action is smooth and positive. There is no need to fumble with focusing adjustments—all lens are pre-focused. The built-in exposure meter takes all the guess work out of exposure setting. Wide scale meter is matched with exposure guide to obtain proper lens opening, for perfecting filming. Also built-in are 3 filters: "conversion" for color film, "haze" for normal black and white and "neutral density" for extremely bright scenes. A choice of 4 speeds, 12, 16, 24 and 32 frames per second plus single exposure. Slide rule footage counter. Spring wound ratchet type motor runs 6 feet of film on a single winding. Exposure guide is calibrated for ASA 10 to ASA 40 film speeds. Direct optical viewfinder. Rugged die cast case in blue and gray. Trigger action, pistol grip handle and leather wrist strap included. Made to our specifications in Japan. Shpg. wt., 5 lbs. Net 39.50
F-702L Net 39.50
F-648 Holster Case for F-702. Shpg. wt., 8 oz. Net 2.95

MATCHED MOVIE OUTFIT

Everything you need for movie-making and showing fun. No need to "shop" for unmatched equipment, no need to pay more. You get all this: Lafayette's F-702, f1.8, Triple Turret movie camera with exposure meter; holster type camera case; "Holiday," F-526, 500-watt projector; F-536 30x40" screen; F-537 Bar Light; 2 F-539 photo flood lamps; 2 F-538 400' reels and cans. Unbeatable for foolproof shooting and showing of indoor and outdoor movies. F-789WX Shpg. wt., 30 lbs. Net 87.95



ZOOM MOVIE OUTFIT

Complete **136.50**
SAVE 14.79 from catalog prices

Complete ZOOM movie outfit contains all the equipment needed for success in taking and showing dramatic home movies. Included are the exclusive Lafayette 8 mm Zoom Camera (F-822), "Ultra" 500 watt projector (F-785), 30x40" folding tripod projection screen (F-536), bar light (F-537) with lamps and case, 2 reels and case (F-538), Zoom case (F-784) and 25 ft. of Kodak film with processing (F-576). F-823WX Shpg. wt., 35 lbs. Net 136.50



BIFLEX "LENS MASK" FOR POLAROID CAMERAS



- Cuts Film Costs in Half
- Doubles Your Enjoyment
- Makes Trick Shots Possible

4.01

Here is an amazing device which will pay for itself the first two times you use it. Simply slips over your Polaroid camera lens and presto—you get 16 pictures from each 8 exposure roll of Polaroid film. Each double frame is 2-9/10" high by 1-4/5" wide. Does not introduce optical distortion, merely covers half the lens for each shot. Fun to use too, many types of trick photographs are possible. Shpg. wt., 6 oz. For series 95, 95a, 95b, 100, 150, 700, 800, 850, 900. F-825 Biflex #1 Net 4.01
For Series 110, 110a, 110L, J66 Net 4.82
F-826L Biflex II

POLAROID ACCESSORIES

CLOSE UP KIT



7.25

Focus as close as 6 inches from your subject. Take portraits — small still lifes — do photocopying. Includes 3 snap-on close up lenses, leather case and built in tape for accurate focusing. Shpg. wt., 8 ozs. F-771L for all except 110B, 110A, 110, J33, J66 Net 7.25

PICTURE ROLLS 10 SECOND DEVELOPING TIME



32 and 42 are panchromatic types with an exposure index of 400 and 200 respectively. 37 and 47 have index ratings of 3000 and are used with the wink-light for indoor shots at normal room lighting levels. Shpg. wt., per roll, 5 ozs. Net ea in Lots

Stock #	Type	Camera Model	Net Per Roll	Net ea in Lots of 3
F-712L	47	All Except 80 Series, J33	1.89	1.80
F-713L	42	All Except 80 Series, J33, J66	1.77	1.68
F-714L	37	80B, 80A, 80, J-33	1.48	1.40
F-715L	32	80B, 80A, 80	1.38	1.30

FOLDING TRIPOD PROJECTION SCREEN



Fine grain glass beading for extra brilliance, excellent viewing. Heavy-duty folding tripod adjustable to various heights. Large 30x40" size. F-536 Shpg. wt., 10 lbs. Net 7.50

MOVIE & SLIDE PROJECTION LAMPS

Exact replacement projection lamps for most movie and slide projectors. Make your pictures sparkle with a new, efficient lamp. Imported. Avg. shpg. wt., 6 ozs.

Stock No.	ASA Code	Watt	Base Type	Net Ea.
F-741	CLS	300	Bayonet	1.49
F-742	CLX	300	Bayonet	1.49
F-743	CMV	300	S.C. Bay	1.49
F-744	CYC	300	S.C. Bay	1.49
F-750	CWD	300	Prefocus	1.69
F-747	EDK	500	Bayonet	1.79
F-745	CZX	500	Prefocus	1.79
F-746	DAK	500	Prefocus	1.89
F-748	DOB	750	Prefocus	2.15
F-749	DFD	1000	Prefocus	2.90



LAFAYETTE ZOOM LENS

- Fill the Screen From 12 to 15 feet—then ZOOM In!

The very latest in projection accessories for the movie fan. Coated, f1.5, 15 to 25mm focusable zoom lens fits most popular priced projectors. Converts our own "Holiday" (F-526) into a modern, zoom projector. Adds realism and depth to old "reels." Fills a 30x40" screen at from 12' to 15'—then zooms in for exciting closeups. Show your movies at the size you want—without moving projector or screen. F-690L Shpg. wt., 6 ozs. Net 6.95



2 LIGHT BAR
2.50

Holds still or movie cameras. Grip-handle prevents light bar from turning. 6 ft. cord. (Bulbs not included). F-537 Shpg. wt., 1 1/2 lbs. Net 2.50
PHOTOFLOOD BULBS, 300-watt, reflector type. F-539 Shpg. wt., 1 lb. Net ea. .95

ROLLAPRINT 10 SECOND PRINTMAKER



- Make Your Own Finished Prints EVERYTIME
- No "Lab" or "Darkroom" Needed
- It's Fun! It's Easy!

NOW ONLY **8.95**

Now every member of the family can have his own prints of precious photos. The amazing new ROLLAPRINT lets you make print after print in just a few seconds WITHOUT A DARKROOM. Prints from popular-size black and white or color negatives up to 3 1/4x4 1/4", in daylight or room light. Dries immediately, has a permanent finish, will not fade. For use at home, camera stores, studios, commercial uses, etc. Shpg. wt., 3 lbs. Net 8.95
F-696

ROLLAPRINT CHEMICAL SET

F-697 Shpg. wt., 2 lbs. Net 1.95

ROLLAPRINT PAPER

F-698 Box of 100. Shpg. wt., 8 ozs. Net 2.95

ROLLAPRINT 35 MM ENLARGER

37.50
NO MONEY DOWN

- Enlarges 35mm Negatives in Normal Room Light
- Uses B & W Negative or Color Slide
- It's Fun! It's Easy

Now you can enlarge your 35mm black-and-white negative or color slide. Just place your 35mm negative, or slide, into the enlarger, insert Rollaprint paper and press exposure button 2-4 seconds. Then run paper through Rollaprint Printer developing section and PRESTO!—a clear, clean, permanently-finished 3 1/4x4 1/4" B/W print. F-812 Less paper. Shpg. wt., 5 1/2 lbs. Net 37.50
ROLLAPRINT PAPER. Box of 100. Shpg. wt., 8 ozs. F-698 Net 2.95

ROLLAPRINT ROLLAKIT



Develops 35mm and 120-620 Films

9.95

Now you can develop your own pictures wherever you are, with the new Rollakit. Develops all 35mm and 120 to 620 films in normal room light. In only minutes you go from exposed film to beautifully finished dry prints, in conjunction with the Rollaprint printer. The Rollakit includes light-proof bag, Rollatank, Rollabath and clips. Shpg. wt., 2 lbs. F-813 Net 9.95

12 TRAY SLIDE CARRY CASE



- Pyroxin covered Kiln-dried Lumber
- FREE! 132-Letter Tinting Set

A sturdy 12-tray slide case, covered with scuff-proof Pyroxin coated material, holds TDC, Wollensak, Keystone, Argus, etc. trays. Special protected fiber inserts guarantee perfect fit for all length trays. Included is a complete tinting set with 132 letters. Overall size 11x11x9 1/2". Shpg. wt., 5 lbs. F-814 Less trays Net 3.59

COMPACT 6-TRAY SLIDE CASE



- WITH 6 UNIVERSAL TDC SLIDE TRAYS
- STURDY WOOD CONSTRUCTION

3.79

Will accommodate Keystone, A0, TDC, Viewflex slides. Scuff-resistant Pyroxin coated, all-wood construction. A convenient and compact way to store and carry your slides. Includes 6 Universal TDC slide trays. Overall 15x7 1/4x2 3/4". F-815 Shpg. wt., 3 1/2 lbs. Net 3.79

LAFAYETTE DIRECT IMPORTS Compare for Value

TESTED AND SELECTED FOR CONSISTENT QUALITY

35mm "RANGEFINDER III"



NO MONEY DOWN
28⁸⁸

- 4 ELEMENT F2.8 COATED LENS!
 - LUMINOUS BRIGHT FRAME VIEW-RANGE FINDER!
 - FILM TRANSPORT!
 - F2.8 45mm COATED LENS!
 - TERMINAL!
 - DOUBLE EXPOSURE PREVENTION
 - BUILT-IN SELF TIMER!
 - SINGLE STROKE RAPID
 - MX SYNCHRONIZATION
 - STANDARD PC FLASH
 - HI-SPEED REWIND!
 - BUILT-IN SELF TIMER!
- Check the features — then compare Lafayette's price with any other brand. Fast F2.8 coated anastigmat lens and extra-wide lens aperture for brilliant, sharper full color or black and white even in poor light. Sight and focus through combined range-view finder. Fully synchronized at all speeds for class M and electronic flash. Speeds from 1 sec. to 1/300th. Rapid advance sets shutter, counts exposure and transports film. Built-in delayed action timer — automatic exposure counter and film stop. Hi-speed rewind with brushed chrome trim—black leatherette covering. 20 or 36 exposures on black and white or color 35mm film. PC flash accessory shoe. All metal body on black and white or color 35mm film. Color covering. 20 or 36 exposures on black and white or color 35mm film. PC flash terminal. Exortly made in Japan. Shpg. wt., 3 lbs. Use series 6 accessories.
- F-778L Less Case Net 28.88
 - F-779L Leather Eveready Case. Shpg. wt., 1/2 lb. Net 3.95
 - Auxiliary Wide Angle and Telephoto Lens Set for "Rangefinder III." Net 15.95
 - F-808L Shpg. wt., 1 1/2 lbs. Net 3.39
 - Optical viewfinder for Wide Angle and Telephoto Lenses. Net 3.39
 - F-647L Shpg. wt., 6 ozs.
- ### MATCHED FILTER AND HOOD SET
- Includes Type "A" conversion, "F" conversion, "80B" photoflood, adapter ring and lens hood. Complete with leather case with room for additional filters.
- F-781L Shpg. wt., 8 ozs. Net 14.95
 - Special Combination Offer: Includes camera above—Eveready case—folding BC Flash gun—and clip-on exposure meter. Shpg. wt., 4 lbs. Net 38.95
 - F-780L

NEW! TRANSISTORIZED ELECTRONIC STROBE FLASH

Operates from Batteries and AC



24⁹⁵

NO MONEY DOWN

- Lightweight & Compact—No Power Pack Needed
- Fully Transistorized
- Operates on 4 Economical "Z" Cell Batteries
- Fits any Camera Shoe

Now you can have a high-powered, transistorized electronic flash that operates from standard AC house current or 4 economical "Z" cell batteries. Compact and featherweight—no power pack is required. Flash duration of 1/2000 sec. for fast pictures. Recycling time: 6-10 seconds; color temperature: 6000° Kelvin. Guide number dial for F stop on back. Complete with AC cord. Less batteries.

- F-827 Shpg. wt., 2 lbs. Net 24.95
- Batteries for above (4 required). Net each .095
- 8A-155

AUTO-DIAL EXPOSURE METER


Holds its reading indefinitely. Meter is aimed and dial stopper depressed. The dial then swings to correct reading and remains fixed when stopper is released. Ideal for widely variant light conditions. Color and black and white calibration with ASA speeds to 25,000. Reflected and incident light read on same scale. EVS 1 to 19. Lens: f/1.0 to f/32. Direct reading cine speeds 8-64 fps. Meter has zero adjust. Leather carrying case and neck strap.

6.75



F-791L Shpg. wt., 1 lb. Net 6.75

35MM LAFAYETTE "ELECTRICK 2.8"



NO MONEY DOWN

49⁹⁵

- Automatic Exposure Control
- Built-in, Cross Coupled, Exposure Meter
- Match The Pointer—Focus and Shoot!
- Coupled Rangefinder

Perfect exposure every time is assured by the cross coupled photoelectric exposure meter; merely set shutter speed and ASA film speed, aim camera, and line perfect exposure at any speed. Superimposed coupled range finder with automatic parallax correction enables accurate focusing from 2.5 ft. to infinity with automatic MX flash synchronization, and a self timer. Fast-action film advance cocks shutter, or black-and-white. Made in Japan to Lafayette's own specifications.

- F-656L Leather Eveready Case Shpg. wt., 3 lbs. Net 49.95
- Auxiliary Wide Angle and Telephoto Lens Set for "Electrick 2.8" wt., 1 1/2 lbs. Net 4.95
- F-809L Shpg. Net 15.96
- Optical viewfinder for Wide Angle and Telephoto lenses. Shpg. wt., 6 ozs. Net 3.39
- F-647L Shpg. wt., 1 lb. Net 3.99
- Folding BC flash gun. With battery and leather case.

LAFAYETTE AG FLASH GUN

- Compact in Size
- Made for the New AC Bulbs
- Dependable B-C Operation

2.99



The new Lafayette AG flash gun is a compact, palm size yet offers dependable B-C operation. Made for the new AG flashbulbs which are small in size and big in performance. The Lafayette flash gun has a fan-type reflector which measures 2" in diameter when opened. Standard shoe fits all standard accessory clips. Features a Compulor Dial for determining correct F stop. Testlight for checking battery and bulb, and Bulb Ejector. Complete with cord. Operates on 15V battery (not incl.). Shpg. wt., 8 ozs.


F-699 Net 2.99
BA-116 15-Volt Battery for above Net .81

BOOSTER EXPOSURE METER

- Includes booster—Leather cases—neck cord
- Stills or Movies • ASA Scale—LVS Scale

6.45

WITH BOOSTER



Extremely versatile—extremely simple. Highly legible direct reading dial. Speeds from 4 sec. to 1/1000 sec. Lens aperture settings from f:1 to f:32. ASA scale 6 to 800. LVS scale 1 to 18. Cine scale 8, 16, 24 and 32 frames per second. Booster cell makes possible readings at extremely low light levels. Small-rugged-light-weight. Includes booster cell, leather cases, neck cord and instructions. Shpg. wt., 1 lb. Net 6.45

"35" CLIP-ON EXPOSURE METER

3.95

- FITS CAMERA ACCESSORY SHOE
- ASA SCALE 10 TO 1000
- MEASURES REFLECTED AND INCIDENT LIGHT

Exceptionally convenient exposure meter. Clips right on camera—quick easy reading. Gives better, more accurately exposed pictures with a minimum of effort. Speeds 1/1200 to 1 Sec. Lens aperture f:1.4 to f:22. Mounts on camera or may be hand held. Complete with leather case and instructions. Shpg. wt., 1/2 lb.

F-351L Net 3.95

MANSFIELD 300 WATT 35MM PROJECTOR

Self Contained Case

- Brilliant 300 Watt—Turbo Blower Cooled
- 4 Inch, 13.5 Coated, Corrected Lens
- Designed for Easy Operation

28.95
NO DOWN PAYMENT



- For All 35 mm, 2 x 2 and Super Slides

Compact, convenient, semi-automatic, plus big-picture. 300 watt brilliance. Takes all 2x2 inch slides—35mm 828 (bantam) and 127 (super-slides). Semi-automatic "Presto-Matic" change; one push-pull movement picks, shows and replaces 36 slides in sequence. Self-contained storage for over 100 slides. Die cast aluminum. Self-contained case. All optics hard coated. Designed for optimum projection brilliance. For 110-120V. AC/DC. Shpg. wt., 12 lbs. Net 28.95

PROJECT-A-SCOPE

- Projects Giant Pictures in Color Or Black and White—Without Films or Negatives
- For Lectures—Study—Classroom or Just Plain Fun!

5.95



Amazingly versatile! Delightfully simple! Adjustable professional lenses. Just place it over anything flat—magazines, books, photos, drawings, coins, stamps, documents, maps, natural objects—and see a brilliant giant enlargement projected on any white wall or screen in glowing true-to-life color or black and white. A boon to students, artists, collectors, lecturers, demonstrators. Children can project their favorite comics or story books to amuse themselves and their friends. Molded of heat resistant, hi-impact polypropylene. Rigid transparent base, flattens and protects photos, prints and stamps. Uses ordinary household bulbs. U/L Approved 110V. AC/DC. Shpg. wt., 2 lbs. Net 5.95

ELEVATOR TRIPOD

- Folds to 16" including Panhead!
- Extends to 47" PLUS 7" Elevator!
- Tri-Tilt head—
- Moves in 3 planes!

8.59

For any small camera—35 mm—reflex—or movie Professional quality for professional results. Strong—steady—lightweight. Pencil slim, chrom plated, brass legs. Lock securely in place—fold down readily. Single action tilt pan—and swing over for taking pictures in vertical or horizontal format. Geared elevator center-post with positive lock and folding crank. Weighs only 31 ozs. All the most wanted features in one tripod. Shpg. wt., 2 1/2 lbs. Net 8.59

MATCHED 35MM CAMERA OUTFIT

Complete, ONLY **65.95**

Reg. catalog price 83.21 YOU SAVE 16.26



A complete 35mm camera outfit for indoor and outdoor picture taking, in color or black-and-white. You save: \$16.26. You get: Lafayette "Electrick 2.8" 35mm camera with automatic exposure control (F-655L); leather carrying case for the camera (F-656L); transistorized electronic strobe flash that operates on batteries and AC (F-827); 4 batteries for the flash (8A-155); roll 35mm Kodachrome film with processing (F-581L). F-810L No Money Down. Shpg. wt., 6 lbs. Net 65.95

GENUINE LEATHER GADGET BAG

4.95




Genuine pigskin—not plastic. Full 10x8x4". Holds your camera and all accessories. 20" zipper top. Pouch in lid holds filters, etc. Outside pouch with strap and buckle. All brass hardware. Loops and straps on bottom to hold tripod. Includes shoulder strap and pad. Shpg. wt., 1 lb. Net 4.95

LAFAYETTE "SPEEDLITE"

ELECTRONIC PHOTOFLASH SYSTEM

- 110V AC or MIDGET BATTERY PACK
- COLOR BALANCED LIGHT
- 35 WATT SEC. OUTPUT
- BUILT IN DIFFUSER
- SUPER POWERED
- FEATHERWEIGHT

25.95
NO DOWN PAYMENT



Thousands of flashes from one lifetime tube—less than 1/2 cent per flash. Coiled cord extends 5 ft. Universal bracket fits any camera with a tripod socket. Gun also mounts on side of portable pack. Light is balanced (6200° Kelvin) for color pictures. Kodachrome guide 25-Tri-X guide 120. Recycles in 6 to 7 seconds. Speed 1/1000 sec. flash duration. Socket for extension or multiple flash use. For any camera having X (zero delay) synchronization. Complete with battery, portable pack, 5 ft. coiled cord, shutter cord. 15 ft. A.C. cord, mounting bracket, clamp and instruction book. Sngp. wt., 4 lbs. Net 25.95

- F-370
- Replacement Battery for above. Shpg. wt., 1 lb. Net 4.50
- BA-13

KODAK FILM WITH PROCESSING INCLUDED

- Slides Returned Mounted, Ready for Viewing or Showing!
- Rigid Processing Controls Assure Highest Quality
- Convenient, direct-mail "mailers" in every roll
- A full number of Prints guaranteed for Kodachrome and black and white.

You get factory-fresh film plus a convenient direct-mail mailer. After the complete roll has been filmed, put it into the mailer, drop into a mailbox and in a few days your finished films are delivered postpaid to your door. You get 3 1/2" square or 3 1/2x5" giant prints with Kodachrome and Black & White—and a full number of prints is guaranteed. Should you get less than the full number of prints of Kodachrome or Black & White printable negatives per roll, you will receive coupons for additional FREE prints. DO NOT MAIL FILM TO LAFAYETTE RADIO.

KODACHROME COLOR MOVIE FILM

Stock No.	Description	Net ea.	Net ea. lots of 6
F-575L	8mm, 25 ft. roll, Daylight	3.55	3.40
F-576L	8mm, 25 ft. roll, Indoor	3.55	3.40
F-577L	8mm, 25 ft. Mag., Daylight	4.60	4.42
F-578L	8mm, 25 ft. Mag., Indoor	4.60	4.42

NEW! KODACHROME II COLOR MOVIE FILM

- 2 1/2 Times Faster; ASA Index Daylight 25, Indoor 40

F-794L	8mm, 25 ft. roll, Daylight	4.49	4.22
F-795L	8mm, 25 ft. roll, Indoor	4.49	4.22

KODACHROME 35mm COLOR SLIPE FILM

F-580L	35mm, 20 Exp. Daylight	2.98	2.85
F-581L	35mm, 20 Exp. Indoor	2.98	2.85
F-582L	35mm, 36 Exp. Daylight	4.38	4.20
F-583L	35mm, 36 Exp. Indoor	4.38	4.20

NEW! KODACHROME II 35mm COLOR SLIPE FILM

- ASA Index Daylight 25, Indoor 40.

F-796L	35mm, Daylight, 20 Exp.	3.59	3.39
F-797L	35mm, Daylight, 36 Exp.	5.49	4.98

KODACHROME COLOR SNAPSHOTS

F-584L	127 Indoor/Outdoor	3.72	3.56
F-585L	120 Indoor/Outdoor	3.72	3.56
F-586L	620 Indoor/Outdoor	3.72	3.56


KODAK BLACK & WHITE ROLL FILM

F-587L	127 Verichrome Pan	1.28	1.17
F-588L	120 Verichrome Pan	1.28	1.17
F-589L	620 Verichrome Pan	1.28	1.17
F-590L	35mm, 20 Exp., Plus X	2.32	2.24
F-591L	35mm, 36 Exp., Plus X	3.45	3.35

LAFAYETTE 9-TRANSISTOR CITIZENS BAND "WALKIE TALKIE"™

EXCITING NEW KORDEX™ -TRANSISTOR TAPE RECORDER

In Economical Semi-Assembled Kit Form



ONLY
17.95

ASSEMBLES EASILY IN
LESS THAN AN HOUR

- Extra Small • Fully portable—Battery Powered • A Mere 2½ lbs. in Weight • Pre-wired 4 Transistor Printed Circuit Amplifier
- Accepts Standard 3" Tape Reel • Instant-Action Play/Rewind Lever Control • Record, Rewind, Playback, Erase.

INCLUDES: Crystal Lapel Microphone, 3" Reel of Tape, Empty Reel, Batteries, Screwdriver.

Here is a precision, full function miniature tape recorder in money saving semi-assembled kit form. In less than one hour the KorDEX Tape Recorder can be assembled and ready for operation. The amplifier is prewired in a rugged printed circuit, thereby eliminating most of the work. Complete it weighs only 2¾ lbs. and slips easily into a briefcase or handbag. Designed for ease of operation, all controls are readily accessible. Fast, instant, Rewind-Off-Play functions are provided by a handy lever control. In addition the front panel also includes a Record-Play Slice Switch, Volume Control, plus Earphone and Microphone jacks. The powerful 4 transistor precision wired amplifier drives a specially designed built-in 2" PM speaker.

With its attractive carrying case the KorDEX recorder is equally suitable for home, office or travel—power is supplied by one standard "C" flashlight cell and one inexpensive 9 volt transistor battery. Complete with crystal lapel microphone, batteries, 3 Inch, 100 ft. reel of tape, empty reel, earphone and instructions. Measures 8Wx6½Dx3"H. Shpg. wt., 6 lbs.

KT-212	Net 17.95
RT-20 3" Reel 300 ft. ½ mil Mylar tape.	Shpg. wt., 4 oz. Net .65
BA-2 9 volt transistor battery for above.	Shpg. wt., 2 oz. Net .39
BA-156 1.5V Battery for above (1 req.).	Shpg. wt., 2 oz. Net .13

plus Diode
and Thermistor

NO LICENSES,
TESTS OR AGE LIMITS



Complete with
LEATHER CASE,
EARPHONE,
ANTENNA
& BATTERIES

- Transmits & Receives Up to 1.5 Miles
- Crystal Control on Both Transmit & Receive
- Leather Case with Shoulder Strap
- Requires 8 Inexpensive Penlight Batteries
- Up to 70 Hours Battery Life
- 46" Telescoping Antenna
- Push-To-Talk Operation
- Earphone For Personal Listening

OTHER CHANNELS ARE AVAILABLE
If desired with any channel other than
channel 10, order HE-31L and specify
channel.

NOW NO MONEY
DOWN
39.95
2 for 78.88

No License or Permit Required—Complete portable two-way communications for everyone, everywhere. Perfect for hunting, fishing, boating, virtually all sports; use at work in construction, warehouse, office, on the farm or for in plant communications. Receives and transmits up to 1.5 miles under average conditions (no intervening obstructions.)

As simple and easy to use as your telephone and twice as handy—weighs only 18 ounces and slips easily into your pocket. Just two controls provide fast, efficient operation, on/off volume and push-to-talk. When push-to-talk button is depressed for transmitting the built-in-speaker acts as a sensitive microphone. Private monitoring of conversation is made possible by means of a special jack and earphone. Telescoping antenna extends to 46 inches.

Constructed with the care and precision of a fine watch, this new Lafayette Citizens Band "Walkie Talkie" achieves optimum reliability and performance by use of sophisticated transistor techniques and advanced design. Full transistor circuitry employs 9 transistors plus 1 diode. Transmitter section is crystal controlled and delivers a power input of 100 milliwatts, meeting FCC specifications for unlicensed units in the 27mc Citizens Band spectrum. Crisp-clear reception is furnished by the efficient superheterodyne receiver. Power is supplied by 8 miniature standard penlight batteries with a life expectancy of up to 70 hours.

Housed in a handsome black and gold aluminum case with leather carrying case and shoulder strap. Supplied with earphone, antenna, batteries and crystals for channel 10. Size 6¾x3¼x1¾". Shpg. wt., 3 lbs.

HE-29AL	Set of 2	Net 39.95
Replacement batteries for HE-29 "Walkie-Talkie," 8 required		Net 78.88
BA-155 2 Cells		Net Each .095
CRYSTALS FOR HE-29A		
HE-830L TRANSMITTING CRYSTAL (Specify Channel)		Net 2.25
HE-758L RECEIVE CRYSTAL (Specify Channel)		Net 2.25

"MIGHTY 9"™ The MOST POWERFUL 9 TRANSISTOR PERSONAL PORTABLE

NO MONEY
DOWN!



with 2 DIODES
and 1 THERMISTOR

ONLY
25.88
NO MONEY
DOWN

- LIGHTWEIGHT SHIRT-POCKET SIZE • PLAYS FOR HOURS ON 2 MOST INEXPENSIVE BATTERIES • SEPARATE MIXER AND OSCILLATOR • 2 IF STAGES • 4 AUDIO STAGES • 2 DIODES • AVC AMPLIFIER • PERSONAL, BUILT-IN EARPHONE JACK • COMPLETE WITH LEATHER CARRYING CASE, BATTERIES, EARPHONE • FULL-TONE SPEAKER

Lafayette's new "Mighty-9" portable, the most powerful transistor radio, is the answer for those who want the best, without spending the most. Compare this portable with others selling for much more—compare feature for feature and you'll see why the Lafayette "Mighty-9" is your best buy. Inside the sturdy, attractive plastic case you'll find an engineer's dream—separate mixer and oscillator, diode detector and diode bias stabilizer, 2 IF stages, AVC amplifier, 4 audio stages including push-pull audio output. Lightweight (only 9 ozs.), pocket size (4½Hx3Wx1¼"D); self-contained stand. Best of all it operates on two of the most inexpensive "Z" cell batteries—plays up to 3 times longer than on other 9 volt batteries. Complete with leather carrying case, batteries and earphone for private listening. Shpg. wt., 2 lbs.

FS-91L	Net 25.88
BA-155 (Burgess Z type battery 2 required)	Net ea. .095

Complete with
carrying case,
batteries and earphone

FAMOUS PICKERING MARK II C CARTRIDGE

SPECIAL
SALE PRICE
9.88

Complete with D9007
Diamond Stylus

REG.
24.00

with D3707A Stylus • .7 Mil Diamond Stylus
• Response ± 2 db 10-30,000 CPS

QUANTITY
LIMITED

Here is the famous Pickering Mark II C Cartridge with .7 mil diamond stylus that reproduces both mono and stereo perfectly. Uses "T-Guard" stylus assembly. Tracking force: 3-7 grams; separation: 25 db; output: .025 volts per channel. Shpg. wt., 3 ozs. Net 9.88



NOW! NO MONEY DOWN when you use LAFAYETTE'S NEW EASY-PAY PLAN!

LAFAYETTE RADIO ELECTRONICS "ASSOCIATE STORE" DEALER LOCATIONS

Lafayette Radio Electronics "Associate Store" Dealers own and operate their own stores as independent franchised dealers. They establish their own terms and prices, which may vary slightly, and do not handle mail orders.

SAN FRANCISCO, CALIF.
1480 Market St.
DENVER, COLO.
1455 So. Sheridan Blvd.
BRIDGEPORT, CONN.
2710 Fairfield Ave.
GROTON, CONN.
171 Thames St.
STAMFORD, CONN.
85 Prospect St.
WATERBURY, CONN.
386 West Main St.
TAMPA, FLA.
3328 Henderson Blvd.

MACON, GA.
4127 Pio Nono Ave.
SALINA, KANSAS
314 West Cloud
SPRINGFIELD, MASS.
527 Belmont Ave.
BALTIMORE, MD.
2014 No. Chartes St.
BEL AIR, MD.
139 Thomas St.
DETROIT, MICH.
1326 Broadway
ASBURY PARK, N. J.
1027 Highway No. 35
CAMDEN, N. J.
305 Broadway

NORTHFIELD
(Atlantic City), N. J.
Tilton Shopping Center
Tilton Road
TRENTON, N. J.
229 South Warren St.
ALBANY, N. Y.
335 Central Ave.
BUFFALO, N. Y.
747 Main St.
ROCHESTER, N. Y.
792 W. Main St.
CHARLOTTE, NO. CAR.
127 W. 1 St.
AKRON, OHIO
34 North Main

CANTON, OHIO
300 Walnut St.
CLEVELAND, OHIO
2001 Euclid Ave.
COLUMBUS, OHIO
122 E. Long St.
AKRON, PA.
127 No. 7 St.
ALLENTOWN, PA.
20 North 7th St.
HARRISBURG, PA.
1419 No. 3rd St.
PITTSBURGH, PA.
640 Grant St.
WILKES-BARRE, PA.
115 No. Main St.

LAFAYETTE RADIO

111 JERICHO TURNPIKE
SYOSSET, LONG ISLAND, NEW YORK

RETURN REQUESTED

BULK RATE
U. S. POSTAGE
PAID
New York, N. Y.
Permit No. 8486

MAIL ORDERS NOT FILLED BY "ASSOCIATE STORE" DEALERS

L M N P Q R S T U V
1 2 3 4 5 6 7 8 9 0