

LAFAYETTE RADIO ELECTRONICS

CATALOG NO. 631

SEE EASY-PAY PLAN ON PAGE 54

BUY the EASY-WAY
with EASY-PAY
and take home more of
what you want when you want it.
NO MONEY DOWN
Up To 24 MONTHS
To Pay

SALE

50%
MORE
BUYING
POWER

Bargain Bonanza!

**FANTASTIC
10 TRANSISTOR
"WALKIE
TALKIE"**™
SEE PAGE
64
HE-29B

- ADDED RF Stage For Greater Selectivity and Sensitivity
- 50% More Powerful
- Complete with Crystal for Channel 10

was 39.95
NOW 33.95
6290
per pair

**LAFAYETTE AUTOMATIC 4-SPEED
RECORD
CHANGER** PK-605W
SEE PAGE
15

- Plays Stereo, LP and 78 Records
- Quality Ceramic Cartridge
- Intermixes
- Automatic Shut-off

was 22.35
NOW 18.95

**LAFAYETTE "TINY" 6
TRANSISTOR RADIO**
SEE PAGE
4
FS-243L

- Big Set Tone
- Vest Pocket Size

Complete with carrying case, batteries and earphone

ONLY 9.97

24-WATT MATCHED STEREO SYSTEM

Lafayette LA-224 Stereo Amplifier
Garrard Autoslim on Base (Walnut or Mahogany)
Lafayette (2) SK-124 Ultra-Compliance Speaker System (Walnut or Mahogany)

LS-225WXM System
only 129.50
No Money Down
SEE PAGE 12

A Family Entertainment Center

Your choice of one of these cartridges:
Shure M3D Empire 880 Pickering U38/AT

**LAFAYETTE DELUXE
DUAL SPEED
TAPE RECORDER**
Selling Below Cost at
59.88
No Money Down
SEE PAGE 17

- Plays up to 7" Reels
- Everything You Need For Tape Recording

3 3/4 & 7 1/2 ips
RK-130 WX

LAFAYETTE RADIO ELECTRONICS

NATICK, MASS.
(Opening Fall 1962)
Route 9
(Opposite Shoppers World)

SHOP BY PHONE DEPT.
Walnut 1-7500
All Departments
Walnut 1-7700

Mail Order and Sales Center
SYOSSET, Long Island, N. Y.
111 JERICHO TURNPIKE
(2 Blocks West of South Oyster Bay Road)

SCARSDALE N. Y.
691 Central (Park) Ave.
(1/2 Mile North of Ardsley Road)
GREENLEAF 2-2700
Open MON., THURS., FRI. 'til 9:30 P.M.

JAMAICA
165-08 Liberty Ave.
Jamaica 33, N.Y.
AXtel 1-7000
Open MON. & FRI.
'til 8:45 P.M.

NEW YORK
100 - 6th Avenue
(off Canal St.)
New York 13, N.Y.
WORTH 6-5300
Open THUR. 'til 8:45 P.M.

BRONX
542 E. Fordham Road
Bronx 58, N.Y.
FORDHAM 7-8813
Open THUR. 'til 8:45 P.M.

NEWARK
24 Central Avenue
Newark 2, N.J.
MARKET 2-1661
Open WED. 'til 8:45 P.M.

PLAINFIELD
139 W. 2nd Street
Plainfield, N.J.
PLAINFIELD 6-4718
Open THUR. 'til 8:45 P.M.

PARAMUS
Paramus, N.J. 182 Route 17
(1 MI. North of Garden State Plaza)
COLIFAX 1-8800
Open MON., WED.,
FRI. 'til 8:45 P.M.

BOSTON
110 Federal Street
Boston 10, Mass.
HUBBARD 2-7850
Open MON., WED.
'til 8:45 P.M.

LAFAYETTE FINEST QUALITY RADIOS



SHIRT
POCKET
SIZE

Amazing "MIGHTY 9"

THE MOST POWERFUL
9-TRANSISTOR
PERSONAL PORTABLE

NOW ONLY
19⁹⁵

1962 Catalog Price
Was ~~25.88~~

9 TRANSISTORS
PLUS 2 DIODES
PLUS
THERMISTOR

- Lightweight Shirt-Pocket Size
- Plays for Hours on 2 Most Inexpensive Batteries
- Personal, Built-in Earphone Jack
- Full-Tone Speaker
- 4 Audio Stages
- 2 IF Stages
- AVC Amplifier

Compare this portable with others selling for much more—compare feature for feature and you'll see why the Lafayette "Mighty-9" is your best buy. Inside the sturdy, attractive plastic case you'll find an engineer's dream—separate mixer and oscillator, diode detector and diode bias stabilizer, 2 IF stages, AVC amplifier 4 audio stages including push-pull audio output. Lightweight (only 9 ozs.), pocket size (4½x3½x1½" D); self-contained stand. Operates on two of the most inexpensive batteries. Complete with leather carrying case, batteries and earphone for private listening. Imported. Net 19.95
FS-91L Shpg. wt., 2 lbs. BA-155 (Burgess Z type battery—2 required) Net ea. .095



Complete
with carrying case,
batteries and earphone

8-TRANSISTOR 2 BAND

AM/MARINE
PORTABLE RADIO

- AM — 550 to 1600 KC
- MARINE — 1.6 MC to 4.6 MC

ONLY **23⁹⁵**
NO MONEY DOWN

- Highly Sensitive Rod-Antenna Plus Built-in Ferrite Core Antenna
- Strong and Shock Resistant Plastic Case
- Covers 55 — 4.6 Mc
- Specially Designed Tuning and Battery Energy Indicator
- Earphone for Private Listening
- Practical Leather Case

LOWER PRICED THAN MANY
AM ONLY 8-TRANSISTOR RADIOS



with
TUNING
METER

- Rod Antenna
- Leather Case
- Earphone

This fine transistorized portable covers both the general broadcast band plus the 1.6-4.6 mc marine band. Your perfect listening companion even when at sea. A built-in antenna is used for the broadcast band and a telescoping antenna for the marine band. The telescoping antenna is readily detachable and may be carried in the same manner as a pocket pen. The receiver circuitry utilizes 8 transistors, 1 diode, and 1 Varistor Superheterodyne system with A.G.C. Also includes a specially designed tuning and battery energy indicator which allows you to check the strength of the batteries

to assure maximum performance. The built-in speaker can be shut off by inserting an external earphone (supplied) for personal listening. Operates on 4 inexpensive Z cells giving up to 3 times longer life than ordinary 6 volt batteries. Comes complete with telescoping antenna, carrying case and earphone. Measures 5½x3½x1½".
FS-244L Shpg. wt., 2 lbs. Imported Net 23.95
Replacement cells for FS-244L, 4 required. Shpg. wt., 4 oz.
BA-155 Z cells Net ea. .095

LAFAYETTE 7-Transistor Marine & Broadcast 2-Band Radio

1962 Catalog Price ~~28.50~~

19⁹⁵

- Covers AM Broadcast Plus 1.6-4.8 MC. Marine Band
- Sensitive Receiver Uses 7 Transistors, 2-Diodes, And 1-Thermistor
- 2 Built-in Antennas, Including 9 Section Telescoping Antenna for Marine Band
- Operates on 2 Inexpensive Penlight Batteries
- Complete With Carrying Case, and External Earphone
- A Must For Marine Enthusiasts
- Compact and Lightweight

With this new sensitive transistorized radio, Lafayette answers the needs of the marine enthusiast. It receives both the standard AM broadcast band and the Marine Band (1.6-4.8 MC). A built-in antenna is used for the broadcast band and a 9 section telescoping antenna for the marine band. The telescoping antenna is readily detachable and may be carried like a pocket pen. The receiver circuitry utilizes 7 transistors, 2 diodes and 1 thermistor for power-packed performance. Simple selector switch allows choice of Broadcast or Marine Bands and a clearly marked slide dial makes tuning simple. The built-in speaker can be shut-off by inserting an external earphone (supplied) for personal listening. Comes complete with 9 section telescoping antenna, carrying case and earphone. Only 5½x3½x1½". FS-223L Shpg. wt., 2 lbs. Net 19.95
Replacement batteries for FS-223 7 Transistor radio, 2 required.
BA-155 Z Cells Net each .095



9 SECTION
ANTENNA EXTENDED

CARRYING
CASE

LAFAYETTE SUPER-DELUXE "MINI" 6 TRANSISTOR RADIO

LOWEST PRICE
EVER! **12³³**

- 6 Transistors Plus Germanium Diode and Thermistor
- Vest Pocket Size—Only 3½ H x 2½ W x 1"D.
- Weighs only 7 ounces with batteries
- Penlight Powered For Economy—Long Life
- Earphone Jack Built-in For Private Listening
- Rich Tone Dynamic Speaker
- Trouble-Free Printed Circuit
- Built-in Ferrite Bar Antenna
- Superheterodyne Circuit

A truly remarkable radio, the "MINI" 6 is so compact and lightweight (just 7 oz.) you hardly know you're carrying it—turn it on and get the biggest, clearest sound yet, from a pocket 6 transistor set. Precision engineered—true superheterodyne printed circuit board assures long trouble-free operation. Push-pull audio output, 6 transistors, one diode and one thermistor are utilized to obtain really phenomenal reception across the entire broadcast band. Only 2 two inexpensive penlight cells are required. This cuts down battery drain and lengthens playing time considerably over ordinary single cell radios. "Jewel" black and gold case of durable plastic and soft attractive black leather carrying case with attached earphone pouch complete this smart set. Includes 2 batteries, carrying case and matched earphone for personal listening. All at our low, low price. Shpg. wt., 1.5 lbs. Imported
FS-235L "MINI" 6 transistor Radio Net 12.33
Extra batteries for FS-235L Type Z (2 required). Shpg. wt., 4 oz.
BA-155 Z Cells Net ea. .095

PRICED EXTRA
LOW!
COMPARE
FOR VALUE



CARRYING
CASE

EARPHONE

BATTERIES

LAFAYETTE FM TUNER

with
MULTIPLY
OUTPUT
JACK

COMPARE!
16⁹⁵



FULLY
WIRED
— NOT
A KIT

- SLIDE RULE TUNING DIAL
- SIMPLEST OPERATION
- CONNECTS TO HI-FI, TV or RECORDER

A Lafayette low cost exclusive! The Model FS-234 Tuner is a real compact beauty. Ideal for use as a "second" FM Tuner—perfect for Students and Teenagers. Just one cable connects it to your Hi-Fi amplifier, TV or tape recorder input to give you static free FM listening enjoyment. Features a built-in multiplex jack for future adaptor installation if desired. Complete with 1 connecting cable. Most radios, TV sets, phonographs and tape recorders have phono input jacks to take the shield-plug connection from the tuner. For equipment not provided with input jack, the necessary connections can easily be made by any serviceman. SPECIFICATIONS: Tuning Range: FM 88 to 108 MC. Controls: on/off—volume, Tuning. Antenna: Provision for external twin lead antenna. Power: 110-115 VAC, 30 watts. Tubes: (2) 12BA6, 12DT8, 12AL5 and Silicon Diode. Size: 6½x4½x4½". Imported. Net 16.95
FS-234 Shpg. wt., 4 lbs.

"CONTEMPORARY" AC/DC RADIO

Distinctive Style — Highest Quality — Incredible Price

10⁹⁹



Swivel Base

- Advanced Handwired Chassis
- Fingertip Tuning
- 5 Tubes For Peak Performance!
- Electrical Safety Interlock

A "better" 5 tube radio—engineered and styled to last. Petite, contemporary design maintains clean, good looks and peak performance. 5 tubes (2 dual purpose), plus a Hi-Q ferrite rod antenna pulls in more distant AM stations. 3½" P.M. speaker, properly baffled in a sturdy, vented cabinet for clear tonal quality. Muted colors to match any color-scheme; gold trim. Pedestal base swivels for sound and reception directivity. Cabinet measures 8½x4½x4" overall. Tubes: 35W4, 50C5, 12AV6, 12BA6, 12BE6. For 117 V. A.C./D.C. Shpg. wt., 3 lbs. Imported. Net 10.99
FS-233

NEW! HOUSE N' CAR RADIO



- Plays in Any 12 V. Car or Boat or on 117V AC/DC
- No Installation — Just Plug in Lighter
- Needs No Outside Antenna
- Complete With Generator Condenser and Noise Suppressor

Play this radio anywhere! In the home — car — boat — trailer! Any place you can obtain a 12 V D.C., or 117 V AC/DC supply! The radio (our FS-233) and the new Dynamo Inverter form a customized package to suit a wealth of needs. You can even run your shaver in your car or boat! Shpg. wt., 5 lbs. Net 18.66
SP-229M

at **UNBEATABLE GUARANTEED PRICES!**


"TENSTAR" 10-TRANSISTOR PORTABLE RADIO

True Space Age Engineering with Sky-High Power

When Only The Best Will Do!

- 10 Perfectly Matched Transistors, 2 Diodes, 1 Thermistor • Powerful Performance — Oversize Ferrite Antenna
- Big Set Tone — 2 3/4" Speaker Acoustically matched and Balanced • Batteries, Earphone, Leather Case Included

NOW! 22⁹⁵



A remarkable achievement in compact design. 10 transistors and 2 diodes provide brilliant performance—equal to table model sets. This means more stations, greater selectivity and sensitivity. Large, dynamic 2 3/4" speaker gives you big tone, indoors, outdoors—wherever you go. Plays for hours on 4 penlite cells carefully encased to protect set against battery acid corrosion. Fine quality leather cases are included for the radio and separate earphone. Two controls for simplicity; volume-off and Tune. Easy-to-read vertical slide rule dial. Complete with batteries and earphone. Size: 3 1/4"x6 1/2"x1 3/4" D. Imported. FS-129L Shpg. wt., 1.5 lbs. Net 22.95 Additional batteries for above. BA-155 (4 required) Net ea. .095

Carrying Case Earphone

LAFAYETTE 12-TRANSISTOR FM/AM SHORTWAVE PORTABLE RADIO

COMPARE the FEATURES!

- ★ 12 Transistors — 4 Diodes — plus Varistor
- ★ 3 Bands FM-AM — SW (4-12 MC)
- ★ 3x5" Speaker — As Large As in Many TV Sets
- ★ High Efficiency — Space Age Circuitry Tuned RF Stage
- ★ Hi-Q Long Range Antennas
- ★ FM/AFC — Locks in Stations
- ★ Tone Control plus AGC
- ★ Optional AC operation
- ★ Superior Audio Output — more than 300 mw
- ★ Precise Sliderule Tuning
- ★ Plays Hundreds of Hours on 6 Flashlight Batteries



ONLY 49⁹⁵
NO MONEY DOWN

• Easily Pulls in European Stations!

Triple your listening pleasure with a 4-12 megacycle shortwave band which can pick up amateur (40 Meters), Police, aeronautical and Foreign stations; exciting programming from all parts of the world, plus static-free FM programs providing life-like music and voice comparable to many large table model radios. Receives AM too, gets excellent reception where lesser portables fail. The 12 Transistor 4 diode plus varistor superheterodyne circuit with 7 section 29 1/2" monopole FM antenna has extra sensitivity to bring in those distant stations. Heavy magnet 3x5" speaker provides rich full tone. Separate Tuning and Volume controls permit easy adjustment to individual taste. FM circuit has AFC switch to "lock-in" stations. Tone Control switch provides desired listening quality for voice or music on all bands and a Band Selection switch. Economical to operate—plays on 6 standard "C" cells or AC with adapter (optional at slight extra cost). Includes earphone and batteries. Dimensions: 9 3/4"x5 1/4"x2 3/4" D. FS-251L Shpg. wt., 5 1/2 lbs. Imported. Net 49.95 Additional Batteries For Above. BA-156 "C" cell, 6 required. Net ea. .13

SAVE BATTERIES • Can be operated on AC House Current with Adapter (optional)



7⁹⁵ LAFAYETTE AC ADAPTER

Rugged long-life design prolongs battery life by allowing set to be operated from 117V 60 cycle AC line. Can be used with FS-251L on this page. Size: 2 3/4"x2 3/4"x5 1/4" D. Shpg. wt., 2 1/2 lbs. FS-255 Net 7.95

NEW!

LAFAYETTE "DUETTE" DUAL SPEAKER OILED WALNUT FM/AM TABLE RADIO



★ You'll Know It's The BEST — The Moment You Hear It!

- Two 4-Inch PM Speakers for Full Dynamic Range
- 6 Tubes Plus 3 Diodes for Console Performance
- Built-in Hi-Q Antenna
- Beautiful, Oiled Walnut Fine Furniture Cabinetry
- External 300-Ohm Antenna Input Terminals
- AFC, AGC and RF Stage on FM and AM
- Provision for Extension Speaker

TOP VALUE! 39⁵⁰
NO MONEY DOWN

Here is a top quality FM/AM table radio. Dual, 4-inch PM speakers, in an acoustically correct cabinet, produce rich full-frequency sound on both FM and AM. Features improved AFC action which "locks-in" FM stations for drift-free reception; Automatic Volume Control to soften any sudden volume blasts and to make tuning stations of different levels easier. A super-sensitive AM antenna brings in distant stations clearly while reducing unwanted noise. An FM wire antenna is provided to assure all benefits of clear, pure FM reception. An external 300-ohm FM antenna

can be attached to built-in input terminals for improved reception of distant stations. Beautifully finished Oiled Walnut cabinet and easy-to-read slide rule dial with an on-off neon indicator light. Contains 6 tubes, 1 varicap, 2 diode detectors and 1 silicon diode rectifier. Meets FCC requirements for radiation shielding. A receptacle on the rear of the radio allows easy, quick addition of an extension speaker. For 110-120 volts, 60 cps AC or DC. Size 17 1/2"x7 3/4"x5 3/4" D. Shpg. wt., 8 lbs. Imported. FS-246 Net 39.50

9-TRANSISTOR FM/AM PORTABLE RADIO



3 ANTENNAS

with pushbutton controls

SENSATIONAL LOW PRICE

39⁹⁵
NO MONEY DOWN

- 9 Transistors — 4 Diodes — 1 Varistor
- Big Tone 3x5" PM Speaker

This superb Lafayette radio will recreate for you all the glorious tones of thrilling, static-free FM programming as well as standard AM broadcasts. Styled for tomorrow, the FS-245 features a beautiful black plastic case with carrying handle. Off, FM, and AM modes are selected by positive push-buttons. A precision slide rule dial with high gear ratio tuning makes this set one of the easiest to tune. Two 22" telescoping antennas pull in most FM stations with ease while the large 3x5" PM

- Over 400 Hours on 4 Flashlight Cells
- Extra Stage of RF
- 3 Antennas

dynamic speaker assures you of glorious tone. Other features include, built-in ferrite rod antenna for AM, tone control and 2 earphone output jacks. Sensitive circuit incorporates 9 transistors, 4 diodes, 1 varistor, automatic gain control. Four inexpensive "C" type cells power the unit. Complete with batteries and earphone. Size: 9 1/4"x5 3/4"x2 1/2" D. Imported. FS-245L Shpg. wt., 4.5 lbs. Net 39.95 BA-156 Extra Batteries for above. (4 required) Net ea. .13

LAFAYETTE "LONG DISTANCE" AM-SHORTWAVE TABLE RADIO

SW VALUE of The Year!

1962 Catalog Price 26.50

NOW ONLY

19⁹⁵



- Attractive Decorator Cabinet
- Power Packed 7 Tube Performance — 5 Tubes (2-dual purpose)
- Large Slide Rule Tuning Dial with Automatic Indicator Lights
- Provision For External Phonograph
- "Big Speaker" Sound

A smart new way to enjoy yourself—listen to short-wave radio! Never before has a SW receiver of this quality been offered at such a low, low price. Beautifully styled to fit into any room, the 231 features 7 tube performance from 5 tubes (2 dual purpose) for maximum station "pulling" power. Separate SW antenna terminal to permit antenna selection suitable for location. Large PM speaker and 3-step tone control enhance your audio pleasure. Extremely legible slide-rule dial has separate pilot lights of different color which automatically switch-on to quickly identify band in use. In addition a phono jack is provided in the rear of the set for connecting any external phonograph. Covers the entire broadcast band and SW band from 3.8—12 MC. Tubes: 6BE6, 6BD6, 6AV6, 6AR5, 6X4. For 117 V, 60 cycles AC. Size 16Wx5 1/4"Dx 5 1/2"H. Shpg. wt., 10 1/2 lbs. Imported. FS-231 Net 19.95

Text

NEW LOW PRICE!

5⁵⁵

2-TRANSISTOR PORTABLE with BUILT-IN SPEAKER



- 2-TRANSISTORS + 1 DIODE • BUILT-IN SPEAKER
- COMPLETE WITH TELESCOPING ANTENNA, EARPHONE & CARRYING CASE

A two-transistor powerhouse that will amaze you with its performance and sound quality. Here's the perfect gift for that youngster who has always wanted a portable radio or use it yourself—take it anywhere, it plays everywhere. Equipped with both a ferrite antenna and detachable telescoping antenna to assure outstanding reception. In addition to its own built-in speaker the radio is supplied with an earphone for private listening. Small enough to fit in the palm of your hand it measures a mere 4x2 1/2x1 1/4". Complete with earphone, telescoping antenna, carrying case and battery. Shpg. wt., 1 lb. Imported. FS-117L Net 5.55 BA-2 Replacement Battery. Shpg. wt., 3 oz. Net .39

LAFAYETTE *Scoops* THE INDUSTRY WITH THESE SIZZLING RADIO *Values!*



LAFAYETTE 3-BAND 10-TRANSISTOR PORTABLE RADIO

Shortwave, Marine, Standard AM Broadcast Bands

ONLY **36⁹⁵**
NO MONEY DOWN

Uses 10 TRANSISTORS
1 DIODE PLUS A
THERMISTOR
FOR CLEAR
HI-FREQUENCY RECEPTION
PLAYS UP TO 400 HOURS

- Three Bands: Short Wave (4-12Mc), Standard AM Broadcast and Marine (1.3-3.8 MC) • AGC Prevents "Directional Fadeout" • True-Tone 3 1/2" Heavy Duty Alnico Speaker • Automatic Volume Control—Keeps Volume Even • High Gain Ferrite Antenna plus Disappearing 30" Telescoping Whip Antenna • Tone Control—Continuously Variable • Earphone For Private Listening, Leather Case and Carrying Strap • Hi-Impact Plastic Case • Powered by 4 Inexpensive Batteries • Microphone/Phono Jack for PA Use

Ship or Shore its hard to find a better buy than this superb Lafayette 3-Band Receiver. 10 Transistor Superheterodyne circuit really pulls in stations from all over the map. Excitement is yours on the shortwave and long wave bands. Hear Europe, weather navigation, aeronautical, police, hams, and more on these most unusual and fascinating bands. Features separate oscillator stage for each band to raise sensitivity and bring in distant stations clearly; AGC transistor to prevent "directional fade-out" when radio is repositioned, Automatic Volume Control, instant 3-position band selector switch, precision tuning; high gain ferrite bar antenna for all bands and 30" telescoping whip antenna for extra pulling power on shortwave. Push-pull output stage and 3 1/2" Alnico speaker provides greater volume and full sound reproduction. Handy input jack enables receiver to be operated with crystal mike for PA or record player. Operates on 4 standard flashlight batteries up to 400 hours. High-impact plastic case resists breaking and chipping. Complete with leather case, carrying handle, earphone and batteries. FS-133M Shpg. wt., 4 lbs. Imported Net 36.95
Replacement Batteries (4 required). BA-156

Net ea. .13

NEW! "GREAT-8" DELUXE PORTABLE RADIO

More Pulling Power — Better Sensitivity
Clearer Reception

Big 2 3/4" Dynamic Speaker
for True Tonal Quality

- 8 Transistors, 1 Diode, 1 Thermistor
- Super-Sensitive Compact Portable
- Built-in Antenna plus Telescoping Antenna
- Complete with Leather Carrying Case with Strap, Antenna Case, Magnetic Earphone, Batteries

ONLY **15⁴⁴**



Lafayette combines compactness, power and long-distance reception to give you hours of AM listening pleasure everywhere you go. The big 2 3/4" permanent dynamic speaker offers fine tonal quality and faithfully reproduces sound of music and voices. 8 transistors, 1 thermistor and 1 diode give you power to spare. Built-in ferrite bar antenna and 5-section telescoping antenna bring in the weaker stations. Plays on 4 inexpensive penlight batteries (included). Earphone jack with earphone for private listening. Complete with leather carrying case, 4 batteries, telescoping antenna with case, and earphone. Size: 3 3/4" x 1 3/4" x 5 3/4". FS-253L Shpg. wt., 2 lbs. Imported Net 15.44
BA-155 Replacement Penlight Batteries (4 required) Net ea. .093

HEAR the Quality — HEAR the Power in LAFAYETTE

FM/AM TABLE RADIOS

NEW! LAFAYETTE "MINUETTE" FM/AM Table Radio



- 7 Tubes and 2 Diodes
- Tuned RF Stage — AFC — AVC
- 3x6" Oval Speaker — As Big As In Most TV Sets!
- "Private Listening" Earphone Jack
- 1 Watt Audio Output
- Low, Slim Appearance — Only 5 1/2" High

ONLY 5 1/2" HIGH

TOP VALUE!
24⁵⁰
NO MONEY DOWN!
EASY PAY PLAN

Get excellent reception and superb reproduction on both FM and AM from this low priced table radio. Tunes regular Broadcast Band and FM Band. Features a 3x6" oval speaker for rich, full sound. Large slide rule tuning dial is easy-to-read for accurate tuning. AFC provides drift-free reception on FM. Has built-in loopstick antenna for AM, and an integral FM antenna is provided—no unsightly external antenna is required. The built-in speaker is shut off when the external earphone (not supplied) is used for personal listening. Attractive contemporary ivory and black plastic cabinet. Tubes: 2-12DT8, 2-12BA6, 1-12BE6, 1-12V6, 1-35C5 plus 2 diodes. For 110-117 volts, 60 cps AC or DC. Size: 4 1/2" x 9" x 9" D. Shpg. wt., 9 lbs. Imported. FS-247 Net 24.50
MS-501 Earphone. Shpg. wt., 8 oz. Net .79

LAFAYETTE "TINY" 6-TRANSISTOR RADIO

SENSATIONAL PERFORMANCE
IN A SMALL PACKAGE!

PLUS DIODE AND THERMISTOR

- Vest Pocket Size — Only 4 1/2" x 2 1/2" x 1 1/4" D
- Earphone Jack Built-in For Private Listening
- Full Tone Dynamic Speaker
- Trouble-Free Printed Circuit
- Built-in Ferrite Bar Antenna
- Superheterodyne Circuit
- Economical—Uses Only One Battery



NEW LOW PRICE
9⁷⁷

Engineered and constructed with the jewel like precision of a fine watch ... true superhet trouble-free printed circuit with push-pull audio output utilizes 6 ultra modern Transistors plus a Germanium Diode and Thermistor—achieves an absolutely fantastic reception over the entire broadcast band. Requires only a single long-life 9-volt battery due to the exceptionally low battery drain. Smart black and gold case of rugged durable plastic. Soft leather carrying case with attached earphone pouch. Just 4 1/2" x 2 1/2" x 1 1/4" thick and weighs a mere 10 ounces. Includes battery carrying case and earphone for personal listening ... all at an unbelievably low price! Shpg. wt., 2 lbs. FS-243L "Tiny" 6-Transistor Radio Net 9.77
Extra Battery for FS-243L (1 required) Net .21
BA-2 Shpg. wt., 2 oz.

"Symphony"

Super-Sensitive FM/AM TABLE RADIO

- Drift-Free Automatic Frequency Control
- 6 Tubes, 3 Diodes for 10-Tube Performance
- Latest Advanced Electronic Engineering
- Ultra-Sensitive Space Age Circuitry
- 3-Gang Tuning with RF Stage on AM & FM
- Built-in Hi-Q Antenna • Provision for Extension Speaker • Balanced 300-Ohm Antenna Input Terminal
- Shielded to Meet FCC Radiation Requirements

11 Tuned Circuits for Superior Selectivity & Sensitivity



The Lafayette "Symphony" is a complete AM/FM table model radio. Incorporating features found only in more expensive units, it brings the luxury of FM reception right to your fingertips. Improved AFC Action—by capacity variable diode, locks in stations and assures drift-free operation. Automatic Volume Control softens any sudden blasts of volume and makes tuning stations of different levels a cinch. A super-sensitive AM antenna brings in stations clearly while reducing unwanted noise. An FM wire antenna assures all benefits of clear pure reception. Built-in input terminals for external 300-ohm FM antenna. The 4" PM speaker produces rich sound from low to high range to enhance your music-listening pleasure. A stylish polished plastic cabinet in distinctive black and white has an easy-to-read slide rule dial with an on-off neon indicator light. Contains 6 tubes, 1 varicap, 2 diode detectors and 1 silicon diode rectifier. An output jack on the rear of the radio permits simple plug-in connection of an extension speaker. For 110-120 volts, 60 cps AC or DC. Size: 10Wx5Dx5 1/2"H. Shpg. wt., 5 lbs. Imported. FS-221A Net 29.50

JUST COMPARE


29⁵⁰

NO MONEY DOWN

Lafayette FM/AM/CLOCK RADIO

Completely Automatic!

- Automatic Telechron Clock • Wake-to-Music Plus Alarm • Sleep-Switch; Lulls you to Sleep • 600-Watt Appliance Outlet • Electrical Safety Interlock • Shielded To FCC Requirements



39⁹⁵
NO MONEY DOWN

Priced Below Many AM only Clock Radios!

Combines a fully automatic Telechron clock with luminous hands and a superb FM/AM broadcast radio. Handy sleep-switch permits you to slowly drift-off to dreamland while the radio shuts itself off at a preset time. A buzzer alarm is included. In addition to a standard AM broadcast radio, a quality FM radio will expand your listening pleasure; has a 600-watt appliance outlet—useful to turn on the coffee pot, light, etc. Slide rule dial for easier tuning. Beautiful low boy plastic cabinet in antique white with gold trim. Tubes: 50C5, 12AU6, 12AL5, 12BA6, 12BE6, 17EW6 plus selenium rectifier. Size 14 1/2" x 6 1/4" x 6" D. 100-120v. 60 cy. AC only. Imported. FS-239 Shpg. wt., 8 lbs. Net 39.95

BIG SAVINGS—SELECTED SPECIALS—TOP QUALITY

NEW! 5 TUBE AM TABLE RADIO

With **BIG SET POWER** Fine, Full Tone

More for Your Money!
• Exceptionally Sensitive



More for Your Money, ONLY
8⁹⁵

- Powerful 5-Tube Circuit
- Efficient Printed Circuit Chassis
- Long Range, Hi-Q Ferrite Antenna
- Electrical Safety Interlock, UL Power Cord • Exceptionally Sensitive

Double your listening pleasure by adding this as a "second" set in your home. Gives big set performance. Dependable built-in Hi-Q Ferrite antenna provides exceptional reception even in difficult reception areas. A 3 1/2" permanent dynamic speaker produces rich, full room tone. Sensitive direct drive tuning dial makes it easy to tune in your favorite AM programs. Convenient on/off volume control. Attractive impact case will not

chip, crack or fade under normal conditions. Back completely enclosed with addition of safety interlock to prevent shock hazard. Convenient size — contemporary design. Tubes: 12BE6, 12BA6, 12AV6, 50C5, 35W4. Measures only 8Wx4 1/2Hx3 1/2"D. For 105-120 volts AC or DC. Shpg. wt., 2 1/2 lbs. Imported.

FS-254 Net 8.95

NEW 7-TRANSISTOR EXECUTIVE

DESK RADIO



- It's a 7-Transistor Radio!
- It's a Cigarette Box!
- It's a Pen Holder!
- Handsome Black Case with Gold Trim!
- Perfect Gift For The Man On The Way Up!

Now a Three-in-one desk set. A powerful 7-transistor AM broadcast radio specially designed to harmonize with the entire unit. Radio operates on four economical penlight cells to give long dependable service. The dial face is tilted and tuning knobs top mounted for maximum legibility and accessibility. Includes Earphone too for private listening! Right hand portion holds an extra large compartment useful for cigarettes or paper clips, etc. Two convenient penholders complete the set (Pens are not included). Beautiful black and gold finish make a most attractive addition to a desk. The ideal gift. Complete with 4 penlight cells and earphone. Size: 11 1/4Wx2 1/4Hx6"D. For 105-120 volts AC or DC. Shpg. wt., 6 lbs.

FS-238L Shpg. wt., 6 lbs. Net 19.50
Extra penlight batteries, 4 required. BA-155 Net ea. .095; 2 for .19

19⁵⁰

SUB-MINIATURE 4-TRANSISTOR HEARING AID

ONLY 2 1/2" LONG x 1 1/4" WIDE x 3/8" THICK

- Lightweight—Weighs Less than 2 oz. Including Battery
- Small Enough To Be Carried in Breastpocket
- Utilizes Economical Penlight Battery
- Unique Telephone Switch Allows Telephone Conversation
- Latest Electro-Magnetic Earphone and Miniature Crystal Microphone

Features an extremely advanced circuit with 4 transistors, a high performance crystal microphone. 3 ft. thin plug-in colorless flexible cord and a unique magnetic earphone providing the clearest reception and sound reproduction yet achieved. Supplied with leather carrying case, earphone and battery. Shpg. wt., 1 lb. Imported.

F-480L Net 22.50
BA-153 Extra Battery (1 required) Burgess NE type. Shpg. wt., 3 oz. Net .08
F-567 Extra Plug-In Cord For F-480 Net .55
F-568 Extra Earphone For F-480 Net 1.59

with Battery
22⁵⁰
NO MONEY DOWN



ULTRA-MINIATURE 3 TRANSISTOR HEARING AID

29⁵⁰

with Battery

- Extremely Light in Weight - Less Than Once Ounce
- Operates From Long-Lasting Mercury Cell
- Extremely Compact, Dimensions: 2 3/8" Long, 3/4" Wide and 3/16" Thick
- Uses Inexpensive, Long Lasting Mercury Cell

Imagine — a powerful 3 transistor hearing aid weighing less than a single ounce (ready to operate with battery) and measuring 2 3/8" long, 3/4" wide, 3/16" thick. Extended research with ultra-miniature, reliable components has permitted so small a device to evolve. This hearing aid could almost be mistaken for a large tie clasp. A compact package, indeed, but a high performer as well, this instrument provides more than adequate volume for any user. Fidelity is of the highest, with excellent high and low frequency tone response. This unit is the ideal replacement for other hearing devices, even those so called small and "miniature" in size.

Dependable 3 transistor circuit derives its power from a tiny mercury cell, known for its extended life. The cell, an inexpensive type (see listing below) is replaceable in seconds without tools. Amplifier case is of

sturdy metal finished in gleaming gold. A hold-down spring clip keeps hearing aid in place. Comes complete with 3 feet of flesh-tinted cord with plugs at both ends and special flesh-tinted earpiece.

Unit is turned on by rotating volume control, which is adjustable over 180° of rotation to provide exactly the amount of amplification necessary. A flick of the MIC-TEL lever readjusts sensitivity for telephone use. After periods of extended use this instrument still supplies undiminished output of the highest quality. Supplied with velvet lined leather carrying case, earpiece, mercury cell and instructions. Shpg. wt., 1 lb.

F-750L Net 29.50

EXTRA BATTERY FOR ABOVE
BA-523 Mallory RM 625R 1.35 volt mercury cell... Net .30

2 3/8" Long
3/4" Wide
3/16" Thick




LAFAYETTE FM RADIO

FEATURES QUALITY

5 TUBE CIRCUITRY WITH AFC

- Automatic Frequency Control
- Locks In Stations
- Full 4" Speaker
- Rugged Printed Circuit

WAS
21.50



NEW LOW,
LOW PRICE!

14⁹⁵

Here's the perfect FM radio for your bedroom, kitchen, office or anywhere you want the music that only FM can provide. Outstanding performance and quality for an FM radio of this size and low price. Specially designed 5 tube circuit together with a high quality 4 inch Alnico magnet speaker provides clear, undistorted reception. Automatic Frequency Control locks in the station and prevents drift while an AFC defeat switch permits tuning weak stations adjacent to strong stations. Front panel contains a pilot light, station selector (covers 88-108mc) and velvet smooth On-Off volume control. Rugged printed circuitry will provide years of trouble-free use. Supplied with antenna. Attractive modern two-tone cabinet is an asset to any decor. For 117V 60 cycle operation. Size: 5 1/2Hx9 1/4Wx4 1/2"D. Covers full FM band from 88 mc to 108 mc. Shpg. wt., 6 lbs.

FS-236 Net 14.95

LAFAYETTE PURCHASES MANUFACTURER'S ENTIRE STOCK OF FAMOUS GONSET MODEL 3311 FM CAR CONVERTERS

Save Over 55%!

Below Regular Distributor's Cost! Lafayette's
LOW, LOW SENSATIONAL PRICE



SOLD FOR \$79.50
NOW ONLY 34⁹⁵

- 7 TUBES • DRIFT-FREE RECEPTION
- AFC TO INSURE PERFECT STABILITY
- QUICK, UNDER - DASH INSTALLATION
- ADD HI-FI TO YOUR PRESENT CAR RADIO

Get added pleasure from your auto radio listening with the GONSET FM Converter. Now you can enjoy fine music in full high fidelity while driving. This FM tuner gives drift-free reception and eliminates "drop-out" from high tension lines and similar interference. Features include: High sensitivity (3.5 μ v for 20 db quieting), high image rejection, AFC to insure perfect stability, accurately calibrated illuminated slide rule dial and instantaneous warmup. Front panel switch selects AM or FM instantly. Tube complement: 2-12CE8, 3-12E26, 1-12A5, 1-12AD6. Complete with mounting bracket and fused cord. Easily installed in minutes. For 12-volt negative ground operation only. Shpg. wt., 5 1/4 lbs.

SP-281 Net 34.95
AA-41 FM Halo Antenna for Gonset 3311 Net 4.95

MUSICAL-AIRE SOUND SYSTEM

A Record Seller at 39.95

NOW **34⁹⁵**

- Fits Air Conditioning and Forced Air Heating Ducts
- Easily Installed
- Every Register Acts as a Speaker
- Costs Far Less Than Complicated Speaker Systems



Musical-Aire, a home sound system devised for use in forced air central heating and air conditioning systems. Transforms every register throughout the home to a speaker. Little time required for installation. No marring or breaking of wall required. Converts to any musical sound-producing mechanism: radio, TV, phono-

graph, etc. Unit is equipped with special baffling and antichatter materials. Use 2 units in both hot air and cold air return for a "stereo" effect. Specs: Speaker range from 55 to 12,000 cps. Resonance of voice coil at 120 cps. Size 6x9". Shpg. wt., 5 lbs., 9 oz.

PA-397 Net 34.95

NEW! LAFAYETTE

teleSpan TRANSISTORIZED
CITIZENS BAND

2 way
RADIO
COMMUNICATION



2
FOR
21⁹⁵

NO MONEY DOWN

11⁹⁵
Each

- No License, Test or Age Limit
- Superregen Receiver, Xtal Controlled Transmitter
- Weighs only 8 oz. with battery and case
- Carrying Case, Earphone, Battery included
- Perfect for Scouting, Camping, Hiking, Fishing Trips
- Keeps the "group" in Contact
- Effective over 400 yds.—and more under favorable conditions

A compact, portable, low cost transceiver set with truly amazing performance. Simple enough for a child to operate—it requires no licenses or tests of any kind under Federal law. Perfect for camping, sports, etc. Rugged 2 transistor circuit features a powerful super-regenerative receiver with plug-in earphone for private listening. Will receive and transmit up to 1/4 mile under average conditions. Fingertip push-to-talk switch provides instant X-tal controlled transmitter operation. Durable printed circuit and 9-volt battery shock mounted, assure reliable operation. A removable telescoping antenna can be carried separately in the carrying case pouch when not being used. On-off switch is only other control. Complete with carrying case, earphones, antennas and 1.9V. battery Size: 5 1/4Hx2 1/4Wx1 1/4"D. Shpg. wt., 3 lbs.

NE-37L Set of 2 Walkie-Talkies Net 21.95
NE-38L 1 Walkie-Talkie Net 11.95
BA-2 Extra batteries for above Net ea. .21



Weights only 8 oz.
with battery and case!

LAFAYETTE 50-WATT STEREO AMPLIFIER MODEL LA-250A

99⁵⁰

NO MONEY DOWN

MADE IN U.S.A.

... Impressive Performance
... Handsome Styling
... Another Unbeatable Lafayette VALUE!

"Let Your Own Ears be the Judge"

ENGINEERED FOR SUPREMACY

ASSURANCE OF COMPONENT QUALITY
ONE YEAR PARTS GUARANTEE
All components in this unit are conservatively engineered to operate well within their performance capabilities. As assurance of this quality, Lafayette guarantees all parts including tubes for one year.

CLUTCH-TYPE VOLUME-BALANCE CONTROL—Provides precise effective means of controlling volume and balancing stereo channels.



DUAL PREAMPLIFIER SECTION—Inputs have been provided for every stereo-monaural function.



- 50 WATTS MONAURAL — 25 WATTS EACH STEREO CHANNEL
- RESPONSE 15-40,000 CPS ± .5 DB (at normal listening level)
- UNIQUE "BLEND" CONTROL
- PREMIUM EL86 OUTPUT TUBES
- SEPARATE BASS & TREBLE CONTROLS
- CLUTCH-TYPE VOLUME-BALANCE CONTROL
- 3rd CHANNEL OUTPUT

breath-taking performance at a price only LAFAYETTE can offer.

The Stereo 250A... a completely new stereo high fidelity amplifier with a high quality of reproduction, remarkable versatility and new distinctive styling—worthy of a place in the finest stereo hi-fi music system. A full range of controls enables you to enjoy the utmost in listening pleasure in any situation. A unique "blend" control which provides continuously variable channel separation—from full monaural to full stereo—may be used to eliminate the exaggerated channel separation found in some stereo source material. Included is a clutch-type Volume Balance control for independent or simultaneous control of both channels, concentric Bass and Treble controls which provide independent tonal control of each channel and a 4-position switch which selects phono, tuner, auxiliary or tape head stereo inputs. Simple slide switches provide channel reversal and phase reversal—or you can reproduce either channel through both amplifiers. A loudness switch permits the volume balance control to function as a compensated loudness control. The LA-250A also features a 3rd channel output which may be used to feed a 3rd single channel amplifier and speaker to provide a wider sound spread, a Tape Output jack for recording purposes, plus dual terminations for 4, 8 or 16 ohm speakers. Advanced circuitry includes DC operated preamp and tone control tube filaments for hum-free operation, 6CW5/EL86 push-pull output tubes, individual bias and balance adjustments on each channel and a hum balance control.


SPECIFICATIONS:
POWER OUTPUT & DISTORTION: 50 watts—25 per channel ± 1 db at less than 1% Total Harmonic Distortion at 1 KC. Less than 0.25% Total Harmonic Distortion at 1 KC at normal listening level (1 watt); less than 0.5% 1M distortion at normal listening level. FREQUENCY RESPONSE: 15-40,000 cps ± 0.5 db at normal listening level. HUM & NOISE: 70 db below rated output at max. volume (high level inputs). SENSITIVITY: For full output high level inputs 0.5V; Mag. Phono 3.5 MV at 1 KC. CHANNEL SEPARATION: Greater than 55 db at 1 KC; greater than 45 db from 20-20,000 cps. IMPEDANCE: 4, 8 and 16 ohms per channel. POWER: 200 watts; 110-125V AC 50-60 cycles.
Attractive beige vinyl laminated steel case. Handsomely designed three color brass etched front panel. Sienna brown molded legs and matching knobs with polished brass inserts. Dimensions with legs and knobs, 14½Wx12¼Dx5½H. Shpg. wt., 28 lbs. LA-250AWX Net 99.50

GENERAL ELECTRIC Model MA-2G STEREO MULTIPLEX ADAPTER

Regular 28.86

Effective Thru October 15, 1962

1895



This adaptor is designed to operate in conjunction with FM tuners to provide two stereophonic audio channels. Completely self-contained and self-powered, the only required connections are those to the separate inputs of the stereo tuner. Frequency response: ± 3db 50 to 15,000 cycles. Hum and noise down 60 db. Mounting base is 10Lx2¼"W, with mounting holes spaced 2¼". 9G-33E Shpg. wt., 3 lbs. Net 18.95

SHERWOOD S-3000 IV FM MULTIPLEX TUNER



160.00

NO MONEY DOWN

The front end of this tuner boasts high sensitivity and wideband selectivity. IF amplifiers, limiters, and discriminator have controlled frequency and phase response—essentially flat to 75kc. The 19 Kc pilot carrier and 67Kc secondary sub-channel transmissions are filtered out by razor sharp networks. Also featured are FM interchannel hush; smooth, balanced fly-wheel tuning knob; "acro-beam" tuning eye and a 7" expanded FM dial scale. Response 20-15,000 cps ± 0.5 db. OTHER SPECIFICATIONS: Typical sensitivity 0.95 µv @ 20 db quieting; IHFM sensitivity 1.8 µv; selectivity 225 Kc @ -3db; FM discriminator 850 Kc peak to peak. Size: 4x14x10½". For operation from 110-120V. 50-60 cycle AC. Shpg. wt., 15 lbs. G-383WX Less Enclosure Net 160.00 G-289W Brown Flextone Cases Shpg. wt., 6 lbs. Net 7.50 G-290W Black Flextone Cases Shpg. wt., 6 lbs. Net 7.50

THE FISHER 500-B

65 WATT FM MULTIPLEX STEREO RECEIVER

359.50

NO MONEY DOWN




The new 500-B receiver has 18 controls and switches for flexible control of its wideband FM multiplex tuner; dual channel preamplifier and dual channel 65 watt power amplifier. FM circuit has 4 IF stages, advanced multiplex design, special switchable noise filter and "Stereo Beam" tuning indicator. SPECIFICATIONS: Amplifier distortion less than 0.5%. Overall frequency response 25-25,000 cps ± 1.5 db; FM sensitivity 0.7 µv into 72 ohm load; IHFM sensitivity 2.2 µv; signal/noise & hum 70 db. IF bandwidth 190 Kc; channel selectivity 52 db; FM response (after deemphasis) 30-15,000 cps. Size: 17½x5¼x12¼" deep. G-403WX Less Cabinet. Shpg. wt., 35 lbs. Net 359.50 FISHER 30-U Oiled Walnut Cabinet for 500-B G-404W Shpg. wt., 6 lbs. Net 24.95

harman kardon

AWARD TA5000X 50 WATT AM/FM STEREO RECEIVER

299.95

NO MONEY DOWN



A complete stereo control center consisting of a sensitive, distortion-free AM/FM Tuner with built-in FM multiplex facilities, 50-watt stereo amplifier (25-watts each channel) plus a versatile stereo amplifier. The TA-5000X features a full range of controls for every stereo function including separate Bass and Treble controls for each channel plus Blend, Balance, Loudness and Function controls. Slide switches provide for Stereo Reverse, Equalization, Contour plus Hi-cut and Lo-cut filters. Size: 16Wx10¼Hx13½"D. Shpg. wt., 40 lbs. G-656WX Net 299.95 G-657WX CX-80 Metal Case. Shpg. wt., 5 lbs. Net 12.95 G-658W WW-80 Walnut Case. Shpg. wt., 5 lbs. Net 29.95

McIntosh MODEL MX110 STEREO FM TUNER PREAMPLIFIER



374.50

NO MONEY DOWN

The MX110 combines in one unit an extremely low-distortion preamplifier with a highly sensitive FM multiplex stereo tuner. IF amplifiers use transformers for maximum adjacent channel rejection. Outputs: Main & L+R, 3 volts; Tape, 0.3 volt. Frequency Response: ± 0.5 db 20-20,000 cps. Distortion: Less than 0.2% @ rated output. Hum and Noise —80 db. Tuner Sensitivity: Better than 2.5 µv @ 100% modulation. IF Bandwidth: 200 KC flat top. Front Panel Controls: Volume; 6-Position Input Selector; 8-Position Mode Selector; L & R Bass; L & R Treble; Muting; LF & HF Filters; Balance; Loudness; Tape Monitor; Phase; 16 Tubes, 12 Diodes, 4 Selenium Rectifiers. For 105-125 volts, 50-60 cps AC. 3 AC outlets. Front panel finished in anodized gold and black. Size: 16½Wx5¼Hx12¾"D. Shpg. wt., 30 lbs. G-343WX Less Cabinet Net 374.50 G-178WX Oiled Walnut Cabinet Net 25.00

MARANTZ MODEL 8B DUAL 35-WATT STEREO POWER AMPLIFIER



249.00

NO MONEY DOWN

A professional instrument in every respect. Built-in test meters and bias adjustment assure optimum performance. 35 watts Power output per channel (70-watts peak) "Ultra Linear" operation, 18-watts of triode operation possible by altering 2 connections. Response 0.1 db from 20-20,000 cps at 35 watts. Distortion: harmonic, less than 0.1%, IM, less than 0.5%. Hum: — 90 db. Input sensitivity 1.3V Heavy duty components throughout. Output impedance: 4, 8 and 16 ohms. Tubes: 2-6BH6, 2-6CH7, 4-EL34/6CA7. Overall size: 13½Wx7¼Hx10½"D. For 117V, 60 cps. AC. Shpg. wt., 57 lbs. G-259WX Marantz Model 8B less cabinet Net 249.00 Model 8G Gold Finish Perforated Snap-on Grille for above. G-257W Shpg. wt., 1 lb. Net 9.00

MODEL 299C 72 WATT STEREO AMPLIFIER



224.95

NO MONEY DOWN

A superb unit designed to accommodate every existing signal source. Uses aluminum chassis and D.C. heated preamp filaments for low hum. Specifications: 36 watts per channel; frequency response ± 1db 20-20,000 CPS; harmonic distortion, 0.8% at full output; IM distortion (CCIF), 0.3%; hum and noise 80db. Also features front panel stereo headphone output, derived center channel level control, loudness, tape monitor switch, two low level magnetic inputs for connection of a stereo tape deck. 6 inputs and scratch and rumble filters. Dimensions in accessory case: 15½Wx5¼Hx13¼"D. Shpg. wt., 28 lbs. G-635WX (less case) Net 224.95 Leather finish steel case for above. Net 13.95 G-147W Net 13.95

H.H. SCOTT NEW! 350B FM MULTIPLEX STEREO TUNER



219.95

NO MONEY DOWN

The new 350B wide-band tuner was designed especially for superior multiplex reception. Incorporates a special Sonic-Monitor that tells you audibly when multiplex is being received. Other front panel accessories include a professional quality signal strength meter and a vernier tuning mechanism for effortless, pinpoint tuning. Special non-magnetic chassis assures high sensitivity, low hum. Specifications: IHFM sensitivity, 2.2 µv; signal/noise ratio is 60 db; harmonic distortion is 0.8%; frequency response—30 to 15,000 cps. Handy front panel stereo tape output. Dimensions: 15Wx4¾Hx11"D. Patent Pending. G-646WX Shpg. wt., 19 lbs. Net 219.95 G-147WX Leatherette Covered Case Net 13.95

The Smart Way to Buy Hi-Fi!


LAFAYETTE'S MOST POPULAR STEREO PHONO SYSTEM

A COMPLETE STEREO SYSTEM BASED ON THE SUPERB LA-250A


breathaking performance at a price only LAFAYETTE can offer.

FREE!

ESL DUST BUG, Stylus Pressure Gauge, 20 ft. Speaker connecting cable, all necessary connectors, and interconnecting instructions with purchase of any Hi-Fi System listed on this page.



CHOICE OF STEREO CARTRIDGE



Pickering U38/AT

Empire 880


Shure M3D

"LISTEN AT HOME GUARANTEE"

Prove to yourself in your own living room, that the hi-fi system you select sounds as good at home as it does in our showroom.

LISTEN at HOME and BE SURE!

With Lafayette's Famous 30 Day FREE Trial if not completely satisfied with your purchase once you get it home, you can return it within 30 days and get your Full Purchase Price returned to you, less only transportation charges.



(OPTIONAL)
2 LAFAYETTE ELIPTOFLEX SERIES BOOKSHELF ENCLOSURES



ALTERNATES

LAFAYETTE WOOD CHANGER BASE




2 LAFAYETTE THINLINE SK-240 SYSTEMS

GLASER-STEERS GS-77T



ALTERNATE SPEAKERS



2 LAFAYETTE SK-210 12" 3-WAY SPEAKERS


LAFAYETTE SK-180 "TRIHELIX" 10" SPEAKERS



LAFAYETTE LA-250A 50-WATT STEREO AMPLIFIER



GARRARD AT6 4-Speed Record Changer



2 LAFAYETTE SK-58 FREE EDGE 12" COAXIAL SPEAKERS

MATCHED COMPONENTS

- Lafayette LA-250A 50-Watt Stereo Amplifier 99.50
- Garrard AT6 4-Speed Record Changer 54.50
- Lafayette Wood Changer Base 3.95
- Pickering U38/AT Diamond Needle Stereo Cartridge 46.50
- 2-Lafayette SK-58 Famous Free-Edge 12" Coaxial Speakers @ 29.50 Ea. 59.00

REGULAR CATALOG PRICE ~~263.45~~

LAFAYETTE SYSTEM PRICE

You Save **63⁹⁵** **199⁵⁰**
NO MONEY DOWN

LAFAYETTE MATCHED STEREOPHONIC SYSTEMS

*Make Certain to Indicate your Choice of Either Pickering U38/AT, Shure M3D, or Empire 880 Cartridge.

System No.	Amplifier	Changer	Cart. *	Base	Speaker	2 ea. Speaker Cabinet**	Shpg. Wt.	Net
LS-285WXM	LA-250A	AT6	Choice of Pickering U38/AT or Shure M3D or Empire 880	† 2 ea. SK-58	—	—	67 lbs.	199.50
LS-286WXM	LA-250A	GS-77T		† 2 ea. SK-58	—	—	—	67 lbs.
LS-287WXM	LA-250A	AT6	Choice of Pickering U38/AT or Shure M3D or Empire 880	† 2 ea. SK-58	2 ea. ELIPTOFLEX	143 lbs.	265.50	
LS-288WXM	LA-250A	GS-77T		† 2 ea. SK-58	2 ea. ELIPTOFLEX	143 lbs.	265.50	
LS-289WXM	LA-250A	AT6	Choice of Pickering U38/AT or Shure M3D or Empire 880	† 2 ea. SK-180	—	67 lbs.	203.50	
LS-290WXM	LA-250A	GS-77T		† 2 ea. SK-180	—	—	67 lbs.	203.50
LS-291WXM	LA-250A	AT6	Choice of Pickering U38/AT or Shure M3D or Empire 880	† 2 ea. SK-180	2 ea. ELIPTOFLEX	143 lbs.	269.50	
LS-292WXM	LA-250A	GS-77T		† 2 ea. SK-180	2 ea. ELIPTOFLEX	143 lbs.	269.50	
LS-293WXM	LA-250A	AT6	Choice of Pickering U38/AT or Shure M3D or Empire 880	† 2 ea. SK-210	—	70 lbs.	233.50	
LS-294WXM	LA-250A	GS-77T		† 2 ea. SK-210	—	—	70 lbs.	233.50
LS-295WXM	LA-250A	AT6	Choice of Pickering U38/AT or Shure M3D or Empire 880	† 2 ea. SK-210	2 ea. ELIPTOFLEX	146 lbs.	299.50	
LS-296WXM	LA-250A	GS-77T		† 2 ea. SK-210	2 ea. ELIPTOFLEX	146 lbs.	299.50	
LS-297WXM	LA-250A	Model A	Choice of Pickering U38/AT or Shure M3D or Empire 880	† 2 ea. SK-58	—	70 lbs.	219.50	
LS-298WXM	LA-250A	AT6		† 2 ea. SK-240††	—	—	93 lbs.	264.50
LS-299WXM	LA-250A	GS-77T	Choice of Pickering U38/AT or Shure M3D or Empire 880	† 2 ea. SK-240††	—	93 lbs.	264.50	
LS-300WXM	LA-250A	Model A		† 2 ea. SK-240††	—	—	96 lbs.	284.50

†=Specify Mahogany, Walnut or Blonde base. **=Specify Mahogany, Walnut, Oiled Walnut or Blonde. GS-77T=Glaser Steers 4-Speed Record Changer. Model A=Garrard 4-Speed Automatic Turntable Changer. ††=LAFAYETTE SK-240 DELUXE THIN LINE SPEAKER SYSTEM. Oil. Wal.

NEW LAFAYETTE CRITERION HI-FI CABINETRY.... to decorate your home with music



Lafayette's Criterion Line — the standard of construction and design by which all others are judged.


The Technical Know-How of Lafayette's Audio Engineers Combined with that of America's Finest Furniture Craftsman, bring to you the new Lafayette Criterion Line of Acoustically Correct Hi-Fi Furniture.

Now your high fidelity listening area can look as good as it sounds. Add the elegance, grace and timeless styling of this decorator inspired furniture grouping to your home music center, but lose nothing in performance. Painsstaking acoustical design by Lafayette's audio engi-

neers provides the best possible relationship between equipment and furniture. The meticulous custom craftsmanship, rich, matched, natural wood veneers and custom hand-rubbed finishes of these fine cabinets are bound to please the most discerning taste.

For Full Details Of Individual Cabinets See Description on Right

THE CRITERION EQUIPMENT CABINET



Interior Dimensions each upper compartment

10" H
18 3/4" W
15 1/2" D

12 1/2" H
18 3/4" W
15 3/4" D

Interior Dimensions each lower compartment



89⁵⁰

"Component Engineered" by Lafayette's audio experts to provide ample, convenient, well-ventilated accommodations for all of your components. When matched with its companion Criterion ELIPTOFLEX speaker enclosure (described on the right) it forms a complete music center. Cabinets employ rigid tongue and groove construction of 3/4" lumber core woods throughout, with matched veneers inside as well as out. Swinging doors with brass pulls and magnetic catches. Smartly styled with tapered legs and gold side trim. Overall Dimensions: 40Wx18Dx32 1/2"H including legs. Shpg. wt., 70 lbs.

- CAB-137WX Walnut Net 89.50
- CAB-138WX Oiled Walnut Net 89.50
- CAB-139WX Mahogany Net 89.50

THE CRITERION ELIPTOFLEX SPEAKER CABINET

The same graceful styling and fine construction as the CRITERION equipment cabinet, which it matches. Designed to accommodate any 12" speaker, this enclosure incorporates the inner construction and acoustic principles of the famous Lafayette "ELIPTOFLEX" enclosure. A specially designed elliptical port with diffracting ring broadens frequency response. This results in natural smoothness and unequalled performance in the low ranges. Constructed of 3/4" lumber core woods with hand-rubbed natural wood veneers. Smartly styled with matching grille cloth, gold trim and tapered legs. Overall Dimensions: 32 1/2 H x 18 D x 16" W. Shpg. wt., 50 lbs.

59⁵⁰
NO MONEY DOWN



- CAB-140WX Walnut Net 59.50
- CAB-141WX Oiled Walnut Net 59.50
- CAB-142WX Mahogany Net 59.50

LAFAYETTE Criterion STEREO COMPONENTS

LAFAYETTE KT-600A STEREO PRE-AMPLIFIER MASTER CONTROL CENTER

MODEL KT-600A
79.50
IN EASY-TO-BUILD KIT FORM
COMPLETELY WIRED AND TESTED
LA-600A
134.50
NO MONEY DOWN!




MADE IN U.S.A.

The KT-600A represents a brilliant stereo achievement. This "no-compromise" stereo pre-amplifier and control unit offers unlimited versatility, includes every feature necessary for the finest reproduction. It has a total of 12 input jacks (6 stereo pairs) for program sources of any type and level—all of which may be selected by front panel control. Separate turnover and roll-off switches provide 24 positions of correct equalization—independent for each channel. Dual concentric stereo function selector for maximum flexibility in controlling selected program sources. A unique Bridge Control provides continuously variable channel separation from full mono to full stereo, or it can optionally be used to regulate the 3rd channel output. A clutch-operated Volume Balance Control provides independent or simultaneous level adjustment of channels. Low impedance Plate follower outputs are used, and a host of many other professional type features.

KT-600AWX Stereo Preamplifier Kit No Money Down Net 79.50
LA-600AWX Stereo Preamplifier, wired and tested No Money Down Net 134.50

SPECIFICATIONS

FREQUENCY RESPONSE: 5-40,000 cps \pm 1 db. DISTORTION: Less than 0.05% 1M at 2 volts out; Less than 0.1% Harmonic, at 2 volts out. SENSITIVITY: Low Level 2.2 mv for 1 volt out; high level 94 mv for 1 volt out; Tape Head inputs 1.8 mv for 1 volts out. HUM AND NOISE: High level inputs better than 80 db below 2.0 volts; low inputs better than 62 db below 2.0 volts. INPUT IMPEDANCES: High level—250K ohms; Mag—96K ohms; Ceramic—96K ohms in series with 68 uuf; Tape Head—470K ohms. OUTPUT IMPEDANCES: Main Outputs—1500 ohms; Tape Outputs—2700 ohms; Bridged Output—1100 ohms. TONE CONTROL RANGE: Bass \pm 15 db at 30 cps; Treble \pm 15 db at 10Kc. RUMBLE FILTER: 12 db/octave slope, down 15 db at 30 cps. SCRATCH FILTER: 12 db/octave slope, down 15 db at 15 Kc. CROSSTALK: Greater than 55 db separation between channels. AUXILIARY AC OUTLETS: 4, 1 unswitched. TUBES: 7-7025, 2-Selenium Rectifiers. POWER REQUIREMENTS: 35 Watts, 105-125 volts AC, 50/60 cycles. SIZE: 14Wx4 $\frac{1}{2}$ Hx11 $\frac{1}{2}$ D, not including projections. Shpg. wt., 16 lbs.



PATENTS APPLIED FOR ON BRIDGE AND VOLUME BALANCE CIRCUITRY.

The KT-600A Solves every Stereo-Monaural problem

- RESPONSE 5-40,000 CPS • AMAZING BRIDGE CONTROL PROVIDES VARIABLE 3rd CHANNEL OUTPUT FOR 3-SPEAKER STEREO
- HIGHLY PRECISE "NULL" BALANCING & CALIBRATION—MORE ACCURATE THAN METERS • TAPE HEAD PLAYBACK EQUALIZATION FOR NEW 4-TRACK STEREO • 4-AUXILIARY AC OUTLETS

"LABORATORY STANDARD"

IN EASY TO BUILD KIT FORM


MODEL KT-550

134.50

MODEL LA-550

184.50

COMPLETELY WIRED AND TESTED
NO MONEY DOWN



the KT-550 100-WATT BASIC STEREO AMPLIFIER KIT

- 50 Watts—per channel—100 watts for monophonic use. Frequency response from 2-100,000 cps. \pm 0, \pm 1 db at 1 watt • Unmeasurable Distortion • Hum and Noise Better Than 90 db Below 50 watts • Multitap Feedback Loop Design (over 50 db) Lower Distortion Without Sacrificing Stability • Metered Control Panel With O.C. Bias and AC Balance Potentiometer • High Power 7027A Output Tubes • Massive Grain oriented steel transformers.

TECHNICAL SPECIFICATIONS

Power Output: 50-watts per channel continuous RMS from 20-20,000 cps; 100-watts monophonic operation. Total Harmonic Distortion: Less than 15% at 1,000 cycles at 50 watts each channel, 0.75% from 20-20,000 cps at 50 watts each channel. Intermodulation Distortion: Less than 0.5% at 50-watts equivalent sine wave power, 60 & 7,000 cps 4:1 ratio, 0.15% at 10-watts equivalent sine wave. Frequency Response: 14-45,000 cps, 0 \pm 1 db at 50-watts; 2-100,000 cps, \pm 0 \pm 1 db at 1 watt. Sensitivity: 1.0 volt RMS input for 50-watts output. Damping Factor: 15 at 1 kc—16 ohms. Feedback: Over 50db in six multiple loops. Hum and Noise: Better than 90 db below 50-watts. Output Impedance: 4, 8 and 16-ohms. Convenience Outlet: Single A.C. convenience outlet. Fuse: Externally accessible fuse. Controls: 4 Bias Controls, 2 AC Balance Controls, Meter Selector Switch and Power On/Off Switch. Tube Complement: (Total of 10) 4-7027A, 4-6CL6, 2-6BR8A plus 5 Silicon Diodes. Power Consumption: 350-watts.

Lafayette introduces the KT-550 "Laboratory Standard" Dual 50-watt Stereo Amplifier Kit—the finest instrument possible to design and produce regardless of price. Advanced engineering concepts in audio design were used to achieve flawless performance at an output of up to 50 watts per channel for stereo operation or 100 watts combined for monaural. The sound reproducing capabilities of the KT-550 are in excess of the audible range \pm 0, \pm 1 db from 2 to 100,000 cps without evidence of ringing or instability. Perfect for low efficiency speaker systems. "Multiple loop" feedback design achieves very low distortion and high stability, with an absence of listening fatigue. Highest quality components were used throughout such as special massively designed output transformers, telephone grade electrolytics, and Corning deposited metal film glass case resistors. The 7027A output tubes are conservatively rated in the KT-550 to insure long life at lowest distortion levels. A well regulated power supply employing 4 silicon diode rectifiers is used. Engineered for the kit builder, two printed circuit boards virtually eliminate any possibility of error. Lafayette's famous step-by-step instruction manuals plus large pictorials provide ease of assembly equal to factory built units. Handsomely finished in contrasting brown and beige; control panel finished in brass. Complete with cover. Size: 17Wx12 $\frac{1}{2}$ Dx8 $\frac{1}{2}$ H. 105-120 V. AC 50-60 cycles. Shpg. wt., 60 lbs.

KT-550WX No Money Down Net 134.50
Dual 50-watt stereo amplifier as above wired and tested. LA-550WX No Money Down Net 184.50

AUDIO

"The published specifications for the '550' are unusually fine, well up amongst the top quality amplifiers available. This amplifier met every one of its published specifications.

"In view of the excellent performance and easy construction, we would recommend this amplifier to any audiophile."

high fidelity

"The listening quality of the '550' was superb. It has proven to be an amplifier capable of performing well under the most exacting applications and suitable for use in the finest of music-reproducing systems. United States Testing Company feels the '550' not only is an exceptionally good value, but is one of the finest amplifiers it has seen."

ELECTRONICS WORLD


"One of the best hi-fi amplifiers on the market. "From the test results obtained, we would rate this amplifier along with the very best in the field. It will provide excellent hi-fi performance whose quality would be limited only by that obtained from the other components in the system."

NOW YOU CAN AFFORD The Very Finest LAFAYETTE BUILD-IT-YOURSELF PROFESSIONAL 100-WATT STEREO SYSTEM



MATCHED COMPONENTS		
Lafayette KT-600A Stereo Preamplifier Kit		79.50
Lafayette KT-550 Dual 50-Watt Basic Stereo Amplifier Kit (with enclosure)		134.50
2 Lafayette SK-215 15" 3-Way Speakers @ 64.50 each		129.00
Garrard Model A Record Changer (less base)		79.50
Base for Model A Changer (Specify Finish)		3.95
Pickering U38/AT Diamond Needle Stereo Cartridge		46.50
Regular Catalog Price		472.95

LAFAYETTE KIT SYSTEM PRICE
414.50
NO MONEY DOWN
YOU SAVE 58.45



LAFAYETTE 100-WATT EXPERTLY MATCHED DELUXE STEREO KIT SYSTEMS

*Be sure to specify Pickering U38/AT, Shure M30 or Empire 880 Diamond Needle Cartridge.

System	Amp. Kit	Preamp Kit	Garrard Changer	Cartridge*	Changer Base	Tuner	Speaker	Speaker Cabinet Kit	Shpg. Wt., lbs.	Net
LSK-559WXM	KT-550	KT-600A	Model A	Choice of Pickering U38/AT, Shure M30 or Empire 880	Laff	—	2 SK-215	—	175	414.50
LSK-560WXM	KT-550	KT-600A	Model A		Laff	—	2 SK-210	2 CK-10	283	469.50
LSK-561WXM	KT-550	KT-600A	Model A		Laff	—	2 SK-210	—	135	369.95
LSK-562WXM	KT-550	KT-600A	Model A		Laff	—	2 SK-210	2 CK-34	183	416.75
LSK-563WXM	KT-550	KT-600A	Model A		Laff	LT-700	2 SK-215	—	193	519.50
LSK-564WXM	KT-550	KT-600A	Model A		Laff	LT-700	2 SK-215	2 CK-10	301	575.00
LSK-565WXM	KT-550	KT-600A	Model A		Laff	LT-700	2 SK-210	—	153	479.50
LSK-566WXM	KT-550	KT-600A	Model A		Laff	LT-700	2 SK-210	2 CK-34	201	524.50

*Specify Mahogany, Walnut or Blonde.

FREE

with purchase of any Hi-Fi Stereo Kit System above! ESL Dust Bug, Stylus Pressure Gauge, 20' Speaker Cable, Connectors and Clear Inter-connecting Instructions.



PAGE 8 LAFAYETTE RADIO ELECTRONICS

YOUR ORDER IS SHIPPED AT THE CURRENT PRICE SO YOU BENEFIT FROM ANY PRICE REDUCTION

THE OUTSTANDING

"Stereo 250A" KIT



ASSURANCE OF COMPONENT QUALITY
ONE YEAR PARTS GUARANTEE

All components in this unit are conservatively engineered to operate well within their performance capabilities. As assurance of this quality, Lafayette guarantees all parts including tubes for one year.

50-WATT INTEGRATED STEREO AMPLIFIER KIT

- DC applied to all preamplifier and tone control tube heaters for hum-free operation • RIAA equalization on phono inputs • NARTB tape equalization on tape head inputs • Individual bias and balance controls • Hum balance Control • Excellent DC power supply regulation provided by silicon diodes • Total of 9 tubes, plus 3 silicon diodes—uses premium 6CW5/EL86 output tubes.

Made in U.S.A.

IN EASY-TO-BUILD KIT FORM
74.50
NO MONEY DOWN

SPECIFICATIONS

POWER OUTPUT: 50 watts (100 watts peak) 25 watts per channel ± 1 db. DISTORTION: Total Harmonic Distortion ± 1 db at less than 1% at 1KC at normal listening level (1 watt); I.M. Distortion less than 0.5% at normal listening level. FREQUENCY RESPONSE: 15-40,000 cps ± 0.5 db at normal listening level, 20-50,000 cps ± 1 db at rated output. HUM & NOISE: Zero volume hum 77 db below rated output; max volume hum high level inputs 70 db below rated output; Mag. phono inputs 50 db below rated output. Sensitivity: For full output high level inputs 0.5V; Mag. phono 3.5 MV at 1KC. CHANNEL SEPARATION: Greater than 55 db at 1KC; greater than 45 db from 20-20,000 cps. SPEAKER AUXILIARY OUTPUT: 1 switched. TUBE COMPLEMENT: 4-6CW5/EL86, 2-7199, 3-12AX7, 3 Silicon diodes. IMPEDANCE: 4, 8 and 16 ohms per channel. POWER: 200 watts; 110-125V AC 50-60 cps. Net 74.50

THE new Lafayette KT-250A offers remarkable versatility, high quality of reproduction and new distinctive styling in one convenient low-cost unit. Designed and engineered for ease of assembly, the KT-250A is a fine stereo preamplifier and 50-watt stereo amplifier combined — with all the controls and features to enable you to enjoy the utmost in listening pleasure in any situation. Whether you use it as a stereo amplifier delivering 25 watts per channel or as a powerful 50 watt monophonic amplifier, you are assured of true high fidelity reproduction — free from hum, noise and distortion.

DELUXE FEATURES

- Unique Separation Control—A new stereo control which provides continuously variable channel separation—from full monophonic to full stereo. Lets you select the amount of separation you want.
- Clutch-Operated Volume Balance Control—Gives you a choice of independent or simultaneous control of both channels—you can use it as a master volume control without disturbing previously selected settings on each channel.
- Independent Tone Controls—Independent Bass and Treble adjustment for each channel. Concentric mounting for convenience—inner knob controls one channel, outer the other channel.
- Mode Switching—Two slide switches provide Normal Stereo—Reverse Channel—Mon A (Channel A reproduced through both channels)—Mon B (Channel B reproduced through both channels).
- Input Selector—4-position switch lets you select instantly any one of your connected monophonic or stereo sources—special non-shorting arrangement on one position permits recording and playback using a permanently connected tape recorder.

Loudness Switch—Provides the frequency response changes required by the ear at low listening levels and permits the Volume-Balance control to function as a compensated loudness control.

Phase Switch—Reverses the phase of one channel electrically—corrects for speakers connected out of phase or for reversed phase recordings sometimes found commercially.

3 Pairs of High Level Inputs—For connection of Crystal or Ceramic phono. Tuner, and auxiliary equipment.

2 Pairs of High Level Inputs—For connection of magnetic phono and Tape Head.

Main Speaker Outputs—Dual 4, 8 and 16 ohm terminals may be paralleled for 4 or 8 ohm operation at 50 watts.

Tape Output—Provides an output for Tape recording—unaffected by Volume and Tone Controls.

Bridged Output—A monophonic blend of both channels which can be fed to a third single channel power amplifier and speaker for a greater sound spread in stereo. May also be used for listening in another room.



NO TECHNICAL SKILL REQUIRED

Designed for ease of construction, the KT-250A can be assembled in a minimum of time. Assembly manual contains detailed step-by-step instructions... guides you every step of the way. Large full-scale pictorials show you where every wire and component goes.



Made in U.S.A.

NO MONEY DOWN

59.50

Lafayette 36-watt stereo amplifier


Wide-range stereo reproduction can be yours when you build this easily constructed 36 watt stereo amplifier (18 watts each channel). The KT-236A provides all the necessary inputs—lets you connect your stereo or monophonic sources permanently, with instant selection provided by the turn of a switch. Has built-in dual preamps for low level phono inputs—RIAA equalized for flat response. It includes a unique "Blend" control which provides continuously variable channel separation from full monophonic to full stereo—you select the exact degree of separation you want. Other features are: Concentric clutch-operated Volume control for independent or simultaneous level adjustment of both channels; Dual concentric Bass and Treble controls—give you 4 independent tonal adjustments; 3-position Selector Switch—Aux-Tuner-Phono; Mode (2 Slide Switches) provide Normal Stereo, Reverse channel, Mon A and Mon B; Phase switch—makes up for reversed-phase recordings sometimes found commercially and also corrects for speakers connected out of phase.

SPECIFICATIONS: POWER OUTPUT: 36 watts—18 watts per channel ± 1 db. Institute of High Fidelity Manufacturers Rating (72 watt peak). FREQUENCY RESPONSE: 15-30,000 cps ± 1 db at normal listening levels. SENSITIVITY: For full output; High level inputs 0.5V; Mag. Phono 3 mv. DISTORTION: Harmonic, less than 0.15% at normal listening level; IM, less than .3%. HUM AND NOISE: (At full volume) High level inputs 70 db below rated output; Mag. phono 53 db below rated output. CHANNEL SEPARATION: Better than 50 db. SPEAKER OUTPUT IMPEDANCE: 8 and 16 ohms. INPUTS: (Total 8) Dual Aux, dual Tuner, dual Crystal Phono, dual Mag. Phono. OUTPUTS: (Total 4) Dual main speaker output, dual Tape Out jacks. TUBE COMPLEMENT: 4-EL84, 2-7199, 3-12AX7 plus 2 silicon diodes. Attractive beige vinyl laminated steel cabinet. Handsomely designed brass anodized aluminum front panel. Sienna brown molded legs, matching knobs with polished brass inserts. 14 1/2" wide x 11 1/2" deep x 5 3/4" high (with legs and knobs). Shpg. wt., 24 lbs. 36 watt integrated Stereo Amplifier Kit, complete with deluxe cabinet and legs, all necessary parts and detailed assembly MODEL KT-236AWX

Net 59.50


THE AMAZING "STEREO 236" KIT

A NEW LOW-COST STEREO AMPLIFIER ANYONE CAN BUILD



Easy to Build!

Anyone can build these superb Lafayette stereo kits—no special skill is needed. Assembly manuals contain clearly worded step-by-step instructions which guide you all the way. Large full-scale pictorials illustrate every stage of assembly—show you exactly where every part goes. Join the thousands who have already discovered this easy low-cost way of owning the finest audio equipment.



Deluxe Stereo Controls

- 1 3-position Selector switch
- 2 Dual concentric Bass control
- 3 Dual concentric Treble control
- 4 Concentric clutch-operated Volume control
- 5 Unique "Blend" control
- 6 Phase reverse switch
- 7 Mode switches

DO-IT-YOURSELF and SAVE with LAFAYETTE HI-FI STEREO KIT SYSTEMS

BUILD THIS 36-WATT STEREO SYSTEM KIT

COMPONENTS

Lafayette KT-236A 36-Watt Stereo Amplifier Kit	59.50
Garrard Autoslim 4-Speed Stereo Record Changer (less base)	39.50
Base for Record Changer (Specify Finish)	3.95
Pickering U38/AT Diamond Needle Stereo Cartridge	46.50
2 Lafayette SK-128 8" Ultra-Linear Bixial Speakers @ 19.50	39.00
Regular Catalog Price 188.45	

LAFAYETTE SPECIAL PRICE **139.95**
YOU SAVE 48.50 ONLY

LAFAYETTE MATCHED 36-WATT STEREO KIT SYSTEMS

- Heart of this excellent system is the easy-to-assemble KT-236A integrated stereo amplifier—A complete stereo control center plus two 18-watt amplifiers in one compact unit. Advanced design features a complete array of controls and inputs.
- Lafayette SK-128 8" Bixial Speakers provide multiple speaker performance with a full even coverage over the entire audible range.
- The renowned Garrard Autoslim or Lesa CD2/21 4-Speed Record Changer supplied with the stereo cartridge of your choice.

System	Amp. Kit	Changer	Cartridge*	Changer Base†	Speakers	Spkr. Cab.	Shpg. Wt.	Net
LSK-241WXM	KT-236A	Autoslim**	Choice of Pickering U38/AT, Shure M30 or Empire 880	Laff	2 SK-128	—	48 lbs.	139.95
LSK-242WXM	KT-236A	Lesa CD2/21		Lesat	2 SK-128	—	50 lbs.	139.95
LSK-243WXM	KT-236A	Autoslim**	Choice of Pickering U38/AT, Shure M30 or Empire 880	Laff	2 SK-128	2 Mini-Duct††	91 lbs.	184.95
LSK-244WXM	KT-236A	Lesa CD2/21		Lesat	2 SK-128	2 Mini-Duct††	93 lbs.	184.95
LSK-245WXM	KT-236A	Autoslim**	Choice of Pickering U38/AT, Shure M30 or Empire 880	Laff	2 SK-58	—	59 lbs.	159.95
LSK-246WXM	KT-236A	Lesa CD2/21		Lesat	2 SK-58	—	61 lbs.	159.95
LSK-247WXM	KT-236A	Autoslim**	Choice of Pickering U38/AT, Shure M30 or Empire 880	Laff	2 SK-58	2 CK-34‡	107 lbs.	205.50
LSK-248WXM	KT-236A	Lesa CD2/21		Lesat	2 SK-58	2 CK-34‡	109 lbs.	205.50

**Garrard Autoslim. †Specify Walnut, Mahogany or Blonde Base. ††Specify Walnut, Mahogany or Oiled Walnut. ‡Unfinished Walnut Veneers

CHOICE OF STEREO CARTRIDGE



LAFAYETTE KT-236A



GARRARD AUTOSLIM



SK-128W SPEAKERS

CHOICE OF STEREO CARTRIDGE



LAFAYETTE KT-250A



SK-58 SPEAKERS



GLASER-STEERS GS-77T

OPTIONAL



LESA CD 2/21



"MINI-DUCT" ENCLOSURES



SK-58 SPEAKERS



"ELIPTOFLEX" KITS



CK-34

FREE

ESL DUST BUG, Stylus Pressure Gauge, 20" Speaker connecting cable, all necessary connectors, and Interconnecting Instructions with purchase of any Hi-Fi System listed on this page.

Deluxe 50-WATT DO-IT-YOURSELF STEREO KIT SYSTEM

Lafayette KT-250A 50-Watt Stereo Amplifier	74.50
Glaser-Steers GS-77T 4-Speed Record Changer (less base)	59.50
Base for Changer (Specify Finish)	3.95
Pickering U38/AT Diamond Stereo Cartridge	46.50
2-Lafayette SK-58 12" Coaxial Speakers @ 29.50	59.00
Regular Catalog Price 243.45	

LAFAYETTE SPECIAL PRICE **184.75**
YOU SAVE 58.70 ONLY

- The KT-250A represents the finest quality in its class—provides everything you could want in a stereo amplifier. Two 25-watt amplifiers integrated with complete stereo control facilities. Provision to expand at a later date with stereo tape deck and/or stereo FM/AM tuner. Features include separate bass and treble controls for each channel and concentric clutch-operated controls for individual or simultaneous level adjustment of each channel—The equal of the finest factory-assembled units and you save by building it yourself.
- Two Famous Lafayette SK-58 12" Coaxial speakers with sheepskin free-edge cone and 3" cone tweeter provide superb reproduction without coloration or distortion.
- The Glaser-Steers GS-77T 4-Speed Record Changer with its record of outstanding reliable performance, supplied with the stereo cartridge of your choice.


LAFAYETTE MATCHED 50-WATT STEREO KIT SYSTEMS

*Be Sure to Specify Choice of Pickering U38/AT, Shure M30, or Empire 880 Diamond Needle Cartridge.


System	Amp. Kit	Changer	Cartridge*	Changer Base†	Speakers	Spkr. Cab.	Shpg. Wt.	Net
LSK-359WXM	KT-250A	GS-77T	Choice of Pickering U38/AT, Shure M30 or Empire 880	Laff	2 SK-58	—	80	184.75
LSK-360WXM	KT-250A	Garrard AT6		Lesat	2 SK-58	—	80	184.75
LSK-361WXM	KT-250A	GS-77T	Choice of Pickering U38/AT, Shure M30 or Empire 880	Laff	2 SK-58	2 CK-34‡	128	229.75
LSK-362WXM	KT-250A	Garrard AT6		Lesat	2 SK-58	2 CK-34‡	128	229.75
LSK-363WXM	KT-250A	GS-77T	Choice of Pickering U38/AT, Shure M30 or Empire 880	Laff	2 SK-180	—	74	188.75
LSK-364WXM	KT-250A	Garrard AT6		Lesat	2 SK-180	—	74	188.75
LSK-365WXM	KT-250A	GS-77T	Choice of Pickering U38/AT, Shure M30 or Empire 880	Laff	2 SK-180	2 CK-34‡	122	233.75
LSK-366WXM	KT-250A	Garrard AT6		Lesat	2 SK-180	2 CK-34‡	122	233.75

*Specify Walnut, Mahogany or Blonde Base. †Unfinished Walnut Veneers.

Compare Features—Compare Value—Then BUY LAFAYETTE!



MODEL LT-78



Interior View Shows Solid Construction

Brilliant Stereo Performance... LAFAYETTE FM-AM STEREO MULTIPLEX TUNER

Two 3-Gang Tuning Condensers with Added Tuned RF Stage for Superior Sensitivity & Selectivity

- 16 Tube Performance—12 Tubes & 5 Diodes & Tuning Meter • MPX Separation 30 db @ 400 CPS. Less than 1% Distortion • Armstrong Circuit with Dual Tuned Limiters and Ratio Detector
- Automatic Frequency Response • Tuned Grounded Grid R.F. Stage on AM & FM • Flywheel Tuning
- Broadband I.F. for AM • Noise Filter Slide Switch • AM Level Control • Stereo Dimension Control • Illuminated Multiplex Indicator

89⁵⁰
NO MONEY DOWN

No Multiplex Adapter Required!

SIMPLICITY, FLEXIBILITY AND SUPERB STYLING have been carefully integrated in this quality tuner. Offering unlimited versatility, the LT-78 features separate AM, FM and FM MULTIPLEX reception at a reasonable price. Superbly styled low silhouette enclosure can be placed proudly on an open bookshelf or custom installation anywhere in your home. Attractively finished in gold and white with contrasting black dial face for added legibility as well as beauty. A complete set of controls provide for every tuner function. On the front panel there is a mode selection switch with a choice of AM, FM or FM stereo; a power on/off slide switch; variable AFC which is adjustable for tuning in weak stations adjacent to strong stations; flywheel tuning for smooth rapid station selection; a precision tuning meter for pinpointing your station to the strongest signal; a noise filter slide switch for weak stations and an illuminated multiplex indicator which shows you are in the FM stereo mode. On the rear panel there is an AM level control and a stereo dimension control to provide the right separation for your systems. Plate follower output permits using the tuner up to 50 ft. from an amplifier. FM circuitry features an Armstrong grounded grid low

noise front end and wide-band ratio detector; superheterodyne AM Circuit with 3 stages. AVC and Ferrite loopstick antenna. Imported.

The LT-78 is the ideal all-around stereo tuner for your home stereo system.
LT-78WX AM-FM Multiplex Tuner Imported Net 89.50

SPECIFICATIONS:

FM: IF Band Width: 200 KC — 6 db; Frequency Response: FM 20-20,000 CPS; Image Rejection — Better than 40 db; IF Rejection — 70 db. Stereo Separation: 30 db @ 400 CPS, less than 1% distortion; Hum — 60 db; Variable AFC Control; Noise Filter; 300 ohm antenna input. FM: Sensitivity 2 μ V and 20 DB S/N; Superheterodyne Circuit Bandwidth — 8 KC, AVC; Ferrite loopstick antenna; Image Rejection — 50 db; Harmonic dist. — less than 1% to 80% modulation. TUBES: 12AX7, 12AU7, 6BE6, (3) 6AU6, (3) 6BA6, (2) 6AQ8, 6X4 plus 5 germanium diodes. Power: 105 — 125 VAC, 50/60 CPS. Dimensions: 15Wx5Hx9 $\frac{1}{2}$ "D. Legs add $\frac{3}{4}$ " to height. Shpg. wt., 16 $\frac{1}{2}$ lbs.

NEW! LAFAYETTE 40 WATT STEREO FM MULTIPLEX RECEIVER -An Outstanding Value!



A MATCHED AM-FM TUNER plus BUILT-IN MULTIPLEX plus A 40-WATT STEREO AMPLIFIER (20-WATTS EACH CHANNEL) AT LAFAYETTE'S AMAZING LOW PRICE!

- 20 Tubes — 7 Diodes
- Complete Stereo Preamp Facilities
- 15 Front Panel Controls
- JUST ADD SPEAKERS FOR A COMPLETE STEREO SYSTEM

189⁹⁵
NO MONEY DOWN


Two 3-Gang Tuning Condensers with Added Tuned RF Stage for Exceptional Sensitivity & Selectivity

The Lafayette LA-226 is a self-contained instrument designed for the control and reproduction of all stereophonic and monophonic sources featuring a new built-in FM multiplex circuit. The receiver section consists of an AM/FM tuner with built-in multiplex which provides more than 30 db separation @ 400 cycles; Precision tuning meter and flywheel tuning for precise station selection. Multiplex pilot light indicates set is tuned to MPX. A sensitivity of 2 μ V for 20 db of quieting is achieved by the FM circuit with AFC and AFC defeat assuring reception of even the weakest signals. FM noise & filter slide switch cuts out unwanted station noise. The AM section features a superheterodyne circuit with AVC, and built-in ferrite loop antenna. The 40-watt amplifier section features large power transformers and a frequency response of 20-20,000 CPS \pm 2 db. Less than 1.5% harmonic distortion on all modes. Complete stereo preamp facilities provide dual concentric front panel controls for bass and treble, Volume control balance; blend for variable channel separation from 5-position selection switch stereo to mono, (AM, FM, FM Stereo, phono, AUX) 4-Position Amplifier mode switch (A, B, AB, REV), rumble filter slide switch, loudness slide switch, and on-off power switch. Rear controls include: Speaker phase switch, 8-16 ohm impedance selector switch, dimension control adjustment, speaker on/off switch, jack for stereo headphones, AC outlet, fuse and stereo tape outputs. Complete with a handsome enclosure in contrasting brown and brass—overall size: 17 $\frac{1}{2}$ Wx15Dx5 $\frac{1}{4}$ "H. Imported
LA-226WX Shpg. wt., 45 lbs. Net 189.95

SPECIFICATIONS

TUNER: HARMONIC DISTORTION: .7 on FM for 100% modulation; FM Freq.-response: 20-20,000 CPS \pm $\frac{1}{2}$ db
FM Sensitivity: 2 μ V for 20 db quieting; MPX Separation: 30 db @ 400 CPS. Hum level: 60 db, Image rejection: FM—50 db. AMPLIFIER: 65 db below full output for low level—75 db for high level. Power Output: 20 watts per channel. Sensitivity: mag phono 2 mv at full output, crystal input 30 mv at full output. Tone Control: \pm 12 db @ 50 CPS (bass), \pm 9 db @ 10 KC (treble) 20-20,000 CPS \pm 2 db. Output Impedance: 8 & 16 ohm, switch selected. Input Impedance: 47 K phono; .22 meg (high level) Rumble Filter—8 db @ 50 CPS. Phono Equalization: RIAA.

No Multiplex Adapter Required!



Interior View Shows Solid Construction

MODEL LT-80B FM TUNER READY FOR MULTIPLEX!



COMPARE FEATURE FOR FEATURE WITH THE MOST EXPENSIVE TUNERS

PIN-POINT TUNING ACCURACY

is provided by this precision tuning meter; evaluates relative strength of the incoming signal... invaluable when tuning weak stations.



49⁵⁰
NO MONEY DOWN

- ARMSTRONG CIRCUIT FOSTER-SEELEY DISCRIMINATOR AND DUAL TUNED LIMITERS • AFC • AFC DEFEAT • EXTREMELY SENSITIVE — 1.5 UV FOR 20 DB QUIETING • 10-TUBE PERFORMANCE — 8 TUBES (2-DUAL PURPOSE) • 20-20,000 CYCLES \pm $\frac{1}{2}$ DB • SUPERB LOW SILHOUETTE STYLING • 3 GANG TUNING CONDENSER • TUNED GROUNDED GRID RF STAGE

Remarkable... Quality, performance and styling that is in every respect the equal and in many instances superior to tuners priced far above the modest cost of this instrument. Designed and constructed of the finest components, with jewel like precision (each unit is hand wired). Engineered to provide maximum FM versatility, the LT-80B is provided with a multiplex output, designed to accept a stereo FM multiplex adapter. Flywheel action tuning control. Tube complement consists of 2-6AQ8, 2-6BA6, 2-6AU6, 1 each 6AL5 and 6X4. Handsome low silhouette enclosure will do justice to any decor. Beautifully finished in gold and white with contrasting black dial face. Complete with cage and legs. Dimensions: 11 $\frac{3}{8}$ Wx8Dx4 $\frac{1}{8}$ "H. Imported

LT-80B FM Stereo Tuner Net 49.50
HTA-18WXM Combination of LT-80B and LT-220 FM Multiplex Adapter You Save 5.00 Net 84.45

For Fine FM Multiplex Stereo Reception add Lafayette LT-220 FM Multiplex Adapter to LT-80B FM Tuner and SAVE!

Reg. 89.45 LAFAYETTE SPECIAL 84.45

HTA-18WXM Combination of LT-80B and LT-220 FM Multiplex Adapter You SAVE 5.00 Net 84.45

See description of LT-220 FM Multiplex Adapter elsewhere in this section.



SAVE \$5.00

NEW! LAFAYETTE FM MULTIPLEX STEREO TUNER

Now! from the
LAFAYETTE
HIGH-FIDELITY
RESEARCH
LABORATORIES



LT-700

124⁵⁰

NO MONEY
DOWN!

3 GANG TUNING CONDENSER FOR EXCEPTIONAL SENSITIVITY & SELECTIVITY.

- Virtually Distortionless Performance—Less than 0.15% Distortion at 100% Modulation, Monaurally
- Low Noise Front End With Triode Grounded Grid Amplifier and Triode Mixer
- Electronic Bar Tuning Indicator
- Double-Tuned Dual Limiters and Foster Seeley Discriminator
- Stereo Separation: 35 db at 400 cps
- Frequency Response: $\pm 1/2$ db 15-35,000 cps, Monaurally
- Variable AFC Literally "Locks-In" Stations
- Sensitivity 1.25 μ V for 20 db of Quieting
- 3 Gang Tuning Condenser

The LT-700 is another impressive example of Lafayette's engineering leadership. For here is a tuner that achieves a level of distortionless performance and flexibility that sets the standard for professional FM multiplex reception. Its superb circuitry features a low noise front end with triode mixer, double-tuned dual limiters and wide band Foster Seeley discriminator. Distortion has virtually been eliminated with less than 0.15% distortion at 100% modulation (monaurally). Sensitivity of the LT-700 is such that in many areas the only antenna needed will be a short piece of wire, except of course in remote locations. Plate follower outputs permit using the tuner up to 50 feet from the amplifier. Designed for maximum versatility, the LT-700 features a convenient front panel volume control for precision adjustment of tuner output level. In addition

LOOK at THESE QUALITY LT-700 FEATURES!



① Simple Front Panel Switch for Mono or Stereo Multiplex

② Variable AFC "Locks-In" Stations

TECHNICAL SPECIFICATIONS

Sensitivity: 1.25 μ V for 20 db of quieting. Variable AFC. Harmonic Distortion: 0.15% at 1Kc 100% modulation. Signal-to-Noise Ratio: Better than 57 db. Freq. Response: $\pm 1/2$ db 15-35,000 cps monaurally. Image Rejection: -50db. Stereo Separation: Built-in MPX section provides 35db separation at 400 cps. Discriminator Linearity: 600 Kc. Audio output: 1.75v at 75 Kc deviation (100% modulation). Simple manual switching for FM multiplex operation. Anode Follower for low impedance wide-band distortion-free output. Automatic FM Stereo indicator light. 2—No. 47 Pilot Lights. Tubes: 12AX7, 6C4, 12BZ7, ECC85/6AQ8, 6BK7B, 2-6BA6, 2-7543, 6AL5, EZ-80 rectifier, 2 matched diodes plus EM-84 tuning eye.

a variable AFC (automatic frequency control) is provided. Once properly tuned, the AFC literally "locks-in" the station and is adjustable for tuning weak stations adjacent to strong stations. Pinpoint tuning accuracy is assured by a special electronic bar tuning indicator that indicates maximum closure at the point of best tuning. Multiplex operation is achieved by a simple front panel switch. This also activates a stereo light when the station tuned to starts broadcasting stereo. Every LT-700 is individually attracted and tested to meet or exceed Lafayette's specifications. Attractively styled with a cream and brushed brass front panel set in a beige finished vinyl enclosure. Size 13 $\frac{3}{4}$ "x10 $\frac{1}{2}$ "x4 $\frac{1}{2}$ "H. For 117V. 50-60 cycle AC. LT-700WX Shpg. wt., 16 lbs. Net 124.50

WITH BUILT-IN MULTIPLEX CIRCUITRY NO MULTIPLEX ADAPTER REQUIRED
MADE IN U.S.A.

NEW! LAFAYETTE FM STEREO MULTIPLEX TUNER model LT-81 with built-in MULTIPLEX

No Multiplex Adapter Required!
3 Gang Tuning Condenser with Tuned RF Stage For Super Sensitivity and Selectivity

- Built-in Multiplex Circuit With 30 db Separation @ 400 CPS
- Ratio Detector and Dual Tuned Limiters
- AFC
- AFC Off
- Extremely Sensitive—2.0 μ V for 20 db Quieting
- 12 Tube Performance 10 Tubes (2-dual purpose)
- Freq. Response 20-20,000 CPS ± 2 db
- Low Silhouette Styling
- 3 Gang Tuning Condenser
- Tuned Grounded Grid RF Stage

ONLY 76⁵⁰

NO MONEY
DOWN

TRULY remarkable, quality performance and styling that is in every respect the equal to and often superior to FM Stereo tuners priced far above the modest cost of this fine instrument. Designed and constructed of the finest components with jewel like precision (each unit has been hand wired and individually tested at the factory) in order to insure that each tuner will maintain its excellence year after year with a minimum of maintenance. Engineered to provide high quality FM and FM stereo multiplex broadcasts the LT-81 has an Armstrong circuit and a Ratio Detector with dual tuned limiters. The multiplex circuit provides a stereo separation of 30 db at 400 cycles with less than 1% distortion. Controls consist of power on/selector switch for FM, Stereo MULTIPLEX, noise filter, AFC slide switch with off position, tuning Meter, Stereo dimension control to custom blend stereo reception (in rear), and Flywheel action tuning control gives velvet smooth tuning action. Pilot light goes on in stereo position. Two stereo output jacks on rear panel. Tube Complement: (2) 12AX7, (3) 6AU6, (2) 6BA6, (2) 6A08, 6X4 and 4 germanium diodes. Handsome low silhouette enclosure looks good in any room setting. Beautifully finished in gold and white with a contrasting black dial face. Complete with cage and legs. Dimensions: 5 $\frac{3}{4}$ "x13 $\frac{1}{2}$ "x9 $\frac{1}{8}$ "D. LT-81WX Shpg. wt., 12 lbs. — Imported Net 76.50

NEW AM-FM STEREO MULTIPLEX TUNER

- Foster-Seeley discriminator
- AFC (plus AFC Defeat Switch)
- Locks-In Stations—Prevents Drifting
- Stereo Separation Control
- Four FM IF Stages plus 2 AM IF Stages
- Flywheel Tuning
- 4 μ V Sensitivity For 30db Quieting
- Dual Channel Cathode Follower Output
- FM Frequency Response ± 1 db 20-20,000 CPS

74⁵⁰

NO MONEY DOWN!

MADE
IN
U.S.A.

An excellent performer with outstanding features and at Lafayette's low price a truly fabulous buy. Engineered to provide the widest possible range of tuner flexibility its capabilities include—Sparkling clear AM reception, highest fidelity FM reception and most important FM multiplex stereo reception. Front panel controls provide complete tuner flexibility with smooth action AM-FM flywheel tuning, Selector Switch (Off-On, FM, FM with AFC, AM), Monaural-Stereo Multiplex Switch, and a Calibrated Stereo Separation Control. The Automatic Frequency Control virtually locks in stations and prevents drift while the AFC defeat position allows easy tuning of weaker or distant FM stations adjacent to stronger stations on the tuning dial. A Stereo Separation Control allows precise channel separation according to individual acoustic requirements during FM stereo multiplex operation. Quality FM circuitry features a Foster Seeley Discriminator with 4 IF stages including discriminator, an R.F. Input stage plus Dual Channel Cathode follower output. The FM stereo MPX section utilizes a Matrix Bridge with 2 Diode Detectors plus a Dual Channel Follower Output. AM circuit features two IF Stages plus OSC/Mixer and Diode Detector with a Dual Channel Cathode Follower Output. In addition an Automatic Volume Control (AVC) insures a constant output in tuning from station to station. Attractive low silhouette styling features brushed brass front panel with contrasting ebony finished steel enclosure. Size: 13 $\frac{1}{2}$ "x4 $\frac{1}{2}$ "x11 $\frac{1}{2}$ "D. Equipped with AM ferrite rod antenna plus FM line cord antenna. For 110-120V 60 cycle AC. G-542WX Shpg. wt., 10 lbs. Net 74.50

FM-AM TUNER Superior Quality and VALUE!

47⁵⁰

NO MONEY DOWN

Receive FM and AM broadcasts with this "best value" tuner. Delivers the same fine performance and value as the (G-542WX) Kordex Tuner described above, but it is equipped with a multiplex output jack that will allow you to add multiplex later at your convenience with one of Lafayette's Kit or factory wired low cost multiplex adapters. Front panel controls include: Selector Switch for OFF, FM and FM AFC positions plus flywheel tuning control for velvet smooth tuning. For 110-120V 60 cycle AC operation. Finished in attractive brushed brass with matching ebony enclosure. Tubes: 6U8, 12A7, 6BE6, 6BA6, 2-6AV6, 6AL5, 6C4, 2-12AU7, plus 2 matched diode detectors. Size: 13x4 $\frac{1}{2}$ x9". G-541WX Shpg. wt., 10 lbs. Net 47.50

LAFAYETTE STEREO TRIUMPH! 24-WATT STEREO AMPLIFIER!

Dual 12-Watt Stereo Amplifier Coupled With a Versatile Stereo Preamplifier . . . Performance The Equal of Units 2 & 3 Times Its Power & Price.

49⁹⁵

NO MONEY DOWN!

SPECIFICATIONS

Power Output: 12 watts per channel stereo. 24-watts monaural operation. Frequency Response: 20-100,000 CPS ± 1 db at 1 watt, 50-50,000 CPS ± 2 db at 12 watts. Hum and Noise: Mag. Phone—56db below rated output, Tuner—73db below rated output. Distortion: less than 1% total harmonic distortion at 12 watts (IKC), less than .25% total harmonic distortion at 1 watt (IKC). Sensitivity: Low Level (Mag Input) 5mv at full output, High Level .6v at full output. Outputs: Dual 8 and 16 ohm impedance speaker outputs. Dual Tape outputs. Tube Complement: Total of 8, 3-12AX7, 4-6GW8, 1-5AR4.

- CHECK THESE QUALITY FEATURES
- ✓ Stereo Headphone Jack
 - ✓ Independent Concentric Bass & Treble Controls For Each Channel
 - ✓ Concentric Volume/Balance Control
 - ✓ Frequency Response: 20-100,000 CPS ± 1 db at 1 Watt
 - ✓ Hum & Noise—73 db Below Rated Output
 - ✓ High Sensitivity Allows Use With All Stereo Cartridges

FIRST RATE—make no mistake, don't be misled by Lafayette's low price. This is a Brilliant Stereo Performer . . . an amplifier with the wide-range frequency response, low distortion, low hum and noise characteristics you'd expect of amplifiers 2, even 3 times its power rating and many times its price. A full range of control facilities have been provided to assure complete Stereo capability and flexibility. Two dual concentric Bass and Treble controls provide separate and individual tone controls for each channel. A dual concentric volume Control acts as an independent level control for each channel and allows precise channel balancing. Fast, easy operation between Stereo, Reverse Stereo, Monophonic Left channel and Monophonic Right channel is furnished by a Mode switch. A selector Switch furnishes switching from Aux, Tuner

or Phono music sources. In addition slide switches are included for Rumble Filter (off-on) Phase (normal-reverse) and to take full advantage of the front panel Headphone jack a switch is provided for speaker or phone operation. Paired inputs located on the rear panel accommodate any of the ordinary stereo sources—inputs are included for magnetic, crystal or ceramic cartridges; Tuner, tape or auxiliary (high output) plus Tape Out jacks for recording through your tape recorder. Beautifully styled in a low silhouette enclosure, color keyed to do justice to any decor. Ivory and gold front panel is contrasted by gold metal knobs and enclosure. Complete with cage and legs. Size: 5 $\frac{1}{2}$ "x12 $\frac{1}{2}$ "x8 $\frac{1}{2}$ "D. For 115V 60 cycle AC operation. Shpg. wt., 20 lbs. LA-224WX Imported Net 49.95

EVERY LAFAYETTE ITEM IS NEW, PREMIUM QUALITY AND GUARANTEED

LAFAYETTE RADIO ELECTRONICS PAGE 11

LAFAYETTE BREAKS THROUGH THE STEREO PRICE BARRIER

NEW! OUTSTANDING STEREO PHONIC PERFORMANCE AT A BUDGET PRICE! LAFAYETTE LA-205 10-WATT STEREO AMPLIFIER IN MATCHED STEREO SYSTEM



SENSATIONAL PRICE!

89⁹⁵
NO MONEY DOWN

COMPLETE! NOTHING ELSE TO BUY!

• The Lafayette Model LA-205 is a self-contained AC operated amplifier designed for the control and faithful reproduction of either stereo or monophonic inputs from record players, changers, tuners and tape recorders. Features concentric Base and Treble controls, Rumble Filter, Phase switch and Front panel jack for connection of stereo headphones. Other controls include volume-off, mode selector, phono-tuner switch and front panel speaker/phone switch. Rear panel has speaker impedance switch; hum adjust and AC convenience outlet. Terminals are provided for the connection of either 8 or 16 ohm speaker systems on each stereo channel. Power output of 5 watts, or 10 watts if used monophonically. Beautiful low silhouette styling to match and enhance any decor.

• Lafayette PK-750 Lafayette—Glaser Steers 4-speed Stereo Record Changer with wide range, 50-15,000 cps cartridge and complete with your choice of Mahogany or Walnut base. Superior performance without rumble or wow provided by a heavy, precision balanced turntable and constant speed motor. Features include fully automatic operation with intermix and automatic shut-off after last record.

• Lafayette "Minuette" hi-fi speaker system. These famous speakers feature a full, rich tone from an extremely small size (8 1/4 x 15 3/4 x 5 7/8"). Complete stereo system as listed above. Shpg. wt., 43 lbs. LS-100WXM Net 89.95

LAFAYETTE LA-205 10-WATT STEREO AMPLIFIER

Same "best value" stereo amplifier as featured in system. Styled in contrasting gold and white. For 117V 60 cycle operation. Tube complement 266, W8/TCL86, 12AX7, 6CAX. Shpg. wt., 15 lbs. Imported. LA-205 Net 39.95

39⁹⁵ NO MONEY DOWN

COMPLETE 24-WATT STEREO PHONO MATCHED MUSIC SYSTEMS with Amazing LA-224 Stereo Amplifier



LAFAYETTE SPECIAL PRICE

129⁵⁰ NO MONEY DOWN

YOU SAVE 49.30

COMPLETE SYSTEM MATCHED COMPONENTS

Lafayette LA-224 24-Watt Stereo Amplifier	49.95
Garrard Autoslim 4-Speed Record Changer	39.50
Base for Changer (Specify finish)	3.95
Pickering U38/AT Diamond Needle Cartridge	46.50
2-Lafayette SK-124 Ultra-Compliance 2-way Speaker System (Specify Walnut or Mahogany) @ 19.95 each	2 For .38.90
REGULAR CATALOG PRICE	179.80



• The LA-224 offers performance the equal of units 2 or 3 times its power and price. Consists of two 12-watt amplifiers coupled with a versatile stereo preamplifier. Provides all stereo controls including front panel headphone jack.


• The 4-speed Garrard Autoslim Automatic/Manual changer introduces a new standard of styling, features and performance and is supplied with your choice of stereo cartridges. Excellent stereo reproduction.

• Two Lafayette SK-124 2-way speaker systems offer absolutely gigantic full size performance. Each occupies less than one cu. ft. of space while providing outstanding purity of sound from 40-16,000 cps. LS-225WXM Complete system as above. Shpg. wt., 64 lbs. Net 129.50

LAFAYETTE 40-WATT MATCHED STEREO SYSTEMS

COMPONENTS	
Lafayette LA-240 40-Watt Stereo Amplifier	79.95
Garrard Autoslim 4-Speed Record Changer	39.50
Wood Base for Changer (Specify Walnut, Mahogany or Blonde)	3.95
Pickering U38/AT Diamond Needle Cartridge	46.50
2-Lafayette SK-128 Biaxial Speakers @ 19.50	39.00
Regular Catalog Price	208.90

YOU SAVE 63⁴⁰
SPECIAL SYSTEM PRICE 145⁵⁰
NO MONEY DOWN



Lafayette 40-Watt Matched Stereo Systems
*Specify choice of Pickering U38/AT, Shure M30, or Empire 880 Diamond Needle Stereo Cartridge.

System	Amplifier	Garrard Changer	Cartridge*	Base	Speakers	Cabinet	Lbs.	Net
LS-353WXM	LA-240	Autoslim	Choice of U38/AT, M30, or Empire 880	†	2 SK-128	—	50	145.50
LS-355WXM	LA-240	Autoslim	†	2 SK-128	2 Mini-Duct**	95	189.50	
LS-357WXM	LA-240	Autoslim	†	2 SK-58	—	58	165.50	
LS-359WXM	LA-240	Autoslim	†	2 SK-58	2 Eliptoflex‡	109	223.50	

†Specify walnut, mahogany or blonde finish.
**Specify walnut, mahogany or oiled walnut.
‡Specify walnut, oiled walnut, mahogany or blonde.

LAFAYETTE LA-240 40-WATT STEREO AMPLIFIER

79⁹⁵ NO MONEY DOWN

- Total Harmonic Distortion at 1 KC.
- Frequency Response 12-100,000 cps—1db at 1 watt
- Hum & Noise: 80 db Below Rated Output
- Dual Concentric Bass & Treble Controls
- Variable Separation Control Eliminates Exaggerated Channel Separation
- Superb Low Silhouette Styling with Gold Finish Enclosure Set Off By An Ivory & Gold Front Panel
- 14 1/2" W x 10 1/2" D x 5 3/4" H
- For 115V 60 Cycles AC Operation

LA-240WX Shpg. wt., 25 lbs. Net 79.95



LAFAYETTE LA-55 15-WATT MONAURAL AMPLIFIER
The most extraordinary Hi-Fi value ever offered


44⁵⁰
NO MONEY DOWN

- Frequency Response: 15-30,000 CPS
- Hum 65 Db Below Rated Output
- Power Output 15 Watts
- Harmonic Distortion Less Than .3%
- Sensitivity: 3 MV Mag. Phono
- 5 Input Channels
- Rumble Filter
- Beautifully Styled
- EL84 Output Tubes in Push-Pull

LA-55WX Shpg. wt., 20 lbs. Net 44.50

LAFAYETTE SUPER-VALUE Hi-Fi PHONO SYSTEM

PLAY STEREO & MONAURAL RECORDS MONAURALLY NOW—ADD COMPLETE STEREO LATER. This economical high-fidelity system is the performance value of the year. Designed for ruggedness as well as beauty, these components will satisfy even the most critical music listener.



COMPONENTS

LAFAYETTE LA-55 15-Watt Complete Amplifier	44.50
GARRARD AUTOSLIM 4-Speed Record Changer	39.50
WOOD BASE FOR CHANGER (Specify Walnut, Mahog. or Blonde)	3.95
PICKERING U38/AT Diamond Needle Cartridge	46.50
LAFAYETTE SK-128 Full Range 8" Biaxial Speaker	19.50
Regular Catalog Price	153.95

Complete system as above with choice of Pickering U38/AT, Shure M30, or Empire 880 Diamond Needle stereo cartridge. Net 109.50
Same as above plus MINI-DUCT Enclosure for SK-128 Shpg. wt., 64 lbs. Net 132.00

SPECIAL LAFAYETTE SYSTEM PRICE 109⁵⁰
YOU NO MONEY DOWN SAVE 44.45

LAFAYETTE Criterion KT-650 FM TUNER KIT

3-GANG TUNING CONDENSER for EXCEPTIONAL SENSITIVITY AND SELECTIVITY

- Low Noise Front End With Triode Grounded Grid Amplifier and Triode Mixer
- Double Tuned Dual Limiters and Foster-Seeley Discriminator
- Sensitivity 1.25 μ v For 20 db of Quieting • Variable AFC Literally "Lock In" Stations • Frequency Response $\pm 1/2$ db 15-35,000 cps
- Multiplex Output For Stereo FM • Easy-To-Build Printed Circuits
- Electronic Bar Tuning Indicator Tube • Pre-Aligned IF and Discriminator Coils • 3 Gang Tuning Condenser • Virtually Distortionless Performance—Less than .15% Distortion at 100% Modulation.

Lafayette proudly presents the KT-650 FM Tuner Kit. The KT-650 ranks with the very finest FM Tuners. . . Lafayette engineers have succeeded in developing an instrument with performance and flexibility that equals and surpasses tuners many times its modest cost. A Multiplex jack is provided for addition of a Multiplex Adapter for FM Stereo Reception. A variable AFC (Automatic Frequency Control) is featured. Once properly tuned, the AFC literally "locks in" the station and is adjustable for tuning weak stations adjacent to strong stations. The convenient front panel Tuner Level Control allows precise adjustment of the Tuner output level.

Time-saving printed circuit boards are utilized to make wiring errors almost non-existent. The superbly styled low silhouette enclosure will do justice to any decor. Beige cover is set off by a Cream and Sienna Brown etched panel and knobs with contrasting Black Dial Face. Complete with cage, legs, interconnecting cables with plugs, indoor folded dipole antenna and alignment tool. Overall Dimensions: 14x5 $\frac{1}{2}$ x11"D. For 117V, 50-60 cycle AC. Power consumption 40 watts. Shpg. wt., 13 $\frac{1}{2}$ lbs.

KT-650WX FM Tuner Kit
LT-650WX Factory Wired & Tested

KT-650 in KIT FORM

54⁵⁰
NO MONEY DOWN

LT-650 FACTORY WIRED & TESTED
79⁹⁵
NO MONEY DOWN



READY for MULTIPLEX!

SAVE! COMBINATION SPECIAL!



Combination Special

71⁵⁰
Reg. 74.00

LAFAYETTE FM TUNER KIT KT-650 plus MULTIPLEX ADAPTER KIT KT-220

Combination of KT-650 and KT-220. Shpg. wt., 18 lbs. Net 71.50

ASSURANCE OF COMPONENT QUALITY

ONE YEAR PARTS GUARANTEE

All components in this unit are conservatively engineered to operate well within their performance capabilities. As assurance of this quality, Lafayette guarantees all parts including tubes for one year.

Made in U.S.A.

COMPARE THESE SPECIFICATIONS:

Sensitivity: 1.25 microvolts for 20 db of quieting. Image Rejection: 66 db. AM Suppression: 48 db. Discriminator Linearity 600 kc. Distortion and Noise: Better than 57 db below 1.5 volts at 100% modulation. Frequency Response: $\pm 1/2$ db from 15 to 35,000 cps with a standard 75 microsecond de-emphasis network. Audio Output: 1.75 volts at 75 KC deviation (100% modulation). Antenna Input: 300 ohms. Controls: Tuning; Level; AFC Control and Power Switch. Outputs: (2) Multiplex Adapter; Amplifier. Tube Complement: ECC85, 6BK7B, 6AL5, 2-7543, 2-6BA6, 6AV6, EM84 Electronic Bar Tuning Indicator Tube and a silicon diode rectifier.

LAFAYETTE KT-500A AM/FM STEREO TUNER KIT

Dual 3 Gang Tuning Condensers for Outstanding Reception!

- MULTIPLEX OUTPUT FOR NEW STEREO FM • TWO PRINTED CIRCUIT BOARDS AND PREALIGNED IF'S • FM AFC AND AFC DEFEAT • 17 TUBE PERFORMANCE—11 Tubes (4 dual-purpose) + Tuning Eye & Selenium Rectifier • ARMSTRONG CIRCUIT WITH DUAL LIMITERS AND FOSTER-SEELEY DISCRIMINATOR • 12 TUNED CIRCUITS AND DUAL CATHODE FOLLOWER OUTPUTS • EXTREME SENSITIVITY AND WIDE FREQUENCY RESPONSE

The KT-500A will receive simultaneous FM and AM stereo broadcasts or may be utilized for normal FM or AM reception. Provides an output for the new multiplex FM stereophonic reception. Apart from its unique flexibility, the KT-500A offers noise-free, drift-free, distortion-free performance. Each FM & AM section is tuned with its own 3-gang tuning capacitor and is provided with individual cathode follower outputs. Also, separate volume controls are provided for each channel so that when used for stereophonic reception, a proper balance between channels can be achieved. Convenient front panel switch changes from stereo to monaural use. Simplified accurate knife edge tuning is provided by magic eye which operates independently on FM and AM. Automatic frequency control "locks in" FM signal permanently. Ferrite rod antenna with loading ring is supplied to bring in weak AM stations. Designed for easy assembly, the kit is built around two printed circuit boards and prealigned IF's insuring fast accurate construction even for the beginner. Employs a cream and brushed brass front panel plus matching brown knobs with copper inserts set in a beige finished vinyl enclosure.



MADE IN U.S.A.

KT-500A IN KIT FORM
74⁵⁰
NO MONEY DOWN
LT-500A COMPLETELY WIRED and TESTED
124⁵⁰
NO MONEY DOWN

Ready for Multiplex!

SAVE! COMBINATION SPECIAL



LAFAYETTE KT-500A AM-FM STEREO TUNER KIT Plus MULTIPLEX ADAPTER KIT KT-220
Reg. 94.00 **91⁵⁰**
Net 91.50

Combination of KT-500A and KT-220. MTA-17WXM Shpg. wt., 22 lbs.

KT-500AWX Stereo Tuner Kit
MTA-17WXM Combination of KT-500A and KT-220 Multiplex Adaptor Kit
LT-500AWX Same as KT-500AWX, completely wired and tested
MTA-13WX Combination of LT-50A and LT-200 Multiplex Adaptor

Net 74.50
Net 91.50
Net 124.50
Net 174.00

You Save 5.00

SPECIFICATIONS

FM CIRCUIT: Armstrong, low noise front end with triode grounded grid amplifier and triode mixer. Double tuned dual limiters, Foster-Seeley discriminator, AFC and AFC defeat. **AM CIRCUIT:** Superhet with 3 stages AVC, 10kc whistle filter, ferrite antenna. **DISTORTION:** Under 1% harmonic on FM; under 1% on AM for up to 80% modulation. **HUM LEVEL:** 60 db below 100% modulation. **SENSITIVITY:** FM—full limiting on signals as low as 1 μ v, 2 μ v for 30 db quieting; AM Terminal Sensitivity 5 μ v. **SELECTIVITY:** FM 200 kc bandwidth; 6 db down, AM 8kc BW; 6 db down. **FREQUENCY RESPONSE:** FM 20-20,000 cps $\pm 1/2$ db. AM 20-5,000 ± 3 db.

IMAGE REJECTION: FM 40 db; AM 30 db. **I. F. REJECTION:** FM 70 db, AM 50 db. **CONTROLS:** 5 controls; FM VOL, AM VOL, FM Tuning, AM Tuning, and five position function selector switch. **TUBES:** 3-6BA6, 2-6AU6, 1 each 6BK7B, ECC85, 6AL5, 6BE6, 12AU7 and 6U5 tuning eye. Selenium rectifier. **OUTPUT IMPEDANCE:** Low impedances cathode follower. Output jacks for FM, AM or Stereo. **ANTENNA INPUT:** 300 ohms. Size 13 $\frac{3}{4}$ x10 $\frac{3}{4}$ x4 $\frac{1}{2}$ "H. Shpg. wt., 18 lbs. Kit comes complete with all parts and metal cover, a step-by-step instruction manual, schematic and pictorial diagrams.

MULTIPLEX ADAPTER KIT MODEL KT-220

FROM LAFAYETTE

Amazing!

- Separation 30db at 400 cycles
- Self-powered
- Ideal for Lafayette tuners equipped with MPX output Jacks

Enjoy thrilling FM Stereophonic sound from any recent Lafayette Tuner or any other quality wide-band FM or FM-AM tuner equipped with multiplex jacks. Hear the full range of audio frequencies in all the realism and magnificence of stereo sound by simply adding this low-cost Lafayette Multiplex adaptor kit. Engineered for anyone to build and operate, the KT-220 is easily connected to your tuners built-in multiplex output and special instructions are provided for connection to tuners without MPX output jacks. Coils are pre-aligned and only minimum adjustments are necessary. Self-powered, the unit may be hidden out of sight or installed remotely from your tuner.

The specifications speak for themselves: Separation—30db at 400CPS; Distortion—below 1%, noise filter controls: on-off with pilot light, Separation control, Tubes: 12AU7, 6BN8, 12AX7 plus a silicon rectifier.

The KT-220 Multiplex adapter is supplied complete with shielded cable for input and output connections; metal case and all parts plus the famous Lafayette detailed kit instruction manual. Front panel is finished in beige and ivory trim with contrasting beige and brown cabinet. Size 8 $\frac{1}{2}$ x4 $\frac{3}{4}$ x4 $\frac{1}{2}$ "H for 110-125 volts, 60 cycle AC.

KT-220 Shpg. wt., 4 lbs.

LT-220 Completely wired and tested

Quality Stereo FM Multiplex At minimum cost

ONLY **19⁵⁰**

Net 19.50
Net 39.95



LAFAYETTE UNIVERSAL MULTIPLEX ADAPTER

Now Enjoy All The Quality & Dynamic Brilliance of Stereo Through Your FM Tuner

COMPARE THESE QUALITY FEATURES

- 35 DB STEREO SEPARATION (AT 400 CPS) • MATCHES WITH VIRTUALLY ALL RECENT MODEL WIDE BAND TUNERS EQUIPPED WITH MPX OUTPUT JACKS • LESS THAN 1% DISTORTION FROM 50-15,000 CPS • PLATE FOLLOWER OUTPUT PROVIDES FOR REMOTE AMPLIFIER CONNECTION • SELF POWERED • COMPLETE WITH ENCLOSURE & ALL NECESSARY CONNECTING CABLES



ONLY **54⁵⁰**
NO MONEY DOWN

• 35 DB Stereo Separation (at 400 cps)

Here's the easiest, most inexpensive way for you to enjoy stereo—not records, not tapes, but stereo with all the fidelity and convenience that only FM can provide. Add this exciting new method of stereo reproduction to your component High-Fidelity system with this brilliant new stereo multiplex adapter. Performs beautifully with virtually any late model, wide band tuner equipped with a multiplex output jack and delivering a mpx output signal from 1.5 to 2 volts. Requires no special knowledge or tools to hook up—as simple and easy to connect as were your original components. Supplied with all necessary audio cables. All that's required is to merely plug the unit into your tuner, amplifier and AC outlet. Engineered for simplicity of operation, a selector switch conveniently located on the front panel provides for ON-OFF, Mono-FM and Stereo-FM. Individual pilot lights indicate when power is on and when adapter is operating

stereophonically. Beautifully styled to match any decor in textured beige finish cover and smart brushed brass anodized aluminum front panel. **TECHNICAL SPECIFICATIONS:** Separation: (at 400 cps) 35db; Harmonic Distortion: Less than 1% from 50 to 15,000 cps; Frequency Response: ± 1 db 50-15,000 cps. Multiplex Input Signal: .15 volts to 2V; Gain: 15 db; Output Impedance: 8000 ohms; Hum: at 60 cps for 1 volt signal input better than 60db; Rejection to 67KC: at least 50db; Rejection to 38 KC: at least 40 db. Four tubes (2 dual purpose) 12AX7, 6CA, 12BZ7, EZ80. Features notch filter for 38KC; low impedance plate follower output (for remote amplifier connection); matched diodes for optimum separation. Supplied with a special low capacitance input cable for optimum separation. Measures 4 $\frac{3}{4}$ x5 $\frac{3}{4}$ x10 $\frac{3}{4}$ "H. For 110-120V, 60 cycle AC. LT-200WX Shpg. wt., 8 lbs. Net 54.50

build your own HI-FI KITS

H.H. SCOTT



NEW MODEL LT-110
WIDE-BAND FM
STEREO MULTIPLEX
TUNER KIT

- First Kit With Built-In Multiplex
- Prealigned Multiplex Section

FM multiplex tuner in kit form. Both the multiplex section and silver plated front end are factory preassembled and prealigned. You need only align the tuner's wide-bandpass IF's and detector using the meter on the tuner itself. Special shielding protects against interaction of tuner and multiplex sections. Unique circuitry eliminates multiplex interference with bias oscillator of any stereo tape recorder. Features stereo Noise Filter, Vernier Tuning; Front panel tuning meter; and Stereo Tape recorder output. IHFM usable sensitivity 2.2 microvolts. 10 Tubes, 11 diodes. Shpg. wt., 20 lbs. 15 1/2" x 5 1/4" x 13 1/4" D.
G-633WX (less case) Net 159.95
Leatherette metal case C for LT-110. Shpg. wt., 5 lbs.
G-147W Net 13.95



MODEL LK-72
72-WATT STEREO
AMPLIFIER KIT

The LK-72 has the same output circuitry as the 299C wired stereo amplifier. Aluminum chassis and D.C. heated preamp filaments give low —80 db hum and noise. Frequency response 20 to 20KC ± 1 db; harmonic distortion at full output 0.8% — IM distortion 9.3% (CCIF); IHFM power bandwidth 21 to 20 KC; speaker output impedances 4, 8, 16 ohms. Front panel controls: Input selector (phono or tape head, Tuner, Extra); Equalization (NAB tape head or RIAA record equalization), Stereo Selector Switch; separate tone controls for channels A & B Stereo Balance; Derived Center Channel Level Control; Loudness On-Off; Scratch Filter; Tape Monitor; Loudness Compensation. 15 1/2" x 5 1/2" x 13 1/4" D.
G-625WX (less case) Shpg. wt., 35 lbs. Net 159.95
Leatherette metal case for LK-72 kit. Net 13.95

LK-48 48-WATT
STEREO
AMPLIFIER KIT



The most remarkable kit value to day—H. H. Scott quality at a nominal price. Has same controls as LK-72 except center channel output does not have front panel level control. Power output—24 watts per channel (IHFM); distortion at full output same as LK-72. IHFM Power band-width to 20 kc. D.C. heated preamp filaments and aluminum chassis for low —80 db hum and noise. Dimensions 15Wx4 3/4"Hx10"D.
G-640WX (less case) Shpg. wt. 35 lbs. Net 124.95
G-147W Leatherette Metal C case for LK-48 wt., 2 lbs. Net 13.95

LC-21 STEREO
CONTROL CENTER
KIT



This preamplifier kit has all the control features of the LK-72 PLUS dual magnetic pickup switch; rumble as well as scratch filter; microphone equalization phase reverse and separate on/off; unique shielding of power supply stage together with aluminum chassis and D.C. heated tubes gives totally inaudible hum even on phono input. Frequency response: 8-50,000 cps ± 1 db; distortion 0.1% at 2.5 volts output (perfect match for input sensitivity of LK-150 stereo power amplifier. 15Wx4 3/4"Hx11 1/2" D.
G-631WX (less case) Shpg. wt., 10 lbs. Net 99.95
G-147W Leatherette Metal case C for LC-21. Wt., 2 lbs. Net 13.95

NEW! harman kardon AWARD SERIES KITS



MODEL F 50XK
12995 NO MONEY DOWN



MODEL A 50K
11995 NO MONEY DOWN



MODEL A 30K
7995 NO MONEY DOWN

MODEL F-50XK FM Stereo Multiplex Tuner Kit. Special wide-band audio output circuitry, 3 IF stages, and triode grounded grid RF stage provide extended sensitivity and Freq. Response. Sensitivity, IHFM 2.8 MV @ 20 db S/N. Freq. Response 10-52,000 cps ± 1 db. Built-in multiplex and tuning meter. Brushed gold panel. Size: 15 1/4" x 5 1/4" x 12" D. Shpg. wt., 22 lbs.
G-659WX Net 129.95

MODEL A50K 50 Watt Integrated Stereo Amplifier Kit. 25 watts per channel music power output. Features center channel gain control, blend control with lamps and front panel stereo headphone jacks. 9 tubes. Freq. Response 12-70,000 cps ± 1 db. Hum — 85 db. High level input sensitivity, 200 mv. for rated output; phono input 2 mv., 12 Stereo Inputs. 2 Mag. phono, 2 tape head, 2 crystal phono, 2 tuner 2 tape amp., 2 aux., 2 tape monitor. Brushed gold front panel. Size: 15 1/4" x 5 1/4" x 12" D. Shpg. wt., 32 lbs.
G-660WX Net 119.95

MODEL A30K 30 Watt Integrated Stereo Amplifier Kit. Features continuously variable blend control to fill the "hole in the middle," gauged bass and treble controls. Freq. Response: 15-70,000 cps ± 1 db. Hum — 80 db. Excellent B+ regulation by silicon diode power supply. 8 Stereo inputs. Brushed gold front panel. Size: 15 1/4" x 5 1/4" x 11 1/2" D. Shpg. wt., 25 lbs.
G-661WX Net 79.95

NEW FISHER HI-FI KITS



THE FISHER KX-200 80
WATT STEREO CONTROL
AMPLIFIER KIT
169.50

Fisher engineers have developed a new concept of kit design known as Stratakit. Major components are pre-mounted and wires are pre-cut. The KX-200 amplifier/preamp specifications are: 80 watts IHFM music power output; (35 watts RMS each channel) Harmonic distortion (at rated output) 0.4%; IM Distortion (SMPT), at rated output 0.8%; Frequency response (overall 20-20,000 cps ± 1 db—total hum and noise 80 db (450mv rep); Channel Separation at 1 KC better than 50 db. Tubes: 6 ECC83, 4-7591, 2-SD95A, 2-SD91A. Built-in D'Arsonval calibration meter. For 117V, 60 cycles AC. Size: 15 1/4" x 12 1/2" x 5 1/4" H. Shpg. wt., 30 lbs.
G-666WX KX-200 Amplifier, less case Net 169.50
G-109W MC-2 Metal Cabinet for KX-200. Shpg. wt., 9 lbs. Net 15.95



NEW FISHER KM-60
FM STEREO TUNER KIT

A high quality FM Stereo multiplex tuner kit with famous Fisher features. Ultra-Sensitive Golden Cascade Front-End provides clear reception even from distant stations. exclusive Stereo Beam instantly indicates whether or not a station is broadcasting in stereo. precision D'Arsonval tuning meter which is also used in alignment of IF and ratio detector sections; pre-aligned front-end and multiplex section. 4 IF stages and 2 limiters. SPECS: Sensitivity 0.6 microvolts at 20db quieting. Signal-to-noise ratio 70db at 100% mod., Freq. response — ± 1db 20-15,000 CPS. 11 Tubes 12 Diodes, Selenium rectifier. Complete with illustrated manual. Size: 15 1/4" x 4 3/4" x 13" D. Shpg. wt., 18 lbs. Less cabinet.
G-667WX Net 169.50
MC-2 Metal cabinet for KM-60 Net 15.95
G-109W Shpg. wt., 9 lbs.



FISHER KX-100 50-WATT
STEREO MASTER AUDIO
CONTROL-AMPLIFIER

Front panel earphone jack. Newly designed Novar type No. 7868 output tubes. Features unique Stratakit assembly design to eliminate possibility of error. Facilities for direct connection of center channel speaker. 14 front-panel controls, including sharp cut-off high-frequency filter. Tape Monitor. Loudness Contour switch. Tape and phono Equalization. 10 tubes. 2 Silicon rectifiers. Size: 15 1/4" x 12 1/2" x 5 1/4" H. Shpg. wt., 24 lbs. Net 129.50
G-105W Metal Cabinet for KX-100 9 lbs. Net 15.95



FAIRCHILD COMPANDER KIT
Automatic Sensing Device
The Fairchild Compander is a deluxe automatic sensing device that allows recreation of original performance dynamics in existing playback equipment for discs, tape or FM. The Compander is not an amplifier. It does not introduce distortion or require a 110 V AC power supply. The Compander is inserted between the output program source: pickup, tape unit, or FM and the input of pre-amp or integrated amp. By deriving and analyzing a signal from the existing amplifier — the Compander automatically increases your amplifier gain to allow dynamic expansion of high level signals to compensate for the controls placed on the original recording. Surface noise; turnable and system noises are minimized. Right or left information is displayed giving insight into original studio mike placement. Dynamically expands signals—increases separation effects of signal. Also can be used as signal compressor for background music control. Specifications: Input Imp. 47 K ohms both channels. Output Imp. 47 K ohms. Control circuit imp. 4-16 ohms; Min. Control Circuit volt. 25V AC. Expansion 8 db max/channel. Compression 20 db max. channel. Distortion—none. Freq. Response — Flat through entire audio range. AC Power Requirements — none. Dim.: 8 3/4" x 5 1/2" x 2 3/4". Shpg. wt., 6 lbs.
G-676WX Compander kit Net 59.95
G-675WX Compander Factory Wired and Assembled Net 75.00

EICO HI-FIDELITY COMPONENTS • Kits and Wired



NEW! EICO ST-84
STEREO PREAMPLIFIER

A comprehensive self-powered stereo preamplifier which features 0.05% distortion or less on all basic functions (mag phono, tuner, tape). Input and mode selectors each have seven positions for maximum flexibility. Independent bass and treble controls provide true variable crossover control to boost or cut. Tape recorder outputs are not affected by controls. Has high and low frequency filtering, Tape Speed equalization and monitor switches for top tape control flexibility. Also includes level, and balance controls and a loudness switch. Frequency Response is 0.3 db from 5 to 25,000 CPS. Hum and noise is a 65db for low level inputs and —75db for high level inputs. RIAA phono equalization and NARTB for Tape. Tube Complement five 12AX7/ECC83 plus one 6X4. Metal cover is included. Finished in brushed gold aluminum faceplate with brown accenting band. Size: 5 1/2" x 15 1/2" x 8 3/4" D.
G-523WX ST-84 Kit Net 59.95
G-524WX ST-84 Wired Net 89.95



EICO 12-WATT HI-FI AMPLIFIER... PREAMP

Compact, attractively styled amplifier with complete front end facilities and true high fidelity performance. Direct tape head and magnetic phono inputs with NARTB (tape) and RIAA (phono) feedback equalizations. Power output: 12 watts continuous, 25 watts peak. Intermodulation distortion 1.5% at 12 watts, 0.55% at 6 watts, 60 to 6000 cps. frequency response: 12-50,000 cps ± 0.5 db at 1 watt; 25-20,000 cps ± 0.5 db at 12 watts. Controls: Selector switch, level control, bass and treble controls. Speaker connections for 16.8, and 4 ohms. Tubes (2) ECC83/12AX7, ECC82/12AU7, (2) EL84, EZ81. Size: 3 1/2" x 12 1/2" x 8 1/4" D.
G-424 Kit — Shpg. wt., 13 lbs. With instructions. Net 34.95
HF12 As above, but factory wired. Net 57.95
G-425



EICO MODEL HFT 90K FM TUNER KIT

Factory pre-wired and pre-aligned front end. Pre-wired tuning eye assembly. Stereo FM Multiplex reception with adaptor, "traveling" tuning indicator, fly-wheel tuning and AGC. SENSITIVITY: 1.5 uv for 20 db quieting; 2.5 uv for 30db quieting; full limiting from 25 uv. INPUT: 300 ohm balanced. OUTPUTS: Cathode follower and multiplier. TUBES: 1-ECC85/40 watts at 110-120 volts AC, 50-60 cycles. Complete with instructions. 12x8 1/2" x 3 3/4". Shpg. wt., 10 lbs.
G-422 Kit Net 39.95
G-423 HFT-90 Same as above, but factory wired Net 65.95
G-431 E-3 Cover for HFT-90. Shpg. wt., 3 lbs. Net 3.95

CITATION STEREO KITS



CITATION III
FM STEREO TUNER KIT

Famous Citation tuner III now has built-in multiplex. Outstanding sensitivity is featured with a completely assembled and prealigned FM cartridge. Maximum selectivity is assured by Nuvistor front end followed by three wide band IF stages. Sensitivity 0.65 microvolts for 20db quieting. Frequency response ± 0.5db, 1-52,000 CPS. (mono) 10-15,000 CPS (stereo); Dual cascaded gated beam limiters; Foster-Seeley discriminator. Hum: 65db below 100% modulation. Stereo Separation, —30db at 10-15,000 CPS. 6x1 1/4" x 12 1/4" H. For 110-120V AC. Shpg. wt., 33 lbs.
G-364WX Citation III FM Stereo Tuner Kit Net 219.95
G-374WX Citation III FM Stereo Tuner wired Net 299.95
G-365WX Citation III FM Tuner Kit with multiplex output jack. Shpg. wt., 32 lbs. Net 149.95
G-366WX Citation III wired with Multiplex output jack Net 229.95
G-232W WC1 walnut enclosure for Citation III and III X Net 29.95
G-373WX Citation III MA FM Stereo Adapter wired. Shpg. wt., 3 lbs. Net 79.95

CITATION HI-FI EQUIPMENT



CITATION I KIT
Stereo Preamplifier Control Center

A high quality stereo monaural preamp-control unit. Inputs: 12 (six pairs) — Aux., Tape Amp. Tuner, low-level phono, high-level phono. Outputs: 5-Two main preamp outputs plus a third channel output. Two tape outputs for recording. Mode selector chooses output types: stereo, Blend A + B, Channel A, Channel B, Stereo Reverse. IM DISTORTION: Less than 0.05% at 2 volts. RESPONSE: to ± 5 db 8-80,000 cps. Tubes: 9-ECC83/12AX7 plus silicon rect. POWER REQUIREMENTS: 110V AC. SIZE: 14 7/8" x 12 1/4" x 6 1/2" H. Shpg. wt., 20 lbs. Gold & Charcoal brown finish
G-230WX Kit Net 159.95
G-231WX Wired Net 249.95
G-232W Walnut Enclosure Net 29.95



CITATION II KIT
120 Watt Stereophonic Hi-Fi Power Amplifier

Two ultra-linear type amplifiers deliver 60 watts each channel or a total of 120 monaural. Frequency Response: 18-40,000 cps + 0 to —1.0 db @ 60 watts, 2-80,000 cps + 0 —1.0 db @ 1 watt; IM Distortion: Less than 5% @ 60 watts, Harmonic Distortion: Less than 0.5%. 20-20,000 cps @ 60 watts. Output 4, 8, 16 ohms. Tubes: 6-12BV7, 4-KT88, plus 4-Silicon Diodes & 1 Selenium rect. Dimensions: 16 3/8" x 9 1/2" x 11 1/2" D. Charcoal Brown & Gold Finish. Shpg. wt., 60 lbs.
G-233WX Kit Net 159.95
G-234WX Wired Net 229.95
G-235W Charcoal Brown Metal Enclosure Net 7.95

dynakit STEREO KITS



DYNAKIT PAS-2 STEREO PREAMPLIFIER KIT

Includes two independent high gain, low noise preamplifier-control channels. Inputs: 3 stereo low level and 4 stereo high level. Frequency response: ± 0.5 db 6-60,000 cps. Distortion: less than .05%. Noise: less than 3 uv. equivalent noise input on RIAA. Gain: 60 db at 1000 cps on RIAA, 20 db on high level. Tubes: 4-12AX7/ECC-83, 6X4, selenium rectifier. Textured vinyl finish. Size: 13x8x4". Shpg. wt., 11 lbs.
G-453WX Kit Net 59.95
Dynakit PAS-2 Stereo Preamp. Same as above, but completely wired. Shpg. wt., 11 lbs. Net 99.95
G-454WX Model PM-3 Panel mounting kit for PAS-2. Shpg. wt., 3 lbs. Net 4.95
G-468



DYNAKIT STEREO 70
70-WATT STEREO AMPLIFIER KIT

The stereo 70 is rated at 35 watts channel or 70 watts for monophonic. Frequency response: ± 0.5 db 10-40,000 cps. IM distortion: less than 1% at 35 watts. Sensitivity: 1.3 volts rms input for 35 watts output. Output impedance: 4, 8, 16 ohms. Minimum channel separation: 55 db. — 1 db 20 cps — 15 KC; Channel Separation 30 db. Size: 13x9 1/2" x 6 1/2". Shpg. wt., 32 lbs.
G-455WX Kit Net 99.95
Dynakit Stereo 70 Stereo Amplifier. Same as above, but completely wired. Net 129.95
G-456WX



EICO ST-40K 40-WATT STEREO
INTEGRATED AMPLIFIER KIT

The ST-40 contains 20 twenty watt amplifiers and a complete stereophonic hi-fi control center on one chassis. FEATURES: Switched sets of stereo inputs including magnetic phono (2), tape head, preamplified tape, FM-AM stereo tuner, FM-FM Multiplex, and Auxiliary. Balance Check switch. Loudness/level switch. Bass and treble controls. Other controls include: Six position mode selector, tape monitor, scratch and rumble, Output 4, 8, and 16 ohm. Third channel speaker connection. Specifications: IM distortion—2% at 40 watts; Harmonic Distortion—1/2% at 40 watts; Frequency response—± 1/2 db. 20-20,000 cps. Shpg. wt., 27 lbs.
G-520WX Net 79.95
G-521WX Same as above, but wired. Net 129.95



EICO ST-70K 70 WATT STEREO
INTEGRATED AMPLIFIER KIT

Consists of 2-35 watt amplifiers and a complete stereophonic hi-fi control center on one chassis. Stereo inputs in switched sets including: 2 magnetic phono (one for turntable, one for changer); tape head, preamplified tape, FM-AM stereo tuner, FM-FM Multiplex, and Auxiliary. Controls: Level with balance check switch and loudness/level switch; bass, treble, six-position mode selector, blend, tape speed, tape monitor, scratch, and rumble. Output: 4, 8, and 16 ohm speaker. Third channel output available. Specifications: IM distortion — 2% at 70-watts. Harmonic Distortion — 1/2% at 70 watts. Frequency response — ± 1/2 db, 20-20,000 cps. Shpg. wt., 35 lbs.
G-518WX Net 94.95
G-519WX As above, but factory wired. Net 149.95



NEW EICO ST-97
TUNER KIT
FM STEREO

Quality FM Stereo Tuner with built-in multiplex adaptor. Employs pre-wired and pre-aligned front end. IF strip and wide-band ratio detector. AFC with defeat. Cathode follower driven Slide-rule tuning with tuning indicator. Stereo indicating pilot lamp, automatically lit by stereo pilot carrier. Controls: Tuning, Separation, AFC on-off, stereo-mono, and power on-off switches. SPECIFICATIONS: IHFM Sensitivity: 3 1/2V (1.5 1/2V at 20 db quieting); IHFM S/N Ratio: 55 db; Harmonic Distortion 0.6%; IHFM IM Distortion 0.2%; IHFM capture ratio: 3 db; Drift: 0.2% without AFC; 5 to 1 correction with AFC. Frequency Response — 1 db 20 cps — 15 KC; Channel Separation 30 db. Size: HED — 5 1/4" x 15 1/8" x 11 3/8" D. Shpg. wt., 17 lbs.
G-444WX FM Tuner Kit Net 99.95
G-445WX FM Tuner Wired Net 149.95

1 LAFAYETTE SALE

Save Up To 46.49

GARRARD • GLASER-STEERS • MIRACORD • UNITED AUDIO

YOUR CHOICE OF ANY ONE OF THESE 3 SUPERB HI-FI CARTRIDGES INSTALLED FOR ONLY 1c WHEN YOU PURCHASE ANY ONE OF THE 6 CHANGERS LISTED BELOW.



GARRARD AUTOSLIM "P" AUTOMATIC INTERMIX CHANGER



PLUS PICKERING, SHURE OR EMPIRE CARTRIDGE ONLY **39⁵¹**

An ultra-compact, 4-speed, automatic-manual changer at a remarkably low price. Intermixes all records; i.e., records of different sizes can be stacked in any sequence. Has separate automatic and manual controls—featuring Garrard's new center-changing mechanism. Shpg. wt., 9 lbs. Imported from England.

GR-138W Less Cartridge and Base	Net 39.50
Garrard Autoslim "P" PLUS Pickering U38/AT Cartridge	Net 39.51
PK-644W Shpg. wt., 9 lbs.	Net 39.51
Garrard Autoslim "P" PLUS Empire 880 Cartridge	Net 39.51
PK-665W Shpg. wt., 9 lbs.	Net 39.51
Garrard Autoslim "P" PLUS Shure M3D Cartridge	Net 39.51
PK-666W Shpg. wt., 9 lbs.	Net 39.51

ACCESSORIES

PK-394W Walnut Wood Base. Shpg. wt., 4 lbs.	Net 4.95
PK-549 Automatic 45 RPM Spindle. Shpg. wt., 1 lb.	Net 3.80

GARRARD MODEL AT6 AUTOMATIC TURNTABLE



PLUS PICKERING, SHURE OR EMPIRE CARTRIDGE ONLY **54⁵¹**

A new, moderately priced 4-speed automatic turntable combining the convenience of a record changer with the performance of a turntable. Tubular tone arm dynamically counter-balanced with adjustable counter weight. Has built-in gram scale; oversized turntable; heavy flywheel action; quiet, powerful 4-pole shaded motor; completely separate automatic and manual controls. Shpg. wt., 12 lbs. Imported from England.

GR-167W Less Cartridge and Base	Net 54.50
Garrard AT6 PLUS Pickering U38/AT Cartridge	Net 54.51
PK-661W Shpg. wt., 12 lbs.	Net 54.51
Garrard AT6 PLUS Empire 880 Cartridge	Net 54.51
PK-662W Shpg. wt., 12 lbs.	Net 54.51
Garrard AT6 PLUS Shure M3D Cartridge	Net 54.51
PK-663W Shpg. wt., 12 lbs.	Net 54.51

ACCESSORIES

PK-394W Walnut Wood Base. Shpg. wt., 4 lbs.	Net 4.99
PK-667 Automatic 45 RPM Spindle. Shpg. wt., 1 lb.	Net 3.80

GARRARD MODEL "A" 4-SPEED AUTOMATIC TURNTABLE



PLUS PICKERING, SHURE OR EMPIRE CARTRIDGE ONLY **79⁵¹**

Precision turntable and tone arm with the convenience of automatic record changing. Plays all 4 speeds and is wired for stereo and monaural use. Tracking force is set by sliding knurled knob along scale. Shpg. wt., 19 lbs. Imported from England.

GR-166WX Less Cartridge and Base	Net 79.50
Garrard Model "A" PLUS Pickering U38/AT Cartridge	Net 79.51
PK-658W Shpg. wt., 19 lbs.	Net 79.51
Garrard Model "A" PLUS Empire 880 Cartridge	Net 79.51
PK-659W Shpg. wt., 19 lbs.	Net 79.51
Garrard Model "A" PLUS Shure M3D Cartridge	Net 79.51
PK-660W Shpg. wt., 19 lbs.	Net 79.51

ACCESSORIES

PK-393W Walnut Wood Base. Shpg. wt., 4 lbs.	Net 4.95
PK-410 Automatic 45 RPM Spindle. Shpg. wt., 1 lb.	Net 3.80

GLASER-STEERS GS-77T 4-SPEED STEREO RECORD CHANGER



PLUS PICKERING, SHURE OR EMPIRE CARTRIDGE ONLY **59⁵¹**

Amazing "Speedminder" automatically selects correct turntable speed. Features dynamically balanced and acoustically isolated tone arm, double channel muting switch, stereo-monaural switch, 4-pole hum-shielded motor and automatic or manual operation at all 4 speeds. Shpg. wt., 13 lbs.

GR-50W Less Cartridge and Base	Net 59.50
GS-77T PLUS Pickering U38/AT Cartridge	Net 59.51
PK-732W Shpg. wt., 13 lbs.	Net 59.51
GS-77T PLUS Empire 880 Cartridge	Net 59.51
PK-733W Shpg. wt., 13 lbs.	Net 59.51
GS-77T PLUS Shure M3D Cartridge	Net 59.51
PK-734W Shpg. wt., 13 lbs.	Net 59.51

ACCESSORIES

PK-350W Oiled Walnut Wood Base. Shpg. wt., 5 lbs.	Net 9.60
PK-352 Automatic 45 RPM Spindle. Shpg. wt., 1 1/2 lbs.	Net 2.95

MIRACORD "STUDIO" HI-FI AUTOMATIC TURNTABLE



PLUS PICKERING, SHURE OR EMPIRE CARTRIDGE ONLY **89⁵¹**

Features a heavy-duty shaded 4-pole induction motor; jam-proof, counter-balanced tone arm; famous "Magic Wand" spindle. Push-buttons select automatic or manual operation at any of 4 speeds. Shpg. wt., 30 lbs. Imported from W. Germany.

GR-351WX Less Cartridge and Base	Net 89.50
Miracord "Studio" PLUS Pickering U38/AT Cartridge	Net 89.51
PK-741WX Shpg. wt., 20 lbs.	Net 89.51
Miracord "Studio" PLUS Pickering Empire 880 Cartridge	Net 89.51
PK-742WX Shpg. wt., 20 lbs.	Net 89.51
Miracord "Studio" PLUS Shure M3D Cartridge	Net 89.51
PK-743WX Shpg. wt., 20 lbs.	Net 89.51

ACCESSORIES

GR-352W Oiled Walnut Wood Base. Shpg. wt., 4 lbs.	Net 9.95
GR-353W Unfinished Wood Base. Shpg. wt., 4 lbs.	Net 8.95
GR-354W Automatic 45 RPM Spindle. Shpg. wt., 1 lb.	Net 5.00

UNITED AUDIO DUAL CUSTOM 1006 4-SPEED COMBINATION STEREO TURNTABLE/CHANGER



ONLY **79⁹⁶**

Plus PICKERING, SHURE OR EMPIRE CARTRIDGE

Unusually flexible and easy to operate. Free-floating tone arm uses ball bearings. Has built-in stylus pressure gauge. 3 1/2 lbs. laminated turntable, separate drive gears for each speed and push-button controls. Shpg. wt., 20 lbs. Imported from W. Germany.

GR-186WX Less Cartridge and Base	Net 79.95
1006 Changer PLUS Pickering U38/AT Cartridge	Net 79.96
PK-735WX Shpg. wt., 20 lbs.	Net 79.96
1006 Changer PLUS Empire 880 Cartridge	Net 79.96
PK-736WX Shpg. wt., 20 lbs.	Net 79.96
1006 Changer PLUS Shure M3D Cartridge	Net 79.96
PK-737WX Shpg. wt., 20 lbs.	Net 79.96

ACCESSORIES

PK-744W Walnut Wood Base. Shpg. wt., 4 lbs.	Net 6.95
PK-392 AS-4 Automatic 45 RPM Spindle. Shpg. wt., 1 lb.	Net 4.80

NEW! LAFAYETTE AUTOMATIC 4-SPEED RECORD CHANGER



RONETTE CERAMIC CARTRIDGE

ONLY **18⁹⁵**

NO MONEY DOWN

MADE IN U.S.A.

• Plays Stereo, LP and 78 RPM

• Quality Ronette Ceramic Cartridge • Automatic 3-Way Shut-Off • Intermixes Records of Same Speed • Heavy Duty-Constant Speed Motor

Feature for Feature, the Lafayette Automatic record changer matches or exceeds costlier units. Built for compatibility with both stereophonic and monaural records, this changer offers superior performance for budget-sparing music systems. The balanced featherweight tone arm operates at only 5-7 grams of needle pressure to minimize record wear. Flip-type, Ronette ceramic stereo cartridge is unaffected by heat and humidity. Heavy precision-balanced turntable and constant speed motor insure smooth rotation without hum rumble or "wow". Plays all 4 record speeds—automatically changes up to fourteen 7", twelve 10" or 12" records. Intermixes 10" and 12" records of same speed. Plays records manually if desired. 45 r.p.m. spindle optional. Automatic 3-way shut-off after last record (returns tone arm to rest, stops

turntable motor, turns set off.) neutral position disengages turntable drive wheel when not in use—prevents rumble producing flat spots. 117 volts AC, 60 cycles. Compact and exceptionally functional, only 13 1/2 x 12 7/8" x 3" below and 5 1/2" above mounting board. Beautiful brown and gold finish. Shpg. wt., 12 lbs.

PK-605W No Money Down	Net 18.95
PK-606W Walnut Base	Net 4.50
PK-607W Mahogany Base	Net 3.95
PK-608W Mounting Board	Net 1.10
PK-609 45 R.P.M. Spindle	Net 1.49



TURNTABLE WILL TRACK AT ANGLES IN EXCESS OF 45°

SALE PRICE **16⁹⁵** 1962 CATALOG PRICE **32.50**

• Distortion Free From 20-16,000 cps • Flat Frequency Response 20-15,000 cps • Feather Light Stylus Pressure—Individually Adjusted For 3-Grams • Hum Free—Entire Arm & Cartridge Case Shielded with Mu Metal

Tone arm resonance is minimized by use of specially designed counter weight, sub weight and lateral damping mechanism. The arm counter balance is floated on a damped suspension bar. Precision bearings assure minimum lateral and vertical friction. Overall height of arm adjusts from 1 1/2" to 2 1/8". Signal to noise level of well over 100 db. Stylus replacement requires only a few seconds, pull out the old stylus and plug in the new. The diamond stylus is capable of supplying up to 2,000 hours of playing time. With .7 mil diamond stylus, mounting instructions, stylus cleaning brush, all hardware. Shpg. wt., 3 lbs. PK-448 Imported Net 16.95

Complete .7 Mil Diamond Stylus Assembly for PK-448 Lafayette Panasonic Tone Arm. Shpg. wt., 1 1/4 lb. Imported Net 7.95

TECHNICAL INFORMATION
Output Voltage . . . 5 millivolts • Channel Separation . . . More than 25 db • S/N Level . . . Over 100 db • Compliance . . . 5x10⁻⁶ cm/dyne • Suggested Load Impedance . . . 50,000 ohms • D. C. Resistance . . . 420 ohms • Tracking Force . . . 3 grams • Stylus7 mil • Frequency Response . . . Distortion free: 20-16,000 cps Flat. ± 2 db 20-15,000 cps • Overall Length . . . 11 1/4"

LAFAYETTE AUTOMATIC RECORD CHANGER



Made Exclusively for LAFAYETTE by GLASER-STEERS

LOOK AT THESE OUTSTANDING FEATURES!

- AUTOMATIC 4-SPEED CHANGER—PLAYS 16 2/3, 33 1/3, 45 and 78 RPM RECORDS AUTOMATICALLY OR MANUALLY
- SUPERB FOR STEREO OR MONAURAL USE
- AUTOMATIC SHUT-OFF AFTER COMPLETION OF LAST RECORD
- JAM-PROOF TONE ARM AND MECHANISM
- FULL 11" TURNTABLE WITH BLACK RIBBED RUBBER MAT
- BUILT-IN ANTI-SKATE DEVICE PROTECTS YOUR RECORDS
- ASTATIC TURNOVER CARTRIDGE WITH 50-15,000 CPS RESPONSE
- INTERMIXES 1" STACKS OF 7", 10" AND 12" RECORDS
- ADJUSTABLE STYLUS PRESSURE
- DIE-CAST ALUMINUM ONE-PIECE TONE ARM
- AUTOMATIC IDLER RETRACTION

ONLY **24⁵⁰** LESS BASE

NO MONEY DOWN

A superb new 4-speed, High Fidelity Automatic record changer made exclusively for Lafayette by Glaser-Steers, an outstanding leader in the development of high quality, reliable changers. This New Lafayette changer has been designed to give the highest standard of performance and dependability. Extremely low Wow, flutter, and rumble. Plays 16 2/3, 33 1/3, 45 and 78 RPM records automatically or manually and intermixes 7", 10", and 12" records. Superb for stereo or monaural use. Built-in anti-skate device prevents tone arm from shooting across the delicate record grooves. Built-in "pop filter" eliminates annoying popping sound between cycles. Automatic shut-off after completion of last record. Arm returns to rest even on manual play. Mass-balanced, one-piece Die-Cast Aluminum tone arm acoustically engineered to accurately and gently perform all its necessary functions. Specially designed motor is dynamically balanced and isolated by rubber mounts. Precision pivot system assures you of feather-light tracking. Special spring suspension ensures freedom from internal vibration. Attractive finish in antique white with contrasting black accessories. Complete with line cord and all connecting cables. For 110/120V, 60 cycles AC. Dimensions—11 1/2 x 13 1/8". Requires 4 1/2" above mounting board, 2 3/8" below mtg. board. Shpg. wt., 8 lbs.

PK-750W Less Base	Net 24.50
PK-753 45 RPM Spindle for above	Net 1.80
PK-749W Walnut base for above	Net 4.50
PK-747W Mahogany base for above	Net 3.95
PK-752W Unfinished mtg. board for above	Net 1.10


YOUR ORDER IS SHIPPED AT THE CURRENT PRICE SO YOU BENEFIT FROM ANY PRICE REDUCTION

LAFAYETTE RADIO ELECTRONICS PAGE 15


LAFAYETTE TOP QUALITY TAPE RECORDERS AT ROCK BOTTOM PRICE

TAKES FULL 7" REEL OF TAPE

NEW LAFAYETTE 2-SPEED TAPE RECORDER FEATURES 4-TRACK MONAURAL RECORD/PLAYBACK WITH 4-TRACK STEREO PLAYBACK*



ONLY 89⁵⁰



COMPLETE with MIKE, SHIELDED PATCH CORDS, EMPTY 7" REEL and 7" REEL RECORDING TAPE.

with ELECTRONIC TRACK SELECTOR SWITCH, VU RECORDING LEVEL METER and PAUSE SWITCH FOR INSTANT EDITING

- Two Speeds—3¾ & 7½ ips
- Sensitive Hand-Held Dynamic Microphone with Swivel Desk Stand
- Pause Lever Provides Instant Stop For Editing
- Record-Erase Safety Switch
- Fast, Rugged Shift Lever Control
- Extension Speaker Jack
- High Impedance Monitoring Jack
- VU Meter Recording Level Indicator
- Electronic Track Selector Switch
- Specially Designed Heavy Duty 6x4 PM Speaker
- Separate Erase and Record Heads

We've tested, we've compared and Lafayette's engineers have certified this new RK-137 Tape Recorder as containing one of the finest, quality constructed, smoothest performing tape mechanisms available. And, at its remarkably low price, the RK-137 must be ranked near the top in Lafayette's long history of best buys. Engineered to provide virtually every wanted tape recorder feature, the RK-137 performs brilliantly, with facilities for 4-track monaural record/playback and 4-track stereo playback (when used with a second channel containing a tape head input such as found in

a component Hi-Fi system). Controls are completely functional and are designed and arranged to make the RK-137 a genuine pleasure to use. Features include: a rugged, easy to use shift lever for fast rewind, fast forward, play and record functions; a special push-button safety record switch assures against accidental erasure of tapes; velvet-smooth volume and on-off tone controls; a pause lever instantly stops tape in motion, especially useful for editing; track switch provides fast, dependable electronic switching between tape tracks 1-4 and 3-2. In addition a VU recording level

meter has been incorporated to indicate correct volume-setting for recording. Speeds are adjustable from 3¾ to 7½ inches per second by means of a simple capstan adjustment. Tape economy is unmatched—from a standard 7½" 1200 ft. reel the RK-137 provides over 2 hours monaural record/playback time at 7½ ips and over 4 hours at 3¾ ips. Jacks are furnished for microphone input, High-impedance Radio-Phono Input, Extension Speaker Output, Monitor Output and Stereo Head Output for playback of 2nd stereo channel. Imported RK-137WX Shpg. wt., 22 lbs. Net 89.50

RESPONSE: 40-15,000 cps at 7½ ips. 40-9,000 cps at 3¾ ips. **SIGNAL-TO-NOISE RATIO:** 42db. **WOW & FLUTTER:** less than 0.3%. **Interchannel separation.** Complete in attractive vinyl covered two-tone case and equipped with a dynamic mike, cable assembly for recording from your phono or radio, stereo head input cable for stereo playback, 1200 ft. 7" Reel recording tape with a 7" take up reel. **SIZE:** 13½x6 ½x10½" D. For 110-120 VAC 60 cycles operation.

NEW! LAFAYETTE RK-142 2-SPEED TAPE RECORDER



59⁹⁵

NEVER BEFORE SUCH QUALITY AND VALUE!



- Takes Reels up to 7"
- With Recording Level Indicator
- ½ Track Doubles Play and Record Time
- Two Speeds—3¾ or 7½ ips.
- 4x6" Speaker for Fine Tonal Reproduction
- Provision for External Speaker
- Permits Direct Recording from Radio or Phono

Perfect for home, school or office. At home, the RK-142 proves ideal for parties or recording your favorite musical performance. Handy fool-proof operation has been provided by a specially designed lever type record switch which completely eliminates the chance of accidental erasure. Speeds are adjustable from 3¾ to 7½ ips by a simple capstan adjustment. Handles up to and including the large 7" variety tape reels. At 3¾ ips, the RK-142 provides more than 4 hours recording on long play ½ mil 2400 ft. tape reel. A special 4x6-inch heavy duty permanent magnet speaker furnishes an exceptionally fine tonal quality. Record level indicator facilitates recording by showing you when the volume control is correctly set. Jacks provided for microphone, phono and extension speaker (special alligator clip cord is supplied). These internal jacks permit making recordings directly from your radio or phonograph regardless of their volume control setting. This feature eliminates distortion, hum and outside noise that may be present and gives you professional recording results. Complete with sensitive dynamic microphone. Finished in attractive scuff resistant material. Dimensions: 11¾x9¾x7½". For 110 volts, 60 cycles. Imported. RK-142WX 59.95

SPECIFICATIONS

Tape speed: 7.5 and 3.75 ips in two speeds. Track system: ½ track monaural record and playback. S/N ratio: —42 db or better at 7.5 ips tape speed. Rewind time: 3 min. for 7" reel. Fast Takeup Time: 3 min. for 7" reel. Erasure: over 60 db. Response: Record-playback response essentially flat with tone control at minimum treble. Approx. 10 db slope between 100 and 7000 cps with tone at max. treble. Wow-Flutter: 0.2% or better at 7.5 ips; 0.3% at 3.75 ips.

EXCITING NEW KORDEX T.M.

4-TRANSISTOR TAPE RECORDER KIT IN SEMI-ASSEMBLED KIT FORM

ASSEMBLES EASILY IN LESS THAN AN HOUR

DUAL TRACK . . .
Plays Twice as long as Full Track



ONLY 17⁹⁵

- Extra Small
- Fully portable—Battery Powered
- A Mere 2½ lbs. in Weight
- Pre-wired
- 4-Transistor Printed Circuit Amplifier
- Accepts Standard 3" Tape Reel
- Instant-Action Play/Rewind Lever Control
- Record, Rewind, Playback, Erase

Here is a precision, full function miniature tape recorder in money saving semi-assembled kit form. In less than one hour the KorDEX Tape Recorder can be assembled and ready for operation. The amplifier is prewired in a rugged printed circuit, thereby eliminating most of the work. Complete it weighs only 2¾ lbs. and slips easily into a briefcase or handbag. Designed for ease of operation, all controls are readily accessible. Fast, instant, Rewind-Off-Play functions are provided by a handy lever control. In addition the front panel also includes a Record-Play Slide Switch, Volume Control, plus Earphone and Microphone jacks. The powerful 4 transistor precision wired amplifier drives a specially designed built-in 2" PM speaker. With its attractive carrying case the KorDEX recorder is equally suitable for home, office or travel—power is supplied by one standard "C" flashlight cell and one inexpensive 9 volt transistor battery. Complete with crystal lapel microphone, batteries, 3 inch, 100 ft. reel of tape, empty reel, earphone and instructions. Measures 8Wx6½Dx3"H. Imported. **KT-212 Shpg. wt., 6 lbs. Net 17.95**

RT-20 3" Reel 300 ft. ½ mil Mylar tape. Net .69
Shpg. wt., 4 oz.

BA-2 9 volt transistor battery for above. Net .21
Shpg. wt., 2 oz.

BA-156 1.5V Battery for above (1 req.). Net .13
Shpg. wt., 2 oz.

LAFAYETTE MIRACLE VALUES IN TAPE RECORDERS

The Magnificent Fidelity of Stereo Tape

... YOURS WITH THIS NEW

LAFAYETTE 2-SPEED STEREO PLAYBACK TAPE DECK

WITH 6-TRANSISTOR DUAL STEREO PREAMPS

PLAYS • Stereo ¼ Track; ½ Track
BACK • Monaural ½ Track; Full Track

COMPARE THESE PERFORMANCE SPECIFICATIONS

- Frequency Response: @ 7½ IPS, 50-15,000 CPS ± 1.5db; @ 3¾ IPS, 50-9,000 CPS ± 2db • Wow & Flutter .15% @ 7½ IPS, 0.2% @ 3¾ IPS • Cross Talk & Stereo Channel Separation: 50db • Signal To Noise Ratio: 50db • Playback Output with Built-In Stereo Playback Preamplifiers 0.5V
- 110-120V 60 cycles AC operation

There is nothing to equal the superlative reproduction and fidelity of prerecorded stereo tape. And now, at the price you'd expect to pay for a record changer you can equip your music system with this new Lafayette Stereo Playback Tape Deck. Precision engineered to satisfy the most discriminating music listener, the RK-141 will playback with uncompromising fidelity ¼ track and ½ track stereo tapes plus ½ track and full track monaural tapes. Unlike other units requiring separate playback preamplifiers, the RK-141 is equipped with its own built-in 6 transistor dual stereo playback preamplifiers equalized for the NARTB tape curve... allows use with virtually any stereo amplifier by merely connecting to the auxiliary, tuner, or hi-level tape inputs. The transistorized playback preamplifiers, powered by a highly rectified DC power supply, together with a specially designed tape head shield on which the pressure pad is mounted, reduce hum and noise levels to professional standards. Its tape handling qualities and mechanism reflect the careful design and construction employed—the precision laminated tape playback head is of the same type found in the costliest units; tape is automatically disengaged from the tape head in rewind, fast, forward and stop positions. In addition, the unit automatically shuts off at the end of the tape (without any need for attaching metal leaders at the tape ends). The 4-pole, heavy-duty, constant speed induction motor is fused and employs a dynamically balanced flywheel. A front panel speed selector switch allows instant selection of 7½ or 3¾ ips speeds. In addition, two rugged lever-action controls provide for Rewind, Off, Play and Fast Forward functions. Accepts all size tape reels up to and including 7". Measures 10" Dx 14 3/4" W x 5" H. Complete with shielded hook up cables. Shpg. wt., 17 lbs. Net 59.50

RK-141WX Imported
Furniture Grade Walnut Base for RK-141. Shpg. wt., 4 lbs. Net 6.95
RK-143W
Portable Carrying Case for RK-141. Shpg. wt., 5 lbs. Net 9.95
RK-147W



Priced At
No More Than You'd
Expect to Pay For
A Record
Changer!

WAS
79.95

59⁵⁰

NO MONEY
DOWN



OPTIONAL PORTABLE
CARRYING CASE

- Dual NARTB Equalized Transistorized Stereo Playback Preamps Allows Use With Virtually Any Stereo Amplifier
- Frequency Response: 50-15,000 cps @ 7½ ips
- 2-Speeds—7½ & 3¾ ips
- Accepts Full-Size 7 Inch Reels
- Automatic Shut-Off At End Of Tape
- Plays back ¼ Track, ½ Track Stereo Plus ½ Track and Full Track Monaural

Fully Equipped!
Contains its own
built-in Stereo
Playback Preamps

LAFAYETTE DELUXE DUAL SPEED TAPE RECORDER MODEL RK-130

PLAYS BOTH
7" and 5" REELS

59⁸⁸
NO MONEY
DOWN

Thousands of these Fine Quality Tape Recorders Sold
at the 1962 Catalog Price of 89⁹⁵



- Two Speeds 3¾ and 7½ I.P.S.
- Plays Both 7" and 5" Reels
- Built-in Speaker and Amplifier
- Complete with Dynamic Microphone

TAKE ADVANTAGE OF THIS
SENSATIONAL ONCE-IN-A-LIFETIME
BARGAIN!

You'll pat yourself on the back
for this Buy!

The perfect companion for language work, voice and instrument study, personal and family use, office work—a worthwhile investment for any classroom. This rugged tape recorder plays both 7" and 5" reels at speeds of 3¾ and 7½ inches per second. Consists of a double track, high frequency bias recording system with a frequency response range of 80 to 10,000 cycles, and a high frequency erase system. Internal amplifier provides 1.5 watts audio output to a built-in 4¾" speaker. An additional speaker may be plugged into the output jack. The RK-130 features simplicity of operation for quick stopping, playing, recording, fast forward winding or rewinding. Two input jacks are provided to permit simultaneous recording from a radio or record player and a microphone. Dynamic microphone is included with the unit. Both volume and tone are adjustable, and a neon tube recording level indicator is provided to facilitate correct settings. A switch allows the user to hear the playback either through the speaker or through a set of headphones (not supplied). A 7" tape reel played on both tracks will last for 120 minutes at 3¾ i.p.s., or for 60 minutes at 7½ i.p.s. A 5" reel will last 60 minutes at 3¾ i.p.s., or 30 minutes at 7½ i.p.s. Internal amplifier tube complement: 1—12AD7, 1—6BM8, 1—6AR5, plus 1—6X4 rectifier. For 117 VAC, 60 cps. Recorder dimensions: 16.4x12.4x8". Complete with 7" empty reel, dynamic microphone, patch cord, instructions, and large, removable strap. Import RK-130WX Shpg. wt., 28 lbs. Net 59.88
7" reel with 1200 ft. of recording tape. Shpg. wt., 1 lb. Net 1.59
RT-10

New Wollensak STEREO TAPE RECORDER

2 & 4 Track Stereo or Mono Record/Playback



T1580
319⁹⁵

Now, a superb 2 and 4 track stereo or mono tape recorder by Wollensak. Features sound on sound recording, PA voice over playback, separate volume control on each stereo channel, precision index counter for accurate monitoring, and a balance tone control on each channel. An instant stop switch is provided for precise editing while an automatic shut off instantly turns the mechanism off when the end of the reel is reached. Incorporated is an automatic head demagnetizer and a self adjusting braking system. Specs—Freq. response: 40-18,000 cps ± 3 db @ 7½ ips, 40-13,000 cps ± 3 db at 3¾ ips; Play time: up to 8 hours on 4 track mono, up to 4 hours on 4 track stereo; Power output: 11 watts per stereo channel (22 watts mono); Wow and Flutter: less than .3% each speed; Signal to Noise ratio: greater than 48 db; Power consumption: 110 volts AC only; Inputs: mike, phono-radio, and preamp. Complete with 2 mikes, vinyl cover, accessories and cables. Size: 6½ x 10½ x 11¾". Shpg. wt., 26 lbs. Net 319.95
RK-474WX

Wollensak TAPE RECORDERS AT PRICES YOU CAN AFFORD



T1500
156⁵⁰

T-1515-4
173⁹⁵

T1700
199⁴⁵



1010

MODEL T-1500 HI-FI TAPE RECORDER

• 10 WATTS PUSH-PULL OUTPUT! • RESPONSE 40-15,000 CPS ± 3 DB AT 7½ IPS! • DISTORTION LESS THAN 0.8%! • WOW AND FLUTTER BELOW 0.3%! • SIMPLIFIED KEYBOARD CONTROL! • WEIGHS ONLY 18 LBS.!

A really precision portable high fidelity recorder made by a famous manufacturer of precision optics. This latest model T-1500 is made available, for the FIRST TIME AT THIS PRICE, BY LAFAYETTE! Dual speed (3.75 and 7.5 inches per second), dual track—provides up to 4 hrs. of record or playback time. Utilizes miniaturized components and all-metal airplane-type construction to achieve real portability—weighs only 18 lbs., measures 6½x10½x11¾". Takes reels up to 7". Additional features of this outstanding recorder include: signal-to-noise ratio 48 db; 2 special hum balance controls: "Balanced Tone" high fidelity; exclusive high speed rewind lever; 2-level recording indicator; precision index counter. Supplied complete with ceramic wide-range microphone, 1 reel of tape, 1 empty takeup reel, radio-tv attachment cord and hi-fi cable. For 110-120 volts, 60 cycles AC. Shpg. wt., 21 lbs. Also available in 50 cycle units; specify. Net 156.50
RK-405WX

MODEL T-1515-4 FOUR TRACK STEREO HI-FI TAPE RECORDER

The Hi-Fi enthusiast's dream in a compact portable tape recorder for true stereo performance. Has all the styling and superb features of the famous monaural T-1550, plus stereo head and built-in second preamplifier. Plays 2 and 4 track monaural and 2 and 4 track stereo. Records up to 4 separate monaural tracks on single roll of tape. 6½x10½x11¾". Shpg. wt., 24 lbs. Net 173.95
RK-417WX

NEW! Model T-1700 Mobile Tape Recorder

Now listen and record outdoors and indoors with true hi-fidelity. The T-1700 is a full size, portable tape recorder designed to operate from both a home AC outlet or a 12 volt car or boat battery by simply plugging into your cigarette lighter. Same fine performance and specifications of the T-1500. Complete with microphone, reels (one with tape), battery clip and connector, lighter plug plus 12 volt power cord. Shpg. wt., 27 lbs. Net 199.45
RK-423WX

1010 STEREO MATE FOR T-1515-4

The Model 10-10 is a second channel amplifier for the T-1515 and T-1616 tape recorders. Self-contained hi-fi amp and speaker combination with 10-watt peak power output from a push-pull amplifier and 4-tube circuitry. Special 6x9" dual cone speaker utilizes built-in crossover network for distortion-free lows and sharp highs. Freq. response 30-10,000 cps; separate volume and tone controls. Use with any stereo tape recorder or phono, or in conjunction with a tuner. Size: 6½x12½x12". Shpg. wt., 9 lbs. Net 37.50
RK-422W

SAVE \$5.50 — SPECIAL COMBINATION OFFER

Model 1515-4 Stereo Tape Recorder plus 10-10 Mate. Net 205.95
SP-200WX

BUY ON TIME—NO MONEY DOWN. SEE PAGE 54.

LAFAYETTE RADIO ELECTRONICS PAGE 17



SUPER VALUES • TAPE RECORDERS LOWEST PRICES

NEW!

LAFAYETTE 4-TRANSISTOR PUSH-BUTTON TAPE RECORDER

For Home, School and Office!



WAS 29.95
NEW SENSATIONAL
LOW PRICE
22.50
NO MONEY
DOWN



QUANTITIES LIMITED

- Lightweight—A mere 2 lbs.
- Records and plays up to 20 minutes with 1 Standard 3" Reel
- Pushbutton Play, Rewind, Off
- Battery operated
- Completely Portable—Take it with you Anywhere

A real triumph in miniature recorders. Space age printed circuitry using a 4 transistor push-pull amplifier and built-in oval 2 1/2 x 4" PM Speaker provides quality sound. Light weight makes it ideal for travel, business use. Has all the most wanted features. Convenient push-button fast Rewind, Off and Play controls. Record safety interlock prevents accidental erasure of tape; volume control is independent of Off switch; erases automatically in record position. No need for AC adapter; operates on 2 inexpensive batteries. Inputs for microphone and earphone for private playback. Designed for maximum tape economy, the RK-133 employs a half-track tape head—upper half is recorded first and turning over tape records lower half. Plays 10 minutes per side with standard tape—more with 1/2 mil long play tape. The handsome two-tone plastic case features a sloping speaker grille which faces front for optimum sound and a snap open top for fast, easy tape loading. Power is supplied by 1 standard 1.5v standard flashlight cell and one 9v transistor battery. Supplied with crystal lapel microphone, magnetic earphone, batteries, 200 ft. 3" reel of tape and an empty reel. Dimensions: 8Wx3 1/2 Hx7 3/8 D. Shpg. wt., 4 lbs. Imported

REPLACEMENT BATTERIES FOR RK-133

BA-2 9 volt transistor battery	ea. Net	.39
BA-157 1.5 volt	ea. Net	.13

Technicorder

6 TRANSISTOR 2-SPEED MINIATURE PUSH-BUTTON TAPE RECORDER



79.50
NO MONEY DOWN

6 TRANSISTORS PLUS THERMISTOR FOR HIGH GAIN

IDEAL FOR OFFICE DICTATION

- Weighs Only 6 lbs. With Batteries
- Fully Transistorized—6 Transistors plus 1 Thermistor
- Records & Plays Up to 64 Minutes
- Dual Track
- Two Speeds—3 3/4 ips & 1 7/8 ips
- Push Button Controls
- Built-in Speaker
- Use Anywhere—Powered By 4 Inexpensive Flashlight Batteries
- Rugged Dynamic Microphone
- Special Synchro-rod Synchronized Tape Speed With Your 8mm Home Movies

Employs the most advanced transistor circuitry (6 transistors plus 1 thermistor). Operation is accomplished entirely by push-button with rewind, stop, play and record functions, furnished by 3 simple push-button controls. In addition as a safety feature, a special record button is provided to prevent accidental erasure. The correct recording level and battery condition is given by a VU meter located on the front panel. Convenient volume control adjustment with jacks external speaker and microphone are easily accessible at the side. For home movie fans a specially designed Synchro-rod is provided, which, when screwed into the capstan allows synchronizing the speed of the RK-126 with that of your 8mm projector. Two speeds, 3 3/4 and 1 7/8 are provided, with speed changes easily accomplished by means of a simple capstan adjustment. Designed for maxi-

mum tape economy, the Technicorder utilizes precision dual track heads (1 erase plus 1 record/playback) to provide record/playback time at 3 3/4 ips for 16 minutes per single track and 32 minutes per dual track; at 1 7/8 ips time is extended to 32 minutes per single track and 64 minutes per dual track. Exceptional fidelity and sound quality are achieved by means of a specially developed 2 3/4 x 8 1/2" oval speaker and AC recording bias system, with a signal/noise ratio of -49 db. Housed in an attractive tan and black hi-impact poly-vinyl case, the Technicorder features a handy snap-open plexiglass top for fast, efficient tape loading. Supplied complete with shoulder strap, dynamic microphone and case, 3" reel of tape and empty reel, batteries, splicing tape and extension speaker cord. Size: 3Hx9 1/2 Wx7 3/8 D Imported



SUPPLIED WITH THE ABOVE



OPTIONAL ACCESSORIES

TECHNICORDER ACCESSORIES

RK-216 AC Adaptor for 115V, 60 cycles AC. Shpg. wt., 3 lbs.	Net	17.95
RK-128 Telephone Pickup. Shpg. wt., 1/2 lb.	Net	3.95
RK-129 Foot Switch for dictation. Shpg. wt., 1 1/2 lbs.	Net	4.95
RK-131 Mike w/Remote Switch for RK-126 Technicorder	Net	7.95
RK-149 Leather Carrying Case	Net	4.95
RT-20 Tape—3" reel of 300 ft. 1/2 mil nylon tape. Shpg. wt., 1 1/2 lb.	Net	.69
BA-157 Replace Batt. for RK-126, 4 reqd. Shpg. wt., 4 ozs.	Net ea.	.13

LAFAYETTE RK-138 2-SPEED 4-TRACK TAPE RECORDER

SECOND PREAMP for STEREO PLAYBACK



SPECIFICATIONS:
Response: 50-10,000 cps. Wow & Flutter: less than 0.3%. Signal-to-Noise Ratio: 40db. Outputs: Include 2 output jacks — 1) second-channel external amplifier. 2) external speaker.

- Plays Back 4-Track Stereo & Records Dual Track Monophonically
- Two Speeds—7 1/2 ips & 3 3/4 ips
- Accepts Up to 7" Reel
- Has 2 Playback Preamplifiers
- Neon Recording Level Indicator

SUPER SPECIAL!

Reg. 99.95 **79.95** NO MONEY DOWN

MADE IN U.S.A.

Loaded with features, precision engineered and built to last, this fine Lafayette tape recorder must be classified a best-buy by any standards. Designed for complete flexibility, the RK-138 offers both stereo and monophonic facilities. In addition to being able to record and play back 2-track monaural material, through its own speaker and amplifier, you can use the RK-138 for 4-track playback of the latest stereo tapes through your own component stereo system. Or, if you wish, use its self contained 6-watt amplifier and speakers (5" woofer, 4" tweeter with electronic crossover) as a second stereo channel in association with your monaural hi-fi system, radio, T.V., or with RK-139 matching speaker/amplifier with patch cord for radio, T.V., or tuner input. Functional design utilizes a single, easy-to-use lever to select "Play-Idle-Record" positions. A special safety interlock in record position insures against accidental erasure of tapes. Fast rewind is accomplished by means of a lock-in lever control with tone and loudness adjusted by a concentric front panel control. Equipped with sensitive microphone 7" take up reel and patch cord. For 110-120V, 60 cycle AC operation. RK-138WX Shpg. wt., 24 lbs. Net 79.95



LAFAYETTE RK-125 4 TRANSISTOR PORTABLE TAPE RECORDER

with BUILT-IN SPEAKER

NEW SENSATIONAL PRICE

ONLY 15.95

Was 21.50



- Camera Size—Only 6Dx8 1/4 Wx2 3/4 H
- Records and Plays Up to 20 Minutes with 1 Standard 3" Reel
- Built-in Speaker and 4-Transistor Amplifier with Push-Pull Output
- Record, Rewind, Playback and Erase

A precision, full function miniature tape recorder perfect for home, office or travel; weighs only 2 1/2 lbs. and slips easily into a briefcase or handbag. Utilizing sophisticated transistor circuitry with 4 transistors, the RK-125AL contains its own 2" x 3" PM speaker and amplifier with push-pull output stage. Engineered for ease of operation, all controls readily accessible from the front panel. A single function control provides for Rewind, Stop and Forward. Volume control, Play or Record panel. Employs a half track tape head for maximum tape economy. 6Dx8 1/4 Wx2 3/4 H. Shpg. wt., 5 lbs. RK-125AL Imported

RT-20 3" REEL 300 Ft. 1/2 MIL MYLAR TAPE. Shpg. wt., 1/4 lb.	Net	15.95
BA-2 9V TRANSISTOR BATTERY. Shpg. wt., 2 oz.	Net	.69
BA-156 1.5V Battery (2 required). Shpg. wt., 2 oz.	Net	.21
	Net	.13

FREE

LAFAYETTE BONUS

of 10 valuable tape recorder accessories with the purchase of any tape recorder on this page



STEREO DELUXE TAPE SPLICER



TAPE HEAD CLEANER



TAPE HEAD LUBRICANT



TAPE HEAD THREADER



"JOCKEY CLOTH" FOR TAPES



REEL HOLDERS



3 REELS OF 7" LAFAYETTE RECORDING TAPE



TAPE EDITING & SPLICING BOOKLET



PACKAGE OF 30 ADHESIVE REEL LABELS



PACKAGE OF 12 TAPE CLIPS

SONY MODEL CS-300 STEREO RECORDER



391⁵⁰

NO MONEY DOWN

A complete 4 and 2-track stereophonic tape recording and playback system with built-in stereo preamplifiers and stereo playback monitors. Recording and playback also for 2 and 4-track monophonic tapes. Two speeds 7 1/2 & 3 3/4 ips. Two built-in VU meters insure accurate playback and record levels for professional sounding tapes. INPUTS: Stereo or monophonic 4 and 2-track recording, from 2 or more microphones. AM/FM stereo tuners, stereo record players and tape players. Separate level controls for microphone and auxiliary inputs provide mixing facilities for sound-over-sound recordings. Low impedance outputs to match external preamp or power amplifier inputs. An instant Stop Lever insures precise editing and cueing. Accidental erasure of important tapes is prevented by a Safety Lock Recording Button. Bass compensation can be chosen from front panel. SPECIFICATIONS: Frequency response: 30-18,000 cps at 7 1/2 ips; 30-13,000 cps at 3 3/4 ips. Signal-to-Noise Ratio 50 db or more per channel. Flutter and Wow—less than 0.15% at 7 1/2 ips; less than 0.25% at 3 3/4 ips. Harmonic distortion less than 2% at 3 db below rated output. Tubes: 2-12AD7, 2-6AU6, 2-6AQ5, 1-12BH7, 1-6CA4. Size: 17Wx8Hx14"D. For 117 volts 60 cps AC. Includes carrying case with 2 built-in speakers and 2 F-7 dynamic microphones, imported. Model CS-300 plus free Lafayette Bonus of 10 valuable tape recorder accessories listed at the top of this page. RK-308WXM Net 391.50

NEW SONY MODEL 464-CS STEREO RECORDING AND PLAYBACK TAPE SYSTEM

- Complete Record/Playback Electronics
- Built-in Monitor Speakers
- Record/Playback 4-Track Stereo and Mono Tapes
- Sound-on-Sound Recording Facilities



229⁵⁰

NO MONEY DOWN

Completely portable stereo recording and playback system utilizing the famous Sony belt-free idler drive wheel mechanism and dynamically balanced capstan-flywheel assembly for maintaining flutter and wow specifications to less than 0.2% @ 7 1/2 ips. Other specs: freq. resp., 30-18,000 cps; bias freq., 80kc — push-pull oscillator circuit; signal-to-noise ratio, better than 50 db. Features push-button channel selector switches and 2 high level line inputs for FM stereo recording. Supplied with 2 F-7 dynamic microphones, imported. Model 464-CS plus Free Lafayette Bonus of 10 valuable tape recorder accessories listed at the top of this page. RK-307WXM Net 299.50

SONY MODEL 101 TRANSISTORIZED DUAL-TRACK TAPE RECORDER



- 2-Speed 7 1/2 & 3 3/4 ips
- Fast Forward & Rewind
- Lightweight

99⁵⁰

NO MONEY DOWN

An AC powered bantam-weight dual-track tape recorder which incorporates the latest design in transistor circuitry. Ideal for those who require low cost, high fidelity reproduction, the model 101 records and plays back monophonic 2-track tape with a frequency response of 50-12,000 cps at 7 1/2 ips and 50-8,000 cps at 3 3/4 ips. Flutter & wow, less than 0.25% at 7 1/2 ips. Imposing features include: a VU meter and volume control; inputs for mike and auxiliary units; external speaker output, tape lifters and built-in AC power supply. Plugs directly into wall outlet. Complete with 7" reel, dynamic mike, speaker and case. Size: 12Wx6 1/2Hx10"D. Shpg. wt., 18 lbs. Imported. Model 101 Plus Free Lafayette Bonus of 10 valuable tape recorder accessories listed at the top of this page. RK-309WXM Net 99.50

NORELCO CONTINENTAL '400' 4-TRACK STEREO RECORDER



299⁹⁵

NO MONEY DOWN

The new "400" model stereo tape recorder, guild-crafted by Philips of the Netherlands, reflects professional quality at a modest price. It is a recorder that was designed to be used and listened to by the music-lover, studio-recording, and high fidelity enthusiast. Four-track stereophonic recording and playback with dual stacked heads plus 4-track monophonic operation. Three tape speeds: 7 1/2, 3 3/4, 1 7/8 ips. FREQUENCY RESPONSE: 50-18,000 cps at 7 1/2 ips, 50-14,000 cps at 3 3/4 ips, 50-7,000 cps at 1 7/8 ips. Signal-to-Noise ratio 55 db or better. Cross-talk 55 db down. Instantaneous locking device for pauses in recording or listening. Wow and flutter less than 0.3% at 3 3/4 ips. Dubbing facilities for producing sound-on-sound. Self-contained record and playback amplifiers including dual hi-fi preamps. SPECIAL CONTROLS: For recording—ganged mike volume, and ganged radio/phone volume. For playback—2-channel tone (individual concentric controls but friction ganged); ganged volume and ganged channel balance. INPUTS: One 2-channel input for stereo microphone; two 2-channel inputs for stereo tuners or phonos. OUTPUTS: For extension speakers (2); for external amplifiers (2); for stereo headphones (1). MIXING CONTROL for electronic mixing of phono and mike inputs. TUBES—2-6F86, 3-ECC83, 2-EL84, 1-EM84. For 117 volts, 60 cps. AC. Size: 18 1/2x15 1/2x11 1/2". Shpg. wt., 55 lbs. Continental "400" Recorder (imported from Holland). Plus Free Lafayette Bonus of 10 valuable tape recorder accessories listed at the top of this page. RK-402WXM Net 299.95

NEW Bell PROFESSIONAL MODEL T-347 STEREO TAPE DECK



313⁵⁵

NO MONEY DOWN

Features built-in stereo record, playback preamplifier for making 2-track and 4-track stereo tapes, off-the-air stereo recordings, copy stereo tapes and discs etc. Professional features include 3 heavy-duty 4-pole motors. Wow and flutter less than 0.2%. Frequency response of 18-16,500 CPS ± 3 db @ 7 1/2 CPS & 18-15,000 CPS ± 3 db @ 3 3/4 IPS (overall record-playback). Playback only extends to 20,000 cps. Signal-to-noise ratio—better than 50 db. Maximum reel size 7". Preamp has 4 inputs—2 high impedances for mikes; 2 high impedance for amps, tuners, etc. 4 outputs and 6 tubes. Has front panel mike jacks, pushbutton speed, off and pause selection, echo effect, off-the-tape monitoring, "DuoSound" and sound-on-sound. Index counter, 2 VU meters. Mounts anywhere, plays in any position. Wood grain finish. Size 15 1/4Wx13 1/2" front-to-back; 5" below mounting surface, 2" above mounting surface. (Includes Preamp). Wt., 23 lbs. Model T-347 Plus Free Lafayette Bonus of 10 valuable tape recorder accessories listed at the top of this page. RK-306WXM Net 313.55

CONCORD MODEL 880 PROFESSIONAL STEREO TAPE RECORDER



- Contains 3 Separate Heads—Stereo Erase, 4-Track Stereo Record, 2-Track & 4-Track Stereo Playback
- Individual Tone & Volume For Each Channel
- 3 Speeds—1 7/8 ips, 3 3/4 ips & 7 1/2 ips
- Two 7" Speakers For Stereo

349⁵⁰

NO MONEY DOWN

A completely self-contained portable stereo high fidelity music recording and playback system which may be used with its own speakers and amplifiers or your present music system. Employs 3 professional quality, laminated tape heads—stereo erase, 4-track stereo record, 2-track and 4-track stereo playback. Features include: sound-on-sound recording, push-button controls, individual recording level controls with VU recording level meters for each channel, separate tone and volume controls for each channel, master volume control and digital tape counter. Interlocked recording controls prevent accidental erasure. Specifications: Tape Speeds: 1 7/8 ips, 3 3/4 ips; Frequency Response: 7 1/2 ips—30-20,000 cps, 3 3/4 ips—30-15,000 cps, 1 7/8 ips—50-8,000 cps; Signal-to-noise ratio: Better than 60 db. Flutter and wow: less than .15% at 7 1/2 ips. Output Level: 10 watts (5 watts each channel). Reel Size: 7" maximum. Complete with 2 mikes, 7" reel. 19 1/2Wx11Hx7"D. Shpg. wt., 50 lbs. Imported. Model 880 Plus Free Lafayette Bonus of 10 valuable tape recorder accessories listed at the top of this page. RK-161WXM Net 349.50

WEBCOR MODEL ED-2250 REGENT CORONET STEREO TAPE DECK




189⁹⁵

NO MONEY DOWN

A new stereophonic, high fidelity tape deck for 2 and 4-track stereo/monaural record/playback. Two built-in pre-amplifiers, one for each channel, with cathode follower recording and playback. Exclusive new Webcor "Synchro-Track" provides for simultaneous recording and playback. Three tape speeds: 7 1/2, 3 3/4 and 1 7/8 ips. Frequency response—Normal voice frequency at 17 1/2 ips. ± 2 db, 50-7,000 cps at 3 3/4 ips. ± 3 db, 40-14,000 cps at 7 1/2 ips. Wow and flutter 0.2% at 7 1/2 ips. Signal-to-Noise Ratio greater than 50 db per channel. SPECIAL FEATURES: 1/4 track stereo record; 1/2 and 1/4 track stereo playback; 4-pole, heavy-duty, electronically balanced motor; Belt driven tape transport, editing and cueing key; Record safety lock; Automatic shut-off of amplifier and recorder mechanism; VU meter to indicate correct recording level for each channel; individual volume controls; "Dual Gang" Bass and Treble controls. INPUTS: 2 microphone, high-level input jack. OUTPUT: External amplifier (2 channels). Will take 3, 5, or 7 inch reels of tape. Numerical type tape counter enables desired locations on tapes to be found quickly. Angled steel mounting brackets allow unit to be operated in vertical or horizontal positions. 6 tubes plus a dual selenium rectifier. For 117 volts, 60 cps AC. Size 7 1/2Hx15Wx15"D. Shpg. wt., 26 lbs. Model ED-2250 Plus Free Lafayette Bonus of 10 valuable tape recorder accessories listed at the top of this page. RK-377WXM Net 189.95 RK-374W Carrying Case for ED-2250 Net 32.50

TECO RP-100 TAPE DECK



399⁹⁵

NO MONEY DOWN

- Separate Transistor Stereo Record and Playback Amplifiers
- 1/4 Track Heads For Erase/Record/Playback
- Electrical Push-button Control
- New Hysteresis-Synchronous Capstan Motor

A professional studio-type tape deck which features 1/4 track heads for stereo record and playback plus off-the-tape monitor and sound-on-sound recordings. Separate transistor record and playback amplifiers, 3 motors including a new hysteresis-synchronous capstan motor; dual recording meters and electronic control facilities for mixing etc. Wow & Flutter: under 0.15% rms @ 7 1/2 ips; Frequency Response: 30-15,000 cps ± 2 db @ 7 1/2 ips, 30-10,000 cps ± 2 db @ 3 3/4 ips. Signal-to-Noise ratio 55 db. 2 speeds. For 110-120 v 60 cycles AC. Size: 15 1/4Wx13 3/8Hx7"D. Shpg. wt., 28 lbs. Model RP-100 Plus Free Lafayette Bonus of 10 valuable tape recorder accessories listed at the top of this page. RK-333WXM Net 399.95 RK-277WX CC-2 Carrying Case. Shpg. wt., 13 lbs. Net 29.95

SONY MODEL 464-D STEREO RECORDER

- 4-Track Stereo & Mono Record/Play
- Built-in Record-Play Preamps
- 2 Speeds—7 1/2 & 3 3/4 ips
- Remote Channel Integrator Control Unit
- Sound-on-Sound



199⁵⁰

NO MONEY DOWN

The compact 464-D is a 2-Speed 4-track stereo and monophonic record/play tape recorder designed for custom installation. Contains built-in record and play preamplifiers with frequency response of 40-15,000 cps. @ 7 1/2, 40-12,000 @ 3 3/4 ips and bias frequency of 60 Kc. Features include: belt-free drive mechanism, sound-on-sound and sound-with-sound switch, push-button mode selector for stereo or 4-track mono record and playback. Signal-to-noise ratio—better than 50 db. Special compact accessory panel permits easy accessibility to microphone inputs and sound-on-sound switching—less case. Size: 13 1/4Wx6Hx11 3/4"D. Shpg. wt., 23 lbs. Imported. Model 464-D Plus Free Lafayette Bonus of 10 valuable tape recorder accessories listed at the top of this page. RK-289WXM Net 199.50



SAVE WITH EXCLUSIVE LAFAYETTE HI-FI

now from Great Britain... **LAFAYETTE PERFORMANCE, DESIGN & VALUE**

THE LAFAYETTE SOVEREIGN 12 ...


3-Way High Performance

High-Fidelity Speaker



SK-210

49⁵⁰
NO MONEY DOWN



- 2 1/4 lb. Ceramic Magnet
- "Rigidflex" Free-Edge Cone Suspension — No Standing Waves Or Surround Resonances
- 3-Way Triaxial Design Provides Unequaled Smooth Low, Mid & High Frequency Coverage
- Special Low-Resonance Woofer Cone, Stiff Mid-Range Radiator.
- Compression-Driver Tweeter
- Frequency response: 30-20,000 C.P.S.
- Fundamental Resonance: 35 Cycles
- Power Handling Capacity: 30 Watts
- Voice Coil: 3 Inches
- Wide Dispersion Tweeter, Self Aligning Aluminum Voice Coil & Diaphragm
- High Efficiency With Low Distortion
- Superb Transient Response
- Impedance: 16 ohms
- Entirely New Unitized Die-Cast Frame

ONE OF LAFAYETTE'S FINEST 12" SPEAKERS

Constructed by master English craftsmen to Lafayette's rigid specifications, the "Lafayette SK-210 Sovereign 12" must be considered among the very finest 12" speakers available. Engineered to satisfy the most discriminating listener, the SK-210 achieves full 3 speaker performance through its advanced triaxial design. Woofer, midrange radiator and tweeter are all axially mounted within a single rigid, unitized die cast frame, to provide an integrated, efficient wide range speaker system. Construction features incorporate a 3 inch voice coil with an exclusive "Rigidflex" cone-bonding and cone-edge treatment process to form a virtually free-edged cone suspen-


sion. All irregularities of the audible frequency spectrum are smoothed out with standing waves and surround resonances eliminated. High efficiency and low distortion are further assured by use of a specially designed 2 1/4 lb. ceramic magnet. The quality of the Sovereign 12" is immediately evident in its uncompromising performance. Frequency response is 30-20,000 cps with a free-air woofer cone resonance of 35 cps. Bass response is tight and solid without boom or hangover to achieve a phenomenal realism. At 2000 cps, frequencies are channeled into a stiff-coned mid-frequency radiator by means of a smooth mechanical

crossover. High frequencies are reproduced with a silkiness and naturalness to beyond the limits of human hearing by means of a compression driver tweeter. This superb new tweeter incorporates a rigid, die cast, flared, hyperelliptical horn, a 1" diameter aluminum voice coil and diaphragm in a self-aligning assembly with air chamber and phase equalizer. A built in crossover allows the tweeter to take over at 5,000 cps and is provided with a high-frequency L-pad level control with attractive escutcheon and knob. Shpg. wt., 15 lbs. Recommended with Eliofoflex enclosures. SK-210 Net 49.50

NOW FROM LAFAYETTE... THE "BIG 8"

34⁹⁵

NO MONEY DOWN



ONLY 8" SPEAKER WITH 1 1/4 LB. MAGNET

THE LAFAYETTE SK-212... A new 8-Inch 3-Way High-Fidelity Speaker with Performance and Capabilities of a 12-Inch Speaker

ONLY 8", BUT LOOK AT THESE SPECIFICATIONS AND PERFORMANCE:

- FREQUENCY RESPONSE: 35-20,000 CPS
- CONE RESONANCE: 45 CPS
- MAGNET: 1 1/4 LB. ALCOMAX
- VOICE COIL: 3" DIAM.
- FLUX DENSITY: 175,000 GAUSS
- IMPEDANCE: 16-OHMS
- POWER HANDLING CAPACITY: 25-WATTS
- 2,000 CPS MECHANICAL CROSSOVER 5000 CPS ELECTRONIC
- CROSSOVER WITH BUILT-IN BRILLIANCE CONTROL
- SPECIALLY DEVELOPED "RIGIDFLEX" FREE EDGE CONE SUSPENSION
- DIE-CAST FRAME
- NEW COMPRESSION-DRIVER TWEETER

LAFAYETTE'S "BIG 8"—The remarkable quality and performance of this new speaker provide it with the largest 8" of sound we've ever heard! With almost uncanny ability, the SK-212 easily re-creates the entire musical spectrum from 35 to 40,000 cps; achieving a standard of natural balance distortionless performance and superb transient response normally associated with larger costlier speakers. Every musical tone is there—from powerful orchestral passages and deepest organ tones to the most delicate of solos. Precision engineered to meet Lafayette's uncompromising specifications and constructed by master English craftsmen, the SK-212 incorporates the design and construction features you'd expect to find in the finest speakers. This excellence of design is best demonstrated by its 3 inch voice coil, 1 1/4 lb. Alcomax magnet, and special "rigidflex" free edge cone suspension. Woofer, midrange radiator and tweeter are axially mounted to provide wide range speaker performance. A mechanical crossover separates bass and midrange frequencies at 2,000 cycles while 5,000 cycle electrical crossover provides a smooth transition from midrange to a newly developed compression driver tweeter. A high frequency level control allows matching of sound to individual taste and room acoustics. Recommended with Eliofoflex enclosures. SK-212WX Shpg. wt., 11 1/2 lbs. Net 34.95

LAFAYETTE SK-130 8" WIDE-RANGE HI-FI SPEAKER

Check These Phenomenal Specifications

- ✓ Frequency Response: 40-18,000 cps
- ✓ Magnet Weight: 1 lb. High Efficiency Alcomax Magnet
- ✓ Flux Density: 13,500 Maxwells
- ✓ Power Handling Capacity: 15 Watts
- ✓ Cone Resonance: 55 cps
- ✓ Voice Coil: 1 Inch
- ✓ Impedance: 16 Ohms


ASTONISHING FIDELITY from a speaker of this size and modest price. Designed and finished with typical British craftsmanship, the SK-130 features an especially designed hyperbolic cone with a plastic surround suspension for wide compliance performance. Bass response is robust and full bodied, while the mid-range and highs are virtually transparent, with never a trace of shrillness or harshness.

The excellent wide-range response of the SK-130 make it ideal for stereo when used in pairs or perfect for use as a high quality extension speaker. Overall Diam. 8 1/2" x 4" Deep. Baffle cut-out 7 1/4". Rigid vibration-free frame is equipped with screw type terminals. See Eliofoflex enclosures recommended for this speaker elsewhere in catalog. SK-130 Shpg. wt., 3 lbs. Net 12.95

12⁹⁵

the Revolutionary LAFAYETTE

Sphericon



SK-146

22⁵⁰

HIGH FREQUENCY SUPER TWEETER

- Frequency response from 3,000 cps to beyond 40,000 cps
- Uniform dispersion over 120 degrees in all directions
- High-sensitivity allows use with any 4-16 ohm speaker
- Requires no high voltage or power supply
- Built-in 3,000 cycle crossover network

Achieve unequalled brilliance and musical warmth from your present speaker system or the system you're now planning. The Lafayette's Sphericon is an entirely new concept in tweeter design. Equipped with a built-in 3,000 cycle crossover network and featuring a specially designed domed phenolic diaphragm with spherical diffractor. The Sphericon produces a virtually linear response from 3,000 cps to beyond 40,000 cps, ± 2 db. to 22,000 cps. High frequencies are radiated in a 120° pattern in all directions, vertically as well as horizontally—with absolutely no trace of stridency or harshness. Unlike electrostatic tweeters the "Sphericon" is highly efficient and may easily be matched with any speaker or speaker systems... especially the low efficiency high compliance type. Precise matching of the "Sphericon" with today's low and medium efficiency speaker is accomplished by means of a special built-in attenuator designed not to affect or lower the efficiency of the woofer. As a result less amplification is needed assuring lower distortion. Power capacity is 30 watts. May be employed with any 4-16 ohm speaker. Beautifully styled with an acoustically designed gold anodized grill set in a sturdy satin black plastic case. Dimensions: 9x4x2 1/2" D. SK-146 Shpg. wt., 4 lbs. Net 22.50

ROYAL DANISH 12" DUAL CONE SPEAKER

• HIGH FLUX DENSITY

7⁹⁵



Lafayette brings you this fine imported high fidelity speaker at a fraction of the price you would expect to pay for so much quality. Two cones are mounted on a pay for so much quality. Two cones are mounted on a single axis, and provide remarkable wide range frequency response from 45 to 14,000 cps. Reproduction of program material is exceptionally lifelike throughout the entire range. An exclusive, special formula cone treatment eliminates cone rim resonance and distortion. Also, the damping effect improves transient response and prevents "hangover." Overall depth, 5 1/2". Completely enclosed, 1" diameter voice coil with an impedance of 6 ohms. Shpg. wt., 6 lbs. SK-86. 12" Dual Cone Hi-Fi Speaker Net 7.95

LAFAYETTE-GOODMAN'S SK-111 15", 1 1/4 LB. MAGNET SPEAKER

QUANTITIES LIMITED!

Special Sale Price

37⁵⁰

NO MONEY DOWN

Reg. 1961 Catalog Price 54.50

Frequency Response: 30-20,000 cps
Cone Resonance: 25 cps
Power Rating: 35 watts
1 1/2" Voice Coil
7" Deep, 15 1/2" Dia. Shpg. wt., 25 lbs.
SK-111WX Net 37.50



CONE TYPE METAL-CASED HI-FI

MK-3

TWEETER

5⁹⁵



- FREQUENCY RESPONSE 2,000-16,000 CPS
- MAXIMUM 20 WATTS • IMPORTED TO SAVE YOU MONEY

It is particularly efficient in the higher end of the audio spectrum where ordinary cone tweeters tend to lose clarity and volume. With this tweeter added to your present system, you will be able to hear all the fine transients and high notes of the upper register as they were actually recorded. Entirely enclosed in metal case with base for standing by itself, or mounting on a flat surface. Bracket is supplied for mounting on panel or in cabinet. Requires crossover network such as Lafayette LN-2, Diameter 3". Depth 2 1/4". Voice coil impedance 8-16 ohms. MK-3 Hi-Fi Tweeter—Shpg. wt., 4 lbs. Net 5.95


THE LAFAYETTE TRIHELIX®

THE WIDELY ACCLAIMED LAFAYETTE SK-58 12" COAXIAL SPEAKER

3 COMPLETELY INDEPENDENT SPEAKERS WITH 3 SEPARATE VOICE COILS IN A SINGLE 10" COMPACT UNIT

- Frequency Response 20 to 20,000 cps (30-18,000 cps ± 3 db)
- Revolutionary "Conical Stiffener"
- Eccentric Baffle Mounting of Midrange & Tweeter Eliminates Interaction Between Speaker Cones
- Built-in Crossover Network and Brilliance Control
- Extremely Efficient
- High Excursion Woofer
- Ideal For Stereo

3250
NO MONEY DOWN



Recreates The Entire Audio Spectrum With Concert Hall Faithfulness—The Lafayette "Trihelix" represents a major breakthrough in three way speaker design. Fresh engineering concepts have resulted in a single 10-inch speaker designed expressly for use in bookshelf size enclosures, that delivers a quality of performance with the unmistakable feel, presence and clarity of a 3-way speaker system. The "Trihelix" is in effect a complete three-way high-fidelity speaker system, with three mechanically and electronically independent speakers mounted within a single 10-inch frame. Although they are individual units the 2-inch tweeter and 5-inch midrange speakers have been especially designed to compliment the woofer. Special treatment of the cones and cone edges with polyester resins provides an even distribution of mid and high frequencies without peaks or resonances. To minimize interaction between the three cones both the midrange and tweeter units are mounted eccentrically or off center in relation to the woofer. In addition the midrange and tweeter are completely enclosed by a specially designed baffle. These unusual design features result in effectively eliminating intermodulation distortion due to interaction between woofer, midrange and tweeter cones—a

common fault in conventionally designed 3-way speakers. The specially treated woofer cone employs a revolutionary "conical stiffener" located at the apex of the cone in order to stiffen the diaphragm and eliminate "break-up," thus providing a true piston action. This carefully designed cone-stiffening procedure, in addition to its very high compliance, enables the woofer to deliver a smooth, crisp, solid bass that balances naturally against a crystal clear midrange and natural treble. A built-in electrical crossover network with crossover points at 1500 cps and 5000 cps, allows each speaker to reproduce its portion of the audio range smoothly and efficiently. An adjustable brilliance control permits matching of sound to room acoustics. SPECIFICATIONS: Overall Response 20-20,000 cps (30 to 18,000 cps ± 3 db). Free Air Resonance 35-55 cps. Impedance 16 ohms. Power Rating: 20 watts Average Program Material. Crossover Points: 1500 & 5000 cps. Overall Diam: 10". Overall Depth: 7". Baffle cut-out: 8 7/8". Screw type terminals are color coded for quick easy connection of amplifier leads. Shpg. wt., 8 lbs. SK-180 10" Lafayette "Trihelix" Net 32.50 SB-62W Adaptor Board To Fit SK-180 Net .89 To 12" Cutout

Now!


OFFERED EXCLUSIVELY BY LAFAYETTE AT

Tremendous Savings

SUPERB PERFORMANCE GUARANTEED—OR YOUR MONEY BACK!

- RESPONSE 30-15,000 CPS
- SHEEPSKIN "FREE EDGE" CONE MOUNTING
- 1 1/4 LB. MAGNET WEIGHT
- 3" COAXIALLY MOUNTED TWEETER
- BUILT-IN LC NETWORK
- RATED AT 20 WATTS CONTINUOUS POWER

2950
NO MONEY DOWN



The World Renowned Original Lafayette SK 58®

Lafayette's exclusive 12" coaxial is a precision-made high fidelity loudspeaker, universally acclaimed by music lovers, hi-fi enthusiasts and professional experts alike as the greatest performance-value on the hi-fi market. It provides a truly faithful reproduction of sound without any "coloration" or distortion, its excellence being responsible for its use in innumerable high fidelity music systems today. The SK-58 incorporates such features as heavy, high flux density TSK-5 magnets for high efficiency; 3/4" wide sheepskin cone-edge suspension and special composition fibre cone material, specially treated for ultra-linear, distortion-free response; heavy rugged cast metal frame for freedom from resonances and for greater rigidity. The coaxially-

mounted 3" cone-type tweeter has a bell shaped mounting for maximum dispersion of high frequencies with no back radiation. With the built-in 3000 cps crossover network it contributes its share to the smooth delivery of the overall wide range response of 30-15,000 cps. Woofer resonance in free air is 40 cps. Speaker power handling capacity is 20 watts continuous sine wave, 35 watts peak program material. Impedance of the voice coil is 8 ohms, connections being made to chrome-plated screw terminals. Finished in gray-brown opalescent enamel, the speaker is supplied complete with "brilliance" level control. Shpg. wt., 11 lbs. SK-58W 12" COAXIAL SPEAKER Net 29.50

THE LAFAYETTE CAVALIER 12" HIGH-FIDELITY 3-WAY SPEAKER


- 1 3/4 lb. High-Efficiency "Alcomax" Magnet
- Special Design For Distortionless Performance From 30-20,000 cps.
- 1 3/4" Voice Coil
- Handles 25 Watts of Power
- Non-Resonant Rigid Frame Construction
- Crossover Complete With Brilliance Control

AN OUTSTANDING PERFORMANCE VALUE . . .

This Lafayette Cavalier 12 integrates the finest acoustic design with precise British Craftsmanship. Its advanced 3-way design with woofer, mid-range radiator and tweeter axially mounted within a specially engineered non-resonant rigid frame is capable of faithfully reproducing the complete audio spectrum from 30-20,000 cps. Construction features include a 1 3/4 lb. high efficiency "Alcomax" magnet, an especially engineered "Rigid-flex" cone-bonding and cone edge treatment process

for a virtually free-edged cone suspension, 1 3/4 inch voice coil plus a stiff-coned midrange radiator with a 2,000 cps mechanical crossover. A 5,000 cps LC crossover equipped with brilliance control channels high frequencies into a compression-driver tweeter; incorporating a rigid die cast flared hyperelliptical horn, a 1" diameter aluminum voice coil and diaphragm in a self-aligning assembly with air chamber and phase equalizer. Impedance: 16 ohms. Shpg. wt., 10 lbs. SK-211 Lafayette Cavalier 12 Net 29.95

WAS 39.95
AMAZING NOW!
LOW PRICE **29.95**
QUANTITIES LIMITED!
NO MONEY DOWN



LAFAYETTE SK-215 3-WAY 15" HI-FI SPEAKER


Custom Built in England To Lafayette's Rigid Specifications

64.50
NO MONEY DOWN

MONEY BACK GUARANTEE

YOU BE THE JUDGE
Try the SK-215WX and/or SK-216WX for 30 days. If not completely satisfied, return them/it for full refund.
*1 Year Service Guarantee

- Massive 5 lb. Ceramic Magnet
- Free-Edged Cone Suspension
- 3-Inch Long Main Voice Coil
- 12 DB/Octave Crossover Network with High Frequency level Control
- Precision Pressure-Driven Horn-loaded Tweeter with Aluminum Diaphragm & Coil



Lafayette combined the finest British craftsmanship and advanced acoustic design to bring you this outstanding 3-way 15" speaker. The SK-215WX utilizes a patented concentric twin-gap magnetic system with a massive 5 lb. Super efficient, double duty cylindrical ceramic magnet. Woofer, mid-range radiator and speaker are axially mounted to achieve unexcelled, efficient wide-range speaker performance. With a cone resonance of 25 cps, the woofer section is vacuum constructed by an exclusive process and features a virtually free-edged cone suspension that eliminates standing waves and surround resonances. An automatic mechanical crossover separates bass and mid-range frequencies at 2000 cps to a highly stable mid-range radiator. A 12 db per octave LC crossover network provides smooth transition at 5000 cps from mid-range to a precision pressure-driven horn-loaded tweeter employing an aluminum diaphragm and coil in a self-aligning assembly with air chamber and phase equalizer. This cross-

over has a high frequency constant impedance L-pad level control for matching of sound to room acoustics and individual listening tastes. SPECIFICATIONS: Cone Resonance, 25 cps; Magnet Weight, 5 lbs.; Magnetic Flux Density, over 250,000 Maxwells; Crossover Frequencies, 2000 and 5000 cps; Power Capacity, 50 watts; Woofer Voice Coil Diameter, 3 inches; Tweeter Voice Coil Diameter, 1 inch; Impedance, 16 Ohms. Dimensions: 6 1/2" overall depth; 15 1/2" diameter. Shpg. wt., 30 lbs. SK-215WX Net 64.50

NEW! LAFAYETTE SK-216 3-WAY 12" HIGH FIDELITY SPEAKER

12" speaker with same specifications as above, Shpg. wt., 25 lbs. SK-216WX Net 57.50

*Repairs which become necessary due to manufacturing defects will be made by Lafayette at no charge during the Guarantee period.

LAFAYETTE "MINUETTE" HIGH-FIDELITY SPEAKER SYSTEM



Room Filling Music Everywhere in Your Home!

12.50
SINGLY

TWO FOR STEREO
23.50


- Shelf Size — 8 1/4 D x 15 3/4 L x 5 7/8 H
- Genuine Walnut Finish on 4 Sides
- Complete with 6' Extension Cable and Phone Plug

An exceptional speaker value . . . the Lafayette "Minuette" Hi-Fi Speaker System will bring music to any room in your home — and for a remarkably low cost. Designed for use where space is at a premium — ideal for the small apartment or listening area. Expand your stereo system to other areas of your home . . . easily used in the den, kitchen, patio or bedroom. Employs a specially designed 5x7" speaker in a rear loaded reflex type enclosure. Provides an exceptionally fine musical quality yet measures only 8 1/4 D x 15 3/4 L x 5 7/8 H — small enough to fit anywhere. Superb Walnut finish on 4 sides allows placing speaker horizontally or vertically. Frequency Response 100-12,000 cps. Impedance 8 ohms. Rated at 10 watts. Supplied with 6 ft. of extension cable and phone plug. SK-181 Shpg. wt., 5 1/2 lbs. Net 12.50 Save — Buy two for stereo. Shpg. wt., 11 lbs. Set of two Net 23.50

BUY ON TIME—USE LAFAYETTE'S EASY-PAY BUDGET PLAN

LAFAYETTE RADIO ELECTRONICS PAGE 21

COMPARE! FOR VALUE PERFORMANCE



64⁵⁰
NO MONEY DOWN

FINISHED ON 4 SIDES
Adapts to any room arrangement. Place horizontally on shelves or vertically on the floor.

ELIPTOFLEX®

COMPLETE SPEAKER SYSTEM with ENCLOSURE

NOW IT IS POSSIBLE TO HAVE THE ADVANTAGES OF A HIGH EFFICIENCY 12" SPEAKER IN A BOOKSHELF SIZE ENCLOSURE.

SPECIALLY DESIGNED 12" COAXIAL SPEAKER WITH SHEEPSKIN CONE EDGE SUSPENSION AND 1¼ LB. MAGNET PROVIDE A RESPONSE FROM BELOW 30 TO 15,000 CPS.

ENCLOSURE BEAUTIFULLY FINISHED ON FOUR SIDES IN HAND RUBBED VENEERS.

The "Eliptoflex" is the result of an intensive research program whose 3-fold purpose was to:

Develop a speaker system that would meet space requirements of stereo.

Utilize the full advantages of efficient 12" speaker performance.

Provide optimum performance without use of large wattage expensive amplifiers.

The Results Were Remarkable... The Eliptoflex utilizes a unique elliptical port which broadens frequency response and provides better transient response. A specially engineered diffracting ring eliminates cancellation effects between front and rear radiation. These engineering advances are coupled with the famous Lafayette free edge SK-58 12" coaxial speaker 3" cone type tweeter, 1¼ lb. TSK-5 high flux density magnet and special ¾" wide sheepskin cone-edge suspension and built-in crossover network level control.

"Eliptoflex" achieves a degree of natural smoothness, low-distortion and rich robust bass hitherto found only in large enclosure speaker systems or inefficient bookshelf speakers many times its price requiring high powered amplifiers. Due to its highly efficient design characteristics the "Eliptoflex" does not require costly high wattage amplification.


The "Eliptoflex" speaker system is beautifully finished on 4 sides in a variety of hardwood veneers for attractive room placement either horizontally or vertically. Dimensions are 14"Hx23-7/16"Wx13-5/16"D. Shpg. wt., 35 lbs.

SY-381WX "Eliptoflex" Speaker System Mahogany	Net 64.50
SY-382WX "Eliptoflex" Speaker System Walnut	Net 64.50
SY-383WX "Eliptoflex" Speaker System Blonde	Net 64.50
SY-384WX "Eliptoflex" Speaker System Oiled Walnut	Net 64.50
SY-392WX "Eliptoflex" Speaker System Unfinished furniture grade birch	Net 59.50

ELIPTOFLEX ENCLOSURE LESS SPEAKER—FINISHED ON 4 SIDES

CAB-83WX "Eliptoflex" Enclosure—Mahogany	Net 36.50
CAB-84WX "Eliptoflex" Enclosure—Walnut	Net 36.50
CAB-85WX "Eliptoflex" Enclosure—Blonde	Net 36.50
CAB-86WX "Eliptoflex" Enclosure—Oiled Walnut	Net 36.50
CAB-124WX "Eliptoflex" Enclosure—Unfinished Birch	Net 29.50

HI-FIDELITY WOOFERS



SK-67W*

SK-68

2395

1550

15" HI-FI WOOFER

• 2 LB. ALNICO MAGNET
• 20 TO 5000 CYCLES—35 WATTS
This efficient 15" low frequency woofer incorporates many exclusive features. For original equipment or replacement, it provides highly efficient extended low-frequency response. Ideal for assembling 2- and 3-way speaker systems. Handles 35 watts of audio power. Frequency response ± 2 db 20 CPS to 1000 CPS, and ± 5 db from 20 CPS to 5,000 CPS with proper baffling. Voice coil dia. 2", impedance 8 ohms, 31.5 oz. Alnico V magnet. Finished in beautiful brown enamel. Cone is seamless type, permanently bound to voice coil. Has 4-way binding posts. Shpg. wt., 13¼ lbs. Cone Resonance 45 cycles. Net 23.95 SK-67W*

12" HI-FI WOOFER

21.5 OZ. ALNICO V MAGNET—25 WATT
Provides efficient, extended low-frequency response of ± 5 db from 35 to 8000 CPS, and features 25 watts of power handling capacity. Perfect for high-fidelity installations or for modernization of older equipment. Ideal for assembling 2- and 3-way speaker systems at a budget price. Enclosed magnet structure—completely dust-proof. Compliance of outer cone and inner spider carefully calculated for best bass response. 21.5 oz. Alnico V magnet, 1½" dia. voice coil, 8 ohm impedance. All exposed surfaces are finished in beautiful brown enamel. Has 4-way binding posts. Cone Resonance 50 cycles. Shpg. wt., 8 lbs. Net 15.50 SK-68

HIGH FREQUENCY TWEETER WITH ACOUSTIC LENS

DIRECT IMPORTATION MAKES THIS PRICE POSSIBLE!

• FREQUENCY RESPONSE FROM 2000 CPS TO BEYOND AUDIBILITY
• LOUVERED ACOUSTIC LENS FOR UNIFORM SOUND DISPERSION
• HANDLES 25 WATTS OF POWER—PRICED EXCEPTIONALLY LOW

New high frequency tweeter featuring a louvered acoustic lens for uniform sound dispersion and capable of handling up to 25 watts of distortion-free power. The directional tendency of high frequency notes is overcome by the natural wide dispersion angle of the short horn and acoustic lens which disperses and radiates the high notes smoothly throughout the entire listening area. The lens is detachable for panel mounting, with a separate base for the tweeter furnished for external mounting where desired. Aluminum voice coil has 16 ohms impedance. Size 4¼" long x 3" diameter, lens extends 2½". Requires a crossover network, preferably one with a level control, such as the LN-2. With full instructions. Shpg. wt., 5 lbs. HW-7 Imported. Net 14.95



1495

2 OR 3 WAY CROSSOVER NETWORK



875

• 4 CROSSOVER FREQUENCIES • L PAD BALANCE CONTROLS • EASY TO USE • IMPEDANCE 16-OHMS

The LN-7 Crossover Network combines quality performance, beauty and versatility at an unbeatable price. It can be used in a two-way system by crossing over at 500 cps or 3300 cps, and in a three-way system by utilizing the two simultaneously. The change from a two-way to a 3-way 6 db per octave network may be accomplished easily. Two level balance controls. Size 5½"x2½"x2½". Shpg. wt., 2¼ lbs. Imported. Net 8.75 LN-7


2- and 3-way L C CROSSOVER NETWORK



1495

This versatile unit can be used either as a 2-way or 3-way 6 db per octave network. You can use this network for a 2-way system now, easily and quickly convert to 3-way later. Six crossover combinations are available—2-way crossover with 2000-3000 cycle or 5000 cycle crossover, and 3-way with crossover frequencies of 350 and 5000, 350 and 2000-3000, 700 and 2000-3000 or 700 and 5000 cycles—a total of four different crossover frequencies! Suitable for 8-16 ohm speakers. The network is housed in an attractive metal case, suitable for mounting inside enclosure or leaving out in the open. Two level controls—Brilliance and Presence controls—are mounted on the front panel. If desired, these level controls may be removed, along with the beautiful gleaming copper escutcheon plate, for external mounting; controls are wired with 3-foot long leads. High quality components are used for long life and top performance. Shpg. wt., 6 lbs. Imported. Net 14.95 LN-5 Lafayette L/C Crossover

PHENOMENAL ELIPTOFLEX PERFORMANCE




PERFORMANCE EXPLANATION

The loudspeaker is mounted on a baffle recessed in the cabinet shell with the front-plate extending partially across the front surface of the baffle forming ducts or tubes from the port openings to the outside air. The elliptical cutout changes the effective length of the duct across its area. This variation in path lengths provide an extremely smooth transition from duct to free air; broadens the frequency response and provide better transient response. A triangular shaped diffracting ring mounted on the front of the baffle board virtually eliminates undesirable cancellation effects normally produced by close coupling of front and rear cone radiation. This results in a "lens" effect, changing relative particle velocities and consequently, phase relationships so as to produce a smooth transition from front to rear radiation. Comparative laboratory and listening tests indicate that "Eliptoflex" performance is demonstratively superior throughout the audio spectrum.

Patents applied for in United States, England and Canada

SPECIAL KIT VALUE Lafayette ELIPTOFLEX in KIT FORM



- Easy To Assemble
- 3 Sides Ready To Finish For Horizontal Placement
- ¾" Furniture Quality Birch
- Decorative Acoustic Grille
- Interior Acoustic Padding


2150

NO MONEY DOWN

PRICED EXTRA LOW!
COMPARE FOR VALUE

CK-14AWX Ready-To-Finish "Eliptoflex" Speaker Cabinet Kit in Birch	Net 21.50
CK-34WX Ready-To-Finish Kit with Walnut veneer	Net 24.50

LAFAYETTE ELIPTOFLEX® BOOKSHELF ENCLOSURE with SK-180 10" TRIHELIX 3-WAY SPEAKER




66⁵⁰
NO MONEY DOWN

An ideal combination of speaker and enclosure that furnishes optimum 3-way speaker performance. Eliptoflex enclosures are finished on all four sides for vertical or horizontal placement. Shpg. wt., 32 lbs.

SY-398WX Mahogany	Net 66.50
SY-399WX Walnut	Net 66.50
SY-400WX Blond	Net 66.50
SY-401WX Oiled Walnut	Net 66.50

VALUE COMBINATION! LAFAYETTE SK-211 CAVALIER SPEAKER with 1¾ LB. MAGNET & FAMOUS ELIPTOFLEX ENCLOSURE




64⁵⁰
NO MONEY DOWN

Get the most in both value and performance with this speaker/cabinet combination. Lafayette's famous Eliptoflex bookshef enclosure assures you of top performance for your SK-211 "Cavalier 12" speaker. Enclosures finished on all four sides for vertical or horizontal placement. Your choice of fine finishes. Size: 14Hx23¾Wx13-5/11"D. Shpg. wt., 34 lbs.

SY-410WX SK-211 & Eliptoflex in Mahogany	Net 64.50
SY-411WX SK-211 & Eliptoflex in Walnut	Net 64.50
SY-412WX SK-211 & Eliptoflex in Blonde	Net 64.50
SY-413WX SK-211 & Eliptoflex in Oiled Walnut	Net 64.50
SY-414WX SK-211 & Eliptoflex in Unfinished furniture grade birch	Net 57.50

FAMOUS LAFAYETTE ELIPTOFLEX ENCLOSURE & SK-210 SOVEREIGN 12" 3-WAY SPEAKER with 2¼ LB. MAGNET



82⁵⁰
NO MONEY DOWN

PERFORMANCE MATCHED—Lafayette's famous Eliptoflex bookshef enclosure matched with the exceptional SK-210 Sovereign 12" 3-way speaker. Finished on four sides in your choice of decorator finishes. Size: 14Hx23¾Wx13¾"D. Shpg. wt., 39 lbs.

SY-405WX SK-210 & Eliptoflex in Mhg.	Net 82.50
SY-406WX SK-210 & Eliptoflex in Walnut	Net 82.50
SY-407WX SK-210 & Eliptoflex in Blonde	Net 82.50
SY-408WX SK-210 & Eliptoflex in Oiled Wal.	Net 82.50
SY-409WX SK-210 & Eliptoflex in Unfinished furniture grade birch	Net 75.50

Save More with Lafayette Speaker & Enclosure Combinations

NEW! 12" WIDE-RANGE HI-POWER HI-FI SPEAKER



- 21.5 OZ. ALNICO 5 MAGNET
- RATED AT 30 WATTS
- RESPONSE 20-14,000 CPS
- SEAMLESS CONE
- SPECIAL HEAVY-DUTY CONSTRUCTION

ONLY **14⁹⁵**



Incorporating a full 21.5 oz. magnet of high-flux density Alnico 5, this new wide-range 12" PM high fidelity speaker is rated at 30 watts and is excellent for use with any hi-fi system. With proper baffling, frequency response is 20 to 14,000 cps. Special constructional features include a 1½" voice coil; epoxy bonding of the voice coil to the seamless cone; completely dust-proof enclosed magnet structure; fibre-to-metal bonds made with heat under extreme pressure; heavy cast-metal frame; metal parts heavily cadmium-plated, with exposed surfaces covered with a handsome mar-resistant hammerloid finish. Voice coil impedance 8 ohms. Outside diameter 12¾", mounting diameter 11¾", depth 6¾". Color-coded 4-way binding-post terminals. SK-137 Shpg. wt., 7 lbs. Net 14.95

Tweeter with baffle Polyester resin treated tweeter edge




LAFAYETTE ULTRA-LINEAR SK-128 FULL RANGE 8-Inch BIAxIAL SPEAKER

19⁵⁰

with Acoustic Tweeter Baffle Design

- 20 TO 20,000 CPS (40 TO 16,000 CPS ± 3 DB) ■ HIGH EFFICIENCY
- HIGH EXCURSION WOOFER WITH UNIQUE "CONICAL STIFFENER"
- HANDLES HEAVY BASS PASSAGES WITHOUT "DOUBLING"


Eccentric Tweeter Mounting & Unique Elliptical Baffle Completely Eliminates Interaction Between Woofer & Tweeter



The SK-128 combines the best features of a multiple speaker system in one compact and economical unit. It offers full, even coverage of the entire audible range, with no distortion or coloration to mar your listening pleasure. The specially treated woofer cone has a unique "Conical Stiffener" at the apex which, coupled with its high compliance, enables the cone to operate in a piston-like manner—delivering a clean, powerful bass response. The 2-inch tweeter has its own voice coil and magnetic field. Special treatment of cone and cone edge provides even distribution of the high frequencies, with no peaks or resonances. The unusual off-center mounting of the tweeter and its elliptical baffle minimizes interaction between tweeter and woofer and insures an overall response free of intermodulation distortion. Electrical crossover from the woofer cone to the tweeter unit is provided by a built-in network. An adjustable brilliance control permits matching of sound to room acoustics. Efficiency of the speaker is such that it will operate from any amplifier with an output of 1 watt or more. Installed in a bass-reflex type of enclosure, it performs outstandingly, and is recommended for all high-quality music systems—whether monaural or stereophonic. SPECIFICATIONS: Overall Response: 20-20,000 cps (40-16,000 cps ± 3 db). Free air Resonance: 45-65 cps. Impedance: 8 ohms. Power Rating: 20 watts Integrated Program Material. Crossover: 2,500 cps. Overall Diam. 8½". Overall Depth: 5½". Baffle cut-out: 7½". Rugged, vibration-free speaker frame with color-coded screw-type terminals for quick easy connection of amplifier leads. Shpg. wt., 5 lbs. SK-128 Full Range 8" Biaxial Speaker.....Net 19.50

NEW! LAFAYETTE-GOODMAN "DOME LENS" ULTRA HIGH FREQUENCY COMPRESSION TWEETER

CUSTOM BUILT IN ENGLAND TO LAFAYETTE SPECS!



- Omni-directional compression tweeter for 2, 3, and 4 way systems
- Has built in crossover at 5000 cps.
- Handles frequencies from 5000 cps to beyond limits of human audibility
- Handles up to 40 watts of power

ONLY **8⁹⁵**

A new "Dome Lens" ultra-high frequency hemispherical compression tweeter made in England by fine British craftsmen. Designed to give full 360° sound dispersion, quality high frequency response of sharp transients and percussive sounds. Can be used to add brilliance to extended range speakers in 2 way systems. Ideal for super-tweeter applications in 3 & 4 way systems. When used in a complete system, this super tweeter can handle up to 30 watts of power. Capable of handling frequencies from 5000 cps. to beyond the limits of human audibility. Has built in crossover at 5000 cps. Voice coil impedance 8-16 ohms. Dimensions: 4Dx2½" length. Shpg. wt., 1½ lbs. Imported from England. SK-214 Net 8.95

SENSATIONAL SPEAKER SYSTEM

JENSEN speakers + UNIVERSAL WOODCRAFTERS cabinets + LAFAYETTE low prices



38⁹⁵

NO MONEY DOWN!

- Heavy 7-Ply Furniture Veneer Cabinets
- Fiberglass-loaded Cabinet for Better Bass Response
- Jensen 12" Woofer, 8" Midrange Driver, 3½" Enclosed Tweeter

Now you can get unparalleled speaker performance at a low, low Lafayette price—the most outstanding value of its kind in the industry. The Uni-Voice hi-fi speaker system is a thrilling blend of fully integrated, unified 3-speaker systems engineered by Jensen with specially developed Jensen components, with cabinetry by Universal Woodcrafters. Contains special 12" woofer; 8" midrange driver independently pneumatically damped in its own hermetically enclosed acoustic surroundings, completely separated from woofer cavity; 3½" fully enclosed, independently baffled tweeter. Woofer electric crossover at 600 cycles, midrange electric crossover at 2000 cycles. Impedance 8 ohms. Response: 35-18,000 cycles. MODEL: UV-30 Bookshelf enclosure finished on 4 sides. Speaker grille completely framed with brass inlay. 24Wx14½Hx13"D. SK-185WX Walnut finish Shpg. wt., 32 lbs. Net 38.95

LAFAYETTE MINI-DUCT™ BOOKSHELF ENCLOSURE WITH SK-128 8" ULTRA-LINEAR SPEAKER


MINIDUCT FINISHED ON ALL 4 SIDES

The perfect answer for those who demand realistic sound reproduction even where space is limited. Two of these systems are ideal for stereo. Beautifully finished on all 4 sides for horizontal or vertical placement. Shpg. wt., 28 lbs.

SY-404WX	Speaker System in Walnut	Net 39.50
SY-455WX	Speaker System in Oiled Walnut	Net 39.50
SY-403WX	Speaker System in Mahogany	Net 39.50
SY-347WX	Speaker System in Unfinished Birch — For 3 Sided Finish Only	Net 37.50

AS LOW AS **37⁵⁰**

NO MONEY DOWN



MINIDUCT SYSTEM FINISHED ON 4 SIDES


A perfect match: The "Mini-Duct" enclosure and the remarkable Lafayette SK-212 3-way high fidelity speaker. Reproduces the entire audio spectrum with a marvelous smoothness. Styled in attractive furniture finishes on all 4 sides for horizontal or vertical placement. Shpg. wt., 35¼ lbs.

SY-436WXM	MAHOGANY	Net 56.40
SY-437WXM	WALNUT	Net 56.40
SY-459WXM	OILED WALNUT	Net 56.40
SY-431WXM	UNFINISHED BIRCH — For 3 Sided Finish Only	Net 52.45

AS LOW AS

52⁴⁵

NO MONEY DOWN



SK-130 MINIDUCT SYSTEM FINISHED ON 4 SIDES


SY-420WXM	MAHOGANY	Net 36.95
SY-421WXM	WALNUT	Net 36.95
SY-458WXM	OILED WALNUT	Net 36.95
SY-415WXM	UNFINISHED BIRCH — For 3 Sided Finish Only	Net 33.95

AS LOW AS

33⁹⁵

NO MONEY DOWN

A combination that rivals the performance of much larger systems. This fine enclosure assures optimum performance from the SK-130. Only 23" W x 11½" H x 11½" D—ideal for mounting in a bookcase or record shelf. Finished on 3 sides in a variety of fine furniture finishes. Shpg. wt., 27 lbs.



"BUILD-YOUR OWN"

SAVE DOLLARS MORE WITH EASY-TO-ASSEMBLE HI-FI ENCLOSURE KITS

LAFAYETTE UNIVERSAL HI-FI BASS REFLEX ENCLOSURE KITS

Entire Cabinet 3/4" Plywood

Heavier Construction—Fully-Cured 3/4" plywood

Smoothly Sanded Ready for a Fine Finish

Picture Frame Moulding Built-In

For 8 1/2", 8" or 5" Mid-range Or No Mid-range, If Desired

Pre-fab 3/4" Baffle for any Lafayette And Almost Any Other Speaker System

Pre-Cut for Most Tweeters Or No Tweeter, If Desired

Pre-Cut for 15" Woofer With Adapter for 12"

Acoustic Grille of Decorative Plastic

Carefully Designed Bass Reflex Port

Supplied With Interior Acoustic Padding

Precision Design—Parts Fit Air-tight

HIGHBOY LOWBOY

At Tremendous Savings To You!

A LAFAYETTE BEST BUY!
At Only **29⁹⁵**

NO MONEY DOWN

- EASIEST TO ASSEMBLE — ALL YOU NEED IS A SCREWDRIVER!
- 3/4" WHITE BIRCH
- PRECISION-CUT — FITS TOGETHER SMOOTHLY.
- PERFECT FOR SINGLE WIDE RANGE, 2-WAY OR 3-WAY SPEAKER SYSTEMS
- HIGHBOY OR LOWBOY STYLE

All pieces of these carefully designed bass reflex high fidelity speaker enclosures are accurately precut of 3/4" Plywood to fit snugly together and eliminate spurious resonances. Surface is white birch veneer. Front panels have picture-frame moulding and plastic acoustic grilles to blend with any finish and room decor. Tapered offset legs are protected by brass ferrules. Acoustic lining material prevents reverberation and cabinet resonance. Cutouts are provided for 15" speaker plus adapter for 12" 8 1/2" or 8" midrange plus adapter for 5" and blank wood block if no midrange speaker is used; cutout with adapter boards for 2 sizes of rectangular and 3 sizes of round compression horn tweeters plus blank block if no tweeter used. Thus, any single wide-range 12" or 15" speaker may be used, or any Lafayette 2- or 3-way speaker system, or almost any other combination of speakers. Kits are supplied unfinished, smoothly sanded and ready for finishing. The lowboy-style cabinet dimensions are (less legs) 28 1/2" x 23 1/2" x 16 3/4" D; legs are 7" high. Highboy has same dimensions with height and width interchanged. Instructions, all parts, hardware, and grille are included. Shpg. wt., 54 lbs.

CK-10WX Unfinished Highboy Enclosure Kit Net 29.95
CK-11WX Unfinished Lowboy Enclosure Kit Net 29.95

LAFAYETTE OILED WALNUT FINISHING KIT

2.69

At Tremendous Savings To You!

Use this professional walnut oiling kit to achieve a beautiful oil finish on all unfinished walnut furniture. Materials are identical to those used by professional finishers; kit contains walnut oiling mixture, walnut paste wax, sandpaper and instructions. Shpg. wt., 2 lbs. Net 2.69

LAFAYETTE HI-FI SPEAKERS AT POCKETBOOK PRICES

SK-103 **11⁹⁵** SK-138 **5²⁵**

12" THREE-WAY HI-FI SPEAKER

This new 3-way speaker answers the needs of many hi-fi enthusiasts. Featuring an 8 oz. dual-diameter magnet it has a frequency response of 35-17,500 cps. The elliptical tweeter gives improved sound dispersion over cylindrical types. Voice coil: diam-1 1/8". Impedance-8 ohms. Plated steel frame finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 6 1/2 lbs. SK-183 Net 11.95

6" MID-RANGE SPEAKER

An excellent mid-range direct-radiator type speaker for installation in 3-way or 4-way speaker systems. Gives clean, distortion-free reproduction at rated power. Features closed back to eliminate interaction with sound waves generated from other speakers in the same enclosure. Rated power handling capacity: 10 watts. Frequency response from 700 to 7000 cps. Magnet weight: 3.16 oz. Voice coil impedance: 8 ohms. Plated steel frame finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 3 lbs. SK-138 Net 5.25

SK-106 **4⁹⁵** SK-93W **8⁷⁵**

LAFAYETTE 8" EXTENDED RANGE SPEAKER

- 45 to 13,000 cps
- SKIVER ROLLED CONE FOR SMOOTH RESPONSE
- 3.16 OZ. NEW TYPE MAGNET

Here is a price buster for the budget-wise hi-fi music lover. This is an extended range domestic speaker whose high sensitivity is achieved through a new hi-efficiency magnetic circuit. Ideally suited for medium and low level monaural or stereo reproduction. It has a 1" voice coil with 8 ohms impedance and will handle musical peaks of 10 watts. Size: O.D. 8 3/8"; Mtg. hole dimensions 7 1/4"; 3 1/2" deep; Brown enamel over heavily plated steel. 4-way binding posts. Shpg. wt., 2 lbs. SK-106 Net 4.95

12" COAXIAL HI-FI SPEAKER

12" Alnico V PM with 1" voice coil and heavy one-piece cone. Specially designed 3" Alnico V PM tweeter completes this combination speaker. Range 40 to 15,000 cps. Built-in high pass filter. Power rating: 12 watts. 6.8 ohm Alnico V magnet. Impedance 8 ohms. Shpg. wt., 8 lbs. SK-93W Net 6.75

SK-69 **6²⁵** SK-164 **10⁹⁵**

8" HI-FI WIDE RANGE SPEAKER

50-13,000 CPS

Answers the need for a good quality but moderately priced speaker with a range of 50-13,000 cycles. An extremely smooth single cone reproducer — ideally suited for hi-fi systems. Excellent for limited space — good overall balance — power handling capacity: 10 watts — 6.8 ohm Alnico V magnet — frequency response: 50-13,000 CPS when properly baffled. Rim treatment on cone minimizes possibility of diaphragm distortion. Voice coil impedance: 8 ohms. Cone resonance 85 cycles. Plated steel frame finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 4 lbs. SK-69 Net 6.25

LAFAYETTE 8" WOOFER

- Rated 20 Watts • Free edge cone
- 14.7 oz. alnico V magnet
- High Compliance • 35 to 7500 cps

Ideal for 2 or 3 way systems where space is at a premium, this 8" woofer provides coverage from 35 to 7500 cps. The 14.7 oz. magnet is extraordinarily heavy for this size speaker insuring the efficiency needed for good clean response. Other features include free edge, high compliance cone, 20 watt power dissipation, voice coil dust cover. Cone resonance 50 cycles, 8 ohm V.C. Has 4-way binding posts. SK-164 Shpg. wt., 4 1/2 lbs. Net 10.95

8" MID-RANGE SPEAKER

Ideal for use with tweeter and crossover networks to make up a 2- or 3-way system. This 8" mid-range speaker is capable of producing undistorted response down to 350 cps, the crossover frequency. Back is enclosed. Power handling capacity: 25 watts. Frequency response 350-13,500 cycles. Recommended to crossover at 5000 cycles to a tweeter. Cone resonance 150 cycles. Impedance: 8 ohms. Plated steel framed finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 4 lbs. SK-74 Net 6.50

NEW! LAFAYETTE 8" 3-WAY HI-FI SPEAKER

PAY LESS FOR HIGHER QUALITY-PERFORMANCE

24⁵⁰ NO MONEY DOWN

- Frequency Range: 40-20,000 cps • Magnet System: 1 lb. • Voice Coil: Aluminum • Impedance 16 Ohms • Power Handling Capacity: 20 Watts • 3-Concentric Radiators • Unique Wide-Angle Compression Lens Tweeter • Special "Rigidflex" Free Edge Woofer Cone • Built-in Brilliance Control • Die-Cast Frame

MADE IN ENGLAND TO OUR SPECS!

For Stereophonic and Monophonic Systems

The Lafayette SK-213 has been specially designed for us in England to reproduce sound with true fidelity without compromise. It is a complete 3-way system, composed of 3 concentric radiators. The "Rigidflex" bass and midrange radiators accurately reproduce frequencies of from 40 to 5,000 cps. The new wide-angle compressor lens tweeter extends the frequency range from 5,000 on up to 20,000 cycles. Here is a speaker capable of a standard of performance previously associated with much larger and more elaborate loud-speaker equipment. Deluxe features such as an aluminum voice coil, heavy 1 lb ceramic magnet system and rigid nonresonant die-cast frame demonstrate the unique marriage of Lafayette custom specifications

and quality English craftsmanship. Small size makes it an ideal choice for mounting in the famous Lafayette "Mini-duct" bookshelf enclosure. Use it in pairs for finer stereo reproduction anywhere in your home. A built-in bass-treble attenuator makes it possible to "customize" the SK-213's sound to your individual requirements. Baffle Hole dia., 7"; Front to back dimension, 3 3/4". SK-213 Shpg. wt., 6 lbs. Net 24.50
SK-213 3-WAY SYSTEM with MATCHING "MINI-DUCT" ENCLOSURES FINISHED ON ALL 4-SIDES
SY-438WX Mahogany Net 46.95
SY-439WX Walnut Net 46.95

NEW! Lafayette BASS REFLEX SPEAKER BOOKSHELF ENCLOSURE KIT FOR 8" or 6" SPEAKERS

COMPARES TO CABINETS PRICED AT \$35

AS LOW AS **10⁹⁵**

Assembles in Less Than 30 Minutes!

Not 1/2", But 3/4" Furniture Grade White Birch Or Walnut Veneer

- Precision Cut — Fits Together Smoothly
- Adapts For 8" or 6" Speakers
- Easy To Follow Pictorial Instructions
- Versatile — Use As Floor or Bookshelf Enclosure

BUILD IT YOURSELF... All that's required to construct this excellent bookshelf speaker enclosure is a screwdriver and thirty minutes of your time. Expensive woodworking equipment isn't needed—each cabinet component has been precision cut and fits together perfectly. There's nothing else to buy... acoustic padding, grill cloth and hardware are provided. Use any 8" or 6" speaker; the mounting board has been precut for 8" speakers and an adapter is supplied for 6" speakers.

Designed for horizontal placement in a bookshelf, along a wall etc. Constructed of 3/4" veneers on 3 sides with handsome picture frame moulding. You save even more by finishing this kit yourself—the 3 sides are smoothly sanded furniture grade wood; ready for a finish you'll be proud of. (See Lafayette's professional finishing kits). Dimensions: 23x9 1/2 x 11". Available in either birch or walnut unfinished veneers.

CK-31WX Birch Kit Shpg. wt., 15 lbs. Net 10.95
CK-35WX Walnut Kit Net 13.95
Speakers for Lafayette CK-31 Cabinet Kit. Lafayette 8" Duo-Cone Speaker; 40-16,000 cps response.
SK-98 Shpg. wt., 5 1/2 lbs. Net 9.95
Lafayette 6 1/2" Coaxial Speaker; 50-16,000 cps response.
SK-97 Shpg. wt., 3 1/2 lbs. Net 6.95



Smooth, Sanded, Ready for a Fine Finish

Built-In Picture Frame Moulding

Adapter for 6" Speaker

Pre-cut for 8" Speaker

Decorative Acoustic Grill Cloth

Carefully Designed Bass Reflex Port

Interior Acoustic Padding


Entire Cabinet 3/4" Plywood

SAVE MORE WITH LAFAYETTE TOP VALUE AUDIO & PHONO ACCESSORIES

LAFAYETTE'S Amazing MINI-DUCT™

AS LOW AS

21⁵⁰
NO MONEY DOWN



Mounting boards accept all types of tweeters



MINI-DUCT BOOKSHELF ENCLOSURE

AS LOW AS

31²⁵
NO MONEY DOWN



SK-98

SPEAKER ENCLOSURE

A universal ducted-port bookshelf enclosure engineered for use with 1, 2 or 3-way speaker systems.

- SOLIDLY CONSTRUCTED OF 3/4" WOODS • START WITH A SINGLE SPEAKER AND BUILD INTO A 2- OR 3-WAY SYSTEM LATER
- ACOUSTICALLY LINED THROUGHOUT
- AVAILABLE IN A VARIETY OF 4-SIDED FINISHES

Now limited space need not necessarily mean limited sound. The Lafayette Mini-Duct is acoustically designed to achieve smooth, distortion-free reproduction with a remarkably full, clean extended bass response that gives no indication as to its small size. Reducing boards are supplied so that the Mini-Duct will accept an 8" Woofer, 6" Mid-Range and a variety of tweeters. This versatility makes it possible to start with an 8" speaker and eventually build into a 2-way or 3-way speaker system. Solidly constructed of 3/4" woods the Mini-Duct is beautifully finished in a variety of fine veneers on 4 sides. Designed for attractive horizontal or vertical placement anywhere in your home with dimensions 23Wx11 1/2Hx11 1/8"D. Shpg. wt., 23 3/4 lbs.

CAB-106WX	WALNUT	Net 24.95
CAB-105WX	MAHOGANY	Net 24.95
CAB-155WX	OILED WALNUT	Net 24.95
CAB-51WX	UNFINISHED BIRCH For 3-Sided Finish Only	Net 21.50

SPEAKER AND ENCLOSURE COMBINATIONS

A PERFECT COMBINATION: The "Mini-Duct" enclosure and the famous Lafayette SK-98 8" mechanical 2-way speaker with patented dual cone construction. This speaker combined with the Lafayette "Mini-Duct" enclosure will give the same wide-range frequency response (40-16,000 cps) normally found only in the coaxial speakers or multiple speaker systems. Shpg. wt., 29 1/2 lbs.

COMBINATION UNFINISHED "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER	Net 31.25
SY-348WX	Net 31.25
COMBINATION MAHOGANY "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER	Net 34.25
SY-377WX	Net 34.25
COMBINATION WALNUT "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER	Net 34.25
SY-378WX	Net 34.25
COMBINATION OILED WALNUT "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER	Net 34.25
SY-456WX	Net 34.25

NEW! LAFAYETTE SK-98® 8" DUO-CONE HI-FI SPEAKER

- MECHANICAL 2-WAY DESIGN
- OVERALL RESPONSE 40-16,000 CPS.
- LARGE MAGNET STRUCTURE
- PATENTED CONE CONSTRUCTION AND MATERIAL HIGH EXCURSION WOOFER



9⁹⁵

The dual-cone construction used in these high quality 8" speakers, provides the same type of wide-range response normally found only in true coaxial speakers or multiple speaker systems. Two separate cones act through a common voice coil. The outer edge of the tweeter cone is attached to the mid-section of the woofer cone; both cones "float" on flexible corrugated edges. This mounting results in true mechanical cross-over, so that both cones operate at low frequencies, but only the tweeter cone operates at high frequencies. This gives improved high frequency directional characteristics and minimum distortion. Patented cone materials provide extremely smooth response over the range of 40-16,000 cps. Magnets are large and heavy, with a flux density of 10,500 gauss and total flux of 56,000 maxwells. Terminals are screw-type for solderless connections. Sensitivity is 99.5 db/watt; free air resonance is 55-70cps; voice coil impedance is 8 ohms. Size is 8" diam., 4 1/4" deep and requires 6 3/4" diam. baffle opening. Shpg. wt., 5 1/2 lbs. Imported

SK-98 8" 2-WAY SPEAKER	Net 9.95
2 FOR STEREO	Net 18.95

NEW! 6 1/2" COAXIAL SK-97® HI-FI SPEAKER

- OVERALL RESPONSE 50-16,000 CPS.
- SPACE SAVING & ECONOMICAL FOR STEREO
- BUILT-IN LC NETWORK
- LARGE, HEAVY MAGNETS




6⁹⁵

An excellent speaker with all the best features of coaxial design, the SK-97 will provide the finest sound reproduction available from a speaker of this size. It is especially recommended where space and/or cost are factors. The 6 1/2" woofer is equipped with large, heavy magnet for maximum efficiency and low distortion. The 2" tweeter is a separate speaker coaxially mounted in a housing which completely seals off back radiation; a mesh dispersion screen provides smooth, wide-angle high frequency propagation. When properly enclosed, the response of this low cost hi-fi speaker is genuinely impressive. Its small size makes it perfect for use in a wide variety of small enclosures—ideal for use in pairs for stereo music systems of up to 8-10 watts. Frequency range, 50-16,000 cps. Woofer free-air resonance, 70 cps. Voice coil impedance, 8 ohms. Built-in electrical crossover network. Color-coded screw-type terminals. Requires 5 1/2" diam. cutout. Size is 6 1/2" diam., 3 3/4" deep. Shpg. wt., 3 1/2 lbs. Imported

SK-97 6 1/2" COAXIAL SPEAKER	Net 6.95
2 FOR STEREO	Net 12.95

LAFAYETTE DUCTED-PORT BASS REFLEX SPEAKER ENCLOSURE



14⁵⁰

- ACCOMMODATES EITHER AN 8" OR 6" SPEAKER
- DUCTED PORT DESIGN FOR EXTENDED BASS RESPONSE
- ECONOMICAL AND SPACE-SAVING
- RECOMMENDED FOR STEREO

An acoustically engineered loudspeaker enclosure designed to provide full wide-range response when used with any 8" or 6" wide range or coaxial hi-fi speaker. Incorporates a special long duct over the usual bass-reflex port for performance equal to many enclosures of much greater size. Only 11 1/4" high, 18" wide and 9" deep—perfect for bookshelf, table top or other limited-space applications. Made of hardwood veneers throughout, hand-rubbed to a high finish, and lined with heavy acoustical padding. Available in Blonde Mahogany, Mahogany or Walnut finishes. (Please specify your choice.) Shpg. wt., 15 lbs.

CAB-29W	Net 14.50
---------	-----------


LAFAYETTE'S ULTRA-COMPLIANCE 2-WAY SPEAKER SYSTEM

VERY SMALL IN SPACE — LESS THAN 1 CU. FT.

Absolutely Gigantic in Performance!

AS LOW AS
19⁹⁵

- Frequency Response 40-16,000 cps
- Especially Designed Vented, Tuned Duct Type Enclosures
- Unique Mechanical 2-Way Speaker With Extra Heavy Magnet
- Enclosure Finished on-4 sides • Excellent For Stereo



FULL SIZE PERFORMANCE — This outstanding Lafayette Ultra-Compliance 2-way speaker system achieves a purity of sound and musical quality that is astounding from a speaker system occupying less than one cu. ft. of space. A perfect speaker for use anywhere in your home or office . . . makes ideal extension units or use in pairs for stereo.

The speaker features a unique dual cone with an extra heavy magnet structure, employed in a specially designed tuned ducted port enclosure. Both tweeter and woofer "float" on flexible, corrugated edges, with the outer edge of the tweeter cone attached to the mid-section of the woofer. This results in a mechanical crossover so that both cones operate in phase at low frequencies, but only the tweeter cone radiates high frequencies. The same type of wide-range frequency response is achieved that normally is found only in true coaxial or multiple speaker systems. Frequency response is 40-16,000 cps — Impedance: 8-16 ohms.

Available in rich mahogany or walnut. Finished on four sides — place it horizontally on its side or vertically on its base. Easily adapts to bookshelf placement or modular use. Dimensions are only 10 3/4Hx18 3/4Lx8 7/8"D. Shpg. wt., 15 lbs. Imported

AVAILABLE IN MAHOGANY OR WALNUT (PLEASE SPECIFY)	
Lafayette Ultra-Compliance 2-Way Speaker System	
SK-124WX	Net 19.95
SK-123WX Oiled Walnut	Net 23.95
Set of Two SK-124 Speaker Systems	Net 38.90
Set of Two SK-123 Speaker Systems	Net 46.90

LAFAYETTE L PADS

139



New L pads for use as "brilliance" controls to vary tweeter level, or as "presence" controls to vary mid-range speaker level. Both wirewound elements are concentrically mounted within one plastic housing. With gold-finished metal escutcheon plate, mtg screws, and attractive black knob. Size: 1 3/4" dia., 7/8" deep (less shaft), 2 1/2" deep overall. Shpg. wt., 6 oz.

VC-49—L pad for 8 ohm circuits	Net 1.39
VC-50—L pad for 16 ohm circuits	Net 1.39

STEREO LEVEL BALANCE CONTROL

- Dual Concentric 8 ohm L Pads
- Logarithmic Curve

289



Provides individual level control for stereo speakers. Varies "brilliance" or "presence" Controls stereo extensions without mismatching. Dual control mounted on concentric shaft. Gold-finished brass plate and attractive black knobs, with gold trimming. L pad for 8 ohm circuits. Plate is 2 1/4" across; overall depth 3 1/4". Shpg. wt., 10 oz. Imported

VC-55 Level Control	Net 2.89
---------------------	----------

STEREO RUMBLE FILTER

249



Filters out turntable vibration and rumble—makes every low-priced turntable and changer quiet and rumble-free. Designed for use with ceramic or magnetic cartridges. 3-position selector switch—ceramic, magnetic cartridge, off. Just plug it in between cartridge and amplifier inputs. Overall size: 5x2 1/2x5/8". Shpg. wt., 14 oz. Imported

PK-444 Stereo Rumble Filter	Net 2.49
-----------------------------	----------

DUST COVERS

495



LAFAYETTE STYLUS PRESSURE GAUGE

.99

With the advent of stereo records, correct stylus pressure becomes all important in obtaining the best reproduction and least stylus and record wear. Lafayette's stylus pressure gauge is an accurate device that allows you to read with the pickup in normal playing position. Range, 0-30 gm. No spring and minimum moving parts. Shpg. wt., 1 lb.

PK-223	Net .99
--------	---------

DUST COVERS

Molded to the contours of the players from sparkling, clear vinyl, these covers provide complete protection from dust and accidents to the precision bearings, levers and tone arm. Shpg. wt., 1 1/2 lbs.

PK-531 Fits Model A	Net 4.95
PK-560 Fits Model AT6	Net 4.95
PK-561 Fits Autolism	Net 4.95
PK-529 Fits Model 210	Net 4.95
PK-530 Fits 88/11 and RC88	Net 4.95



PHONO-TUNER ADAPTER

2 phono jack inputs; simple switch selects either. A convenient phono output jack for connecting to amplifier. Includes mounting screws. Av. shpg. wt. for above units is 1 lb. Imported

MS-785	Net .98
--------	---------

SPEAKER PHASING CONTROL

Allows you to reverse speaker connection to obtain correct phasing without disconnecting leads from speakers. A must for stereo. Complete with screw terminals and all mounting hardware. Shpg. wt., 1 lb. Imported

MS-796 Speaker Phasing Control	Net .98
--------------------------------	---------

STEREO-MONAUURAL-REVERSE SWITCH

Lets you switch instantly from stereo to monaural or reverses stereo channels. 2 phono jacks input . . . 2 phono jacks output. Completely shielded, ready to mount with all hardware. Shpg. wt., 1 lb. Imported

MS-737 Stereo-Monaural-Reverse Switch	Net 7.29
---------------------------------------	----------

MULTI-INPUT SELECTOR CONTROL

Connects any one of 5 inputs to 1 output AM, FM, phono, tape, aux. Completely shielded to prevent hum. Complete with mounting hardware. 5 phono jacks input, 1 phono jack output. Shpg. wt., 1 lb. Imported

MS-758 Multi Input Selector	Net 1.76
-----------------------------	----------

REMOTE MICROPHONE VOLUME CONTROL

No more running to the P. A. amplifier to adjust volume when you are using a mike. Now, control volume output right at the microphone. Attached between the microphone and the cable, this completely shielded control has practically no insertion loss and induces no hum. Can be used at any desired distance. Fitted on one end with a female mike connector and male mike connector on the opposite end. Finished in gleaming chrome, its appearance will blend in with the most expensive microphones. Comes completely ready to use. Shpg. wt., 12 oz. Imported

MS-755 Remote Volume Control	Net 1.76
------------------------------	----------



Group your Components
Into A Distinctive,
Custom Home
Entertainment Center.

Decorator Inspired!!

NEW LAFAYETTE HI-FI COMPONENT SHELF/CONSOLE

NEW
LOW
PRICE! **47⁵⁰**
28⁹⁵

OILED WALNUT FINISH
NO MONEY DOWN

UNFINISHED
NO MONEY DOWN


As functional as it is beautiful, this new Lafayette Shelf Console combines the beauty and compact all-in-one convenience of a console with the versatility of a shelf arrangement. The ideal answer to your Hi-Fi Stereo component placement problems — measures 62½" long, yet holds over 150 records with more than enough room for your amplifier, turntable or record changer, tape deck and stereo speakers. Available in both finished and unfinished versions. Both feature ¾" warp-proof construction. Top shelf measures 11Hx31½Wx16"D. Lower shelf is 15¼Hx16Dx

3½"W and to protect your records contains a veneered rear panel, finished on both sides to allow placement of the unit as a room divider. Speaker compartments are 27Hx16Dx14¾"W—Large enough to accept virtually all of today's popular bookshelf size units and are spaced far enough apart to provide proper separation for stereo. Overall dimensions: 66½Wx16Dx33¾"H including 5" legs. Shipped knocked down—Assembles in minutes. Shpg. wt., 65 lbs.


CK-37WX Oiled Walnut Finish Net 47.50
CK-36WX Unfinished Chip Board Net 28.95

- ROOM FOR ALL YOUR COMPONENTS • STURDY ¾" WOOD NON-WARP CONSTRUCTION • HOLDS OVER 150 RECORDS
- AN ATTRACTIVE ADDITION TO ANY HOME - PLACE ALONG A WALL OR USE AS A ROOM DIVIDER

COMPLETE ALL-IN-ONE STEREO CABINETS BY Casard




A.



B.

Your Choice
of Contemporary, French
Provincial
or Italian
Provincial
Styling **8895**
No Money
Down



- Ample Space For Your Components including Stereo Speakers • Luxurious Hand Rubbed Veneers
- Contains Two Sealed Bass-Reflex Ducted-Port Enclosures • Your choice of Contemporary, French Provincial or Italian Provincial Styling

Here's period styling and furniture craftsmanship in the old world tradition. And at Lafayette's low, low price these new all-in-one stereo cabinets represent a superb value. Hand crafted in luxurious ¾" woods and veneers. Cabinets have been acoustically designed to showcase your component stereo systems to its best advantage. Enclosure is structurally reinforced to eliminate cabinet resonance. Speaker sections are acoustically insulated with fiber glass and utilize a sealed, bass-reflex, ducted port construction designed to accept either an 8" or 12" full-range speaker or a two or 3 way speaker system. Speaker enclosure section measures 17x13½x15½". The center or component section is protected by two sliding front panels and features a removable shelf. Lower compartment contains a pull-out mounting base which will accept a turntable or record changer (mounting base requirements are 3" below and 6½" above mounting board). Upper compartment provides ample room for a tuner-amplifier combination (receiver) or a separate tuner and

amplifier. Compartments measure: Upper—8½Hx17¼Wx15½"D; Lower—9¾x17¼x15½". Available in three superb styles—Contemporary, in your choice of fine Oiled Walnut or Mahogany finishes plus Italian Provincial and French Provincial, both finished in Fruitwood. Special plastic case grill cloth is matched to each style and finish. Overall Size: 48x18x28"H. Shpg. wt., 90 lbs.

(A) CONTEMPORARY STYLE	
CAB-143WX Oiled Walnut	Net 88.95
CAB-144WX Mahogany	Net 88.95
(B) FRENCH PROVINCIAL	
CAB-146WX Fruitwood	Net 88.95
ITALIAN PROVINCIAL STYLE (Not Illustrated)	
CAB-145WX Fruitwood	Net 88.95

NEW! LAFAYETTE CUSTOM CRAFTED EQUIPMENT CABINET



BEAUTIFUL CABINETRY
DESIGNED TO ENCLOSE
YOUR COMPONENTS

As Low as
4250
NO MONEY
DOWN

- Available In A Variety Of Fine Finishes • Rigid ¾" Wood Warp-Proof Construction • "Component Engineered" To Provide Adequate Circulation For Your Equipment

A magnificent example of contemporary furniture design—it's slender, graceful styling is sure to win approval in virtually every fine music room/living room arrangement. Features rigid ¾" wood warp-proof construction with two adjustable center shelves to accommodate virtually any amplifier and tuner. The bottom section has space for a pull out drawer to provide easy access to your record changer. Proper circulation of air around components is maintained by use of a perforated rear panel. Precision fitted swing-out front doors are equipped with magnetic latches. Size: 33¼"H overall (including 5" legs) x 18Dx20"W.

CAB-151WX Oiled Walnut	Net 52.50
CAB-152WX Walnut	Net 52.50
CAB-153WX Mahogany	Net 52.50
CAB-154WX Unfinished Birch	Net 42.50

LAFAYETTE SPECIAL PHONOGRAPH SALE with

FREE DIAMOND STYLUS!

You get BOTH Sapphire and
Diamond Styli at no extra cost!




5250

NO
MONEY
DOWN

- Garrard 4-Speed Automatic Intermix Changer
- Compatible — Plays Both Stereo and Monaural

Attractively styled stereo-monaural phonograph featuring Garrard 4-speed automatic intermix record changer with stereo crystal cartridge and dual sapphire styli; Automatic shut-off and arm return at end of last record. Free floating motorboard. Takes all record sizes, plays all 4-speeds: 16⅓, 33⅓, 45 and 78 RPM. Has separate volume controls for each channel and dual channel tone control. Both main unit and removable cover have 5" Alnico 5 PM speakers. 8 ft. cable supplied for placement of second speaker. Covered in Charcoal Hammetone with White Trim. Tubes: 2-50C5, 1-12AX7 and 35W4 rectifier. For 110-120 volt 60 cycle AC. Size 19¼x15½x8¼". Shpg. wt., 23 lbs

PH-164WX Net 52.50



6750

NO MONEY
DOWN

- Garrard Changer • 3 Speakers
- 4 Tubes plus Rectifier • 4 Controls

Deluxe phonograph with Garrard Automatic 4-speed intermix stereo-monaural changer. Turnover Cartridge with dual sapphire styli. Plays all sizes, all speeds. Automatic shut-off and arm return. Separate volume controls for each channel, treble control for wings, and bass control for center. Main case has 6" speaker with 2.15 oz. Alnico 5 magnet, each wing has 5" Alnico 5 speakers. Wings detachable. Tubes: 2-35C5, 1-12AX7, 1-50EH5 and 35W4 rectifier. For 110-120 volt, 60 cycle AC. Color: charcoal with silver motif. Size 20x15½x9". Shpg. wt., 29 lbs.

PH-165WX Net 67.50



8950

NO MONEY
DOWN!

OUR finest
PORTABLE PHONO!

With
FREE
Diamond Stylus!

PLAYS BOTH STEREO AND MONAURAL!

- FULLY AUTOMATIC GARRARD CHANGER • TWO POWERFUL 10 WATT AMPLIFIERS
- SECOND SPEAKER EASILY DETACHED • 3 SPEAKERS

A complete portable and compact stereo phonograph in one convenient case. System uses the well-known Garrard High-Fi 4-speed stereo changer which features true intermix of 12" and 10" records in any order with instant selection of either automatic or full manual operation. Uses a stereo turnover cartridge to play all your records—whether monaural or stereo. Two powerful 10 watt amplifiers provide a frequency response of 50 to 12,000 cps. Controls included: Master Volume; Remote speaker volume; Master treble; Master bass. Detachable front speaker cabinet houses a 6" x 9" speaker with 9 ft. extension cord. Main unit houses two speakers—one 6" x 9" woofer and one 4" tweeter. Phonograph has easy-grip handle on attractive smart-looking Pyroxylin covered case. Size: 23x16x9¼". Shpg. wt., 40 lbs. Available in choice of 2 attractive coverings.

PH-150WX Charcoal Silver	Net 89.50
PH-151WX Tan	Net 89.50



"LEADER" 4-SPEED MANUAL

1395

Plays up to 12" monaural records at 16⅓, 33⅓, 45 or 78 RPM. A single lever selects any speed. The lightweight pickup arm is equipped with a single all-purpose needle for all records. Has volume control with on-off switch. Retractable 45 RPM chuck. Fine quality Alnico 5 PM speaker. Attractive leatherette covered case. For 110-120 volts, 60 cycles. Size 11¾x10½x5". Shpg. wt., 9 lbs.

PH-160W Net 13.95

With this portable phonograph you can play any record up to 12" size at 16⅓, 33⅓, 45 or 78 rpm. Has retractable 45 RPM chuck. A single lever selects any speed. The lightweight pickup arm is equipped with a turnover cartridge with dual sapphire styli. Has both tone control and volume control with on-off switch. Has jack for adding extension speaker. Fine quality Alnico 5" PM speaker. Attractive 2-tone leatherette covered case. Color: Charcoal linen and gray airbrush with matching grill cloth. For 110-120 volts, 60 cps. AC. Dimensions 12½x10½x7½". Shpg. wt., 10 lbs.

PH-161W Net 18.45

STANDARD
4-SPEED MANUAL

1845



pioneer

MODEL SE-1 STEREO HEADPHONES



1995

- Actually 2 High Fidelity Dynamic Speakers
- Frequency Response 25 to 15,000 Cycles
- Soft Foam Rubber Ear Pads
- Frequency Response 25 to 15,000 Cycles
- Actually 2 High Fidelity Dynamic Speakers
- Soft Foam Rubber Ear Pads

495

For the audio connoisseur who demands the finest in stereophonic headphone performance, the Pioneer Stereophones combine broad frequency response and faithful reproduction with comfort-oriented design, to fulfill the most exacting requirements. The Stereophones are actually two 2 1/2" high fidelity dynamic speakers with a frequency response range of 25 to 15,000 cycles. Perfect for stereo and monaural operation, the headphones are rated at 1/2 watt maximum input; impedance, 8 ohms per phone. The soft foam rubber ear pads provide extremely comfortable listening, help to keep out noise and maintain an excellent bass response. Imported.

- F-770 Shpg. wt., 2 lbs. Net 19.95
- Model SE-2 resistor box for SE-1. Permits flexible one-switch changeover from speakers to Stereophones. Net 4.95
- F-800 Model SE-3 "Y" connector for connecting 2 or more sets of headphones to a single source. Net 2.45
- F-301 Model SE-4 12' extension cord for SE-1 phones. Net 2.95
- F-802

NEW! THE SUPERB LAFAYETTE SLIM "decor-ette" SPEAKER SYSTEM

• Now Lafayette Offers The Most Advanced Design and Styling for Superlative Sound in Slim Speaker Systems at Lafayette's Low Sensational price • 5-Speaker 3-Way System Custom Built in England to Lafayette's Rigid Specifications • 2 8" Woofers with 1/2 lb. Magnets and Rigidflex Floating Piston Hyperbolic Cones, 1 6" Open Back Mid-Range Driver, 1 Dome Lens Compression Horn Tweeter, 1 3 1/2" Cone-Type Tweeter • Never Before Such Speaker Quality in the Concept of Slimline Sound • Custom Assembled in a Genuine Hand-Rubbed Oiled Walnut Veneer Cabinet, of Extra Heavy 3/4" Stock • Frequency Response, 40-20,000 cps. • Power Handling Capacity, Continuous 30 Watts; Instantaneous Peak Load Power, 60 Watts • Impedance 8 Ohms


• Truly magnificent sound from a thin line speaker! Only 25"Hx17"Lx4 3/4"W.

• 5-Speaker 3-Way System • 1 Jensen 8" Woofer, 2 Jensen 6" Midrange Drivers, 2 Jensen 3 1/2" Tweeters

The "decor-ette" now makes it possible to get a truly magnificent sound from a slim-type speaker cabinet. Lafayette has had the finest British audio engineers design and construct the "Decorator II" slim-type speaker system to our rigid specifications. The results achieved are of unequalled brilliance with outstanding speaker performance at such a sensationally low Lafayette price. The genuine hand-rubbed oiled walnut veneer cabinet has been designed and styled for either vertical or horizontal placement. A real space-saver, it is slim in appearance and can be placed on a bookshelf, mounted on the floor, used as a room divider or hung on the wall. The beauty of your present room will be enriched by this outstanding system in its decorator styled enclosure. The "decor-ette" is a 5-speaker 2-way system utilizing the latest advanced acoustic designs. Two 8" woofers with 1/2 lb. magnets incorporate a Rigidflex Floating Piston Hyperbolic Cone resulting in a free floating cone rim and a completely rigid cone center to provide maximum distortionless bass from 500 cycles down to 40 cycles. The specially designed 6" mid-range closed back driver provides uniform response from 500 to 7500 cycles. The 3 1/2" cone-type tweeter gives wide dispersion of the mid-highs smoothly from 1000 to 10,000 cycles. The 3 1/2" dome lens type compression tweeter response is from 5000 to 35,000 cycles. Omni-directional, this tweeter gives 360° sound dispersion to add overall brilliance to the system. RC electrical crossover frequency is 5000 cps. Overall frequency response, 40-20,000 cps. Power handling capacity, continuous 30 watts; Instantaneous peak load power, 60 watts. Impedance, 16 ohms. Size: 25Hx17Lx4 3/4"W. Supplied with 4 1" round walnut decorator legs which can be mounted on the cabinet for either vertical or horizontal placement. Shpg. wt., 24 lbs.

SK-240WX Oiled Walnut Finish

Net 59.95




FOR VERTICAL FLOOR MOUNTING

ONLY 59.95

ONLY 4 3/4" IN WIDTH

NO MONEY DOWN



UP TO 24 MONTHS TO PAY

FOR HORIZONTAL MOUNTING ON BOOKSHELVES



STEREO AUDIO ANALYST™

Single Needle Dual Channel VU Balance Meter

- UNIQUE TWO COIL GALVANOMETER TYPE PRECISION METER MOVEMENT
- SEVEN RANGES OF METER SENSITIVITY
- PROVISION FOR USE AS VU METER AND TAPE RECORDER LEVEL INDICATOR
- MAXIMUM METER SENSITIVITY 120 ua

1195


Provides the solution to all stereo balancing problems. When both signals are equal and balanced the resultant deflection on the scale will measure 0. Individual channels may be measured by two slide switches. Stable meter action and protection from peak voltages is provided by special damping networks. Single seven-step range control serves for both channels and facilitates use of meter with all amplifier power levels. By properly positioning this control the movements may be used as VU meters when terminated across the 600-ohm load. The scales are calibrated in "Volume Units". Sensitivity is 1.2 volts for 0 vu for 100 percent indication. Finished in a rich satin gold. Overall size is 4 3/8x5 1/2x4 3/4"W. Shpg. wt., 2 lbs. Imported

TM-66 Audio Analyst Net 11.95

LAFAYETTE MINIATURE HI-FI SPEAKER and ENCLOSURE

- ATTRACTIVE MAHOGANY FINISH-EO WOOD CABINET
- COMPLETE WITH 25 FEET OF CABLE

695




Enjoy music everywhere in your home with this amazing Lafayette miniature speaker system. Perfect as an extension speaker for your den, basement, kitchen or bedroom. Use two as extension speaker units for stereo or with your TV and Radio. Housed in a beautiful mahogany-finished wood cabinet with ventilated back cover, the 5-watt 4x6" speaker is designed to work from either 4 or 8 ohm outputs. System is supplied with 25 feet of cable which should meet any hook up requirement. Over-all size: 9 1/2x7 3/4x4 H (inc. feet) x 3 1/4"D. Imported

SK-109 Miniature Speaker System. Shpg. wt., 5 lbs. Net 6.95

JUST OUT!! LAFAYETTE SK-228 "MUSIC MITE" SPEAKER

- AMAZING TONAL QUALITY
- CONTAINS SPECIAL 6x4" OVAL SPEAKER
- HANDSOME MAHOGANY FINISHED WOOD ENCLOSURE
- EQUIPPED WITH 25 FT. OF EXTENSION CABLE

Only **825**




Truly amazing tonal quality—Utilizing a specially designed 6x4" oval speaker in a rigid rear vented wood enclosure this new speaker unit delivers a quality of reproduction out of all proportion to its small size. It measures only 9 3/8x5 3/4x4 1/4"D. Ideal for that inexpensive music and/or paging installation you've wanted for your store, office, den or kitchen. Use two for stereo. May be connected to either 8 or 4 ohm amplifier outputs. Supplied with 25 ft. of extension cable. Cabinet is attractively finished in mahogany. Imported

SK-228 Shpg. wt., 6 lbs. Net 8.25

NEW SENSATIONAL "SLENDERETTE" SPEAKER SYSTEM

JENSEN SPEAKERS and UNIVERSAL WOODCRAFTERS CABINETS

- Low Lafayette Price • Superb Custom Styling
- 7-Ply with Genuine Walnut Veneer • Oil Walnut Finish



JUST 5" IN WIDTH

ONLY **39.95** each

- 5-Speaker 3-Way System • 2 Jensen 6" Woofers, 1 Jensen 8" Midrange Driver, 2 Jensen 3 1/2" Tweeters

A new concept in the design of speaker systems enables you to place each system in almost any desired location of your choice—floor, wall, or top of bookshelf. A hermetically sealed cabinet, by Universal Woodcrafters, measuring only 5" deep, 24" in height, and 20" in length, represents an outstanding achievement in speaker system development. A beautifully styled grill harmonizes with all home interiors. Provides unbelievably fine speaker performance at a low, low Lafayette price. Contains a carefully integrated pneumatically dampened 5-speaker 3-way system engineered by Jensen with specially developed Jensen speaker components. Contains 2 special 6" woofer driver elements; one 8" midrange driver enclosed in its own sealed acoustic surroundings, completely separated from the woofer cavity, and 2 3 1/2" fully enclosed tweeters. Woofer has an electric crossover at 400 cps. Midrange crossover at 2,000 cps. Frequency response 50-15,000 cps. 20 watt capacity. Impedance 8 ohms. Comes equipped with hangers for wall mounting. Oil walnut finish. Shpg. wt., 24 lbs.

Net 39.95

TRUTEST STEREO 8 AMPLIFIER

NEW!



17.95

A GIGANTIC VALUE—With That Compact Low Silhouette Styling! Complete with case—to grace any location in your Home or Business. Small Enough To Fit Anywhere.

- Separate Stereo Volume-Balance Controls
- Variable Tone Control With On-Off Switch
- Front-Panel Phono-Tuner Switch for Selection of Phono or Tuner
- Selector Switch for Monaural or Stereo Operation

One of the finest stereo values we have ever offered. This attractive, compact dual channel stereo amplifier will amaze you with its fine performance—ideal for that low cost stereo system you are planning for your living room, den, bedroom or business. Its petite size lends itself easily to any location—it's attractive low silhouette styling will blend beautifully with the furniture decor in any room of your home or business. Excellent for converting your present monaural console or portable to stereo.

Controls include separate Left Channel and Right Channel Volume-Balance Controls, Stereo/Monaural Mode switch, Variable Tone control with On-Off switch, Phono/Tuner Selector switch; 4 jacks in rear for stereo tuners and stereo crystal or ceramic phono cartridges; 2 pair of 4-ohm output terminals accept most speakers. Tubes and components mounted horizontally for compactness. Complete with case. Tube complement: 1-12AX7, 2-35C5, and 1-35W4. Size: 7 1/4x4 1/2x5 3/4"D. PK-728W Shpg. wt., 6 lbs. Imported

Net 17.95

NEW! TruTest™ STEREO/5 AMPLIFIER

- Individual Stereo Volume-Balance Controls
- For Both Stereo and Monaural
- Fully Wired—Ready For Stereo

Only **10.95**



One of the finest stereo values we have ever offered. This rugged, precision made dual channel stereo amplifier will amaze you with its fine quality. Ideal for that low cost stereo system you're planning for your home or business. Perfect for converting your present console or portable to stereo. Controls include separate left channel and right channel volume controls, stereo-monaural mode switch, tone control switch and on-off switch. Provision for crystal or ceramic cartridge, 4 ohm output terminals accept most speakers. Tube complement: 2-35C5, 1-35W4 and 1-12AX4. Size: 4 1/2x5 1/2x4 1/2"D. 115 volt 60 cycles. Shpg. wt., 5 lbs. Imported

Net 10.95

COMPLETE STEREO PHONO SYSTEMS



AS LOW AS **4850**

NO MONEY DOWN

TruTest Stereo/8 Stereo Amplifier Lafayette Glaser-Steers Automatic 4 Speed Record Changer with wide range cartridge*. 2 Lafayette SK-109 Miniature Speaker Systems in Attractive Mahogany veneer finish.

Above system supplied complete with 25' speaker cable for each speaker. Shpg. wt., 26 lbs.

PK-761WXM Net 55.50

Same system as above except with Stereo/5 stereo amplifier instead of Stereo/8 stereo amplifier.

PK-751WXM Shpg. wt., 25 lbs. Net 48.50

PK-747W Mahogany base for changer Net 3.95

169

LAFAYETTE DIAMOND NEEDLES

169

COST LESS - LAST LONGER CHECK OUR FAMOUS GUARANTEE!

ALL DIAMOND STYLI ARE NOT ALIKE
• MADE FROM WHOLE DIAMONDS • PRECISION
GROUND AND POLISHED



Each Lafayette's diamond stylus is made from individual diamond, properly oriented and ground to close tolerance;

The synthetic sapphire used in these styli are of the same fine quality used in precision watch bearings.

FULL 1 YEAR REPLACEMENT GUARANTEE AGAINST DEFECTS IN WORKMANSHIP AND MATERIAL ON ALL DIAMOND STYLI

169

ANY DIAMOND or DIAMOND-SAPPHIRE NEEDLE IN THIS LISTING

KEY TO POINT CODES
HOW TO ORDER


The symbols in the column headed "PT SIZE" are explained in the table below.

LP = SINGLE 1 MIL MICROGROOVE FOR 33 1/3 AND 45 RPM

COMB = DUAL 1 MIL DIAMOND AND 3 MIL SAPPHIRE

Identify your needle by cartridge number and illustration and order by stock no. Note that all needles listed here are for monaural cartridges.

STEREO DIAMOND 169 NEEDLES



Stylus Stock No. Fig. For Cartridges

PS-89L C ACOS 73
.7 mil diamond and 3 mil sapphire styli No. 73-1

ADMIRAL CARTRIDGES
PS-80L C 409833-1(1-2-1)
PS-81L B 409C37-1

ASTATIC CARTRIDGES
PS-92L N 17, 170
PS-86L 70TS, 74TS, 76TS

COLUMBIA CARTRIDGES
PS-84L J SC-1-2-7-8

ELECTROVOICE CARTRIDGES
PS-80L C 21 and 26 Series

EUPHONICS CARTRIDGES
PS-93L K E-1-3

GENERAL ELECTRIC CARTRIDGES
PS-87L A GC7
PS-89L A VR227

MAGNAVOX CARTRIDGES
PS-80L C 560233-3-4
PS-94L D 560280-1

MONARCH (BSR)
PS-86L F TC8S, TC-8SM

MOTOROLA CARTRIDGE
PS-80L C 59K64335
PS-81L B 59B645397

PERPETUUM-EBNER
PS-81L B PE90 (M, N)

PHILCO CARTRIDGES
PS-80L C { 35-2809-1, 35-2824-1,
325-8047, 35-2825-1,
325-8036
PS-81L B { 35-2820-1, 35-2826-1,
325-8048, 325-8049
PS-86L F { 35-2827-1, 35-2829-1,
325-8051, 325-8052

RCA CARTRIDGES
PS-81L B T-1
PS-85L E { 106770-1, 106690,
108213,
108718
PS-86L {

RONETTE CARTRIDGES
PS-81L B { 0V, 0V1, T1 Single BF40
105, 105-1 (2,3,4),
106-1(2,3,4)

SONOTONE CARTRIDGE
PS-82L D { Combination .7 Mil
(stereo) diamond and 3
mil (78RPM) sapphire
for 8T and 8TA
PS-95L L { Same as above
but for 9T Series
PS-96L M { Same as above
but for 12T Series
PS-83L O { Combination .7 mil
(stereo) diamond and 1 mil
(monaural LP) sapphire
for 8T and 8TA

TELEFUNKEN CARTRIDGE
PS-90L H T20-2

VACO CARTRIDGES
PS-86L F ST20, ST40, ST100,
ST200, ST2, ST4

VM CARTRIDGES
PS-80L C 16707-A
PS-82L O 16708-F

WEBCOR CARTRIDGES
PS-80L C 21P573
PS-81L B 21P596, 21P598
PS-82L O 21P700-1-2-3-4

ZENITH CARTRIDGES
PS-81L B 142-998

Stock No.	Size Pt.	Fig.	Cartridge	REPLACES JENSEN NO.
PS-10L	LP	1	409A11, 409A300, 98A54-1	JPS-30LPD
PS-16L	COMB	6	409B21	JPS-35SD
PS-17L	LP	7	409A30	A81LPD
FOR ASTATIC CARTRIDGES				
PS-20L	LP	3	AC Series, 40T, 41T, 40-1, 41-1, 42-1, 90T series, 10-L-3, 11L-3	A-75LPD
PS-23L	LP	12	408	M-70LPD
PS-25L	COMB	14	GCD, 409, 55-T, 55T1, 55TM	A-71SD
PS-23L	LP	12	410	M-70LPD
PS-17L	LP	7	CAC, CQ, CQ-1, LQD, LQD-1, QT, QT-33, 44-T, 46-1, 48-1, 166T Series	A-81LPD
PS-35L	LP	54	118, 120, 124 series, 310T, 312T, 420, 422, 424TS series, 310-1, 310-TB, TS, 312-TB, TS, 414-1	CRA-55LPD
FOR MAGNAVOX CARTRIDGES				
PS-31L	COMB	37	560176, 560180, 560133, 560151, 560169-1, 560170	M-50SD
FOR MAGNAVOX CARTRIDGES				
PS-35L	LP	53	560176, 560180	CRA-55LPD
PS-70L	COMB	51	560161	S-66SD
FOR PHILCO CARTRIDGES				
PS-56L	COMB	43	45-9612, 76-4649, 425-0016	PH-13SD
PS-56L	COMB	43	45-0009, 425-0011, 425-0014	PH-13SD
FOR PERPETUUM EBNER CARTRIDGES				
PS-64L	COMB	47	P12/RG	RX550SD
PS-63L	COMB	48	PE-8, PE10	RX551SD
PS-66L	LP	22	P7000 (M), (MD) (LP only)	RX552LPD
FOR R.C.A. CARTRIDGES				
PS-23L	LP	12	74067	M-70LPD
PS-10L	LP	1	S5652, 76257, (988370-1), 75044	JPS-30LPD
PS-20L	LP	3	76257, (988370-2)	A-75LPD
PS-70L	COMB	51	78748, 79807, 100653	S-66SD
PS-25L	COMB	14	100329	A-71SD
FOR SONOTONE CARTRIDGES				
PS-70L	COMB	51	1P-LB-1D, 2T0, 2TS, 2T-SD, 2T-LB-D, 2T-LB-S, 2T-LB-SD, 9980-S, 9980-SD, 9980D, 5T, 57-LB-S, 5T-LB-SD	S-66SD
PS-32L	COMB	51	3T, 3TS, 3TD	S-61SD
FOR WEBSTER ELECTRIC CARTRIDGES				
PS-17L	LP	7	BX	A-81LPD
PS-10L	LP	1	F11	JPS-30LPD

REPLACEMENT STYLI FOR GE CARTRIDGES

Direct replacements for clip-in styli in GE VR II series models 4G-050, 4G-052, 4G-053, 4G-040, 4G-041, 4G-063, 4G-061 cartridges. Avg. shpg. wt., 2 oz.

PS-48L 1 mil diamond LP clip-in stylus. Replaces GE 4G-01D Net 1.69

PS-54L 1 mil sapphire LP clip-in stylus. Replaces GE 4G-01S Net .69

PS-54B 3 mil sapphire LP clip-in stylus. Replaces GE 4G-03S Net .69

MODERNIZATION ASSEMBLIES (FIG. 33)

Modernize your old triple-play cartridge. These assemblies replace both the old and new series "A." Once installed, you can replace one point at a time.

DIAMOND SAPPHIRE. Replaces old RPJ-013 and new RPJ-013A. Avg. wt., 2 oz. Net 1.69

DUAL DIAMOND. Replaces old GE RPJ-012 and new RPJ-012A. Net 3.90

PS-79L Net 3.90

DUAL SAPPHIRE. Replaces old GE RPJ-010 and new RPJ-010A. Net .99

PS-54S Net .99

STYLI FOR OLD TYPE GE CARTRIDGES (FIG. 32)

Exact replacement for all old type single needle GE cartridges. Avg. wt., 2 oz.

PS-45L Diamond 1 mil (LP) replaces GE RPJ-004 Net 1.69

PS-54L Sapphire 1 mil (LP) replaces GE RPJ-005 Net .69

PS-54O Sapphire 3 mil (78) replaces GE RPJ-001 Net .69

FOR GE SERIES A CARTRIDGES (FIG. 34)

Individual styli replacements that clip in to all GE "A" series. Avg. wt., 2 oz.

PS-47L Diamond 1 mil (LP) replaces GE RPJ-01D Net 1.69

PS-54J Sapphire 1 mil (LP) replaces GE RPJ-01S Net .69

PS-54Z Sapphire 3 mil (78) replaces GE RPJ-03S Net .69

DIAMOND STYLI FOR G.E.

AS LOW AS

169

LAFAYETTE HI FI STEREO-MONAUROAL TEST RECORD

• TESTS RUMBLE EACH CHANNEL • TESTS LEVEL EACH CHANNEL
• TESTS RESONANCE • TESTS EQUALIZATION • STYLUS WEAR TEST
• TESTS BALANCE • INCORPORATES PHASE CHECK

For stereo testing this two-sided 12" LP stereo record has on its stereo side two 1000 cycle bands to check the level of each channel separately; balance check to set the level of each channel using special metronome recording; rumble test. There are stylus wear test grooves on both outer and inner edges of each side to check both stereo and monaural styli. Incorporates phase adjusting check to simplify phasing of speakers. For monaural testing it provides an RIAA equalization test in 9 steps from 30 to 15,000 cycles, a continuous glide band from 10 to 35,000 cycles, to test for resonances of tone arm or of cabinet. Also features sections of stereo sound effects of jet planes, boat whistles, etc. A terrific value and a "must" for the Hi-Fi enthusiast. Comes with complete instructions for use. Shpg. wt., 1 lb. PR-14 Net 2.95



SPECIAL!

1.95

TONE ARM CONTROL

An absolutely essential addition for every Hi-Fi enthusiast. Ends groove and stylus damage caused by accidental dropping of tone arm onto record, greatly extending record life. Accurately and smoothly lowers tone arm into run-in groove and lifts arm off record at end of play. Ideal for "cueing." Designed to fit practically every known turntable arm as well as record changer with manual features. Supplied with adhesive mounting base to keep unit in position and with both wood and metal mounting screws for permanent installation. Shpg. wt., 6 oz. MS-785 Net 1.95

4 SPEED PHONO MOTOR WITH TURNTABLE

Quiet, dependable A-C operation assured by rubber shock-mounted friction drive motor. Speed change control through idler driving an 8" turntable. Mounting centers 4 1/2 x 3 3/4" 2 1/4" depth below base plate. Shpg. wt., 3 1/2 lbs. ML-24 Phono and turntable Net 5.35 PK-149 Mounting board for motor Net .95

5.35



STATI-CLEAN .88

Sprays a fine mist which keeps your record clear of surface noise created by static (common to all vinyl records) and clean of dust attracted by the static charge. Prevents groove and needle wear caused by static-dust and keeps records lustrous. Extends their life. Two applications a year is sufficient. Enough for hundreds of records. Shpg. wt., 8 oz. PK-105 Net .88

LAFAYETTE RECORD CLEANING KIT

Clean your valuable records the professional way with this Lafayette Kit. Contains a non-gumming anti-static detergent in polyethylene bottle. Squeeze to apply for complete elimination of static in the record grooves. Supplied with special velvet applicator in plastic pouch. Shpg. wt., 10 oz. PK-508 Net 1.29

1.29

ELECTROSONIC LAB "DUST BUG"

Automatically removes dirt and dust on each playing. Light plastic arm mounts by suction cup. Can be permanently mounted by rubber cement. The bottle of anti-static cleaning fluid has a built-in wick for application to a brush and pad at the end of arm. Shpg. wt., 6 oz. PK-156 Standard model (A) Net 5.63

ESL CHANGER DUST BUG (B). The tuft and pad assembly clips onto arm of changer. Performs the same as the standard model. Shpg. wt., 4 oz. PK-246 Changer model (B) Net 4.65

DISPENSER OF ACTIVATING FLUID. For Dust Bugs. PK-247 Net 1.22

PK-173 Replacement plush pad .78

PK-174 Replacement nylon brush .98

5.63

PHONO AMPLIFIERS

THREE TUBE AC-DC PHONO AMPLIFIER
(Fig. A) Equipped with a variable tone control and a separate volume control. Delivers two watts output. Phonograph motor connects to the amplifier. Uses 12AV6, 50C5, and 35W4 rectifier. For 110-120V, 60 cycles AC or 110-120V DC. Supplied with line cord and plug, but less tubes. Shpg. wt., 2 lbs. PK-23 2.95

2 TUBE AMPLIFIER WITH TUBES
(Fig. B) A two tube phono amplifier using a 50L6 and 35Z5 tube as rectifier. Well-built, good tone and volume. Contains volume control with switch. AT A BIG SAVING! Shpg. wt., 3 lbs. PK-24 with tubes Net 4.50

(Fig. C) Output transformer matches output tube to 3-4 ohm voice coil. Shpg. wt., 1/2 lb. TR-10 Singly ea. .49

In lots of 5, ea. .45

MODERN RECORD RACK

Attractive, brass plated rack carries 60 records of all sizes. Spring steel separators numbered 1 to 60. Heavy carrying handle. Rubber tipped feet. Size 17Lx 5 3/4x7"D. Shpg. wt., 4 lbs. PK-227 Net 1.79

1.79

NEW! .7 MIL DIAMOND STYLUS FOR SHURE M7D STEREO CARTRIDGE

PS-91L Net 4.50

4-SPEED HI-FI TURNOVER PICK-UP

• ARM TAKES STEREO OR MONAUROAL CARTRIDGES
• WITH WIDE RANGE MONAUROAL CARTRIDGE • ADJUSTABLE ARM HEIGHT AND STYLUS PRESSURE

Arm is wired for stereo, for future conversion. Has a wide range turnover monaural crystal cartridge with dual sapphire styli. Output is 1 1/2 V. Easy height adjustment at base, 1 1/4" to 1 3/4". Also stylus pressure adjustment. Plastic arm 9 1/2" long overall. Base 1 3/4" with mounting holes on 1 3/8" centers. Shielded leads. Satin smooth light maroon finish.

PK-146 Shpg. wt., 2 lbs. Net 2.75

PK-158 Sapphire LP replacement Needle Net .49

PK-159 Sapphire STD replacement Needle Net .49

2.75



LAFAYETTE TOP QUALITY RECORDING TAPE

LAFAYETTE RECORDING TAPES

LAFAYETTE QUALITY IS BACKED BY OUR MONEY-BACK GUARANTEE



LAFAYETTE'S FAMOUS MONEY-BACK GUARANTEE

Lafayette's tape is made by outstanding nationally known manufacturers. It is first quality, splice free, red oxide coated, with full frequency response, uniform output and no "drop-outs". Resistant to moisture, heat, cold and abrasion. We guarantee absolute satisfaction or your money back. If you do not find it equal to tapes costing up to twice the price, if for any reason you are dissatisfied, return the tape in 30 days and we will refund your money. You are the sole judge.

LAFAYETTE MYLAR BASE RECORDING TAPE

AS LOW AS **1.42** RT-19 900 ft. 25 & up

Mylar base is especially strong, durable and break resistant, and is virtually impervious to heat, cold or humidity. All in clear plastic reels, individually boxed.

Stock No.	Feet	Reel	Mils	Wt. Lbs.	1-4	5-24	25 Up
RT-19	900	5"	1	3/4	1.75	1.58	1.42
RT-12	1800	7"	1	1 1/4	2.50	2.25	2.13
RT-13	2400	7"	1/2	1 1/4	3.69	3.39	3.22

Tensitized Mylar
Prestretched, super-strong mylar base.

Stock No.	Feet	Reel	Mils	Wt. Lbs.	1-4	5-24	25 Up
RT-16	2400	7"	3/4	1 1/2	4.95	4.45	4.23

3" REEL 300-ft 1/2 mil Mylar tape. AS **.63**
Shpg. wt., 1/2 lb.
RT-20 Net ea. 1-4, .69; 5-24, .63

Recording Tape on 3 1/4" Reel 600 Foot 1/2 Mil Mylar Base

1 HR. PLAYING TIME AT 3 3/4 IPS. TWO TRACK FITS ALL TAPE RECORDERS. INCLUDING MINIATURE AND TRANSISTORIZED TYPES.
3 1/4" reel, 600 ft., 1/2 mil Mylar tape. Individually boxed. Shpg. wt., 3/4 lb.
RT-21 Net ea. 1-35, 5-24 ea., 1.21; 25 up ea., 1.10

CLEAR PLASTIC REELS

AS LOW AS **.23** IN LOTS OF 6

Individually boxed plastic reels for recording tape. Av. shpg. wt., 4 oz. singly.
MS-920 3 1/4" reel. In lots of 6, Ea., .23; Singly, Ea., .26
MS-692 5" reel. In lots of 6, Ea., .26; Singly, Ea., .29
MS-267 7" reel. In lots of 6, Ea., .38; Singly, Ea., .45

LAFAYETTE TAPE HEAD DEMAGNETIZER



Lafayette Tape Head Demagnetizer uses removable pole-pieces. Three complete sets are furnished: straight, 45° and 90° (right angle), permitting quick and easy use with any tape head. Far from being a luxury, a tape head demagnetizer is necessary for best tape recorder performance. Although unmagnetized when new, tape heads gradually become magnetized by sharp switching pulses occurring while switching the recorder from play to record or vice versa. The solution is to use a demagnetizer to remove this permanent magnetism from the head, thus reducing the noise level. Periodic head demagnetization is required for all tape recorders to insure optimum signal-to-noise ratio. Now Lafayette enables anyone with even the most modest budget to perform this necessary demagnetization with a minimum of effort. For 110 volts 60 cycles. Shpg. wt., 1 lb.
PK-230 Tape Head Demagnetizer 3.95

NEW! STROB-LOOP RECORDER TEST TAPE

CHECKS: • SPEED • TIMING • WOW • FLUTTER
Accurate within 1/10th of One Percent!
For 7.5 I.P.S. Shpg. wt., 6 oz.
MS-914 Net .98

YOU BE THE JUDGE! LAFAYETTE ACETATE BASE RECORDING TAPE

AS LOW AS **.85** RT-17 600 ft. 25 & up

Acetate base magnetic recording tape with uniform standard red oxide coating provides wide range high fidelity response over the audio spectrum. Features noise free reproduction, low abrasion and uniform output. In 1 mil and 1 1/2 mil thickness.

Stock No.	Feet	Reel	Mils	Wt. Lbs.	1-4	5-24	25 Up
RT-17	600	5"	1 1/2	1/2	.99	.90	.85
RT-18	900	5"	1	3/4	1.35	1.20	1.08
RT-10	1200	7"	1 1/2	1	1.59	1.49	1.35
RT-11	1800	7"	1	1 1/4	1.98	1.88	1.79

LAFAYETTE MYLAR SPECIAL

THE RECORDING TAPE BUY OF THE YEAR—YOU BE THE JUDGE!
1200 FT. 1 1/2 MIL SPLICE-FREE LIFETIME MYLAR BASE RECORDING TAPE

AS LOW AS **.89** RT-22 5 and up

Sensational buy by Lafayette brings you this 1 1/2 mil splice-free mylar base lifetime recording tape at an unbelievable low price. This 1 1/2 mil mylar tape features unprecedented recording tape strength as well as exceptional resistance to heat, cold, humidity and abrasion. 7" reel. Shpg. wt., 1 lb.
RT-22 Each Net 1.19
5 and up Each Net .89

METAL STORAGE CANS

Your best protection for valuable recorded tapes and movie film. Cans are ribbed for easy storage. Precision fit makes opening and closing easy. Attractively finished in grey. 3 sizes to choose from to fit any size reel. Av. shpg. wt., 8 ozs.
ML-154 3" Can. lots of 6, Ea. .18 Singly, Ea. .20
ML-155 5" Can. lots of 6, Ea. .27 Singly, Ea. .30
ML-61 7" Can. lots of 6, Ea. .36 Singly, Ea. .39

BUY 12 TWIST LOCK TAPE CANS

NEW! FOR ONLY **4.95**



AND GET STORAGE CHEST FREE!
12 dust-free, moisture-proof unbreakable styrene tape cans in storage chest. Can has foolproof twist lock feature and is ribbed for convenient stacking. Center locking stud prevents reel movement on all 7" reels and most 3" and 5" reels. Shpg. wt., 6 lbs.
ML-302 Net 4.95
TWIST LOCK CANS ONLY
ML-151 Lots of 6 ea. .45; Single ea. .49

LAFAYETTE BULK TAPE ERASER AND DEMAGNETIZER

PROFESSIONAL MODEL

- Erases 1/2" Tapes in One Operation—No Reversing
- For 3", 5", 7" or 10 1/2" Reels
- Completely Erases Tapes
- Two Erasing Coils
- Erases up to 1" Tape

1895



A carefully designed and precisely manufactured tape "degausser" for complete erasing of tapes. Just place the tape reel on spindle of demagnetizer, slowly rotate 2 or 3 turns, take off, and that's all. Reduce tape hiss to the level of new "virgin" tape. Two completely separate coils are used for doubly-effective erasures, even of large, 10 1/2" reels. Will erase 1" wide tape. An extra powerful unit for heavy-duty use—draws over 9 amperes. Can be used to demagnetize tape, magnetically stripped film, plus tools and watches. Has a heavy, custom finished case, a rugged non-magnetic top, heavy duty on-off switch and power cord. Has built-in fuse. Pilot light prevents accidentally leaving it turned on. Size 6 1/2 x 7 1/2 x 3 1/2". Shpg. wt., 14 lbs. Imported.
ML-120 Net 18.95


STANDARD MODEL

- Takes Reels Up To 10 1/2"
- Reduces Noise Level
- Top Value

1250



A bulk tape demagnetizer that erases existing recorded signals and noise from magnetic tapes quickly and efficiently. Also capable of demagnetizing metal parts and work tools. Ideal for the recording enthusiast desiring clean, noise-free tapes. Simply rotate reel of tape several turns, per unit, turn over and repeat once. Has two spiral positions: Inner position for tape reel sizes up to 7" in diameter, and the outer one for 10 1/2" reels. Push button energizes the coil, and a pilot light installed on top of the unit indicates unit in operation. Non-magnetic bakelite plate for tape reel rest. One powerful coil is used for effective erasure of all quarter-inch tapes. Current consumption—5 amps. Heavy duty, rugged gauge metal case. Attractive finish. For 105-125 volts, 60 cycles. Size 7 1/2 x 4 3/4 x 3 1/2". Shpg. wt., 9 lbs.
ML-176 Net 12.50



(A) ROBINS "GIBSON GIRL" SPLICER

Cuts 2 rounded indentations in the tape splice, leaving the edges of the tape which contact parts of the recorder entirely free of adhesive. Adhesive deposited on initial parts of recorder is a frequent cause of wow and flutter. As little as 1/4" tape need be removed. Shpg. wt., 1/2 lb.
MS-288 Net 6.25
MS-473 Replacement Blade .98

(B) EDITALL TAPE EDITING KIT

This kit has all the equipment required to execute a complete editing job on a professional basis. The cutting block supplied is simple to operate but is precise in its application, made of duraluminum precisely machined and polished (makes straight or diagonal cut). All accessories such as grease pencil, blades, splicing tape, 66 ft. roll of 3/32" supplied. Comes with instruction booklet in a smart metal case. Shpg. wt., 1 lb.
MS-474 EDITALL KIT Net 8.82

NEW! Lafayette RECORD, PLAYBACK and ERASE HEADS

3.95 per set
Ideal for Experimenters
Half-Track Recording Playback and Erase

A Lafayette special—ideal for the experimenter interested in tape recorders. Recording head has impedance of 9K ohm at 1,000 cps, DC resistance 130 ohms, reproduction level—40, recording at—10db. Bias frequency 30KC, bias 10MA, Frequency 60-12,000 cps ± 5db. SN ratio—40db. Erasing head: DC resistance 10 ohms, erasing current 15-20 milliamp. AC bias, DC erase systems. Record head 7/8 x 3/8 x 3/8"; erase head 3/8 x 1/8 x 3/8". Shpg. wt., 8 oz.
F-687 Net 3.95

LAFAYETTE SPECIAL 3.95 per set

Size: 1/2 W x 1/2 D x 1/4" H
RECORD PLAYBACK and ERASE HEADS for MINIATURE TRANSISTORIZED TAPE RECORDERS

A two-piece set consisting of one record/playback and one erase tape head. Designed for use in dual track miniature tape recorder. These units will replace the heads in most Japanese-built recorders, and are also excellent for the experimenter. Record/playback head specifications: impedance 2.2K at 1 KC; DC resistance: 160 ohms; reproduction level: -45db (recording at -10db); bias frequency: 35KC; bias current: 400ma; voice current: 100ma; response: 100-7000 cps ± 5db; S/N ratio: better than 45db; bias system: AC & DC reproduction: gap: .00024 in. (.006mm); dimensions: approx. 1/2 W x 1/2 D x 1/4" H. Erase head same dimensions. Total shpg. wt., 3 oz.
F-633 Net 3.95

MAGNETIC TAPE SPLICER

1.47
Cut Both Ends Simultaneously
Easy to Operate
Durable & Sturdy
An excellent accessory that splices tapes accurately and eliminates joint noise. Both ends cut simultaneously. Nicked brass finish. Shpg. wt., 1 lb.
MS-289 Net 1.47

METAL TAPE STORAGE CHEST

STANDARD CASE: Sturdy all steel carrying case. Holds 12 7" or 5" reels and cons. Twin snap locks for positive closure: perfect portability. Guards against exposure and accidental erasure. Platinum gray hammeroid finish. Metal separators between reels. Includes index cards. Shpg. wt., 5 lbs.
ML-60 Net 2.99

REEL LOCKS

.59 Set of Two
Holds tape recorder reel in place by locking spindle to reel. Especially useful if recorder is in vertical position. Will not interfere with normal operation of reels. Easily removable. Shpg. wt., 6 oz.
MS-564 Set of two .59

RCA SPLICING TAPES

Pressure sensitive for editing and splicing. Shpg. wt., 3 oz.
RT-266 Type 515C1 1/4" x 100" Net .17
RT-267 Type 511C1 1/2" x 100" Net .22
RT-268 Type 512C1 1/2" x 150" Net .30
RT-269 Type 513C1 3/4" x 100" Net .32
RT-270 Type 514C1 3/4" x 150" Net .39

TAPE CLEANER

1.49
Simple, unique recorder head cleaner. Tape is impregnated with special formula cleaner. Simply run through like regular roll of tape. Entire job done in 2 minutes. Can be reused many times. 100' roll on plastic reel. Shpg. wt., 8 oz.
PK-283 Net 1.49

ADHESIVE REEL LABELS

Convenient press-on adhesive labels for positive identification of tape reels. Easy to apply or remove. Shpg. wt., 5 oz.
MS-292 Pkg. of 30 .13

TELEPHONE PICKUP

1.89 COIL ONLY
Effective thru October 15, 1962
This telephone pick-up coil is designed to feed into the microphone input of either a tape recorder or any high gain amplifier. The pick up can be easily attached to the telephone by the use of a rubber suction type attachment. The coil is electrostatically shielded to minimize hum pick-up. When properly positioned on telephone handset, the output of this device is more than adequate for a fully modulated tape recording. Complete with 5' shielded cable. Shpg. wt., 6 ozs.
MS-693 Net .89

ROBINS TAPE THREADER

.79
No more awkward fumbling while threading a reel. Just place the tape against the reel, slip your Robins threader over the capstan shaft and over the empty reel. Tip of threader holds the tape firmly against the reel. A few turns on the crank and you're ready to play or record. Saves time and tape. Shpg. wt., 2 oz.
MS-222 .79

LAFAYETTE P.A. AMPLIFIERS AND SYSTEMS

NEW! LAFAYETTE 40-WATT PUBLIC ADDRESS AMPLIFIER



- Power Output Sufficient to Drive Many Speakers Simultaneously
- Flat Response from 30 Cps to 15 Kc
- Two Microphone Inputs, One Phonograph Input
- Separate Volume Control for Each Input
- Excellent Hum and Noise Suppression
- Attractive New Styling

69⁹⁵

NO MONEY DOWN

Here is a powerful new public address amplifier suitable for use in large department stores, stadiums, amusement parks, industrial plants, summer camps, etc. Power output is a full 40 watts. Three inputs are provided: Two microphone inputs for crystal or dynamic mikes, and one phono input for a crystal or ceramic pickup, a tape recorder, tuner or other high level program source. Frequency response: -2 db from 30 cycles to 15 Kc. Input sensitivity: mike inputs, 5 mv for full output; phono 300 mv. Input impedance: mike, 1 megohm; phono, 500,000 ohms. Hum and noise are 64 db below rated output with mike inputs and 74 db below with phono input. Hum balance control provided in rear. Each input has its own volume control to permit proper blending and balance when two or three inputs are in use simultaneously. Separate bass and treble controls. Output impedances of 4, 8, 16 and 250 ohms, and a 70V line may be taken either from a terminal strip in the rear, or from two 6-prong sockets provided for rapid connection and disconnection. Groups of speakers may be connected directly to the amplifier in various series, parallel, and series-parallel configurations. Tube complement: 1-12AX7/ECC83 microphone preamplifier, 1-6AV6 tone control, 2-6AQ8's and 4-6BQ5/EL84 output tubes (two parallel pairs operating push-pull). For 110-120 volts, 50-60 cycles AC. In an unusually attractive metal cabinet with modern black and gray panel. 5 1/4 x 13 1/4 x 9 1/4" D. Shpg. wt., 30 lbs.

Net 69.95

NEW! 40 WATT DUAL SPEAKER PA SYSTEMS



125⁹⁵

- New Lafayette Powerful 40 Watt Public Address Amplifier
- 2 University or Electro-Voice Horns For Outdoor Systems
- 2 25-Watt Speakers & Wall Baffles For Indoor Systems
- Choice of Deluxe Dynamic Mikes
- 70 Ft. of Speaker Cable

Highly efficient permanent sound systems for large halls, department store music and paging systems, railroad stations, restaurant music, etc. The outstanding Lafayette PA-268 40 watt amplifier assures top performance under all operating conditions. For 117 volts, 60 cps AC.

40-WATT PERMANENT INDOOR SYSTEM
Consists of the PA-268 40-watt amplifier, two 12" PM speakers, two attractive walnut wood baffles, two 35' speaker cables with plugs, an Atlas MS-10C floor mike stand, and Argonne AR-3 dual impedance dynamic microphone with ball-joint desk stand, for hand-held, desk stand or floor stand use. Shpg. wt., 75 lbs.

PA-284WX Net 125.95
Same as above, except with Electro-Voice 664 mike, in place of AR-3
PA-283WX Net 149.95

40-WATT OUTDOOR PA SYSTEM
Consists of a PA-268 40-watt amplifier, two Lafayette PA-57 driver units and two University PH trumpets, two 35' speaker cables with plugs, and an Argonne AR-3 dynamic mike with desk stand. Shpg. wt., 75 lbs.

PA-282WX Net 139.45
Same as PA-282WX, except with Electro-Voice 664 dual impedance cardioid dynamic mike and MS-10C floor stand, in place of AR-3
PA-281WX Net 168.45

Same as PA-282WX except with 2 Electro-Voice 848 projectors in place of PA-57 and University PH.
PA-280WX Net 157.95

Same as PA-280WX with Electro-Voice 664 mike and floor stand, in place of AR-3
PA-279WX Net 186.95

LAFAYETTE 30 WATT PA AMPLIFIER



PA-62 with PA-65 Phono Top Less phono-top

52⁵⁰

Ideal for use in churches, schools, small theaters, lecture halls and industrial plants. Separate bass and treble tone controls, permits adjustments to meet all acoustic requirements. Two mike inputs; optional 4-speed phono top, 70 volt constant voltage output tap. Provides coverage up to 100,000 square feet when used with trumpet type speakers. Chassis is equipped with 2-speaker plug-in output sockets. Housed in sturdy steel, well-ventilated cabinet, in baked hammerloid enamel. Removable escutcheon plate for rack and panel mounting.

SPECIFICATIONS: TUBES: 3-6EU7, 2-6L6GB, 5U4GB (Rectifier). **POWER OUTPUT:** 30 Watts. **INPUT GAIN:** Microphone 125 db, Phono 80 db. **FREQUENCY RESPONSE:** 30 to 15,000 cps, ± 1 db. **tone controls:** Bass ± 15 db at 50 cps; Treble ± 15 db at 10,000 cps. **HUM LEVEL:** 70 db below rated output. **INPUTS:** 3; 2-Microphone and 1-Phono. **CONTROLS:** 6; Microphone-1, Microphone-2, Power off-on, Phono-Bass, Treble, Slide Switch for operating magnetic phono thru channel 2. **OUTPUT IMPEDANCES:** 4, 8, 16, and 250 ohms (70 volt line). High impedance output for coupling booster amplifier. **POWER CONSUMPTION:** 135 Watts, 110/120 V.A.C. 50-60 cycles. Fused. 14Wx8Dx6"H. Shpg. wt., 20 lbs.

PA-62WX Complete with Tubes Net 52.50

4-SPEED PHONO TOP

Fits in place of cover. 16 2/3, 33 1/3, 45 and 78 rpm. Turnover cartridge is complete with two precious metal needles. Has arm-rest and plug connection; for 110 Volt 60 cycle. Shpg. wt., 10 lbs.
PA-65W 4-Speed Phono Top Net 17.95

DUAL-SPEAKER 30-WATT PORTABLE SYSTEMS



ATLAS MS-10C FLOOR STAND



CHOICE OF DYNAMIC MICROPHONES

ARGONNE AR-3 DUAL IMPEDANCE DYNAMIC MIKE

ELECTRO-VOICE 664 DELUXE CARDIOID DYNAMIC MIKE



The most popular system for schools, RR waiting rooms, gyms, churches, noisy factories. Ideal for rentals.

AS LOW AS

110⁵⁰

NO MONEY DOWN

- CHOICE OF DELUXE DYNAMIC MIKES
 - TWO 25-WATT SPEAKERS
 - MONEY-BACK GUARANTEE
- This 30-watt system is one of our most popular models. Large enough for the majority of sound system applications — used in thousands of school auditoriums, churches, theatres, dance halls, dance studios and lecture halls. The ideal system for rentals; these systems have been sold to many hundreds of dealers. **AND REMEMBER OUR MONEY-BACK GUARANTEE AND OUR LOW, LOW PRICE! DUAL SPEAKER 30-WATT PORTABLE SYSTEMS INCLUDE:** The outstanding feature-filled Lafayette Model PA-62 30-watt amplifier; 2—25-watt PM speakers; 2—35' speaker cables and plugs; your choice of the popular Argonne AR-3 All-Purpose Dynamic dual-impedance microphone for hand-held, desk stand or floor stand use, with removable ball-joint desk stand and floor stand adapter and 6' cable; or the deluxe dual-impedance Electro-Voice 664 Cardioid dynamic microphone for use where high-feedback problems exist, with 40-15,000 cps response, on-off switch and 18' cable; the famous Atlas MS-10C floor mike stand; and the handsomely designed split-type portable carrying case covered in high quality dark blue leatherette. Size of case 22 1/2 x 16 1/2 x 15" D — provides a secure place for the system components. For 110-130 volts, 60 cps AC operation. Shpg. wt., 75 lbs. less phono; with phono 85 lbs.
- PA-232WX 30-watt Portable System, Less Phono Top and less MS-10C floor stand. Net 110.50
complete as described with Argonne AR-3 dynamic mike Net 140.50
PA-233WX Same as above, with E-V 664 dynamic microphone and MS-10C floor mike stand Net 128.50
PA-234WX Same as PA-232WX with 4-speed phono top Net 158.50
PA-235WX Same as PA-233WX with 4-speed phono top

30-WATT MOBILE OUTDOOR PA SYSTEMS



ELECTRO-VOICE 647

AS LOW AS

145⁵⁰

NO MONEY DOWN

2—UNIVERSITY PH TRUMPETS AND LAFAYETTE PA-57 DRIVERS
CHOICE OF DYNAMIC OR CRYSTAL LAVALIER MICROPHONES
CHOICE OF OUTDOOR HORNS

- FOR 6V-12V BATTERY, 117V AC
 - WITH OR WITHOUT 4-SPEED PHONO TOP
 - CHOICE OF EITHER OF 2 LAVALIER MIKES
- 2 sound systems for the price of 1, with plenty of power for any job, whether mobile or indoor. Provides coverage for areas up to 100,000 square feet. Operates from any 6 volt or 12 volt automobile, truck or bus storage battery or from 110-130 volts 60 cycles AC. 30 watts output. **REMEMBER: THE AMPLIFIER IS UNCONDITIONALLY GUARANTEED AGAINST DEFECTS IN MATERIAL AND WORKMANSHIP FOR 1 FULL YEAR... AND COMPARE OUR PRICE!**


COMPLETE MOBILE SYSTEMS INCLUDE: The Lafayette Model PA-64 30-watt mobile amplifier complete; a set of AC and battery cables; your choice of 2—Lafayette PA-57 driver units and University PH reflex trumpets or 2—Electro-Voice 848 CDP 30-watt compound diffraction projector wide-angle horns; your choice of the Lafayette PA-31 wide-range crystal microphone with on-off switch, lavalier cord and bracket and 7' cable and connector, and with swivel-type mike stand adapter, for chest, hand-held or stand use—or, the deluxe Electro-Voice 647 lavalier dynamic mike with neck cord, support clips and 18' cable, for chest, hand or desk use; PLUS 2—35' speaker cables and plugs. Shpg. wt., 75 lbs. less phono; with phono 85 lbs.

PA-236WX Complete 30-watt mobile outdoor system with PA-64 30-watt mobile amplifier less phono top; with AC and battery cables, 2 Lafayette PA-57 driver units and 2—University PH trumpets, 2—35' speaker cables and plugs and Lafayette PA-31 microphone Net 145.50
PA-237WX Same as PA-236 except with E-V 647 mike Net 177.00
PA-238WX Same as PA-236 except with 2 E-V 848 CDP 30-watt projectors Net 164.00
PA-239WX Same as PA-237 WX except with 2 E-V 848 CDP projectors Net 195.50
PA-240WX Same as PA-236WX except with 4-speed phono top Net 165.50
PA-241WX Same as PA-237WX except with 4-speed phono top Net 197.00
PA-242WX Same as PA-238WX except with 4-speed phono top Net 184.00
PA-243WX Same as PA-239WX except with 4-speed phono top Net 215.50
PA-64WX 30-Watt Mobile Amplifier only, less phono top, 25lbs. Net 84.75

NEW! LAFAYETTE MODEL LA-75 20-WATT MUSIC AMPLIFIER



LA-75



INSTRUMENT CONTROL PANEL RECESSED FOR EASY ACCESSIBILITY

69⁵⁰

NO MONEY DOWN

- 20 Watt High-Fidelity Amplifier
- For Presenting Amplified Live Music and Voice to an Audience
- Adjustable Tremolo for "Quivering" Effect
- Built-in 12" Heavy-Duty Hi-Fi Speaker
- Separate Volume and Tone Controls for Instrument and Voice Inputs

Here is a music amplifier which will deliver 20 watts of clean power, to a built-in 12" heavy-duty 20 watt speaker or to an external 4, 8 or 16 ohm speaker. There are 3 inputs: two instrument inputs and one microphone input for voice. The two instrument inputs have volume and tone controls separate from the corresponding controls on the voice input. Built-in tremolo circuit superimposes an oscillator signal on the audio signal to create a periodic fluctuation or "quiver" whose frequency and amplitude may be adjusted by the "speed" and "strength" controls, respectively. There is a jack provided for turning the tremolo on and off by means of a foot switch (available as an accessory). Frequency response: ± 3 db from 33 cycles to 20 Kc on voice

input; ± 3 db from 33 cycles to 15 Kc on instrument inputs. Mike input sensitivity is 9 mv RMS; mike jack is shorting type to minimize hum pickup when mike is not plugged in. Tube complement: 2-12AX7's, 1-6AU6, 2-7189 output tubes, 1-6CA4 rectifier. Dimensions: 15 3/4" H (including rubber feet) x 19 1/2" W x 8 1/4" D. With carrying handle. Shpg. wt., 30 lbs.

Net 69.50

LA-75 WX
FOOT SWITCH to remotely control the tremolo in the LA-75. Equipped with cable terminated in standard phone plug to fit corresponding jack on LA-75. Shpg. wt., 1 1/2 lbs.
SW-103 Net 5.95

FOOT PEDAL

LAFAYETTE 25-WATT MOBILE ALL TRANSISTOR PA AMPLIFIER




NO MONEY DOWN

74⁵⁰


- Plugs Directly Into Cigarette Lighter
 - Operates Off 12 Volt Battery
- This all transistorized amplifier is ideal for sound trucks, parks, boats or any place where AC power is not available. Operates from any 12 volt DC source such as car battery and delivers 25 watts of power for outdoor meetings of any kind. Plugs right into cigarette lighter. Has 2 inputs: 1 for phono (2 volts) and 1 for low impedance microphone. Five control knobs are microphone volume, phono volume, bass, treble and power. Freq. response 80-12,000 cps ± 2 db. Output impedances 4, 8 and 16 ohms. Noise level: phono—80db, mike—60db. Low idling current drain. Fused. Size: 11Wx3 1/2 x 8" D. Shpg. wt., 10 lbs.

PA-256WX less phono top Net 74.50
PA-257WX 4-speed phono top for above Net 32.40

Most Outstanding Values in Wireless History



LAFAYETTE WIRELESS INTERCOM



- Move it from Room to Room—No Wires Needed
- 3-Position Operation Bar-Lever
- Dependable 3" Speaker
- For Home and Office Use
- Add as many Extra Remotes as Desired

2 WIRELESS INTERCOMS
29⁹⁵
NO MONEY DOWN

Lafayette offers the most outstanding intercom value ever. The Lafayette Wireless Intercom offers quality performance at an amazing low price. Features a three-position operation bar-lever: Dictate (for use as 'baby sitter', lengthy talking), Talk (has spring return to Listen position), and Listen. Can be plugged into any 117V outlet—move from room to room, no wires to connect. Front panel has volume control plus easy-to-see pilot light. Rear panel has adjustable squelch control. Dependable 3" speaker. For use in the home and office and use as many remotes as you need. Shpg. wt., 10 lbs.
PA-294 2-Station Intercom Net 29.95
Extra Remote for PA-294. Shpg. wt. 5 lbs.
PA-293 Net 15.25

NEW! ELECTRONIC TRANSISTORIZED INTERCOM SYSTEM

6 Station Master PLUS 2 Remotes



- Works Instantly—No Warm-up Required
- 6 Station Master Accommodates up to 6 Remote Stations
- Keep in Touch Instantly with Playroom, garage, workshop, bedrooms, offices, etc.
- Supplied With 2 Remote Stations

ONLY **19⁹⁵**

An efficient intercommunication center that is fun for the whole family. Attractively styled to enhance the appearance of any room or office. More than adequate volume with clear tone. Easy to use—just set selector to desired station—talk and listen. No need to be close to instrument when talking. Excellent for all intercom communications as well as for baby sitting. May be placed on desk or mounted on wall. Operates on 4 inexpensive "D" type flashlight batteries. Complete with 50 ft. of connecting wire, neatly packaged in carton, less batteries. Shpg. wt., 14 lbs.
PA-395 Master and 2 remotes Net 19.95
Extra remotes for above. Shpg. wt., 1 1/2 lbs.
PA-396 Net 3.98
1 1/2 volt battery (4 required) for above. Net ea. .13
BA-157 Shpg. wt., 8 oz.
Additional 2 conductor intercom wire. Net .69
WR-12 100' coil. Shpg. wt., 2 lbs.

EASY-PHONE TELEPHONE AMPLIFIER



- Lends A Valuable Helping Hand
- Amplifies Telephone To Room Volume
- 4 Transistors + Varistor
- No Dangling Wires, Pickups To Connect
- A Reminder That Caller is Waiting On The Wire
- No Warm-Up, Instant Operation

Why keep running over to the receiver to maintain contact with the other party? Instead, place the receiver on the Easy-Phone telephone amplifier and then proceed with important business while still within earshot of the telephone party. There is no need to use up one hand to hold phone, or grab receiver between neck and shoulder. With the receiver cradled on the Easy-Phone, there is complete freedom to take notes the party dictates using either long hand, short hand or typewriter. When engaged in long distance conversation, Easy-Phone will clearly amplify the communication so relatives or business associates can hear every word as it is said. On occasion the search for some pertinent article of information prevents "holding on to the wire." Easy-Phone permits the information to be sought while keeping an ear "on the wire."
Easy-Phone can be kept at office or at home—ready at all times for instant action. A four transistor, battery powered amplifier and inductive pickup, compactly

Installed in a most attractive plastic case, compose the Easy-Phone. Completely self-contained with no protruding plugs and twisted hook-up cords, it will not disarrange the orderliness of work space.
Operation is this simple: Placing the receiver on Easy-Phone turns amplifier on, then adjust volume to the proper level. Volume control is independent of on/off switch (which is depressed by receiver's weight). SPECIFICATIONS: 4 transistor circuit with 1 varistor; powered by 4 pen-light, 1.5 volt cells, self-contained; 3" dynamic speaker, out of view under amplifier; battery life 6 months with moderate usage. Weight 25 ozs. Heavy black bakelite case measures: 8 1/2 x 3 1/2 x 2 1/2". Easy-Phone rests on two sturdy chrome plated runners. With miniature plug and jack for recorder input. Shpg. wt., 3 lbs.
F-759 With Batteries. Imported Net 17.50
EXTRA BATTERIES FOR ABOVE Net .095
BA-155 Pentite cell

2-STATION INTERCOM



13⁹⁵

- SMART STYLING
- ALL-METAL CABINET
- 4" SPEAKERS
- CABLE SUPPLIED

New! Low cost intercom system that combines smart new styling with quality performance. A Lafayette special, this 2-station intercom is a must for your home, store, or business office. Units come complete with 50 feet of interconnecting cable and will save you thousands of steps and needed energy. An additional remote station may be added if needed at very low cost. The Master unit has its own volume control with "on-off" switch. No switch is necessary on remote. Power consumption is only 29 watts. This set uses a 12AT7 Dual-Diode amplifier plus a Selenium rectifier. 4" Alnico speakers are used in both Master and Remote. 110 Volts AC or DC. Measures only 6 1/2" x 4 1/2" x 4 3/4". Shpg. wt., 6 lbs.
PA-269 2-Station intercom complete Net 13.95
PA-270 Extra Remote Station Net 5.83

BRAND NEW! TRANSISTORIZED "BULL HORN"



HUNTERS
CAMPERS
BOATING
SPORTS

Until Oct. 15th, 1962

SALE PRICE **6⁸⁸**

- Weighs only 2 1/2 lbs.
- Range up to 2,000 ft.
- Completely Transistorized
- Can be Used as Long-Range Listening Device

Considered the most modern development in bull horns because it is completely transistorized—instantly operates on 6 standard 1 1/2V. "C" flashlight batteries (not incl.). With its range up to 2,000 ft., it is ideal for all outdoorsmen, for work or sports. Trigger switch is simple to operate—just press to talk. May be used as a sound detector and amplifier as well as a voice amplifier. Shpg. wt., 3 lbs.
9PA-271 Net 6.88
BA-274 1.5 Volt Batteries (6 req.) Net ea. .16

NEW! LAFAYETTE MINIATURE HORN PAGING SPEAKER

- Mounts Easily
- 90° Dispersion
- Weatherproof



7⁹⁵

An excellent general purpose paging speaker of amazingly compact size. Ideal for portable PA systems, patios, etc. Long throw projection of 90° dispersion offers maximum speech intelligibility in high noise areas. Compact size enables it to be mounted anywhere in almost any position. Frequency response 400-12,000 CPS. Impedance 8 ohms. Power handling capacity 5 watts, 8 watts maximum. Complete with mounting bracket, 2-conductor cable. Horn diameter 5 1/2". Depth 4 3/4". Imported.
PA-295 Shpg. wt., 1.4 lbs. Net 7.95

6 PUSH-BUTTON TELEPHONE



16⁹⁵

- Made by Western Electric
 - Complete with Dial and Ringer
 - 6 Illuminated Type Buttons
- Popular radie-type phone with 6 push-buttons that can be illuminated. Reconditioned like new and guaranteed to work. Ideal for intercom and private phone systems. Size and appearance may vary slightly.
PA-377 Shpg. wt., 10 lbs. Net 16.95

LAFAYETTE 25-WATT DRIVER UNIT

Fits All Trumpets And Projectors

9⁸⁵



Hermetically sealed weatherproof driver unit. Delivers 25 watts of power. Perfect for any location where high volume with low distortion is desired. The PA-57 will fit any trumpet or projector of your choice without modification. The wide-range frequency response of 120-7,100 cps assures excellent reproduction of music and speech. 16 Ohm impedance matches all amplifiers. Size 4" Diameter, 3-5/8" depth. Shpg. wt., 3 3/4 lbs.
PA-57 Net 9.85

DIAL PHONE



- For Intercoms
- Extensions
- Private Systems

5⁶⁹

Popular, modern dial phone. Can be used to make complete private systems. Equipment taken from service—guaranteed working condition. Simple, 3-wire hook up. Complete with dial, bell and connecting cable. Shpg. wt., 8 lbs.
PA-331 Net 5.69

TELEPHONES FOR INTERCOM & PRIVATE PHONE SYSTEMS

WESTERN ELECTRIC HANDSET
4²⁵
Dependable, rugged Western Electric F-1 Handset. Has countless valuable applications for intercom, private phone, etc. Reconditioned for fool-proof service. Complete with retractable cord. Shpg. wt., 1 lb.
PA-379 Net 4.25

WESTERN ELECTRIC TYPE SG-1 SOUND POWERED HANDSETS.
5⁹⁸

3 CONDUCTOR COILED CORD
.89
Exceptional value in a tough, 3-conductor coiled cord with strain relief. Excellent for phones in private phone systems, intercoms, etc. Extends to 6'. Shpg. wt., 1/2 lb.
PA-376 Net .89

Simple 2-way communications for miles. No batteries required. Just connect phone clips to two conductor wire. Excellent for Private Intercom System, Construction, TV Installer, Motels, Camps, Farms, Factories, Stores, Homes, Ski Resorts, etc. Any number of handsets can be installed on one line. Complete with retractable cord and alligator clips. Shpg. wt., 4 lbs.
PA-375 Net 5.98
PA-376 Set of two Handsets with 100 ft. of 2 Conductor Inside-Outside Wire Net 12.75




NEW! LAFAYETTE HE-20C Deluxe CITIZENS BAND TRANSCEIVER



NOW APPROVED for use in
CANADA

By Canadian Dept. of Transport
Type Approval No. 169361029

EXCELLENT FOR BUSINESS, FARM, INDUSTRY,
CAR, BOAT, PERSONAL AND SPORTS USE



LOOK AT THESE QUALITY FEATURES

- 1 14-Tube Performance, 3 Diodes
- 2 8 Crystal-Controlled Transmit Positions
8 Crystal-Controlled Receive Positions
- 3 Tuneable Receiver over all 23 channels
- 4 Illuminated Direct Reading "S" Meter for RF Power Output, Receiver "S" Readings, and Transmitter and Antenna Efficiency
- 5 Dependable Push-To-Talk Ceramic Microphone
- 6 Adjustable Squelch Control
- 7 Receive Tuneable or Fixed Crystal Selector Switch
- 8 Illuminated Dial
- 9 Highly Effective Automatic Series Gate Noise Limiter
- 10 Built-in 12 or 6 volt Power Supply for Mobile Use
- 11 Complete with channel 9 Transmit & Receive Crystals

Not A Kit!
COMPLETELY WIRED!

MADE IN U.S.A.

109⁵⁰
NO MONEY
DOWN

NOW WITH . . .
8 CRYSTAL RECEIVE POSITIONS
8 CRYSTAL TRANSMIT POSITIONS

New Efficient, Dependable Communications Microphone

Quality engineering, design, and features give this Deluxe transceiver a place all-its-own in the Citizens Band Field. Operating within the limits prescribed by the FCC, the HE-20C supplies you with a highly efficient 2-way radio-telephone communications system from your office, truck, auto, boat, store, home, etc. Two or more will serve as an effective communications system over a distance of up to 20 miles or more, depending on the terrain and the height of the antenna.


3 dual-function tubes, 1-Quadri-purpose tube, 3 tubes, and 2 Silicon rectifiers give 14 tube performance. The transmitter section features precision engineering to insure power-packed communications. The 5 watt-input crystal-controlled transmitter may be operated on any 8 of the 23 channels assigned by the FCC. The operating channel can be selected by a knob on the front panel (transceiver comes with pair of crystals for channel 9). The receiver circuits provide for 8 crystal controlled receiving channels plus a tuneable superheterodyne receiver that covers all 23 assigned channels, with a sensitivity of 1 microvolt. Effective built-in Squelch circuit quiets the receiver when no signal is being received. Series Gate Noise Limiter materially reduces ignition noise and other unwanted interference. An illuminated dial with planetary vernier tuning is clearly marked with channel numbers and lights up when tuned to any channel. New tuneable or fixed receiver switch permits selection of tuneable and fixed receive operation. The receiver terminates in 4" speaker amply supplied by over 2 watts of audio power. The unit comes

complete with a push-to-talk ceramic microphone that is conveniently mounted to the side of the transceiver. Push-to-Talk operation is accomplished with a sturdy, dependable relay. An illuminated "S" meter calibrated in S units 1-9 and to 30 db. above S-9, allows measurement of incoming signal strength. The meter is wired with a switch to enable monitoring of final amplifier wattage output and as indicator of transmitter efficiency. Incorporates Pi-network for optimum matching to 30-100 ohm antenna for high signal output. A low-loss antenna jack is mounted at the rear of the cabinet to accept the popular PL-259 connector used with dipole, ground plane, rod, and direct mounting (Lafayette HE-19) Antennas. Rugged, low silhouette case with a bracket handle for installation at any location and in any position. Tube line up: 1-6AW8A, Oscillator/Amplifier; 1-6BA6, RF Amplifier; 1-6AU6 1st IF Amplifier; 1-6EA8/6U8A, mixer/rec. osc. 1-6EA8, 2nd IF Amplifier and 1st Audio Amplifier; 1-6AQ5 Audio Output/Modulator; 1-6T8, ANL, Detector, AGC, Squelch Clamp and 2nd Audio Amplifier. Size 12x5x8 1/2" D. With 115 Volts AC/12 Volts DC or 115 Volts AC/6 Volts DC Power supply.

ME-20CWX 115 AC/12 Volts DC, Shpg. wt., 14 lbs.	Net 109.50
ME-43BWX 115 Volts AC/6 Volts DC	Net 109.50
ME-65CWX 220 Volts AC, 50/60 cycles—12 Volts DC	Net 109.50
ME-830 Transmit Crystal (Specify Channel or Frequency)	Net 2.25
ME-22L Receive Crystal (Specify Channel)	Net 2.25
Direct plug in antenna for short distance communications.	
ME-19 Shpg. wt., 1 lb.	Net 3.95



NEW! LAFAYETTE HE-15B 2-WAY SUPERHET CITIZENS BAND TRANSCEIVER!



NEW
8 Crystal Transmit Positions
Increased Selectivity in IF's
Attractive Modern Styling

NEW SENSATIONAL LOW PRICE **54⁵⁰** NO MONEY DOWN

COMPLETE 2-WAY COMMUNICATIONS FOR BUSINESS, HOME, FARM, BOAT, AND SPORTS

Not Superregenerative but SUPERHET!
NOW WITH ADDED FEATURES

- 8 Crystal-Controlled Transmitting Positions
 - Effective Full-Wave Variable Noise Limiter
 - RF Jack on Front Panel
 - Ceramic Temperature-Free Microphone
- SUPERHETERODYNE TUNEABLE RECEIVER OVER FULL 23 CHANNELS • 4 DUAL FUNCTION TUBES, PLUS 2 SINGLE-FUNCTION TUBES, PLUS 2 RECTIFIERS FOR 12-TUBE PERFORMANCE • PLANETARY VERNIER TUNING • COMPLETE WITH TRANSMITTING CRYSTAL FOR CHANNEL 9

THE GREATEST VALUE
in the CITIZENS BAND FIELD

The Lafayette HE-15B Superheterodyne Transceiver is both a compact precision transmitter and receiver designed to operate on the new class D "Citizens Band." Two or more of these units furnish your own communications system covering up to a 20 mile or more radius depending on antenna height and terrain. The Transceiver features 8 crystal controlled transmitting channels operating at a maximum legal power input of 5 watts fully modulated, RF stage in both transmitter and receiver. The 8 position crystal selector on the front panel selects any one of 8 transmitting frequencies. These 8 crystals are readily accessible by means of a removable front plate. The superheterodyne receiver is tuneable over the full 23-channel band, with 3 watts audio output, AVC, and an amazingly effective Full-Wave Variable Noise Limiter. The Noise Limiter is continuously variable from the front panel for diminishing ignition and other unwanted noise pickup.

RF jack on the front panel may be used to monitor the current in the final tube using external meter. Controls include a 3-position function switch (transmit, receive, and transmit with spring return), planetary vernier tuning, plus variable noise limiter. Output impedance matches 52 and 72 ohm antenna with Amphenol type coax connector. Has large PM speaker; input jack for crystal or ceramic microphone; power receptacle in rear

for AC line and 6 or 12 volt external power supply. Supplied with single transmitting crystal for channel 9, high output ceramic microphone, and brackets for easy mounting of units in auto, boat, etc. Operates on 115 volts AC. Addition of 6 or 12 volt power supply (separately supplied) adapts transceiver for mobile operation. Size 10 1/2 x 5 1/2 x 6 1/2" D. Tube complement: 2-6U8A/6EA8, 1-6AL5, 1-6V6, 1-12AX7, 1-6AW8.


ME15BWX Shpg. wt., 11 lbs.	Net 54.50
POWER SUPPLY: Adapts HE-15B for mobile operation. Complete with cable, 6 or 12 volt vibrator and mounting flanges. Completely enclosed. Size 4 1/2 x 6 x 4 1/2" H. Shpg. wt., 4 lbs.	Net 10.95
ME-16W For 12 Volts	Net 10.95
ME-18W For 6 Volts	Net 10.95
ANTENNA: Base loaded telescoping whip antenna with PL259 coax connector. Mounts directly on rear of cabinet. Telescopes to only 15". For short distances.	
ME-19 Shpg. wt., 2 lbs.	Net 3.95
TRANSMITTING CRYSTALS: For any of the 23 channels. Specify channel or frequency.	
ME-830	Net 2.25

LAFAYETTE

STOCKS THE MOST COMPLETE LINE OF CITIZENS BAND ANTENNAS AND ACCESSORIES AT THE LOWEST PRICES

ANOTHER OUTSTANDING LAFAYETTE CITIZENS BAND VALUE

NEW! 11 METER BUMPER MOUNT ANTENNA WITH STAINLESS STEEL STRAP



8⁹⁵

- Chrome Plated Bumper Mount with Stainless Steel Strap
- 102" Stainless Steel Whip, Heavy Duty Chrome Plated Stainless Steel Spring

An outstanding Lafayette antenna featuring a full size 102" stainless steel whip and a fully adjustable chrome plated mount with a stainless steel strap which will fit most cars. Heavy duty chrome plated stainless steel spring is built for rugged use. Shpg. wt., 3 lbs. HE-802WX

Net 8.95

Superb Lafayette Fiberglass CB Antenna!

48" CONTINUOUSLY LOADED CITIZENS BAND COWL MOUNT ANTENNA



6⁹⁵

- Rugged Fiberglass Construction
- Easily Mounts On Cowl or Rear Deck

Lafayette makes antenna news with this new continuously loaded fiberglass antenna — only 48" high but performs like 102" antennas. Designed for cowl mounting this latest development in mobile antennas provides an excellent radiation pattern. Substitutes for conventional 1/4 wave whips as well as base-loaded and center loaded antennas in the 27 mc band. The four foot whip eliminates the possibility of striking overhead objects. A black plastic covering of whip insures against shorting. Specially designed rocker support assures 8 point grounding and permits mounting up to 35° angle on fender, cowl or rear deck — Fits any 1/4" to 1 1/4" mounting hole. Complete with 5 ft. of RG-58-U cable. HE-57W Shpg. wt., 3 lbs.

Net 6.95

LOW COST — ECONOMY CITIZENS-BAND GROUND PLANE ANTENNA

LIGHTWEIGHT TUBULAR ALUMINUM ELEMENTS



8⁸⁰

Here's rugged performance in a Citizens-Band base station antenna at a truly economical price. Incorporating a special "drooping radial" design for improved impedance characteristics, this excellent ground plane antenna utilizes a 360° polar pattern to provide complete coverage in any direction. Made-to-last construction features a rugged 1 inch diameter radiating element. A double U-bolt arrangement provides the strongest possible mount under the most severe conditions. HE-694WX


Shpg. wt., 6 lbs. Net 8.80

THE LAFAYETTE "Super-Beam" ANTENNA

A 3 Element Vertical or Horizontal Beam Antenna For Citizens Band.

MULTIPLIES POWER 8 TIMES **25⁹⁵**

No Money Down



Developing a tremendous forward gain of 9db this new Lafayette "Super Beam" is the most powerful CB antenna available. Works equally well for transmitting and receiving. Front to back ratio of 25 db and front to side ratio of 40 db. Provided with bracket for vertical mounting for contacting mobile stations or ground plane equipped base stations. Units may be stacked horizontally or vertically for an additional 3db gain which effectively redoubles power; making the effective radiated power of your 5-watt CB transmitter equivalent to approximately 80 watts input. Ruggedly constructed of all aluminum heat treated alloy. Two inch O.D. boom is 8 feet long. Elements measure 16 1/2 ft. long with 3/4" to 5/8" O.D. HE-64WX

Shpg. wt., 18 lbs. Net 25.95

LAFAYETTE TM-59'er "S" METER



8⁹⁵

- Now For Hams, SWL's and CB'ers—A Signal Strength Meter Using VTVM Principles • Easy To Install and Operate
- Magnetic Feet For Mobile Dashboard Mounting
- Sensitivity and Zero Adjust Controls

Designed for use with any superheterodyne receiver employing AVC, the TM-59'er utilizes a high input Wheatstone bridge circuit which produces no detrimental loading effect upon the receiver. Meter is calibrated in "S" units from 1 to 9, and in db up to 40db over S9. Includes zero adjust and sensitivity controls. Partial peak clipping is provided for noise limiting. Installation is simple—only 4 leads to connect for input, B+, filament and ground. The use of a 12AU7 tube makes the TM-59'er adaptable to either 6 or 12 volt equipment, and to receivers using 150 ma or 300 ma series string filament systems. Requires 150-200 VDC for B+ which can be "stolen" from most receiver power supplies. Complete with 12AU7 and installation instructions. TM-59A Shpg. wt., 2 lbs.

Net 8.95

LAFAYETTE MODEL TM-15A WAVE-METER for AMATEUR and CITIZEN BANDER




8⁹⁵

A miniature wavemeter for checking transmitter output. Determines relative strength of fundamental frequency and any harmonic or parasitic radiation, and in so doing aids in elimination of these unwanted emissions. Complete and self contained, the TM-15A requires no power source. Telescoping antenna is included. Merely choose proper band and turn tuning knob until edgewise 3/4" panel meter indicates the presence of RF. If indications occur at several points within the range of the wavemeter, the transmitter is probably radiating spurious frequencies. Tunes 1.6 to 150 mc in four calibrated bands. Only 3 1/8" x 2 3/4" x 1 1/2" D. Antenna is 10 3/4" extended. 3 1/4" telescoped, is fitted with a banana plug and is removable. Total shpg. wt., 8 oz. TM-15A

Net 8.95

NEW DELUXE LAFAYETTE GROUND/PLANE ANTENNA



11⁹⁵

- The Ideal Antenna For Your CB Base Station
- High Efficiency Ground Plane Antenna
- All Aluminum Construction
- Accepts PL-259 Connector

Solid aluminum 108 inch heat-treated radials and radiator. Elements supplied in two 54 inch lengths joined by threaded coupling nuts. Radials droop for 50 ohm match. Accepts 1 1/4 inch tubing RG-58/U cable and PL-259 connector. Shpg. wt., 4 lbs. HE-890W

Net 11.95

LAFAYETTE TELESCOPIC CITIZEN'S BAND WHIP ANTENNA

SENSATIONAL VALUE IN A DIRECT MOUNTING CITIZENS BAND ANTENNA



3⁹⁵

Sturdy, attractive chrome plated whip antenna that telescopes from approx. 45" fully extended to only 15" to facilitate portability and storage. Ideal for shorter distances up to several miles. Has enclosed base loading coil for proper impedance matching. Complete with removable PL-259 connector that permits direct top, side or rear mounting to transceiver. HE-19 Shpg. wt., 1 lb. Net 3.95

LAFAYETTE GENERATOR NOISE FILTER

- Frequency Range 3-30 mcs • Simple to install
 - Maximum Current 25 Amps • Adjustable
- Enables quiet receiver operation for Citizens Band. Amateur and industrial frequencies. Standard frequency range 3-30 mcs. Maximum current 25 amps. CF-135 Shpg. wt., 1 lb. Net 2.49

NEW "SPEAKEASY" AUDIO COMPRESSOR AMPLIFIER for CITIZEN BAND TRANSCEIVER



- For Mobile and Base Transceivers • Built-in Modulation Meter • Works with all Popular CB Units
- Automatically and effectively increases average modulation, voice, readability, and therefore distance without over modulation. Speak Easy is suitable for mobile or base use, and is available for 115/12 or 115/6 volts. Final power input to transmitter remains within legal 5 watt limit, but effective voice power is increased many times. Easily attaches to your CB transceiver, requires practically no power for operation. Complete operational and installation instructions are provided. 2 1/4" x 4" x 4" D. Shpg. wt., 3 lbs. 9HE-905 'Speak Easy' 115VAC/12DC Net 29.50 9HE-906 'Speak Easy' 115VAC/6DC Net 29.50

ANTENNA SPECIALISTS NEW "BLACK BOX" M-82 CB ANTENNA AMPLIFIER




- Produces Constant 100% Legal Power at the Antenna
- Increases the Effective Transmitted Modulation Gain by 10 db, The Received Gain by a Minimum of 20 db.
- Drastically Reduces Inherent Mobile Interference

An entirely new class of CB power accessory that gives you fantastic new performance into and out of your present CB equipment. Increases the effective transmitted modulation gain by 10 db, the received gain by 20 db (minimum). SPECS: Control Box—On/Off Switch, Neon Pilot Light, Fused; with 10' RG-58/U Cable and PL-259 Connector. 3x4x5". Amplifier—Aluminum Weatherproof Case, 4 tubes, 10' RG-58/U Cable, Self-powered, 3 1/2" dia. x 1 1/4" deep. Meets FCC Limitations. Easy to install. Shpg. wt., 15 lbs. HE-969WX

Net 78.35


ANTENNA SPECIALISTS MAGNUM-27 1/2 WAVE 27MC ANTENNA



Compact vertical radiator with an actual 6 DB gain over any single element omni-directional antenna. Constructed of rigid aluminum and cadmium plated steel, it is corrosion resistant, waterproof and fits on most masts or directly into wooden areas. Hi-Q phasing transformer provides proper resonance over entire CB band. Direct ground lightning protection. 50 ohm feed. Total height is only 18" 2", (17" 3" radiator, 4-54" radials. Shpg. wt., 12 lbs. HE-487WX

Net 27.86

LAFAYETTE "DUMMY" ANTENNA LOAD FOR CB TRANSCEIVERS



A 52 ohm non-inductive load for testing and tuning-up Citizens Band transmitters up to 5 watts. It permits tune-up into a non-radiating element instead of into antenna in compliance with F.C.C. regulations. Built-in PL-259 coaxial plug is easily connected and disconnected from equipment. Shpg. wt., 1 lb. HP-203

Net .98

CDR AR-22 AUTOMATIC ROTOR FOR CITIZENS BEAM



This heavy-duty rotor unit will handle antennas up to 150 lbs. Simply set the control unit pointer to the desired direction, and the antenna will automatically rotate to this position and stop. Perfect for TV, Ham or Citizen Band application. Rotor unit employs 12 heavy duty ball bearings in two 6 1/2" races. Weather-proof motor reverses instantly and is factory lubricated for life. Reversible clamps on rotor will take masts from 7/8" to 2" O.D. Control unit is marked in compass points. N.S.E.W. N.W. N.E. S.W. and S.E. Housed in attractive brown plastic cabinet with rubber feet. Complete with rotor, control unit and instructions. For 110-120 volts 50-60 cps AC. Requires 4 conductor cable. HE-476WX

Net 32.77

4-Conductor cable for HE-476WX rotor WR-24 ea. ft. Net .03; 100 foot length Net 2.39

LAFAYETTE TRANSISTORIZED FIELD STRENGTH METER

- Permits Easy Tune-Up For Maximum Transmitter Output
 - Earphone Jack to Monitor Audio • Tuned Input from 2.53 to 57 MC
- A transistorized tuned field strength meter covering 2.530 Mc to 57,000 Mc in 3 bands. Ideal for use with ham, Citizens Band or other transmitters within this frequency range. Enables user to tune his transmitter and antenna for maximum RF output. The RF is sampled by a plug-in telescoping antenna (supplied) and relative field strength is read on a 200 μ a meter calibrated from 0 to 10. Earphone jack provided for the monitoring of any audio on the signal. Electrical and mechanical zero adjustments on front panel. Other controls: gain/on-off switch, tuning, and band selector switch. Powered by single small 1 1/2 volt battery with lifetime approaching "shelf life"—can be operated anywhere. In attractive metal cabinet with telescoping antenna and battery. TM-16A Shpg. wt., 2 lbs. Net 15.95
- High output earpiece for use with TM-16A. MS-439 Net 1.09
- BA-155 Replacement battery for above Net .095

15⁹⁵

TM-16A



LAFAYETTE RADIO FIELD INDICATOR

- A MUST FOR ALL HAM AND CB OPERATORS
- Continuously indicates transmitter output
- Rugged 200 μ a meter movement
- Requires no Electricity, Batteries, or Transmitter Connection
- Powerful Magnet on Bottom Plate for Mounting on Dashboard or Other Metal Surface

With this rugged, new radio field indicator you can check performance of your marine, mobile or fixed transmitter. Features a 200 μ a meter movement with variable sensitivity control. Earphones can be plugged in for an aural check of output. Antenna extends from 3 1/4" to 10 3/4". Powerful magnet on bottom plate allows easy mounting on car dashboard or metal surfaces. Use anywhere... requires no electricity or batteries. Dimensions: (less antenna) 3 1/8" x 2 3/4" x 2" D. TM-14 Shpg. wt., 7 oz. Net 6.95

High output crystal earpiece for use with TM-14. MS-439 Net 1.09

6⁹⁵



TM-14

CITIZENS BAND 2-WAY RADIO COMMUNICATIONS

FREE!

CITIZENS BAND ANTENNA

Select 1 of the 4 CB antennas listed below and receive this antenna free with the purchase of any Citizens Band Transceiver on this page.

ANTENNA SPECIALISTS MODEL MC-27 GROUND PLANE ANTENNA



15⁶³

Solid aluminum 108 inch heat-treated radials and radiator. Elements supplied in two 54 inch lengths joined by threading coupling nuts. Radials droop for 50 ohm match. Accepts 1 1/4 inch tubing RG-58/U cable and PL-259 connector. Shpg. wt., 4 lbs. HE-661WX Net 15.63


LAFAYETTE DELUXE BUMPER MOUNT ANTENNA



15⁹⁵

Adaptable to virtually all American and Foreign cars. Includes double bumper mount with cable terminals, cadmium plated spring 102" stainless steel whip, 20 ft. of RG-58/U cable with PL-259 connector on one end, solder lugs on the other, and whip hold-down clip. Shpg. wt., 5 lbs. SP-198WX Net 15.95

HI-PAR MODEL CO-27 COAXIAL ANTENNA



14⁹⁵

The half-wave coaxial antenna is widely used in commercial and emergency communications. It consists of a quarter-wave vertical element (108" long) above a quarter-wave cylindrical "skirt" which surrounds and is concentric with the mast. Constructed entirely of aluminum, it requires 15 ft. 1 1/4" TV mast-ing or 12 ft. aluminum tubing for support. Uses RG-59/U or RG-11/U coaxial line. Overall height, 17'6". Shpg. wt., 5 lbs. HE-804WX Net 14.95

ANTENNA SPECIALISTS MODEL M-23 MOBILE REAR COWL MOUNT ANTENNA



18⁵²

Complete Antenna Kit for rear deck or side mounting. Consists of cadmium plated base, special alloy cadmium plated spring, 102" stainless steel whip, cable and gutter clip. Furnished with 20 ft. RG-58/U cable, having PL-259 connectors on both ends. Shpg. wt., 6 lbs. HE-674WX Net 18.52



JOHNSON VIKING "MESSENGER" CB TRANSCEIVER

AS LOW AS **134⁹⁵**

Designed for reliability and easy installation in your home, business location, car, truck or boat. Excellent receiver sensitivity and selectivity. Features 5 crystal controlled receiving and transmitting channels. Transceiver has 10 tubes (including rectifier). Compact modern styling — 5 3/4" x 7 1/4" x 1 3/4" D. Complete with tubes. Push-to-talk microphone, and crystals for one channel. Shpg. wt., 1 1/2 lbs.

HE-447WX Model 242-128 115VAC/12VDC	Net 144.95
HE-448WX Model 242-127 115VAC/6VDC	Net 144.95
HE-451WX Model 242-126 115VAC	Net 134.95
Universal Dash Mounting Kit for HE-447WX, HE-448WX, HE-451WX.	Shpg. wt., 2 lbs.
HE-407 Model 251-828 Lafayette transmit type crystal for Johnson "Messengers."	Net 2.50
HE-830 (Specify Frequency) Lafayette receiver type crystal for Johnson "Messengers."	Net 2.25
HE-833L (Specify Frequency)	Net 2.25

NEW! VOCALINE ED296 TRANSISTORIZED 6-CHANNEL TRANSCEIVER

249⁹⁵
NO MONEY DOWN



The advanced Vocaline ED296 Transceiver has 22 transistors, 8 diodes, and 3 tubes. 3-stage AGC, eliminates blasting and fading. Receiver is a double conversion superheterodyne unit. Transmitter provides a full 3 watts output, with 100% modulation. Features "S" meter for easy tuning. Sensitivity better than 0.2 μV for a 6db signal plus noise/noise ratio. Selectivity is 40db down ±6kc. Entire unit mounts quickly for rugged mobile use or operates as a free-standing unit. Power requirements: 117VAC/12VDC. Complete with mike and one transmit crystal. Size: 5 3/4" x 9 3/4" x 9 3/4". HE-258WX Shpg. wt., 16 lbs. Net 249.95

Lafayette Transmit Xtal for ED296 (specify channel). Net ea. 2.25
HE-255L Net 2.25

SONAR MODEL E 5-WATT CITIZENS BAND RADIO

179⁵⁰
NO MONEY DOWN



The Model E combines a highly sensitive superheterodyne receiver with a 5 watt transmitter in a completely self-contained, compact unit. Receiver features a sensitivity of 0.5 microvolt for 10 db quieting, an adjustable squelch and an automatic series noise limiter. Selectivity is 5 KC at 6 db down. Can be operated on 8 crystal controlled channels or tuned over all 22. Transmitter input is a full 5 watts (FCC limit), modulated up to 100%. Operates on 8 crystal controlled channels, with a frequency stability of .005% or better. Adjustable squelch. Includes high impedance ceramic microphone with push-to-talk switch. Completely self-contained dual power supply. Measures only 11 1/4" x 9 1/2" x 4 3/4" H. HE-372WX For 117VAC/12VDC — Shpg. wt., 12 lbs. Net 179.50
HE-373WX For 117VAC/6VDC Net 179.50
Lafayette matched receive/transmit crystals for Model E Net 4.50
HE-832L (Specify frequency) Net 4.50

NEW POLY-COMM "N" CB TRANSCEIVER

189⁵⁰



Designed for continuous, heavy-duty operation, the "N" with a NuVistor front end, an ultra high-gain stage which pulls in the weakest signals, provides sensitivity of better than 0.1 μV for 6 db S/N and better than 0.14 μV for 10 db S+N/N. Precision engineered and tested to fine professional performance. Equipped with all electronic transmit/receive switching and 4 crystal controlled transmit/receive channels. Other features include: dual conversion superheterodyne receiver with adjustable squelch circuit and floating series gate type noise limiter, built-in carrier and modulation indicator, 4 full watts audio output. Minimum of 3 watts power output to antenna. Adjustable antenna matching for 52 or 72 ohms. Weather-proof 4" 8m speaker, cadmium plated weatherproof steel case and chassis. Shock proof ceramic microphone has press-to-talk switch and retractable coil cord. 11 tubes and 7 diodes give eighteen tube performance. Complete with crystals for one channel. Microphone and instructions. Size 11x7 1/2 x 5". Shpg. wt., 18 lbs. HE-293WX 115VAC/12VDC Net 189.50
HE-294WX 115VAC/6VDC Net 189.50
Lafayette matched crystals (receiver/transmit) for Poly-Comm "N". HE-297L (Specify Channel) Net 4.50

ALL STAINLESS STEEL CITIZEN BAND MOBILE ANTENNA

OUTSTANDING FEATURES

- 102 1/2" Stainless Steel Whip For Optimum 11 Meter Performance
- Heavy-Duty Chrome Plated Stainless Steel Spring
- Chrome Plated Swivel Ball Jointed Mount Base

6⁹⁵

Chrome plated swivel ball mount base designed to be mounted on any surface. Stainless steel spring holds rod in properly adjusted position and prevents rod damage from shocks and blows. Stainless steel whip for maximum resiliency and strength. Shpg. wt., 4 lbs. Has lug terminals for HP-52 cable assembly. HE-800WX Net 6.95

NEW! LAFAYETTE CHROME PLATED MOBILE BUMPER MOUNT WITH STAINLESS STEEL STRAP

- Completely Adjustable For Use With Most Types of Automobile Bumpers
- Highly Reliable and Durable!



3⁹⁵

An outstanding new Lafayette mobile Bumper Mount featuring chrome plated mount and stainless steel strap which is completely adjustable for vertical mounting on most types of automobile bumpers. Eliminates need of cumbersome link type chain mounts. Shpg. wt., 1 1/2 lbs. HE-33 Net 3.95

NEW UNIVERSAL LAFAYETTE CITIZENS BAND AMATEUR SPRING AND SWIVEL BALL-MOUNT BASE

2⁸⁹



• Heavy-Duty Chrome Plated Stainless Steel Spring HE-54

1⁹⁵



• Chrome Plated Swivel Ball Jointed Mount Base HE-53

New universal Lafayette HE-53 chrome plated swivel ball mount base with lug terminals for use with mobile antennas. Exclusive Lafayette design provides easy adjustment and at the same time prevents loosening by vibration or shock. Can be mounted vertically or horizontally on any surface. With lug terminals for use with mobile antennas. HE-53 Net 1.95

New Universal Lafayette HE-54 Heavy duty chrome plated stainless steel spring. Provide maximum support for long whips and heavy center-loaded whips. HE-54 Net 2.89

LAFAYETTE AUTO-MARINE ENGINE NOISE SUPPRESSOR KIT

9⁴⁵




• A Must For Mobile CB & Ham Operators
• 14 Components Plus Hook-Up Wire

This easily installed kit will effectively suppress ignition, generator and voltage regulator noise. Consists of 8 spark plug suppressors; 1 distributor suppressor, 1 voltage regulator suppressor; 4 coaxial capacitors; shielded cable and braid for wiring filter system. All necessary hardware and instructions for installation are included. Shpg. wt., 2 lbs. HE-204 Net 9.45

JUST OUT!

NEW LAFAYETTE CITIZENS BAND COLINEAR GROUND PLANE ANTENNA



- Double Power In All Directions
- 3.4 DB Gain Over Normal Ground Plane Antennas
- Built-To Heavy-Duty Commercial Specifications

Only **24⁹⁵**
No Money Down

Increase the performance of your Citizens Band rig with this newly developed Lafayette antenna. Utilizes a new concept in CB antenna design which achieves gain through colinear action. Concentrates more power at lower angles to the horizon. Performs equally well receiving or transmitting, greatly increasing the range of consistent CB communications. Precision Tuned and matched for 52-ohm coaxial cable, either RG-8/U or RG-58/U. Overall only 20-ft. high; radiator is 1 1/2" O.D. to 3/4" O.D. heavy wall heat-treated aluminum tubing. 9-ft. long radials of 3/8" O.D. aluminum tubing. Accepts all masts up to 1 3/4" diameter. Complete with matching stub and assembly instructions. Shpg. wt., 10 lbs. HE-63WX Net 24.95

SQUELCH THAT INTERFERENCE!

NEW LAFAYETTE HE-55 SQUELCHER



- PROVIDES FULL SQUELCH AND NOISE LIMITING TO MOST SUPERHETERODYNE TRANSCEIVER OR RECEIVER
- VASTLY IMPROVES MOBILE TRANSCEIVERS WHEN VEHICLE IS IN TRAFFIC
- REDUCES NOISE FROM IGNITION SYSTEMS AND OTHER SOURCES

10⁹⁵

The Lafayette "Squelcher" noise eliminator was designed to improve reception and reliability in most superheterodyne transceivers or receivers including the Lafayette HE-20A, HE-20B, HE-20C, HE-30, HE-45, HE-50 and KT-320. Reduces noise from ignition systems and other sources. Quiets receiver when no signal is received. Vastly

improves sensitivity of mobile transceiver when operating in traffic. Complete with 2 tubes (6AL5 and 12AX7) and instructions for installation. In Satin aluminum with blue gray perforated cover. Furnished with cable. Size 2 3/10" x 3 3/4" x 4 1/4". HE-55 Shpg. wt., 1 1/4 lbs. Net 10.95

20 FT. RF COAXIAL CABLE ASSEMBLIES FOR CITIZENS BAND EQUIPMENT



A 2.95

B 2.45

These cable assemblies are necessary for connection between Citizens Band Transceiver and Antenna. TYPE A—Consists of 20 ft. RG-58/U cable with PL-259 plus UG-175/U on both ends. Required for Ground Plane and Coaxial and Mobile Antennas terminating in a coaxial jack. Shpg. wt., 8 oz. HE-51 Type A 20 ft. length Net 2.95
TYPE B—Same as type A except one end is terminated with PL-259 plus UG-175/U and other end with universal ring type terminal lugs for mobile antennas. Shpg. wt., 8 oz. RECOMMENDED FOR USE WITH HE-800WX MOBILE ANTENNA HE-52 Type B 20 ft. length Net 2.45

LAFAYETTE BROADCAST TO CITIZENS BAND COUPLER




6⁹⁵

Specially designed network permits any Citizen's band mobile antenna to be used also for broadcast reception. No switching necessary. With SO-239 antenna receptacle. 2 ft. lead with coaxial auto plug for broadcast radio connection and 2 ft. lead with PL-259 coaxial plug for transceiver connection. Shpg. wt., 3/4 lb. HE-202 Net 6.95

LAFAYETTE 12 POSITION CRYSTAL SELECTOR

6⁵⁰

Houses and selects up to 12 crystals - increases channel coverage. Chassis has 12 ceramic crystal sockets, wired to a 12 position, no stop selector switch. Long reach shaft permits practical mounting. Chassis size: 2 1/4" D x 2 1/4" W x 2 1/4" H. Shpg. wt., 1 lb. HE-201 Net 6.50





Model HE-51
10 tube 30-50 MC

- Tuneable and Crystal Controlled

52⁵⁰
NO MONEY DOWN

LAFAYETTE FM AM POLICE RECEIVERS

- 10 TUBES
- BUILT-IN 4" PM SPEAKER
- EASY-VISION SLIDE RULE DIAL
- DRIFT-COMPENSATED



Model HE-52
10 tube 145 - 175 MC

52⁵⁰
NO MONEY DOWN

- Tuneable

Here is a quality communications receiver which picks up police calls, fire department, CD etc., all over town. Keep alert to emergencies at any hour. Quality built, it is safe to say that a better communications receiver could not be found at twice its price. Look at these features. Powerful 10 tube performance, even a short length of wire will suffice to bring in strong local signals. 3 IF stages; Crystal controlled and tuneable, the HE-51 can be accurately tuned to a pre-selected frequency for long periods of time. Critical tuning and drift problems are virtually eliminated. The crystals for fixed frequency operation can be ordered separately—(See below) Though most signals in the 30-50

MC range will be FM, some transmissions are AM and a handy front panel FM-AM slide is provided. Built-in squelch circuit reduces background noise, without adversely affecting its sensitivity. The built-in 4" speaker can be cut-out for headphone operation with a panel mounted slide switch. Either high or low impedance phones may be used. Provision has been made for connection of a larger external amplifier if desired. Tube complement: 6AQ8, 6BC5, 6U8, (3) 6AU6, 6AL5, 12AX7, 6AQ5, 6X4 for 105-120 VAC. Size: 12 1/2 x 4 1/2 x 6 1/2". Shpg. wt., 14 lbs. Imported

HE-51WX Net 52.50

Crystal for Fixed Freq. operation—30-50 MC. Please specify exact operating freq.—supplied within .005%. Allow 30 days for delivery.

HE-759L

Net 5.95

M-80LB Window mount antenna for 30-50 MC. Shpg. wt., 3 lbs.

HE-959W

Net 7.35

Now you too can "listen-in" to police, fire, forestry, civil defense, marine and other important municipal and industrial activities right in your own home. Keep yourself constantly alert to emergencies at any hour. Quality built, the HE-52 offers powerful 10 tube performance at a low, low Lafayette price. Look at these features: Sensitive RF stage for maximum low noise amplification—even a short length of wire (2 1/2 to 5 ft.) will suffice to bring in sufficiently powerful signals. Provision has been also made for connection of more elaborate 75 or 300 ohm antennas if needed. 3

IF stages; built-in squelch circuit functions without reducing the receiver's sensitivity to information-bearing signals. The built-in 4" speaker may be turned off when switching to phone operation. Either high or low impedance earphones may be used if they are terminated by phone tips. An amplifier jack is provided on the rear of the unit to enable connection of a larger external amplifier if desired. Tube Complement: 6Q8, 6AQ8, (3) 6AU6, 6AL5, 12AX7, 6AQ5, 6X4. For 105-120VAC. Dimensions: 12 1/2 x 4 1/2 x 6 1/2". Shpg. wt., 14 lbs. HE-52WX Tuneable only Imported Net 52.50

M-7A low power, high quality ground plane antenna for 145-175 MC.

Net 5.39

HE-960 Shpg. wt., 1.5 lbs.



POLICE CALLS



OCEAN TUGS



FIRE ALARMS

AMAZING NEW 4 BAND LAFAYETTE SHORTWAVE BROADCAST RECEIVER

MODEL HE-60
ONLY **39⁹⁵**
NO MONEY DOWN

FREE

**BONUS
RECEIVE
HEADSET**

& Phone Plug for Headset Absolutely Free with Purchase of HE-60 Receiver.



- Covers 550 KC to 30 MC in Four Bands: 550 - 1600 KC (Broadcast Band) - 1.6-4.4 MC, 45-12 MC, 11-30 MC (Shortwave bands)
- Sensitive Superheterodyne Circuit • Easy Tune Slide Rule Dial • Built-in 4" Speaker • Receives Voice or Code Signals


Listen to the wonderful sound of international broadcasting with this fine shortwave and standard broadcast receiver. Enjoy the many fascinating foreign broadcast programs in English and other languages and also the bands used by ships, planes and amateurs plus standard AM broadcasts. Tunes all frequencies from 550 kilocycles to 30 megacycles in four bands. Features a modern superheterodyne circuit for 5 tube performance and clear reception. Large easy to read slide rule dial permits simple accurate tuning for any station on-the-air. Bands: (1) 550-1600 KC; (2) 1.6-4.4 MC; (3) 4.5-12 MC; (4) 11-30 MC. Front panel controls consist of On/off vol-

ume, Main Tuning, Band Selection and Phone/CW switch. Code Signals are received by using the Phone/CW switch. Private listening can be achieved by connecting low impedance headphones to the built-in front panel jack. Front panel speaker is automatically disconnected when headphones are used. 3 tubes plus silicon diode. In attractive wrinkle finish. For 115-125V 50/60 cycles AC. Size: 10 1/4 x 5 3/8 x 8 1/8" D. Shpg. wt., 9 lbs. Imported. Lafayette Shortwave Broadcast receiver HE-60 plus Free headset and phone plug for headset. Net 39.95

HE-60WX Imported

LAFAYETTE CLASS D C.B. CRYSTALS

For Popular CB Transceivers
Extremely accurate 3rd overtone crystals. Meets F.C.C. tolerance requirements of .005%. For use as transmit crystal for the following popular 11 meter CB transceivers:



As low as **195**
each
in lots of 3 assorted


- LAFAYETTE HE15A
- LAFAYETTE HE15B
- LAFAYETTE HE20A
- LAFAYETTE HE20B
- LAFAYETTE HE20C
- LAFAYETTE HE29A
- LAFAYETTE HE29B
- BROWNING S-9
- EICO 772
- GEN. RAD. MC1
- GEN. RAD. MC2
- GEN. RAD. MC3
- GLOBE CB100
- GLOBE CB100A
- HAMMARLUND HQ105TR
- JOHNSON VIKING
- HEATH CB1
- HEATH GW10
- LASALLE LA-101
- MIRATEL CR117
- PHILMORE TC-90
- RADSON RT70A
- RAY JEFFERSON
- RCA MARK VII
- SONAR MODEL "D"
- SHELL CB-12
- SONAR MODEL "D"
- TEL-RAD
- UTICA MC27
- WESTRON 909
- WORLD RADIO ECBK
- DEWALD TR910

Pin spacing, .486" pin diam., .050". Frequencies available:

27 MC TRANSMIT CRYSTAL FREQUENCY CHART			
Channel	Meg.	Channel	Meg.
1	26.965	9	27.065
2	26.975	10	27.075
3	26.985	11	27.085
4	27.005	12	27.105
5	27.015	13	27.115
6	27.025	14	27.125
7	27.035	15	27.135
8	27.055	16	27.155
		17	27.165
		18	27.175
		19	27.185
		20	27.205
		21	27.215
		22	27.225
		23	27.255

HE-830 Specify Channel or Crystal each, 2.25 in lots of any 3 assorted, each, 1.95

HARTMAN SHIP-TO-AUTO ALL TRANSISTOR CONVERTER



- Ship-to-Ship Broadcast • Marine Telephone
- WWV • Coast Guard (weather) • Ship-to-Shore Conversations

Now you can listen to marine broadcasts on your car radio. A flick of the switch and your auto radio becomes a powerful long range marine receiver. Switch back and it plays the normal broadcast band. All transistor circuitry uses only 1/2000 of an amp from built-in battery; virtually the batteries entire shelf life. Converter selects any frequency between 2000 KC and 3000 KC. Operates with either 6V or 12V automobile ignition system. Net 19.95



Hi-gain
SWI ANTENNA
FOR INDOOR USE

Convenient indoor Model SWI improves the performance of any shortwave receiver. Covers 5-30 MC. Easy to install and operate. Six-foot cable (included) is attached to receiver, the telescoping "rabbit ear" extended, and the "match" and "tune" controls set for maximum signal strength. Attractively housed in unbreakable plastic with chrome-plated antennas. Model SWI. Shpg. wt., 2 1/2 lbs. Net 14.75

HYGAIN MODEL SWO FOR OUTDOOR USE

Model SWO high efficiency doublet antenna for outdoor use. Traps peaked on the 11, 13, 16, 19, 24, 31 and 40 meter shortwave bands. Only 40 feet long. With insulators, 100 ft. of lead-in wire and instructions. Shpg. wt., 2 1/2 lbs. Net 14.75

SPECIAL LAFAYETTE UNIVERSAL 6 METER AND BROADCAST MOBILE ANTENNA

AT OUR LOWEST
PRICE EVER

4.75 375

Effective Thru Oct. 15, 1962

ONE ANTENNA FOR BROADCAST & 6 METERS!

Here is a highly efficient 6 meter antenna that replaces your Auto radio antenna for operation on both 6 meters and for regular AM broadcast reception. 59" stainless steel mast, all chrome ball type base adjustable to 180° for front rear or side mount. Complete with 54" lead. Highly versatile and durable. Shpg. wt., 4 lbs. Net 3.75

HE-801WX Imported

NEW LAFAYETTE ALL STAINLESS STEEL 6 METER MOBILE ANTENNA

695

OUTSTANDING FEATURES

- 58 in. Stainless Steel Whip For Optimum 6 Meter Performance
- Heavy-Duty Chrome Plated Stainless Steel Spring
- Chrome Plated Swivel Ball Jointed Mount Base

Chrome swivel ball mount base designed to be mounted on any surface. Stainless steel spring holds rod in properly adjusted position and prevents rod damage from shocks and blows. Stainless steel whip for maximum resiliency and strength. Shpg. wt., 4 lbs. Net 6.95

HE-49W Net 6.95

Hi-Par "SATURN 6" MOBILEER

ONLY **16⁵⁹**

A compact, horizontally polarized mobile antenna for 6 meters. It is essentially an end-loaded folded dipole with 3 ring design, approximately 20" in diameter, 5" high. Design center is 50.5 Mc but resonant frequency may be varied between 50.5 and 53.0 Mc. Easily fed with RG58/U coax. Rigid aluminum construction; net weight under 2 lbs. Easily supported on pipe, tubing or stiff rod. Model S-1—"Saturn 6" Antenna, 2-piece adjustable aluminum mast, mast bracket, universal bumper hitch. No holes to drill. Less coax feed line. HE-805W Shpg. wt., 5 lbs. Net 16.59

ANTENNA SPECIALISTS 6 AND 10 METER VERTICAL COAXIAL BASE STATION ANTENNAS

MODEL M-39 10 meter 1/2 wave length coaxial antenna providing a low angle, omnidirectional radiation pattern. Operates with 52 ohm cable. 1/4 wave jointed, solid aluminum vertical radiator bolts to 2" diameter 1/4 wave aluminum skirt. Total height is 16 1/2". Mounts on 3/4" IPS pipe (not supplied). Accepts PL-259 connector. Shpg. wt., 8 lbs. Net 19.55

MODEL M-40 6 meter coaxial antenna with same features as model M-39. Total height is 9 1/2". Shpg. wt., 5 lbs. Net 14.57

HE-968W Net 14.57


BRAND NEW LAFAYETTE HE-48 SPEAKER

DESIGNED TO GIVE SUPERIOR
VOICE REPRODUCTION FOR SSB,
AM, CW AND OTHER VOICE APPLI-
CATIONS.

795

The HE-48 speaker is handsomely styled to enhance your present facilities. Special 3x5 speakers gives distortion free response, 8 ohm impedance. Imported. Net 7.95

HE-48 Net 7.95



NEW! ANOTHER SMASHING LAFAYETTE HAM VALUE!


SEE THESE ALL STAR FEATURES

- ★ 90 watts phone or CW — 80-10 meters
- ★ Built-in 3-section Low Pass Filter
- ★ Neutralized Final Amplifier
- ★ Clear, Chirpless Grid Block Keying

COMPARE!

79⁵⁰

NO MONEY DOWN



LAFAYETTE STARFLITE™ 90-WATT PHONE AND CW TRANSMITTER KIT

The new Lafayette Starlite Transmitter Kit was designed to meet the needs of the greatest number of amateurs — General AM Phone or CW. Easy to build, its many quality design features offer superior engineering and premium quality components comparable to high-priced commercial units. Single-knob bandswitching provides instant coverage of 80 through 10 meters. The Starlite operates on a power input of 90 watts. A front panel switch selects any of five crystal positions with provisions for an external VFO. Controlled carrier modulator permits almost 100% of the CW input to be used on AM peaks. Grid-block keying provides chirp-free operation; a rugged efficient full-wave silicon diode power supply effects extremely low output ripple for cleaner CW transmission. Other quality features include an electron-coupled Pierce oscillator, capacitance bridge neutralization of the 6146 final and a three-stage low-pass filter. An illuminated edgewise D'Arsonval panel meter indicates final grid or plate current for easy tune-up. Pi-network output provides the proper match between the impedance plate circuit and any 50-72 ohm coaxial antenna. Assembly is simplified by the clearly written and profusely illustrated Lafayette instruction manual. Modern low silhouette in heavy gauge steel cabinet. KT-390 Shpg. wt., 25 lbs. Net 79.50

SPECIFICATIONS:

POWER INPUT — 90 watts peak; OPERATION: CW, AM phone — crystal or VFO control; Band Coverage: 80 to 10 meters; COUPLING: Pi-network; Tubes: 6146, (2) 6CL6; 12AX7, 6DE7. LOW PASS FILTER. Power requirements: 105-125VAC, 50/60 CPS. 225 watts.

NEW! TRANSISTORIZED 100 KC CRYSTAL CALIBRATOR MODEL TE-29



TE-29

ONLY **11⁹⁵**

- Generates Useful 100 Kc Harmonics Up To 54 Mc
- Transistorized, Self-Powered and Self-Contained
- Completely Wired—Not a Kit
- Tunes to WWV Signals

The TE-29 is a transistORIZED 100 Kc oscillator with an output of high harmonic content. It will provide accurate markings every 100 Kc up to 54 Mc. Can be used to calibrate receivers and VFO's, or to mark band edges to insure in-band operation. The TE-29 may also be used as a constant signal source. The output may be coupled to the receiver directly. Can be tuned to WWV signals for accurate frequency calibration and the coil can be peaked for optimum output. These points are easily accessible from the bottom of the unit. Powered by a small 9-volt battery, the transistor oscillator is completely self-contained—requires no "digging" into the receiver for power. Housed in a 5Wx2½x2½" H sturdy metal box. Complete with battery. Net 11.95
TE-29 Shpg. wt., 1½ lbs. Net .49
BA-3 Replacement battery for above

NEW! TRANSISTORIZED 100 KC & 1 MC MARKER CALIBRATOR



TE-27

ONLY **17⁹⁵**

- Gives Markers Every 1 Mc, or Every 100 Kc, at the Flick of a Switch
- Fully Transistorized, Self-Contained and Self-Powered
- Completely Wired—Not a Kit
- Tunes to WWV Signals

Here is a unique marker calibrator offering all the features of a conventional calibrator plus many unusual advantages. It consists of two crystal controlled transistor oscillators running at 100 Kc and 1 Mc, respectively. The function switch on the front panel has 3 positions: Off 1 Mc, and 100 Kc. The 1 Mc markers are useful in locating amateur band edges up through 6 meters, and for rough calibration of general coverage receivers. Since they are farther apart, they are easier to identify in frequency than the 100 Kc markers, so that they may be used as starting points in calibration. Once the 1 Mc intervals are established and identified, the switch may be thrown to the 100 Kc up to 54Mc, so that the calibration may be refined to intervals of tenths of a megacycle. Completely self-contained and powered by a small 9-volt battery. Output is taken from one binding post, on the side, housed in a 5Wx2½x2½" H sturdy metal box. With battery. Net 17.95
TE-27 Shpg. wt., 1½ lbs. Net .49
BA-3 Replacement Battery for above

JUST OUT! "AUDIOPHONIC" MICROPHONE KIT



- Specially Designed Ceramic Element
- Frequency Response: 30-10,000 CPS
- Requires Only 15 Minutes Assembly Time



EQUALS MIKES THREE & FOUR TIMES IT'S PRICE
The ideal microphone for audio enthusiasts, amateurs, education and sound laboratories. Employs an attractive lightweight cast aluminum housing with a specially designed, rugged ceramic element which is unaffected by temperature and humidity. Frequency Response is 30-10,000 CPS. Sensitivity at 1000 CPS is — 52db. Assembles easily in only 15 minutes. Complete with 36" cable. Size: 1½x4½". Shpg. wt., 1½ lbs. Net 6.88
M-70

HIGH QUALITY TOP NOTCH CRYSTAL MICROPHONE



PRICED EXTRA LOW!
COMPARE FOR VALUE

3⁹⁵

Lafayette makes history with a high quality CRYSTAL MICROPHONE at a price that is less than any comparable Crystal Microphone on the market today. Excellent for PA systems, home recorders and general applications. Frequency response 30 to 10,000 cycles. Output level—52 db. provides ample output for use with low gain amplifiers. Uses quality moisture sealed crystal; Die-cast case in rich green baked enamel finish, with chrome grill. Completely equipped with 5 feet of shielded cable. Mike may be used on any stand with ¾"-27 thread. Grill diameter, 2¾", depth 4¼", height 4½". Shpg. wt., 3½ lbs. Imported Net 3.95
PA-24

3-WAY SLIM CRYSTAL MICROPHONE



- May be hand-held, stand mounted or suspended by lavalier cord!
- RESPONSE 60-10,000 CPS
- ON-Off Switch

SALE PRICE

Reg. 3.95

3²⁹

until Oct. 15, 1962

A tremendous value! Unique design, only 4½x1½" diam. Comes complete with swivel adapter to fit all standard mike stands, and lavalier cord and bracket which leaves both hands free. Smooth wide range response. Locking type on-off slide switch. Detachable 7 ft. cable and connector. Shpg. wt., 2 lbs. Imported PA-31 Singly Each 3.29



STUDIO CRYSTAL MICROPHONE

- DUAL CRYSTAL CARTRIDGES
- ALL DIRECTIONAL
- FINE QUALITY
- HIGH OUTPUT

4⁹⁵

Here is a microphone with a 360° pickup, and the added power and sensitivity of two individually shock mounted and phased crystal cartridges. This arrangement assures you of maximum pickup from all sides. Swivel mounted to give fuller flexibility. Case is chrome plated. Standard ¾"-27 thread. Overall size 7Hx3"W complete with 4 ft. cable. Shpg. wt., 4 lbs. Imported PA-17 Net 4.95

11⁹⁵



NEW! DUAL IMPEDANCE SLIM DYNAMIC MICROPHONE

- ON-OFF SWITCH
- RUGGEDLY CONSTRUCTED
- 600 & 50,000 OHM IMPEDANCES SELECTED BY SIMPLE ROTATION OF PLUG

Beautiful, professional-looking dynamic with solidly-cast, tapered, slim case with satin-chrome finish. Heavy duty slide-type on-off switch. Built-in transformer supplies dual unbalanced impedances—low Z is 600 ohms, high Z is 50,000 Ohms. Swivel mount fits all standard ¾"-27 threaded stands. Blast filter eliminates unpleasant "pops" with voice use. Omnidirectional when used vertically—cardioid pattern when tilted. Engineering design and finish are of the highest quality, making this microphone excellent for any application. Complete with 5 ft. plug-in cable. Shpg. wt., 2½ lbs. Imported PA-46 Net 11.95

TRANSISTORIZED MIKE MIXER



6⁹⁵

- Up to 4 Channels
- Matches Hi Impedance Microphones

A compact microphone mixer capable of providing professional results. Mixer controls from one to four signals from hi-impedance microphones, tuner, phonograph and/or recorder. Permits amplifying or fading of any channel while holding the volume of other channels. Inputs accept standard 2-circuit phone plugs—output jack accepts standard circuit phone pin plugs. Requires single 9-volt battery (not supplied). Size 6Wx2½Hx3¼"D. Shpg. wt., 1½ lbs. PA-292 Imported Net 6.95
BA-2 Battery for above Net .39

ATLAS MICROPHONE ACCESSORIES



1.85 .85

Amphenol Mike Switch. Attach between male and female of 75 series connectors. Push-to-talk with lock. Shpg. wt., 6 oz. CM-87 Amphenol 75-MC1S Net 1.05
"Y" Connector. Has 2 males and 1 female. Shpg. wt., 2 oz. MS-84 Net .85

8⁹⁵

Specifically designed for Citizens Band Use!

DYNAMIC PUSH-TO-TALK MICROPHONE FOR CITIZENS BAND TRANSCEIVERS

- Specifically designed For CB Use
- Momentary-on Spring Return Switch
- Lightweight • Deluxe Styling

Lafayette now offers a new top quality dynamic microphone at an unusually low price. Specifically designed for citizen band and communication transceivers. Attractive design in black and chrome; tapered styling to fit the hand easily. High impedance dynamic transducer will not be adversely affected by heat and smooth frequency response of 100 to 11,000 cycles make it most suitable for communications work—indoors or out. Comes equipped with a momentary push-to-talk switch, coiled rubber cable with a 5-prong plug and a convenient hang up bracket. Shpg. wt., 1 lb. Imported PA-274 Net 8.95

NEW "DYNA-SLIM" MICROPHONE

- HIGH IMPEDANCE 50,000 OHMS
- ON-OFF SWITCH
- "QUICK-SLIP" ADAPTER

6⁹⁵

New dynamic, high output microphone with many features of "mikes" sold above Lafayette's price! Output level — 55 db. Smooth response from 60 to 10,000 cycles. Omnidirectional head. External on-off switch. Slips on or off stand adapter in a wink. Standard ¾"-27 adapter permits tilting mike for multi-angle use. Satin black and chrome finish. Complete with detachable cable and connector. 8" long, 1½" max. dia. tapered barrel 7". Shpg. wt., 2 lbs. PA-43 Imported Net 6.95

MICROPHONE VOLUME CONTROL



1⁷⁶

No more running to the P.A. amplifier to adjust volume. Now, control volume output right at the microphone. Attached between the microphone and the cable; Can be used at any desired distance. Fitted on one end with a female mike connector and male mike connector on the opposite end. Shpg. wt., 12 oz. MS-755 Remote Volume Control Imported Net 1.76

Sensational Values In Lafayette Communication Receivers!



LAFAYETTE Professional Quality AMATEUR COMMUNICATIONS RECEIVER

Designed for TODAY'S CROWDED AMATEUR BANDS


4-BAND { • 4.8 mc-14.5 mc • 550 kc-1600 kc
• 10.5 mc-30 mc • 1.6 mc-4.8 mc

SUPERHETERODYNE CIRCUIT

HE-30 WIRED
99⁹⁵
NO MONEY DOWN

KT-320 SEMI-KIT
79⁹⁵
NO MONEY DOWN

- 8 TUBES PLUS RECTIFIER TUBE
- 1 RF + 2 IF STAGES FOR HIGH GAIN RECEPTION
- EASY-TO-READ, ILLUMINATED, SLIDE RULE DIAL
- BUILT-IN Q-MULTIPLIER FOR CROWDED PHONE OPERATION
- ANTENNA TRIMMER FOR OPTIMUM PERFORMANCE ON ALL BANDS
- CALIBRATED ELECTRICAL BANDSPREAD ON AMATEUR BANDS 80 THRU 10 METERS
- 0-100 LOGGING SCALE FOR SWL'S
- EFFECTIVE AUTOMATIC NOISE LIMITER
- AVC-MVC SELECTOR ON FRONT PANEL
- STABLE OSCILLATOR AND BFO FOR CLEAR CW AND SSB RECEPTION
- BUILT-IN EDGWISE S-METER



795

RECEIVER
SPEAKER-MATE HE-48



Outstanding Bandspread, Selectivity with a built-in Q-multiplier, and sensitivity combine to make the HE-30 one of the "hottest" general coverage bandspread receivers ever priced below \$200. For the crowded amateur bands—illuminated Slide Rule Dial, bandspread with markings every 5 KCS on 80 and 40 meters (IT TAKES 16 REVOLUTIONS OF THE BAND SPREAD DIAL TO COVER EACH OF THESE BANDS), every 20 KCS on 20 and 15 meters, and every 50 KCS on 10 meters, plus an edgewise S-meter. For the SWL—a 0-100 logging scale for "instant reset" to a desired station plus coverage from 0.55-30 MCS. The 8 tube (plus a husky 5Y3 Rectifier) circuit provides an RF stage with an antenna trimmer for peak performance PLUS 2 IF stages for improved selectivity. The HE-30 utilizes a 5Y3 tube in a transformer Full Wave rectifier power supply for performance with a minimum of hum. Receiver sensitivity—1.0 microvolts for 10db Signal-to-Noise Ratio. The built-in BFO can be used to separate CW stations by means of the pitch control, while the Q-multiplier adds the selectivity needed for crowded phone band operation. Front panel controls: FUNCTION SWITCH, AUDIO GAIN, SELECTIVITY (Q-Multiplier), FREQUENCY (BFO), BAND SELECTOR, IF GAIN, TRIMMER, AVC-MVC SWITCH, ANL SWITCH, MAIN TUNING BANDSPREAD TUNING, and headphone jack. Selectivity — 60db at 10KC, 0.8 KC @ 6db (with Q-multiplier), IF — 455KCS, Speaker — External PM type (not supplied), 4 or 8 ohms impedance, Audio Output — 1.5 watts. Tubes — 6BA6 — RF Amplifier, 6BE6 Mixer, 6BE6 — Oscillator, 6AV6 — Q-Multiplier-BFO, 2-6BA6 — IF Amplifier, 6AV6 — Detector-AF Amplifier — ANL 6AQ5 — Audio Output, 5Y3 — Rectifier. Size — 7x15x10"D. For 105-120, 60 cps AC, 50 watts. Imported

HE-30WX Shpg. wt., 25 lbs. Net 99.95

NEW! KT-320 SEMI-KIT

This receiver is also available in kit form with all major components and front end pre-mounted and pre-calibrated. All other components supplied for easy mounting.

KT-320 Semi Kit Net 79.95

RECEIVER SPEAKER MATE

SPECIAL 3x5 speaker in handsomely styled cabinet to match HE-30. Gives clean audio response. 8 ohm impedance. Size: 7 3/4 Hx 3 1/2 Wx 5" D. Shpg. wt., 4 lbs.

HE-48 Net 7.95

LAFAYETTE AMATEUR COMMUNICATIONS RECEIVERS

SUPERHETERODYNE CIRCUIT UTILIZING 8 TUBES & RECTIFIER TUBE

KT-200 SEMI-KIT
64⁵⁰

HE-10 WIRED
79⁹⁵

NO MONEY DOWN

The KT-200 represents a significant departure from usual kit designs. As soon as it is unpacked, it is already half finished. All of the mechanical mounting is completed. Tube sockets, transformers, main tuning capacitor, filter capacitor, controls, even knobs and pilot lamps are all in place. The tuning assembly is installed and operative. Most important of all, the complex coil assembly and alignment capacitors for the oscillator mixer and rf amplifier stages are factory mounted and pre-aligned. Thus only a slight touch up will be required to achieve maximum sensitivity and selectivity. Features such as built-in "S" meter with

adjustment control, switchable AVC and automatic noise limiter make the KT-200 worth many times its low price. Supplied with all components.

KT-200WX Same as above, factory wired Net 64.50
HE-10WX & Tested Net 79.95

RECEIVER SPEAKER MATE
The HE-48 speaker is handsomely styled to enhance your KT-200 or HE-30. Special 3x5 speakers gives distortion free response. 8 ohm impedance. Size: 7 3/4 Hx 3 1/2 Wx 5" D. Shpg. wt., 4 lbs.
HE-48 Net 7.95

SPECIFICATIONS:
AM, 80-40-20-15-10 meter bands. Pre-calibrated band spread. Sensitivity: 1.25 mv for 10 db Signal-to-noise ratio. Selectivity: ± 10KC, —60db (at 1MC). Audio Output: 1.5 watts. Tubes: 3—6BD6, 2—6BE6, 2—6AV6, 1—6AR5, 1—5Y3. Power: 100-125 V AC 50/60 cps. Size: 15 1/2 Lx 8 1/4 Hx 12" D. Shpg. wt., 22 lbs.


ELECTRONICS ILLUSTRATED
"... even the most inexperienced constructor should have no trouble."
"Sensitivity was so great the IF gain had to be turned all the way down to prevent overloading."

15 73
"... excellent value"
"... rugged, well made, and uses good components."




RECEIVER SPEAKER-MATE

HE-48
795



LAFAYETTE SHORTWAVE BROADCAST RECEIVER KIT

4 BAND Power Packed Superheterodyne Circuit Covering the Broadcast Band (550-1600KC) and Shortwave From 1600KC to 30 MC (1.6-4.4MC, 4.5-11MC, 11-30MC).



KT-222 Semi-Kit plus FREE Soldering Pencil
39⁹⁵
NO MONEY DOWN

- Improved Sensitivity • Electrical Bandspread • Built-in "S" Meter
- AVC — Noise Limiter • BFO • Phone Jack • Big 5" Speaker

SMARTLY STYLED DURABLE METAL CABINET

Now, you can tune in the world with this fabulous, new Lafayette KT-222 BC-SW receiver. Keep up to date with the spot news coverage. Power packed superheterodyne circuit covers the broadcast band (550-1600KC) and shortwave from 1600 KC to 30 MC in four bands. The perfect radio for shortwave listeners. Features a precision electrical bandspread with slide rule bandspread dial, 0-100 logging scale for easy self-calibration. Separate bandspread tuning condenser and calibrated "S" meter for accurate tuning. Meter can be electrically adjusted by rear panel control. Sensitive circuit features AVC (Automatic Volume Control) to minimize blasting and/or fade out; Automatic noise limiter to reduce annoying interference. Includes convenient front panel B.F.O./selectivity control to allow for reception of CW (telegraphy). Also has convenient front panel headphone jack which automatically disconnect

speaker. Jack can be used to drive an external speaker. Built-in 5" PM speaker provides big, clear sound on all stations. Useful tone switch is included to vary sound to suit conditions, or taste. Three antennas (ferrite loop for broadcast band, adjustable 58" whip for short wave and wire antenna) provide high sensitivity and flexibility for best reception. Low impedance phones are recommended for use with this unit. Attractively styled steel cabinet with silver trim. Powered by 4 tubes plus a selenium rectifier. 1—12BE6; Converter, 1—12BA6; IF Amplifier, B.F.O., 1—12AU6; Audio Amplifier, AVC detector, 1—50C5; Audio output. Operates on 105-125; 50/60 cycle AC/DC. Size 13 1/2 Wx 5 7/8 Hx 8 3/4" D. Shpg. wt., 12 lbs.

KT-222 Semi-Kit plus FREE Soldering Pencil
HE-77M Imported Net 39.95
SAME AS KT-222, but factory wired and tested.
HE-77 Imported Net 49.95

BUILT-IN "S" METER

FREE! Soldering Pencil with Purchase of KT-222

LAFAYETTE'S MONEY BACK GUARANTEE IS YOUR ASSURANCE OF SATISFACTION

LAFAYETTE RADIO ELECTRONICS PAGE 37

New! LAFAYETTE Deluxe 6 METER TRANSCEIVER MODEL HE-45A

**NOW! front panel antenna loading controls!
VFO POWER JACK! popular new ham mike!**

- Highly Sensitive Superheterodyne Receiver Section for 50-54 Mc
- With minimum drift circuitry
- 3-Stage, 12 Watt Transmitter with 2E26 Final
- Built-in 117 VAC and 12 VDC Power Supplies
- Pi-Network Transmitter Output
- Illuminated Panel Meter for Plate Current and "S" Readings
- Effective Series Gate Noise Limiter
- Complete With Push-To-Talk Ceramic Microphone

Now, for 6 meters, Lafayette offers a deluxe transmitter-receiver in a single package, with features which make the low price hard to believe. Provides maximum convenience and flexibility in either mobile or fixed operation. The superheterodyne receiver section employs an RF stage with peaking control on front panel, and two i.f. stages at 1650 Kc. for 1 μ v sensitivity and 35 db image rejection. Tunes the entire 6 meter band from 50 to 54 Mc. with calibrated illuminated vernier tuning dial. Features an adjustable series gate noise limiter, built-in speaker. Illuminated panel meter serves as an "S" meter when meter function switch is set to the proper position. Transmitter section employs a 6U8 oscillator and buffer/multiplier, driving a 2E26 final with a plate input of approximately 12 watts on AM. Pi-network coaxial output, and front panel antenna loading controls. Sockets for 28 Mc fundamental crystals plus an input for external VFO on the front panel chosen by 3-position selector switch. A spotting switch is provided for zero beating or for locating the transmitting frequency in the receiver. Panel meter reads plate current when switch is set to proper position. A dual power supply for 117 VAC and 12 VDC is built in, making the HE-45A perfect for mobile operation. Push-to-talk operation provided. Tube complement: 12BA6 RF amplifier, 1-6U8/6EA8 osc./mixer, 12BA6 1st i.f. amp., 1-6U8/6EA8 2nd i.f. amp./1st audio, 1-6CN7 detector/noise limiter, 1-6AQ5 audio output and transmitter modulator, 1-6U8/6EA8 transmitter oscillator and buffer/multiplier, and 1-2E26 transmitter final amplifier. Housed in a rugged, low-silhouetted base with attractive, metal panel, the HE-45A comes complete with push-to-talk ceramic microphone, crystal for 50.12 Mc, detachable mounting bracket, and all power cables. Only 12x5x8 1/2" D. Shpg. wt., 15 lbs.


HE-45AWX

Net 114.95

114⁹⁵

NO MONEY DOWN

MADE IN U.S.A.



LAFAYETTE 6 METER TRANSCEIVER

SMALL, COMPACT COMPLETE 6 METER STATION—TAKE IT WITH YOU ANYWHERE!

57⁵⁰

NO MONEY DOWN

- Superhet Receiver Tunes Entire Band (50-54 mc)
- Efficient Adjustable Noise Limiter
- 7 Watts Input to 6CX8 Pentode Final
- New Efficient Pi-Network Output with Hi-"Q" Tuned Circuit
- Separate Oscillator—Final Stage
- Accessible Front Panel Socket With Crystal For 50.2 MC Output

Meet the enjoyable challenge of 6 meter operation efficiently and economically with the Lafayette HE-35 6 meter transceiver. This small, compact transceiver features a Transmitter with 7 watts input to a 6CX8 pentode final, high quality plate modulation built-in adjustable TVI filter, and antenna matching network for 30 to 100 ohm antenna. Superheterodyne receiver tunes entire 6 meter band (50-54 mc) and includes variable noise limiter. The transmitter uses a 3rd overtone crystal in easily accessible socket located on front panel; has RF output and modulation indicator. Low-loss SO-239 coaxial antenna output jack. Complete with attractive high output ceramic microphone, crystal for 50.2 Mc, and mounting brackets for mobile mtg. 6 or 12 volt power supply separately available for mobile operation. Built-in power supply operates on 110-120 volts, 60 cycle. 10 1/2 x 5 x 6 3/4" D. Tubes: 2-6U8A/6EA8, 6AL5, 12AX7, 6V6GT, 6CX8.

HE-35AWX Shpg. wt., 11 lbs.

HE-16W 12 Volts MOBILE POWER SUPPLIES. 5 3/8 x 4 3/4 x 2 1/4" D. Shpg. wt., 4 lbs.

HE-18W 6 Volts

HE-36L Additional Crystals—Specify Frequency. Shpg. wt., 4 oz. Delivery 3 wks.

Net 57.50

Net 10.95

Net 10.95

Net 4.95

6 METER PACKAGE SPECIAL!



Lafayette Famous HE-35A 6 Meter Transceiver Plus Popular HE-49 6 Meter Mobile Antenna Plus Extra HE-36 Crystal

LAFAYETTE SPECIAL PACKAGE PRICE

REGULAR CATALOG PRICE 69.40

59⁹⁵

Package Stock No. SP-259WXM NO MONEY DOWN



• Ceramic Temperature-Free Microphone

MADE IN U.S.A.

LAFAYETTE 10 METER TRANSCEIVER MODEL HE-50

- Effective Series Gate Noise Limiter
- With Push-To-Talk Ceramic Microphone
- 12-Watt Transmitter with Pi-Network Output
- Built-in Dual Power Supply for 117 VAC and 12 VDC—Ideal for Mobile or Fixed Operation
- Superhet Receiver Tunes 10 Meter Phone Band from 28 to 30 Mc


109⁵⁰

NO MONEY DOWN

Here is a new transceiver with the deluxe mechanical and electrical features of the HE-45, applied to the 10 meter amateur phone band. Receiver has 1 μ v sensitivity. The i.f. of 1650 Kc results in a 45 db image rejection on 10 meters. Includes automatic series gate noise limiter. Transmitter runs 12 watts input to a 2E26 final, with pi-network coax output to match any antenna. Uses 7 Mc fundamental crystals or external VFO. Sockets for 5 crystals plus VFO input, with corresponding 6-position selector switch, located on front panel. Physical layout is identical to that of the HE-45. Includes big illuminated tuning dial and illuminated panel meter which serves as "S" meter and final plate current meter. Built-in dual power supply for 117 VAC and 12VDC make the HE-50 the ideal solution to the problem of finding a compact, completely self-contained 10 meter rig which can be operated mobile or used at home without modification. The many transmitter and receiver features which are combined in this single package make it a value that is hard to beat, at a price designed for the conservative budget. Tube complement: 1-6BA6 RF amplifier, 1-6U8/6EA8 osc./mixer, 1-6BA6 1st i.f. amp., 1-6U8/6EA8 2nd i.f. amp 1st audio, 1-6CN7 detector/noise limiter, 1-6AQ5 audio output and transmitter modulator, 1-6U8/6EA8 transmitter/oscillator and buffer/multiplier, and 1-2E26 transmitter final amplifier. Housed in a rugged, low-silhouetted case with attractive, metal panel. The HE-50 comes complete with push-to-talk ceramic microphone, crystal for 28.60 Mc, detachable mounting bracket, and all power cables. Only 12x5x8 1/2" D.

HE-50WX Shpg. wt., 15 lbs.

Net 109.50



MADE IN U.S.A.

LAFAYETTE HE-50 10 METER SPECIAL

HE-50 10 Meter Transceiver

PLUS

HE-62 10 Meter VFO

HE-67WXM Combination HE-50 and HE-62

Reg. 129.45
COMBINATION SPECIAL **114⁹⁵**
YOU SAVE 14.50

Net 114.95

NEW! LAFAYETTE 10 METER VFO

- HIGHLY STABLE OSCILLATOR CIRCUIT
- FULLY WIRED — NOT A KIT

A highly stable variable frequency oscillator designed for HE-50 or any 10 meter rig employing a standard 7 MC crystal input. A completely shielded Hi-Q clapp oscillator circuit assures drift-free performance. Uses OA2 VR tube to eliminate possible drift effects from line voltage variation. Supplied with cable to connect to HE-50. Instructions are given for connections to units not equipped with 5-prong VFO Jack. Illuminated dial is calibrated from 28 to 30 megacycles. Precision planetary gear mechanism with single knob control of 180° rotation. Tube complement consists of one 12BA6 oscillator and an OA2 voltage regulator. Size 3 3/4 x 4 3/4 x 4 1/4" D. Shpg. wt., 3 lbs.

HE-62

Net 19.95

Made in U.S.A.



NEW! LAFAYETTE 6 METER VFO for 6 METER TRANSMITTERS AND TRANSCEIVERS

- HIGHLY STABLE OSCILLATOR CIRCUIT
- FULLY WIRED — NOT A KIT

A deluxe 6 meter variable Frequency Oscillator designed for high stability and versatility. Completely shielded, the tuning components are isolated from direct heat of components. A High-Q Clapp oscillator circuit assures drift-free performance. An OA2 VR tube further eliminates any effects due to line voltage variation. Operating in the 4 to 4 1/2 Megacycle range, the output frequency is 8 MC. Ferrite tuned coil output is approximately 10 volts. The HE-61 can be used with any transceiver which has a standard 8 MC crystal. Cable with 5-prong power plug for units equipped with VFO 5-prong power jack input. Instructions supplied for units not equipped with 5-prong VFO jack. Also supplied with cable and standard crystal plug for VFO input. The dial is calibrated from 50-54 megacycles and is illuminated for your tuning convenience. Precision planetary drive mechanism with single knob control of 180° rotation. Tube complement consists of one 12BA6 oscillator and an OA2 Voltage regulator. Furnished complete with cable and instructions. Size: 3 3/4 x 4 3/4 x 4 1/4" D. Shpg. wt., 3 lbs.

HE-61

Net 19.95



Made in U.S.A.

19⁹⁵

Lafayette for the BEST VALUES in Amateur Equipment

h hallicrafter



**FREE! FAMOUS NAME
ELECTRIC WORLD CLOCK
WITH PURCHASE OF
HALLICRAFTERS
S-120**

Only **69⁹⁵** No Money Down

NEW! HALLICRAFTER S-120 RECEIVER

Covers Broadcast Band, 550-1600 KC, plus 3 Short Wave Bands—1600 Kc to 30 Mc. 3 Antennas, Slide Rule Bandspread Dial, New Compact Styling.

This new precision built receiver features electrical bandspread with slide rule bandspread dial and separate bandspread tuning condenser. Front panel head-phone jack which automatically disconnects self-contained speaker may be used to drive remote 8 ohm speaker. Has 3 antennas (ferrite loop for broadcast band; adjustable whip for short wave; wire antenna).

Tube complement: 12BE6 Converter, 12BA6 I-F amplifier, B.F.O., 12AV6 Audio amplifier, AVC detector, 50C5 Audio, plus Selenium Rectifier, 455KC IF. Attractive gray steel cabinet with silver trim. 13 1/2" x 5 1/2" x 8 3/4" D. (U.L. Approved). Operates on 105-125V 50/60 cycles. AC/DC. Shipping weight 12 lbs.

HE-146 M S-120 RCVR plus free Electric Clock 59.95

**NEW! NATIONAL 105
GENERAL COVERAGE RECEIVER**



**FREE! LAFAYETTE
HE-48 SPEAKER WITH PURCHASE
OF NATIONAL NC-105 GENERAL
COVERAGE RECEIVER**

ONLY **119⁹⁵**

FOR BOTH
NC-105 RECEIVER
+ LAFAYETTE
HE-48 SPEAKER.

An efficient fixed tuned peaking type Q multiplier provides continuously variable IF selectivity—from 7 KC for full fidelity music reception to 500 cycles for crowded CW Band conditions. Large edge-type illuminated S-meter operates during AM, SSB and code reception for accurate measurement and logging of signal strength. Separate combination BFO/product detector assures maximum performance during SSB and CW reception. Calibration charts are provided for all popular amateur and foreign broad-

cast bands. Exclusive tuner output permits detector to be fed into hi-fi amplifier for quality reception for tapping SW. Tunes 550K to 30MC in four bands. Available in either a functional steel cabinet or custom oiled walnut enclosure. Dimensions (in steel cabinet) 7 1/2" x 13 1/2" x 8 5/8" D. For 105-125 A.C., 60/60 cycles. Shpg. wt., 27 lbs. National NC-105 General Coverage Receiver plus free Lafayette HE-48 speaker. Net 119.95

**E. F. JOHNSON
"CHALLENGER" TRANSMITTER**



**FREE
"ON THE AIR" SIGN
WITH E. F. JOHNSON
"CHALLENGER" TRANSMITTER**

ONLY **154⁷⁵** NO MONEY DOWN

"Challenger" trans. plus free on the air sign.

A full size transmitter with plenty of reserve. The "Challenger" features 70 watts phone input on 80 through 6 meters—120 watts CW input on 80-10 meter—85 watts CW input on 6 meters. Uses front-panel plug in crystals or external V.F.O. Special "LC" keying circuit provides true CW waveform, suppresses clicks and chirps. Hi-O output circuit handles 40-600 ohm antennas; tunes out large amounts of

reactance. Plate circuit capacitor switching provides the best combination for variable and padding capacity for easy tuning and proper loading. Filtered for effective TVI suppression. Operates on 105-125 volts AC, 50-60 CPS less mike, key and crystal. Size: 13 1/4" x 9 1/2" x 10 1/2" D. Shpg. wt., 28 lbs. "Challenger" trans. plus free on the air sign. SP-261WXM Net 154.75

**POLYCOMM 6-METER
TRANSCEIVER**



- New "Minitoad" VFO
- Nuvistor RF Amp — .2µV Sensitivity
- 10 Watts RF Output

Rugged construction, covers entire 6 meter band. Features "Minitoad" VFO with adjustable differential capacitor which maintains virtually zero drift. .2 microvolt sensitivity @ 6 db S/N using 1-6DS4 & 1-6CW4 Nuvistor RF amps. Receiver is a dual conversion superheterodyne. Frequency range: 49.750 to 54.250MC. Selectivity: —6 db bandwidth 8KC±2KC. Features: 6-1 tuning ratio; AGC; adjustable squelch, series gate noise limiter. 5 watts

max. audio output. Hum and noise better than 40 db down. Freq. response 250-3000 cps. AC power consumption: 90 watts rec., 140 watts trans. DC current: 10A rec., 16A, trans. @ 12.6V. For 117V 60 cycles AC 12V DC. Complete with mounting bracket, microphone. Size: 11Wx5Hx10"D. Shpg. wt., 23 lbs. Polytronics PC-6 6 meter transceiver plus FREE Hy Par Saturn 6-6 meter mobile antenna. HE-299WXM Net 319.50

**FREE —
HY PAR "Saturn 6"
6-Meter Mobile Halo Antenna
(reg. price 16.59)
free with purchase of Polycomm
PC-6, 6-Meter Transceiver.**

ONLY **319⁵⁰**
NO MONEY DOWN

MULTI-ELMAC 6-BAND STATION



ONLY **410⁰⁰**
NO MONEY DOWN


EFFECTIVE THRU
OCTOBER 15, 1962

**THIS FAMOUS STATION WHEN PURCHASED SEPARATELY SELLS FOR
464.00 WHEN BOUGHT AS A LAFAYETTE SPECIAL — SAVE 54.00**

A tremendous saving in a complete amateur station for operating on 80 through 6 meters! Ideal for mobile or fixed stations. Features the AF-68 transmitter with the PMR-8 receiver and the M-1070 power supply. Transmitter features 60 watts input AM and CW to a 6146 final with pi network coaxial output. Receiver features a high degree of sensitivity and

selectivity plus double conversion for 80 — 6 meters PLUS the standard broadcast band. Sensitivity: 0.5 µv. for 10 db quieting. Selectivity: 3 KC at 6 db down, 12 KC at 60 db down. Sizes: PMR-8, 4 1/2" x 9 1/2" x 7"; AF-68, 6 1/2" x 13 1/2" x 7"; M-1070, 6 x 8 x 5". For 6 or 12V DC and 110-120V, 60 cps AC. Shpg. wt., 43 lbs. 9HE-944WXM Net 410.00

**EICO 720K
TRANSMITTER KIT**




Brand new 90 watt band switching rig for 80 through 10 meters. Features a 6146 Final amplifier for 90 watts CW input, up to 65 watts phone with external modulation. 6AQ5 clamper tube protects final in case of loss of excitation. Variable pitch Pi-net output matches 50-100 ohm loads. Oscillator keying permits full break-in operation. Panel meter indicates exact operating currents and helps in tuning up. Its "novice limit" calibration safeguards the novice against exceeding the 75 watt power

limit. Tubes: 6CL6 Colpitts oscillator, 6AQ5 buffer-multiplier, 6146 final amplifier, 6AQ5 clamper, and GZ34 rectifier. Copper plated chassis, ceramic switches, ingenious metal case with complete shielding. 5Hx15Wx 9 1/2" D. Shpg. wt., 27 lbs. With all parts and instructions. EICO 720K Transmitter Kit plus free "Ultra Electro Tool Kit." HE-337WXM Net 79.95

FREE!

**DELUXE ULTRA TOOL KIT
with PURCHASE of
EICO 720 KIT
ONLY
79⁹⁵ NO MONEY DOWN**



NEW! HE-34 SWR AND FORWARD POWER METER

- Reads SWR and Relative Power Output Up To 1 KW
- For Continuous Use in 52 Ohm Lines
- Highly Compact—Only 2 1/2" x 5 1/2" x 2 1/2"
- Switch Selects SWR or Forward Power—No Reversing Necessary



16⁹⁵

A compact SWR and relative power meter which can be permanently inserted into a 52 ohm coaxial line to monitor transmitter and antenna performance. The ideal aid in adjusting beams, trap antennas, matching networks, etc., or for tuning transmitters for maximum output. Designed for the frequency range from 3 to 200 mc, and for powers from 25 watts to a full kilowatt. Above 7 Mc, as little as 10 watts will provide adequate sampling; above 100 Mc as little as 5 watts. The unit is installed by means of a standard coaxial connector on

each side, and becomes part of the 52 ohm line. Insertion loss is negligible. Once installed the unit need never be reversed. A switch on the front panel is set to SWR SET for relative forward power readings up to 1 KW on a scale calibrated from 0 to 10, and for adjustment of the sensitivity control for SWR readings. The switch is set to SWR for measurement of reflected power, on an SWR scale calibrated from 1:1 to 100:1. The HE-34 measures only 2 1/2" x 5 1/2" x 2 1/2", excluding coax connectors. Imported. HE-34 Shpg. wt., 1 1/4 lbs. Net 16.95

24⁵⁰ NEW LAFAYETTE HE-26 HYBRID PHONE PATCH



Enjoy the pleasure of handling phone patch traffic with this deluxe hybrid patch. Hybrid circuit permits use of AM or SSB with voice control by effectively isolating the receiver audio output from the transmitter audio input. Provides an accurate balance between 500 ohm line and station equipment—with negligible insertion loss. Four connections on rear for receiver output (voice coil, 3-4 ohms), transmitter input, Station microphone, and telephone. Easy to operate after a few preliminary adjustments, all from the front panel. Null and balance controls are adjusted with the aid of readings on the edgewise panel VU

meter, for balance and maximum receiver-transmitter isolation. Thus the receiver audio signal, which would ordinarily trip the VOX circuit, is balanced out from the transmitter audio section. The gain control is adjusted for proper transmitter and receiver audio level. VU meter continuously monitors line level. The patch can be switched in and out by means of a front panel switch, so that it may be permanently installed. Compact, sloping cabinet will fit into any station arrangement. Sits on 4 non-slip rubber feet. Size: 3 1/2" x 5 1/2" x 4" D. Imported HE-26 Shpg. wt., 3 lbs. Net 24.50

NEW HE-56 LAFAYETTE 6-METER CONVERTER



- SELF-POWERED
- PRINTED CIRCUIT
- 7-11 MC OUTPUT

ONLY **29⁹⁵**
NO MONEY DOWN

A deluxe 6 meter converter designed to respond to the weakest signals with very low noise. The HE-56 will convert any short-wave receiver that tunes 7-11 Mc. to cover 50-54 Mc. Easy to install between main antenna and receiver's antenna terminals. When the converter's control switch is in the OFF position, signals from the main antenna will be fed around the converter circuit into the receiver thus the receiver will receive both the original frequencies and the 6-meter band. Rugged

printed circuit and heavy gauge steel chassis make this unit as durable as the receiver it's connected to. SPECS: Freq. range—50-54 Mc. Crystal freq.—43 Mc. Sensitivity—better than 1 microvolt for 40 db s/n ratio. Image Rejection—in excess of 40 db. Antenna input impedance—52 ohms. Tubes—6AQ8, 6BL8. For 117VAC, 50-60 cps. Size: 7 1/2" x 3 1/2" x 5 1/2" D. HE-56 Shpg. wt., 6 lbs. Imported Net 29.95

**NEW! CITIZENS BAND
MONOCALL SELECTIVE
CALL SYSTEM**



- No More Headaches from Continuous Monitoring!
- Your System Sets are "Silent" Until You Call Them or They Call You!
- Easy to Attach to Your C-B or Communications Unit!

ONLY **59⁹⁵**
NO MONEY DOWN

A new selective call device for use with citizens Band and Communication Systems that eliminates the need for continuous annoying monitoring. Your set and those in your system are "Silent" until you call them or they call you. Most selective call devices use a single tone burst. With a single tone system the decoder is subject to false triggering because of squeals and voices. Monocall's multiple tone burst and special computer circuitry all but eliminate this undesirable characteristic. Only minutes required to attach Monocall to your existing Citizen Band or Communication unit. Can be field modified by changing just two wires to give any one of six code combinations for additional privacy when desired. Size: 3 1/2" x 2 1/2" x 5 1/4". Shpg. wt., 3 lbs. HE-848 Encoder and Decoder. (Combined Calling and receiving Units) Net 59.95 HE-849 Encoder only. Shpg. wt., 1 1/2 lbs. Net 29.95

LAFAYETTE KITS-

always offer more
for **LESS!**

BUILD YOUR OWN NEW! EXCITING "EXPLOR-AIR" 4 BAND RECEIVER KIT



LAFAYETTE KT-196 2-STATION INTERCOM SYSTEM KIT

Made
in
U.S.A.



- Attractive, Modern Styling
- Complete—One Master and One Remote Station Plus 50 Ft. of Cable
- Perfect as Baby Sitter or Sickroom Watcher
- 2 Complete Stages of Amplification

1475

The perfect 2-station intercom kit beautifully styled and engineered by Lafayette's Kit Divisions. It will grace any room in the home, office, shop, school, etc. Consisting of a Master Station and a Remote station, most useful to communicate with the basement, garage, playroom or nursery. The master unit features a highly sensitive 3-tube circuit with 2 complete stages of audio amplification for maximum talk-power, and sensitive reception. Makes a marvelous "baby-sitter." Remote unit may be left in permanent "Talk" position. Master Station has a 3-way lever switch which provides Momentary Talk, Listen, and a lock-in talk position to free hands for other duties or for extended conversation. Master station front panel also includes a combined on/off switch, volume control. Only the master unit need be plugged into outlet — remote may be placed anywhere. The system may use up to 3 remotes. Famous Lafayette instruction manual simplifies assembly. Size of each unit: 4Hx8Wx4 3/4"D. Attractive metal enclosures. Tubes: 36AM3A, 60FX5, 18FY6. Complete with all parts necessary and 50 feet of 3-wire cable. For 105-125V 50-60 cycles AC or DC.

KT-196 2-Station Intercom Kit. Shpg. wt., 7 lbs. Net 14.75
 LA-196 Factory Wired Net 19.50
 Extra Remote Station Kit—For use with above. Less cable. Net -3.45
 KT-197 Shpg. wt., 2 1/2 lbs. Net 3.95
 LA-197 Factory Wired Remote Net 3.95
 Hook-up wire for above. WRC-113 per ft. Net .02



Tune in the World!

2195
Made
in
U.S.A.

NO MONEY DOWN

- 4 Bands for total coverage: - 550-1600 Kc broadcast band; 1.7-5.0 Mc., 5.0-14 Mc., 14-30 Mc. shortwave bands • Complete band-switching from front panel • Built-in Big 4" PM Loudspeaker

A complete shortwave and standard broadcast set which covers the entire region from 550 kilocycles to 30 megacycles. Four whole bands of fascinating programming unavailable elsewhere. Only a regenerative circuit can offer such amazing performance and yet be so simple to build. Building this fine kit is an absolute pleasure—it's so well designed you can't go wrong. Kit includes all the parts you need, and the detailed step-by-step instruction book with its giant pictorial drawings shows you just how to put them together. One front panel knob does all the bandswitching at the flick of the wrist. All coils are prewound for greater accuracy. The chassis is completely isolated from the circuit, so there is no shock hazard.

This precision radio kit is just full of extra features. Complete 4 band coverage of broadcast stations, international broadcast bands, amateur, maritime, fire and police services, yes, even satellite signals. Big 4" speaker and sensitive circuit with 50C5 output stage, 35W4 rectifier and .12A77 regenerative detector and amplifier stages give you all the volume you want. Phone jack for privacy automatically disconnects speaker. All controls are on the front panel: On-Off Volume, Main Tuning, Band Spread, Bandswitch, Antenna Tuning, and Regeneration. 110 volt 50-60 cycle AC-DC power supply lets you use this fine set anywhere. Size: 10x7x5".
KT-135 EXPLOR-AIR RECEIVER KIT (Less Cabinet) wt., 5 lbs. Net 21.95
ML-150 Leatherette covered Wooden Cabinet for above, 1 lb. Net 2.75



Special Sale

**LAFAYETTE
KT-199**

**2-TRANSISTOR + DIODE
BROADCAST RADIO KIT**
POWERFUL REFLEX CIRCUIT

- No Soldering A Child Could Build It!
- Pre-wired Switch and Control
- 50 Mile Range
- Beautifully Styled Cabinet

was 11.63

695

Complete with Earphone & Battery

Absolutely no soldering or hole punching is necessary. All wiring and components are connected to fahnstock clips mounted on a pre-punched board. It is the ideal kit for beginners interested in transistor circuits. The on-off switch and level control are already prewired—just clip them in. A clear construction manual is included with simple How-To-Do-It instructions so that a child could build it. And that's not all. Lafayette engineers have designed this transistor radio to have a receiving radius of approximately 50 miles! Only one 9 volt battery powers its 2-transistor reflex circuit. Ferrite core loop antenna and a variable gang tuning condenser insure crisp reception on the entire AM broadcast band from 550-1600KC. Will accept any high impedance earphone for private listening. Size: 5 1/2 Lx2 3/8 Hx4 3/4 D. 2-2N165 PNP transistors, 1N48A diode. Complete with instruction manual. Shpg. wt., 1 1/2 lbs.

SP-262M Complete 2 transistor kit—Complete with earphone and battery Only 6.95
 Recommended Earphone
 AR-50 Dynamic earphone 3,000 ohm Net 1.39
 BA-2 9-volt battery Net .21



SUPER-SENSITIVE PHOTOCELL ELECTRONIC RELAY KIT

Made
in
U.S.A.

- WITH CLAIREX CADMIUM SULPHIDE PHOTOCELL • ADJUSTABLE SUPER SENSITIVITY —WORKS WITH JUST A FLASH-LIGHT AT 250 FEET! • NEEDS NO SPECIAL HIGH-INTENSITY LIGHTS • INSTANTANEOUS OR SUSTAINED OPERATION ON THE FLIP OF A SWITCH!

1295

Ideal for sustained operation required for burglar alarms, door buzzers and for instantaneous on-off operation required for counters, packaging, door opening, motor activation plus countless industrial applications. Switch converts unit from instantaneous "on-off" to sustained "on" operation. "RESET" switch opens the external circuit and turns off the alarm. The unit operates on 110 volts AC and incorporates the efficient 5823 cold cathode tube. A simple change in wiring (in instructions), as well as convenient input terminals, enable you to supply the external circuit with any desired voltage. Relay contacts rated at 3 amps permitting up to 300 watts external load on 110 Volts AC. Complete with all parts, photocell, tube, chassis, silkscreened metal cabinet and easy-to-follow illustrated instructions. Size: 3x4x5".
KT-133A Kit, Complete. Shpg. wt., 3 lbs. Net 12.95

ACCESSORIES FOR ABOVE

EL-85 Electric Bell, 110V AC. Shpg. wt., 2 oz. Net 1.49
 EL-86 Electric Buzzer, 110V AC. Shpg. wt., 10 oz. Net 1.29
 F-553 6-Digit Electric Counter. Shpg. wt., 1 1/2 lbs. Net 9.95

LIGHT SOURCE

- COMPLETELY WIRED
- FOCUSING ADJUSTMENT
- INCLUDES RED FILTER

750

Completely wired and assembled light source with AC line cord and plug. Will actuate the relay at 500 feet. Knob on rear moves bulb assembly forward for focusing. Removable red filter makes light beam invisible by day and very difficult to detect at night. Metal case. Size: 4 1/4 x 3 1/2". For 110V 60 cycle AC. Shpg. wt., 4 lbs. PC-43 Net 7.50



NEW! ELECTRONICS EDUCATIONAL KIT



Complete With 116 Page
Instruction Manual —
Virtually A Textbook
& Laboratory Manual

2450


- 194 ILLUSTRATIONS • INCLUDES QUESTIONS & ANSWERS FOR EACH SECTION • CLEARLY WORDED STEP-BY-STEP INSTRUCTIONS • COVERS BOTH AC & DC IN THEIR ENTIRETY • TEACHES, AS YOU BUILD • 12 COMPLETE EXPERIMENTS RESULT IN A FINISHED AC & DC TEST INSTRUMENT • ENABLES REPAIR OF HOUSEHOLD APPLIANCES

The fascinating world of electronics introduced in a simple, easy-to-follow manner through this new Lafayette KT-180 Electronic Educational Kit. Not a toy—this kit is a complete beginners electronics laboratory course featuring an extremely useful AC/DC Multitester.

In the process of constructing this test meter, the fundamental principles of electricity and electronics are introduced in a "learn-by-doing" method. The focus of attention is on the basic sensitive meter for measuring the flow of electrical current. From this simple measurement, the meter is built up to indicate voltage and resistance. The detailed 116 page instruction manual contains 194 illustrations and is written in a simple, easy-to-read, step-by-step manner with questions and answers supplied for each section. Providing a virtual "guided tour" of electrical fundamentals, this kit furnishes a complete course in AC and DC including ohms law, series and parallel connections, making electro-magnets, producing electricity by induction and testing house appliances. The kit is supplied with less batteries.

KT-180 Shpg. wt., 5 lbs. Net 24.50
 BA-155 (Burgess Z type battery, 2 required) Net ea. .095

PHONO AMPLIFIER KITS



1095

Made in U.S.A.

LAFAYETTE KT-92 5-WATT PUSH-PULL AMPLIFIER KIT

- PUSH-PULL AUDIO OUTPUT STAGE • INVERSE FEED-BACK CIRCUIT • SEPARATE VOLUME, BASS & TREBLE CONTROLS • AC OR DC OPERATION

Here in kit form is an AC-DC hi-fi amplifier that presents unusual features despite its amazingly low price. The separate bass and treble controls permit adjustment of both low and high frequency response and balance. Works equally well with both crystal or ceramic cartridges. Has a 4-tube line up—a 12AX7 amplifier and phase inverter, a 35W4 rectifier and a pair of 35C5's in push-pull, having a power-packed low distortion output. The circuit utilizes an inverse feedback loop to reduce the level of hum and distortion. Kit is complete containing all essential parts, tubes and detailed instruction manual showing pictorial and schematic diagrams. Shpg. wt., 4 lbs. Net 10.95

NEW! AC/DC BROADCAST RADIO SEMI- KIT



995

- ALL MAJOR COMPONENTS PRE-MOUNTED
- CONTEMPORARY STYLING
- 5 TUBE SUPERHETERODYNE CIRCUIT
- FUSED POWER LINE

Imagine the joy of building your own full size table model radio. The perfect kit for beginners. Everything but tools is included in the kit to build this fine radio. All the major components are pre-mounted on the chassis by the factory. Two clearly marked cards identify the few resistors and capacitors necessary to complete the set. No special tools are required for alignment either. A simple procedure is outlined in the Lafayette illustrated instruction manual which will enable you to achieve excellent reception across the entire broadcast band (540-1600 KC). Sounds as good as it looks too. Styled in a beautiful contemporary plastic cabinet with a finished back. Vented back provides proper baffling and ventilation for components. 5 tubes (2 dual purpose) plus a high "Q" ferrite rod antenna for better AM reception. Cabinet measures 8 1/2 x 4 1/4 x 4" overall. Muted colors match any color scheme. Tubes: 35W4, 12AV6, 12BE6, 12BE6 and 50C5. For 117 V AC/DC. Shpg. wt., 3 lbs Imported Net 9.95

LAFAYETTE *Easy-to-Build* EDUCATIONAL KITS



LAFAYETTE R/C TRANSMITTER KIT

MADE IN U.S.A.


WITH .005% TOLERANCE CRYSTAL TWICE AS GOOD AS FCC REQUIRES! OVER 1 MILE LINE-OF-SIGHT TRANSMISSION! EXCEPTIONAL STABILITY FOR FOOL-PROOF CONTROL OF MODEL PLANES, BOATS AND CARS.

You'll marvel at the neatness, simplicity and dependability of Lafayette's RC Citizens Band Transmitter. Crystal-controlled with a .005% tolerance crystal for extra frequency stability; exceeds FCC tolerance requirements. Fits comfortably in the palm of your hand, yet is unaffected by hand capacitance or motion. Has new attractive wide scale meter for visually tuning transmitter. Wide, non-critical tuning for optimum foolproof performance. Tuning for proper output and antenna loading easily accessible. Complete with telescoping antenna, meter, tube, crystal, alignment tool, all parts and easy step-by-step instructions. FCC license application forms enclosed. Size 10x4x2 1/2". Shpg. wt., 5 lbs.

KT-127A less batteries Net 17.25
 BA-157 Burgess No. 2 battery Net .13
 BA-1 BATTERY (2 needed) 1.59 ea.

New! 20-IN-1 TRANSISTOR Experimenters Kit

FUN TO BUILD—EDUCATIONAL—and ALL 20 projects result in a useful working instrument!



PROJECTS YOU BUILD


1. TRANSISTOR TESTER
2. VOICE ACTUATED ALARM
3. PHOTO TIMER
4. AUDIO AMPLIFIER
5. CRYSTAL SET
6. SOLAR RADIO
7. RAIN ALARM
8. TIMER
9. ONE TRANSISTOR RECEIVER
10. CODE PRACTICE OSCILLATOR
11. METRONOME
12. TWO TRANSISTOR RECEIVER
13. ELECTRONIC GAME
14. HOME BROADCASTER
15. PHOTO ELECTRIC RELAY
16. BURGLAR ALARM
17. WIRELESS TRANSMITTER
18. REGENERATIVE RECEIVER
19. CITIZENS BAND MONITOR
20. AUDIO OSCILLATOR

This new Educational Kit opens the field of transistor-electronics, with all its fascinating circuits and gadgets, in a simple, easy-to-follow manner. Excellent for beginners as well as advanced experimenters, this kit enables you to build and learn about 20 interesting and useful transistor circuits. By utilizing "bread-board" construction, each project can be simply wired and traced. After building the basic circuit, any of the 20 projects can be built by simply inserting a few preassembled component blocks and interconnecting leads between them. A soldering iron is only required for the basic wiring and not for subsequent projects. All wiring is covered in a step-by-step manner by the instruction manual. Each of the 20 projects is clearly presented with step-by-step instructions, large easy-to-read pictorial wiring diagrams, schematic diagrams, and an explanation of the circuit behavior. There are no AC voltages to produce shock hazard. Amaze your friends with a Voice-Actuated Alarm, Rain Alarm, Home Broadcaster, and other projects. Build useful projects for the home—Metronome, Burglar Alarm, and Timer. Learning Morse Code with the Code Practice Oscillator and receiving Short-Wave Citizens Band Stations. The kit is complete with perforated mounting board, 2 transistors, 1-diode, earphone, light sensitive plate, and all other parts required for construction. The detailed 28 page instruction manual contains a wealth of information about each project. Less batteries and tools. Shpg. wt., 6 lbs.

KT-173 Complete Net 18.95
 BA-155 Z Cell Battery for Kit projects Net .09
 BA-270 22 1/2 Volt Battery for Kit projects Net 1.61

1895

LAFAYETTE 10-IN-1 LABORATORY KITS



MADE IN U.S.A.

WITH THIS KIT YOU CAN BUILD

1550

1. RADIO RECEIVER
2. PHONO-MICROPHONE AMPLIFIER
3. PHONO OSCILLATOR
4. BROADCAST STATION
5. CODE PRACTICE OSCILLATOR
6. SIGNAL TRACER
7. CAPACITY OPERATED RELAY
8. ELECTRONIC TIMER
9. ELECTRONIC SWITCH
10. PHOTOCELL RELAY

Here is a new laboratory tested experimenters kit designed to provide maximum instruction and entertainment and which is ideal for both the beginner and advanced experimenter. Features practical and interesting circuits which enable you to do many novel and interesting things while learning how these circuits function. You can broadcast your voice or play a phonograph through your radio from anywhere in the house, send code through a headphone or radio, or use light or body capacitance to activate electrical circuits. Safe, low voltage is utilized. Kit is complete with perforated mounting board, 3 vacuum tubes, microphone and all parts necessary for construction. A detailed 12 page instruction manual contains simple-to-follow pictorial and schematic diagrams for each project. Less headphone, photoelectric cell and socket, wire and solder.

KT-36A Shpg. wt., 5 lbs. Net 15.50
 PHOTOELECTRIC CELL TUBE TYPE 868. Shpg. wt., 8 oz. 3.75
 CM-70 AMPHENOL 77MIP4 SOCKET FOR ABOVE. Shpg. wt., 1 oz. .13
 ME-33 CANNON AM-15-1 1000 OHM SINGLE HEADPHONE. Shpg. wt., 1 lb. 1.18

LAFAYETTE STEREO PHONO AMPLIFIER KIT



MADE IN U.S.A.

- 4 WATTS STEREO OUTPUT
- ISOLATION TRANSFORMER
- SEPARATE VOLUME CONTROLS
- GANGED TONE CONTROLS
- STEREO-MONAUROUS SWITCH

1895

This is a complete 4-watt hi-fi stereo amplifier having 2 watt output per channel. Features separate volume control for each channel; ganged tone controls; stereo-monaural switch to feed one channel to both speakers and to reverse the channels. Just right for use anywhere a small stereo amplifier is required—ideal for custom mounting in even the tightest locations. Excellent for small apartments. Complete with instructions. For 3 or 8 ohm speakers. Tubes: 2-50C5, 2-12AX7 plus selenium rectifier. For 110-120 volts, 60 cycle AC.

KT-126 Kit, Complete. Shpg. wt., 7 lbs. Net 18.95

LAFAYETTE has MORE switches LOWER prices BETTER quality

HEAVY DUTY 6 AMP DPDT CENTER OFF TOGGLE SWITCH

● Standard Replacement .49

LAFAYETTE SPECIAL .49

6 Amp DPDT Center Off: For P.A., lighting circuits, etc. Rated 6 amps 125 V.A.C. 1 1/2" x 3/4" x 1" behind panel including screw terminals. Bushing 3/8" x 1/2". 3/8" bat handle. Shpg. wt., 3 oz. Imported SW-19 net, ea. .49 In lots of 10, ea. .45

SINGLE POLE SINGLE THROW TOGGLE SWITCH

● Standard Replacement .22

SPST Bat Handle: Rated 3 amps — 125V. Body size 1 1/4" x 3/4" x 1/2" behind panel. Bushing 3/8" diam. 3/8" long. Bat handle 1/2" long. Shpg. wt., 3 oz. Imported SW-21 net, ea. .22 In lots of 10, ea. .19

2 GANG 9 POLE 3 POSITION MINIATURE ROTARY SWITCH

1.19 ea.

Non-shorting type with 12 circuits per gang or section. Rated current capacity is 50 ma at 100 V. A.C. Insulation resistance 100 megohms at 500 V. D.C. Contact resistance without load is 10 milliohms at 6 V. D.C. Perfect for transistor applications. Mounting depth 1" diam. 3/8", 3/8" knurled shaft.

SW-87 net, ea. 1.19 In lots of 10, ea. 1.15 In lots of 100, ea. 1.08

PUSH-TO-TALK SWITCH

● 4-Circuit 2-Contact .79

MODEL SW-102. Designed especially to fit Lafayette Model HP-73 Printed Circuit Board or use for transistorized and miniature applications where a high quality push-button, maintain contact switch is required. Contact resistance is 15 milli-ohms at 50 ma. DC. Will withstand 500 VAC per minute. Insulation resistance is 100 meg-ohm up at 500 VDC. Size (including mounting brackets) 1 1/2" x 3/4" x 3/4". Mounting center at 3/8". Shpg. wt., 2 oz. Net .79 SW-102

HEAVY DUTY 10 AMP OPDT MOTOR SWITCH

● MOLDED PHENOLIC CASE .79

● METAL FACE PLATE

Heavy Duty 10 Amp OPDT: Rated 10 amps at 125 V.A.C. will easily take current surge of motor starting. Freeflow solder type terminals. 1 3/4" x 3/4" x 1". Bushing 3/8" x 1/2". D. 3/8" bat handle. Shpg. wt., 3 oz. SW-25 net, ea. .79 In lots of 10, ea. .75

NEW! AUTOMOTIVE TOGGLE SWITCH

● Paddle Handle—Flick Action .99

Imported Shpg. wt., 3 oz.

Automotive SPST Toggle: Rated 6 Amp 125V or 3 Amps 250 V. Max. Voltage is 1000V AC with .010 ohm contact resistance. Designed for dash board or instrument installation. Measures 1 1/4" long x 1/2" W. mounting shaft 3/8" L. x 3/8" Diam. 1 1/4" Toggle. SW-84 net, ea. .99 In lots of 10, ea. .95

3 GANG 9 POLE 3 POSITION MINIATURE ROTARY SWITCH

1.49 ea.

Designed for subminiature applications in transistor circuits. Total of 12 circuits are provided each gang or section. Rated current capacity is 50 ma at 100 V. A.C. Insulation resistance 100 megohms at 500 V. D.C. Contact resistance without load is 10 milliohms at 6 V. D.C. Non-shorting type switch. Mtg. depth 1 1/2". Diam 3/8", 3/8" knurled shaft.

SW-88 net 1.49 In lots of 10, ea. 1.32 In lots of 100, ea. 1.27

NEW! MAGNETIC PROXIMITY SWITCH

NEW! Use in burglar alarm systems, electric trains, and many more uses. As the magnet approaches the switch, the circuit closes. Hermetically sealed; 15 watts resistive max, up to 1 amp at 250 volts. With leads. SW-105 Shpg. wt., 3 ozs. Net 1.74

DPDT LONG BUSHING SWITCH

● 3/4" Long Bushing .79

● Designed for Wood Panel Mounting.

Imported

3/4" long shaft DPDT: Rated 6 amps at 125V. A.C. Designed for easy wood panel mounting. Measures 1 1/2" x 3/4" x 1 1/4" behind panel. Bushing is 3/8" x 1/2" diam. Bat handle, 1 1/2" long. Shpg. wt., 3 oz. SW-86 net, ea. .79 In lots of 10, net ea. .75

HEAVY DUTY 10 AMP SPDT CENTER OFF TOGGLE SWITCH

Imported .39

Heavy Duty 10 Amp. SPST center off: Rated 10 amps at 125V. Silvered lugs for low loss connections. Body size 1 1/4" x 3/4" x 3/8" depth behind panel. Bushings 3/8" Dia., 3/8" long. Bat handle 1/2" long. SW-27 net, ea. .39 In lots of 10, ea. .35

NEW! MINIATURE 4PDT ROTARY SWITCH

● 3/4" Long x 3/8" Diam. .69

Ideal for transistor application. Precision 1 Gang, 4 Pole, 2 Position rotary switch. Contact resistance is less than 0.01 ohm. Current capacity is 1 ampere at 6V DC. Insulation between any two terminals or between any terminal and shell is not less than 100 megohms at 100V DC. Measures only overall 3/4" diam by 3/4" long including 3/8" shaft. Shpg. wt., 3 oz. Net ea. .69 Lots of 10 Net ea. .65 SW-80

NEW! RUGGED TELEPHONE TYPE 4PDT LEVER SWITCH

CHROME PLATED CAM .69

Telephone Type 4 PDT. Lever switch: 3 position lever action switch of non induction construction. Has 4 sets of SPDT contacts - Has 3 locking positions - Heavy insulated rollers. Panel mount, 1 1/4" mounting centers. Size 2 1/4" long behind panel, 3/4" wide 1 1/4" high. Shpg. wt., 3 oz. Imported SW-20 net, ea. .69 In lots of 10, ea. .65

HEAVY DUTY 6 AMP DPDT SWITCH

.32

A TERRIFIC BUY!

Heavy Duty 6 Amp DPDT: Rated 250V at 3 Amps or 125V at 6 amps. Switch body 1 1/2" x 3/4" x 3/8" behind panel including terminals. Bushings 3/8" Dia., 3/8" long. Bat handle 1/2" long. Shpg. wt., 3 oz. Imported SW-22 net, ea. .32 In lots of 10, ea. .29

SUB MINIATURE PUSH BUTTON SWITCH

● INDUSTRIAL SPECIAL .18

ea. in lots of 10

Momentary contact push button switch. SPST, non-snap action. Rated 115 V.A.C. at 100 ma. Overall dimensions 3/8" x 3/8" L. Bushing 1/4" long. Shpg. wt., 1 oz. Net, ea. 20; in lots of 10, ea. .18 SW-70

ROTARY SWITCHES 4 POLE-3 POSITION

.39

Four pole rotary selector switch, 3 positions per pole. Useful in hi-fi preamps and stereo applications. Spring loaded, positive detent action. Shorting type. Over-all diameter 1 1/4". Depth behind panel, including lugs, 3/4". Bushing 3/8" x 3/8". 1/4" knurled shaft, 1 1/4" long. Shpg. wt., 3 ozs. Net ea. .39 In lots of 10, ea. .35 SW-30

6 POT SLIDE SWITCH

.79

6PDT SLIDE SWITCH: Panel mount. Current capacity 500 ma at 125 VAC. Contact resistance 500 milli-ohms. DC insulation resistance 20 megohms. Measures 1 1/2" x 3/4" x 1 1/4" D. Mounting center 1 1/4". Shpg. wt., 3 oz. Imported SW-99 Net ea. .79 In lots of 10, ea. .75

TRANSCIVER SELECTOR SWITCH

● 3 Position .98

● Spring Return

TRANSMIT — RECEIVE — TRANSMIT SPRING RETURN SWITCH. A 4-pole 3 position switch for use in citizens band switching circuit. Position 1 — Transmit (locks); Position 2 — Receive; Position 3 — Transmit, with spring return, for short periods of transmissions. Shpg. wt., 6 oz. Net .98 HP-65

DPDT "SEE SAW" SWITCH

● Rocker Arm Actuated ● Flush Mounting .62

Flip action, rocker arm type equipment switch. Mounts flush in panel up to 3/8" thick. Requires rectangular mounting hole 1 1/2" x 1 1/4" long. Mtg. centers 1 3/8". Mtg. holes tapped for 4-36 machine screws. Rated 4 amps at 125 V.A.C. Insulation resistance 100 meg ohms or more @ 500 V.A.C. Shpg. wt., 2 ozs. Net ea. .69; lots of 10 ea. .62 SW-111

OUTSTANDING VALUES FOR for Experimenter - Kit Builder, Hobbyist



NEW!

LAFAYETTE AUTOMATIC PHOTO-ELECTRIC 'LUMINATOR



- Automatic Light Switch
- Lights on at sunset—off at sunrise

4.95

New photo-electronic, light sensitive switch turns lights on and off at dusk and dawn. Better than a clock—no setting and re-setting of timer. Variance in "on-off" cycle adds extra protection when away from home. You need never come home to a darkened house. The controlled lamps go on as darkness falls—stay on until sufficient day light returns or until manually turned off. Just plug it in for protection from prowlers—to turn on night lights—illuminate outdoor areas—light up brooders—green houses—displays—show windows—any place you require automatic illumination. Mounts most anywhere on rubber suction cup feet. Unobtrusive—measures only 3 3/4" x 2 1/2" x 1 1/4". Use on 117 volt AC only. Maximum 300 watts lamp load. Instructions included. Shpg. wt., 1 lb. Imported

MS-790

Net 4.95



ULTRA-THIN MINIATURE SPEAKER

- Ideal for Replacement and Miniature Builders — Hobbyists, Experimenters, etc.
- Only 3/8" Thick

1.29

A value-priced miniature speaker ideal as replacement in Japanese portable radios as well as initial speaker for experimenters and hobbyists for miniature building. Voice coil impedance: 8 ohms; minimum response: 350-450 cps; input power: 0.3 watt; frequency range: 50-6,000 cps. Overall 2 1/4" dia. x 3/8" thick. Imported

SK-178 Shpg. wt., 4 oz. Net 1.29

NEW! ULTRA SUB-MINIATURE TRANSISTOR COIL KIT



- Smallest 2 Gang Variable Ever Made!
- Size: 1 1/4" Square, 3/8" Deep
- 3 I.F.'s and OSC: 1" Square, 3/8" High
- Ferrite Loop Antenna

3.45

All in one kit—a complete set of matched micro-miniature coils, ferrite loop antenna, ultra-compact 2 gang variable condenser, tuning dial and schematic diagram for building a subminiature 6 transistor radio. Kit includes: Shielded and impregnated high-Q 455 KC IF transformers and oscillator coil-all slug tuned. Proper impedances are provided for optimum circuit performance. Variable condenser has protective case and rear trimmer adjustment. Flat ferrite loop antenna measures 2 1/4" x 1 1/4" thick. Clearly-printed circuit diagram indicates all parts necessary for a powerful 6 transistor receiver. Tuning dial and knob (1 7/8" dia.) fits securely on V.C. shaft. Shpg. wt. of kit is 1 lb. Imported

MS-828

Net 3.45

NOW! RESISTOR PHOTOCELL



SENSATIONAL LOW PRICE .89

A cadmium sulphide light activated resistor used to actuate door openers, burglar alarms, relays, light controls, production counters, etc. Resistance varies from 75 ohms at approx. 93 foot-candles to over 10 megohms in total darkness. Maximum volts: 110VAC peak 110VDC; maximum dissipation: 2 watt @ 40 C, 1 watt @ 50 C, 0 @ 60 C. Capacity approx 6 mmf. 1 1/2" diam. x 3/8" thick. Shpg. wt., 3 oz.

MS-922

Net .89

SELF GENERATING PHOTOELECTRIC CELLS



BELCW DISTRIBUTOR COST!

- Complete with leads
- No external power needed
- Output in sunlight up to 60 MA

.53

• Up To 750 ua at 100 ft. Candles

Selenium, self-generating photocells convert sunlight or artificial light energy into electrical energy without any auxiliary source of power. Sensitive to a wide spectrum including white, colored or ultra-violet light. All unmounted, complete with leads. Outputs in table below taken at 100 foot candle illumination with 100 ohm load. Higher outputs obtainable with greater light. Shpg. wt., 3 oz. Imported

Stock No.	Out μ a	Size	1-4	5-9	10
MS-771	100	1 1/4" x 1 1/4"	.59	.56	.53
MS-772	250	1 1/4" x 1 1/4"	.79	.75	.71
MS-773	350	1 1/4" x 1 1/4"	.89	.85	.80
MS-774	750	1 1/4" x 1 1/4"	3.18	3.03	2.89

AS LOW AS .79

A FABULOUS BUY! GENUINE IBC and ALLEN-BRADLEY Resistor Kit



100 INSULATED RESISTORS WITH PLASTIC HINGED BOX!

4.50

10% TOLERANCE 1/2 WATT RMA Color Coded

Quant.	Ohms	Quant.	Ohms
3	100	10	.1 meg
3	470	4	.15 meg
4	1,000	4	.27 meg
3	2,200	10	.47 meg
4	4,700	10	1 meg
5	10,000	4	2.2 meg
4	22,000		Other
4	27,000	20	popular values
4	33,000		
4	47,000	100	TOTAL

Lafayette leads the field with a genuine Allen Bradley and IRC 1/2 watt, 10% tolerance, molded resistor kit with a Transparent Plastic Utility Box (built in partitions) size: 8 1/4" x 4 1/4" x 1 1/2". Meet JAN-R-11 specifications. Stock No. K1-23—Total 100 molded resistors with Transparent Plastic Case Net 4.50

NEW! MICRO-PERFORATED BOARDS



- Ideal For Transistor And Subminiature Circuitry
- Copper-Clad For Printed Circuits
- Unclad Type For Wired Circuits



These sturdy, perforated boards are the ideal base for builders, experimenters, and labs to mount miniaturized components. Two types available: either high grade bakelite for wired circuits, or one side copper-clad for

"printed" circuitry. Holes are 1/16" diameter with 3/16" between hole centers. All boards are 1/16" thick. For contacts, the MS-263 flea clips listed on this page are ideal. Avg. shpg. wt., 6 oz.

COPPER CLAD BOARDS

Stock No.	Size	Net Each	Lots of 100	Lots of 250
MS-847	2 1/2" x 3 3/4"	.35	.30	.24
MS-848	3 1/2" x 6 3/4"	.55	.50	.45
MS-849	7 1/4" x 6 3/4"	1.15	.96	.87
MS-850	10 1/2" x 7 1/4"	1.90	1.58	1.42

UNCLAD BOARD

Stock No.	Size	Net Each	Lots of 100	Lots of 250
MS-304	2 1/2" x 3 3/4"	.25	.20	.18
MS-305	3 1/2" x 6 3/4"	.45	.40	.35
MS-306	7 1/4" x 6 3/4"	.75	.65	.60
MS-846	10 1/2" x 7 1/4"	1.20	1.08	.97

COPPER CLAD LAMINATE AT LAFAYETTE'S LOW PRICES!

Finest quality XXXP bakelite base, copper clad boards for printed circuit work. Av. shpg. wt., 2 ozs.

NO.	DESCRIPTION	NET
MS-510	XXXX Copper Lam.—1 side—9"x12"	1.50
MS-511	XXXX Copper Lam.—1 side—6"x4 1/2"	.45
MS-512	XXXX Copper Lam.—1 side—3"x4 1/2"	.30
MS-513	XXXX Copper Lam.—1 side—2"x4 1/2"	.25
MS-514	XXXX Copper Lam.—1 side—3"x2 1/2"	.24
MS-515	XXXX Copper Lam.—2 sides—9"x12"	1.95
MS-516	XXXX Copper Lam.—2 sides—6"x4 1/2"	.60
MS-517	XXXX Copper Lam.—2 sides—3"x4 1/2"	.40
MS-518	XXXX Copper Lam.—2 sides—2"x4 1/2"	.30
MS-519	XXXX Copper Lam.—2 sides—3"x2 1/2"	.27

FLEA CLIPS FOR TRANSISTOR AND SUBMINIATURE CONTACTS

"Flea" clips are specially designed for subminiature work. Fit perfectly in holes in perforated copper-clad and unclad boards listed above. Made of beryllium copper, silver plated finish. Simply insert wire thru hole for positive grip contact.

MS-263	Package of 12	Net .25
MS-851 <th>Package of 1000</th> <th>Net 15.75</th>	Package of 1000	Net 15.75
MS-852 <th>Package of 5000</th> <th>Net 76.15</th>	Package of 5000	Net 76.15
MS-853 <th>Package of 10,000</th> <th>Net 149.30</th>	Package of 10,000	Net 149.30

POWERMASTER TYPE CDS-10 CADMIUM SULPHIDE PHOTOCELL



2.50

A miniature crystal photocell that is ideal for actuating, counting, measuring photo-electric control. Acts as a resistor that varies with the intensity of light from over 1 megohm in total darkness to under 1500 ohms at 100 foot candles. Rapid response fast enough to operate relays in 1/10 second. Minimum current output 66 ma at 50 ft. candles at 90 Volts. Output varies with illumination intensity and applied voltage to as low as .08 ma at 1 ft. candle at 6 volts. Power dissipation 1/2 watt continuous, 2 watts for 5 seconds. Usable response to entire visible spectrum with peak sensitivity to blue-green light and good red response. Response to infra-red is low. Size 1 1/4" x 1 1/4" x 1/4".

MS-739

Net 2.50

CADMIUM SULPHIDE PHOTOCELL



1.59

- For Sensitive Relay Actuation
- For Photo Electric Control

A neatly constructed crystal photocell that has countless applications in counting, relay actuation, etc. Resistance varies with light from 1 megohm in total darkness to approx. 1500 ohms at 100 foot candles. Responds to entire visible spectrum and has 1/10 sec. response for relay operation. Minimum current output 60 ma at 50 ft. candles at 90 volts. Power dissipation 2 watts for 5 seconds, 1/2 watt continuous. Output as low as .08ma at 1 ft. candle at 6 volts, varying with illumination intensity and applied voltage. Neatly capsulated for easy mounting with leads for electrical connection. 1 1/4" x 1 1/4" overall Imported

MS-827

Net 1.59

SELENIUM PHOTOCELL

- Excellent for
- Burglar Alarms
- Door Openers
- Counters

8.75



OPERATES RELAYS DIRECTLY

Barrier layer, self-generating type; light striking upon cell generates current sufficient to operate relays directly without the use of auxiliary power. Lifetime of cell is unlimited 600 microamperes output at 100 foot candles. 2 inches in diameter. Mounted in a handsome plastic case. Imported

MS-826 Photocell, Wt., 8 oz.

Net 8.75

CM-70 Socket for MS-826

Net .13

LAFAYETTE SUPER-VALUE SUN BATTERY



1.95

- Excellent for Experimenter, Kit Builder, etc.

Sensational buy enables Lafayette to offer this amazing selenium photocell at a fraction of the price of similar photoelectric cells! Surpasses by far, specifications of cells of equivalent size! Specifications: 0.9 ma Current Output at 100 ft. candles with 100 ohm load; 0.27 ma Current Output at 100 ft. candles with 1000 ohm load. 1 1/4" diameter. With colored pigtail leads. Imported

MS-891

Net 1.95

NEW! SELENIUM PHOTOCELL FOR HEAVY DUTY OPERATION

2.45

- 3/4" Light Area

An efficient selenium photocell utilizing an extremely sensitive film element with 3/4" light area. Ideal for relay operation. Use door openers, counters, etc. Rated at 200V; 20 ma; 0.2W power dissipation at 20°C. Sensitivity is 610 - 50. Resistance Value Characteristics — 0 Ft. Candles: 1M ohm up; 0.929 Ft. Candles: 33K ohms; 9.29 Ft. Candles: 8K ohms; Size 1 1/4" Diam. x 3/4" depth. Imported

MS-886

Net 2.45

NEW! LAFAYETTE SELENIUM PHOTOCELL

1.95

A quality selenium photocell, perfect for transistor and printed circuit use. Employs sensitive film element with 3/8" light area. Rated at 200V; 10ma; 0.1W. power dissipation @ 20°C. Sensitivity is 610 - 50. Resistance Value Characteristics — 0 Ft. Candles: 2M ohms up; 0.929 Ft. Candles: 100K ohms; 9.29 Ft. Candles: 25K ohms; Size 3/8" Diam x 3/8" Depth. Imported

MS-885

Net 1.95

NEW! LAFAYETTE MINIATURE SILICON RECTIFIER

.49

• ONLY 3/8" x 1/2" W

Premium quality and small size make this precision rectifier ideal for prototype and miniature applications. Measures 3/8" D x 1/2" W plus 1/2" mounting lip. Rated AC input voltage 100V. DC output current 20ma. Intermittent 40ma. Maximum Input Capacitance 80MF. Imported


MS-887

Net .49

3 TRANSISTOR SUBMINIATURE AM BROADCAST TUNER USED ONLY IN THE MOST EXPENSIVE RADIOS!

- 4 TRANSFORMERS: 3 IF plus 1 Oscillator Transformers for Exceptional Superhet Sensitivity and Selectivity
- 540KC TO 1600KC
- FEATURES COMPLETELY WIRED PRINTED CIRCUIT BOARD

AN OUTSTANDING AM BROADCAST RADIO WHEN CONNECTED TO ANY TRANSISTOR AUDIO AMPLIFIER—A SNAP!



A deluxe 3 transistor subminiature AM broadcast tuner that features 3 dependable transistors, 3 IF plus 1 oscillator transformer, and ferrite antenna in a super efficient, completely wired superheterodyne circuit on a sturdy printed-circuit board.

Now you can build your own highly efficient broadcast receiver by simply adding this exceptional tuner to any of the transistor audio amplifiers listed below or elsewhere. The long tuner leads for connecting to

external amplifier and/or to a separate 9 volt battery, makes this easy as pie. Also features a large clearly visible calibrated tuning dial. The printed circuit board layout permits either vertical or horizontal mounting. Supplied complete with mounting brackets and detailed instructions. Size: 4x1 1/4x2 1/4" with brackets. Shpg. wt., 8 oz.

PK-633

Net 7.95

LOWER PRICES - BIGGER SAVINGS

FOR EXPERIMENTER KIT BUILDER, HOBBYIST

QUALITY SEMICONDUCTORS AT ECONOMY 'PACKAGE' PRICES

10 GERMANIUM DIODES
Pkg of 10 germanium diodes that replace 1N34, 1N34A, 1N46, 1N48, 1N51, 1N60, 1N64, 1N64A, 1N87, 1N105, 1N109, 1N147, 1N267, 1N268, 1N295, etc. Shpg. wt., 6 oz.
SP-234

10 SILICON DIODES
SP-235
Package of 10 silicon diodes. Replaces 1N34, 1N34A, 1N46, 1N48, 1N51, 1N60, 1N64, 1N87, 1N295, etc. Shpg. wt., 4 oz.

4 PNP GERMANIUM TRANSISTORS
SP-236
Package of 4 PNP General Purpose Type Transistors similar in performance to 2N107, 2N218, 2N1265, CK722, GT222, TR722, 2N1191, etc. Shpg. wt., 6 ozs.

.89
per pkg.
Any 4 Asst. Pkgs.
3.09

2 PNP TRANSISTORS
SP-237
Mixer/Oscillator Converter - Replaces 2N112, 2N114, 2N135, 2N136, 2N137, 2N140, 2N219, 2N411, 2N412, 2N414B, 2N415, CK760, CK766, 2S52, etc. Shpg. wt., 4 oz.

2 PNP GERMANIUM TRANSISTORS IF AMPLIFIER
SP-238
Pkg of 2 PNP germanium IF amplifier transistors that replace: 2N111, 2N111A, 2N112A, 2N139, 2N218, 2N409, 2N410, 2N413, 2N413A, 2N414, 2N414A, 2N416, GT760, 2S53, etc. Shpg. wt., 4 oz.

2 PNP GERMANIUM TRANSISTORS AF AMPLIFIERS (Up to 12 Volts)
SP-239
Pkg of 2 PNP Germanium AF amplifier transistors that replace: 2N133A, 2N138A, 2N138B, 2N151, 2N186A, 2N187A, 2N215, 2N217, 2N319, 2N320, 2N359, 2N360, 363, 2N407, 2N408, 2N1008, A, B, CT81R, GT109, 2S56, 2S838, etc. Shpg. wt., 4 oz.

2 GOLD PLATED SILICON RECTIFIERS 500 MIL - 400 PIV
SP-240
Pkg. of 2 miniature size exceptional 24 karat gold plated silicon rectifiers rated at 500 milliamps, 400 PIV. Shpg. wt., 4 oz.

2-10 WATT POWER TRANSISTORS
SP-243
Package of 2 PNP 10 Watt germanium power transistors in popular TO-3 case. Similar to 2N155, 2N176, 2N235, 2N351, 2N242, 2N257, 2N268, 2N301A, 2N255, 2N554, 2N555, etc. Shpg. wt., 8 oz.

STUD MOUNT SILICON RECTIFIER 2 AMPERE 400 PIV
SP-242
Outstanding Buy! 2 amp. 400 Peak Inverse Volts Silicon Rectifier, stud mounting. $\frac{3}{4}$ " long less lug. $\frac{1}{8}$ " hex nut. Shpg. wt., 6 oz.

2 TOP HAT SILICON RECTIFIERS 750 MIL - 400 PIV
SP-241
Pkg. of 2 top hat type silicon rectifiers rated at 750 milliamps, 400 PIV. Shpg. wt., 6 oz.

40 WATT HIGH POWER TRANSISTOR
SP-244
Amazing value is this 40-Watt high power PNP germanium transistor! Excellent for experimenter, hobbyist and kit builder for power supplies, auto replacement, audio output, etc. Similar to 2N173, CTP1504, SFT266, etc. Bolt mounted. Shpg. wt., 8 oz.

1 TOP HAT SILICON RECTIFIER 750 MIL 750 PIV
SP-275
Package of 1 top-hat axial lead silicon rectifier rated 750 milliamps, 750 Peak Inverse Volts. Shpg. wt., 4 oz.

4 TOP HAT SILICON RECTIFIERS 750 MIL 100 PIV
SP-276
Package of 4 top-hat axial lead silicon rectifiers rated 750 milliamps, 100 Peak Inverse Volts. Shpg. wt., 6 oz.

TRANSISTOR - DIODE PACKAGE SPECIAL
.79 Pkg.
3 Pkgs. (can assort.) 2.09

5 GENERAL PURPOSE DIODES
SP-218
Package of 5 germanium glass diodes similar to 1N34A, 1N60, 1N64, 1N87A, etc.

4 PNP TRANSISTORS
SP-220
Package of 4 PNP Audio transistors similar to 2N107, Beta 15 minimum.

2 NPN TRANSISTORS
SP-219
Package of 2 NPN germanium transistors similar to 2N170 for Audio & RF Beta 70 minimum.

GENERAL PURPOSE DIODES
.19
EXCELLENT DETECTOR FOR TRANSISTOR AND VACUUM TUBE RADIO RECEIVERS
EQUIVALENT TO: 100 for 1N34, 1N34A, 1N38A, 1N48, 1N56, 1N69, 16.50
SP-148 General Purpose Diode Net .19 each; 10 for 1.75

PNP AUDIO TRANSISTOR
AS LOW AS **.31**
LAFAYETTE SP-146 PNP TRANSISTOR TERMINAL LEAD IDENTIFICATION
COLLECTOR - EMITTER
BASE
JETEC #30 WELDED CASE
General audio type PNP transistor for experimenters and hobbyists, for code practice oscillators and similar small signal devices. In new JETC 30 welded case. Net, singly, each .39
SP-146 10 for 3.69; 50 for 16.95; 100 for 31.00

LAFAYETTE SPECIAL SILICON POWER RECTIFIERS
Top hat lead type silicon rectifiers excellent for TV Radio and power supplies as half-wave, full wave rectifiers and voltage doublers.
Type A: 750 Ma, 400 PIV @ 25°C, 500 Ma, 400 PIV @ 90°C. SP-196 Shpg. wt., 4 oz. Net .57 10 for 5.13; 100 for 47.00
Type B: 750 Ma, 200 PIV @ 25°C, 500 Ma, 200 PIV @ 90°C. SP-197 Shpg. wt., 4 oz. Net .47 10 for 4.25; 100 for 38.50

NEW! PHOTO-MULTIPLIER POWER TRANSISTOR

A COMPLETE PHOTOELECTRIC SYSTEM IN ONE UNIT
• PHOTO ELECTRIC CELL
• POWER TRANSISTOR AMPLIFIER
• ELECTRONIC RELAY
Complete with Instructions, Data and Diagrams for photo control systems, photo-electronic amplifiers, Relays, Alarms, etc.
SP-256 Ea. Net 1.79 3 for 4.77

750 MIL 400 PIV EPOXY SILICON RECTIFIER
SP-266 Net, ea. .39; 10 for 3.45; 100 for 29.95

HIGH POWER STUO-MOUNT SILICON RECTIFIERS
10 AMPERE 200 PIV SILICON RECTIFIER
1 1/2" long overall, 1 1/4" hex. Shpg. wt., 6 oz.
SP-267 Net, ea. 1.09; 10 for 9.60
10 AMPERE 400 PIV SILICON RECTIFIER
1 1/2" long overall, 1 1/4" hex. Shpg. wt., 6 oz.
SP-268 Net, ea. 1.98; 10 for 17.50
20 AMPERE 400 PIV SILICON RECTIFIER
1 1/2" long overall, 1 1/4" hex. Shpg. wt. 8 oz.
SP-269 Net, ea. 2.98; 10 for 26.00
50 AMPERE 50 PIV SILICON RECTIFIER
1 1/4" hex. Shpg. wt., 10 oz.
SP-270 Net, ea. 3.50; 10 for 30.00

30 MC HIGH GAIN TRANSISTOR
SP-271
High Quality PNP RF transistor—Excellent for 27MC Citizens Band Walkie Talkie Transceivers, etc. 30 to 35 MC. Average Beta -25. Shpg. wt., 6 oz.
Net, ea. .69; Lots of 10 ea Net .62

POPULAR POWER TRANSISTORS
TESTED AND GUARANTEED TO MEET SPECIFICATIONS
MEDIUM POWER TRANSISTORS
Beta = 30; BV_{CE} = 36 Volts. Shpg. wt., 12 oz. Similar to: 2N155, 2N176, 2N235, 2N242, 2N255, 2N256, 2N301, 2N307, 2N554, AR-5, CTP-1104, TS-176, etc.
SP-147 Medium Power Transistor Net ea. .65 In Lots of 100, Each Net .55
HIGH POWER TRANSISTORS
Beta=50; BV_{CE}=36 Volts. Min. Shpg. wt., 12 oz. Similar to: 2N157A, 2N176B, 2N235A, B, 2N257, 2N285A, 2N301A, 2N352, 2N359, etc.
SP-277 High Power Transistor In lots of 100, Each Net ea. .69 Net .59

RECTIFIER MOUNTING KITS
Consist of 2 Mica Washers, 1 plated nut, 1 Teflon Washer, 1 Plated Washer, 1 Connector Lug. Shpg. wt., 4 oz.
FOR 1/4" HEX BASE Net, ea. .17; 10 for 1.59
FOR 1/2" HEX BASE Net, ea. .27; 10 for 2.49
FOR 1 1/4" HEX BASE Net, ea. .35; 10 for 3.15

NEW! "MITY-AMP" POWERFUL 2-WATT AUDIO AMPLIFIER MODULE

2x3 1/2 x 1 1/4"
• For Monaural, Stereo, Intercom, P.A., Signal Tracer, etc.
• Full 2 Watt Power
• Ruggedly Constructed & Completely Encapsulated
8.95
With Applications Booklet and Schematics.
Frequency Response: 20 cycles to 15KC ± 2 db at 1 watt. Input Impedance: 45 ohms to 50K ohms; Output Impedance: 3.2 ohms to 45 ohms; Power Requirements: 6 to 12 volts at 300 to 700ma. Overall 2x3 1/2 x 1 1/4". Shpg. wt., 10 oz. PK-638 Net 8.95

NEW! 4 TRANSISTOR SUBMINIATURE PUSH-PULL AUDIO AMPLIFIER

OUTPUT 100 MW
• SIZE: 3" x 1 1/4" x 1 1/4"
4.95
• TERRIFIC FOR THE EXPERIMENTER, HOBBYIST AND KIT BUILDER!
• COMPLETELY WIRED, NOT A KIT!
• PRINTED CIRCUIT BOARD
• COMPLETE WITH TRANSISTORS
A tiny, transistorized push-pull audio amplifier with a multitude of applications. Only 3" x 1 1/4" x 1 1/4", it can be mounted inside other equipment to serve as a subminiature phono amplifier, tape recorder, amplifier, etc. Can be the complement of a homebuilt project which needs only an audio amplifier to make it complete and self-contained. Two stages of audio are followed by a push-pull output stage designed to deliver 100 mw to an 8-11 ohm impedance. Low impedance input, with a sensitivity of 0.9 mv. Input transformer for matching high impedances to the amplifier available as an accessory (see below). Includes leads for input, speaker, and volume control/on-off switch. Battery clips and leads supplied for 9 volt miniature battery (one required). Shpg. wt., 5 oz. Imported PK-543 Net 4.95
ACCESSORIES FOR ABOVE
BA-2 9 volt battery. Shpg. wt., 2 oz. Net .39
VC-31 50K ohm volume control w/switch. Shpg. wt., 2 oz. Net .69
SK-193 8 ohm voice coil speaker. 3" Shpg. wt., 10 oz. Net 1.49
SK-189 8 ohm voice coil speaker. 2" Shpg. wt., 8 oz. Net 1.49
SK-191 8 ohm voice coil speaker. 2 1/2" Shpg. wt., 8 oz. Net 1.49
TR-120 Input transformer for matching high impedance (mike, etc.) to amplifier. Net .89

5 TRANSISTOR PUSH-PULL AUDIO AMPLIFIER

6.95
• SIZE: 3 1/4" x 1 1/4" x 1 1/4"
• 360 MW OUTPUT
• COMPLETELY WIRED
• DIRECT WIRING
A more powerful and more sensitive version of the PK-543, this amplifier employs 3 stages of audio driving a push-pull output stage. Power output is 360 mw, designed for speakers with a voice coil impedance of 8-11 ohms. Low impedance input has sensitivity of 300 microvolts. Input transformer for matching high impedance to the amplifier input available as an accessory (see below). Comes with leads for low impedance input, speaker, volume control/on-off switch. Battery clips and leads supplied for 9 volt miniature battery (one required). Shpg. wt., 5 oz. Imported PK-544 Net 6.95
ACCESSORIES FOR ABOVE
BA-2 9 volt battery. Shpg. wt., 2 oz. Net .39
VC-28 10,000 ohm volume control w/switch. Shpg. wt., 2 oz. Net .69
SK-193 8 ohm speaker. 3" Shpg. wt., 10 oz. Net 1.49
SK-189 8 ohm speaker. 2" Shpg. wt., 8 oz. Net 1.49
SK-191 8 ohm speaker. 2 1/2" Shpg. wt., 8 oz. Net 1.49
TR-120 Input transformer for matching high impedance (mike, etc.) to amplifier. Net .89

3 TRANSISTOR SUBMINIATURE AUDIO AMPLIFIER

• SIZE: 2 1/4" x 1 1/4" x 3/4"
3.75
• FOR THE EXPERIMENTER, HOBBYIST, AND KIT BUILDER!
• PRINTED CIRCUIT
• COMPLETE WITH TRANSISTORS
Here is an amazing little audio amplifier with a multitude of challenging applications; i.e., subminiature phono amplifier, tape recorder amplifier, hand-held public address amplifier, telephone pick-up amplifier, etc. Output sufficient for average listening. Has leads for any one of the following inputs: Tape recorder record/playback heads, radio-tuner, crystal or ceramic phono cartridge, and crystal or ceramic microphone. Has lead terminations for ON-OFF switch, Volume Control, 4 to 10 ohm speaker, and leads terminating in clips for a 9 volt miniature battery. Imported Size 2 1/4" x 1 1/4" x 3/4". Can be readily mounted on chassis. Shpg. wt., 8 oz. PK-522 Net 3.75
BA-2 9 Volt Battery Net .39
VC-31 50K ohm Volume Control with SPST Switch and Knob; Shpg. wt., 2 oz. Net .69
SK-193 8 ohm speaker. 3" Shpg. wt., 10 oz. Net 1.49
MS-108 Miniature Crystal Microphone 1 1/4" Diam. x 1/4" Deep. Shpg. wt., 6 oz. Net 1.49
SK-66 Miniature Speaker 2 1/2" Diam. 10 ohms Voice Coil Impedance. Shpg. wt., 8 oz. Net 1.49

SAVE! CHECK EACH SENSATIONAL VALUE!

LAFAYETTE BATTERIES AT TREMENDOUS SAVINGS



These popular batteries are for Portable and Transistor radios, R/C equipment, experimenters, labs, and hobbyists, etc.

FRESH STOCK — BRAND NEW GUARANTEED

Here are six of the most popular types used and at RIDICULOUSLY LOW PRICES

Stock No.	Voltage	Singly	Lots 10 Each	RCA	REPLACEMENTS FOR Burgess Eveready	Others
BA-1	67½	1.49	1.39	VS215 VS216 VS218	P45 P45M	BL-M145
BA-2	9	.21	.20	VS312 VS323	2U6 216	BL-006F
BA-3	9	.34	.29	VS300A VS314	P6 P6M	BL-M106
BA-5	67½	1.29	1.19	VS318	UX45	BL-045
BA-6	67½	1.45	1.35	VS016	XX45	BL-145
BA-7	9	.53	.45	VS309A	YL-6 E-177	TR-177

LAFAYETTE PHOTOFLASH, BC AND HEARING AID BATTERIES

Stock No.	V.	Singly Net Ea.	Lots 10 Ea.	Fig.	Replacements for Burgess Eveready RCA	Shpg. Wt.
BA-11	15	.49	.44	A	Y10 504	3 oz.
BA-14	22½	.59	.53	A	Y15 505	3 oz.
BA-12	22½	.59	.53	B	U15 412	VS084 3 oz.
BA-16	45	1.98	1.83	C	M30 482	VS013 2 lb.
BA-15	90	2.36	2.12	D	N60 490	VS090 1 lb.
BA-13	240	4.50	—	E	U160 491	— 1 lb.

9 VOLT TRANSISTOR RADIO BATTERY

Priced Lower than ever!

.20 ea. in lots of 10

Guaranteed first quality—long life—most popular transistor radio battery replacement for RCA VS323, Burgess 2U6, Eveready 216, Zenith 2216, Ray-O-VAC 1604, NEDA 1604, and others such as BL-006F. Shpg. wt., 2 oz. Imported.

BA-2 Net ea. .21
Net ea., Lots 10 .20



"B" BATTERY ELIMINATOR and CHARGER

245

Replaces Eveready 416, Burgess UX-45, and RCA VS 318 67½V B batteries used in Radio Control units and many portables. Just plug in the AC cord and you can save your battery for outdoor use. Also recharges your battery. 110 volts. 3½x1½". Shpg. wt., 7 oz.
F-550 Net 2.45

LAFAYETTE 9-VOLT TRANSISTOR RADIO BATTERY CHARGER AND ELIMINATOR



- Charge Battery, Operate Set On AC, or Both
- Isolated Transformer Shock-Proof

290

Just Plug into any 117-volt AC receptacle and recharge your old 9-volt battery for many hours of extra use; or operate your set indoors without using the battery at all; or you can both charge battery and operate set at the same time. Has 4-position switch for above functions plus off position and pilot light. It is well filtered insuring low hum and excellent regulation to minimize power losses and to extend life of your set. Transformer is isolated to eliminate shock hazard. Complete with ivory plastic case, AC cord and assort. of snaps to fit all 9-volt batteries. Size: 4Wx1½Hx2½D.
F-790 Shpg. wt., 1 lb. Net 2.90

TRANSISTORIZED CODE PRACTICE OSCILLATOR



- MINIATURE-PORTABLE
- SELF CONTAINED BATTERY POWER SUPPLY
- PRODUCES CLEAR, CRISP, CW NOTE

Here is an ideal, inexpensive code practice oscillator for the amateur radio enthusiast. Long 38 inch wire from oscillator to earpiece, allows two persons to practice without interference. The unit is completely portable, and weighs only 6 oz. Tone produced is clear and crisp, similar to that received during F.C.C. licensing examinations. Low voltage transistorized circuit utilizes 1.5 volt penlight type battery which completely eliminates any possible shock hazard. Earpiece is crystal type, and housed in sanitary plastic. Shpg. wt., 5 oz.
F-429 Oscillator only Net 2.29

229

CODE PRACTICE OSCILLATOR WITH KEY
Above oscillator plus adjustable telegraph key (MS-319). Key has spade lug connectors, making it possible to disconnect the key from the oscillator and use it separately if desired. Shpg. wt., 9 oz.
F-479 MS-319 Key and Oscillator Net 2.95

NEW! "STORAGE CELL" for TRANSISTOR RADIOS!

ONE CHARGEABLE BATTERY OUTLASTS 100 CONVENTIONAL BATTERIES

- Replaces 2U6, 216, BL-006P and BA-2
- Fluid Storage Type—Can't Leak Out
- Plays About 15 Hours on One Charging
- Battery Recharges Overnight
- Battery Can Be Used Over and Over Again
- Complete—Battery Plus Charger

The next best thing to a battery that will last a lifetime—this battery can be used for 1100 to 1500 hours of playing time, AND MORE, its long life is based on 2 new features: 1. A fine storage battery that cannot have fluid leakage; 2. Recharges Overnight—just plug the battery into the charger, the charger into your electrical outlet. Let it charge for 10-12 hours... it cannot burn out on recharge. After charging, the battery is good for about 15 hours of playing time. When the battery runs down, just charge it up and it's ready to play. Will outlast more than 100 conventional batteries. 9V Battery complete with charger. Battery 1½x1½". F-619 Battery and Charger. Shpg. wt., 6 oz.
BA-8 Battery Replacement for above Net 1.48



269

CODE PRACTICE SET LAFAYETTE SPECIAL



179

Key has adjustable spring tension, and contact clearance. High frequency buzzer has frequency and tension adjustment with lock nuts. Provision for insertion of head set. For individual, group or remote listening. Uses Burgess #2 1½ Volt battery. Overall length 8½". Shpg. wt., 2 lbs. (less battery).
MS-438—Code practice set Net 1.79
BA-157—Burgess #2 Net .13
MS-369—Stethoscope Headset Net 1.39



Reg. 1.48
NOW **.95**

SAVE OVER 35%! CODE PRACTICE SET

Set consists of key and buzzer. Key of chrome and nickel plated metal parts, molded phenolic base. Adjustable spring tension and contact clearance. 2 mounting holes. Buzzer of molded phenolic housing, has screw adjustment for changing tone. Works with 1½ volt battery. Shpg. wt., 18 oz.
SP-278M Net .95

LAFAYETTE SPECIAL CODE COURSE



10 LESSONS ON A 12" LP RECORD

350

Learn Morse Code the modern practical way. Supplied with 10 lessons and a non-breakable high quality 33½ rpm long playing record, recorded with code sound to provide further aid. Perfect for home studying. Speed progresses steadily from 2 to 15 wpm. Complete with sturdy record album and instruction manual. Shpg. wt., 1½ lbs.

PR-13 Lafayette Code Course Net 3.50

ECONOMY ALL-PURPOSE DYNAMIC EARPHONE

- For Transistor and Subminiature Receivers
- For Silent Radio and TV Listening

A sensitive all-purpose earphone designed with both your listening pleasure and pocketbook in mind. Extensive range and excellent tone combine, to provide excellent reproduction. Lightweight, equipped with a practically invisible ear support, that slips comfortably over either ear, from which the earphone can't slip out or fall. Ideal for use with TV and radio sets, amplifiers, miniature and transistor receivers, etc. Shiny chrome finish. 3 ft. cord. 6 ohm impedance, with subminiature phone plug.
MS-591 Shpg. wt., 5 oz. Net .79

.79

TEST-O-CHARGE-5-IN-1 ELECTRONIC MARVEL

- It's a 3 Amp 6V/12V Battery Charger
- It's a Tube Tester
- It's a 9V Transistor Battery Charger
- It's an Electric Appliance Tester
- It's a Shock Hazard Detector

A new, multi-functional compact unit for home, farm, garage. Combines 5 practical and useful units for everyday use by practically everyone. Will charge any 6V or 12V car, marine or farm battery over-night—can be plugged into cigarette lighter. Circuit breaker protects Test-O-Charge and the battery. Will also test appliances and power tools by tracing faulty parts; detects any shock hazard on electrical devices; checks tubes for burned out filaments. 5¼x3¼x3". For 110-125V AC 60 cycles. Shpg. wt., 4 lbs.
CV-60 Net 9.95

ONLY 995

COLD-START BOOSTER-CHARGER

The First Combination Battery Charger and Booster

- 50 Amp Booster (6 volt)
- 25 Amp Booster (12 volt)
- 10 Amp Charger (6/12 volt)

2150

Perfect for starting 6V, 8V, 12V cars. Works as a booster—as a charger. As a booster will supply a maximum of 50 amps; as a charger, 10 amps. Supplied with heavy copper cables; thermal switch prevents overheating; works up to 200-ft. away from AC power source. Power output: 12V Boost, 25 amps maximum; 6V Boost, 50 amps max.; 6/12V Charge, 10 amps tapering to 5 amps max.; Power Input: 5 amps max. at 117V AC, 60 cycles. Shpg. wt., 9½ lbs.
CV-58 Net 21.50

SAVE

RECEIVING TUBES AT LOWEST PRICES EVER! \$\$\$ PLUS FREE CASH CREDIT DIVIDENDS \$\$\$



UP TO
56% OFF

MFR'S SUGGESTED LIST*
ASSORTMENT PRIVILEGE: TUBES MAY
BE ASSORTED FOR QUANTITY PRICE
*Lafayette Never Sells at These Mfr's Sug-
gested List Prices Which May or May Not
Be Generally Followed by Retailers.

NOTE: This is a partial listing.
This offer also applies to your selection
from our complete receiving tube listing
on Pages 112 and 113 of our Catalog 630.
Your order is shipped at current prices.
You benefit from any price reductions dur-
ing life of this catalog.

Name _____
Street _____
City _____
State _____

DEALER DIVIDEND-WORTH UP TO \$20.

Check one box and
enclose this coupon
with your order

- I enclose my order for 15 tubes
Credit toward the other mdse. on my order — **1.00**
- I enclose my order for 25 tubes
Credit toward the other mdse. on my order — **2.00**
- I enclose my order for 50 tubes
Credit toward the other mdse. on my order — **5.00**
- I enclose my order for 100 tubes
Credit toward the other mdse. on my order — **12.00**
- I enclose my order for 150 tubes
Credit toward the other mdse. on my order — **20.00**

A LAFAYETTE BONUS: With every order for receiving tubes you may choose
any additional merchandise from this Flyer, or our General Catalog, up to
the values listed below — **ABSOLUTELY FREE!**

This Offer Expires October 15, 1962

THIS COUPON USEABLE ONLY FOR PURCHASE OF MOSE. NOT GOOD FOR CASH REFUND.

Tube Type	Mfr. Sugg. List*	Net Each Asst. 1-9 10-up	Tube Type	Mfr. Sugg. List*	Net Each Asst. 1-9 10-up	Tube Type	Mfr. Sugg. List*	Net Each Asst. 1-9 10-up	Tube Type	Mfr. Sugg. List*	Net Each Asst. 1-9 10-up	Tube Type	Mfr. Sugg. List*	Net Each Asst. 1-9 10-up
024	2.40	1.18 1.06	5U8	3.30	1.62 1.46	6BY6	2.60	1.27 1.14	6CY5	2.75	1.35 1.21	6W4GT	2.40	1.18 1.06
163GT/1B3GT	2.90	1.42 1.28	5V3A	3.85	1.89 1.70	6BK5	3.70	1.81 1.63	6CY7	3.20	1.57 1.41	6W6GT	2.85	1.40 1.26
1I3	2.90	1.42 1.28	5Y4GA	3.50	1.71 1.55	6BK7B	3.40	1.66 1.49	6CZ5	4.10	2.01 1.81	6X4	1.65	.80 .73
1R5	2.70	1.32 1.19	5Y3GT	1.75	.86 .77	6BL7GTA	3.95	1.93 1.74	6DE6	2.55	1.25 1.12	6X5GT	2.10	1.03 .93
1S5	2.65	1.30 1.17	6AB4	2.15	1.05 .94	6BN4A	2.50	1.22 1.11	6D18	5.00	2.45 2.20	6X8	3.15	1.54 1.39
1T4	2.50	1.22 1.11	6AC7	5.10	2.50 2.24	6BN6	2.95	1.44 1.30	6DK6	2.35	1.15 1.03	7AU7	2.60	1.27 1.14
1U4	2.50	1.22 1.11	6AF4A	4.00	1.96 1.76	6BQ5	2.35	1.15 1.03	6DQ6B	4.15	2.03 1.83	7C5	3.50	1.71 1.55
1U5	2.20	1.08 .97	6AG5	2.75	1.35 1.21	6BQ6GA	4.35	2.13 1.92	6DQ6A	2.15	1.05 .94	7N7	7.55	3.70 3.33
1X2B	3.05	1.49 1.34	6AG7	5.90	2.89 2.60	6BQ6GT/6CUG	4.35	2.13 1.92	6E5	4.45	2.18 1.96	100E7	3.40	1.66 1.49
2B4A	2.55	1.25 1.12	6AGH	4.70	2.30 2.07	6BQ7A	3.95	1.93 1.74	6E8	3.20	1.57 1.41	12AB5	2.45	1.20 1.08
2CY5	2.85	1.40 1.26	6AK5	4.25	2.08 1.87	6BR8A	3.65	1.79 1.61	6E8B	4.00	1.96 1.76	12AB6	2.30	1.13 1.02
3AL5	1.85	.91 .81	6AL5	1.85	.91 .81	6BS8	3.75	1.84 1.66	6H6	3.95	1.93 1.74	12AB5	2.40	1.18 1.06
3AU5	2.15	1.05 .94	6AMBA	3.45	1.69 1.52	6BU8	2.80	1.37 1.23	6J5	3.65	1.79 1.61	12AT6	1.85	.91 .81
3B8G	3.05	1.49 1.34	6AN8A	4.00	1.96 1.76	6BY5CA	5.10	2.50 2.24	6J5GT	3.65	1.79 1.61	12AT7	3.05	1.49 1.34
3BZ6	2.30	1.13 1.02	6AR5A	2.15	1.05 .94	6BY6	2.50	1.22 1.11	6J6A	2.80	1.37 1.23	12AUG	2.15	1.05 .94
3C8G	2.30	1.13 1.02	6AR8	3.00	1.47 1.32	6BZ6	2.25	1.10 .99	6K6GT	2.65	1.30 1.17	12AU7A	2.45	1.20 1.08
3C8G/3BC5	2.35	1.15 1.03	6AS5	2.40	1.18 1.06	6BZ7	4.00	1.96 1.76	6L6	8.60	4.21 3.79	12AV6	1.65	.80 .72
3CE5/3BC5	2.40	1.18 1.06	6AS8	3.80	1.86 1.67	6C21	1.85	.91 .81	6L6CC	4.20	2.06 1.85	12AV7	3.55	1.74 1.57
3R6	2.20	1.08 .97	6AT6	1.90	.93 .84	6C2A	2.25	1.10 .98	6S4A	2.50	1.22 1.11	12AX4GTB	2.70	1.32 1.19
3OT6A	5.65	2.77 2.49	6AT8A	3.80	1.86 1.67	6C06GA	5.80	2.84 2.56	6S47	4.30	2.11 1.90	12AX7A	2.55	1.25 1.12
3B5GT	2.65	1.30 1.17	6AUSGT	4.30	2.11 1.90	6CES/6BC5	2.35	1.15 1.03	6SCT	4.20	2.06 1.85	12AZ7A	2.75	1.35 1.21
354	2.50	1.22 1.11	6AUGA	2.10	1.03 .93	6CF6	2.55	1.25 1.12	6SC7	4.60	2.25 2.03	12AZ7A	2.70	1.32 1.19
3V4	4.00	1.96 1.76	6AUBA	3.50	1.71 1.55	6CC7	2.45	1.20 1.08	6S7	4.15	2.03 1.83	12BAG	1.65	.80 .72
4BQ7A	3.55	1.74 1.57	6AV5CA	4.00	1.95 1.76	6CC8A	3.30	1.62 1.46	6SK7	3.95	1.93 1.74	12BEG	1.75	.86 .77
5AM8	4.00	1.96 1.76	6AV6	1.65	.80 .72	6CL6	3.75	1.84 1.66	6SK7GT	3.95	1.93 1.74	12BH7A	3.05	1.49 1.34
5AN8	2.20	1.08 .97	6AW8A	3.70	1.81 1.63	6CM7	2.90	1.42 1.28	6SL7GT	3.50	1.71 1.55	12BQ6GA	4.50	2.20 1.99
5AS4A	3.30	1.62 1.46	6AX4GTB	2.65	1.30 1.17	6CN7	2.75	1.35 1.21	6SN7GTB	2.60	1.24 1.14	12BQ6GT/12CUG	4.45	2.18 1.96
5AT8	3.65	1.79 1.61	6AX5GT	2.95	1.44 1.30	6C06	3.30	1.62 1.46	6SQ7	3.75	1.84 1.66	12BY7A	3.05	1.49 1.34
5BR8	3.65	1.79 1.61	6BAG	2.90	.98 .88	6C08	2.35	1.15 1.03	6S07GT	3.80	1.86 1.67	12CA5	2.50	1.22 1.11
5CC8	3.25	1.59 1.43	6BC8	4.00	1.88 .88	6C05	2.35	1.15 1.03	6T8A	3.40	1.66 1.49	12CUG/12C5	2.35	1.15 1.03
5CL8A	3.15	1.54 1.39	6BE8	2.20	1.08 .97	6CUB	4.15	2.03 1.83	6UBA	3.30	1.62 1.46	12DQ6B	4.20	2.06 1.85
5T8	3.40	1.66 1.49	6B06GA	6.50	3.18 2.86	6C04	4.45	2.18 1.96	6V6	6.75	3.31 2.98	12L6GT	2.45	1.20 1.08
5U4CB	2.10	1.03 .93	6B8G	2.70	1.32 1.19	6CX8	3.65	1.79 1.61	6V6GTA	2.15	1.05 .94			

LAFAYETTE BUDGET-PRICED TV PICTURE TUBES MONEY SAVING SPECIALS!

**FULL 1-YEAR
GUARANTEE**

Every Lafayette picture tube is top quality—made of
entirely new materials except the glass, which is
tested and inspected to meet new-glass standards.

AVERAGE SHIPPING WEIGHTS FOR PICTURE TUBES

Size of tube	Avg Shpg Wt	Size of tube	Avg Shpg Wt	Size of tube	Avg Shpg Wt
5"	5 lbs.	12"	17 lbs.	20"	30 lbs.
7"	7 lbs.	14"	17 lbs.	21"	35 lbs.
8"	8 lbs.	16"	22 lbs.	23"	40 lbs.
9"	10 lbs.	17"	24 lbs.	24"	44 lbs.
10"	14 lbs.	19"	26 lbs.	27"	45 lbs.

The size of the picture tube is determined by the first two digits in the
type No.

Net price "With Dud" based on your prepaid shipment or delivery of old
picture tube (Dud). Returned tubes must be intact and without scratches.
When ordering give stock number and type. Tubes which fall in normal
use within one year will be replaced with a new tube. *Indicates tubes
with aluminumized screens. †Indicates metal tubes. ††Tube supplied only
with dud.

Stock No.	Type	NET PRICE Less Dud	With Dud
PT-404X	10BP4A††	—	7.50
PT-405X	12KP4A*	10.33	—
PT-350X	12LP4A	9.00	—
PT-352X	14C/B/EP4B*	11.50	—
PT-351X	14EP4/CP4	10.25	—
PT-391X	14QP4A*	12.50	—
PT-393X	14RP4*	13.65	12.00
PT-353X	16AP4/AP4A†	15.10	13.45
PT-354X	16GP4†	13.94	13.39
PT-355X	16KP/VP4	9.00	—
PT-356X	16KP4A/RP4A/TP4A*	11.50	—
PT-394X	17AVP4	15.00	12.80
PT-395X	17AVP4A*	17.20	15.00
PT-357X	17BP4/BP4A	10.77	9.67
PT-358X	17BP4B*	12.53	11.33
PT-396X	17BRP4*	21.18	17.33
PT-406X	17BP4A*	21.18	17.33
PT-407X	17BP4A*	21.18	17.33
PT-408X	17BP4A*	21.18	17.33
PT-359X	17CP4†	16.75	15.25
PT-360X	17GP4/TP4†	17.65	16.00
PT-361X	17HP4/RP4	11.33	—
PT-362X	17HP4B/RP4C	12.95	—
PT-363X	17LP4/VP4	13.10	12.00
PT-364X	17LP4A/VP4B*	15.50	14.40
PT-397X	17QP4/YP4	12.21	11.11
PT-398X	17QP4A/YP4A*	13.77	12.67

Stock No.	Type	NET PRICE Less Dud	With Dud
PT-366X	19AP4A/AP4B†	17.50	16.95
PT-367X	20CP4A/DP4A	12.50	11.40
PT-368X	20CP4D/DP4C*	14.43	13.33
PT-370X	21ACP4A/AMP4A/BSP4*	17.70	12.75
PT-372X	21ALP4A/B/ATP4A*	17.40	13.00
PT-369X	21AP4†	21.90	17.50
PT-373X	21AU/AVP4*	16.95	12.00
PT-374X	21AU/AVP4B*	18.95	14.00
PT-400X	21BTP4/BTP4A*	17.62	12.67
PT-375X	21CBP4A/B/CMP4*	21.15	16.20
PT-409X	21CEP4/DFP4*	21.33	17.33
PT-410X	21CQP4*	21.73	17.33
PT-401X	21DEP4/DAP4/CZP4*	21.33	17.33
PT-376X	21EP4A	14.32	12.67
PT-377X	21EP4B*	16.00	14.35
PT-378X	21FP4A/KP4A	14.32	12.67
PT-379X	21FP/KP4C*	15.65	14.00
PT-402X	21MP4†	23.40	19.00
PT-380X	21WP4	17.10	13.80
PT-381X	21WP4A*	17.55	14.25
PT-382X	21YP4	17.62	12.67
PT-383X	21YP4A*	18.95	14.00
PT-384X	21ZP4/ZP4A	17.62	12.67
PT-385X	21ZP4B*	18.26	13.33
PT-387X	24CP4/CP4A/VP4/TP4/ADP4	24.92	18.67
PT-389X	24DP4/DP4A/YP4A*	25.25	19.00

A LAFAYETTE Serviceman SPECIAL!




**Economy
TUBE CADDY**

• Holds More Than 150 Tubes

Only **6⁹⁵**

Lafayette now offers a tube caddy with a capacity of
more than 150 tubes at this low, low price. Sturdily
constructed of wood and kraftboard with easy-to-open lid.
Overall 17Wx12½Hx7¾"D. Shpg. wt., 8 lbs.
ML-265W Net 6.95



RCA ALL AMERICAN 5-TUBE KIT

New Low Price!

2⁶⁶

Sensational buy by Lafayette brings this RCA all Ameri-
can 5-Tube kit to you at the unusually low price of
2.95. Used in most popular AC-DC Superheterodyne
Radio Receivers. Kit consists of 1 each: 50C5, 35W4,
12AV6, 12BA6 and 12BE6.
SP-258 Net 2.66

Serviceman & Dealer

SPECIAL!

INDOOR T.V. ANTENNA

Classic design for any TV set. 3-section
telescoping elements. Shpg. wt., 1 lb.

AN-105

85^c ea.

6 or more **77^c ea** | 12 or more **65^c ea**



LAFAYETTE—RF SIGNAL GENERATOR

EXCLUSIVE VALUE!



- Perfect for Engineers, Servicemen, Students and Experimenters
- Quality Assembled Equipment at a **KIT PRICE!**

COMPLETELY WIRED
NOT A KIT!

27⁹⁵
NO MONEY DOWN

- FACTORY CALIBRATED AND TESTED
- SIX BANDS: 120 KC - 260 MC
- DUAL OUTPUT RF TERMINALS
- SEPARATE VARIABLE AUDIO OUTPUT
- DIAL CALIBRATION $\pm 2\%$
- ETCHED CIRCULAR DIAL - (Vernier Tuned)

A stable, wide-range signal generator engineered to fill the need for an accurate low cost service instrument. Saves you time and money compared to spent building a kit of lesser quality. Since the delicate oscillator coils and tuning assembly are factory mounted and adjusted for optimum performance, the TE-20 is ready to go to work for you the instant you unpack it. This top-flight signal generator can be used for IF-RF alignment, audio signal tracing of TV, FM and AM sets, TV linearity checks and 400 cycle audio testing. In addition, it can serve as a marker generator when used with a suitable sweep generator. Look at some of the TE-20's features which make it the service instrument buy of the year. Incorporates a large 4 1/4" etched circular dial for easy, accurate frequency adjustments. Provides a fundamental frequency output of 120 KC to 130 MC in 6 bands plus a calibrated harmonic output of 130 MC to 260 MC. The built-in audio oscillator operates at 400 KC with adjustable output to 8 volts. Continuously variable RF attenuator for proper signal attenuation and two plug-in RF output terminals provide a choice of high and low outputs for maximum flexibility. High output and tuning dial calibration of $\pm 2\%$ give evidence of features not found elsewhere at twice its price. Imported

Net 27.95

SPECIFICATIONS

Full frequency range: 6 Fundamental bands—120-320 Kc 320-1000 Kc. 1-3.4 MC, 3.2-11 MC, 11-38 MC, 36-130 MC.
One harmonic band 130-260 MC.
Frequency Accuracy: $\pm 2\%$. Audio Output: to 8 volts.
Large 4 1/4" Etched Circular Dial (Vernier tuned)
High-Low RF Output Terminals.
Tube Complement: 12BH7A, 6AR5, Selenium Rectifier.
Power Requirements: 105-125VAC 50/60 Cps., 12 Watts.
Attractive gray wrinkle steel case with leather carrying handle.
Complete with test leads.
Size: 7Hx10 1/2Wx5 3/4"D. Shpg. wt., 9 lbs.

LAFAYETTE—SINE SQUARE WAVE AUDIO GENERATOR

TOP QUALITY!



- FACTORY CALIBRATED AND TESTED
- LOW DISTORTION
- FREQUENCY RANGE - SINE: 20 cps—200 KC IN 4 BANDS; SQUARE WAVE RANGE: 20-25 KC (Vernier Tuned)
- ETCHED CIRCULAR DIAL
- FREQUENCY RESPONSE - $\pm 1.5\text{DB}$, 60CPS - 150KC 4 1/2" VERNIER DIAL

COMPLETELY WIRED
NOT A KIT!

32⁵⁰
NO MONEY DOWN

The Lafayette TE-22 is especially designed for radio-TV servicemen, Hi-Fi fans and students who require a dependable sine and square wave generator at low prices. A completely wired and tested instrument, it is equal in quality to higher priced separate generators and far more convenient to use. A terrific buy, this generator will outperform most higher priced kits with ease. Among its many applications are square wave testing of audio amplifiers, determining the frequency and transient response of loudspeakers, TV audio circuit testing and many other uses. Quality features consist of a frequency response of ± 1.5 db from 20 cps to 200,000 cycles in 4 bands. A large easy-to-read etched dial (vernier tuned) adds a professional quality touch. Variable attenuator prevents overloading circuits and permits proper tracking of test response. A full wave power supply is incorporated to provide low distortion and constant output. Factory wiring and calibration insure its accuracy to be within 3%. High output voltage is 7 volts (max.) across a 1 megohm load. A rugged steel cabinet and shock proof mountings protect components, complete with instructions and test leads. A handsome instrument—one which you will be proud to own. Imported

Net 32.50

SPECIFICATIONS

Frequency range: Sine wave: 20-200,000 cps in 4 bands.
Square wave—60-30,000 cps
Output Voltage—Sine: 7V RMS; Square 7V P-P
Output Impedance—0-5000 Ohms. Frequency Accuracy: $\pm 3\%$.
Distortion: Less than 2%.
Tube Complement: 1-6BM8, 1-12AT7, 1-6X4
Power requirements: 117V 50/60 cps. 19W.
Gray wrinkle steel case with leather carrying handle.
Complete with a pair of test leads.
Size: 7Hx10 1/2Wx5 3/4"D. Shpg. wt., 10 lbs.

LAFAYETTE CAPACITANCE-RESISTANCE ANALYZER

SPECIAL BUY!



- Factory Wired and Tested
- Capacitance Bridge Circuit
- Direct Reading Scales for Capacitance and Resistance
- "Magic-Eye" Null Indicator and Meter
- Checks Opens, Shorts, Leakage and Intermittents
- Determines Power Factor of Electrolytics
- 2 Turns Ratio Scales
- Measures Impedance

COMPLETELY WIRED
NOT A KIT!

37⁵⁰
NO MONEY DOWN

Here is a real service value which can do wonders in your shop or lab. The TE-25 is a completely self-contained AC operated, bridge-type capacitance-resistance analyzer which has a number of time saving applications. It is a high caliber, factory built instrument, not a kit. All readings are made directly without complex, time wasting calculations. "Lab" accuracy within $\pm 5\%$ for values to 200 mfd. and $\pm 5\%$ from 200 mfd. up. It measures capacity and resistance in 4 separate ranges—from 1 mmf—5000 Mfd and from 0.5 ohms—500 megohms on a large permanently etched circular metal scale. You will find it invaluable for the following jobs: Measurement of Capacitance for paper, mica, ceramic and electrolytic capacitors. Resistance measurement. Power Factor measurement on electrolytics from 0-55%; shorts, opens and leaky capacitors. Also determines turn and impedance ratio of audio and power transformers. Read insulation resistance of paper, mica and ceramic capacitors directly on meter to 500 megohms. Eliminates guessing with neon lamps. DC voltage may be varied up to 600 volts to find leakage current of electrolytics. Two ranges: (0-6) (0-60) ma is directly read on meter. No guesswork is necessary. Ratio scales are provided to measure impedance and turns ratio of power and audio transformers (to 500:1) in 2 ranges. "Magic-Eye" tube shows capacitance null indication—opens, shorts for electrolytics. calibrated power factor control is provided to check capacitor efficiency. No service shop or laboratory should be without one. Shpg. wt., 12 lbs. Imported

Net 37.50

SPECIFICATIONS

Capacity, 4 Ranges — 00001 mfd — .005 mfd; .001 mfd — .5 mfd; 1 mfd — 50 mfd; 50 mfd — 5000 mfd. Resistance — 4 Ranges — 0.5 ohms — 500 ohms; 50 ohms — 50K ohms; 5K ohms — 5 megohms; 5 megohms — 500 megohms. Transformer Turns Ratio — 1:1 — 10:1; 10:1 — 500:1. Impedance Ratio: — 1:1 — 100:1; 100:1 — 250K:1. DC Leakage Test — Voltages: 0-600 Volts DC. Leakage Current — 6MA — 60 MA — 2 Ranges. DC Insulation Test — 600 Volts Constant — 10 megohms — 500 megohms. Tube Complement: — 1—6R4; 1-6E5. Power: — 117V; 50/60 cps AC. Size: 10 1/2Wx7Hx 5 1/4"D. Complete with instructions and test leads. Handsome grey wrinkle steel case with leather carrying handle.

LAFAYETTE CRT REJUVINATOR TESTER

CAPACITOR CHECKER



MODEL TE-19

- Checks and Corrects Each Gun Of Color Tube Separately

- Rejuvenates All TV Picture Tubes Including Color and 110° Types

COMPLETELY WIRED
NOT A KIT!

39⁵⁰
NO MONEY DOWN

- Factory Wired & Tested
- Locates TV Tube Defects

The fabulous TE-19 is a "must" for every TV service shop. It will quickly pay for itself in time saved and money earned. Light in weight, completely portable, The TE-19 is ideal for "in the home" service calls. Solves most picture tube problems usually encountered without any fuss. Cuts service operating costs, makes your home visits more profitable. This quality factory wired and tested instrument rapidly checks and corrects black and white and color TV picture tubes including 110° types without removing them from the set. All controls are functional and clearly marked. Factory assembled, hand wired circuit assures long, trouble-free service. Needs only seconds to warm up and short test may be made without warm-up. Restores brightness and emission to old CRTs. Rejuvenates all cathode ray tubes. Lens type neon lamp lights when tube filaments are shorted.

Nothing could be simpler. Determines quality of CRTs by means of an emission test. Large 4 1/2" meter gives legible readings at a glance with colored Good-Bad scale. Neon tube provides positive leakage indication. Selector switch provides a choice of dual filament voltages of 6.3 V and 12.6 V. Checks and corrects each gun of color tube separately. Repairs inter-element shorts and open circuits. Includes 2 additional tube socket adaptors for 110° deflection type tubes. Operates on 105-125V 60 cycle AC. Handsome portable leatherette covered gray case with detachable top. Size: 4 1/4x7 1/2x13 1/2". Shpg. wt., 9 lbs. Imported

TE-19 Adapter for new 23EP4 picture tube Net 39.50
TE-26 Net 1.50



MODEL TE-44

14⁹⁵

COMPLETELY WIRED
NOT A KIT!

- Checks Capacitors Without Disconnecting Leads
- Tuning Eye Indicator
- Not A Kit—Completely Wired & Tested

The TE-44 allows you to check most capacitors, from 10 mmfd. to 2,000 mfd., for open or shorted conditions without unsoldering—no leads to disconnect. Tests for opens on capacitors of 10 mmfd. or more; for shorts up to 2,000 mfd. shunted by not less than 10 ohms. If capacitor is intermittent, tuning eye indicator will flicker. Ideal for checking bypass, blocking and coupling capacitors. Uses a 20-24 MC frequency for "open" test and a 60 cps frequency for "short" test. Complete with test leads and mounted in an attractive gray wrinkle-finish metal cabinet. Tubes: 1-6C4, 1-6E5. Built-in power supply uses a selenium rectifier. Size: 7 1/4Wx5Hx4 1/4"D. Shpg. wt., 5 lbs. Imported

Net 14.95

DELUXE LAFAYETTE PEAK-TO-PEAK V.T.V.M. KIT

An Outstanding Development In V.T.V.M. Design The Only V.T.V.M. Available With These Features



- Special Low AC Ranges Provide Noise & Gain Measurements (as low as 1 mv) for Audio & Hi-Fidelity Applications
- Scope Monitor Terminals For Direct Connection To Oscilloscope
- Newly Designed Lafayette Push-Button AC/DC Omni-Probe
- Calibration Controls—Accessible Without Removing Cabinet
- Measures AC Peak-To-Peak, AC RMS, DC Voltage & Resistance
- Direct Reading DB Scale
- Regulated & Balanced Bridge Circuit Provides Unequaled Accuracy & Stability
- Circuit Employs 12AU7 Twin Triode Operating Only Within Its Linear Capabilities
- 1% Precision Multiplier Resistors
- Accurate 200 μ a Meter Movement with Large 4 1/2" face

In Every Respect A Professional Test Instrument—Engineered to meet and exceed the rugged standards, accuracy plus required sensitivity demanded in laboratory, industrial and service applications. The KT-174 offers in remarkably easy-to-build kit form, a Vacuum Tube Volt Meter that achieves a level of performance and versatility rivaling factory wired equipment many times its price. Unquestionably The Finest VTVM in its class. Utilizing a printed circuit board, Lafayette's famous step-by-step instructions and huge pictorial diagrams assure ease of assembly. Attractive dark grey front panel is set in a contrasting textured light grey metal case. Complete with tubes, battery and special Lafayette Omni-Probe. Size: 8 1/2"x6Wx5 1/2" D. For 105-125 volts, 60 cycles AC. Shpg. wt., 8 lbs.

LABORATORY TEST EQUIPMENT IN EASY-TO-BUILD KIT FORM

NO MONEY DOWN

KT-174 | TE-31
44⁵⁰ | **57⁰⁰**
IN KIT FORM | COMPLETELY WIRED AND TESTED

COMPARE THESE SPECIFICATIONS

DC VOLTMETER—Ranges: 0-1.5, 5, 15, 50, 150, 500, 1500V. Input Resistance: All ranges—11 Megohms. Sensitivity—1.5V Range: 7.3 Megohms/Volt. Accuracy: $\pm 2\%$ of full scale at 117VAC—deviation due to line voltage variation between 105-125 volts is negligible. AC VOLTMETER—LOW AC—Ranges: RMS-0 to 50 mv, 0-150 mv, 0-500 mv. Peak-To-Peak—0-140 mv, 0-420 mv, 0-1400 mv. Accuracy: $\pm 5\%$ of full scale. Input Impedance: 1 megohm at 1 KC. Freq. Response: ± 1 db from 20 to 300,000 cps from 600-ohm source. REGULAR AC—Ranges: RMS—0-1.5, 5, 15, 50, 150, 500, 1500 volts. Peak-To-Peak: 0-4.2, 14.0, 42, 140, 420, 1400, 4200V. Accuracy: 3% on all ranges except 5% on 0 to 5V. Freq. Response: ± 1 db 20 cps to 4 mc from 600-ohm source. Input Impedance at 1 KC: 0-1.5V, 5V, 15, 50-83 Meg. 0-150V, 1.3 meg—0-500V, 1500V—1.5 meg. OHMMETER—7 Ranges: 0-1000 RX1, RX10, RX100, RX1000, RX10K, RX100K, RX1M using precision 1% dividing resistors. Meter Movement: 200 μ a for full scale deflection. Tubes: 1—6BN8, AC full-wave peak rectifier and low AC amplifier; 1—12AU7 twin triode meter DC amplifier and balanced bridge. Incorporates Half Wave Selenium Rectifier and Well Filtered Fused Power Supply.

Net 44.50
Net 57.00
Net 3.75

LAFAYETTE V.T.V.M. KIT WITH 6" METER



- Wide Band—AC Measurements on any Waveform from 30 Cycles to Over 5 MC, Without Additional Probes or Accessories
- 11 Megohm Input Resistance—Negligible Loading Effects on DC Circuits
- Direct Reading DB Scale
- Balanced Push-Pull Amplifier—Isolates and Protects Meter
- Etched Circuit Design Simplifies Construction
- Selected 1% Zero Temperature Coefficient Multiplier Resistors for Dependable, Accurate Readings
- Giant 6" Full-View Meter With Easy-To-Read Two-Color Scales

An indispensable test instrument for the service technician, experimenter or hobbyist. The KT-202 is a high quality V.T.V.M. in easy-to-build kit form, which offers features unusual at this low price. It is a highly accurate DC voltmeter, AC voltmeter and ohmmeter employing a giant 6", 400 μ a meter with clear black and red scales. High input impedance of 11 megohms, accurately measure DC voltages up to 1500 volts while presenting a negligible load to the circuit under test. As a wide band AC voltmeter, it will measure AC peak-to-peak voltages up to 2,000 volts on any waveform. All this from 30 cycles to above 5 Mc—without any accessory probes! AC RMS voltages may be read directly up to 1,500 volts if the waveform is sinusoidal. The wide frequency response makes this meter ideal in audio, radio and TV applications. Resistances can be read directly on the Ohms scale from 0.2 ohms to 1,000 megohms. A direct reading decibel scale is calibrated from -10 to +18 db (reference 1.73 volts, 6 mw into 500 ohm line). In addition, zero center measurements can be made. The KT-202 utilizes a 12AU7 balanced push-pull DC amplifier and two 9006 tubes as peak-to-peak voltage rectifiers. The meter is isolated making it virtually impossible to burn it out. Multiplier resistors are 1% zero temperature coefficient types, to assure maximum accuracy and minimum variation due to heat. Front panel controls: Function Selector—selects Pwr. Off, A.C.V./P-PV, D.C.V. Neg., D.C.V. Pos., Ohms; Range Selector—for 7 voltage and resistance ranges; Ohms Adjustment; Balance (zero) Adjustment. There are 3 probes: Common, A.C.V.—Ohms, and a shielded D.C.V. probe with 1

megohm isolating resistor. Printed circuitry makes construction of this kit easy. Selenium rectifier transformer—operated power supply for 110-120 VAC, 60 cps. Dimensions: 7 1/2"x6 1/2"x5 1/2" overall. Kit comes with 1 1/2 volt battery for ohmmeter circuit and complete instructions. Shpg. wt., 7 lbs.

Accessories: Accessory RF probe for KT-202 or other 11 megohm V.T.V.M. Net 25.77
Carrying case for KT-202, complete with handle. Net 3.75
KT-203 Shpg. wt., 1 lb. Net 2.95

MODEL KT 202
25⁷⁷
NO MONEY DOWN

SPECIFICATIONS

DC VOLTMETER RANGES: 0-3, 15, 75, 150, 300, 750, 1500 volts. Input resistance: 11 megohms (1 megohm in probe) on all ranges. AC VOLTMETER RMS RANGES: 0-3, 15, 75, 150, 300, 750, 1500 volts. PEAK-TO-PEAK RANGES: 0-8, 40, 200, 400, 800, 2000 volts. DECIBEL RANGES: -10 to +18db, +10 to +38db, +30 to +58db. Response: 30 cycles to above 5 Mc. OHMMETER RANGES: 0-1000, 10,000, 100,000 ohms: 0-1, 10, 100, 1000, megohms. CENTER SCALES: 10, 100, 1000, 10,000, 100,000 ohms, 1 megohm, 10 megohms. TUBES: 1—12AU7 twin triode balanced meter bridge, 2—9006 peak to peak rectifiers. 1 power supply selenium rectifier. POWER: 110-120 VAC, 60 cycles.

NEW! LAFAYETTE COMBINATION SIGNAL GENERATOR AND SIGNAL TRACER KIT

MODEL KT-208



MADE IN U.S.A.

Another Outstanding Achievement by Lafayette Test Equipment Engineers SEMI-KIT CONSTRUCTION

This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory.

SIGNAL GENERATOR

- Covers From 250 KC to 120 MC in 5 Bands
- High Stability Electron Coupled Oscillator
- Attenuator For Both RF and Audio Circuits
- Most Used Frequencies Marked on Panel in Color
- Utilizes New Ruggedized Industrial Type Tubes

SIGNAL TRACER

- Hi-gain Cascade Pre-amplifier
- Front Panel Output For VTVM, Scope or Phones
- Low Distortion Triode Output Stage
- 4 1/2" Permanent Magnet Speaker
- Separate R.F. and Audio Signal Probes

19⁹⁵

Two test instruments in one! And available in easy-to-build kit form. The Signal Generator will serve as a full service instrument and the Signal Tracer will follow any signal whether generated by a broadcasting station or injected by the Signal Generator section of the Model KT-208. When used in combination, with no dependence on outside signals, the compatibility of Model KT-208 provides ideal service, for unlike any standard signal tracer, it first injects its own signal then traces that controllable signal to locate the source by standard signal tracing technique. Designed

for use with AM, FM, TV and audio circuitry. Features 5 frequency ranges and an attenuator switch to control both the R.F. signal (either modulated or unmodulated) and the 400 cycle audio tone. Front panel output jacks which can be used for oscilloscope, VTVM or earphone connections. Famous Lafayette kit building manual with large pictorials will make it a pleasure to build. Housed in a beautiful crackle finish steel cabinet with a deep etched aluminum panel. Dimensions: 7 1/2"x4 1/2"x5 3/4". Complete with 2 probes. Shpg. wt., 9 lbs. Net 19.95


SPECIFICATIONS

RANGE: BAND A: 250KC to 850KC; B: 850KC—300KC; C: 3.0MC to 11MC; D: 11MC to 45MC; E: 35MC to 120MC: 400cps audio signal; modulation slide switch,

RF/AF attenuator and power switch; Signal output jack; AF input jack. 2 Preamp. output jacks. 4 1/2" Alnico 5 speaker. Tubes: 5965, 5687, 6350.

NEW! LAFAYETTE TUBE TESTER KIT TESTS TUBES IN SECONDS

MODEL KT-209



MADE IN U.S.A.

- Test Over 1,000 Tube Types
- Checks For Shorts and Leaks
- Checks Between All Elements
- Tests Filament Continuity
- Checks All Modern Tubes
- Five Year Free Tube Data
- 7 and 9 Pin Tube Straightener
- Rugged, Accurate, Meter Movement With Sealed-Air Damping Chamber

SEMI-KIT CONSTRUCTION

This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory.

17⁹⁵

FEATURES & SPECIFICATIONS:

The KT-209 is a complete portable tube tester designed to test the modern tubes found in radio, TV and hi-fi amplifier systems. Speedy operation is assured by use of a single rotary switch in place of one-at-a-time slide switches normally used. Just insert tube in one of the seven panel sockets, set filament selector switch and then rotate the Element switch. Shorts show up instantly on the "leakage indicator" lamp. Tube emission quality is indicated on the highly damped meter's calibrated "Good—?—Bad" scale. A two position slide switch for regular or special higher voltage tubes sets up the meter test. 7 and 9 pin straighteners are provided to insure long life for these sockets. Superbly

detailed, step-by-step Lafayette instruction manuals with giant diagrams will assure you of factory-type assembly. This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory. All you have to do is wire it up! American made, and replacement parts are always available if needed. No finer value available anywhere. Housed in a portable leatherette carrying case with removable cover for easy accessibility. This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory. Dimensions: 10 1/2"x8 3/4"x3 1/2". Shpg. wt., 6 lbs. Net 17.95

KT-209 Kit Net 17.95

EICO MODEL 955 IN-CIRCUIT CAPACITOR TESTOR KIT



19⁹⁵

Checks for shorts (even in the presence of as little as 1 ohm shunt resistance). Checks for opens: capacitors as small as 15 mmf. in or out of circuit. When bridge circuit measures capacitance with $\pm 10\%$ accuracy between 0.1 mp and 50 mp. at any point on the 4" lucite dial-product, convertible into dissipation or power factor-indications visible on electron ray tube. Includes line adjust control. For 105-130 VAC. Size: 8 1/2"x5 3/4"x6 1/2" D. Shpg. wt., 4 lbs.

TE-737 955 Kit Net 19.95
TE-738 955 Wired Net 39.95

EICO MODEL 460 WIDE BAND SCOPE KIT




79⁹⁵

Excellent Lab precision scope featuring push-pull direct coupled vertical amplifier with high sensitivity: 25 mv/in. Response flat from DC to 4.5 mc, useful to 10 MC. Ideal for reproduction of 3.58 mc color TV sync. burst. Complete with all components and instructions for easy assembly. 13x 8 1/2"x16". For 105-125 VAC. 50-60 cycles. Shpg. wt., 30 lbs.

TE-222WX Kit Net 79.95
MODEL 460 As above, but factory wired and tested. Net 129.50
TE-223WX

EICO MODEL 680 TRANSISTOR and CIRCUIT TESTER KIT




25⁹⁵

Provides accurate measurements of diodes and ICBO and ICEO. The VOM includes 5 DC current ranges. 2 DC volts ranges at 20,000 ohm/volt, and 3 resistance ranges. 3 1/2" D'Arsonval meter has 2% accuracy. Self-powered, uses 4 size AA and 1 "C" battery. Includes 3 permanently connected clip-on test leads on a panel socket for transistor connections; 2 banana jacks. Housed in a sturdy bakelite case. Size: 6 3/4"x5 1/4"x3 3/4" D. Shpg. wt., 3 lbs.

TE-735 680K Kit Net 25.95
TE-736 680 Factory wired and tested Net 39.95

SIMPSON MODEL 260 SERIES III AC-DC V-O-M



47⁹⁷

Now offered in a new and improved form. Sensitivity—20,000 ohms; V.D.C.—5,000 ohms—V.A.C. Ranges: DC: 0-25V, 2.5V, 10V, 50V, 250V, 500V; AC: 0-2.5V, 10V, 50V, 250V, 1000V, 5000V; AF: 0-2.5V, 10V, 50V, 250V; DB: 20 to +10 db; -8 to +22 db; +6 to 36 db; +20 to +50 db. DC current ranges from 0-50 μ amps, 0-1, -10, -100, -500 ma; 0-10 amps, DC resistance from 0-2000 ohms, 0-200,000 ohms, 0-20 megohms. Accuracies: DC volts $\pm 3\%$ F.S.; AC volts $\pm 5\%$ F.S.; DC resistance $\pm 3\%$ of arc from absolute value of resistance measured. Meter housed in Bakelite case, measures 5 1/4"x7 3/8". Comes with battery and test leads. Shpg. wt., 6 lbs. Net 47.97

TE-310 Net 47.97

The Sensational LAFAYETTE TE-15 TUBE TESTER



COMPLETELY WIRED — NOT A KIT

- Accurately Checks Over 1000 Different Tubes
- Tests for Cathode Emission, Leakage and Shorts plus Filament Continuity
- Completely Portable—Weights Only 6 lbs.
- Highly Accurate Easy-to-Read Meter with Replace—Good Scale
- Fast-Setting Slide Switches
- Slide Out Tube Chart

Highly dependable, the Lafayette TE-15 is equipped to test most of the tube types employed in Radio, Hi-Fi, Monochrome, Color TV, etc. Sockets have been provided for 7-pin miniature, 9-pin miniature, octal base, loctal base, hoval and sub-miniature types. A special alligator clip lead is furnished for testing tubes with top caps. Slide switches are employed to connect the various tube elements to their respective test circuits. A 3-position tube slide switch adjust for checking shorted elements, cathode emission and filament continuity. In conjunction with the leakage-quality switch a leakage indicator light is employed which glows when on inter-element short or leakage is present in a tube. A power switch turns the unit on and additionally serves to adjust for various AC line voltages. Large easy-to-read meter calibrated 0-100 has a red-green "Replace—Good" scale, plus a special scale for checking diodes.

A handy slide out metal tray contains tube charts which facilitate rapid selection of test settings. Metal case is attractively finished in cream and steel gray. Completely portable—weights only 6 lbs. and measures 8 1/2" D x 9 3/4" W x 2 3/4" H. Supplied with carrying case. For 105-125 volts, 60 cycle AC. Shpg. wt., 7 lbs. Imported TE-15 Tube Checker Imported Net 19.95

LOW,
LOW PRICE!

19⁹⁵

FULL
SIZE
9 3/4" W
x 8 1/2" D
x 2 3/4" H

NO MONEY
DOWN

An accurate, versatile, precision instrument that actually tests over 1000 different tubes. The low cost and superior performance of the Lafayette TE-15 Tube Tester combine to make it the outstanding test instrument value today—the ideal tube tester for any radio-TV serviceman, experimenter, technician, etc.

20,000 OHM PER VOLT SEMI-KIT MULTITESTER



A New Kind
of Kit
ONLY
11⁹⁵

The semi-kit is a new concept in test equipment kits. All the important or difficult parts are already mounted. All that remains to be done is to mount and wire in a few small parts—a job so simple you'll finish before you realize it, and best of all, you'll have one of the finest high sensitivity multitesters on the market. When used in a circuit, the high input resistance on all DC and AC ranges does away with the highly inaccurate readings common to low resistance testers which load the circuit. Ranges: DC Volts, 0-10-50-250-500-1000; AC Volts, 0-10-50-250-500-1000; DC CURRENT, 0-500 ua, 0-10-250 ma. OHMS, 0-10K-100K-1 meg; DECIBELS, —20 to —36; PLUS 0-5000 henrys inductance and 250 mfd. to .02 mfd. Black case 5 3/4 x 3 3/4 x 1 7/8". Complete with test leads, all parts, and instructions and battery. Shpg. wt., 3 lbs. Imported. Net 11.95

FILAMENT CONTINUITY TUBE CHECKER



1⁶⁹

Small and compact as a cigarette box. Quickly checks filament continuity in a matter of seconds. Ideal for the serviceman or the technician working in the field. Tests filaments of radio, TV picture tubes. Also can be used to test many other electrical devices and line cords, fuses, lamps and bulbs. Has sockets for TV picture tube and loctal, octal, 9-pin, as well as 7-pin sockets. Provided with two test leads. Grey hammettone finish. Size: 4 x 3 1/2". Shpg. wt., 12 oz. TE-11 Imported Net 1.69

NEW! 10,000 OHMS PER VOLT MULTITESTER



OUTPERFORMS INSTRUMENTS
MANY TIMES ITS SIZE

9⁹⁵ • EXTRA LARGE
3 1/2" METER FACE
• ALL ACCESSORIES
INCLUDED

• COMPLETELY WIRED (NOT A KIT)

FULL SCALE RANGES

DC VOLTS: 0-6, 0-30, 0-120, 0-600, 0-1200; AC VOLTS: 0-6, 0-30, 0-120, 0-600, 0-1200; DC CURRENT: 0-120uA; 0-3M; 0-300M RESISTANCE: 0-30K; 0-3 MEG DECIBELS —20 to —63 in 5 scales; Capacity 50 uF to .01uF; and .001uF to .15u; OUTPUT RANGES 0-6, 0-30, 0-120; 0-600; 0-1200.

Unbelievable Bargain. Lafayette's new multitester is a complete factory wired and tested instrument (not a kit). It can be conveniently carried in the pocket, and features unusually sensitive 10,000 ohms-per-volt AC-DC meter, 1% precision resistors, and the largest meter ever placed on an instrument of this size. Single easy-to-use range selector switch can be appreciated by the novice and the engineer alike. Case and panel are made of durable bakelite. First capacity range requires 120 volts AC, second range requires 6 volts AC. Probes and flexible leads are plastic coated and color coded. Size: 4 1/2 x 3 1/2 x 1 1/2". Complete with leads and battery. Shpg. wt., 1 1/2 lbs. Imported. Net 9.95

TE-10 Pigskin carrying case for TE-10. Shpg. wt., 8 ozs. Net 11.95
TE-14 Imported

NEW! 20,000 OHMS PER VOLT MULTITESTER



13⁵⁰

- 20,000 OHMS PER VOLT DC—10,000 OHMS PER VOLT AC
- 40 MICROAMPERE 3" D'ARSONVAL METER MOVEMENT

• HIGH INPUT RESISTANCE ON ALL DC AND AC RANGES

This new multitester has extra-luxury features, found in the most costly instruments. Easy visibility is provided by the large 3" meter with two color scales for resistance on all ranges: 20,000 ohms per volt on DC; 10,000 ohms per volt on AC. This plus 1% tolerance resistors all the measuring of voltages without unduly loading the circuit, thus preserving accuracy of readings. Besides the extreme sensitivity and superior versatility of this instrument, it features ranges not found on other, competitively priced VOM's. Measures 0-10-50-250-500-1000 DC volts, 0-10-50-250-500-1000 AC volts, 0-10K-100K-1 meg ohms, 0-500 microamperes, 0-10-250 milliamperes, —20 to —36 decibels. PLUS two special ranges 0-5000 henrys inductance and 250 mfd to .02 mfd capacity. Employs one standard 1 1/2 v penlight battery. Size 3 3/4 x 5 3/4 x 1 7/8". Shpg. wt., 3 lbs. MODEL RW-60 Multimeter Imported Net 13.50

TE-37 Felt-lined carrying case for above instrument, Imported Net 2.95

NEW HIGH SENSITIVITY MULTITESTER



- 20,000 OHMS PER VOLT DC
- 10,000 OHMS PER VOLT AC
- RESISTANCE RANGE 0-60 MEGOHMS
- 40 uA MOVEMENT
- 1% RESISTORS
- 0-0.6 VOLT DC RANGE FOR AUDIO AND TRANSISTOR WORK
- COMPLETELY WIRED
- 28 RANGES

17⁹⁵

A new high-quality, low-priced multitester. Its light weight makes it a perfect portable instrument for technicians, servicemen, etc. Rugged design withstands hard use. Features large easy-to-read meter and sensitive 40 microamp meter movement. 1% tolerance resistors provide extreme accuracy of measurements. Housed in rugged bakelite case. Single knob selector and clearly marked positions permit easy operation. Recessed zero-ohms knob adjustment provided. Features sensitivity of 20,000 ohms volt DC, and 10,000 ohms volt AC. Ranges: DC volts: 0-0.6, 0-6, 0-30, 0-120, 0-600, 0-1200, 0-3000, 0-6000 volts. AC volts: 0-6, 0-30, 0-120, 0-600, 0-1200 volts. Resistance: RX1, RX10, RX1K, RX10K. DC current: 0-0.06, 0-6, 0-60, 0-600 ma. Decibels: —20 to —17 (0 db — 0.774 V). Capacity: .0001-0.1, .005-20 mfd. Output ranges: 0-6, 0-30, 0-120, 0-600, 0-1200 volts. Complete with color-coded heavy duty test probes and battery. Size: 6 x 3 7/8 x 1 3/4". Shpg. wt., 1 1/4 lbs. Imported Net 17.95

TE-12 Pigskin carrying case for above instrument, Imported Net 2.95

NEW! POCKET AC-DC VOM

6⁹⁵
SALE PRICE
4⁹⁵



Effective Thru Oct. 15, 1962

- Extremely Compact. Measures Only 3 7/8 x 2 1/8 x 1". Weighs 5 Ozs.
- 1,000 Ohms Per Volt Sensitivity
- Completely Wired (Not A Kit)
- 1% Precision Resistors
- Reads: 0-1000 Volts AC-DC, 0-100KΩ, 0-150 MA

Lafayette's new, pocket multitester features small physical size, and a wide selection of useful ranges. It can be used for trouble-shooting any type of electronic circuits or electrical appliances such as irons, lamps, radios, television, hi-fi equipment, etc. It is also useful for testing complex electrical circuits. Extreme portability allows unlimited usage either at home or in the field.

1000 ohms per volt sensitivity, and 1% precision resistor components assure accurate, precise readings. Operation is extremely easy, simply plug the leads into the desired scale, and you are ready to go. No switching or fiddling required. Ranges Volts: 0-15, 0-150-1000 AC and DC. Ohms: 0-100K; MA 0-150. The VOM comes completely wired and tested, and is enclosed in durable plastic case. All accessories including battery are rubber insulated, color coded. Flexible test leads are supplied. Imported.

TE-13 AC POCKET VOM Shpg. wt., 1 lb. Net 4.95

NEW! CAPACITANCE SUBSTITUTION BOX



2⁹⁵

- 36" Color Coded Test Leads & Clips

- 9 Ranges From .0001 to .22 MFD

A must for the serviceman, experimenter or student. Fast accurate selection of any one of 9 capacitor values from .0001 to 22 MFD. Condensers are porcelain cased tubular type impervious to moisture and are rated at 600 volts working capacity. 9 capacitance ranges are .0001, .0022, .0047, .01, .022, .047, .1 plus 22 MFD. Complete with 36" red and black test leads and alligator clips. Size: 4 3/4 x 2 5/8 x 1 5/8". Shpg. wt., 1 1/2 lbs. Imported. Net 2.95

TE-16

NEW! RESISTANCE SUBSTITUTION BOX



3⁹⁵

- 24 Resistance Ratings
- Two Ranges — Low 15-10K Ohms. High 15K-10 Megohms.
- 36" Red & Black Test Leads with Alligator Clips

Ideal for laboratory or service application. Substitute resistance values fast and accurately in trouble shooting circuits where values may have changed. Easy to find bias resistance in experimental vacuum tube or transistor circuits. Slide switch selects two ranges—Low: 15 ohm—10K ohm (1 watt resistors) High: 15 K ohm—10 Megohms (1/2 watt resistors). Two rotary switches (12 steps each) selects 24 separate resistances. Size: 4 3/4 x 2 5/8 x 1 5/8". Shpg. wt., 1 1/2 lbs. Imported. Net 3.95

TE-17

SPECIAL

SENIOR V.T.V.M with 6 1/2" METER

Not a Kit...
This is a
completely wired
and calibrated
instrument

29³⁵

- ± 3% Accuracy of Full Scale
- Giant 6 1/2" Meter Face
- Direct Reading DB Scale

COMPARE THESE FEATURES
D.C. VOLTMETER. Ranges 0 to 3, 30, 150, 300, 1500 volts. Accuracy ± 3% of full scale. Input resistance: 11 megohms. ZERO CENTER VOLTMETER (for discriminator alignment) Ranges 0 to 1.5, 15, 75, 150, 750 volts. Accuracy ± 3% of full scale. Input resistance: 11 megohms. AC VOLTMETER. RMS RANGE: 0 to 3, 30, 150, 300, 1500 volts. Peak to Peak Ranges: 0 to 8, 80, 400, 800 volts. Accuracy ± 3% of full scale. OHMMETER: Ranges 0 to 1000 megohms (5 overlapping ranges). Center scale values: 10, 100, 1000, 100,000 ohms, 10 megohms. DECIBEL METER (for all audio measurements) Ranges: —10 to +5, +6 to +25, +26 to +45 decibels. All bases on zero db. At 1.73 volts on 500 ohm line. Pilot light indicates when unit is "on." Complete with D.C. V.T.V.M. probe and cable plus pair of standard test leads. Housed in a rugged grey high-impact case, with color matched etched aluminum panel and portable handle. Size: 5 1/2 x 7 1/2". Net 29.35

TE-500 Shpg. wt., 6 lbs.

NEW! Lafayette ELECTRONIC AUTO TESTER

COMPLETELY ASSEMBLED NOT A KIT! - A TRUE VTVM IGNITION ANALYZER

Compact Combination Automobile Test Instrument

CHECK ✓ Power ✓ Performance ✓ Economy



Reg. 39.95
SALE PRICE
34.95
Until Oct. 15, 1962
NO MONEY DOWN

- No Complex "Curves" • "Scope" Type Indications are converted into Direct Meter Readings • Check Your Car's Ignition System—Plugs, Coils, Condenser, Points, Wiring • Special Capacitive Clip Prevents Overloads and Shocks Even when Ignition System is Operating • Large, Easy-to-Read Dial Face • Operates from 12-Volt Car Battery

The new Lafayette Electronic Auto Analyzer will pinpoint auto ignition trouble quickly and accurately without confusing curves or complicated interpretations. As accurate as an expensive oscilloscope, the TE-40 incorporates a highly sensitive VTVM to locate troubles in coils, plugs, points, condensers, etc. without any circuit drain. The large, easy-to-read multi-colored meter eliminates complicated curves and scope interpretations—you get direct, simple readings.

Featured is a variable resistance loading circuit which simulates a heavy engine load such as driving at high speed or hill climbing—you test under conditions simulating actual driving. The TE-40 also has a special capacitance clip which enables you to make high voltage measurements, including surges, without danger of shock. Operates on 12-volt auto batteries. Complete, ready-to-use with detailed operating instructions. Shpg. wt. 16 lbs.
9TE-40 Net 34.95

LAFAYETTE ILLUMINATED AMMETER & OIL PRESSURE GAUGES

4.99



- Complete with Cable and All Standard Fittings

DON'T trust flashing indicator lights—a burned out bulb can ruin your motor or strand you with a dead battery. All cars with warning lights for oil and battery need these precision gauges. Lights only indicate when oil pressure falls below 15 lbs. or whether or not the generator is working. These Lafayette gauges will replace your panel lights (or if you wish to use both lights and gauges, buy the Tee fitting listed below). Keep a constant check on the condition and performance of your car's electrical and oil pressure systems. The ammeter calibrated in a 60-0-60 scale measures the actual rate of current flow... helps prevent generators from burning out and overcharging or discharging the battery. Exact oil pressure from 0 to 80 lbs. is indicated. Easily installs in any 6 or 12 volt car below the dash, without drilling or can be mounted right in the dash. Both meters are mounted in an attractive chrome panel. Easy to read meters feature 1 3/4" diam. black dial faces with calibrations in white. Size: 5 1/8" x 2 1/8" x 2 1/8" D. Supplied with 6 and 12 volt bulbs and wire, all necessary fittings plus full instructions.

AA-105 Imported. Shpg. wt., 1 1/2 lbs. Net 4.99
MS-912 Tee Fitting Net .49

PROFESSIONAL 3-AMP. BATTERY CHARGER

- For Both 6 and 12 Volt


8.95



A professional type 6 - 12 volt battery charger with automatic reset circuit breaker. Indicator light flashes on when circuit breaker trips. Front panel switch for change-over from 6 to 12 volts. Delivers a tapering charge starting at 3 amps for 6 or 12 volts. Noiseless, aircooled construction. Oversized components and vented case for troublefree operation. Runs cool even under constant use. 6 ft. charging cables with heavy duty, 25 amp battery clips. Measures 4x6x3 1/4". For 105-125 volt, 50-60 cycle A.C. Shpg. wt., 5 lbs. CV-51 Net 8.95

2-IN-1 BATTERY CHARGER


4.95



- Full 1 Amp Charge Rate on 6 or 12 Volt Batteries
- Automatic Taper Rate—Can't Overcharge
- Manual Reset Circuit Breaker

End dead battery trouble in your car, boat, truck or tractor. This powerhouse battery charger keeps all 6 and 12 volt batteries fully charged for peak performance even at 40° below freezing. Full 1 amp. "safe" charge rate prevents flacking and plate buckling—same method used by storage battery dealers. Easy to use—plug the line cord into any 110V outlet, connect the two terminals and forget it. Warning trouble light indicates incorrect terminal connection. Can't overcharge—automatically tapers off. Welded constructed steel. Shpg. wt., 3 1/2 lbs. Net 4.95

AUTOMOTIVE TESTING EQUIPMENT



(A) MOTOR ANALYZER

All the advantages of a well-equipped service shop in a light, hand-held package. Ideal for do-it-yourselfers, sports car Rallyers, etc. The Analyzer enables you to test ignition coil output, spark plugs, insulation breakdowns, locate poorly adjusted carburetor, sticky or burnt valves, weak valve springs, checks valve timing, choke, muffler, vacuum tank, manifold, fuel pump vacuum and pressure and vacuum operated equipment. 14Wx7 1/2"Hx3 1/2"D. Shpg. wt., 5 1/2 lbs. AA-49 Net 15.95

(B) REMOTE STARTER SWITCH

Eliminates the need of a second man when making compression, fuel pump, generator, starter, and electrical tests. Permits the mechanic to crank the engine from any position. Shpg. wt., 1/2 lb. AA-50 Net 2.59

(C) MOTOR GUIDE-VACUUM FUEL PUMP TESTER

Combination motor guide, vacuum and fuel pump tester. 4 color zones: Economy Driving, Fast Pick-up, Coasting and Idle. Promotes good driving habits and economical gas-mileage. Warns when tuneups are necessary. Shpg. wt., 12 oz. AA-51 Net 3.75

(D) COMPRESSION TESTER

Gives quick, accurate readings of compression pressure. Merely unscrew the spark plug, plug tester into spark plug hole and read pressure. 2 1/2" dial reads to 300 lbs. Stem is offset 15° for reaching back cylinders. Complete with instructions. Shpg. wt., 12 oz. AA-52 Net 3.75

(E) STANDARD TIMING LIGHT

Employs the stroboscopic principle of light synchronized with motion for adjustment and setting of ignition timing under actual operating conditions. Shpg. wt., 1 lb. AA-53 Net 3.25

(F) TACHOMETER

Here's the instrument for the most important check of an engine's performance—the RPM test. Tests 4, 6 and 8 cylinder engines with both 6 and 12 volt systems. Operated by two inexpensive penlight batteries which last about a year. Large dial reads 0-1000 and 0-5000 RPM. Shpg. wt., 2 1/2 lbs. AA-54 Net 28.50

CAM-DWELL INDICATOR



A high quality instrument for solving all CAM-DWELL problems. Checks the number of degrees a distributor can rotate while the breaker points remain closed. Too much rotation means points are set too close, too little means breaker points are not closed long enough for adequate build up of the magnetic field in primary coil, permitting arcing across points. Requires no electrical outlet. Distributor need not be removed. Compact, portable. Complete with case and includes chart showing specifications for all popular cars. AA-98 Shpg. wt., 2 lbs. Net 3.95

EMERGENCY BLINKER


- MAGNETIC BASE
- VISIBLE FOR 1000 FEET
- OPERATES ON 2 FLASHLIGHT BATTERIES

Every motorist needs it. Bulb flashes 60 times a minute. Stands by itself on road; has hanger or magnetic base which holds it firmly to any metal surface. Rugged plastic dome. 5 3/4" diam. x 3 3/4" high. Shpg. wt., 2 lbs. With spare, non-blinking bulb for steady light, less batteries. AA-99 Net 1.49
BA-157 #2 batteries (2 needed) ea. Net .13

MOTOROLA ALL-ELECTRONIC ALTERNATOR SYSTEM

30-Amp System **59.95**

45-Amp System **74.95**



- Always Charges Battery Even at "Idle" Speed
- All-Transistor Voltage Regulator and Advanced New 7-Diode Alternator
- Extends Battery Life
- Reduces Maintenance Cost Caused by Generator and Regulator Failures
- Fits 12-Volt Cars with Negative Ground

• GUARANTEED FOR 3 YEARS (OR 30,000 MILES)*

Tired of replacing expensive car batteries? Frustrated by stalling cars and costly towing? Now you can save time, money and trouble with Motorola's all-electronic alternator system. This is the low cost solution to the heavy demands made by your car on its electrical system... heaters, radios, defrosters, air conditioners, power seats and windows. The new Motorola alternator eliminates all the fuss and expense caused by chronic run-down battery due to generator and voltage regulator failures. Unlike D.C. generators, it supplies a charge at idle speeds and keeps the battery at a uniform high level of charge. The all-transistor voltage regulator has no contact points to stick or burn... nothing but trouble-free transistors and diodes that virtually never wear out. So reliable it's sealed for life and is not affected by shock, vibration, moisture or

dust. The alternator is 50% smaller than a generator and weighs 50% less. Guaranteed for 3 years or 30,000 miles. Motorola's advanced new alternator fits all domestic cars with 12-volt, negative ground electrical systems. Available in 2 sizes: 30-amp for autos and light trucks; 45-amp for police cars, taxis, and heavy duty use. The complete system includes: alternator (with standard-size pulley); all-transistor regulator (with all connecting wires); universal mounting bracket; instructions for installation in less than 1 hour. AA-109 30-Amp (shpg. wt., 1 1/2 lbs.) Net 59.95
AA-110 45-Amp (shpg. wt., 1 3/4 lbs.) Net 74.95
*Manufacturer's guarantee covers repair or replacement of parts within 3 years or 30,000 miles (whichever occurs first).



Lafayette
HOT CAR-GO
Starts Your Car INSTANTLY

OUR LOWEST PRICE EVER!

- Starts Wet or Cold Motors Instantly
- Saves Battery and Gasoline
- Installs Easily and Quickly
- 6 and 12 Volt Cars

2.95

Avoid excess wear and tear on your motor and battery—install Lafayette's Hot Car-Go. Provides 5 times the normal spark for fast starting in any weather, and automatically disconnects when engine is running. Will not damage plugs or distributor. Simple to install—instructions included. Shpg. wt., 1 lb. Imported MS-784 Net 2.95

NEW! DO-IT-YOURSELF PLATING KIT

Tune Up Your Chrome—Plate or Replate Most Metal Surfaces



- Fast-Easy-Inexpensive
- Non-Electric
- For Use in Home, Car, Boat, Office

3.98

• Combination of Cadmium, Nickel, Chromium
Now you can replate worn, rusted or pitted iron, steel, copper or brass—even metal parts that have never been plated before. Your finished plating is a combination of cadmium for rust proofing, nickel for protection and luster, chromium for hardness and brilliance. Ideal for car, plumbing fixtures, door hardware, and most any metal surface except aluminum. Kit consists of 4 oz. copper chelate, 4 oz. chrome chelate, 1/2 pint plating sealer, sponge, catalizer wool, 1" brush, sandpaper, steel wool, 4 oz. rust remover. Shpg. wt., 2 lbs. AA-106 Net 3.98

SUPER PLATING KIT

Similar to above but in larger quantities. 12 oz. copper chelate, 12 oz. chrome chelate, 12 oz. spray can of plating sealer (no brush needed), 12 oz. rust remover, sponges, catalizer wool, sandpaper, steel wool. Shpg. wt., 4 lbs. AA-107 Net 9.95

"RUSTY" RUST REMOVER

- Dissolves Rust from Iron and Steel
- Cleans Stains from Porcelain, Cement, Tile
- Frees Frozen Nuts and Bolts

A few drops of Rusty and rust dissolves without affecting the sound metal. No more heat or torches necessary; no more long waits. Use for car or home—anywhere there is rust, corrosion, stained porcelain and cement. Frees frozen nuts and bolts; loosens frozen pipe joints. Non-flammable; safe to use. Shpg. wt., 8 oz. AA-108 Net .86

TIMING & OCTANE SELECTOR

- Increases Gas Mileage & Horsepower
- Advances or Retards Spark As you Drive
- Spark Indicator Light Shows Engine Load
- Gives Longer Engine Life
- Premium Performance on Regular Gas

Recover the gas mileage and power your car is now wasting with this Timing and Octane Selector. Enables you to dial-in the most effective spark timing from the dash, as you drive. Harmful ping and spark knock are eliminated—you get premium performance from regular gas. Will not interfere with your distributor's advance mechanism. Mounts on your dash. Simple, do-it-yourself installation instructions—no tools needed. Shpg. wt., 1 1/4 lbs. AA-112 Net 4.54

YOUR ORDER IS SHIPPED AT THE CURRENT PRICE SO YOU BENEFIT FROM ANY PRICE REDUCTION

LAFAYETTE RADIO ELECTRONICS PAGE 49

MOTOROLA RADIOS for FOREIGN & DOMESTIC CARS

ALL NEW TRANSISTORIZED AUTO RADIOS for FOREIGN & DOMESTIC CARS

COMPLETE WITH FREE MOUNTING KIT

NEW! TRANSISTOR POWERED ALL AMERICAN AUTO RADIO WITH FREE ANTENNA



39⁹⁵
NO MONEY DOWN

5-TRANSISTOR MANUAL CAR RADIO

- In-dash or Under-dash Mounting** - A tremendous value in an all-transistor car radio. Hand-wired chassis with 5 transistors, 2 diodes, 1 thermistor. Built-in Golden-Voice hi-fi speaker. Set plays as soon as you turn it on—no warm-up time required. Custom fits most cars, sport cars, trucks and boats—in-dash or under-dash installation. Low battery drain. Features full variable tone control, cool chassis operation, band pass circuit, automatic gain control. For 12-volt cars, reverse polarity. Size: 6 1/2" x 2 1/2" x 7 1/4" D. Shpg. wt., 7 lbs. CR-128 Model 320T Net 39.95
- All-Transistor, Hand-Wired Chassis**



51⁹⁵
NO MONEY DOWN

6-TRANSISTOR MANUAL CAR RADIO

- Custom Fits "Difficult to Fit" Cars** - A flexible car radio with movable control shafts to accommodate the most difficult-to-fit cars. Push/Pull audio system gives smooth high-fidelity sound and delivers a full 12 watts of peak power output. Employs 6 transistors, 2 diodes and 1 thermistor in a hand-wired chassis. Low battery drain of only .5 amp. Features Golden-Voice hi-fi speaker, full variable tone control, automatic gain control. Plays as soon as you turn it on—no warm-up needed. 12-volt cars, negative ground. Size: 7 1/2" x 2 1/2" x 5" D. Shpg. wt., 7 lbs. CR-129 Model 2MT Net 51.95
- Push/Pull Audio System for Hi-Fi Sound**



54⁹⁵
NO MONEY DOWN

ALL-TRANSISTOR PUSHBUTTON CAR RADIO FOR FOREIGN CARS

- Pushbutton Convenience** - Simple, pushbutton convenience with all-transistor power and dependability. Hand-wired, transistor chassis means instant play without warm-up, cool chassis operation, and 64% less battery drain, only .7 amp. Full variable tone control, automatic gain control, band pass circuit, plus the exclusive Golden-Voice hi-fi speaker. For 12-volt cars, reversible polarity. Size: 6 7/8" x 2 1/2" x 7 1/4" D. Shpg. wt., 8 lbs. CR-130 Model 520T Net 54.95
- 5 Transistors, 2 Diodes, 1 Thermistor**



59⁹⁵
NO MONEY DOWN

6-TRANSISTOR PUSHBUTTON CAR RADIO For Domestic Cars

- 6 Transistors, 2 Diodes, 1 Thermistor** - A new, all-transistor car radio designed to custom fit most domestic cars on the road. The push/pull audio principle results in smooth, uninterrupted sound. Delivers 12 watts of peak power output. Features 30% cooler chassis operation; 64% less battery drain; instant play, no warm-up; full variable tone control; automatic gain control. Exclusive Golden Voice 6x9" speaker. Size: 9 1/4" x 3 1/2" x 7" D. For 12 volt cars, negative ground. CR-131 Model 12AT-2 (6x9 speaker) Net 59.95 CR-132 Model 12ATIS (5x7 speaker) Net 59.95
- Push-Pull Audio System for Hi-Fi Sound**



39⁹⁵
NO MONEY DOWN

MODEL 406 — TUBE & TRANSISTOR AUTO RADIO For 6-Volt System

Compact radio set that is ideal for custom underdash or in-dash installation. "Golden Transistor" circuit employs 2 transistors and 4 tubes. "Volumatic" constant level output eliminates fading and distortion. Antenna band pass filter. Reverse polarity. Size: 6 1/2" x 2 1/2" x 7 1/4" D. Shpg. wt., 6 lbs. CR-28 Model 406 Net 39.95

Full 1-year warranty on all parts and labor. Manufacturer's guarantee covers free exchange or repair of any component power defective in normal use. Removal and re-installation labor extra. Arranged through your local service dealer.

Consult This Chart To Determine Which Sets Fit American Cars, Sports Cars and Foreign Cars.

The below chart shows the make and model of cars which use the above Motorola radios which can be used with the different types of automobiles. Use this Car Radios. The "Use-Set" column indicates the stock number of the radio or stock number when ordering. Also list make, model and year of your car.

MAKE, MODEL AND YEAR	USE SET	MAKE, MODEL AND YEAR	USE SET	MAKE, MODEL AND YEAR	USE SET
Austin Healy '57-'63	CR-128M	Falcon '60-'62	CR-128M, CR-129M, CR-132M	Plymouth '56-'62	CR-128M, CR-129M, CR-131M
Borgward '57-'63	CR-28M	Fiat 600-1100 '57-'63	CR-128M	Rambler '59-'62	CR-128M, CR-129M
Buick '54-'62	CR-128M, CR-129M	Ford '57-'62	CR-128M, CR-131M	Rambler-American '60-'62	CR-128M, CR-129M, CR-132M
Buick Special (Compact) '61-'62	CR-128M, CR-129M, CR-131M	Hillman Minx '57-'62	CR-128M	Renault Dauphine '60-'62	CR-28M
Chevrolet '58-'60	CR-128M, CR-129M	Karmann-Ghia (V.W.) '58-'63	CR-28M	Renault Dauphine 12 V. '58-'63	CR-128M
Chevrolet '61-'62	CR-28M	Mercedes Benz '58-'63	CR-128M, CR-130M	Studebaker Lark '59-'62	CR-128M, CR-129M, CR-131M
Citroen ID-19, DS-19 6 V.	CR-128M	M.G. Magnette, MGA '57-'63	CR-128M, CR-130M	Sunbeam Rapier '57-'63	CR-28M
Citroen '58-'63 12 V.	CR-128M, CR-129M, CR-132M	Opel '57-'63	CR-128M, CR-130M	Taurus '58-'63	CR-28M
Comet '60-'62	CR-128M, CR-129M	Oldsmobile F-85 '61-'62	CR-128M, CR-129M, CR-131M	Triumph TR-3 '58-'63	CR-128M, CR-130M
Corvair '60-'62	CR-129M, CR-131M	Peugeot '58-'63	CR-28M	Valiant '60-'62	CR-128M, CR-132M
Dodge Dart '57-'62	CR-128M, CR-129M, CR-132M	Pontiac Tempest '61-'62	CR-128M, CR-130M	Volkswagen '52-'63	CR-28M
Dodge Lancer '61-'62	CR-128M, CR-130M	Porsche '57-'63	CR-128M, CR-129M, CR-131M	Volkswagen Bus '52-'63	CR-28M
English Ford '57-'63	CR-128, CR-130		CR-28M	Volvo PV-44, PV-544 '57-'63	CR-28M
				Volvo 12 V.	CR-128M

REAR SEAT AUTO SPEAKER KITS



AS LOW AS **305**

6" x 9" KIT WITH CHROME OR GOLD GRILLE
Complete kit for adding second speaker in rear of your car. Includes a 6x9" PM speaker, 3-position selector switch for cutting in front, rear, or both speakers; dial plate with mounting bracket, knob, and hardware; chrome or gold grille; wire, and wiring instructions. Simple to install. Shpg. wt., 5 lbs.
SK-94 Speaker kit chrome grille Net 3.45
SK-196 With gold grille Net 3.45

DELUXE 6" x 9" KIT with 2.15 oz. ALNICO V MAGNET
Same as above but with deluxe speaker with extra-heavy Alnico V magnet (2.15 oz.). This is same speaker used in kits selling at twice the price. Shpg. wt., 5 lbs.
SK-37 Speaker kit chrome grille Net 4.65
SK-197 With gold grille Net 4.65

5" x 7" KIT
Same as SK-94 but with 5x7" speaker and grille. 5 lbs.
SK-42 Chrome grille Net 3.05
SK-198 With gold grille Net 3.05

FADER TYPE AUTO KITS

Rear-seat speaker kits identical to those above except with fader-type controls to cut either speaker in or out or balance both. Shpg. wt., 5 lbs.
SK-55 5x7" kit. Same as SK-42 but with fader control. Chrome grille Net 3.29
SK-195 With gold grille Net 3.29
SK-95 6x9" kit. Same as SK-94 but with fader control. Chrome grille Net 3.69
SK-200 With gold grille Net 3.69

DELUXE 6" x 9" FADER KIT

Deluxe kit with extra-heavy-magnet 6x9" speaker, plus fader control. Shpg. wt., 5 lbs.
SK-56 6x9" kit. Same as SK-37 but with fader. Chrome grille Net 4.89
SK-201 With gold grille Net 4.89

NEW SPEAKER KITS FOR TRANSISTORIZED AUTO RADIOS

• Features Multi-impedance Match For 40, 20, 8 ohms or less
• New Slim Line Construction

Lafayette offers a complete line of speaker kits for the new all transistorized automobile radios using speakers of 20 ohms and 40 ohms. Slim line in construction these speakers feature a multi-impedance match for 40, 20, 8 ohms or less.

SPEAKER KITS
Complete 6 x 9" rear seat kit featuring new multi-impedance Slim line 6 x 9" speaker; chrome grill, 100 ohm Fader control, 40 ohm adapter for Motorola Radios, and a 20 ohm adaptor for Automatic radios. Shpg. wt., 6 lbs.
SK-241 Net 6.25
SK-242 Same as above, with gold grill Net 5.95
SK-243 Same as SK-241, but with 5 x 7" speaker—Chrome Grill Net 6.25
SK-244 Same as SK-242, but with 5 x 7" speaker—gold grill Net 5.95
Special Custom Rear Speaker Kit with 6" Slim line multi-impedance speaker, 100 ohms Fader control, 40 ohm adapter and 20 ohm adapter for the following cars: Impala, Bonneville, Invicta, and 2 door Custom Autos equipped with 40 ohm Motorola or 20 ohm Automatic radios—less grill 5 lbs. SK-245 Net 5.70
Station Wagon Rear Speaker Kit—includes self-contained multi-impedance 4 x 6" speaker, 40 ohm and 20 ohm adapters. Shpg. wt., 6 lbs. SK-246 Net 8.75

MULTI IMPEDANCE SPEAKERS IN NEW SLIMLINE CONSTRUCTION

Stock No.	Size	Shpg. wt.	Net
SK-247	6x9" with jumper wires	2 1/2 lbs.	3.25
SK-250	6" Round with jumper wires	2 lbs.	2.75
SK-259	4x6" with jumper wires	1 1/2 lbs.	2.48

DUAL HI-FI REAR-SEAT SPEAKER KIT*



949

• **Woofer-Tweeter-Crossover**
"Universal" speaker kit includes two Alnico V units—a 5 1/2" woofer and 3" tweeter with electronic crossover network; chrome grille and baffle which fits regular 6x9" cut-out; plus pre-wired, pre-soldered, 3-position switch.
SK-148 Shpg. wt., 4 lbs. Net 8.48

3-WAY PUSH-BUTTON SWITCH



.89

Lots .75 of 3 ea.

Just push a button to select either front speaker alone, rear speaker alone or both together. Comes completely assembled on black & silver metal plate with cable, hardware and simple instructions. Imported. Shpg. wt., 1/2 lb.
MS-890 Lots of 3, ea. .75 singly, each .89

MAGNETIC UTILITY LIGHT



High intensity trouble lamp for car or boat. Powerful magnetic base holds easily to metal surface. Double ball joint for use at every possible angle. Folds down to an "egg" sized unit. Long life, horizontal filament lamp, gives more light than conventional types. Heavy chrome plate over brass plated steel for exceptional corrosion resistance. 15 ft. cord gives plenty of leeway in positioning. Includes red filter for use as a warning light, lighter plug and vinyl case for storage. For 12V. DC only. Shpg. wt., 1 lb. F-631 Net 4.95
Spare Bulb for F-631 F-632 Shpg. wt., 2 oz. Net .28

NYLON "BULLDOG" 10 FT. TOW CABLE



375

The perfect cable for towing ANYTHING UP TO 5,000 LBS. Constructed of heavy-duty, 1" wide, DuPont Nylon webbing that stretches 25% to take up shocks for smooth, safe towing. Oil, grease and water resistant too! Dual, self-aligning clip attaches to any bumper. Shpg. wt., 3 lbs. AA-57 Net 3.75



ONLY **29⁹⁵**
NO MONEY DOWN

Transistor powered car radio with 2 transistors and 3 tubes for trim under-dash mounting. Plays as soon as you turn it on—no warm-up required. 5" speaker has 1 oz. magnet. Separate tone control; extra speaker jack. For 12-volt, reverse polarity cars. Size: 6 7/8" x 3 1/2" x 7" D. Top cowl mount. 3-section antenna measures 23" closed, 58" open. Total shpg. wt., 5 1/2 lbs. CR-134M Radio plus Antenna Net 29.95

AUTOMOBILE ANTI-THEFT PROTECTOR



Protects Your Car from Being Stolen

698

- Protects Your Car by Sounding An Alarm
- Prevents Ignition Switch from being Jumped
- Prevents Car's Lights and Accessories from Working
- Easy to Install

Here is the ideal auto protection for salesmen, servicemen, delivery vans, all motorists. Not only will it prevent your parked car from being stolen, but will also safeguard valuables in the trunk as well as parts under the hood. Sounds an alarm in case of attempted theft and completely immobilizes the car—ignition can't be jumped, lights and accessories will not operate. Instructions included for easy installation. AA-111 Shpg. wt., 1 1/2 lbs. Net 6.98

NEW! RADIO TRANSVERTER

Converts Transistor Radio to Car Radio




Only **147**

- For all 9-Volt Transistor Radios
- Plugs into Cigarette Lighter
- Fits all Cars

Now you can avoid the expense of buying a car radio with this new radio transverter. Simple to operate—remove 9-volt battery from your transistor radio, connect contacts from transverter to battery contacts in the radio, and then plug into the cigarette lighter. Fits all cars. Shpg. wt., 5 ozs. AA-102 For 12-volt Cars Net 1.47
AA-103 For 6-volt Cars Net 1.47

CARDIO-MASTER



- Convert your Transistor Radio into a Car Radio
- For all Makes of Cars — Cabs — Trucks

298

Cardio master is a magnetic device designed to hold a portable transistor radio in the area of a car's windshield to make it operate as an auto radio. Car's owner can remove a radio from the Cardio master for use as portable or to avoid theft while the car is parked. Fits any "pocket" transistor radio. Will not come loose in the bumpiest roads. Includes magnetic base, brackets, hardware, adjustable band and complete, illustrated instructions. AA-45 Shpg. wt., 2 lbs. Net 2.98

LAFAYETTE REAR SEAT SPEAKER KIT



275

- Fits Compacts, Station Wagons • Fits Foreign Cars, Sports Cars • Pre-wired — Self Contained • 3-Position Switch

Here is just the right rear seat speaker for your car. Pre-assembled, self contained, pre-wired switch. Easy to install, it will fit any auto radio in any domestic or foreign car including station wagons and convertibles. Finished in a gleaming chrome shock resistant case, it can be hung up or clipped on almost anywhere. Includes all necessary wire, instructions and 3-position switch for front, rear or 2-speaker operation. Shpg. wt., 12 oz. SK-178 Net 2.75

LAFAYETTE'S SPECIAL AUTOMOTIVE ACCESSORIES

New! LAFAYETTE TRANSISTORIZED TACHOMETER

19⁹⁵

- Accurate 0-8,000 RPM Scale
- Adjustable Shift Point Indicator
- Economy Range-Finder
- Easy to Install



Here is the modern electronic guide to big gas savings, full power and longer engine life. The Lafayette Tach helps you shift right... tune right... drive right. Features an "Adjustable Speed Shift Indicator" that shows exact shift points for fastest acceleration, and "Economy Range-Finder" that indicates engine's safest,

most economical operating range. Handsome 3-color illuminated dial has accurate 0 to 8,000 RPM scale. Dependable transistor design; self-contained with chrome head. Easy 5-minute installation on any car. Shpg. wt., 1 lb.

Car Model	Year	Cylinders	No.	Car Model	Year	Cylinders	No.	Car Model	Year	Cylinders	No.
Borgward*	All	4	AA-116	Edsel	1958-60	8	AA-114	Plymouth	1956-61	8	AA-114
Buick	1953-61	8	AA-114	Ford	1958-60	6	AA-115	Ply. Valiant	1956-61	6	AA-115
Buick Special	1961	8	AA-114	Ford	1956-61	8	AA-114	Pontiac	1955-61	8	AA-114
Cadillac	1953-61	8	AA-114	Ford Falcon	1960-61	6	AA-115	Pontiac Tempest	1961	8	AA-114
Chevrolet	1955-61	8	AA-114	Hudson	1956	8	AA-114	Rambler	1956-61	8	AA-114
Corvair	1960-61	6	AA-115	Lincoln	1956-61	8	AA-115	Renault*	1956-61	6	AA-116
Chrysler	1956-61	6	AA-115	Lincoln	1955-61	8	AA-114	Studebaker	1956-61	8	AA-114
Chrysler	1956-61	8	AA-114	Mercury	1956-61	8	AA-114	Volvo*	1956-61	6	AA-115
Crown Imp; 300	1956-61	8	AA-114	Mercury	1956-61	6	AA-115	V.W.*	All	4	AA-116
DeSoto	1956-61	8	AA-114	Mercury Comet	1960-61	6	AA-115	Willys*	All	4	AA-116
Dodge	1956-61	6	AA-115	Nash	1956	8	AA-114	AA-114	1940-59	4	AA-116
Dodge	1956-61	8	AA-115	Oldsmobile	1956-61	8	AA-114	AA-114	For 8-Cylinder Cars	Net	19.95
Dodge Dart	1961	8	AA-114	Olds. F-85	1961	8	AA-114	AA-115	For 6-Cylinder Cars	Net	19.95
Dodge Lancer	1961	6	AA-115	Packard	1956	8	AA-114	AA-116	For 4-Cylinder Cars	Net	19.95

*6-Volt Negative Ground



NEW! ELECTRONIC MPG COMPUTER

Works Continuously—as you drive!

- Calculates Relative MILES PER GALLON!
- Measures Engine SPEED!
- Computes Relative GAS CONSUMPTION!
- Easily Installed—NO Gas Line Connections!

24⁵⁰

An all-electronic instrument engineered to be your guide to fuel economy. Measures relative miles per gallon at all speeds. Gives a visual indication of optimum operating efficiency. You can control your car to suit conditions of terrain, weather, traffic flow. Guides you to the economy of smooth acceleration, proper cruising speed, the best gas for your car. Pays for itself in gas savings. Easy-to-read, illuminated indicator mounts above dash. Simple installation—no gas line connection—only three wires to connect to easily reached points. Requires no automotive knowledge for installation. Complete unit includes illuminated indicator head, transducer, cable and instruction and use manual. For 12 volt, negative ground systems. Shpg. wt., 3 lbs. AA-144

Net 24.50

RADAR ALERT warns of radar traffic zones

- Dual Band Circuit Detects Radar Beams on Both "S" and "X" Frequencies
- Gives Advance Warning Within 1/2 Mile Range
- Miniature and Completely Transistorized
- No Wires or Antennas Needed



Radar Alert, the miniature electronic detector, warns you of radar traffic zones in advance—up to 1/2 mile away. The Dual-Band circuit detects all commonly used police radar speed meters and traffic control devices to promote safer driving. Miniaturized and completely transistorized. Radar Alert does not require wires or antennas. Constructed of top quality components; printed wiring; 8 transistors; two 1,000 hour mercury cell, self-testing batteries (equivalent to 35,000 miles of driving at 35 M.P.H.). Magnesium case eliminates radio, TV and other interference. Weighs only 13 ozs., measures 3 3/4" x 2 1/4" x 3 1/4" D; clips to sunvisor. Complete with batteries, sunvisor clip. Instructions included. AA-104 Shp. wt., 1 1/2 lbs.

34⁹⁵


NO MONEY DOWN

Net 34.95

DELSWIFT AUTO MIRROR-AERIAL

A Handsome Side-View Mirror PLUS A Top-Performing Aerial

5⁹⁷



- Maximum Signal Strength Without Adjustment
- Anti-Glare Mirror
- Eliminates Broken and Stolen Car Antennas

A revolutionary mirror-aerial that combines two jobs into one. Chrome-plated for lifetime luster. No more bent, broken or stolen antennas. Perfect radio reception everywhere, without adjustment. Fully adjustable, flat anti-glare mirror gives wide-angle rear vision. Easy to fit to any car. Complete instructions and installation template included. Shpg. wt., 2 1/2 lbs. AA-119

Net 5.97

MATCHING MIRROR. Same quality and same base design. Mounts easily and quickly on opposite fender for greater safety. Shpg. wt., 2 lbs. AA-120

Net 2.37

AUTO SAFETY KIT

- Can of Instant Flat Tire Sealant
- Road Flare Kit
- Anti-Fog Cloth
- Reader's Digest First Aid Handbook

2⁹⁹



A must for every auto. Anti-fog Cloth is chemically treated to keep glass free of steam, fog and mist. Instant Seal seals and inflates flats—tube and tubeless tires—without jack or tools. Road Flare Kit has 2 1-hour flares and extinguisher for road emergency safety. Reader's Digest First Aid Handbook tells you what to do, and not to do, before medical help arrives—can be the difference between life and death. Shpg. wt., 3 lbs. AA-117

Net 2.99

AUTO ROAD FLARE KIT

- Gives Instant Warning
- Windproof and Rainproof



Sets up quick-as-a-wink to give instant warning during road emergencies. Unaffected by wind or rain. Two 1-hour flares can be snuffed out and used again—reusable up to 1 hour each. Kit also includes 1 flare extinguisher. May also be used for emergency cooking or light. Shpg. wt., 10 ozs. AA-118

Net .79

UNBREAKABLE PLASTIC "JERRY CAN"

- For Gas, Water, Juice, Oil—Car, Boat, Barbecue, Lawn Mower
- Will Not Rust, Corrode, Break or Shatter
- Reversible, Self-storage Spout



1¹⁰

Lightweight, unbreakable plastic can ideal for carrying any liquid, for any use. Improved spout for easy pouring, reverses for self storage. Air vent for free pouring. Chemically inert, not affected by oil, acid, etc. Won't dent or break. Built-in carrying handle. 1-gallon size fits in refrigerator.

AA-121 One-Gal. Size; Shpg. wt., 1 1/2 lbs. Net 1.10
AA-122 Three-Gal. Size; Shpg. wt., 2 lbs. Net 2.15

AUTOMATIC SIPHON

- Outboards • Generators
- Autos • Power Mowers

1³⁹

Automatic, safe, simple pump for transfer of gasoline or any liquid. Pump-type siphon works without putting tube to mouth. Just squeeze the bulb to start the flow. Transparent inserts permit view of liquid flowing. Use for any gas engine equipment. Handy in camp for plumbers chemical plants industrials. Shpg. wt., 8 oz. HD-725

Net 1.39

PRIMETTA "FOGGLES"



FOR SAFER DRIVING: • AT NIGHT • IN SNOW • IN FOG • IN RAIN
A Zeiss Formulation Newly Developed Insures True Color Contrast

Night driving is safer and easier with Primetta Radar Night Glasses. Scientifically designed to protect the eye from the glare of headlights, street lights, etc. without materially reducing vision. Ideal while driving at night in the rain, fog and snow. The filter lens exclude all ultra violet rays. Designed for 20-20 vision. With heavy, suede-lined leather case. Shpg. wt., 6 oz. AA-113

Net 2.69

Clip on "Foggles" with case, for use over existing glasses. AA-123

Net 1.83

TWINTUNE EXHAUST BOOSTER

MORE POWER BETTER GAS MILEAGE



5⁹⁷

- Scientifically Tested and Proven
- Increases Engine and Muffler Life

Get greater economy, efficiency and performance from your car with this Twintune Exhaust Booster. Engineered to let your engine breathe better and disperse exhaust gases quickly to increase performance, acceleration and fuel economy. Adds life to your engine and muffler. Acclaimed by motor magazines, automotive experts and racing drivers. Fits easily on your present tailpipe and can be transferred to another car with the same size tailpipe. Shpg. wt., 3 1/2 lbs.

Stock No.	Tailpipe O.D.	Net each
AA-124	1 1/8" to 1 1/4"	5.97
AA-125	1 3/8" to 1 1/2"	
AA-126	1 1/2" to 1 3/4"	
AA-127	1 7/8" to 2"	



SAMPSON DE LUXE SHOCK SPRINGS

6⁹⁵ pair

- Custom Engineered for Ride Control

Eliminate drag, sag and car bottoming with these shock springs—get more road clearance EVEN WITH OVERLOADS. Can be installed on your present shock absorber—no replacement needed. Provides a level, cushioned ride, stabilizes car for easier steering and greater safety. Fits rear of cars listed below. Shpg. wt., 7 lbs.

Car	Year	Car	Year
BUICK	1956-60	MERCURY	1949-60
CADILLAC	1950-60	(Except '55 and '56 Series and Park Lane)	
CHEVROLET	1949-60	METROPOLITAN	1954-60
DART	1960	OLDSMOBILE	1951-57
DeSOTO	1938-60	PACKARD	1940-56
DODGE	1939-60	(Except '55 Series 60-80-88 and '56 Series 40-60-80-88)	
FALCON	1960	PLYMOUTH	1939-60
FORD	1947-60	PONTIAC	1937-60
(Except Thunderbird)		RAMBLER	Late 1952-60
HUDSON	1940-54	STUDEBAKER	1950-60
IMPERIAL	1955-60	VALIANT	1960
KAISER, HENRY J.	1947-54	WILLYS	1941-60
LINCOLN	1949-51		
	1956-58		

Net pair 6.95

SAMPSON JR. LOAD-HELPER SPRINGS

- Increases Load Capacity 750-1000 lbs.
- Assembled—Easy-to-Install in Only 15 Minutes
- Heavy-Duty Base—Special Tempered Steel Cord
- Fits Most Cars 1940-59 with Elliptical Springs

AA-88 Shpg. wt., 7 lbs. Net pair 5.85



DISKOMATIC 100% AUTOMATIC SPARK PLUGS

100% AUTOMATIC SPARK PLUGS

- Precision made replacement for all ordinary SPARK PLUGS
- Reacts AUTOMATICALLY to all engine temperature changes
- Up to 40% greater voltage & increased power
- A "must" for foreign and compact cars

Stock No.	Type	Description	Net
AA-132	9C	Set of 4	4.60
AA-92	9C	Set of 6	6.90
AA-93	9C	Set of 8	9.20
AA-94	22C	Set of 6	6.90
AA-95	22C	Set of 8	9.20
AA-96	45C	Set of 6	5.90
AA-97	45C	Set of 8	9.20

Use This Chart To Select Proper Type for Your Car

MAKE	YEAR	TYPE	MAKE	YEAR	TYPE	MAKE	YEAR	TYPE
Buick	53-61	9C	Chrysler	54-58 N. York and Imp V8	22C	Mercury	55-61	45C
Cadillac	53-61	9C				Olds.	50-61	9C
Chevrolet	58-61 "W" Ser V8	22C	Chrysler	59-61	9C	Opel	All	9C
			Corvette	All	9C	Plymouth	46-61	9C
			Dodge	50-61	9C	Plym, 6 Cyl.	60-61	22C
			Ford	46-54	9C	Pontiac	50-61	9C
			Ford	55-61	45C	Rambler	All	9C
			Mercury	46-54	9C	Renault	All	9C
						Volvo	All With 14mm Heads	9C



SPARK PLUG WRENCH AND GAP GAUGE SET
For removal of most spark plugs and adjustment of spark gap. Gauge provides 6 different gaps. With wrench handle. Shpg. wt., 1 lb. HD-898

Net .77

NON-THERMO BATTERY HYDROMETER



1²⁹

Perfect for testing small batteries and batteries mounted in close quarters. Three-color float scale clearly marked "Poor," "Fair," "Good." Soft rubber tip will not damage battery plates. Float calibration: 1.100-1.300 in .05 subdivisions. AA-140

Net 1.29

Amazing New CHEMTRON CAR SHAMPOO



Contains Carnauba Wax

Non-Streak—No Wiping Needed—you'll be amazed with the results of this new wash and wax car shampoo. Removes grease, road film, insect stains, etc. Special formula contains Carnauba-Wax. Provides your car with an amazing show-room finish. Contains 16 ozs. Shpg. wt., 1 1/2 lbs. AA-133

Net .88

IGNITION CABLE SET



- Easier, Quicker, Surer Starts in All Weather
- Seals Out Dirt, Dampness, Rain, Snow

2⁷⁹

Eliminate car starting problems in any weather. Ideal for marine use too. Keeps the moisture out, the spark in. 8-cylinder set consists of 27 1/2-ft. ignition wire, 8 angle spark plug terminals, 8 straight spark plug terminals, 10 distributor wire terminals, 8 spark plug protectors (plastic drycaps), 9 distributor nipples, 1 ignition coil nipple (plastic hydra-caps). Shpg. wt., 2 lbs. AA-130

Net 2.79

4 & 5-CYLINDER SET. As above but with 20-ft. ignition wire; 8 distributor wire terminals; 7 distributor nipples; 6 each angle spark plug terminals, straight spark plug terminals, spark plug protectors; 1 ignition coil nipple. AA-131

Net 2.15

MOTOR TUNE-UP

Lubricates, cleans and protects engine parts. In oil: removes and prevents carbon formation, increases power and gas economy, eases starting, desludges motor. In gas: frees and cleans sticky valves, provides upper cylinder lubrication. 1-pint size. AA-129 Shpg. wt., 1 lb. Net ea., .79; 2-for 1.28



CONCENTRATED MOTOR OIL ADDITIVE

Reduces wear in valve and valve lifters; quiets hydraulic valve lifters. Neutralizes corroding acids, improves lubrication, performs with any motor oil. Recommended for all cars and trucks in normal or heavy duty use. Shpg. wt., 1 lb. AA-128



Net ea., .99; 2-for 1.66

AUTO BUTLER—SWING-AWAY LITTER CONTAINER



- Fits Every Car
- Swings Away Out of Sight
- Removable Washable Plastic Container


AA-91 Shpg. wt., 12 ozs.

Net .89

LAFAYETTE HAS MORE VALUES FOR EVERYONE

NEW LAFAYETTE PHOTO-ELECTRONIC RELAY SYSTEM

Includes Photo Cell Receiver Plus Electronically Operated Relay Plus Exciter Lamp
Efficient 2-Unit, 3-Element Design



- Complete — Ready to Operate — NOT A KIT!
- Operates Bells, Buzzers and Counters
- The Perfect "Guard for Homes, Stores and Industry"
- Removable Infra-Red Filter For "Invisible-Light" Operation

1895
Per Set



The Lafayette Photo-Electronic Relay is your key to an inexpensive indoor warning or counting system. Consisting of a rugged exciter and relay unit and operating on 110-120V AC, it can be connected to signal persons entering a room, counting people or merchandise or function as an effective alarm system to warn of intruders. Effective up to 23 feet (without filter, 15 to 18 feet with filter), relay unit has a convenient variable sensitivity control and switch for intermittent alarm operation. Exciter has removable infrared filter. Mounts easily across area to be supervised. Metal case. Size: 4 1/4 x 3 3/4 x 4 1/2" D. Imported
PC-40 Shpg. wt., 6 lbs. Net 18.95

ACCESSORIES FOR ABOVE

EL-85 Electric Bell, 110V AC. Shpg. wt., 2 oz.	Net 1.49
EL-86 Electric Buzzer, 110V AC. Shpg. wt., 10 oz.	Net 1.29
F-553 6-Digit Electric Counter. Shpg. wt., 1 1/2 lbs.	Net 9.95

BENDIX RADIATION MEASUREMENT SET

Certified by Bendix to Meet or Exceed Office of Civil Defense Mobilization Specifications

- Simple To Use • Direct Reading • Pocket Size
- Rugged—Reliable—Portable

1995 Each **1795** Lots of 3



Set Includes:

Bendix CD V-736 Ratemeter (0-120 r/hr)—Indicates precisely how much radiation is present at a given moment
Bendix CD V-746 Dosimeter (0-600 r/hr)—Records total radiation exposure
Bendix VD V-756 Charger—Charges and retests the Ratemeter and Dosimeter to zero

The Bendix Radiation Measurement Set is extremely simple to use. To read the calibrated scales just hold them up to a light source. The Charger is used to reset the hairline indicators to zero before new readings are taken. The Ratemeter measures the amount of radiation at a given moment. There are two scales: one calibrated from 0-120 r/hr for reading one minute after exposure; the second calibrated from 0-12 r/hr

for reading 10 minutes after exposure should the first reading be below 10 r/hr. The Ratemeter may also be used in industry for determining protection in any isotope program. The Dosimeter records total radiation exposure and is calibrated from 0-600 roentgens.
TE-666 Complete Set. Shpg. wt., 5 lbs. Net 19.95
TE-668 Pocket Dosimeter. Shpg. wt., 1 lb. Net 11.25
TE-669 Pocket Ratemeter. Shpg. wt., 1 lb. Net 11.25

BAR CARRIER



370

BAR CARRIER—A quality product at a big saving! Rigid 1-piece construction with attractive, baked-on enamel finish. Suction cups assure positive grip. Completely assembled. 42" long. Shpg. wt., 5 lbs.
ML-213W Net 3.70

NEW! "THE BIG EAR"



- Powerful Transistorized Listening Device
- Big 18" Reflector Disk Concentrates Sound Waves into Transistor Unit and Amplifies Them Loud and Clear


1295



Powerful new transistorized listening device. Not just a toy—works on the same principle as the fabulous Missile Tracking Antennas. Pick up sounds too distant for you to hear. Make your own wildlife recordings or carry on long range 2-way communications (using a "Bull Horn"). Ideal for experimenters, etc. Complete with sturdy tripod and stethoscope-type earphones. Uses one 9V Battery (not supplied). Shpg. wt., 5 lbs.
AP-96 Net 12.95
BA-2 9V Battery for above Net .21

TRANSISTORIZED PORTABLE BIKE RADIO

4 Transistor Radio Plus Horn Plus Light In One Streamlined Unit



- Built-In Speaker
- Telescoping Antenna
- Sturdy Clip-on Mount

CLOSEOUT PRICE **1295**

A sensitive 4 transistor radio, powerful horn plus a light, all in one streamlined unit. The perfect accessory for that new bike or for that matter your Golf-Cart, Baby Carriage or Boat. A sturdy handle bar clip-fitting allows you to attach this unit virtually anywhere. Radio covers full AM band from 530 to 1605 KC and is equipped with volume control, station selector and built-in speaker and earphone jack. In addition a detachable telescoping antenna is provided. Horn is activated by a simple to use push-button, while an On-Off slide switch controls light. Supplied with earphone for private listening plus 9V transistor battery for radio and standard D cell for horn and light.
FS-122L Shpg. wt., 3 lbs. Net 12.95

NEW LAFAYETTE - HAMILTON Illuminated Electronic Auto Clock




ONLY **995**

- Use any Voltage From 4 to 16 VDC!
- Swivel-Lock Mount — any Position!
- Precision Time Keeper — Accurate — Dependable
- Runs Continuously — NO Winding, NO Resetting

"Custom" designed, exceptionally handsome electric clock for auto, aircraft or marine use. High-quality Hamilton movement assures accuracy and dependability. Electronic movement requires no resetting in normal use. Runs continuously but draws so little current it can not run your battery down. Swivel-lock ball and socket mounting permits placing most anywhere on or above dash. Simple, one wire connection. Operates on any voltage from 4VDC to 16VDC. Hands set from front. Sleek, modern face—sweep second hand. Vinyl case cover to match your car's decor. Shpg. wt., 2 1/2 lbs.
AA-141 Red Vinyl Cover 9.95
AA-142 Beige Vinyl Cover 9.95
AA-143 Black Vinyl Cover 9.95

NEW HIGH SPEED 3500 RPM MOTOR

- Dual Shaft • Oilite Bearings



ONLY **169**

Ultra-quiet, durable high speed AC motor for driving fans, pumps, etc.—hundreds of applications. Features twin motor cooling fans for continuous operation; dual shaft, 3/8" diameter, 3/4" long each side; oilite bearings give long life lubrication; 12" color coded trimmed leads. For 115 volts 60 cycle AC. Size: 2 3/4 x 2 1/4 x 2 1/4" H. Shpg. wt., 2 lbs.
SP-263 Net 1.69

NEW! INSTANT LETTERING



- Instant Dry Transfer
- Meticulous Lettering
- No Equipment Needed

As low as **250**

Quick, simple pressure transfer that leaves no trace of adhesive to sully artwork. Works on wood, paper, card, glass, metal or any other smooth surface. Sharply defined letters, words, and numerals. Package contains 24 sheets. 1 sheet of over 600 numerals and + or —; 1 sheet of prox 400 letters, both prox 1/4" high; and 22 sheets of most often used electronic words, with popular ones repeated. Shpg. wt., 6 oz.
P-478 per package Net 4.95
Individual sheets may be reordered in packages of 12 of any 1 sheet (not assorted). Specify sheet number when ordering.
P-479 Pkg. Net 2.50

"Liqua Gold"

Chemical Plating Solution

- No Electricity—No special equipment
- Plates by Ionic displacement
- Will not tarnish—needs no polishing

Gold plate practically any metal object. Not a paint—true gold plating by chemical solution. Uses no electricity—plates by ionic displacement—a tried and true method long used commercially. Plates all common metals—copper, brass, bronze, nickel, iron, steel, tin, pewter, cadmium solder, zinc, etc. Plate novelties—ornaments—ash trays—door knobs—jewelry—buttons—buckles. Plate electrical contacts to end corrosion for ever. Printed circuits—connectors—terminals—sockets—plugs—switches—relays. The plating deposit is 24K pure gold. Includes complete instructions. Will plate 300 sq. in. Shpg. wt., 4 ozs.
HD-686 Net 1.66
Enough to plate 600 sq. in. Shpg. wt., 8 ozs. Net 3.32
HD-687

1575



MINIATURE HI-INTENSITY LAMP

• Palm-Size • Brilliant Light—150 Candles at 12"
Never before such a big light in so small a space. Bulb has an intensity greater than 100 watts, yet is only 1/10 the size of equivalent lights. Base has an electrical outlet which may be used by other electrical apparatus when lamp is on or off. Cork insulated reflector swivels 160°. Arms are double 1/4" steel tubing with 3 friction plates; overall 15". Compact size is 10Lx2 1/2Wx4"H. Ideal for reading, hobbyists, doctors, designers, artists, etc.
FL-23 Shpg. wt., 4 lbs. Net 15.75

DRY CHEMICAL FIRE EXTINGUISHER



- The Most Efficient Fire Extinguisher Ever Made!
- 6 B:C—Highest U.L. Rating for ITS SIZE
- Exceeds I.C.C. & U.S. Coast Guard Requirements
- Safety Zone Pressure Gauge
- 12 Times as Effective as a CO₂ Extinguishers of Comparable Size

The most powerful, efficient fire extinguisher of its size. Dry chemical extinguisher utilizing a specially developed non-toxic, non-corrosive, dry chemical powder rated 6 B:C by U.L., extremely fast rate of damp in spraying chemical, non-clogging valve insures perfect closure without leaking. Safety Zone Pressure Gauge shows instantly whether extinguisher is ready for use. Forged brass valve body equipped with vehicle mounting bracket, locking clamp.
HD-987 Shpg. wt., 7 lbs. Net 11.33
DO-IT-YOURSELF RECHARGE KIT. Contains 234 lbs. of Dry-Kern-S dry chemical powder. Shpg. wt., 5 lbs. HD-988 Net 1.47

HANSEN BATTERY CELL TESTER



479

The Hansen Model 12 Tests battery cells under load simply, accurately! Special alloy shunt between adjustable legs places 200 amp load on battery during test. Eliminates guesswork of unloaded testing. 3-color dial reads bad, weak, and good battery condition. Rugged molded grip design fits all batteries. Indicates ability of battery to deliver power. Locates corroded cables, loose connections, etc.
AA-139 Shpg. wt., 1 1/2 lbs. Net 4.79


DESK LAMP

- Ideal Student or Utility Lamp
- Molded-in Pen and Pencil Holder
- Brass Finished Goose Neck
- Separate Stamp and Paper Clip Compartments



only **2.98**
An attractive desk lamp. Fully louvered to give the best light transmission. With molded-in pen and pencil holder. Separate stamp and paper clip compartment with a hinged lid. White louvre with gleaming black hood and base; brass finished goose neck. About 14" high. Uses standard incandescent lamp. Shpg. wt., 1 1/2 lbs.
FL-20 Less lamp Net 2.98

LAFAYETTE SPECIAL



AUTOMATIC TIMER MECHANISM THAT DOES EVERYTHING

ONLY **595**

- Turns Appliances On Or Off
- Never Needs To Be Reset
- Handles 1650 Watts
- Operates From 30 Minute To 23 Hr. Cycle

Makes practically everything electrical completely automatic. Will handle load up to 1650 watts. Turns radio on and off — does not have to be reset each night. Defrosts refrigerator — turns lights on and off — controls roaster, electric blanket, washing machine, coffee makers, vaporizers, etc. 30 min. minimum on time — 23 hours maximum. As easy to set as an electric clock. Easy to read 24 hour "day and night" dial. Operates day after day without attention. Can be controlled manually without automatic reset. For 110 volt 60 cycle AC only. Instructions included. Easily built into any case. 3 1/2 x 4 1/4 x 2 1/2" D. Shpg. wt., 2 lbs.
MS-810 Net 5.95

AUTO PROTECTOR MATS SPECIAL

ONLY **179**



- Door-to-Door

• Over the Hump • All Rubber
All rubber protector mats. Front mat measures 63 1/2" x 26". Fits the front of any car. Provides protection of floor board, toe board and over the hump. Easy to install—easy to remove for cleaning. Rear protector mat measures 63 1/2" x 19". Fits over the hump and into the floor wells. Available in Black only. Shpg. wt., Front mat 5 1/2 lbs. Rear mat 5 lbs.
AA-146 Front Mat Net 1.79
AA-147 Rear Mat Net 1.69

LAFAYETTE "Sprazon"



- If It Can Be Painted, You Can Use Lafayette "Sprazon"
- For Indoors and Outdoors
- Dries in Minutes

SPRAY PAINT

Modern fast way to paint. Give a lasting finish to all types of surfaces. Time tested alkyd resin spray enamel base. Made by dependable chemists under the strictest quality control, superior in quality and performance. Can be used on garden tools, furniture, boats, appliances, tools, automobiles, furnaces, kitchen cabinets, picture frames and etc. 16 oz. can. Shpg. wt., 1 1/2 lbs.

Stock No.	Color	16-oz. can.
P-480	Glossy White	89c
P-481	Flat White	
P-482	Ivory	
P-483	Glossy Black	
P-484	Flat Black	
P-485	Machine Gray	
P-486	Dove Gray	
P-487	Cherry Red	
P-488	Baby Pink	
P-489	Regal Blue	
P-490	Alpine Blue	Any 3, 79c
P-491	Hunter Green	
P-492	Mist Green	
P-493	Orange Flame	
P-494	Bright Yellow	
P-495	Pastel Yellow	
P-496	Brown	
P-497	Bright Silver	
P-498	Bright Gold	

Buy the EASY-WAY with EASY-PAY

UP TO 24 MONTHS TO PAY

with

LAFAYETTE'S 3-in-1 EASY-PAY CREDIT PLAN

ONE OF THESE 3 PLANS SUITS YOU BEST:

- REGULAR PLAN.** No Money Down. Monthly payments as low as \$5. (See Easy-Pay Schedule below).
- E-X-T-E-N-D-E-D PLAN.** No Money Down, Up to 24 Months to Pay. (See Easy-Pay Schedule below).
- ALTERNATE 60-DAY PLAN.** No Credit Service Charge. Select the Regular or Extended Plan. Make your first payment within 30 days as scheduled. Pay the full balance, if any remains, within 60 days of shipment and you automatically convert to the Alternate 60-Day Plan and **SAVE THE ENTIRE CREDIT SERVICE CHARGE.**

Lafayette's Easy-Pay Plan

Makes It Easier For You To Buy Now ...

10 TIMES EASIER

- IT'S EASY TO OPEN AN ACCOUNT.** Just fill in the agreement on the back of any order blank.
- IT'S EASY TO ORDER.** Use any regular Lafayette order blank. First order may be as low as \$20.
- NO DOWN PAYMENT.** Whether you pay within 60 days, or 24 months, you pay no money down.
- ONE LOW MONTHLY PAYMENT** buys anything Lafayette sells. (Pre-recorded tapes, records, and items intended for resale excepted.)
- IT'S EASY TO MAKE "ADD-ON" PURCHASES FOR ANY AMOUNT AT ANY TIME.** No need to pay your current balance in full before making "add-ons" ... just add them to your account. No down payment, no minimum order, and in many cases no increase in monthly payments.
- IT'S EASY TO REORDER AT ANY TIME.** Once your credit has been established you can re-order at any time ... no minimum, no down payment.
- UP TO 24 MONTHS TO PAY.** No need to wait—buy what you want NOW, up to 24 months to pay.
- LOW CREDIT SERVICE CHARGES.** Easily and quickly seen on schedule below.
- SEND NO MONEY FOR 30 DAYS.** First instalment payment is not due until 30 days after shipment.
- NO WAITING FOR MONTHLY STATEMENTS.** You always know the exact amount of your balance.

NO MONEY DOWN

"DOLLAR POWER PLUS"

You Get "DOLLAR POWER PLUS" with Lafayette's 3-IN-1 Easy-Pay Plan. One Low Monthly Payment Buys More For You.

Monthly Payments FOR ONLY	Unpaid Balance (Total amount less down payment - if any) YOU CAN BUY UP TO
\$ 5	\$100.00
6	120.00
7	140.00
8	160.00
9	180.00
10	200.00
11	225.00
12	250.00
14	275.00
15	300.00
17	350.00
19	400.00
22	450.00
24	500.00

For monthly payments on balances over \$500, please write us.

Here's How To Open Your Easy-Pay Account:-

Use the regular Lafayette order blank (more will be supplied upon request). Complete both sides of the form carefully, following the step-by-step instructions and illustration. Accuracy will speed handling of the form from the moment of receipt and permit immediate shipment upon approval of credit. Be sure to sign the agreement and indicate which Easy-Pay Plan you prefer — the liberal Regular or special Extended.

For both Plans, minimum order is \$20 and first instalment is not due until 30 days after shipment.

No Credit Service Charge for the alternate 60-Day Plan. For the Regular and Extended Plans, you are privileged to prepay the balance in full at any time to obtain a partial rebate of normal credit service charges.

Easy-Pay privileges are available to qualifying U.S. citizens or residents of all 50 States, Puerto Rico, Canada, and U.S. territories having comparable postal and express facilities. Any responsible individual over 21 years old with a steady source of income can apply.

FOR EASY PAY PURCHASE USE THIS SIDE AFTER FILLING IN MERCHANDISE ON REVERSE SIDE

RETAIL INSTALLMENT CONTRACT

Buyer's Copy Mailed—Date _____ By _____

(Please Print)
 Name _____
 Present (A) _____
 Home Address _____
 City _____ Zone _____ State _____
 How Long At Telephone _____
 This Address _____

To fill in spaces below correctly refer to EASY PAY PLAN Schedule on this sheet and note example.

EXAMPLE - (Standard Plan)

1. Total Cash Price*	106.50
2. Sales Tax (N.Y.C. only)	11.00
3. Total (items 1+2)	117.50
4. Down Pay (Altho Not Required Reduces Svce. Chrgs. & Paymts.)	10.00
5. Unpaid Balance (item 3 minus item 4)	110.00
6. Credit Service Charge (See EASY PAY Schedule)	7.50
7. EASY PAY BALANCE (Add items 5+6)	
8. Total EASY PAY Price (Add items 3+6)	

Beginning one month after shipment BUYER AGREES TO PAY \$ _____ per month for _____ months, and a FINAL monthly payment of \$ _____ to the place and/or to any party designated in writing by the Seller.

RETAIL INSTALLMENT CONTRACT

(L.S.) DATE _____

By _____ Signed _____

PRESENT ACCT. = EP _____ DATE DUE _____ To combine additional purchase with a previous account, indicate UNPAID BALANCE \$ _____

How to convert to Alternate 60-Day Plan: Pay 1st instalment within 30 days of shipment. Complete payment of balance, if any remains, within 60 days of shipment and Save Entire Credit Service Charge.

If Unpaid Balance Is	Standard Plan		Extended Plan		If Unpaid Balance Is	Standard Plan		Extended Plan	
	Credit Svce Charge	Monthly Payment	Credit Svce Charge	Monthly Payment		Credit Svce Charge	Monthly Payment	Credit Svce Charge	Monthly Payment
UP to 20.00	2.00	2.00	AVAILABLE ONLY		225.01 - 250.00	25.00	14.00	38.00	12.00
20.01 - 30.00	3.00	3.00	ON ORDERS WITH UNPAID BALANCES	5.00	250.01 - 275.00	27.50	17.00	41.00	14.00
30.01 - 40.00	4.00	4.00	OVER \$50.00	6.00	275.01 - 300.00	30.00	19.00	44.00	16.00
40.01 - 50.00	5.00	5.00		7.00	300.01 - 350.00	35.00	21.00	47.00	18.00
50.01 - 60.00	6.00	6.00		8.00	350.01 - 400.00	40.00	24.00	50.00	20.00
60.01 - 70.00	7.00	7.00		9.00	400.01 - 450.00	45.00	27.00	53.00	22.00
70.01 - 80.00	8.00	8.00		10.00	450.01 - 500.00	50.00	30.00	56.00	24.00
80.01 - 90.00	9.00	9.00		11.00					
90.01 - 100.00	10.00	10.00		12.00					
				13.00					

For purpose of receiving credit for above EASY PAY PLAN purchase, the buyer makes the following representation:

With Parents Spouse Living Alone Landlord's Name and Address _____
 Home Address _____ Permanent (Check Previous which) _____ How Long (Years) _____ (Months) _____
 Age _____ Single Married Divorced Spouse Employed by _____ Salary _____
 Draft Classification _____ Have you bought Reserve Status _____ from Lafayette before? No Yes On Time Payment? No Yes If yes, please give your Lafayette Time Payment Account Number. No. _____
 Real Estate Owned—Address _____ City _____ State _____ Mortgage \$ _____
 Recorded In Name of _____ Present Value \$ _____
 Name _____ If self-employed, give nature of self-employment. _____
 Present Employer _____ Position Badge No. _____ Salary _____ How Long (Years) _____ (Months) _____
 Business Address _____ Any Other Income _____ Source _____ How Long (Years) _____ (Months) _____
 Name & Address Former Employer _____
 Bank Savings Checking _____
 First Trade Reference _____ Name & Address _____ (City and State) _____ Highest Credit \$ _____ Still Owning \$ _____ Monthly Payment \$ _____
 Second Trade Reference _____
 Third Trade Reference _____
 Nearest Relative _____ Name _____ Address _____ Relationship _____
 (DO NOT LIST THOSE WITH WHOM YOU RESIDE)

MINIMUM ORDER \$20.00 TOTAL CASH PRICE — NO DOWN PAYMENT No money down when you buy with Lafayette's new Easy-Pay Plan.

ADDITIONAL PURCHASES: Once you establish credit, you can "add-on" to your account for any amount at any time. No down payment required on "add-ons" or reprinted accounts. Just list the items you want on the order blank, write "add to my account", give your account number, also indicate if you want instalment payment combined. Make certain you sign the Retail Installment Contract


NOTICE TO THE BUYER: 1. Do not sign this agreement before you read it or if it contains any blank space. 2. You are entitled to a completely filled in copy of this agreement. 3. Under the law, you have the right to pay off in advance the full amount due and under certain conditions to obtain a partial refund of the credit service charge.

LAFAYETTE RADIO ELECTRONICS CORPORATION (SELLER)
 111 JERICHO TURNPIKE, SYOSSET, L. I., N. Y.

seller and buyer purchases merchandise as described on reverse side hereof to be kept in good repair and unencumbered at buyer's stated address. Seller shall retain title to and right to possession of merchandise until fully paid. The unpaid balance of this order together with applicable credit service charge, may be added to an existing unpaid account, for convenience of both buyer and seller. Should the buyer place subsequent orders, unpaid balances on such orders may be combined with any balance owing on this order together with applicable credit service charge, if buyer so authorizes and seller accepts in appropriate spaces elsewhere in this contract. Upon default of any payment or payments seller may declare entire unpaid balance due at once and may also repossess merchandise retaining previous payments as compensation for the use thereof. If proceeds of resale of merchandise are insufficient to cover buyer's obligation, buyer will pay the deficiency to seller; if proceeds result in overage, seller will pay such overage to buyer. Payments will be made to the place and/or to any party designated by the seller in writing.

LAFAYETTE RADIO ELECTRONICS CORPORATION (SELLER)

MORE BARGAINS FOR EVERYONE!



KING-SIZE STEEL "STOR-SHED"

- Sturdy All-Steel Construction
- Weatherproof, Fireproof, Rustproof
- Room Enough for Your Garden and Lawn Equipment and Tools Too!

All-steel utility storage shed holds everything including the kitchen sink. Completely weatherproof, undercoated to prevent rust. Sloped roof with rain gutter for quick, easy run-off of rain water. All-steel floor. Locks securely and safely, keys included. Safely handle inside prevents "lock-ins". Pegboard on back and side walls for easy hanging of tools. Easy-to-open hinged doors open practically an entire end for walk-in ease. Prime coat of green paint, may be repainted for your own taste; white doors. Ventilated for air circulation. Complete with nuts, bolts and instructions for assembly. Shipped F.O.B. Altoona, Pa. warehouse. No C.O.D.

As low as
79⁵⁰
No Money Down

"STOR-ALL" LAWN LOCKER

- For Toys, Lawn and Pool Equipment, Trash Cans, etc.
- Heavy-Duty Steel Construction

22⁸⁸
No Money Down

Sturdy steel construction including steel floor. Roof folds back on piano-type hinge for easy access. Doors snap shut with spring latch. Provides 24 cu. ft. of clean-lined storage space for hundreds of uses—storing, protecting and concealing. Green prime coat may be repainted if you wish. Overall 4'W, 2'D, 3'H. Complete instructions for easy assembly. Shpg. wt., 60 lbs. ML-310WX Net 22.88



TRAVELER UMBRELLA TENT

FEATURES ALUMINUM EXTERIOR FRAME—EASY TO CARRY, SETS UP FAST, LENGTHENS TENT LIFE, LEAVES INTERIOR UNOBSTRUCTED.

39⁵⁸
No Money Down

- Nylon Screened Window and Zipper Door
- Water-Resistant, Mildew-Resistant Fabric
- Sewed-in Floor

Easy to erect, the exterior spring steel framework enables tent to be set up in less than 10 minutes. Leaves the interior obstruction-free. Top of 6.74 oz. and sides of 6 oz. forest green water and mildew resistant drill. Sewed-in floor, nylon screened window, nylon screened zipper door, hardwood stakes. 9x9-ft. base, 6 1/2-ft. center height, eaves 5'1" high and 38" square. Sleeps 2-3 people and capacity can almost be doubled by using double-decker cots. (Awning poles not included). SE-18WX Shpg. wt., 45 lbs. Net 39.58



AIR-VENT CAMPER

- Perfect 2 Men Camper
- "Umbrella" Type — Needs No Stakes

29⁹⁵
NO MONEY DOWN

Features nylon screened ventilator on top for fresh air even during a rain. Insect-proof zipper door with two 10x15" nylon screened windows with storm flaps. Sewed-in floor. Exterior steel framework leaves interior obstruction-free. Hardwood stakes included but tent need not be staked down under normal conditions. 6 oz. forest green, water and mildew resistant drill. 7x7-ft. base, 5 1/2-ft. center height. Ideal for 2-man camping. Shpg. wt., 26 lbs. SE-19WX Net 29.95




STEEL STORAGE UNITS

595 For 4 Shelves
30"x12"x60"

- Triple Bent Shelves
- Heavy Angle Posts
- Shelves Adjustable on 1 1/2" Centers
- Braced on Back & Sides

For stores, offices, garages, basements, pantries, closets—just what you need to solve your storage problems, you'll find dozens of uses for these rugged racks. And now, Lafayette offers them at a bargain price. Available in two sizes to fit virtually anywhere — 30Wx12Dx60"H with 4 shelves, or 30Wx12Dx72"H with 5 shelves. Corner post and all edges are rounded and snag proof with back and side braces providing added strength and rigidity. Gray enamel finish. Shipped unassembled with all necessary hardware for fast easy assembly. Size 12x30x60". Shpg. wt., 25 lbs. ML-306WX Net 5.95
Size 12x36x72" Shpg. wt., 33 lbs. ML-305WX Net 6.89



TWO-MAN MOUNTAIN TENT

- Nylon Screened
- Plus Canvas Front

15⁸⁸

Hardwood "A" frame at front and exterior rear pole eliminate interior poles and provides full doorway access. Nylon screened insect-proof door with full-length front zipper and bottom zippers. Sewed-in floor; extension end. Rugged 6 oz. forest green, water and mildew resistant drill. 7'3" long, 5' wide, 3 1/2" high. With jointed metal poles, hardwood stakes, guy ropes. SE-20W Shpg. wt., 14 lbs. Net 15.88



5 LB. DN-200 FILLED SLEEPING BAG

As Low As **9⁷⁷**

- Double Pull Zipper—2 Bags Zip Together to Form One Double Bag

Filled with 5 lbs. of DN-200 (70% rayon, 12% polyester, 7% acetate, 6% cotton, 5% nylon)—the all-new filling which provides excellent insulation, is lightweight, resilient, non-allergenic, mat resistant and comfortable. Water repellent forest green outer cover and hood of rugged duck; soft flannel lining. Double air mattress pocket. 100" double pull zipper, weatherstripped. Cut size 36x80"; approx. finished size 33x75". Shpg. wt., 9 1/2 lbs. SE-16W Net 14.55




DACRON-FILLED SLEEPING BAG. Similar to SE-16 above but filled with 3 lbs. of Dacron Fiberfill—keeps shape, won't absorb moisture. Snap-on hood; built-in tabs for attaching removable flannel lining. Double pull zipper. Cut size 36x80"; approx. finished size 33x75". Shpg. wt., 8 lbs. SE-15W Net 19.44

ECONOMY SLEEPING BAG. 3-lb. DN-200 filling. Water repellent olive green top cover, with vinyl coated fabric bottom and hood; colorful lining. Heavy-duty 32" zipper, weatherstripped for warmth. Cut size 36x80"; approx. finished size 33x75". Shpg. wt., 7 lbs. SE-17W Net 9.77


PUTTNIK-INDOOR PUTTING PRACTICE

- Indoor Fun for the Entire Family
- Takes off Strokes from Dad's Golf Game
- Returns Balls Within 5" Radius of Cup



ONLY **8⁸⁸**

Improves putting technique of any golfer as well as providing many hours of play for the entire family. This all-steel unit is as close to being a cup on the green as is possible. Your golf ball is retrieved automatically—when the ball lands on the green surrounding the cup, it is collected and returned electromagnetically. Takes strokes as long as 10 to 20 feet away. UL approved. 115V, AC. Shpg. wt., 5 lbs. SE-21 Net 8.88
Sudden Death Regulation Putter. Shpg. wt., 1 1/2 lbs. SE-22 Net 3.88



ELECTRIC POWER PLANT

145⁵⁰ NO MONEY DOWN

1000 WATT

- 3-H.P. Engine • 90-Day Parts Warranty • Regulating Governor • Easy-To-Use Rope Starter • 1000 Watts Continuous • 1250 Watts Intermittent

A compact, rugged direct coupled power plant. Supplies 115 V.A.C., 60 cycles at 1000 watts continuous, 1250 watts intermittent duty. The engine is a 3 h.p., 4 cycle, air cooled Briggs & Stratton. Operates on regular gasoline. Uses standard weight motor oils. Recoil manual start. Drip-proof, continuous duty, self excited, 2 pole, 3600 RPM generator. Features a pre-lubricated, sealed, ball-bearing commutator, mica insulated. 3 cycle maximum frequency variation. ±5% voltage regulation. Gas consumption at 1000 watts; 0.2 gal per hr.; at 1250 watts, 0.39 gal. per hr. Includes instructions, parts lists and 90 day parts warranty. Made in U.S.A. Shpg. wt., 70 lbs. VIA EXPRESS ONLY. ML-266WX Net 145.50
1750/2000 WATT POWER PLANT: Similar to above with 4 h.p., 4 cycle engine. Shpg. wt., 110 lbs. ML-267WX Net 194.50
2500/3000 WATT POWER PLANT: Similar to above with 5 1/2 h.p., 4 cycle engine. Shpg. wt., 156 lbs. ML-268WX Net 279.95



HEAVY-DUTY SUMP PUMP

- Rust-Proof Cast Aluminum Base
- Rust-Proof Seamless Aluminum Column
- 3,920 Gallons-per-Hour to a 10-ft. Head

NO MONEY DOWN **37⁵⁰**

A rugged automatic electric pump with a dependable 1/2 HP motor with safety-designed overload protector. Features a plastic float, non-corrosive in any water; extra large separate screen to prevent clogging; vertical 1 1/4" discharge that eliminates base elbow. Lifetime guarantee on all moving parts (1-yr. guarantee on electrical components). Oilite base bearing for long life. Individual pressure plate to assure consistent water flow. Designed to operate at top performance:

Gallons Per Hour	Discharge Height
3,920	10-ft.
3,215	15-ft.
1,600	20-ft.
540	25-ft.

ML-297WX Shpg. wt. 25 lbs. Net 37.50

FASCO 200 CFM BLOWER

- 3,000 RPM — 200 Cubic Feet Per Minute
- 3 1/4" Diam. Screened Intake — 2 1/2" x 2 1/2" Output
- Flange with Mounting Holes



Efficient, quiet, dependable and economical. Usable in many applications—air distribution in confined areas, exhaust fumes and gas, etc. Suitable for ventilation equipment in home, marine and commercial use. Welded pressed steel housing. Shaded-type motor for efficient, quiet operation. Moves 200 cubic feet of air per minute. Mounting flange, 5 1/4"x4", 2-ft. AC line cord and plug. 110V, 60 cycles; 1.4 amp. SP-279 Shpg. wt., 7 lbs. Net 9.95

9⁹⁵

DELRON SUBMERSIBLE PUMP

- Will Not Corrode or Rust
- Hermetically Sealed Motor
- For Circulating and Dispensing Water

12⁷⁵



It's the all-new Delron aluminum pump for under water use. Guaranteed not to corrode or rust; hermetically sealed motor. Circulates and dispenses water and mild-acid solutions for use in fountains, beverage dispensers, aquariums, photo developing, air conditioning, etc. Gallons per hours delivery: 240 @ 1 ft.; 180 @ 3 ft.; 125 @ 5 ft.; shut off @ 12 ft. Outlet 3/8"; inlet 1/2" pipe O.D.; height 4 1/2"; depth 4 1/2"; 6 ft. safety cord. 115 V, 60 cy, AC. 49 watts load; .67 amps load. Shpg. wt., 3 1/4 lbs. ML-312 Net 12.75

WATERFALL KIT

Enchanting waterfall of cascading water constantly recirculated by electric pump. Gallons per hour delivery: 180 @ 1 ft.; 140 @ 3 ft.; 100 @ 5 ft.; shut off @ 10 ft. Outlet 3/8"; inlet 1/2" pipe O. D. Load: amps 65; watts 43. No concrete needed; complete with instructions. Kit consists of pump, 8-ft. plastic hose, 7-ft. sealing poly, pump filter. Shpg. wt., 4 lbs. ML-311 Net 15.88

HOME FIRE ALARM

- Loud Clear Buzzer Alarm
- Input for Adding Multiple Detector Switches
- Provides Protection Everywhere in the Home

4⁹⁵



Set up a fire alarm system in your home now. This home fire alarm alerts you and your family before the flames can spread. The Basic Unit trips at 145° with a clear, loud buzzer alarm. Measures 4 1/2 x 5 1/4 x 2 1/4". Has input for adding as many detector switches as needed to protect your entire house. Hang-up hole in rear for easy mounting. Oblong slot on bottom for testing of unit. With AC line cord and plug. For 110-120V, AC. SP-280 Basic Unit. Shpg. wt., 2 lbs. Net 4.95
135° DETECTOR SWITCH. Shpg. wt., 3 oz. EL-103 Net 1.95
200° DETECTOR SWITCH. Shpg. wt., 3 oz. EL-104 Net 1.95
TEST BUTTON. Shpg. wt., 3 oz. EL-30 Net .16
18 Gauge, Twisted Pair Control Wire. Shpg. wt., 3 lbs. per 100-ft. WR-122 100-ft. Net 1.65
WR-123 500-ft. Net 7.50

ELECTRONIC POWERMEG TRANSISTORIZED PORTABLE MEGAPHONE

- RANGE 100-300 FEET • LIGHTWEIGHT COMPACT
- COACHES • CHEERLEADERS • SCOUTING • MIKING • BOATING


CLOSEOUT PRICE **5⁹⁹**



Carries the voice 100-300 feet, loud and clear. Can be used at outdoor gatherings, picnics, song fests, square dances, hikes, camping trips—anywhere there is a need for a small portable P.A. system. A valuable aid for the safe conducting of waterfront activities at camps and resorts, or for close range boat-to-boat communications. Just press button and talk into microphone (included). Volume control regulates loudness. Requires 4 standard 1.5 volt flashlight cells. With shoulder strap. Shpg. wt., 4 lbs. PA-275 Net 5.99
BA-274 1.5V Battery (4 required) Net ea. .16

Cordomatic DOG TENDA

Automatically Controls Your Dog's Freedom **6⁴⁷**



Do away with outmoded chains and ropes, give your dog a larger area of freedom with no tangling or binding. This new Dog Tenda extends or retracts automatically with your pet's movement. Rotates 360° both horizontally and vertically. 15 ft. nylon covered flexible steel cable allows 30 ft. of running room and a roving area of over 700 sq. ft. Feather light tension with freely rotating snap bolt fits any dog collar. Complete with all mounting hardware for both wall and inground mounting. Shpg. wt., 3 1/2 lbs. HD-660 Net 6.47

TRY TO BEAT THESE ANTENNA PRICES!

Lafayette Has The BIGGEST Selection At The LOWEST Prices.

MAXIMUM PERFORMANCE FRINGE ANTENNA

- 21 Active Elements
- Snap Open Design
- Fiberglass Insulators
- Compound Yagi Array

Range to 100 Miles

1188

GOLD ANODIZED

Field proven design for fringe reception. Gold anodized to combat corrosion. Compound yagi array to "sock-in" signals where other designs fail. "Tension-lok" hardware. Heavy wall tubing throughout. Less mast. AN-67WX Gold Anodized. Shpg. wt., 8½ lbs. Net 11.88

"U-INSTALL-IT" KIT with chimney mount. Includes AN-67WX antenna and installation kit AN-12W as shown below. Shpg. wt., 15 lbs. Net 14.88 AN-60WXM

LAFAYETTE DEEP FRINGE-PROBER

Up to 150 miles of Extra Power Fringe Reception

- 27 Electrical Elements
- Inline twin driven yagi design
- Deep Fringe Gain on all VHF channels
- Completely pre-assembled
- Gold Alodized

1798

Delivers the extra picture power needed for crisp, clear pictures in remote areas. Inline twin driven yagi design provides more gain and higher front-to-back ratio. Result: More TV stations, more picture power. Factory preassembled for snap-out assembly. Reinforced gold alodized aluminum construction. Less mast and twin lead. Shpg. wt., 10 lbs. AN-215WX Net 17.98

Leader IN-LINE Antenna Kit

- Complete-Ready To Install
- Time-proven Design

GOLD ANODIZED

COMPLETE KIT 649

Ideal metropolitan and suburban antenna kit. Broad band, uni-directional response. Perfect impedance match on high and low bands results in reduced stray reflections and ghosts. Designed for maximum in phase currents on both high and low bands. Shpg. wt., 4 lbs. AN-154W Net 3.79

"U-Install-It" Kit. Includes AN-154 and roof mount kit, AM-10, as below. Shpg. wt., 10 lbs. Net 6.29
"U-Install-It" Kit. Includes AN-154 and Chimney mount kit, AM-12, as below. Shpg. wt., 11 lbs. Net 6.49
AN-153WM

ALL CHANNEL'S "RIVIERA"

WORLD'S MOST POWERFUL ULTRA-FRINGE VHF-UHF-FM ANTENNA
GUARANTEED 200 MILE VHF RECEPTION OR YOUR MONEY BACK

- Receives channel 2-83 from all directions without a rotor
- Broadband UHF-VHF and FM, motorless all direction reception
- All aluminum flip-out assembly

19⁸⁵



Field tests reception on VHF of up to 200 miles has made possible this unprecedented guarantee. Here is an antenna with one transmission line for all UHF, VHF and FM stations, in all directions without the use of a rotor. The nine position selector switch connected at the set electronically rotates antenna beam instantly without physically moving the antenna. Gain on channels 2-6 comparable to 4-bay conicals; on channels 7-13 comparable to stacked 10-element single channels yagis; on 14-83 comparable to bow-tie reflector. 16½" doweled aluminum elements are 60 inches long. Complete with switch, coupler, 45" stacking bars and 2 7½" angle type mast insulators for Polymicalene line listed below. AN-135WX Less Mast. Shpg. wt., 10 lbs. Net 19.85

The Riviera is ideal for FM Stereo/Multiplex reception. Elements are a full wave length at FM frequencies.

"U-Install-It" Kit: Includes Riviera antenna, chimney mount, two five ft. masts, 100 ft. of Polymicalene 4 conductor lead-in wire, 8 stand off insulators and complete instructions. AN-42WXM Shpg. wt., 16 lbs. Net 27.32

THE RIVIERA MUST BE USED WITH THE LOW LOSS LEAD IN WIRE LISTED BELOW

Special 4 conductors, matched impedance transmission line. Low loss, mica-filled Polymicalene copperweld conductors.

WR-8W 50 ft. length	Net 5.00
WR-9W 75 ft. length	Net 7.50
WR-18W 100 ft. length	Net 8.90

FULL 20 ELEMENT STACKED


- SNAP OPEN CONICAL
- ALL ALUMINUM
- NO LOOSE PARTS
- FASTEST INSTALLATIONS

525

singly each

495

each, in lots of 3



Best antenna deal yet for servicemen-dealer-and installation specialists. All the most wanted features. Quickest-easiest installation possible. No loose hardware. All elements snap open and lock in without tools. Most efficient conical design for all reception areas. Two complete bays with Q bars, less mast.

AN-28WX—Singly, ea. Shpg. wt., 8 lbs. Net 5.25
Lots of 3, ea. Net 4.95

"U-INSTALL-IT" KIT With All Angle Roof Mounts. Includes AN-28 antenna and installation Kit AM-11 with two 5 ft. masts. As shown below. AN-32WXM Shpg. wt., 18 lbs. Net 7.95
"U-INSTALL-IT" KIT With Chimney Mount. Same antenna and accessories but includes chimney mount instead of roof mount. AN-43WXM Shpg. wt., 18 lbs. Net 8.75

NEW LAFAYETTE UNI-TENNA

- RANGE TO 75 MILES
- ONE ARRAY FOR FM & TV
- A MUST FOR MULTIPLEX

Fig. A

Fig. B

585

1055

A high quality antenna designed for operation in semi-fringe areas. Excellent pattern and high gain provide top reception of color and black-white TV and is ideal for stereo FM multiplex. Uses combination TV and FM antenna on one boom with separate transmission lines. The 5¾ ft. boom has square cross sections for added strength and maintains parallel alignment of elements. 4 Element yagi is used for TV, 3 elements yagi for FM, 10 Elements operating on high band as patented calinear yagi. Shpg. wt., 6 lbs. AN-211WX Fig. A Net 10.55

NEW LAFAYETTE UNI-TENNA

- ONE RIG FOR TV & FM
- METROPOLITAN AND SUBURBAN MODEL

Similar to AN-212 but with less elements and use of omnidirectional FM halo. Designed for local and suburban use. Provides full response operation for TV, FM and Multiplex. Shpg. wt., 3½ lbs. AN-212WX Fig. B Net 5.85

NEW LAFAYETTE ULTRA-LITE ALL DIRECTIONAL FM ANTENNA

210

- Perfect for Indoor Concealed Installations
- Solid Rod Elements.



Here is the FM antenna you have been waiting for. Designed for either outdoor mast or indoor closet/attic installation. Easy to install—no holes to drill. Provides excellent gain for areas up to 35 miles from station. Perfect for multiplex reception. Brings in all stations clearly. Gold corrodized finish for weather and corrosion protection. Strong, yet lightweight design. Shpg. wt., 1 lb. AN-213 Net 2.10

FM Antenna Kit Same as above, but with kit containing 50 ft., 300 ohm line, 3-31 ½" Stand-offs; 1-7 ½" stand-off and 1 mast wrap around stand-off. Shpg. wt., 3 lbs. AN-214 Net 3.23

"MULTIPLEX 10" EXTENDED RANGE FM ANTENNA

988

GOLD ANODIZED

Ideally suited to Multiplex FM reception. Stereo (Multi-plex) FM signals, for the average tuner, have a range of approximately half that of ordinary (monaural) FM signals. This 10 element, double driven, yagi array has the necessary added gain, sensitivity and directivity to compensate for the lack of signal strength. Assures full-fidelity reception and highest signal/noise ratio. All aluminum, gold anodized construction. Fibreglas insulators. Torsion lock hardware, sure-lock mast clamp. Broad banded to cover the entire 88 to 108 mc band. Shpg. wt., 7 lbs. AN-250WX Net 9.88

NEW "HI-5 FM YAGI"

595

- DESIGNED EXPRESSLY FOR FM

GOLD ANODIZED

High gain antenna designed for the audiophile who seeks perfection in FM reception. Extra elements on this antenna serve to pull in stations where others fail. Trouble free operation even under severe weather conditions. The fully automatic snap-lock brackets insure easy, rapid and secure installation. AN-49WX Shpg. wt., 3 lbs. Net ea. 5.95

SPECIAL SHIELDED TWIN LEAD for FM MULTIPLEX

898

Improves the Signal-to-Noise Ratio so vital to satisfactory FM MPX reception.

300 ohm twin lead for FM MPX, shielded with tinned copper for outstanding noise-resistant performance. Each conductor insulated with heavy, 20 gauge abrasion-proof black vinyl. Delivers noise-free signal from antenna to set efficiently.

WR-161 100 ft. coil	Net 8.98
Shpg. wt., 7 lbs. per 100 ft.	Net 43.01
WR-162WX 500-ft. spool	Net 82.44
WR-163WX 1000-ft. spool	

SPECIAL UHF ANTENNA

479

- Highest Gain on 70 UHF Channels
- Completely Preassembled
- Excellent Directivity
- Flat Response Across Each Channel

Four bay, UHF bowtie antenna. Exceptionally high (12db) gain—relatively flat across the entire spectrum. Fully factory assembled. Quickest and easiest to install. High efficiency screen grid reflector boosts front to back ratio. Unique "cross-over" phasing bars—open V elements. Rugged—rigid—corrosion resistant construction. Shpg. wt., 5 lbs. AN-200WX Net 4.79

UHF "TRANSLATOR" 4-BAY ANTENNA

Four bay bow-tie and screen reflector—tuned to the UHF translator frequencies. Average 16db gain on channels 70-83. Completely preassembled. AN-201WX Shpg. wt., 5 lbs. Net 4.79

NEW! FM ANTENNA KIT ALL DIRECTIONAL

285

- GOLD ANODIZED
- FULL SIZED
- READY TO INSTALL
- FULLY ASSEMBLED

ANTENNA ONLY 3.98 COMPLETE KIT

Provides excellent gain for areas up to 35 miles from the station. Use on existing masts—new installation—or as an attic installation. Gold anodized aluminum for years of trouble free operation. Capable of receiving FM signals from practically all directions with equal efficiency. Complete with 50 ft. of 300 ohm twin lead, mast stand-off, screw eye standoffs, mast mount. AN-53 Shpg. wt., 5 lbs. Net 3.98

FM ANTENNA ONLY. Shpg. wt., 3 lbs. Net 2.85 AN-66

REMBRANDT

TV DIRECTION FINDER

- Receives Signals From All Directions—Without a Rotor!
- Supercharges Any TV Antenna—Boosts The Pick-Up Power!
- Filters Out Interference
- Rejuvenates TV Antennas
- Amplifies The TV Signal
- No Installation Problem

595

The latest television invention! Seeks out—and beams in—TV signals from any channel, in any direction, without a mechanical rotor. Electrically rotates the polar-receiving pattern of your existing antenna and phases the ground wave picked up by the electrical wiring system with the sky wave picked up by the antenna. Improves any existing antenna: indoor, outdoor, master or built-in. Boosts pick-up power of any antenna—old or new. Just a flick of the selector control tunes out ghosts—filters out interference—tunes in those "hard-to-get" problem channels. Automatically amplifies TV signal strength for "snow" free, brighter, clearer pictures. Works on every channel—in any location—with any antenna—for any TV set. No installation problem—simply attach to antenna terminals in back of TV set—and plug into 110V AC/DC socket. Complete satisfaction guaranteed or your money back. AN-140 Shpg. wt., 2 lbs. Net, ea. 5.95
In lots of 6 ea. Net 5.00

SPECIAL CONICAL & V-BEAMS

260

229

All aluminum 8 element conical. Full sized. Rugged insulator block. Designed for rapid assembly. Fan front of 6 full length elements. Real value. Shpg. wt., 4 lbs. AN-11W Singly ea. Net 2.60
Lots of 3 ea. Net 2.40

"U Install It" Kit includes AN-11 and roof-mount kit AM-10 as shown below. Shpg. wt., 11 lbs. Net 4.95
AN-33WM
"U Install It" Kit. With chimney mount kit, AM-12 as below. Shpg. wt., 11 lbs. Net 5.50
AN-44WM

Popular primary area antenna. Rugged aluminum construction. Light weight easy to install. Sharply directional. Shpg. wt., 4 lbs. AN-21W Net 2.29

AN-20W 2 bays stacked Net 4.59
"U Install It" Kit. Includes AN-21W and roof mount kit AM-10, as below. Shpg. wt., 11 lbs. Net 4.70
AN-45WM
"U Install It" Kit. With chimney mount kit, AM-12 as below. Shpg. wt., 11 lbs. Net 5.29
AN-46WM

"U-INSTALL-IT" KITS

All the items for simple installation. You get an all angle roof mount—lightning arrester—75 feet of 300 ohm twin lead—screw eyes—mast standoffs and 5 ft. 1¼ O.D. steel mast.

AM-10WM Shpg. wt., 7 lbs.	ea. 2.95
AM-11WM with 2-5 ft. masts. Shpg. wt., 10 lbs.	ea. 3.55
AM-12WM Same as AM-10W and chimney mount	ea. 3.25
AM-13WM Same as AM-11W with chimney mount	ea. 3.75
AM-14WM Same as AM-10W with aluminum wall bracket	ea. 2.95
AM-15WM Same as AM-11 with aluminum wall bracket	ea. 3.55

Lafayette Offers More Accessories—Better Service—Lower Prices

ALLIANCE ANTENNA ROTATORS



AS LOW AS
18⁰⁸



Rotator redesigned and restyled to provide faster, smoother, better efficiency. Rotation speed is 1 R.P.M. Magnetic brake affords instantaneous stop. There is full 360° rotation. Factory lubricated for life. Contacts are self-wiping. A reinforced zinc die cast housing affords all weather protection.

Model U-98 (1 & 2)—Fully automatic, just set control knob and antenna rotates to desired position and stops automatically. Indicator shows antenna position. Size: Rotator 7 $\frac{3}{4}$ x5 $\frac{1}{4}$ x8". Control Case 7 $\frac{3}{4}$ x4 $\frac{1}{2}$ x4". 110V. 60 cps AC at 65 watts. Shpg. wt., 12 lbs.

TL-71W Net 25.77
T-12 (1 & 3)—Manually operated with direction indicator. Needle indicates position of antenna on control panel. Has clockwise and counter-clockwise revolution. Highly styled decorator case. Size: Rotator 7 $\frac{3}{4}$ x5 $\frac{1}{4}$ x8". Control Case 6 $\frac{1}{2}$ x2 $\frac{1}{2}$ x4 $\frac{1}{2}$ ". Operates on 110V 60 cps at 30 watts. Shpg. wt., 12 lbs.

TL-72W Net 22.12
Model K-22 (1 & 4)—Economy model—Provides positive instant finger tip control of rotation. Push on one end of bar and antenna turns clockwise. Push down on other end and antenna turns counterclockwise. Center disc automatic signal light indicates when limit of travel has been reached. Size: Rotator 7 $\frac{3}{4}$ x5 $\frac{1}{4}$ x8". Case 5x5x4". Shpg. wt., 12 lbs.

TL-73W Net 18.08
TBB THRUST BEARING BRACKET increases stress capacity of Tenna-Rotors up to 300 lbs. Withstands winds up to 90 M.P.H. Prevents buckling and bending. Shpg. wt., 3 lbs.

TL-74 Net 2.91
WR-24—4 conductor flat cable for above per ft. .03 per C ft. 2.39



BLONDER-TONGUE UHF CONVERTER

The only converter with 3 section tuner for "Class A" signal areas with these exclusive features. Tuned input tracks with oscillator, rejects spurious signals, suppresses oscillator radiation. Precise impedance match gives maximum signal conversion—no line ghosts—no picture smear. Drift-free performance is achieved by use of a thermally compensated oscillator circuit. One knob tuning; no VHF channel switching; output on channel 4, 5, or 6. Complete with tubes and instructions. Shpg. wt., 4 lbs.

TL-100 Net 16.41

B-T ULTRAVERTER DELUXE UHF-TV CONVERTER



Adds all UHF channels (primary, satellite, and translator) to standard TV sets. Insures finest pix even in weak areas. Features dual-speed channel selection with direct and fine tuning controls; stable, shielded oscillator. Max. signal transfer to channels 5 or 6 of TV; Precise 300 ohm match and triode amplification; Improved tuner design meets new FCC standards; UL approved; Tuning channels 14-83 (470-890 mc); Tubes: 6AF4A and 6ERS; Power: 117 volts at 60 cps AC, 20 w. Size 6 $\frac{1}{2}$ x5x4 $\frac{3}{4}$ ". Shpg. wt., 4 lbs.

TL-107 Net 27.44



TV-FM HI-PASS FILTER

Hi-pass filter passes all frequencies above 40 mc. Rejects all frequencies below 40 mc. Automatically eliminates electrical disturbances in the antenna circuit. Clears disturbances caused by neon, X-Ray, ignition, appliances, diathermy, short wave, etc. Shpg. wt., 1 lb. Imported

TS-331 Net 2.39

TV TUBE 'BRITENER'

Absolutely no tools or soldering needed for installing this handy inexpensive tube rejuvenator. You simply attach two plugs as directed on the instructions. For magnetic tubes and PARALLEL CIRCUITS only. Restores brightness contrast. Wt., 8 oz. Ea.

MS-12 singly .59

TV PICTURE TUBE SHORT ELIMINATOR

Eliminates expensive picture tube repairs. No elaborate equipment needed. Repairs grid and cathode shorts in two minutes—without pulling the chassis! Simple "plug in, switch-on" operation. Works with any TV picture tube. Imported

TS-282 Shpg. wt., 1/2 lb. Net .99

UNIVERSAL TV TUBE 'BRITENER'

Restores brightness to dim TV picture tubes. Operates on all types—magnetic or electrostatic—and in all circuits—parallel or series. Shpg. wt., 10 oz. Ea.

TS-170 in lots of 6 each 1.22
Singly each 1.39

LO-PASS LINE FILTER

Exceptionally efficient line noise eliminator. Utilizing dual ferrite core coils, heavily wound. Eliminates line noises caused by motors, industrial RF, neons, appliances, etc. Particularly useful on TV and FM sets, radios, tuners, record players. Automatic attenuation of unwanted disturbances. Shpg. wt., 1 1/4 lbs. Imported

TS-327 Line Filter. Net 2.49

UNIVERSAL 110° CRT REJUVENATOR

A new Universal picture tube brightener designed for application on 110° picture tubes. A single heavy-duty unit which performs four ways. A simple adjustment adapts it for either series or parallel wired filaments and it can be used on electromagnet or electrostatic focus tubes. Shpg. wt., 1 lb.

TS-283 For Sylvania Type 110° Tubes Net 2.20
TS-284 For RCA Type 110° Tubes Net 2.20

PEAK ROOF MOUNT

A heavy gauge steel peak roof mount. Heavily plated to resist corrosion. Will accommodate mast, up to 2" in diameter. Fully adjustable can be easily rotated. Complete with all necessary hardware. Shpg. wt., 5 lbs.

TS-41 Net 1.10


NO RUST BARGAIN MOUNT

The ideal chimney mount for life-long satisfactory service under the most severe conditions. Hot dip galvanized steel "W" mount. Two 10 ft. stainless steel straps and stainless steel seals. And at Lafayette's bargain prices. Shpg. wt., 4 lbs.

TS-90 Net Each 1.88
Lots of 3 Each 1.80

LAFAYETTE IV/FM 4-SET POWER BOOSTER

The MOST Gain for the LEAST Money



- Boost Signal For Up To 4 TV Sets
- Ideal for Master "Home" Installation
- Equally Useful In Primary and Fringe Areas
- Electro-Matched to Lafayette IV-FM Antennas
- Updates and improves any TV/FM antenna installation

Provide a stronger TV or FM signal to up to 4 sets anywhere in the home. Low noise-high output amplifier boosts and distributes the signal over ordinary twin lead. Special isolation circuitry prevents interaction and interference between sets. Provides as much as 7 to 10 db gain on all channels 2 through 13 when used with one TV set. From 2.5 to 5 db when used with 2 sets. Will often supply more gain when used with an indoor antenna than elaborate, unboosted outdoor antenna supply. Requires no tuning. Installs with just a screwdriver. Uses ordinary twin lead to "antenna-matched" terminals. Mounts behind set or in any convenient location. Measures 5 $\frac{3}{4}$ x3 $\frac{3}{4}$ x1 $\frac{1}{4}$ ". For 117 V.A.C. 60 cycles.

TL-75 Shpg. wt., 2 lbs. Net 9.95

SPECIAL 300-ohm TWIN LEAD



High quality—heavy gauge—all purpose twin lead. Perfect FM/TV transmission line. 80 mil polyethylene insulation. Shpg. wt., 2 1/2 lbs.

SP-260 Net .98

LIFELINE FM/TV TWIN LEAD

Guaranteed to Provide Perfect Transmission for the Life of Your Antenna—or Your Money Back

Take advantage of this unprecedented guarantee—you can't lose! 100 ft. of heavy duty twin lead—made of the finest available materials. Chemically protected against deterioration. Supplied in a dust-proof—tangle-free—self-measuring dispenser. 100 ft. coil. Shpg. wt., 3 lbs.

WR-164 Net 1.98

TWO SET COUPLER

Uses one antenna for two sets. Compact electronic set coupler assures performance of two TV sets on one installation. Easy to connect. Nothing to go wrong. Shpg. wt., 1 lb. Imported

TS-326 Each .43
In lots of 3, Each .39

TRI-SET COUPLER

Highly efficient 3 set coupler. For coupling 2 or 3 TV or FM sets to one antenna of any type. No interaction—less than 6 db insertion loss. 40 to 50 db rejection ratio. Shpg. wt., 1 lb. Imported

TS-332 Net 2.29

WIZARD 300 MASTER COUPLER

Provides for the coupling of any number of TV (color or black and white) and FM sets to one antenna line. The first set is connected directly to the line, and each additional set is connected through a separate WIZARD 300, without the need for an amplifier or booster. Shpg. wt., 3 oz.

TS-347 Net 1.15
In lots of 3 Net ea. 1.03

UNIVERSAL TV-FM PLUG & SOCKET

Compact-low loss—300 ohm plug and socket combination. For all TV & FM lead in applications. Surface mounting socket—low loss polystyrene plug. Constant impedance design. Solderless screw terminals. Includes hardware and instructions. Shpg. wt., 2 ozs. Imported

TS-328 Plug & Socket Net .35

DELUXE TV SERVICE LITE

Keep your hands free. Spring clamp with rubber covered ends attaches anywhere in T.V. cabinet. 4 $\frac{1}{2}$ " highly polished aluminum reflector uses standard 25 watt bulb. Complete with 6 ft. cord and plug, less bulb. Shpg. wt., 1 1/2 lbs.

MS-63 Net 1.59

ALL CHANNEL UHF-TV CONVERTER

13⁴⁴



- For Clear Sparkling Pictures
- Class A Signal Areas
- Adds UHF Channels 14-83 to Your TV Set

Enjoy all the new programs on UHF channels 14-83 on your present TV set with this UHF converter. Simple one-knob tuning with single on-off knob. Easy to install to terminals of your TV set and is easily attached to rear or side of cabinet. Gold, unbreakable metal housing. Power: 117V AC, 60 cycles. Size: 5x3 $\frac{3}{4}$ x2 $\frac{1}{2}$ ". Shpg. wt., 3 lbs.

TL-98 Net 13.44

NEW! MODEL AB-4 MAST MOUNTED TRANSISTORIZED TV/FM BOOSTER

A complete, compact amplifier—distribution system for up to 4 TV or FM sets. Reliable transistor circuit provides low noise and high gain. Stripless 300-ohm terminals on booster, and remote power supply for fast, positive installation. Requires four 1.5 volts flashlight batteries for power. Noise Figure: 4 db avg. High TV gain from 2-17 db and FM 12 db avg. depending on number of sets connected. Shpg. wt., 1 1/2" lbs. Size: AB-4 2 $\frac{1}{4}$ x3 $\frac{1}{2}$ x1 $\frac{3}{8}$ "H. RP-4 (power supply included) 3Wx7 $\frac{1}{4}$ Lx1 $\frac{7}{8}$ "H.

TL-165 Net 18.62

BA-157 1.5 volt Battery (4 required). Net .13
Shpg. wt., 15 oz.

MODEL AB-4AC, As above, with AC power supply. Net 21.27
TL-168 Shpg. wt., 1.5 lbs.

MODEL IT-4 TRANSISTORIZED 4-SET TV/FM BOOSTER

The highest gain of any home TV booster. Boosts antenna signal up to five times. More power for up to 4 TV or FM sets. The perfect basic unit for a home master TV-FM system. Draws so little current it need never be turned off—no tubes to replace. Engineered to provide an excellent impedance match and maintain necessary isolation between sets. Can also be used to boost amplification from most mounted boosters or in master systems. Solid electrical contact with the turn of a screw. Size: 2 $\frac{7}{8}$ x4x1 $\frac{3}{8}$ ". For 117 volts, 60 cy. A.C., .01 amp. Shpg. wt., 1 lb.

TL-166 Net 19.60

UHF-VHF LIGHTNING ARRESTER

Saw-tooth washers grip transmission line without stripping. Designed for flat, tubular, oval or open types. With mounting screw and steel strap. U/L approved. Shpg. wt., 10 oz.

TS-11—Lots of 10 Each .29
Singly35

TV TUBE RESTORER

One simple unit provides the cure for most ailing picture tubes. Latest model features slide switches—not pin plugs as older units do. Rugged, well made socket—compact, single unit design. Works on electrostatic or electromagnetic focusing tubes, in series or parallel circuits. Includes instructions. Shpg. wt., 1 lb. 4 ozs.

TS-333 Net 3.23

STRAPLESS CHIMNEY MOUNT

Can be installed in seconds with hammer and wrench on brick, stone or cement block chimneys of any size, or on the corner of almost any building. Mount is capable of up to 1500 lbs. clamping pressure and cannot rust away. Shpg. wt., 2 lbs.

TS-351 Net 1.25

LAFAYETTE'S "PORTABLE POWER" SHOP

THOR SPEEDWAY 3/8" DRILL

- FEATURING THE MOTOR THAT WON'T BURN OUT
- COMPLETE DRILL UL INDUSTRIALLY RATED & CSA APPROVED
- PRECISION GEARED CHUCK WITH KEY
- HI TORQUE MOTOR RATED AT FULL 2.5 AMPS



1195

Here is a professional 3/8" electric drill at an amazingly low price. Hi-torque 2.5 amp, 115 VAC motor with 3-conductor lead cord, precision geared 3-jaw chuck with key, all-steel precision hobbled gears and newly developed special alloy bearings throughout. Capacity in steel, 1 1/2" in hardwood, 1". No load speed 1750 rpm, full load speed, 1150 rpm. Momentary contact switch with locking pin. Sturdy diecast aluminum alloy housings with attractive hi-polish finish. Overall length, 8 1/4". Shpg. wt., 5 lbs. Net 11.95 HO-939

NEW! 10 inch Electric 1 3/4 h.p. CHAIN SAW

- Pruning-Trimming-Felling Small Trees
- Cuts Cord Wood-Joists-Heavy Beams
- Bores Cuts in Walls
- Draws 8 Amps



54.95

NO MONEY DOWN

A powerful, top-quality portable chain saw designed for professional or industrial use. This rugged, multi-purpose tool will also do dozens of jobs for the home craftsman, carpenter, contractor or on the farm. Positive chain adjustment eliminates slack. Chain travels at 1300 feet per minute for fast, true cuts up to 10 inches deep. Cool-running, bearings. Beautifully balanced, weighs only 12 lbs. Motor develops 1 3/4 h.p., 8.0 amps. 115V, 25-60 cy., AC/DC. 3 wire, 6 ft. cord. Shpg. wt., 14 lbs. Net 54.95 HO-181
EL-108 25 ft., 3 wire ext. cord Net 2.13
EL-109 50 ft., 3 wire ext. cord Net 3.51

NEW! FULL POWER 1/4 DRILL

OUR TOP DRILL VALUE

788



- UL APPROVED • GEARED CHUCK AND KEY
- UNIVERSAL 3/8 H.P. MOTOR

Lafayette's top drill value. 1/4" geared chuck drill rated at a full 3/8th horsepower. Universal motor. U.L. approved. 1/4" capacity in steel, 1/2" capacity in hardwood, 1200 to 1500 rpm speed under load, 2000 to 2400 rpm no load speed. Precision anti-friction bearings. Automatic trigger switch. Specially designed gear train for maximum torque transfer. Overall length, 8". For 115 VAC, 25-60 cycles. Shpg. wt., 4 lbs. Net 7.88 HO-708

THOR-SPEEDWAY 3/8" ELECTRIC DRILL




64-PIECE PROFESSIONAL POWER WORKSHOP 1995

- A Complete Workshop For Do-It-Yourself Jobs
- Drills, Sands, Grinds, Buffs, Saws • Home, Garage, Shop

Here is the complete electric power workshop at Lafayette's typical low price. You can do almost every at-home job with this versatile 64-piece set. Look what you get: Thor-Speedway 3/8" electric drill, 11-pc. power boring set with bits from 1/4" to 1 1/4"; 14-pc. twist drill set with metal index; 12-pc. sanding and polishing set; 7-pc. grind and buff set; 9-pc. 7-size hole saw; 7-pc. countersink and drill saw set; 3-pc. power screwdriver attachment. The Thor-Speedway 3/8" drill has 2.5 amp., 110 V AC motor. No-load speed, 1750 rpm; full load speed, 1150 rpm. Special alloy bearings throughout. U.L. approved. Shpg. wt., 10 lbs. Net 19.95 HO-976

NEW! WEN ZIPP SAW, MODEL 920



33.05

NO MONEY DOWN

- Cuts Anything—Anywhere—Fast
- 1/2 HP, 4.25 Amp Motor
- "Free Hand" Cutting

The new Wen Zipp Saw handles like a keyhole saw, but the motor does the work. Uniquely designed base plate permits cutting flexibility without adjustments. Cuts metal up to 1/2" steel and wood up to 6x6"; flush cuts: fine scrollwork. Powerful 1/2 HP motor delivers 3200 1" strokes per minute. Heavy-duty roller and oilite bearings; heavy-duty hardened gears. Conventional saw grip with finger control trigger switch. Use it anywhere—from a construction job to a hobby shop. 115V, AC. Shpg. wt., 8 1/4 lbs. Net each 33.05 HO-99 In lots of 3 Net each 29.37

THOR SPEEDWAY 1/2" ELECTRIC DRILL

Featuring the Motor that Won't Burn Out

- Complete Drill UL Industrially Rated & CSA Approved
- Powerful 4.0 Amp Rating
- Precision Hobbled Steel Gears

21.33

No Money Down



An outstanding value featuring a universal series wound motor that won't burn out. Top handle and 2-position rear handle are removable. Top quality construction with precision hobbled steel gears. 1/2" capacity in steel, 2" in wood. No-load speed 600 rpm; full load 400 rpm. AC-DC momentary contact switch with locking pin; special alloy self-oiling bronze bearings. Lustrous hi-polish finish with rich black crackle trim. Overall length 14 1/2". Shpg. wt., 12 lbs. Net 21.33 HO-999

METEOR JIG SAW

- With 3 Assorted Wood and Metal Cutting Blades



13.88

Enjoy new versatility sawing curves, scrolls, straight and rip cuts. Powerful 3-amp motor cuts 2" in wood, 1 1/2" in steel. Adjustable plate permits accurate angle cutting to 45° on either side—cuts 2x4's at 45°. No load speed 3000 strokes per minute; AC/DC positive push-through switch; self-oiling bronze bearings. Auxiliary knob handle; rip guide; 3 blades. Base tilts to 45°. 6-ft., 3-wire cord. Standard 115V. Shpg. wt., 5 lbs. Net 13.88 HO-439 Pkg. 5 Wood & Metal Cutting Blades Net .59

METEOR ORBITAL SANDER

- Push-Button Switch



11.89

A motor-driven power sander for home and shop. Idea for rough or finish sanding, polishing, massaging. Fast powerful action, lightweight, easy to handle. Special self-oiling bronze bearings; teflon coated thrust washer and ball bearing on sander drive plate. 2-pole induction type, 1.8 amp motor; no load speed 3450 rpm push-button switch. Sanding area 4 1/2 x 5 1/2". Hi-polish finish with black crackle trim. 115V, 60 cycle AC. 6-ft. 3-wire cord. Shpg. wt., 6 lbs. Net 11.89 HO-94
HO-865 Lambswool Polishing Pad Net .75
HO-866 18 Sheets Assorted Sandpaper Net .98

WEN 'SOUPED UP' SABRE SAW MODEL 909

- HEAVY DUTY—FULL 6 AMP.
- 1/2 H.P. MOTOR—1" STROKE
- LARGEST CUTTING CAPACITY
- 6" 90° CUT • 4" 45° CUT



NO MONEY DOWN

33.05

Bigger—more powerful—more versatile—faster cutting. Super-long blade easily cuts through 6x6" lumber. Cuts 4x4" at a 45° angle! Power enough to cut steel plate up to 1/2" thick—iron pipe up to 2" in diameter. Comfortable—conventional saw grip with auxiliary knob for 2 hand control. Saw tilts 45°—sole plate always remains flat. Finger control trigger-switch. Constant air stream flows dust from line of cut. 3400 1" strokes per min. Includes seven blades for cutting wood—steel—hardboard—sheet metal—pipe—leather—rubber—formica—etc. Equipped with rip guide and circle cutter guide. 8 ft., 3 cond cord and adapter. 110 watts 6 amp., AC-DC. 8 1/2 x 7 1/2 x 7 1/2" H. Shpg. wt., 8 1/4 lbs. Net 33.05 HO-466
Net each in lots of 3 29.37

SPRAYIT 600 PROFESSIONAL-STYLE SPRAY UNIT

- Integral Compressor-Motor
- All-Aluminum Spray Gun
- Sprays Oil, Paints; Stains




29.95

NO MONEY DOWN

All-purpose spray unit that gives professional results from the start. Adjusts pattern from small-as-a-dime to a fan 10" wide—4 times faster than a brush, and cleans easier too. Easy-to-use 2-finger trigger gun. Never needs lubrication. Air delivery: 1.5-2.0 CFM @ 15-20 lbs. Complete with 6-ft. cord with plug, 8-ft. hose with connections. Net 29.95 HO-933 Shpg. wt., 11 lbs.

MODEL 4100 VERSAMATIC



11.25

- WITH YANKEE STYLE BIT HOLDER
- TURNS 1/4" DRILL INTO HIGH POWER TOOL
- REVERSES—INCREASES POWER—REDUCES SPEED

Seven to one speed reduction develops tremendous torque! Hand clutch control for easy, instant stop-start action! Look at these fabulous features! Power screwdriver—handles largest screws—reverses to extract them! Power drill tapping head! Plenty of power for oversize drilling! Perfect for concrete or any kind of masonry drilling! Low speed and high power for hole saw attachments! A professional tool that anyone can use! Comes complete with screwdriver bit—Phillips bit—socket set adapter—wrench pin and instruction book. Shpg. wt., 5 lbs. Net 11.25 HO-195

1/2" CHUCK FOR VERSAMATIC

Geared chuck—1/4" to 1/2" capacity—#33 taper to fit Supreme Versamatic. Shpg. wt., 1/2 lb. Net 7.35 HO-268

JACOBS TYPE DRILL CHUCK



2.98

Comparable to Jacobs 18 Key type geared tool chuck. Capacity 0-1/4" thread 3/8x24". Ruggedly constructed. Polished finish. Used as standard equipment on most electric drills. Made to rigid specifications. Compare our really low price. You'll find this same chuck selling for twice as much! Net 2.98 HO-186 Shpg. wt., 1 lb.

STANLEY HEAVY DUTY SABRE SAW



31.47

- CUTS FLUSH TO A WALL
- FULL 3/8" STROKE—3300 STROKES PER MINUTE
- ANTI VIBRATION MECHANISM

New Stanley Heavy Duty Sabre Saw—rugged enough to cut 1/2" steel bars. Will do the work of rip, crosscut band, jig, keyhole and hack saws. Particularly suited for use where it's difficult to use a circular or band saw. Cuts curves, scrolls, pockets, intricate patterns in wood, plastics, veneers. Cuts full 2" lumber—conduit—cable—1/2" steel bar—aluminum—brass. 2 position base plus flush cutting blade allows cuts right up to a wall. Improved chip blower—single screw blade lock—positive slide switch—cool, comfortable handle. 2.5 amp. 115V, AC/DC motor. Includes one each wood—metal—and flush cutting blade. Shpg. wt., 6 1/2 lbs. Net 31.47 HO-701

RAM BUFF-'N-SAND

23.73

NO MONEY DOWN



- Two Tools in One
- A Combination Polisher Buffer & Sander

A rugged all-purpose polishing and sanding tool half the weight of similar units. Perfect for sanding or polishing furniture, cars, floors and walls. Engineered to operate at 500 rpm to avoid hi-speed heat and friction on working surfaces. Universal AC-DC motor employs thrust ball bearings for smooth rotary action. Supplied with heavy duty 3-conductor cord, 7 1/2" O.D. lambswool bonnet and 24 sanding discs. Overall length 13 1/2". Shpg. wt., 5 1/2 lbs. Net 23.73 HO-931

ARCO SCREW & NUT DRIVER ELECTRIC DRILL ATTACHMENT




5.84

- Complete 15 Piece Screw and Nut Driver

For rapid fastening of both screws (slotted and Phillips) and nuts (hex and square head). Has non-slip industrial type clutch for fast easy driving. Bit holder prevents screw head slippage. Includes flat bits and bit holders for #4-8 and #8-14 screws, #1-2 Phillips head bit, 6 hex socket wrenches (1/4", 3/8", 1/2", 3/4", 1", 1 1/2"). 2 sq. socket wrenches (1/4", 3/8") and socket wrench holder with ball lock. Net 5.84 HO-944 Shpg. wt., 1 1/2 lbs.

LAFAYETTE DIRECT IMPORTS Compare for VALUE!

TESTED AND SELECTED FOR CONSISTENT QUALITY



35mm CAMERA SPECIAL—THE RANGEFINDER III

- 4 Element F2.8 Coated Lens!
- Coupled Rangefinder • Luminous Bright Frame View-Range Finder!
- Single Stroke Rapid Film Transport!
- Nine Shutter Speeds to 1/300!
- MX Synchronization • Hi-Speed Rewind!
- Standard PC Flash Terminal!
- Double Exposure Prevention • Built-in Self Timer!

28⁸⁸ No Money Down

Fast F2.8 coated anastigmat lens and extra-wide lens aperture for brilliant, sharper full color or black and white. Sight and focus through combined range-view finder. Fully synchronized at all speeds for class M and electronic flash. Speeds from 1 sec. to 1/300th. Rapid advance sets shutter, counts exposure and transports film. Built-in delayed action timer—automatic exposure counter and film stop. 20 or 36 exposures on black and white or color 35mm film. PC flash terminal. Use series 6 accessories.

F-778L Less Case. Shpg. wt., 3 lbs. Net 28.88
 F-779L Leather Eveready Case. Shpg. wt., 1/2 lb. Net 3.95
 Auxiliary Wide Angle and Telephoto Lens Set for "Rangefinder III" F-808L Shpg. wt., 1 1/2 lbs. Net 15.96
 Optical Viewfinder for Wide Angle and Telephoto Lenses. F-847L Shpg. wt., 6 oz. Net 3.39



NEW AIRES PENTA 35 REFLEX


- 50mm 4-ELEMENT F2.8 LENS
- EXCEPTIONALLY BRIGHT PENTA PRISM VIEWING WITH "BULLSEYE" SPLIT-RANGE RANGE FINDER
- FULLY AUTOMATIC DIAPHRAGM
- 11 SHUTTER SPEEDS TO 1/500
- LVS SYSTEM—CROSS-COUPLED APERTURE AND SPEED SETTINGS
- FLASH SYNCHRONIZED AT ALL SPEEDS

NO MONEY DOWN
54⁹⁵ ONLY

BUY ON TIME

A fine camera with professional capabilities and the ease of use the amateur requires. The large penta prism finder shows an unreversed, accurate color fidelity view of what will be recorded on the film. Unusually bright, clear to the corners. Parallax-free. "Bullseye" image for simple focusing and centering. The automatic diaphragm allows full-aperture viewing and focusing; stops down to pre-set opening automatically, and returns to full open when film is advanced. Single-stroke

lever advances film, cocks shutter and sets exposure counter. 10 speeds to 1/500th plus B. LVS system of cross-coupled aperture and shutter speed settings with one knurled ring. Fully flash synchronized. M and X. Built-in self-timer. Click-set shutter and aperture scales. All settings visible from top of camera. Accepts standard 20 or 36 exposure color or B & W film. Less case. Shpg. wt., 3 1/2 lbs. Net 54.95
 F-860L Net 54.95
 F-861L Leather Eveready Case Net 4.95



KALIMAT "35" CAMERA KIT

- 35mm Electric Eye Camera + Flash
- Automatic Exposure Control
- Double—exposure Prevention
- Automatic Film Exposure Counter
- Die Cast Aluminum body

A LAFAYETTE PHOTO SPECIAL
37⁹⁹ ONLY No Money Down

Here is the camera you have been waiting for. No fumbling with exposure. No fumbling with different films—you can get a perfect exposure every time—automatically. A low price exclusive—the Kalimat "35" has a "viewfinder signal" which indicates when there is insufficient light to take a picture. In addition this camera automatically sets the exposure according to light conditions with a built-in meter. Other features include: fast single stroke film advance and shutter cocking lever, 40mm color corrected lens, bright frame viewfinder and built-in flash synchronization. The complete kit is supplied with camera, flash gun and leather carrying case. F-845L Shpg. wt., 6 lbs. Net 37.99



MAMIYA AUTOMATIC 16 SUBMINIATURE CAMERA

Featuring Exclusive Built-in Exposure Meter and Cross-Coupled Exposure Control.

- Fast, Clear F:2.8 lens • Focus—1 ft. to infinity • Shutter Speeds — B, 1/5-1/200
- Built-in Filter and Flash Synchronization • Life-Size Viewfinder • Automatic Exposure Counter • With Soft Leather Case and Braided Leather Wristband

Only **49⁹⁵** NO MONEY DOWN

The fabulous Mamiya 16 automatic combines professional quality and features with the simplicity of operation found in a box camera. Pocket size—it is always available to make that special shot often missed by slow, bulky cameras. With the automatic Mamiya 16, you achieve correct exposure all the time. The extremely wide shutter speed range—from B, 1/5 second up to 1/2000 second; the fast F2.8 Mamiya-Sekor lens, and built-in exposure meter all combine to give accurate exposure control suitable for making enlargements of high—magnification. Focusing is adjustable from 1 ft. to infinity for maximum sharpness. Capable of high speed candid photography. Other features include: protective lens cover, built-in filter, flash synchronization, and automatic exposure counter. Dimensions 4 1/4 x 1 3/8". F-843L Shpg. wt., 1 1/4 lbs. Net 49.95

NEW! TRANSISTORIZED ELECTRONIC STROBE FLASH

Operates from Batteries and AC



- Lightweight & Compact — No Power Pack Needed • Fully Transistorized • Operates on 4 Economical "Z" Cell Batteries • Fits any Camera Shoe

21⁵⁰ NO MONEY DOWN

Now you can have a high-powered, transistorized electronic flash that operates from standard AC house current or 4 economical "Z" cell batteries. Compact and featherweight—no power pack is required. Flash duration of 1/20000 sec. for fast pictures. Recycling time: 6-10 seconds; color temperature: 6000° Kelvin. Guide number dial for F stop on back. Complete with AC cord. Less batteries. F-827 Shpg. wt., 2 lbs. Net 21.50
 Batteries for above (4 required). Net each .095 BA-155



NEW! COMMANDER CAMERA OUTFIT

EVERYTHING YOU NEED FOR PICTURE-TAKING

- Nothing else to buy • Built-in Flash • Perfect for the beginner
- Makes Super Slides • Shoots Color or Black & White

ONLY **8⁸⁸**



INDOORS OR OUT—you can't go wrong with this new Commander camera. Makes an ideal gift too for birthdays and graduations. Look at what you get. A fine Commander camera which features double exposure prevention, built-in flash synchronization using tiny AG-1 bulbs for perfect indoor snaps; large optical viewfinder to see what you're taking and the American Optical Nycron lens is capable of shooting color or black and white film with perfect clarity. Also included are 2 rolls of Kodak 127 Verichrome pan, 2 penlight cells, 6 AG-1 miniature flash bulbs and a handy neck strap. The camera is guaranteed for one year, takes 12 jumbo pictures on roll of 127 size film. F-844 Shpg. weight of Commander Set, 2 lbs. Net 8.88

BOOSTER EXPOSURE METER

- Includes booster—Leather cases—neck cord
- Stills or Movies • ASA Scale—LVS Scale

6⁴⁵



Extremely versatile—extremely simple. Highly legible direct reading dial. Speeds from 4 sec. to 1/1000 sec. Lens aperture settings from f:1 to f:32. ASA scale 6 to 800. LVS scale 1 to 18. Cine scale 8, 16, 24 and 32 frames per second. Booster cell makes possible readings at extremely low light levels. Small-rugged-light-weight. Includes booster cell, leather cases, neck cord and instructions. Shpg. wt., 1 lb. F-349L Net 6.45

LAFAYETTE AG FLASH GUN

- Compact in Size
- Made for the New AG Bulbs
- Dependable B-C Operation

2⁹⁹



The new Lafayette AG flash gun is a compact, palm size yet offers dependable B-C operation. Made for the new AG flashbulbs which are small in size and big in performance. The Lafayette flash gun has a fan-type reflector which measures 2" in diameter when opened. Standard shoe fits all standard accessory clips. Features a Computer Dial for determining correct F stop, Testlight for checking battery and bulb, and Bulb Ejector. Complete with cord. Operates on 15V battery (not incl.). Shpg. wt., 8 ozs. F-699 Net 2.99
 RA-116 15-Volt Battery for above Net .81

MANSFIELD 300 WATT 35MM PROJECTOR

Self Contained Case


- Brilliant 300 Watt—Turbo Blower Cooled
- 4 Inch, 13.5 Coated, Corrected Lens
- Designed for Easy Operation

28⁹⁵ NO DOWN PAYMENT

- For All 35 mm, 2 x 2 and Super Slides

Compact, convenient, semi-automatic, plus big-picture, 300 watt brilliance. Takes all 2x2 inch slides—35mm 828 (bantam) and 127 (super-slides). Semi-automatic "Presto-Matic" changer, one push-pull movement picks, shows and replaces 36 slides in sequence. Self-contained storage for over 100 slides. Die cast aluminum. Self-contained case. All optics hard coated. Designed for optimum projection brilliance. For 110-120V. AC/DC. Shpg. wt., 12 lbs. F-667 Net 28.95

NEW! DROPPRONT "PRO" BAG



- BIG 13x7x9 1/2"
- LUGGAGE-STYLE PROFESSIONAL BAG
- ACCEPTS ALL CAMERAS—FROM MOVIE TO PRESS-TYPE
- EXCEPTIONALLY RUGGED AND DURABLE

ONLY **9⁹⁵**

A heavy-duty professional bag with plenty of room for all your equipment. Zippered, for easy access. Luggage styled for easy, hand or over-the-shoulder carrying. Removable, adjustable straps snap on or off in an instant. Durable, chrome plated front snap-lock, feet and hardware. Handsome, heavy, rich looking, black simulated cowhide with leather and corduroy lining. Gussets prevent contents from falling out when front is open. Front tripod carrying straps. Measures 13Lx7Wx9 1/2"H. Shpg. wt., 3 lbs. F-862 Net 9.95

"PRO" ELEVATOR TRIPOD

- Holds Heaviest Equipment
- Velvet Smooth Panning Action
- Extends to 46 1/2"—Elevator Adds 10"—Closes to 22"

ONLY **11⁹⁵**

All aluminum construction. Gear drive elevator with positive lock. Large, cushioned pan head fits any camera. Head pans 360°—tilts 180°. Legs lock at any height. Lock and unlock with a half twist. Completely rigid, even when fully extended. Long section construction for maximum stability. Over-size thumb locks and handle for ease of use. Velvet smooth action in all planes of motion. Positive leg stops prevent overspread. Rubber tipped feet for solid footing on any surface. Satin black and aluminum finish—chrome trimmed. Shpg. wt., 4 lbs. F-850 Net 11.95



New! LAFAYETTE REFLEX ZOOM F/1.8 MOVIE CAMERA



ZOOM f 1.8 REFLEX CAMERA with AUTOMATIC ELECTRIC EYE

ONLY
69⁹⁵
NO MONEY DOWN

- f 1.8 Focusing Zoom Lens
- Zooms in Focus From 3 Ft. to Infinity
- Reflex Viewing—You Look Thru The Lens
- Automatic, Cross Coupled Electric Eye Photometer
- Uses Any Film ASA-10 to 100
- Trigger Action Pistol Grip

You see precisely what the camera lens see, through the lens true reflex system. Nothing can match a Zoom Lens Movie Camera for unusual, dramatic effects and all-around versatility. Focusing through the zoom lens is universal. You get needle sharp zoom pictures from Wide Angle through Normal to Telephoto—by extending a single lens. The automatic electric photometer needle is visible in the view finder and cross-coupled to the shutter diaphragm. Just match the needle in the view for perfect film exposure. Calibrated for ASA 10-25-32-40 and 100 film speeds. Needle sharp focusing from 11mm wide angle to 33 mm telephoto. Three way operation provides normal run, back and single frame for special effects. Standard "double — 8" roll is quick loading spool type. Lens: Zoom f 1.8 with focal lengths variable from 10mm at wide angle to 30mm telephoto, zooming ratio 1:3. Quiet ratchet wind motor has a continuous run of 6 ft. (30 sec. @ 16 fps), on one full wind. Sturdy die cast body in two-tone charcoal black and gray. Precision 0-25 footage counter. Trigger action, pistol grip handle provides a firm, comfortable grip for smooth, steady pictures.

F-864L Expertly crafted in Japan. Shpg. wt., 5 lbs. Net 69.95
ZOOM CASE: Holds camera with pistol grip attached. Room for accessories. Measures 10x8 1/2 x 3 3/4". Net 5.79
F-784 Shpg. wt., 2 lbs.

THE REMARKABLE LAFAYETTE f 1.8 TRIPLE TURRET 8 mm MOVIE CAMERA with Built-In Exposure Meter

- 3 TURRET INTERCHANGEABLE f 1.8 LENS — Wide Angle — Normal View-Telephoto
- Built-in Wide Scale Electric Eye Exposure Meter With Exposure Guide
- THREE Built-in Filters — For Color, Normal and Bright Scenes

- Pistol Grip With Trigger Release
- "Combe-View" Finder — For Normal, Wide Angle and Telephoto Areas
- Ratchet Spring Wind

was 39⁹⁵
29⁹⁵
NO MONEY DOWN

Lafayette is proud to offer a modern 8 mm movie camera that is ready for "rapid fire" shooting. A three turret assembly for instant change over to one of three lens, electric eye exposure setting, and pistol grip trigger release are time saving features the serious moviemaker should not overlook. A twist of the turret selects wide angle (f = 6.5 mm), normal (f = 13 mm), or telephoto (f = 25 mm), f 1.8 coated and color corrected lens. Turret action is smooth and positive. There is no need to fumble with focusing adjustments—all lens are prefocused. The built-in exposure meter takes all the guess work out of exposure setting. Wide scale meter is matched with exposure guide to obtain proper lens opening, for perfecting filming. Also built-in are 3 filters: "conversion" for color film, "haze" for normal black and white and "neutral density" for extremely bright scenes. A choice of 4 speeds, 12, 16, 24 and 32 frames per second plus single exposure. Slide rule footage counter. Spring wound ratchet type motor runs 6 feet of film on a single winding. Exposure guide is calibrated for ASA 10 to ASA 40 film speeds. Direct optical viewfinder. Rugged die cast case in blue and gray. Trigger action, pistol grip handle and leather wrist strap included. Made to our specifications in Japan. Shpg. wt., 5 lbs.




F-702L Net 29.95
F-648 Holster Case for F-702. Shpg. wt., 8 oz. Net 2.95



ZOOM MOVIE OUTFIT

149⁹⁰
NO MONEY DOWN

A complete Zoom movie outfit with matched components to assure success in taking and showing home movies. The camera is Lafayette's Zoom f 1.8 Reflex (F-864L), "Ultra" 500 projector (F-785WX), 30"x40" folding screen (F-536), new Hi Lite movie gun (F-868M), 2 Sets of 400' reels & cans (F-538), Zoom camera case (F-784), 25 ft. roll of Kodak movie film with processing (F-576).
F-866WX Shpg. wt., 40 lbs. Net 149.90



MANSFIELD "ULTRA" 500 WATT 8 mm MOVIE PROJECTOR

- FAST, EASY LOADING
- FORWARD, STILL & REVERSE
- SELF-CONTAINED CARRYING CASE

No Money Down
59⁹⁵

The new "Ultra" 8 mm projector features several unusual conveniences to uncomplicate movie showing. Has swing-out gate for fast threading. Forward, Still and Reverse positions. Bright 500 watt DFA lamp gives uniformly bright picture. Cinepar .750" f/1.6 lens. Self contained carrying case.
F-785 WX Shpg. wt., 10 lbs. Net 59.95
F-786 Replacement Lamp (DFA) Net 2.78

MATCHED MOVIE OUTFIT

79⁹⁵
No Money Down

Everything you need for movie-making and showing fun. No need to "shop" for unmatched equipment, no need to pay more. You get all this: Lafayette's F-702, f 1.8, Triple Turret movie camera with exposure meter; holster type camera case; "Holiday," F-526, 500-watt projector; F-536 30x40" screen; F-537 Bar Light; 2 F-539 photo flood lamps; 2 F-538 400' reels and cans. Unbeatable for foolproof shooting and showing of indoor and outdoor movies.
F-789WX Shpg. wt., 30 lbs. Net 79.95



BIFLEX "LENS MASK" FOR POLAROID CAMERAS

- Cuts Film Costs in Half
- Makes Trick Shots Possible
- Doubles Your Enjoyment

4⁰¹

Here is an amazing device which will pay for itself the first two times you use it. Simply slips over your Polaroid camera lens and presto—you get 16 pictures from each 8 exposure roll of Polaroid film. Each double frame is 2-9/10" high by 1-4/5" wide. Does not introduce optical distortion, merely covers half the lens for each shot. Fun to use too, many types of trick photographs are possible. Shpg. wt., 6 oz. For series 95, 95a, 95b, 100, 150, 700, 800, 850, 900.1. Net 4.01
F-825L Biflex #1 For Series 110, 110a, 110L, J66 Net 4.02
F-826L Biflex II Net 4.02

AUTO-DIAL EXPOSURE METER

7⁹⁹

Holds its reading indefinitely. Meter is aimed and dial stopper depressed. The dial then swings to correct reading and remains fixed when stopper is released. Ideal for widely variant light conditions. Color and black and white calibration with ASA speeds to 25,000. Reflected and incident light read on same scale. EVS 1 to 19. Lens: f/1.0 to f/32. Direct reading cine speeds 8-64 fps. Meter has zero adjust. Leather carrying case and neck strap. Imported.
F-791L Shpg. wt., 1 lb. Net 7.99




"35" CLIP-ON EXPOSURE METER

3⁹⁵

- FITS CAMERA ACCESSORY SHOE
- ASA SCALE 10 TO 1000



Exceptionally convenient exposure meter. Clips right on camera—quick easy reading. Gives better, more accurately exposed pictures with a minimum of effort. Speeds 1/1000 to 1 Sec. Lens aperture f:1.4 to f:22. Mounts on camera or may be hand held. Complete with leather case and instructions. Shpg. wt., 1/2 lb. Imported.
F-351L Net 3.95



CLOSE UP KIT

7²⁵

Focus as close as 6 inches from your subject. Take portraits—small still lifes—do photocopying. Includes 3 snap-on close up lenses, leather case and built in tape for accurate focusing. Shpg. wt., 8 ozs.

F-721L for all except 110B, 110A, 110, J33, J-66 Net 7.25

PICTURE ROLLS 10 SECOND DEVELOPING TIME

32 and 42 are panchromatic types with an exposure index of 400 and 200 respectively. 37 and 47 have index ratings of 3000 and are used with the wink-light for indoor shots at normal room lighting levels. Shpg. wt., per roll, 5 ozs.

Stock #	Type	Camera Model	Net Per Roll	Net ea. in Lots of 3
F-712L	47	All Except 80 Series, J33	1.89	1.80
F-713L	42	All Except 80 Series, J33, J66	1.77	1.68
F-714L	37	80B, 80A, 80, J-33	1.48	1.40
F-715L	32	80B, 80A, 80	1.38	1.30

NEW! "HI-LITE"™ MOVIE LIGHT

- Mounts Like a Flash Gun
- Fits Any Camera
- New Dual Reflector Lamp Folding Flex-Angle Bracket

5⁹⁰



A completely new lamp design that creates a uniform, soft lighting effect that simulates sunshine. Evenly illuminates subject and background to give needed depth and roundness. The secret is in the dual reflector: one spherical and one elliptical surface, producing a broad beam of soft even light. The subject is bathed in a controlled, broad beam without uneven illumination or exaggerated effect. The quality of the light adds sparkle and aids texture. The beam angle is approximately 100°, average color temperature 3200°K. The flex-angle bracket adjusts to practically any desired angle. Convenient thumb switch is located for use while gripping the camera and light assembly. 500-watt, Dual Reflector lamp. For 110-120 V AC. Shpg. wt., 2 lbs. Imported.
F-868M Net 5.90

NEW DUAL REFLECTOR PHOTOFLOOD LAMPS
F-854 500 watts Net 1.95
F-853 300 watts Net 1.65



GENUINE LEATHER GADGET BAG

4⁹⁵

Genuine pigskin—not plastic. 7 1/2" x 10 1/2" x 4". Holds your camera and all accessories. 20" zipper top. Pouch in lid holds filters, etc. Outside pouch with strap and buckle. All brass hardware. Loops and straps on bottom to hold tripod. Includes shoulder strap and pad. Shpg. wt., 1 lb.
F-326 Net 4.95

LAFAYETTE ZOOM LENS

6⁹⁵

- Fill the Screen From 12' to 15' feet—then ZOOM in!

The very latest in projection accessories for the movie fan. Coated, f1.5, 15 to 25mm focusable zoom lens fits most popular priced projectors. Converts our own "Holiday" (F-526) into a modern, zoom projector. Adds realism and depth to old "reels." Fills a 30x40" screen at from 12' to 15'—then zooms in for exciting closeups. Show your movies at the size you want—without moving projector or screen. Imported.
F-690L Shpg. wt., 6 ozs. Net 6.95

NEW! ZOOM OPERA GLASS

Coated Zoom Optics 2 to 4 x 30
Perfect for Sports, Theater

10⁹⁵



Zoom in on your subject—make it big as life. Actually magnifies 2 to 4 times larger than can be seen with the naked eye! Just right for the opera, sporting events, bird watching or all around use. Small enough to fit in your pocket, exceptionally lightweight. These glasses feature zoom optics, 2 power to 4 power. Brings everything up close fast. Individual focus with master zoom control. Coated optics and wide angle give an amazingly clear view. Compares favorably with larger binoculars. Neck band and zipper leather case included. Shpg. wt., 1 lb. Imported.
F-835 *Add 10% Fed. Excise Tax Net 10.95*

MOVIE & SLIDE PROJECTION LAMPS



Exact replacement projection lamps for most movie and slide projectors. Make your pictures sparkle with a new, efficient lamp. Imported. Avg. shpg. wt., 6 ozs.

Stock No.	ASA Code	Watt	Base Type	Net Ea.
F-869	DCA	150	4-Pin	2.70
F-786	DFA	150	Prefocus	2.70
F-741	CLS	300	Bayonet	1.40
F-742	CLX	300	Bayonet	1.40
F-743	CMV	300	S.C. Bay	1.40
F-744	CYC	300	S.C. Bay	1.40
F-750	CWD	300	Prefocus	1.69
F-871	CZA	500	4-Pin	2.49
F-747	EDK	500	Bayonet	1.79
F-745	CXZ	500	Prefocus	1.79
F-746	DAK	500	Prefocus	1.89
F-748	DOB	750	Prefocus	2.15
F-749	DFD	1000	Prefocus	2.90

ELEVATOR TRIPOD

- Folds to 16" including Panhead!
- Extends to 47" PLUS 7" Elevator!
- Tri-Tilt head — Moves in 3 planes!

8⁵⁹

For any small camera—35 mm—reflex—or movie. Professional quality for professional results. Strong—steady—lightweight. Pencil slim, chrom plated, brass legs. Lock securely in place—fold down readily. Single action tilt-pan—and swing over for taking pictures in vertical or horizontal format. Geared elevator center-post with positive lock and folding crank. Weighs only 31 ozs. All the most wanted features in one tripod. Shpg. wt., 2 1/2 lbs. Imported.
F-339 Net 8.59

LAFAYETTE TELESCOPES ARE WORTH LOOKING INTO!



269.50
NO MONEY DOWN

189.00
NO MONEY DOWN

79.50
NO MONEY DOWN

39.95
NO MONEY DOWN

16.95

Arcturus

• 454x with Barlow Lens

3" EQUATORIAL REFRACTOR

- Ultra Precise Helicoid Focusing • 7 Coated Eyepieces Plus Barlow Lens • 76.2 mm Clear Aperture
- Most Advanced Equatorial Mount • 25x, 42 mm Finder Scope

79-mm hard coated, air-spaced Fraunhofer achromat of 910-mm focal length with 3" clear aperture, focal ratio of f/12 and resolving power of 1.6". Seven coated eyepieces provide magnifications of 227x, 152x, 101x, 73x, 35x, 18x and 25x through viewfinder. Helicoid focusing by means of a massive wheel and helicoid gear. Finder Scope, with rack and pinion focusing, features a 1.6 inch clear aperture objective of 500-mm focal length. Micro-motion controls with extended flexible shafts and compression locks in all axes. Accessories: include three sunglasses, moon-glass, sun diagonal, two star diagonals, sun projection screen, erecting prism, heavy extensible field tripod, brace, accessory shelf, separate wooden cases for telescope and mount. Shpg. wt., 100 lbs. VIA EXPRESS ONLY. F-385WX

Net 269.50

Galactic

• 454x with Barlow Lens

RESEARCH QUALITY 3" EQUATORIAL REFRACTOR

- Viewfinder Scope 25x, 42-mm • 910 mm Focal Length • 76.2 mm Clear Aperture • Micromotion Controls for Declination and Right Ascension • Resolving Power 1.6 • Barlow Lens Included

The objective lens is a 79-mm, hard coated, air spaced Fraunhofer achromat with a clear aperture of 76.2 mm (3"). Focal length 910 mm, focal ratio f/12, resolving power 1.6". Seven coated eyepieces provide magnifications of 227x, 152x, 101x, 73x, 45x, 35x plus 25x through the viewfinder. Barlow lens add ranges of 454x, 304x, 202x, 146x, 90x, 70x and 50x. Focusing by means of micro-precision rack and pinion drive. The viewfinder scope has a 42-mm (1.6 inch clear aperture) objective—500-mm focal length-rack and pinion focusing—and will accommodate various eyepieces. Finely calibrated hour and declination circles for rapid finding and setting. Body tube of white enameled aluminum. Accessories include three sunglasses, moon-glass, two star diagonals, sun diagonal, erecting prism, sun projecting screen, extensible field tripod, chain brace, accessory shelf, wooden cabinet. VIA EXPRESS ONLY. F-384WX Shpg. wt., 60 lbs. Net 189.00

Polaris

• 320x with Barlow Lens

2.4" EQUATORIAL REFRACTOR

- Eyepieces for 160x, 88x, 40x, Barlow Lens gives 320x, 176x, 88x • 800 mm. focal length • 62-mm objective • Micromotion adjustments on both axes • Coated optics throughout • Equatorial mount

Objective: Fraunhofer-type achromat, hard coated, 62.5-mm., 800-mm. focal length. Collects about 75 times as much light as the naked eye, resolving power 2 seconds, faintest discernible star 10.7 magnitude. Eyepieces are hard-coated Huygenians. 160x (5-mm), 88x (9-mm), 40x (20-mm). Barlow Lens included give ranges of 320x, 176x and 80x. Finder scope is 6x, 30-mm. Tripod head with latitude adjustment. Clamp lever for declination and inclination. Accessories include sunglasses, star diagonal, erecting prism, sun projection screen, field tripod, wooden case. Rack-and-pinion focusing. Heavy plating to prevent rusting.

F-342WX Shpg. wt., 30 lbs. Net 79.50

F-391 4-mm. orthoscopic eyepiece for 200x (400x with Barlow Lens) Net 8.95

(A) ZOOM SPOTTING SCOPE

- Any Power from 15X to 30X!
- Ideal for any "Spotting" Need!
- Pan-Head, elevator Tripod

True Zoom action—finger tip control—from 15 power to 30 power. Choose the right power for any "spotting" or viewing need. Brilliant image at any power. 50mm objective, hard coated for maximum light gathering power. Prismatic system greatly reduces length—only 15" overall. Precisely machined, all metal body. Lightweight scope alone weighs only 2 lbs. May be hand held or used with tripod supplied. Precision fingertip focusing with oversized, milled ring. Aluminum and chrome-brass tripod adjustable from 12" to 18". Locking pan-head swivels and tilts to any angle. Optical train is fully hard coated. Shpg. wt., 5 lbs. F-685 Net 39.95

(B) 30x, 60mm SPOTTING SCOPE

• Coated Optics • Complete With Leather Case
Field of view is 85 feet at 1000 yds.! Both front and rear optics are coated. High relative brilliance due to 60mm objective lens. Exceptionally small and light—weighs only 2 lbs. including metal tripod! The perfect companion for shooting—hunting—viewing—naturalists—and hobbyists. Equipped with 1 1/2" tripod and zippered leather carrying case. Shpg. wt., 3 lbs. F-149 Net 16.95



1200X "RESEARCHER"

- 25X to 1200X in 12 Ranges
- Full Range Fine Focus Adjustment
- Integral Mechanical Stage
- Rotating Diaphragm

44.50
NO MONEY DOWN

Closely parallels the "Society" grade microscope, yet is available at a very low price. Four Huygenian eyepieces: 5X, 10X, 15X, P20X combine with four achromatic objectives: 5X, 10X, 40X, 60X to yield 12 combinations: 25X, 50X, 75X, 100X, 150X, 200X, 300X, 400X, 600X, 800X, 900X, 1200X. Dual knob rack and pinion coarse focusing with tension adjustment for slow motion. Micro-motion fine focusing adjustment. Spring loaded to prevent objective from driving through slide. 85mm x 85mm stage can be moved in any direction, with slide, by 2 knurled screws while looking through the eyepiece. Sub-stage has rotating, 5-position diaphragm and 35mm plano/concave reflecting mirror. Stable horseshoe base. Complete with set of 5 basic dissecting instruments, 10 slides, pack of cover slips, tube of mounting fluid. All in a dovetailed wooden carrying case with handle and four rubber feet. Shpg. wt., 10 lbs. Imported from Japan. F-369 Shpg. wt., 10 lbs. Imported from Japan. Net 44.50

NEW! 1200X "MICRO-TECH" MICROSCOPE

19.95

- 80X to 1200X in 8 Ranges
- Built-in Sub-Stage Illuminator
- Dual Knob Lever Type Fine Focus • Complete Set of Dissecting Instruments

Perfect for the intermediate student or hobbyist. Huygenian eyepieces, 10X and 20X. 4 achromatic objective lenses. Magnifications of 80X, 100X, 160X, 200X, 400X, 600X, 800X and 1200X. Rack and pinion, coarse focus and lever type fine focus. Stage includes optical condenser, 5 aperture, diaphragm. Sub-stage illuminator-mirror combination for direct, incandescent illumination or reflected illumination. Spring loaded rack prevents damaging objective. Includes 2 prepared slides, 4 blank slides, spatula, scalpel, probe, scissors, tweezers and magnifying glass. Wooden case with carrying handle. Illuminator operates on pen-light cells or house current, by means of transformer. Less batteries. F-700 Shpg. wt., 6 lbs. Imported Net 19.95
F-701 Replacement bulb for F-700 Net .11
BA-155 Battery (2 required) Net ea. .095
Transformer: Permits use of house current for illumination of F-700 "Micro-Tech" microscope. Net 1.80
F-761 Shpg. wt., 8 ozs. Net 1.80



NEW 900X "ZOOM" MICROSCOPE


- 100X to 900X with Zoom Action
- Built-in Substage Illuminator
- Zoom Ratio 1 to 1.5 For Maximum Resolution

9.95



An excellent value for the beginning student or hobbyist. Features advanced zoom type micro-optics. Zoom action permits smooth, vibration-free, variable magnification without disturbing stage or specimen. Four hard coated objectives set in a revolving "click stop" turret give magnifications of 100X, 150X, 200X, 300X, 450X, 600X, and 900X. Zoom Action permits choosing multiple magnifications without changing eyepiece or objective. The eyepiece zooms smoothly from 10X to 15X. Illuminator operates with batteries or house current, by means of transformer listed below. Round hole disc diaphragm controls illumination. Includes instructions, sample slides and wooden carrying case. F-855 Less Batteries, Shpg. wt., 5 lbs. Net 9.95
BA-155 Batteries (2 required) Net .095
Transformer: Permits use of house current for illuminating F-855 Microscope. F-761 Shpg. wt., 8 oz. Net 1.80

LAFAYETTE BINOCULARS



AS LOW AS
17.95

Precise design—quality material—and expert workmanship. All lenses are hard coated—prisms clamped in lightweight alloy frame and body—sealed against dust and moisture—properly collimated and aligned. All are center focus with adjustable right eyepiece. Hand leather case and neckstraps included.

7X35 Popular, versatile, all purpose binoculars. For the sportsmen—hunter—bird watcher—vacationer. High luminosity. Compact design. Shpg. wt., 3 lbs. F-183 Net 17.95

7X35 Wide Angle. Top performance—highest quality. Almost twice the field of view of ordinary 7x35 binoculars. Spots and holds a moving target faster and easier. Oversize oculars and prisms. Shpg. wt., 3 1/2 lbs. F-184 Net 27.50

7X50 Navy style night glasses. Favored for marine use. The choice of professionals because of exceptionally high light gathering power. Superior image brightness. Shpg. wt., 3 1/2 lbs. F-164 Net 21.95

20X50 King of the long range. Hunters, mountain climbers, plane spotters, forest rangers—any long distance viewing and observation requirement. Shpg. wt., 4 1/2 lbs. F-185 Net 27.50

Add 10% Fed. Tax to the above prices.

TRU-ZOOM™

- Not a "Vari-Power"—One Control Zooms both barrels!

NO MONEY DOWN

39.95


*Add 10% Fed. Tax

- 7X to 12X— or any Power in Between
- Center Focus—Right Eye Adjust—Plus Single Synchronous Zoom Control! • The Perfect Power For Any View!

Sensational Zoom action holds even fast-moving subjects in perfect view. Sight in any subject at 7 power—then Zoom up to 12 power (or any four in-between) for closeup viewing. Full 40mm. objective lenses, hard coated achromats. Field of view is 290 feet at 1000 yds. at 12 power (5.5°). Prisms clamped in shock-resistant mounts. Lightweight alloy frame and body. Sealed against dust and moisture. Includes plush-lined, hard leather case and straps. Shpg. wt., 5 lbs. Imported. F-793 Net 39.95*



"MICRO'DAPTER"®



- Micro-photography! • Astro-photography! • Inexpensive — accurate — easy to use • Use any camera/microscope or camera/telescope set-up • Photo-record your observations

19.75

The MICRO'DAPTER permits the use of any camera—even movie cameras—with practically all microscopes and telescopes. May be used with all color and black and white film. No need to remove the camera lens. All exposures are made with the camera set at infinity. You view the specimen—choose the field of view—and focus while sighting through the MICRO'DAPTER's viewing telescope. Cross hairs are superimposed on the image for centering. The telescope is focusable for diopter variations. The viewing image is automatically in focus for the camera when viewed in focus through the MICRO'DAPTER. A special prism arrangement allows 15% of the light to pass through the viewing telescope for easy focusing. The camera shutter is operated in the normal fashion. Accessory sleeves permit the MICRO'DAPTER to be used with other than Society size microscopes. The MICRO'DAPTER may be used with any telescope by attaching to eyepieces of 29mm (1 1/4") maximum diameter. Complete with lateral viewing telescope, accessory sleeves and fitted case. Shpg. wt., 1 1/2 lbs. Imported from Japan. F-506 Net 19.75

LAFAYETTE GUARANTEED QUALITY—LOWEST PRICES FOR SCIENCE AND TECHNOLOGY

Minivac® 601 DIGITAL COMPUTER

95.00
NO MONEY DOWN

Not A Toy — Performs Functions of Full Size Computer — Solves Scientific and Business Problems



Model 6010

The Minivac 601 can be used by anyone with an inquiring mind. Designed to introduce teenagers and adults to the fascinating world of machines that "think". The 601 demonstrates how computers operate, what they can and cannot do by simulating computer applications in business, science and military. It can learn, remember, calculate, and make decisions. Indispensable to teachers, businessmen who need to keep up with modern technology, a first hand opportunity to explore space age techniques and experimentation. A set of six comprehensive manuals are provided with each Minivac 601. These provide step-by-step experiments demonstrating how computers do arithmetic, use logic, provide automatic control, and language translation. It even plays games as an opponent, partner or referee. The Minivac is ready to

- Teaches Basic Concepts of Computer Operation and Technology
- A Product of 2 Years of Research

use the moment you unpack it. Operates on a low 12 volt system—it is as safe to use as an electric train. Minivac consists of a 24" console with 12 indicator lights, 1 circuit breaker; 6 DPDT memory storage relays; 6 secondary memory storage switches; 6 data input push buttons; 16 position switch (motor driven); game matrix; 194 dual terminals and 100 program wires. The console measures 24x13x5 1/2" H. Shpg. wt., 17 lbs. Power input 110 V AC. **NE-647W** Net 95.00

NEW MINIVAC 6010. A deluxe version of the 601 which is capable of handling a larger variety of more advanced computer programs. Ideal for industrial use. A seventh capacitor/resistor manual will accompany the 6010. Now with the additional features of individual protective dust covers for relays, improved slide switches and pushbuttons for tighter specs and greater reliability. **NE-644WX** Net 155.00

MINIVAC CAPACITOR-RESISTOR KIT FOR THE 601 Enlarge your MINIVAC 601's capacity as a computer simulator with these new components. This kit makes it possible to construct and understand over 24 more advanced experiments. Kit includes 6 capacitors, 27 resistors and programming connectors and the Capacitor/Resistor manual. **NE-648** Net 24.50

GENIAC PORTABLE MEMORY CARD FILE



HOW TO FILE A CARD IN 25 PLACES SIMULTANEOUSLY

17.96

For the busy scientist, engineer, teacher, business man or student who must keep basic information on file. NOW the Geniac Portable Memory Unit (PMU), a low cost information retrieval system can conservatively sort 400 cards per minute—using no electrical parts or gadgets. Sorting is by rods. Information is coded into the cards by matching prepunched holes around the edge of the card. No previous knowledge is necessary. Once coded the card is filed at random and will automatically appear during sorts for the various categories. Serves as a useful adjunct to company integrated information systems. The basic PMU contains a matching hand punch, sorting rods and 300 cards. **F-832** Shpg. wt., 6 lbs. Net 17.96
F-833 Additional Cards, pkg. of 100 Net 3.92

NEW! LAFAYETTE VECTORLOG SLIDE RULE



The Slide Rule for Communications Engineers and Physicists **16.88**

- LAMINATED BAMBOO CONSTRUCTION • P, P', AND Q SCALES — FOR DIRECT VECTOR ADDITION • HYPERBOLIC SINE AND TANGENT SCALES • TWO SINE SCALES—ONE MARKED IN DEGREES, ONE MARKED IN RADIAN • 5 LOG LOG SCALES PLUS A VOLTAGE DB SCALE • COMPLETE WITH BELT CARRYING LOOP AND LEATHER CASE

The Lafayette VECTORLOG Slide Rule provides a new concept in scientific calculation, incorporating scales and arrangement designed for quick-easy-manipulation. Twenty-seven (27) scales incorporate the many problems encountered in Electrical Engineering and Physics. The unique P, P', and Q scales allow direct right angle right angle. No longer are several settings required to obtain right angle vector sums—these scales work in the same manner as the C and D for multiplication. The two Hyperbolic Sine and one Hyperbolic Tangent Scale, the voltage db scale, and the five Log Log scales, provide maximum coverage of these dynamic fields. VECTORLOG is the result of extensive tests for ease of manipulation. Several of these features are: C and D scales on both the front and back of the rule; Sine scales in both degrees and radians, removing the necessity of bothersome conversion of units; A problem-tested location of scales; and adjustment screws to allow variable tension on the slide. Scales include: (FRONT) Tr-1, Tr-2, P, P', Q, ST, S-r, S-O, C, D, LLO1, LLO2, LLO3, LL1; (REAR) Sh-1, Sh-2, DF, A, B, CI, CF, Th, C, D, LL3, LL2, db. With instruction book, leather carrying case, and belt carrying loop. Imported **F-686** Shpg. wt., 1 1/2 lbs. Net 16.88

LAFAYETTE'S ENGINE DIVIDED IMPORTED SLIDE RULES



10" LOG LOG DUPLI TRIG SLIDE RULE

- Laminated Bamboo Warp-Free Construction • Complete With Leather Carrying Case

Specially selected, laminated, non-hygroscopic bamboo. Scales machine engraved on white plastic in permanently accurate calibrations. Adjusting screws permit varying tension on slide. 21 scales including C, D and CI on both sides. LLO and LLOO scales refer to B scale. All other scales coordinate and refer to D scale. Scales are L, LL1, DF, CF, CIF, CI, C, D, LL3, LL2, LLO, A, B, K, CI, C, D, S, ST, and T. Scale characteristics permit multiplication, division, proportion, inverse proportion, reciprocals, cotangents, squares, square roots, cubes, cube roots, logarithms, tangents, sines, etc. Imported **F-341** Shpg. wt., 1 1/2 lbs. Net 10.43


NEW! DECI-LOG™ DELUXE 5" LOG LOG DUPLI DECIMAL TRIGONOMETRIC SLIDE RULE



ONLY 6.88

A pocket version of our 10" Log Log Dupli Decimal Trigonometric slide rule (F-428). Contains all the scales of the 10" rule except the "ST" scale. Two color scales—positioned for ease in use and rapid calculations. "C" and "D" scales on both sides of the rule. "P" scale for direct, cursor line reading of cosines of angles. Scales included, front face: LL1, LL2, LL3, DF, CF, CIF, CI, C, D, LL3, LL2, LL1. Back face: LLO, L, K, A, B, S, T, C, D, DI, LLO. Engine divided rule of laminated, non-hygroscopic bamboo. Complete with instruction book and leather case with pocket clip. Imported **F-681** Shpg. wt., 8 oz. Net 6.88

DELUXE LOG LOG DUPLI DECIMAL TRIGONOMETRIC SLIDE RULE



- 25 Scales with 8 Log Log Scales
- Extended Range Avoids "Going Off Scale"
- Extra P Scale Simplifies Computations
- Two Color Scales

15.95

10" log log duplex trig slide rule contains 25 scales including 8 Log Log Scales. Troublesome end-for-end resetting is eliminated by extensions of C and D scales. Twin set of Log Log scales run from scale length each compared with ordinary log log slide rules. Extra value. Scales include P scale which enables direct "readout" of cosine LL2, LL1, LLOO, L, K, A, B, S, ST, T, C, D, DI, P, and LLO. With instruction book, saddle leather case. Overall length is 14". Imported **F-428** Shpg. wt., 1 1/2 lbs. Net 15.95



2.89


5" POCKET SLIDE RULE

5" Pocket Slide Rule: Convenient pocket sized slide rule of specially selected and treated bamboo. Will not warp, shrink or lengthen under varying atmospheric conditions. A, B, CI, C, D and K scales engraved on white plastic surface. Reverse side of slide has standard S, L and T scales. The upper beveled edge of the rule is graduated in m/m to 13 cm. Other edge is divided into 5 inches by 32nds. Only 5 1/4" long over all. Carried easily in any pocket. Shpg. wt., 8 oz Imported **F-340** Net 2.89



PROFESSIONAL GIANT BOW 3.50
6" Size with Center Wheel Adjustment
• Finely Balanced—Professional Type

Professional quality utility set in a fitted, velvet lined case. Made in Western Germany of nickel plated, hard-rolled brass. 6" giant bow has preferred center wheel adjustment. Makes circles from 1/4" to over 10" in diameter. Set includes 6" giant bow, interchangeable pen and pencil parts, extra needle for using bow as divider, handle for use with pen and pencil parts, lead, lead box and repair parts. Shpg. wt., 1 lb. Imported **F-44** Net 3.50




TECHNICAL DRAFTING SET

- Center Wheel Adjustment
- Professional Quality

6.59

A fine set of imported nickel plated brass instruments priced far below the usual price for this quality. Contains 6 1/4" self-centering compass, one leg knuckle joint with divider, pencil, pen parts and lengthening bar; 6 1/4" self-centering divider; spring bow divider 4 1/4", center wheel adjustment with interchangeable needle points; spring bow pencil and spring bow pen, both 4 1/4" with center wheel adjustment and interchangeable needle point; two 5 1/4" ruling pens; extra handle for pen and pencil parts; adjustment tool; lead case and leads; and spare parts kit, all in velvet lined snap closing case. Shpg. wt., 1 1/2 lbs. Imported **F-65** Net 6.59

8" PROFESSIONAL DIVIDER




- IMPORTED FROM GERMANY

4.96

Extremely accurate finely made proportional dividers. Basic equipment for draftsmen—architects—engineers—students. Replaceable steel points—in hard, leather covered, felt lined case. Used for proportional reductions and enlargements, copying drawings in enlarged or reduced scale, dividing lines or circles into equal parts, quick solving of difficult measuring problems, finding distances on maps without scales, etc. Flat form-replaceable steel points. Pressure setting. Graduated for lines from 3/4" to 10"—Circles from 6" to 20". Excellent, accurate utility model. Shpg. wt., 8 ozs. Imported **F-167** Net 4.96

DECIMAL "TIME-OUT" TIMER



9.75 **6.90**

Ideal for industrial time-studies. Easy-to-read outer dial divided in 1/100 of a minute registering up to one minute. Inner dial graduated in minutes and registers up to 30 minutes. Push button, for timing out, brings both hands back to zero. Pressures on the crown will consecutively start, stop and again start the timer. Dependable 7-jewel movement. Swiss made. Shpg. wt., 8 oz. **F-664L** Net 8.75

1/10th Second "Time-Out" Timer

Suggested for close timing. Large hand registers 1/10 of a second, up to 30 seconds; small hand in minutes, up to 15. Start, stop, and continue from crown; instant return to zero by push button. Accurate 1-jewel movement. Chromium plated nickel case. Shpg. wt., 8 oz. **F-665L** Net 6.90



1/10TH SECOND "ELECTRONIC" TIMER

- Made to Gov't. Specifications
- MIL-W-6510 (USAF) Type A-B
- Exceptional Accuracy


25.95

Especially useful as timing components of electronic and radar equipment. Made in accordance with government specification number MIL-W-6510 (USAF) type A-B. Dial face calibrated in 1/10 seconds. Sweep hand completes turn in 10 seconds. Register divided in 10 sec. increments, completes turn in 5 minutes. Luminous figures on black face. Start, stop and fly back to zero by successive depressions of the crown. Balance staff shock protected, unbreakable mainspring, nickel finished case. Swiss made. **F-774L** Shpg. wt., 8 ozs. Net 25.95

HARD MAPLE PANTOGRAPH

3.75

- ENLARGES
- REPRODUCES!



21" adjustable pantograph—21 different ratios from 1 1/4 to 8. Enlarges, reduces or reproduces drawings—sketches—diagrams—pictures—maps, etc. Most rapid accurate means of reducing or enlarging to scale. Lacquered highly finished bars are 21" long and 3/4" wide. Heavy metal standard, with bearing eliminates all friction. Chrome plated hardware — ratio thumb screws and nuts. Complete with lead, accessories and detailed instructions. Shpg. wt., 2 lbs. **F-158** Net 3.75

SUPER DRAWING KIT



7.95

- COMPARE OUR PRICE!

Contains all the necessary equipment for drafting, mechanical drawing, designing. Sturdy accurate components. Includes 20x24 1/2" drawing board 24" T square, 10" 30°/60° triangle, 8" 45° triangle, french curve, 12" triangular rule, 6" 180° protractor, 4 pencils, pencil pointer, erasing shield, thumb tacks, and art gum eraser. If purchased separately these components would cost many times our low price. An unbeatable value. Shpg. wt., 10 lbs. **F-180** Net 7.95

SPECIAL COMBINATION OFFER

Consists of F-65 Technical Drafting Set and F-180 Super drawing outfit. **F-181** Shpg. wt., 12 lbs. Net 13.06

Never

IN OUR 42 YEARS HAVE WE SEEN SUCH A TRULY SENSATIONAL TAPE DECK VALUE!

NEW! LAFAYETTE *Deluxe* Professional Quality 4-TRACK STEREO RECORD and PLAYBACK TAPE DECK

Complete with Built-In Transistorized Record and Play Preamps

- PLAYS: 4-Track Stereo Tapes, 2-Track Stereo Tapes, 4-Track, 2-Track and Full-Track Monophonic Tapes
- RECORDS: 4-Track Stereo or Monophonic from AM, FM, FM Multiplex, Radio, or Phono Sources; Live from Microphones

RECORDS Sound-on-Sound!

Begin your stereo component system with this outstanding tape recorder reproducer. The RK-140 abounds in professional-type features making it suitable to meet every stereo and monophonic recording situation. Styled right too! Tape transport and electronic components are integrated into one lightweight unit, for use in either a portable carrying case or a handsome built-in home installation. Rugged tape transport has an ultra quiet 4-pole air-cooled induction motor and belt drive for double flutter filtering. Provides smooth drive action. Automatic tape stop at end of the tape or during a break in the tape, and handy pause control give absolute control over tape. Superb electronics consist of transistorized and tube stereo preamps for self-contained record and playback facilities. Makes 4-track stereo and monophonic recordings, plays back 2 and 4-track stereo and monophonic tapes. The two channels operate independently to permit recording one channel at a time (sound-on-sound). Clear FM multiplex recording is assured by high (80 KC) bias operation. Both heads and pressure pads are mu-metal shielded to eliminate hum. The simplicity of the RK-140 makes it easiest to use—all transport and electronic controls are located on the top panel for easy access. Two jacks are provided for connection of stereo microphones (not included) for making "live" stereo recordings. Two recording meters permit accurate recording levels to be set making it simple to have professional-type recordings you will be proud of. The Pause control further assists in making "pro" recordings by stopping the tape momentarily for editing out commercials, poor notes etc. For 117V, 60 cycles AC. Tape Deck is complete with preamps, 4 connecting cables and empty reel. Shpg. wt., 20 lbs.

RK-140WX Net 99.50
 RK-143WX Deck with carrying case Net 114.50
 RK-145W Deluxe carrying case Net 15.00



2 RECORDING LEVER METERS

TAPE INDEX COUNTER

PAUSE CONTROL

SHOWN with OPTIONAL CASE

CONNECTING CABLES & EMPTY REEL




ONLY **99⁵⁰**
 NO MONEY DOWN

SPECIFICATIONS

Frequency Response, Record/Playback: 40-18,000 cps @ 7 1/2 ips; 40-12,000 cps @ 3 3/4 ips. 4-transistors, 4 tubes, 1 full wave bridge rectifier. Audio Output: 2 watts per channel, S/N Ratio: 45 db, Interchannel Separation: 45 db or better; Wow & Flutter: Less than 0.25% @ 7 1/2 ips, Under 0.4% @ 3 3/4 ips; Bias & Erase: 80 KC; Rewind Time: Less than 4 minutes for 1200 ft. of tape. Speed Accuracy: start to finish — under 2%. Controls: Pause, 2 Record Buttons W/Safety Interlocks. Rewind/Stop/Play; Stop/Fast Forward; Power on/Speed Selector, 3 volume controls, Counter: 3 digit, 2 audio output, 2 monitor jacks, 4 input jacks. For 117 volts 60 cycles AC. Size: 15Wx6 1/4Hx10 1/2"D. 5 1/2" Deep below panel.

PROFESSIONAL OPERATING FEATURES GIVE UTMOST FLEXIBILITY



- A SUPPLY REEL—Takes up to 7" size
- B AUTOMATIC CUT-OFF SWITCH—Stops recorder at end of tape or if tape breaks. Also serves as tape guide
- C TAKE-UP REEL—For Reels up to 7 Inches
- D HEADS—Separate Record/Play and Erase. Mu-metal Shielded Heads and Pressure Pads Eliminate Hum
- E INDEX COUNTER—Accurately Indicates Tape Position in Either Direction
- F SPEED CHANGE LEVER/POWER ON-OFF—Selects 2 Speeds 3 3/4 ips & 7 1/2 ips Automatically Equalized
- G LEVEL INDICATORS—2 Meters Indicate Recording Levels For Each Channel
- H INDIVIDUAL VOLUME CONTROLS—For Each Channel Can Also Be Used For "Trick" Sound Effects
- I MASTER VOLUME CONTROL—Provides over-all Playback Level
- J RECORD BUTTONS—One for Each Channel Permits Sound-On-Sound
- K PAUSE CONTROL—Self-holding—Makes Editing Easy
- L REWIND/STOP/PLAY LEVER—Instantaneous Selection. Rewind Time Less Than 4 Minutes For 1200 ft. Reel
- M STOP/FAST FORWARD—Fast Forward Control and Stop which Stops Tape Quickly Yet gently From Fast Forward Motion
- N MICROPHONE JACKS—2 Side Mounted Stereo Input Jacks for Microphones
- O ON/OFF PILOT LIGHT

NOW! NO MONEY DOWN WITH LAFAYETTE'S NEW EASY-PAY PLAN!

NEW LAFAYETTE HE-29B "WALKIE TALKIE" FAMOUS CITIZENS BAND TRANSCEIVER

NOW With 10 Transistors plus diode

& thermistor, with extra RF stage ... **50% MORE POWERFUL!**

- Transmits & Receives Up to 2 Miles
- Crystal Control on Both Transmit & Receive
- Requires 8 Inexpensive Penlight Batteries
- NO LICENSES, TESTS OR AGE LIMITS (FCC REG. 15)
- Up to 50 Hours Battery Life
- 46" Telescoping Antenna
- Push-To-Talk Operation
- Earphone For Personal Listening

ONLY **33⁹⁵** NO MONEY DOWN
 Complete with LEATHER CASE, EARPHONE, ANTENNA & BATTERIES
2 for 62⁹⁰



OTHER CHANNELS ARE AVAILABLE if desired with any channel other than channel 10, order HE-31BL and specify channel.


frequency of 27mc. Crystal controlled superheterodyne receiver provides crisp clear reception. Power is supplied by 8 miniature penlight batteries. Housed in a handsome black and silver aluminum case with leather carrying case and shoulder strap. Supplied with earphone for private monitoring, 46" telescoping antenna, batteries and crystals for channel 10. Size: 6 3/4Hx3 1/4Wx1 1/2"D. HE-29BL Shpg. wt., 3 lbs. Imported Net 33.95 2 for 62.90

CRYSTALS FOR HE-29B
 HE-830 Transmitting Crystal (specify channel) Net 2.25
 HE-758L Receive Crystal (specify channel) Net 2.25
 BA-155 Replacement Batteries Net ea. .095 (8 "Z" cells required)

Lafayette's latest version of the famous HE-29 Walkie Talkie. The HE-29B, scoops the industry with a carefully engineered 10-transistor circuit plus diode and thermistor, which meets the FCC power input specifications of 100 milliwatts. The "Walkie-Talkie" is as simple to use as a telephone and twice as handy. Perfect for outdoor sports, construction work, office, warehouse, farm or in-plant communications. Compact size, slips into your pocket— weighs only 18 ounces. Two controls—"on/off" and "push-to-talk" provide fast, efficient operation. Sophisticated transistor circuitry now has an additional RF stage for exceptional sensitivity, selectivity and signal-to-noise ratio. Transmitter section is crystal controlled and operates on a

FREE!

LAFAYETTE'S NEW 1963 CATALOG NO. 630 388 Giant-Sized Pages ... The Biggest Catalog in Our 42-Year History



It's New— It's Better Than Ever It's from the "World's Hi-Fi & Electronics Shopping Center"

- LAFAYETTE OFFERS THE LARGEST STOCK SELECTION
- Hi-Fi Stereo
 - Citizens Band
 - Amateur and Ham Equipment
 - Cameras and Optics
 - Test Instruments
 - Tape Recorders
 - Radio & TV Tubes and Accessories
 - Industrial Supplies

PLUS EXCLUSIVE LAFAYETTE KITS

Get Your Free Catalog—Get One For a Friend Too! Mail the Coupon Today!

LAFAYETTE RADIO ELECTRONICS
 P.O. Box 10, Syosset, L. I., N. Y.

STUV
 1 2 3 4

Send the FREE 1963 Lafayette Catalog No. 630

My Name _____ Friend's Name _____
 Address _____ Address _____
 City _____ Zone _____ State _____ City _____ Zone _____ State _____

UP TO 24 MONTHS TO PAY - FOR DETAILS SEE PAGE 54

LAFAYETTE RADIO ELECTRONICS "ASSOCIATE STORE" DEALER LOCATIONS

- | | | | | |
|---|---|--|--|---------------------------------------|
| HUNTSVILLE, ALA.
604-8 Andrew Jackson Way N.E. | ORLANDO, FLA.
1203 No. Mills St. | DETROIT, MICH.
1326 Broadway | UTICA, N.Y.
1415 Orriskany St. West | HARRISBURG, PA.
1419 No. 3rd St. |
| TUCSON, ARIZONA
503 E. Grant Rd. | TAMPA, FLA.
3328 Henderson Bl. | ASBURY PARK, N.J.
1027 Highway No. 35 | BEAUFORT, SO. CAR.
Ribaut Rd. | PITTSBURGH, PA.
640 Grant St. |
| BUENA PARK, CALIF.
6306 Beach Blvd. | IDAHO FALLS, IDAHO
945 Westchester Ct. | CAMDEN, N.J.
305 Broadway | AKRON, OHIO
34 North Main | WILKES-BARRE, PA.
115 No. Main St. |
| SAN FRANCISCO, CAL.
1480 Market St. | SALINA, KANSAS
314 West Cloud | NORTHFIELD (Atlantic City), N.J.
Tilton Shopping Center, Tilton Rd. | CANTON, OHIO
300 Walnut St. | BRYAN, TEXAS
3219 Texas Ave. |
| DENVER, COLO.
9515 E. Colfax Ave. | ASHLAND, KY.
212 - 15th St. | TRENTON, N.J.
229 S. Warren St. | CINCINNATI, OHIO
505 Elm | HOUSTON, TEXAS
8601 Lng. Pt. Rd. |
| BRIDGEPORT, CONN.
2710 Fairfield Ave. | SPRINGFIELD, MASS.
527 Belmont Ave. | ALBANY, N.Y.
335 Central Ave. | CLEVELAND, OHIO
2001 Euclid Ave. | SAN ANTONIO, TEXAS
5090 Blanco Rd. |
| GROTON, CONN.
171 Thames St. | BALTIMORE, MD.
2014 N. Charles St. | BINGHAMTON, N.Y.
129 State St. | COLUMBUS, OHIO
122 E. Long St. | LYNCHBURG, VA.
1624 Park Ave. |
| STAMFORD, CONN.
85 Prospect St. | BEL-AIR, MD.
139 Thomas St. | BUFFALO, N.Y.
747 Main St. | STEUBENVILLE, OHIO
411 Washington St. | GREEN BAY, WISC.
412 Dousman St. |
| WATERBURY, CONN.
386 W. Main St. | HAGERSTOWN, MD.
13 W. Antietam St. | ROCHESTER, N.Y.
792 W. Main St. | AKRON, PA.
127 No. 7th St. | CHEYENNE, WYO.
1400 Hugur |
| NEW CASTLE, DEL.
1420 Dupont Blvd. | BAY CITY, MICH.
408 E. Midland St. | | ALLENTOWN, PA.
20 N. 7th St. | |

MAIL ORDERS NOT FILLED BY "ASSOCIATE STORE" DEALERS

LAFAYETTE RADIO ELECTRONICS

111 JERICO TURNPIKE SYOSSET, LONG ISLAND, NEW YORK

BULK RATE U.S. POSTAGE PAID New York, N. Y. Permit No. 8486