


Wireless World


September 1973 20p

Homodyne receiver
Total communications



Australia 20 cents
Belgium Fr. 41.40
Canada 90 cents
Denmark Kr. 8.00
Finland Fmk. 3.50
Germany Dm. 3.50
Holland Dfl. 3.25
Israel L.S. 2.50
Italy L. 400
Malaya M\$ 2.30
New Zealand 65 cents
Nigeria 55k
Norway Kr. 4.50 inkl. Moms
Rhodesia 70 cents
South Africa 65 cents
Spain Ptas. 25.00
Sweden Kr. 25 inkl. moms
Switzerland Fr. 4.30
U.S.A. \$ 1.00

The Go-Go Modulation Meter.



Meet the masterly modulation meter that goes wherever you go: M.I.'s f.m./a.m. TF 2303.

Portable, compact, light to carry in its special case with compartment for accessories, it operates both on mains and on re-chargeable batteries for time-saving, trouble-saving mobile radio testing in the field.

The TF 2303 measures f.m. deviation in three ranges from 1.5 kHz to 15 kHz at carrier frequencies up to 520 MHz, the expanded lower range being particularly useful for measuring narrow band performance. It has 'locked on' frequency control as a further advantage. And it is substantially protected against overload damage. All this . . . and splendid value too!

And to make this helpful instrument even more helpful – and to provide easy connection to transmitters – there's the most comprehensive range of accessories; a de-emphasis unit, a 12-watt termination, one-watt and twenty-watt 20dB attenuators, a 'signal sniffer', and an r.f. fuse.

No doubt about it: M.I.'s TF 2303 is just what you need where the action is – either at your bench or out and about here, there, and everywhere. So get going with it just as soon as you can!


The full facts are yours for the asking from:



MARCONI INSTRUMENTS LTD.,
Longacres, St. Albans, Herts. AL4 0JN,
England.

Telephone: St. Albans 59292. Telex: 23350.
A GEC – Marconi Electronics Company.

WW-001 FOR FURTHER DETAILS



THE FG1 FUNCTION GENERATOR

WAVEFORMS AVAILABLE

Sine, square, triangles and ramps. Continuous swept, triggered, gated bursts, frequency modulated, externally sync'd.

AMPLITUDE

Max. 20V pk-pk into open circuit (10V into 50 Ω) on selected waveform at main output. Adjustable from 1mV.

Four basic waveforms available simultaneously from 600 Ω at fixed level of 2.5V pk-pk.

ATTENUATOR

4 positions, 60dB in 20dB steps. For best possible resolution and signal to noise ratio at low signal levels.

FREQUENCY

0.02Hz to 2MHz in seven decade ranges - sine, square and triangle. 1000:1 continuous coarse and fine adjustment on each range. 0.01 Hz to 1kHz in five decade ranges - ramp. Dial accuracy $\pm 3\%$ of range max. 0.02 Hz to 200kHz.

OFFSET

± 5 V d.c. bias will offset waveform above or below zero. Push-pull adjustable control.

EXT. VCO

0 to +10V gives 1000:1 frequency upshift from min. dial setting.

0 to -10V gives 1000:1 frequency down shift from max. dial setting, within any selected range.

Voltage may be a.c. or d.c.

Frequency modulation of the output about a centre frequency is possible.

SWEEP

Range: 1000 to 1. Mode: Lin or log. Times 1mS to 1000S.

Width: 5 position switch gives stepped reductions as a percentage of max.

SYNC

Sync. pulse output may be used to trigger an oscilloscope, X-Y plotter etc. Or the output frequency of the FG1 may be locked to a periodic reference signal for tests requiring coherent signals.



Farnell

— real value for money at **£195** U.K.
(excluding V.A.T.)

INSTRUMENTS DIVISION

FARNELL INSTRUMENTS LTD · SANDBECK WAY · WETHERBY · YORKSHIRE LS22 4DH · TELEPHONE 0937 3541 · TELEX 557294

LONDON OFFICE: TELEPHONE 01-802 5359

WW-005 FOR FURTHER DETAILS

BIG BOOST FOR THE GARDNERS RANGE

50Hz 300VA Square Wave Inverters



If it's produced by Gardners it must be something special, and it is! Now available, models 107A and B are precision built inverters providing 240 volts a.c. from 12 and 24 volt battery systems.

Both models offer unusually high output ratings enabling the user to operate many conventional loads such as lighting and small power tools in situations where main power supplies are not available.

Gardners inverters are designed to drive any mains operated equipment which is not unduly sensitive to the difference between sine and square waveforms. Incandescent lamps, TV sets, electric drills are typical of a wide field of possible applications . . .

Both the 107A and B models are rated at 300VA (300W U.P.F.) and will accommodate reasonable short term overloads. Price £61 plus VAT. Brochure GT 26 gladly sent on request.



Specialists in Electronic Transformers and Power Supplies

GARDNERS

TRANSFORMERS LIMITED

Gardners Transformers Limited Christchurch Hampshire BH23 3PN
Telephone 02-015 2284 TELEX 41276 GARDNERS XCH.

WW-006 FOR FURTHER DETAILS

EHPL

it takes over where
MTBF leaves off

While others talk of MTBF, we introduce a new concept—EHPL, Estimated Half-Power Life. Our 400W and 1kW all-solid-state broadband HF linear amplifiers have over five years of it, counted in operational hours. Which, with a remarkably low Mean Time To Repair, means 99.9% up-time.

The multiple p.a. modules of these compact units, arranged in parallel for maximum reliability, ensure that even in the unlikely event of several component failures occurring together, the amplifiers go on working—long after others have stopped.

Moreover, thanks to Redifon's unique Transmit Level Control, they always deliver to any antenna—even to a badly damaged one—the maximum power that is safe, whatever the mismatch.

All of which means that the pair of transmitters in the picture represent the finest and most reliable in the world for civil and military applications, whether in fixed, mobile or containerised stations. And they are in production and service, right now.

**Redifon Telecommunications Ltd,
Radio Communications Division,
Broomhill Road, London, SW18 4JQ
Telephone: 01-874 7281 Telex: 264029**



☼ A member of the Rediffusion organisation

Redifon Telecommunications Limited




SME

The best pick-up arm in the world


Whichever way you look at it

Write to SME Limited · Steyning · Sussex · England
Telephone: Steyning (0903) 814321

LTD/520



WW—008 FOR FURTHER DETAILS



Electronic valves (a comprehensive range)
 semi-conductors (a wide variety)
 integrated circuits...and now a comprehensive
 range of Hybrid Microcircuits. Prices on request.

Teonex offers more than 3,000 devices. They are competitively priced and they are superlative in performance because the company imposes strict quality control. Teonex concentrates entirely on export and now operates in more than sixty countries on Government or private contract. All popular types in the Teonex range are nearly always available for immediate delivery. Write now for technical specifications and prices: Teonex Limited, 2a Westbourne Grove Mews, London W11 2RY, England. Cables : Tosuply London W11. Telex : 262256



AVAILABLE ONLY
 FOR EXPORT

FREE

HEATHKIT Electronic kit Catalogue

SAVE ON OVER 130 KITS
YOU CAN BUILD



HOME APPLIANCES such as Pocket and Desk Top Electronic Calculator Kits, Electronic Digital Clock, Ultrasonic Burglar Alarm, Indoor/Outdoor Intercoms.

AUTOMOTIVE Testers, Engine Analysers, Tune-Up Meters, CD Ignition System, Timing Lights, Battery Charger.

PORTABLE Radios for Medium, Medium/LW, FM reception.

INSTRUMENTS for Test and Service, Transistor/Diode Checkers, Chart Recorders, Scientific.


SHORTWAVE AND AMATEUR RADIO includes:— Complete Stations, Receivers, Transceivers, Transmitters, a wide range of ancilliary/auxilliary equipment.

STEREO Hi-Fi Systems, Compacts, Separates, Cassette, Loudspeakers, Transcriptors, Cartridges.

METAL DETECTORS

All models offer Kit savings—outstanding performance. Enjoyable leisure activities. Payment is so easy—choose cash or low deposit terms (from £2 per month for £40 credit).

May we have your enquiries today!



Visit your Heathkit Centres

LONDON showroom
233 Tottenham Court Road
Tel 638 7349

GLOUCESTER showroom & factory
Bristol Road, Gloucester
Tel 0452 29451

Please send me a FREE Heathkit catalogue


Name _____

Address _____

HEATH Heath (Gloucester) Limited, Dept. WW/9/73
Schlumberger Gloucester GL2 6EE. Telephone 0452 29451

INDUSTRIAL INSTRUMENTS LIMITED

INTRODUCE



NICKEL CADMIUM BATTERIES

AVAILABLE WITH CAPACITIES OF 2 TO 500 Ah
FOR
EMERGENCY LIGHTING, ENGINE STARTING,
TELECOMMUNICATIONS, SWITCH TRIPPING ETC.

WE ALSO OFFER COMPLETE ELECTRONIC
AND DIESEL EMERGENCY POWER SUPPLIES

FOR FURTHER DETAILS CONTACT

**INDUSTRIAL
INSTRUMENTS
LIMITED**


TRANSIPACK

Sales and Laboratories
STANLEY ROAD, BROMLEY, BR2 9JF,
KENT, ENGLAND.
Telephone: 01 460 9861
Telegrams: TRANSIPACK, BROMLEY.
TELEX: 896071
Factory
THEAKLEN DRIVE,
PONSWOOD INDUSTRIAL ESTATE,
HASTINGS, SUSSEX, ENGLAND.
Telephone: Hastings 7344/5/6.


BIG NEWS FROM BARR & STROUD

Modular Filtering


ONE MAIN FRAME—MANY OPTIONS




High Pass




High Pass/Low Pass



High Pass/High Pass



Low Pass



Low Pass/Low Pass

and that's only the start!

Barr & Stroud's new EF3 Electronic Filter System means no more compromises when you buy variable filters. Now you can get the filter you need today, and additional plug-in units tomorrow. Today — the basic main frame and your choice of two modules to operate in low-pass, high-pass, band-pass, band-stop, band-separate, band-combine or cascade modes. Tomorrow — other interchangeable modules to meet your newest requirements. The first two modules,

already available, provide filtering with variable cut-offs between 0.01Hz and 10.0kHz, stop-band attenuation of 48dB/oct. (96dB/oct. in cascade), and pass-band response from dc to 500kHz. Get full details of EF3, the big breakthrough in electronic filtering by using the reply card.

BARR & STROUD LIMITED
 London Office: 1 Pall Mall East, London SW1Y 5AU
 Telephone: 01-930 1541 Telex: 261877



Glasgow and London

WW—012 FOR FURTHER DETAILS

Collect Wireless World Circards. And build a valuable dossier on circuit design.


Circards is a new and comprehensive system, launched by Wireless World, to provide professional engineers and enthusiasts with valuable and up-to-the-minute data on circuit design. Data not available from any other single source.

Each Circard is 8" x 5" and shows a specific circuit, a description of the circuit operation; component values and ranges; circuit limitations; circuit modifications; tested circuits; performance data and graphs.

The double-sided format enables the Circard to be filed in standard boxes for easy reference. And the plastic wallet provided keeps the cards well-protected.

Each set of circards costs £1 (£1.15 overseas). A subscription to Nos. 6-15 costs £9 (£10.50 overseas) – sets published monthly.

Start your personal dossier on circuit design by completing and returning the coupon below.



Subjects already covered by Circard.

1. Basic Active Filters. 2. Switching circuits: Comparators and Schmitts.
3. Waveform Generators. 4. AC Measurements.
5. Audio Circuits: preamplifiers, mixers, filters and tone controls.

Subjects to be published during the year.

6. Power Amplifiers. 7. Constant Current circuits.
8. Opto-electronics. 9. Basic Logic Gate circuits.
10. Astables. 11. Micropower circuits.
12. Wideband Amplifiers. 13. Alarm circuits.
14. Pulse Modulators. 15. Digital counters.

To: J. Rider, Wireless World, IPC Business Press Limited, Sundry Sales Dept, 33 Bowling Green Lane, London, EC1R 0NE.

Please send me set no(s) @
 £1 (£1.15 o/s) each *
 I wish to subscribe to set Nos. 6-15 @
 £9 (£10.50 o/s) *
 I enclose cheque/money order for £
 *Tick as required

Name

Address


Company registered in England. Registered address, Dorset House, Stamford Street, SE1 9LU England Registered Number 677128

audix

SOUND SYSTEMS AND ELECTRONICS

...and this is standard equipment!

Nobody wants amplifiers: situations demand them. Amplifiers cost money, consume power and space, and can break down at crucial moments. Audix understand your problems and have designed a range of amplifiers which provide reliable service without worry and problems. Our amplifier costs are kept to a minimum by quantity production of proven designs. Preset controls are eliminated and output circuitry is protected by electronic sensing ensuring long, reliable service. Our designers have created a perfect balance between power rating, unit size and appearance and the many thousands of amplifiers serving industry, government and educational authorities, hospitals, broadcast and recording studios, are proof of our success. For helpful advice and full details of our product range please contact Ken Parry of our Sales Department.




audix

**MANUFACTURERS OF
SOUND SYSTEMS AND
ELECTRONICS**

**AUDIX LIMITED · STANSTED · ESSEX CM24 8HS
TELEPHONE: BISHOP'S STORTFORD 813132
(4 lines) (STD 0279)**

WW—014 FOR FURTHER DETAILS

HERE'S WHY YOU SHOULD NOT BUY A STORAGE SCOPE



Medelec Fibre Optic Oscilloscopes are top quality general purpose units for industry or research. They are based on the well proven techniques developed by Medelec in the exacting field of medical instrumentation.

- HIGH QUALITY, LOW COST RECORDING
- SIMULTANEOUS RECORDING & VIEWING
- SINGLE FRAME OR CONTINUOUS RECORDS FROM A BUILT-IN CAMERA

You will want to know more about the Medelec FOR-4 Fibre Optic Oscilloscopes—please contact us for detailed information or a personal demonstration.

Medelec Limited Woking Surrey
Tel: Woking (048 62) 70331
Telegrams: Medelec Woking

FOR-4

RECORDING OSCILLOSCOPES




medelec

WW—015 FOR FURTHER DETAILS

Vortexion

**50/70 WATT ALL SILICON AMPLIFIER
WITH BUILT-IN 4-WAY MIXER USING F.E.T.s.**

This is a high fidelity amplifier (0.3% intermodulation distortion) using the circuit of our 100% reliable 100 Watt Amplifier with its elaborate protection against short and overload, etc. To this is allied our latest development of F.E.T. Mixer Amplifier, again fully protected against overload and completely free from radio breakthrough.



The mixer is arranged for 2-30/60 Ω balanced line microphones, 1-HiZ gram input and 1-auxiliary input followed by bass and treble controls. 100 volt balanced line output or 5/15 Ω and 100 volt line.

50/70 WATT ALL SILICON AMPLIFIER WITH BUILT-IN 5-WAY MIXER USING F.E.T.s.

This is similar to the 4-way version but with 5 inputs and bass cut controls on each of the three low impedance balanced line microphone stages, and a high impedance (10 meg) gram stage with bass and treble controls plus the usual line or tape input. All the input stages are protected against overload by back to back low self capacity diodes and all use F.E.T.'s for low noise, low intermodulation distortion and freedom from radio breakthrough. A voltage stabilised supply is used for the pre-amplifiers making it independent of mains supply fluctuations and other stabilised supply for the driver stages is arranged to cut off when the output is overloaded or over temperature. The output is 75% efficient and 100V balanced line or 8/16 Ω output are selected by means of a rear panel switch which has a locking plate indicating the output impedance selected. The mixer section has an additional emitter follower output for driving a slave amplifier, phones or tape recorder, output .3V out on 600 ohms upwards.

100 WATT ALL SILICON AMPLIFIER. A high quality amplifier with 8 ohms-15 ohms or 100 volt line output for A.C. Mains. Protection is given for short and open circuit output over driving and over temperature. Input 0.4 V on 100K ohms.


THE 100 WATT MIXER AMPLIFIER with specification as above is here combined with a 4 channel F.E.T. mixer, 2-30/60 Ω balanced microphone inputs, 1-HiZ gram input and 1-auxiliary input with tone controls and mounted in a standard robust stove enamelled steel case. A stabilised voltage supply feeds the tone controls and pre amps, compensating for a mains voltage drop of over 25% and the output transistor biasing compensates for a wide range of voltage and temperature. Also available in rack panel form.

CP50 AMPLIFIER. An all silicon transistor 50 watt amplifier for mains and 12 volt battery operation, charging its own battery and automatically going to battery if mains fail. Protected inputs, and overload and short circuit protected outputs for 8 ohms-15 ohms and 100 volt line. Bass and treble controls fitted.

Models available with 1 gram and 2 low mic. inputs, 1 gram and 3 low mic. inputs or 4 low mic. inputs.

200 WATT AMPLIFIER. Can deliver its full audio power at any frequency in the range of 30 c/s-20 Kc/s \pm 1 dB. Less than 0.2% distortion at 1 Kc/s. Can be used to drive mechanical devices for which power is over 120 watt on continuous sine wave. Input 1 mW 600 ohms. Output 100-120 V or 200-240 V. Additional matching transformers for other impedances are available.

F.E.T. MIXERS and PPMs.



Since we have been supplying professional mixers for 25 years we have delayed the introduction of solid state units until they were at least as good as their valve counterparts. (Which will continue where required.)

The various sections of the FET mixers and BBC type PPM's have been performing successfully for several years in other equipments with complete reliability. The PPM also uses an FET in its time constant circuit so that polyester capacitors can be used. The response from the 600 Ω output (25 Ω source impedance) is level 20 Hz to over 30 kHz with very low intermodulation distortion to zero level + 12dB. The input signal voltage range is over twice that of the valve unit and the noise at least halved.

VORTEXION LIMITED,
Telephone: 01-542 2814 and 01-542 6242/3/4

257-263 The Broadway, Wimbledon, S.W.19
Telegrams: "Vortexion, London S.W.19"

WW-016 FOR FURTHER DETAILS

www.americanradiohistory.com

Join the Digital Revolution

Digital Computer Logic and Electronics

A Self-instructional Course

C P Gane MA (Cantab)
A W Umwin BA (Cantab)

Book 1 Basic computer logic

Book 2 Logical circuit elements

Book 3 Designing circuits to carry out logical functions

Book 4 Flipflops and registers

Teach yourself the latest techniques of digital electronics

Computers and calculators are only the beginning of the digital revolution in electronics. Telephones, wristwatches, TV, automobile instrumentation — these will be just some of the application areas in the next few years.

Are you prepared to cope with these developments?

This four volume course guides you step-by-step with hundreds of diagrams and questions through number systems, Boolean algebra, truth tables, de Morgan's theorem, flipflops, registers, counters and adders. All from first principles. The only initial ability assumed is simple arithmetic.

At the end of the course you will have broadened your horizons, career prospects and your fundamental understanding of the changing world around you.

£2.95 A complete programmed learning course in 4 volumes

**Designer
Manager
Enthusiast
Scientist
Engineer
Student**

This course is written to meet your needs in coming to grips with the theory and practice of digital logic and electronics. The programmed instruction system ensures a high level of retention of everything you learn.



£2.95

including post & packing

Guarantee

If you are not entirely satisfied with Digital Computer Logic and Electronics you may return it to us and your money will be refunded in full, no questions asked.

To: Cambridge Learning, 8a Rose Crescent, Cambridge

Please send me set(s) of Digital Computer Logic and Electronics at £2.95 for which I enclose cheque/PO/money order value

Name _____

Address _____

WW—017 FOR FURTHER DETAILS

The world's
most universal
audio bridges

Wayne Kerr's B224 and B642



The B224 is a manually operated bridge, the resistive and reactive terms being independently set to a null indicated on the meter. A rechargeable battery is fitted in order to make the instrument portable.



The B642 balances itself automatically. The meters read real and quadrature terms and highly stable analogue outputs are provided which are directly proportional to capacitance and conductance above 10Ω impedance and also to inductance and resistance below 10Ω . One or two decades can be set to provide the first significant figures of the measurement, thereby increasing the meter sensitivity by 10 or 100 times. If a chart recorder is connected to the output of either term, drifts in component values to at least four significant figures can be observed.

For more information, either call Bognor (02433) 4501 or write to the address below:

WAYNE KERR

Durban Road, Bognor Regis, Sussex PO22 9RL
A member of the Wilmot Breeden group.

SPECIFICATION

Frequency	B224 (Manual balance)		B642 (Autobalance)	
		1592Hz (internal) 200Hz - 50kHz (external)		1592Hz (internal) 200Hz - 20kHz* (external)
Ranges for specified accuracy				
	0.1%	0.3%	0.1%	0.3%
C	100fF - 10 μ F	10 μ F - 10mF	1pF - 10 μ F	10 μ F - 10mF
G	1nS - 100mS	100mS - 1kS	10nS - 100mS	100mS - 100S
L	1mH - 10kH	100nH - 1mH	1mH - 10kH	1 μ H - 1mH
R	10 Ω - 1G Ω	1m Ω - 10 Ω	10 Ω - 100M Ω	10m Ω - 10 Ω

NOTE: 0.1% accuracy relates to parallel component measurements above 10Ω impedance. 0.3% accuracy relates to series component measurements below 10Ω impedance.

*Manual operation only.

Dymar personal RT keeps people in touch.



Wherever they are.

Two hundred feet up on a building site. At the far point of a security patrol. In the middle of a cliff rescue. In situations like these, Dymar personal radiotelephones provide a vital link.

Essential personnel are in touch at all times. Help is always at hand. Important messages are not missed.

Specify Dymar personal RT and

you specify reliable VHF (AM or FM) circuitry in rugged, weather-proof diecast aluminium cases. With single or two-frequency simplex, three channel operation, there's a choice of aeriels and a choice of rechargeable batteries. A range of accessories is available, including multi-point battery chargers, carrying cases and head sets to fit industrial helmets.

There are intrinsically safe versions for use in dangerous environments, like oil refineries. There are marine as well as land types. There's even a high power version that can be attached to a vehicle aerial and used as a mobile set.

A lot of people keep in touch with Dymar — police, security organisations, construction crews, maintenance gangs and members of HM Coastguard.

For more information, use the Reader Enquiry Service, or contact Dymar direct.

DYMAR

the name in radiotelephones

Dymar Electronics Limited Colonial Way Radlett Road Watford Hertfordshire WD2 4LA. Tel: Watford 21297. Telex: 923035. Cables: Dymar Watford

WW—019 FOR FURTHER DETAILS

Dixons Technical have something in black and white to make CCTV importers green with envy.



Mirage: new from Dixons Technical.

Dixons Technical have the largest range of CCTV equipment in the country. And now they've added Mirage: their very own CCTV system.

Mirage is the all-purpose CCTV system comprising the finest components available. It can be used by schools, by industry, as an audio-visual aid, or with Mirage automatic video, switchers and monitors, it's perfect for surveillance purposes.

The Mini 500 is a small, discreet camera specially designed for surveillance. It comes complete with an f1.8 lens.

The HD800 gives a high definition picture. Incorporates a Mullard separate mesh tube. And accepts external drives.

The HD800 VF boasts the same high standard of specifications as the HD800, but

also has a 5" monitor screen. It's the perfect semi-professional studio camera.

With both HD800 models, Plumbicon (R),* and Silicon tubes can be fitted without modification to the circuitry.

Every piece of equipment is backed by Dixons Technical superb after-sales service.

If you don't wish to spend cash, no problem. The entire Mirage range is available for hire, lease or rent.

To: Dixons Technical Ltd., 3 Soho Square, London, W.1.
Tel: 01-437 8811.

WW/109

Please send me lots of information on the entire Mirage range.

Name: _____

Address: _____

Dixons
Technical Ltd
OF SOHO SQUARE

*Plumbicon is the registered trade mark of Mullard.

WW—020 FOR FURTHER DETAILS

Westinghouse TV colour tubes guarantee purity in both colour and black & white

Today's Westinghouse Electric colour tubes, in addition to offering recognised excellence of colour definition, have white field purity... vitally important to reception of black and white transmission.

Two 67 cm diagonal versions

These improved Westinghouse tubes are made available in two configurations – the standard 90° and the 10 cm shorter profile wide-neck 110° version... permitting their compatibility to the needs of the larger portion of European TV set manufacturers.

Expanded European facilities

Pacing the growing demand in Europe for Westinghouse tubes, we have made a permanent commitment to fully support our customer. ■ With trained technical sales personnel in major European cities. ■ With

warehousing and testing facilities in Kassel, W. Germany and Le Mans, France. ■ With a sustaining European oriented R&D programme.

Customer oriented

In these ways—compatible product availability—outstanding development facilities—local technical assistance... Westinghouse Electric respond to dynamic customer requirements—here in Europe and throughout the world.

Westinghouse Electric S.A.
1 Curfew Yard, Thames Street
Windsor Berks. Phone Windsor
63392. Telex 847069.

GENEVA FRANKFURT LONDON
MILAN PARIS STOCKHOLM




The 110° Ⓜ A67-140X TV colour tube is 10 cm shorter in profile than the 90° Ⓜ A67-120X... both offer superb colour definition as well as white field purity for black & white.



Westinghouse Electric

WW—021 FOR FURTHER DETAILS

ANDERS MEANS METERS...



Actual size illustration


Scale length 4.3"

PROFILE 350 EDGEWISE METER


- Long scale while retaining small overall size
- Process control and electronic applications
- Easily stackable
- Horizontal/vertical use
- 60 μ A upward, AC/DC
- Self-shielding rugged movement

Anders provide what is probably the largest range of meters available from a single source in Europe: MC/MI, dynamometer, vibrating reed, electrostatic, etc. in over 100 case styles and sizes, a few of which are shown below.


Popular models and ranges are stocked in depth while a specially equipped instrument department enables swift production of non-standard ranges and scales, to suit individual customer requirements, in large or small quantities.




Oxford Long Scale 240°. 2 models, 5.5", 8" scales. DC moving coil and AC moving coil rectified.



Vulcan Moving Iron. 4 models, 1.5", 1.8", 2.7", 3.7" scales. Voltmeters, ammeters and motor starting meters.




Kestrel Clear Front. 7 models, 1.3"—5.25" scales. DC moving coil, AC moving coil rectified, AC moving iron.




Soliconroller Moving Coil Relay. DC moving coil and AC moving coil rectified. 1 or 2 adjustable alarm controls.



Models KE1 and KE2 Miniature Edgewise Meters. Nominal scale lengths 1.2" and 2". Available in sensitivities from 50 microamps Moving Coil.



Regal Range 100 ϕ flattened arc. 2 models 2.5" and 3.2" scales. Taut band. DC moving coil and AC moving coil rectified.



Stafford Long Scale 240 6 models, 3.5"—11.5" scales. DC moving coil, AC moving coil rectified, AC moving iron. Also 98° scale.



Lancaster Long Scale 240 . 2 models, 4", 5.5" scales. DC moving coil and AC moving coil rectified.

Send for fully illustrated catalogue.

ANDERS ELECTRONICS LIMITED 48/56 Bayham Place, Bayham Street, London, N.W.1. Telephone 01-387 9092.

Manufacturers and distributors of Electrical Measuring Instruments. Sole U.K. distributors of FRAHM Resonant Reed Frequency Meters and Tachometers. Manufacturers of purpose built electrical and electronic equipment to customers' requirements.

WW—022 FOR FURTHER DETAILS


www.americanradiohistory.com

Eddystone Radio



RADIO FREQUENCY INTERFERENCE MEASUREMENT

Noise measuring set 31A



RUGGED PORTABLE
Suitable for field use
in all weather conditions

The Eddystone Model 31A, a Ministry of Posts and Telecommunications design marketed under licence from the Post Office, is a solid-state equipment meeting the requirements of Post Office Specification W6912 for a Portable VHF Interference Tracing and Measuring Receiver

31-250MHz in three ranges

110dB measuring range with high accuracy

Collapsible antenna, housed in removeable cover

Operation from an internal rechargeable battery supply

Weight-19lb (8.6kg)

Illustrated brochure obtainable from:

Eddystone Radio Limited

Alvechurch Road, Birmingham B31 3PP
Telephone: 021-475 2231. Telex: 337081

A member of Marconi Communication Systems Limited

LTD/ED107

WW-023 FOR FURTHER DETAILS

NEW BROADBAND VERSATILITY for AC/DC VOLTAGES

The latest Model of the URV series now developed by ROHDE & SCHWARZ features:

an **INCREASED SENSITIVITY** most sensitive subrange 3 mV.

a **HIGHER ACCURACY** error limits 1% for DC. 2% for AC.

and **NEW ACCESSORIES**,

The new URV is battery powered with a life of 6000 hrs., making it completely portable and completely independent of earth loops and mains-borne interference



HF-DC Millivoltmeter model URV with RF probe and 20- or 40-dB attenuator.

The model HF-DC Millivoltmeter URV measures DC and AC voltages from 0.5 mV (50 μ V for DC) to 1000 V and with a small RF probe, and proved coaxial insertion units (50, 60, 75 Ω) the URV can be used for a wide variety of RF-Voltage measurements in the range from 1 kHz to 1.6 GHz.

For full details and specifications apply to:

AVELEY ELECTRIC LTD.

Roebuck Road,
Chessington, Surrey

Tel: 01-397 8771
Telex: Avel London 928479

WW-024 FOR FURTHER DETAILS

Here it is!

Our two new ranges of 75 ohm TV distribution cables are now made on an extrusion line unique in Western Europe.

We're one of the most technologically advanced cable manufacturers, using new techniques to produce TV distribution cables at a consistently high standard to tolerances much closer than previously possible. At very competitive prices.

The two ranges:

Aeraxial Semi Air Spaced Polyethylene dielectric copper taped braided and polythene sheathed television distribution cables. Five cables in the range, with inner conductor sizes from 1.27 mm to 3.05 mm.

Solid Polyethylene dielectric copper taped and polyethylene sheathed television distribution cables. Five cables in the range, with inner conductor sizes from 0.73 mm to 3.65 mm.



Aerialite will specially manufacture TV distribution cables for any special TV application—also, you can make use of the Aerialite free technical advisory service to help you in the selection and application of distribution cables.

For further information, send for Aerialite's new publication giving full technical specifications of the latest range of TV Distribution Cables.

Aerialite

Aerialite Cables Limited,
Castle Works,
Stalybridge, Cheshire SK15 2BS.
Telephone: 061-338 2223
Cables: Aercables, Stalybridge.
Telex: 669902

To Aerialite Cables Limited:
Please send me your brochure
entitled Aerialite Television Distribution Cables.

NAME _____

POSITION _____

COMPANY _____

ADDRESS _____

6 volume library '67-'73 is now ready

the only work of its kind anywhere

Speedier, more efficient servicing means increased turnover . . .

This library is a gold-mine of technical information. Six hard-bound volumes giving vital data on more than 1500 models of Television (colour and mono), Radios, Car Radios, Stereograms, Record Players and Tape Recorders. More than 4000 pages clearly display thousands of circuits, printed panel diagrams, component layout diagrams, waveform graphs, block diagrams, etc. Over 800 pages, devoted entirely to Colour TV, include installation instructions, new term explanations, purity adjustments, colour balance, static convergence and a wealth of invaluable information. Here, in fact, is all the data you need for efficient and speedy repair work.

Your Guarantee

Sending for these valuable books, even though you also enclose your remittance, commits you to nothing. Unless you are absolutely satisfied you are perfectly free to return the set and if you do so within 10 days of delivery your money will be refunded in full and without question.

How to get your 6-volume set

Detach the Order Form below and send it, with the appropriate remittance to :

**Purnell Book Service Ltd.,
Box 20 Abingdon, Berks, OX14 4HE**

Makes of Colour TV include :

Alba, Baird, Bang and Olufsen, B.R.C., Bush, Decca, Dynatron, Ecko, Ferguson, Ferranti, G.E.C., Invicta, H.M.V., Marconiphone, I.T.T./K.B., Masteradio, Murphy, Philips, Pye, Sobell, Stella, Ultra, Hitachi, Thorn Consumer Electronics, Korting, R.G.D., Sony, Telefunken.

All these makes of Mono TV, Radios, Car Radios, Stereograms, Record Players, Tape Recorders :

Aiwa, Alba, Baird, Bang and Olufsen, Beogram, Beolit, Blaupunkt, B.R.C., Bush, Cossor, Crown, Dansette, Decca, Defiant, Dulci, Dynatron,, Eddystone, Ecko, Elizabethan, Ferguson, Ferranti, Fidelity, G.E.C., Grundig Hacker, Halcyon, H.M.V., Hitachi, Invicta, I.T.T./K.B., JugoElektra, Klinger, Loewe Opta, Marconiphone, Masteradio, Monogram, Murphy, National, Nivico, Perido, Peto Scott, Philco, Philips, Portadyne, Pye, Radiomobile, Radionette, R.G.D., Roberts' Radio, Robux, Sanyo, Sharp, Sobell, Sony, Standard, S.T.C., Stella, Stereosound, Telefunken, Teletron, Thorn, Sanyo, Ultra, Van Der Molen, World Radio, Thorn Consumer Electronics, Elpico, Rigonda (USSR), Waltham.

Plus, such developments as :

Mullard Integrated Units, Electronic Video Recording and Reproduction - EVR system, Radio Receivers - Car radios, Stereo Multiplex reception, Capacitance Diode Tuning, Colour Television Test Equipment - Cross-hatch Generator, Degaussing Coil, E.H.T. Meter, Colour Bar Generator, Cathode Ray Oscilloscope, Power Supply requirements, Alignment, Circuit design.

To: Purnell Book Services, P.O. Box 20, Abingdon, Berks OX14 4HE

Please send me the 6-volume set of RADIO & TV SERVICING for which I enclose cheque/P.O. No. _____, crossed and made payable to Purnell Book Services Ltd.

for the full cash price of £27.75 tick

for £10 deposit to be followed by 4 successive appropriate
monthly payments of £4.75 (total £29) box

I understand that unless I am entirely satisfied I may return the volumes in good condition within 10 days and my money will be refunded in full. **BLOCK LETTERS PLEASE**

Name

Address

TRADE APPLICATION (To be accompanied by Trade Order)

Please supply _____ 6-volume set(s) of RADIO & TV SERVICING at £27.75 per set. (Credit 30 days)

BLOCK LETTERS PLEASE


Name

Company

Signature

IMPORTANT: Individual volumes are available on application.

Please return entire form. Available U.K. only.



JAMES SCOTT

F.M. ELECTRONICS ALIGNMENT UNITS

This is a companion unit to the DR Alignment Unit and is used to align the record and reproduce electronics of F.M. recording channels of multi-channel instrumentation tape recorders conforming to the I.R.I.G. Intermediate and low band requirements.

The two main functions in an F.M. recording system which require periodical checking are:


- (a) The accuracy and linearity of the Record Modulator.
- (b) The accuracy and linearity of the Reproduce Demodulator.

The F.M. Alignment unit checks both these functions by the use of a standard voltage and a range of standard frequencies corresponding to the tape speed carrier centre frequencies and the $\pm 40\%$ deviation frequencies for each recording speed.



CUT ALIGNMENT TIME & COST

JAMES SCOTT (ELECTRONIC ENGINEERING) LTD. Carntyne Industrial Estate Glasgow E2 Tel. 041-778 4206



WW-027 FOR FURTHER DETAILS

SHIBADENS NEW TIME LAPSE RECORDER

A single VTR that brings maximum FLEXIBILITY to any application

Shibadens new Time Lapse Recorder mixes and matches recording and playback times so that whatever your requirement you can get the complete answer with this versatile new VTR unit. The SV 612 E (K) will shorten one recording and lengthen another or vice versa. And however you use the Recorder – for Traffic Systems, the study of nervous diseases, sporting events or to improve security – no matter what the mode, you will not be troubled with tape compatibility, because the SK 612 E (K) uses tapes on any EIA-J type I format VTR.

CHOICE OF FIVE RECORDINGS

Each unit offers a choice of five recordings and playback periods – ranging from 1, 6, 12, 24 or 48 hours. Reproduction quality and picture stability are maximised by the use of ferrite video heads. The SV 612 E (K) is equipped with AGC for video and audio output and has audio dubbing facilities.

From a standard 60 minute tape you can obtain up to 48 hours playback. The Quick Motion playback permits extensive use for such studies as flowers in bloom and metamorphosis whilst for sporting events the slow motion playback facility extends a one hour recording at normal speed to 6, 12, 24 or 48 hours.



If you need maximum flexibility for record and playback in a single unit you need Shibadens new Time Lapse Recorder. Write now for full technical specifications or telephone the Shibaden Technical Service.

HITACHI SHIBADEN (U.K.) LIMITED

BROADCAST & CCTV EQUIPMENT MANUFACTURERS
Lodge House · Lodge Road · Hendon · London
NW4 4DQ. Telephone: 01-203 4242/6

WW-028 FOR FURTHER DETAILS

www.americanradiohistory.com




4 channel decoder modules

Tate 4-channel equipment decodes all quadrasonic matrix records and broadcasts and adds dimensional realism to ordinary stereo programme sources. It also controls 4-channel tapes when played through your system and CD-4** records when used with a separate demodulator.

They are characterized by their ultra low distortion characteristics and six-pole wideband phase shift networks. These combine to produce an acoustic performance giving highly articulate sounds from the back as well as the front channels. The amplitude accuracy is better than $\pm 1\text{dB}$ from 5Hz to 100KHz.

tate 2




High definition SQ* quadrasonic decoder Fully built home constructor module
 features: exclusive wide band phase shift network; distortion typically 0.04%. Ideal for use with other kit projects and even with the world's finest amplifiers.

Recommended retail price (excluding VAT) **£12.95**

Dimensions: 85 x 60 x 25mm

Operating Voltages: 18-30VDC at 11ma

tate 4



High definition SQ* quadrasonic decoder Fully built home constructor module
 featuring **wide band** matrix decoding circuit board with integrated power supply, switching, master gain and exclusive rear level control.

Recommended retail price (excluding VAT) **£21.95**

Dimensions: 165 x 140 x 26mm

Operating Voltages: 110-240VAC at 3watts

Specifications

Input Impedance	40K Ohms
Output Impedance	<300 Ohms
Phase Shift Network 90 \pm 10'	20Hz-18KHz
Nominal Gain	Unity
Frequency Response $\pm 1\text{dB}$	5Hz-100KHz
Nominal Input Level	250mVrms
Nominal Distortion	0.025%
Clipping Point	2.5Vrms
Distortion before Clipping	0.08% max.
Front Separation	>60dB
Rear Separation	>20dB

Tate Audio Transmission Equipment Limited
 5-7 Covent Garden Cambridge CB1 2HS England
 Telephone 0223 67873 Telex 81640
 Registered in London No. 1059684

*TM CBS Inc. **TM Victor Japan

The only way to really understand the difference between ordinary stereo and SQ Quadrasonic sound is to hear it. However, if you remember the difference between mono and stereo upon hearing it for the first time, multiply the recollection of that experience by a factor of ten and you will be able to appreciate what is in store for you: when you first hear SQ Quadrasonic sound.

Please send **tate 2** at £14.25 each (including VAT)
 tate 4 at £24.15 each (including VAT)


I enclose cash/cheque/money order

Name (BLOCK LETTERS) _____

Address _____

WW93

LITTLE WONDER



THE MINITEST IS PREFERRED

The SEI MINITEST has made a remarkable impact in the pocket-sized multi-range meter market, by making itself a firm favourite with discerning people in the industry. Let's look into the reasons why.

First, the appearance. Diminutive, neat, wipe-clean plastic cover with pressed steel case. Controls are simple and easy to use.


Second, the range. The Minitest measures a.c. and d.c. voltages d.c. current and resistance over 20 ranges to a sensitivity of 20,000 and 2,000 ohms per volt d.c. and a.c. respectively.

Third, high voltage probes. These extend the range to 25 or 30kV d.c.

Little wonder the Minitest is preferred!


SALFORD ELECTRICAL INSTRUMENTS LTD

Peel Works, Barton Lane, Eccles, Manchester M30 0HL.
Telephone: 061-789 5081. Telex: 667711.
A member company of GEC Electrical Components Ltd.



WW-030 FOR FURTHER DETAILS

Accurate and direct measurement of speed without coupling to moving parts



FRAHM resonant reed TACHOMETERS

for hand use or permanent mounting

Ranges and combinations of ranges from 900 to 100,000 r.p.m.

Descriptive Literature on Frahm Resonant Reed Tachometers and Frequency Meters available from the sole U.K. Distributors. Manufacture and Distribution of Electrical Measuring Instruments and Electronic Equipment. The largest stocks in the U.K. for off-the-shelf delivery.


ANDERS ELECTRONICS LIMITED

Anders means meters

48/56 Bayham Place, Bayham Street, London NW1. Tel: 01-387 9092

WW-031 FOR FURTHER DETAILS

nombrex



MODEL 41 R.F. SIGNAL GENERATOR Price £35.00.

FROM APRIL 1st PLEASE ADD 10% ON TO PRICE FOR V.A.T.

- ★ 150 KHz — 220 MHz on fundamentals.
- ★ 8 clear scales — Total length 130mm.
- ★ Spin-Wheel Slow Motion Drive 11 — 1 ratio.
- ★ Overall Accuracy — 2½%.
- ★ Modulation. Variable depth and frequency.
- ★ Internal Crystal Oscillator providing calibration checks throughout all ranges.
- ★ Mechanical scale adjustment for accurate alignment against internal 1MHz crystal oscillator.
- ★ Powered by 9V Battery.

Trade and Export enquiries welcome.

Send for full technical leaflets.

Post and Packing 35p. extra.

NOMBREX (1969) LTD., EXMOUTH, DEVON.
Tel: 03-952 3515

WW-032 FOR FURTHER DETAILS

Handful of relay know-how!



We are one of the largest manufacturers of Miniature Plug-in Relays in Europe.

Varley miniature plug-in relays including the Miniaturised Bi-stable polarised relay type VPR and Post Office approved relay type 23 are used and approved by most leading electronic manufacturers throughout the world. The reasons: PERFORMANCE, RELIABILITY, PRICE.

Varley go to great lengths to ensure a consistently high standard of performance and reliability in the manufacture of their range of relays. Ultrasonic cleaning is used throughout manufacture. Each relay is checked under dynamic conditions for contact performance and timing.

If you have a relay requirement or problem contact Varley Technicians now, or send the coupon for the Varley catalogue.



Oliver Pell Control Ltd.
Cambridge Row, Burrage Rd., Woolwich,
London, SE18. Tel: 01-854 1422 Telex: 897071

Name _____
Company _____
Address _____

WW 9-73

WW-033 FOR FURTHER DETAILS


Save millimetres AND money with this new Brimar Tube

If you're planning an oscilloscope – or any instrument for waveform monitoring – Brimar has good news for you. The **Brimar D10-230** mono-accelerator tube is a real winner where low cost and small size are important considerations.

Short in length, small around the neck, it can save you a whole lot of space... give you far greater freedom in your designing. The flat 4" diameter face offers minimum total scans of 80mm and 64mm, in X and Y directions respectively. And its voltage requirements are within the capability of normal, low-cost, transistorised circuits.

This tube with its Standard B14G Colour tube base also allows economies to be made in Socket costs and, being round, requires no twist coil.

- ★ Maximum overall length: 260mm
- ★ Maximum neck diameter: 38mm
- ★ First anode voltage: V_{a1} , 1500V
- ★ Second anode voltage for focus: V_{a2} , 230 to 380V
- ★ Grid voltage for spot cut-off (approx.):
 V_g -30 to -65V
- ★ X plate deflection coefficient: D_x , 21 to 26V/cm
- ★ Y plate deflection coefficient: D_y , 13 to 16V/cm
- ★ The standard phosphor is GH
(green, medium persistence).



Ask for full data, or for a sales engineer to call:-

CRT reliability

BRIMAR

Thorn Radio Valves and Tubes Limited,
Mollison Avenue, Brimsdown, Enfield,
Middlesex EN3 7NS.
Telephone: 01-804 1201

THORN

WW-034 FOR FURTHER DETAILS

We'll pot your 'babies' for you



When you've got components that call for encapsulation—bring them along to Whiteley. With efficient potting, your components will be totally insulated and environmentally protected—and Whiteley experience in developing this advanced plastics technique will ensure that it is applied to full advantage.

We can encapsulate in epoxy resin or polyurethane—hot setting or cold setting as required. Where fillers offer advantages, we can apply them, expertly. We are ready to handle small quantities or volume production for you. It's one more way in which you can capitalise on our production resources. For electrical and electronic work—right through from design to final assembly—you can safely follow the example of many famous names—and call in Whiteley.

Whiteley

versatility...

ELECTRONIC & ELECTRICAL DESIGN

PRODUCTION CAPABILITY

CABINET MAKING

SHEET METAL FORMING/FINISHING

PLASTICS MOULDING

ENCAPSULATION


WHITELEY ELECTRICAL RADIO CO. LTD.
Mansfield, Notts, England. Tel. Mansfield 24762
London Office: 109 Kingsway, W.C.2. Tel. 01-405 3074

WW-035 FOR FURTHER DETAILS

BULGIN

Two New
Competitive Products

**NOW
IN
STOCK**



A new ingenious design of moulded Toggle switch employing a QMB wiping contact action, for AC/DC compatibility and heavy silver plated contacts/tags for long life. Illustrated is S.910. S.P.C.O. rated 2A at 250V. AC., is S.900 Make-Break contacting, rated 3A at 250V. is also available.

BOTH of these new switches are economically priced but of a high standard of quality and reliability.

And Now!




**NEW DESIGN
5 X 20^{mm}
FUSEHOLDER
LIST NO. F.396
NOW AVAILABLE WITH
RATING INDICATORS**

INTRODUCING a new design fuseholder F.396, which conforms to the safety standards of IEC 257, shown here fitted with our new 'rating indicator' P.No.11233/ Rating. This simple attachment avoids the possibility of errors in fuse replacements, thus preventing damage to expensive electronic equipment due to incorrect fuse being used. The amperage of the fuse is clearly visible, being printed in black on a silver-matt finished aluminium background.

BOTH the fuseholder and indicators are proving very popular since they were first shown at the London Electronic Components Exhibition.

THE indicator is available in six popular ratings (As illustrated left) at most competitive prices. It can be used in conjunction with the following fuseholders, F.296, F.297, F.298, F.296/POT, F.297/POT, F.296/S, F.297/S and F.396.



TECHNICAL LITERATURE AVAILABLE ON REQUEST. QUOTE: WW/4/73



A. F. BULGIN & CO. LTD.
ELECTRONIC COMPONENT MANUFACTURERS

BYE-PASS ROAD BARKING ESSEX IG11 0AZ
TEL: 01 594 5588 (12 lines) P.B.X. TELEX: 897255

WW-043 FOR FURTHER DETAILS

ENGINEERS!

**WRITE FOR THE BOOK
THAT CAN CHANGE
YOUR WHOLE FUTURE**



The B.I.E.T. guide to success should be read by every ambitious engineer. Do you want promotion, a better job, higher pay? "New Opportunities" shows you how to get them through a low-cost B.I.E.T. home study course. There are no books to buy and you can pay-as-you-learn.

Send for this helpful 76 page FREE book now. No obligation and nobody will call on you. It could be the best thing you ever did.

CUT OUT THIS COUPON
CHOOSE A NEW FUTURE NOW!

Tick or state subject of interest. Post to address below.

- | | | |
|---|--|--|
| <input type="checkbox"/> MECHANICAL | <input type="checkbox"/> Work Study Works | <input type="checkbox"/> CONSTRUCTIONAL |
| <input type="checkbox"/> A.M.S.E. (Mech) | <input type="checkbox"/> Management | <input type="checkbox"/> A.M.S.E. (Civil) |
| <input type="checkbox"/> C & G Eng. Crafts | <input type="checkbox"/> DRAUGHTSMAN- | <input type="checkbox"/> Architecture |
| <input type="checkbox"/> C & G Fabrication | <input type="checkbox"/> SHIP | <input type="checkbox"/> Building |
| <input type="checkbox"/> Diesel Eng. | <input type="checkbox"/> A.M.I.E.D. | <input type="checkbox"/> Carpentry & Joinery |
| <input type="checkbox"/> Inst. Eng. & Tech. | <input type="checkbox"/> Electrical | <input type="checkbox"/> Civil & Municipal Eng. |
| <input type="checkbox"/> Inst. Motor Ind. | <input type="checkbox"/> Draughtsmanship | <input type="checkbox"/> Constructional Eng. |
| <input type="checkbox"/> Maintenance Eng. | <input type="checkbox"/> Gen. | <input type="checkbox"/> Construction |
| <input type="checkbox"/> Mechanical Eng. | <input type="checkbox"/> Draughtsmanship | <input type="checkbox"/> Surveyors Institute |
| <input type="checkbox"/> Sheet Metal Work | <input type="checkbox"/> Jig & Tool Design | <input type="checkbox"/> Council Eng. |
| <input type="checkbox"/> Welding | <input type="checkbox"/> Technical Drawing | <input type="checkbox"/> Health Eng. |
| <input type="checkbox"/> ELECTRICAL & ELECTRONIC | <input type="checkbox"/> RADIO & TELE-COMMUNICATIONS | <input type="checkbox"/> Hydraulics |
| <input type="checkbox"/> A.M.S.E. (Elec.) | <input type="checkbox"/> C & G Radio/TV/ | <input type="checkbox"/> Inst. of Builders |
| <input type="checkbox"/> C & G Elec. Eng. | <input type="checkbox"/> Electronics | <input type="checkbox"/> Inst. Clerk of Works |
| <input type="checkbox"/> C & G Elec. Inst. | <input type="checkbox"/> C & G Telecomm. | <input type="checkbox"/> Inst. Works & Highway Supers. |
| <input type="checkbox"/> C & G Elec. Tech. | <input type="checkbox"/> Technicians | <input type="checkbox"/> Painting & Decorating |
| <input type="checkbox"/> Computer Elec. | <input type="checkbox"/> Pract. Radio & Elec. (with kit) | <input type="checkbox"/> Structural Eng. |
| <input type="checkbox"/> Electronic Eng. | <input type="checkbox"/> Radio Amateurs | <input type="checkbox"/> Surveying |
| <input type="checkbox"/> Electrical Eng. | <input type="checkbox"/> Exam. | <input type="checkbox"/> GENERAL |
| <input type="checkbox"/> Install. & Wiring | <input type="checkbox"/> Radio Servicing & Repairs | <input type="checkbox"/> Agricultural Eng. |
| <input type="checkbox"/> MANAGEMENT & PRODUCTION | <input type="checkbox"/> Transistor Course | <input type="checkbox"/> Council of Eng. Inst. |
| <input type="checkbox"/> Computer Prog. | <input type="checkbox"/> TV Main & Serv. | <input type="checkbox"/> General Education |
| <input type="checkbox"/> Electronic Data Processing | <input type="checkbox"/> AUTO & AERO | <input type="checkbox"/> Pract. Slide Rule |
| <input type="checkbox"/> Estimating | <input type="checkbox"/> Aero Eng. | <input type="checkbox"/> Pure & Applied Maths. |
| <input type="checkbox"/> Foremanship | <input type="checkbox"/> A.M.I.M.I. | <input type="checkbox"/> Refrigeration |
| <input type="checkbox"/> Inst. Cost & Man. | <input type="checkbox"/> A.E.C. Cert. | <input type="checkbox"/> Rubber Technology |
| <input type="checkbox"/> Accountants | <input type="checkbox"/> Auto Engineering | <input type="checkbox"/> Sales Engineers |
| <input type="checkbox"/> Inst. Marketing | <input type="checkbox"/> Auto Repair | <input type="checkbox"/> University Ent. |
| <input type="checkbox"/> Management | <input type="checkbox"/> C & G Auto Eng. | |
| <input type="checkbox"/> Motor Trade Man. | <input type="checkbox"/> Garage Management | |
| <input type="checkbox"/> Network Planning | <input type="checkbox"/> MAA/IMI Diploma | |
| <input type="checkbox"/> Personnel Man. | <input type="checkbox"/> Motor Vehicle Mechanics | |
| <input type="checkbox"/> Production Eng. | | |
| <input type="checkbox"/> Quality Control | | |
| <input type="checkbox"/> Salesmanship | | |
| <input type="checkbox"/> Storekeeping | | |

G.C.E. 58 'O' & 'A' LEVEL SUBJECTS
Over 10,000 Group Passes

Coaching for many major exams, including C & G and also assistance in O.N.C./H.V.C

SEND FOR YOUR FREE BOOK NOW!
BRITISH INSTITUTE OF ENGINEERING TECHNOLOGY




DEPT. BWW08 ALDERMASTON COURT, READING RG7 4PF

NAME _____
BLOCK CAPITALS PLEASE
ADDRESS _____

OTHER SUBJECTS _____ AGE _____
Accredited by the Council for the Accreditation of Correspondence Colleges.


AMTRON kits for the Audio Enthusiast

These kits have been selected from AMTRON's vast range of electronic kits. Each unit comes with all components, instructions, and solder.



UK187 HI-FI QUADRIC STEREO AMPLIFIER 20+20W.

The UK187 Hi-Fi Amplifier has an output of 20W per channel plus a 'quadric' section feeding two groups of speakers, front and rear.



UK175 STEREO PREAMPLIFIER WITH TONE CONTROLS

The UK175 has been specially developed to be used with UK192 50W per channel stereo amplifier.



THREE-WAY CROSS OVER FILTER 12db/OCTAVE

The UK800 three-way cross-over filter with a 12db/Octave roll off is a true separation for bass speaker, mid range and tweeter units

THE BIG NAME IN ELECTRONIC KITS



4 & 7 CASTLE STREET, HASTINGS, SUSSEX TN34 3DY

TEL: HASTINGS 2875



Check in one direct move with Brandenburg's new HV meter

We thought it was about time somebody supplied *direct reading* meters for high voltage, so we've produced three—one for up to 5kV, one for 15kV and one for 30kV to complement our range of HV power supplies.

The meters are operated by two 9V internal batteries (800 hours life) linked with a built-in checking facility. Positive or negative ground is available, selected by a front panel switch. And, as with all Brandenburg products, there is a 12 months unconditional guarantee.

- Accuracy of 1% fsd over voltage range of 0.30kV d.c.
- Less than 1 μ A drawn at 30kV d.c.
- 4.5in (114 mm) scale mirror-backed meter.
- Temperature range 5-35°C.
- Dimensions only 7 x 8 x 5½in high (200 x 145 x 178mm).
- Recorder output.

Yet another Brandenburg piece in the
high voltage game

brandenburg

STABILISED HIGH VOLTAGE

Brandenburg Limited, 939 London Road, Thornton Heath, Surrey, CR4 6JE, England. Tel: 01-689 0441 Telex: 946149


Agents or distributors in most principal countries.

P6437

WW—038 FOR FURTHER DETAILS

THERMOCOUPLE POTENTIOMETER

Type P8



RANGE 0 to 50mV
 RESOLUTION 1 μV
 ACCURACY ± 0.01%

3 TEST CIRCUITS
 IN-LINE READOUT
 BATTERY OPERATED

Request full details from:

CROYDON PRECISION INSTRUMENT CO.

HAMPTON ROAD, CROYDON, CR9 2RU

Telephone: 01-684 4025 and 4094

WW—039 FOR FURTHER DETAILS



MODEL U-50DX

SANWA MULTI TESTERS

USED THROUGHOUT THE WORLD. SANWA'S EXPERIENCE OF 30 YEARS ENSURES ACCURACY, RELIABILITY, VERSATILITY. UNSURPASSED TESTER PERFORMANCE COMES WITH EVERY SANWA 6 Months' Guarantee Excellent Repair Service

MODEL P2B	£6.67	MODEL AT45	£21.52
MODEL JP5D	£8.00	MODEL 380CE	£21.85
MODEL 360YTR	£11.30	MODEL N101	£25.41
MODEL U50DX	£11.43	MODEL 460ED	£29.72
MODEL A303TRD	£15.04	MODEL EM800	£72.79
MODEL K30 THD	£17.21	MODEL R1000CB	£75.27
MODEL F80TRD	£18.73		

THESE PRICES ARE SUBJECT TO AN ADDITIONAL CHARGE OF 10% FOR V.A.T. Cases extra, available for most meters, but not sold separately.

Please write for illustrated leaflet of these and other specialised Sanwa meters

SOLE IMPORTERS IN U.K. QUALITY ELECTRONICS LTD.

47-49 HIGH STREET, KINGSTON-UPON-THAMES, SURREY. KT1 1LP
 Tel: 01-546 4535

WW—040 FOR FURTHER DETAILS

'W.W.' DIGITAL MULTIMETER


(D. E. O'N. Waddington, March 1973)

LIST OF PARTS NOW AVAILABLE

Please send a stamp
 We will also include our illustrated lists of other components

CAVERN ELECTRONICS
 29 CLAREFIELD ROAD, LEICESTER LE3 6FB
 Tel.: Leicester (0533) 857223
 (Mail Order only)

WW—041 FOR FURTHER DETAILS



for the professional

contact **Derek Owen** at 01-874 9054 or Telex 923455

LEEVERS-RICH

EQUIPMENT LIMITED


Agents in Scandinavia, Eastern and Western Europe, Middle East, Africa, Australasia and the Far East.

LEEVERS-RICH EQUIPMENT LIMITED
 319 TRINITY ROAD · LONDON SW18 3SL
 Telephone 01 874 9054 · Telex 923455
 Cables LEEMAG LONDON



WW—042 FOR FURTHER DETAILS

www.americanradiohistory.com



What is TELEFI?

Telefi brings you for the first time real Hi-Fi results from your existing 625 line television.

T.V. Studios transmit superb quality but skimping in the sound section of the receiver means low-fi sound.

Celestion Terefi changes all this - simply coupled to most T.V. receivers - the first T.V. music you hear through Telefi will convince you the dramatic improvement is what you have been waiting for.

Telefi a remarkable innovation exclusive to Celestion for use in

conjunction with Hi-Fi and Audio systems for providing high quality television sound reproduction. No direct connection to the T.V. is required, the coupling being effected by an inductive pick-up.

Telefi is complete in a handsome natural teak veneered case 7 1/2" x 5 1/8" x 2 1/8" approx.

"The Telefi is a very worth while device and will give greater overall enjoyment than the T.V. manufacturers normally provide." *John Gilbert 'The Gramophone'*

Celestion



Also send for details of the complete range of Celestion Loudspeakers

ROLA CELESTION LTD.

DITTON WORKS, FOXHALL ROAD, IPSWICH, SUFFOLK IP3 8JP

WW-044 FOR FURTHER DETAILS

NEW INTEGRATED CIRCUITS



Quadraphonic decoder MC 1312P MC 1313P	Designed to decode an SQ encoded programme into four separate channels. The device conforms to specifications for decoding quadraphonic records using the popular CBS system. (includes CBS royalty) £2.24
FM Stereo decoder MC 1310P	Requires only thirteen resistor/capacitors to build a complete unit that will convert an existing mono FM tuner to stereo operation. Has a built in mono/stereo switch capable of driving a 75mA signal lamp. £2.93
Stereo preamplifier MC 1339P	A low noise stereo pre-amp in one TO-116 package and sensitive enough to handle a magnetic cartridge input! Provision is made for a tone control network and the device has a built in power supply ripple filter. £1.07
2 watt mono amplifier with pre-amp MC 1316P	A useful low cost device for all phono applications, intercoms, baby alarms etc. Has a full 2W RMS output with no extra heat sink required. The pre-amp is electrically separate from the power amp giving the device useful versatility. £1.44
Timing Circuit MC 1455P1	A highly stable controller in which time delays (microseconds through hours) are accurately controlled by one external resistor and capacitor. Triggering and resetting terminals provided. Output can source or sink up to 200mA. £0.87
FM Radio or Colour TV Tuning Indicator ML 1335P	A must for spot on tuning. The device switches on a lamp when the receiver is precisely aligned on the centre of the incoming signal. Off centre tuning results in a dim lamp, noise only (no signal) will extinguish the lamp. £0.87

Specifications and Application information supplied with all devices.

To Jermyn Home Electronics
113 Vestry Estate, Sevenoaks, Kent

Please supply the following devices return of post

Type No. Quantity

I enclose cheque/POrder for £

Add 20p packing and postage +10% VAT on total order.

Jermyn

WW-036 FOR FURTHER DETAILS

Contractors to H.M. Govt, P.O.

REPAIRS

OF ELECTRICAL MEASURING INSTRUMENTS

7-14 DAYS SERVICE



MODEL B MK.V



STOCKISTS
ALSO SUPPLIERS OF GEC
RISO AND OTHER
MULTI-RANGE TEST SETS

WE SPECIALISE IN ASSEMBLIES, AND IN THE REPAIR, CALIBRATION AND CONVERSION OF ALL TYPES OF INSTRUMENTS, INDUSTRIAL AND PRECISION GRADE.

LEDON INSTRUMENTS LTD.

76-78 DEPTFORD HIGH STREET,
LONDON SE8.
TEL: 01-692 2689

GLADSTONE WORKS GLADSTONE RD.,
FOLKESTONE, KENT
TEL: (STD) 0333 57555

→ BRITAIN'S FASTEST SERVICE ←

component specialists for the discerning amateur and professional

COMPREHENSIVE
CATALOGUE

48 PAGES OF SEMICONDUCTORS AND
ASSOCIATED DEVICES ESSENTIAL
FOR PROJECT & PROTOTYPE

COMPREHENSIVE
CATALOGUE

ARROW ELECTRONICS LTD.

DEPT. WW1, 7 COPTFOLD ROAD, BRENTWOOD, ESSEX.




WW-045 FOR FURTHER DETAILS

SCOPEX 4D-25

The precision scope for
the demanding engineer

3% accuracy — which
just about summates
this new 25MHz
dual-trace instrument
from Scopex.
A professional scope
by any standards
— yet at £175 in a
price bracket far
below its design
specification.



- * DC-25MHz, full screen
- * Measuring accuracy 3%
- * Signal delay on both channels
- * Trig level and polarity from one simple control
- * Wide timebase range, 200 ns/cm to 200 ms/cm
- * Sensitivity 10mV/cm to 50 V/cm
- * High brightness PDA tube
- * Lightweight portability


NEW!

SCOPEX

Write now, or telephone:
Scopex Instruments Limited,
Pixmore Industrial Estate,
Pixmore Avenue,
Letchworth, Herts.
Tel: Letchworth 72771
(STD 04626)

WW-046 FOR FURTHER DETAILS

DDL 0465



Si451 Millivoltmeter

- * 20 ranges also with variable control permitting easy reading of **relative** frequency response

£35.00

JES AUDIO INSTRUMENTATION

Illustrated the Si453 Audio Oscillator

SPECIAL FEATURES:

- ★ very low distortion content—less than .05%
- ★ an output conforming to RIAA recording characteristic
- ★ battery operation for no ripple or hum loop
- ★ square wave output of fast rise time

£40.00

also available

Si452 Distortion Measuring Unit

- * low cost distortion measurement down to .01% with comprehensive facilities including L.F. cut switch, etc.

ALL PRICES PLUS V.A.T.

£30.00

J. E. SUGDEN & CO. LTD., CARR STREET, CLECKHEATON, YORKS. BD19 5LA.

Tel: 09762-2501

WW-047 FOR FURTHER DETAILS

MULLARD BOOKS ON ELECTRONICS

FOR THE ENGINEER ENTHUSIAST AND STUDENT

- APPLICATIONS OF INFRARED DETECTORS**
152 pages, illustrated..... £2.00
- COLOUR TELEVISION**
46 pages, illustrated in colour..... 87½p
- FIELD EFFECT TRANSISTORS**
132 pages, illustrated..... £1.80
- MAGNADUR MAGNETS FOR D.C. MOTORS**
52 pages, illustrated..... 75p
- MOS INTEGRATED CIRCUITS AND THEIR APPLICATIONS**
176 pages, illustrated..... £2.00
- MULLARD DATA BOOK**
160 pages, illustrated..... 30p
- POWER ENGINEERING USING THYRISTORS - VOL. 1 TECHNIQUES OF THYRISTOR POWER CONTROL**
240 pages, illustrated..... £1.50
- TRANSISTOR AUDIO AND RADIO CIRCUITS - 2nd EDITION**
238 pages, illustrated..... £1.80

ALSO MULLARD MINI BOOKS

an educational series.

- Integrated Circuits..... 40p
Magnetic Core Memories..... 40p
Principles of Electrostatics..... 20p
Principles of X-Rays..... 20p
Semiconductor Devices..... 37½p
Thyristors..... 50p

AND SIMPLE MEASUREMENT SERIES

experiments for education and training.

- Simple Transistor Measurements..... 25p
Simple Oscilloscope Measurements..... 25p
Simple Valve Measurements..... 25p
- The Diagnostic X-Ray Tube..... 50p
A Programmed Book on Semiconductor Devices..... 62½p

HOW TO GET YOUR COPY

From your local bookseller or cash with order plus postage and packing from:
Selray Book Company Limited,
60 Hayes Hill, Hayes, Bromley, Kent BR2 7HP
Or send for full list of Mullard titles from:
Dept. CIH Mullard Limited,
New Road, Mitcham, Surrey CR4 4XY.

M57

WW-048 FOR FURTHER DETAILS

INSIST ON VERSATOWER



Acclaimed as the World's leading telescopic tiltover tower in the field of radio communication Models from 25' to 120'



Look for the name **STRUMECH**

Strumech Engineering Co Ltd
Coppice Side, Brownhills, Walsall, Staffs.

WW-049 FOR FURTHER DETAILS

TWO NEW SOLDER SIPPERS MAKE DE-SOLDERING QUICK & EASY



Maxi-Super HT 1810 and Maxi-Mini HT 1800 Solder Sippers

Designed for use when working or re-working P.C. Boards. Permits removal of molten solder from Multi-leg components, enabling easy extraction. The solder is 'sipped' through the nozzle, and automatically ejected when the instrument is next used. A Swiss precision instrument manufactured to a high degree of accuracy.

The anti-corrosive outside casing has a knurled finish for more positive grip, and encases plated internal parts.

The Maxi-Super has been designed with a 3.5 kg. spring action recoilless plunger, whilst the Maxi-Mini with its conveniently shaped operating button, has a 2.5 kg. spring action plunger, protected by a channel guard. Both models have been designed with an easy-to-replace 'dupont' teflon screw-in nozzle.

Longs

Longs Ltd.
Hanworth Lane
Trading Estate
Chertsey Surrey
KT16 9LZ.

PLEASE FORWARD without obligation further details. PLEASE SUPPLY Maxi-Super HT 1810 at £6.60 PLEASE SUPPLY Maxi-Mini HT 1800 at £4.95

I enclose cheque value £ _____

NAME _____ POSITION _____

COMPANY _____

ADDRESS _____

SIGNED _____

Prices include VAT

Reg. England 68496

WW-050 FOR FURTHER DETAILS


THE 5350 — A NEW CONCEPT IN NUCLEAR SPECTROMETERS



This is an entirely new range of purpose-built Nuclear Spectrometers with many outstanding new features which will have immediate appeal to those engaged at any level in the analysis of radioactivity.

- ★ 4-mode pulse height analysis
- ★ Wide-range ratemeter with zero suppression
- ★ Simple controls
- ★ Charge-sensitive input
- ★ NIM-compatible signal levels
- ★ Integrated circuits throughout
- ★ Attractive yet robust housing
- ★ Low cost

For full information: —




ESI NUCLEAR LIMITED,
2 CHURCH ROAD, REDHILL,
SURREY RH1 6QA
 Tel: Redhill (91) 64993

An Associate Company of Edwards Scientific International,
 Mirfield, Yorkshire.

WW—051 FOR FURTHER DETAILS

New — 15MHz Portable Dual Trace Oscilloscope

Type 201 — £170* (UK, excluding VAT)



5mV/Div.
 100 nS/Div.
 PLUG-IN
 Timebase and
 Amplifier
 Modules

* with 212 Amplifier and 211 Timebase

Utterly portable, accurate and easy to use. Features exceptional triggerability and high definition CRT. Get in touch now for further details.



Meteronic Ltd.,

114/116 Shipbourne Road,
Tonbridge, Kent.
Tel: Tonbridge 61448.

WW—052 FOR FURTHER DETAILS

MULLARD BOOKS ON ELECTRONICS

NEW!
MOS
INTEGRATED
CIRCUITS
AND THEIR
APPLICATIONS

This book describes the construction, manufacture and characteristics of MOS integrated circuits, and the ways in which they can be used.


The MOS integrated circuit has considerable advantages over the bipolar type in applications where large arrays of devices are used. Some typical applications where this type of integrated circuit shows its advantages are discussed.

Contents:

MOS fundamentals - manufacture of MOS integrated circuits - dc or static characteristics - MOS static inverter - MOS switching characteristics - MOS gate circuits, static logic - dynamic logic circuits - four-phase dynamic logic circuits - interface circuits - input and output protection - MOS logic applications. Size 8½" x 6" clothbound, 176 pages, illustrated.

Price £2.00

THE MULLARD DATA BOOK 1973/4



The colour-coded sections of the latest edition of Mullard Data Book are packed with information on valves, integrated circuits, semiconductors, picture tubes and components. The book also lists equivalents and comparables. **ORDER NOW!**

Price 30p

HOW TO GET YOUR COPY

From your local bookseller or cash with order direct from Selray Book Company Limited, 60 Hayes Hill, Hayes, Bromley, Kent, BR2 7HP.

WW—053 FOR FURTHER DETAILS

Soldering was never so simple.

Greenwood Electronics brings you four top-class electronics applications products.

Iso Tip cordless soldering iron.

For the first time ever in the UK you can have a safe, high-power soldering iron which can be used anywhere without a mains lead.

This is the direct result of a breakthrough in the use of nickel cadmium cells as a rechargeable power source.

Tip performance is up to 50 watts, with over 360°C tip temperature.

The tip reaches operating temperature within 5 seconds. It cools equally rapidly.


It comes with a charging stand for either 240V or 115V A.C. operation. There is also a 12-volt model that can be charged from a car battery. Each charge is capable of more than 60 soldering joints. £9.95 +V.A.T.

Adjustable bench vice.

The new Oryx adjustable bench vice is designed to operate where accurate workpiece location is essential. So the user is able to carry out soldering and assembly on printed circuit boards and handle drilling and cutting operations on even the most delicate components.

Positioning of the vice is easily and quickly carried out, without removing the workpiece.

The vice has two adjustment facilities. Replaceable nylon jaw linings enable the workpiece to be firmly gripped without damage. £13.85 - V.A.T.



Oryx 50: an authentic temperature controlled soldering iron.

The Oryx 50 is another instrument which is ideal for precision soldering, and totally independent of external controls. The iron is mains operated, light, compact and easy to handle. However, despite its small size it's equipped with a large 50W element loading, giving rapid heating and high performance with constant tip temperature.

Temperature control is within $\pm 2\%$, with one long life iron-coated tip serving all temperatures.

A comprehensive range of replacement tips is available.

As a safety feature, an indicator lamp is fitted. Choice of voltages: 12, 24, 50, 115 and 210/250.

£5.20 V.A.T.



The Oryx SR3A desoldering tool.

The SR3A is a new, improved desoldering tool, especially designed for removal where components are tightly grouped or otherwise inaccessible.

It instantly removes all unwanted solder from printed circuits and all other solder joints.

Simple, reliable, speedy and accurate, it meets today's most stringent safety regulations. £4.50 + V.A.T.

If you do any soldering at all, and certainly if you do a lot of soldering, you owe it to yourself to make it as easy as possible. Write today for full details of our range.



I'd like to make precision soldering easier.

Please send me details on how to do it.

I understand this places me under no obligation.

Name

Address

Greenwood Electronics,
21 Germain Street, Chesham,
Bucks, HP5 1LL.
Tel: 02405 4808

ww/9/73


GREENWOOD ELECTRONICS

21 Germain Street, Chesham, Bucks, HP5 1LL. Tel: 02405 4808

WW-054 FOR FURTHER DETAILS

REW


The finest independent video and audio centres in Europe



leading Audio Equipment is also on display. The opening of the new showrooms at Centrepoint means we can now extend our expert service to customers in the West End of London.

R.E.W. Audio Visual Co. now have two video and audio centres serving the needs of industry, commerce and education. At Colliers Wood there is a complex covering 7,000 square feet with its own spacious car park and housing Video Demonstration Studios, Video Recording Studios and a Hire Department. Vast stocks of leading equipment are available including Video Cassette Recorders and 525 line American Standard Equipment. There is a trade counter for immediate sales service on Video Tapes and Accessories and a Service Department, 2,000 sq. ft. in area staffed by qualified engineers. A special Department is available for Video Tape Dubbing and Video Tape Copying of all formats. A large range of

AKAI VTS 110 DX Portable battery/mains video system




Rec'd Price £595 + VAT

VERY SPECIAL OFFER

£535 + VAT

- * Portability
- * Batt/Mains
- * Built-in monitor for instant replay
- * $\frac{1}{4}$ tape — low cost soft ware
- * Simple operation
- * Convenient light weight — 18.6 lbs.



THE LATEST SONY AV SERIES AT REW NOW!


High picture resolution of more than 300 lines using high density $\frac{1}{2}$ inch tape.

AV-3420 'ROVER' Portable VTR & camera

- * Half-hour playing time on 1,200 ft. 5 inch tape.
- * Features playback through camera eye-piece or any attached monitor.

£750 + VAT

HIRE SERVICE We have the full range of Sony, Akai, Shibaden, Philips, IVC, Ampex etc. for immediate hire from stock. Also American Standard 525 line Sony Equipment and 525 line NTSC Sony U-Matic colour Video Cassette Recorders.



REW AUDIO VISUAL CO.


R.E.W. House, 10-12 High Street, Colliers Wood, London SW19 2BE. Telephone: 01-540 9684/5/6/7
Centrepoint, Junction of New Oxford Street & Charing Cross Road, WC2.
Also at 146 Charing Cross Road, London WC2.

Linstead Laboratory Instruments



M2B

WIDE RANGE MILLIVOLTMETER
High impedance millivoltmeter with 20 scales total measurement range 60 micro-amp a.c. to 400 volts d.c. 10 megohm input with overload protection and frequency range of 500 kHz. **£35.00**



G5


WIDE BAND SIGNAL GENERATOR
Sine-square wave wide band high power signal generator. 10 Hz—1 MHz, 0—6 volts r.m.s., 2 watts into 5 ohms incorporating short circuit protection. **£32.00**

Linstead

means a good deal
in electronics

Linstead Electronics, Roslyn Works, Roslyn Road,
London N15 5JB. Telephone: 01-802 5144

WW—056 FOR FURTHER DETAILS



Get to grips
with your problem
by using WCL
electrolytic
capacitors
NOW!


BLORE-BARTON LTD
Reedham House
Burnham Bucks
telephone Burnham 5524
telex 847322



WW—057 FOR FURTHER DETAILS


PEAK PROGRAM METERS

to all B.B.C. specifications



AND VU METERS

TO THE BELL SPECIFICATION



OVERSEAS AGENCIES		
R. Schmidt	Copenhagen	Denmark
OyChester	Helsinki	Finland
Theal N.V.	Amsterdam	Holland
Vianello	Milan	Italy
Rieck	Bergen	Norway
Eltec	Lisbon	Portugal
Nordstrand	Stockholm	Sweden

Ernest Turner
ELECTRICAL INSTRUMENTS LTD
CHILTERN WORKS
HIGH WYCOMBE
BUCKS
ENGLAND

WW-058 FOR FURTHER DETAILS

If you want to be in the know

about Europe's most advanced ENTERTAINMENT SOUND SYSTEMS

then place a tick in appropriate box, complete coupon and send to SNS Electronics Group, 851 Ringwood Road, Northbourne, Bournemouth BH11 8LN. We'll send you some interesting details by return. *I am interested in:*

- | | |
|---|---|
| <input type="checkbox"/> Discotheque Systems | <input type="checkbox"/> Heavy Duty Speakers |
| <input type="checkbox"/> Vocal Mixer Amplifiers | <input type="checkbox"/> Distinctive range of specialist Loudspeakers |
| <input type="checkbox"/> Instrument Amplifiers | <input type="checkbox"/> Radio Microphone Systems |
| <input type="checkbox"/> Other..... | |

Name _____

Address _____



WW-059 FOR FURTHER DETAILS

PRODUCTION TESTING


DEVELOPMENT

SERVICING

EDUCATION

POWER UNITS

NOW AVAILABLE WITH 3 VARIABLE OUTPUTS



Type VRU/30/25 — £158 80

Input 200-250V, 50Hz
or 100-120V, 60Hz to order
Output 1:0-30V, 25A, D.C.
Output 2:0-70V, 10a, A.C.
Output 3:0-250V, 4A, A.C.

Other units are also available with outputs of:
0-60V 12A.
0-120V 6A.
0-240V 3A.

ALL CONTINUOUSLY VARIABLE

SEND FOR FURTHER DETAILS OF THESE VERSATILE UNITS TO


Valradio LIMITED, BRDWELLS LANE, FELTHAM, TW13 7EN, MIDDLESEX. TELEPHONE 01 890 4242

WW-060 FOR FURTHER DETAILS

Telford Oscilloscope cameras

Type A modular system with widest range of film backs, lenses, viewing systems and adaptors to meet virtually all requirements.

Plus inexpensive Type P (prices from £50) utilising coaterless Polaroid® film and Type C with economical 35mm film for continuous feed.




®Reg. Trade Mark.

More complete details available on request from:

Telford PRODUCTS LTD.

WADSWORTH ROAD PERIVALE GREENFORD MIDDX. ENGLAND Telephone: 01-998 1011 Telex: 935524 **DAVALL** A MEMBER COMPANY OF BENTIMA INDUSTRIES LIMITED

WW—061 FOR FURTHER DETAILS




SIGNALMASTER MARK 6

Producer of FM front-ends with MOS-FET dual gate mixer — single or combined with I/C IF amplifier with ceramic filters.

Also the complete module series for assembling of Signalmaster Mark 6: Power supply, memomatic operation unit, I/C stereo-decoder, frontplate and cabinets. Please send for brochures with all details and tech. data.

Trade and educational enquiries welcome.



7251
TUNER MODULE




Electronics since 1924

LARSEN & HOEDHOLT

RYESGADE 51-53 DK-2100 COPENHAGEN Ø. DENMARK

WW—062 FOR FURTHER DETAILS



ALL IN ONE TEST SET BY HATFIELD

The Hatfield Milliwatt Test Set 747 gives laboratory standards of accuracy in one portable unit powered from internal batteries. It outdates the need for more than one instrument or special options to standardise signal levels when working with 75Ω, 134/140Ω and 600Ω ohms circuits. Range from +1dB to -1dB is covered on a scale length of over 4" on a taut band meter with full overload protection.

Send for full details of Hatfield Attenuators and a copy of our Short Form Catalogue.

HATFIELD
forward thinking
in electronics

HATFIELD INSTRUMENTS LIMITED
Burrington Way, Plymouth PL5 3LZ, Devon.
Tel. Plymouth (0752) 72773/4 Grams: Sigjen, Plymouth. Telex: 4592
South-East Asia: for prompt service and deliveries, contact
Hatfield Instruments (NZ) Ltd. P.O. Box 561, Napier, New Zealand

WW—063 FOR FURTHER DETAILS

If you want to be in the KNOW

about Europe's most advanced
electronic equipment in

HOTEL MANAGEMENT & GUEST SERVICES

then place a tick in appropriate box, complete coupon and send to SNS Electronics Group, 851 Ringwood Road, Northbourne, Bournemouth BH11 8LN. We'll send you some interesting details by return.

I am interested in:

Radio & Music
Distribution Systems

Reception/Room
Intercom Systems

Wake-Up Systems

Room Status Schemes

Message Waiting
Indication

Guestmaster Personal
Bar Services

Other.....

Name _____

Address _____

Please cut it out

WW—065 FOR FURTHER DETAILS

Another reason why Enthoven is No.1 in solder



Superspeed solder wire

Enthoven's Superspeed soldering wire features an activated-rosin flux core and is ideal for those applications where a wide variety of different jobs must be handled with a single solder.

But don't forget the rest of the Enthoven range. It gives you a wide choice of high-quality products developed for use with modern techniques. It includes Flux Cored Solder Wires, Solder Pre-forms, Solid Solders, Selective Fluxes, solder specialities, materials for printed circuitry and for soldering aluminium.


And behind every Enthoven product stands a comprehensive advisory service that can solve your knottiest soldering problems.

Enthoven Solders Limited

Dominion Buildings, South Place
London EC2M 2RE.

Tel: 01-628 8030 Telex: 885737

Cables: ENTHOVENLONDON EC2M2RE



WW—064 FOR FURTHER DETAILS

Come and listen at the year's most exciting exhibition

Join thousands of Hi-Fi enthusiasts in an atmosphere that will set your ears tingling with excitement. The 1973 Audio Festival and Fair looks like being the best yet – and will run up to and include Sunday. The international giants of the Hi-Fi industry will be there – showing the latest specialist equipment: unit audio, tape recorders (cassette, cartridge and reel-to-reel), loudspeakers, tuners, receivers, amplifiers, radios, tapes and discs. There will be continuous demonstrations in specially constructed Audio Studios – and the Sunday Mirror is giving away £500 worth of equipment as prizes in exciting competitions. Don't miss this great event.


THE 1973 INTERNATIONAL AUDIO FESTIVAL AND FAIR

Sponsored by the Sunday Mirror

OLYMPIA

 London

Tuesday 23 October to
Sunday 28 October
Weekdays 10 am to 9 pm
Sunday 11 am to 7 pm
Admission 45p



BIAS ELECTRONICS

B
E
I
O
O

S
T
U
D
I
O

R
E
C
O
R
D
E
R

Excellent Performance
High Reliability
Mono or Stereo $\frac{1}{4}$ "
4 track $\frac{1}{2}$ " versions
in console, rack mounting
or transportable form.
At very reasonable prices.



Phone or write to

BIAS ELECTRONICS LTD. 01-947 3121
UNIT 8 COOMBE TRADING ESTATE
112-120 COOMBE LANE, LONDON SW20 0BA.

WW—066 FOR FURTHER DETAILS

CONVERTERS

British Made



VOLTAGE to FREQUENCY CONVERTERS

- 15VF-1 Wide frequency range, floating output, input neg.
- 15VF-2 pos. input accuracy 0.01% to 0.05%.
- 15VF-5 Audio range 0.01%, general purpose.
- 15VF-6 Low cost, general purpose.
- 15VF-8 High speed.

FREQUENCY to VOLTAGE CONVERTERS

- 15FV-3 Wide frequency range 0.02% to 0.05%.
- 15FV-4 Audio range, general purpose.
- 15FV-4a 0-500 Hz .2% accuracy.
- 15FV-7 .1% to 10 Hz.

TIME to VOLTAGE CONVERTER

- 15TV-7 Measures voltage free contact closure.

PERIOD to VOLTAGE CONVERTER


- 15PV-7 Measures interpulse periods.

AUXILIARY MODULES

- TELEMETRY AMPLIFIERS Line transmission.
- CLOCK MODULES Accurate pulses.

ancom limited devonshire street cheltenham 53861

WW—067 FOR FURTHER DETAILS



Audio Connectors

Broadcast pattern jackfields, jackcords, plugs and jacks
 Quick disconnect microphone connectors
 Amphenol (Tuchel) miniature connectors with coupling nut
 Hirschmann Banana plugs and test probes
 XLR compatible in-line attenuators and reversers
 Low cost slider faders by Ruf

Future Film Developments Ltd.
 90 Wardour Street,
 London W1V 3LE
 01- 437 1892/3

WW—068 FOR FURTHER DETAILS



QUARTZ CRYSTALS - FAST!

AEL

AEL GATWICK HOUSE, HORLEY, SURREY, ENGLAND
 Tel: Horley (02934) 5353
 Telex: 87116 (Aerocon Horley) · Cables: Aerocon Telex Horley

WW—069 FOR FURTHER DETAILS

If you want to be in the know

about Europe's most advanced COMMERCIAL SOUND SYSTEMS

then place a tick in appropriate box, complete coupon and send to SNS Electronics Group, 851 Ringwood Road, Northbourne, Bournemouth BH11 8LN. We'll send you some interesting details by return.

I am interested in:

- Public Address Mixers/Amplifiers
- Crystal controlled Tuners
- Tuner Amplifier Systems
- Specially designed Power Rack & Console Schemes
- Radio Microphone Systems
- Distinctive range of specialist Loudspeakers
- Other


Name _____

Address _____




WW—070 FOR FURTHER DETAILS


TAYLOR ARE EXPERT AT THE PANEL GAME.



Models 250 and 350
 10 mV to 1000 V dc (1000 Ω /V)
 10 μ A to 30 A dc
 10 V to 1000 V ac (1000 Ω /V)
 50 μ A to 50 mA ac (to 50 A with external transformer)




Clarity range
 10 mV to 100 V dc (1000 Ω /V)
 10 μ A to 30 A dc
 10 V to 1000 V ac (1000 Ω /V)
 50 μ A to 50 mA ac (to 50 A with external transformer)




Vista range
 10 mV to 1000 V dc (1000 Ω /V)
 10 μ A to 30 A dc
 10 V to 1000 V ac (1000 Ω /V)
 50 μ A to 50 mA ac (to 50 A with external transformer)




Model 55
 10 mV to 1000 V dc (1000 Ω /V)
 10 μ A to 30 A dc
 10 V to 1000 V ac (1000 Ω /V)
 50 μ A to 50 mA ac (to 50 A with external transformer)



Models 400 and 500
 10 mV to 1000 V dc (1000 Ω /V)
 10 μ A to 30 A dc
 10 V to 1000 V ac (1000 Ω /V)
 50 μ A to 50 mA ac (to 50 A with external transformer)




Edgewise range (typical)
 50 mV to 400 V dc (1000 Ω /V)
 50 μ A to 500 mA dc
 10 V to 400 V ac (1000 Ω /V)
 50 μ A to 5 mA ac




Fyneline standard range
 10 mV to 1000 V dc (1000 Ω /V)
 10 μ A to 30 A dc
 10 V to 1000 V ac (1000 Ω /V)
 50 μ A to 50 mA ac (to 50 A with external transformer)



Fyneline Pictureframe Window range
 10 mV to 1000 V dc (1000 Ω /V)
 10 μ A to 30 A dc
 10 V to 1000 V ac (1000 Ω /V)
 50 μ A to 50 mA ac (to 50 A with external transformer)



Fyneline Wide angle range
 500 mV to 1000 V dc (1000 Ω /V)
 500 μ A to 50 mA dc
 10 V to 1000 V ac (1000 Ω /V)
 500 μ A to 50 mA ac



Model 45
 10 mV to 1000 V dc (1000 Ω /V)
 10 μ A to 30 A dc
 10 V to 1000 V ac (1000 Ω /V)
 50 μ A to 50 mA ac (to 50 A with external transformer)

Sensitivities above 1000 Ω /V available on application.

And there are many more. So why not write for the Taylor Panel Meter Catalogue.



Thorn Measurement Control and Automation Division. Taylor Electrical Instruments Ltd, Archcliffe Rd, Dover, Kent CT17 9EN. Tel: Dover (STD 0304) 202620.

Taylor

WW—071 FOR FURTHER DETAILS

How versatile can an amplifier be?

Brookdeal
can answer
that...



Outstandingly low distortion to a typical non-linearity of 0.001% makes this the ideal preamplifier for many test systems. **Fast overload recovery** typically <math><10\mu s</math> for recovery from 40dB overload makes 9452 the choice for systems where large overload signals can occur. Bandwidth covers 1Hz to 1MHz with selectable frequency response. Variable gain control, with 1% accuracy, 19dB to 100dB. But get the full data and you'll see just how versatile an amplifier can be!

Brookdeal Electronics Limited, Market Street, Bracknell, Berks.
An **EG&G** Company Telephone: 0344-23931 Telex: 847164

The radically high performance of our Brookdeal 9452 opens up wide new areas of amplifier capability... **Superb low-noise input** even at low frequencies, enables the 9452 to span a wide spectrum of low-level signal applications.

ORTEC Brookdeal

WW-072 FOR FURTHER DETAILS

CBS SQ* FOUR CHANNEL DECODER NOW USED IN THE

*Regd. CBS inc.

P. E. RONDO

A complete kit for the home constructor that can be built in under an hour with just a soldering iron and a pair of cutters. Just pop the components into the positions clearly marked on the fibre glass board, crop and solder. You then have the identical decoder board used in the P.E. RONDO Quadraphonic Sound System Kit as described in PRACTICAL ELECTRONICS.

£8.00 post free, including licence fee to CBS + 80p V.A.T. **complete with lucid instructions.**

ANNOUNCEMENT

WE WILL BE PROVIDING COMPLETE KITS OF EACH PART OF THE P. E. RONDO AS THEY APPEAR EACH MONTH IN PRACTICAL ELECTRONICS.

Trade enquiries welcomed

PHASE LOCKED LOOP STEREO DECODER

(as in Wireless World, July 1972)

Another complete kit that takes about 30 minutes to build. No alignment problems and coils to adjust. Just four simple steps to obtain perfect stereo from your mono tuner.

- (1) Connect decoder to your tuner, possibly disconnecting one or two de-emphasis components.
- (2) Provide 10 to 16 volts D.C. either from your tuner or a separate power supply.
- (3) Tune to a stereo broadcast.
- (4) Turn a "preset" resistor until the stereo beacon lights up. You then have stereo radio.

£3.40 post free + 34p V.A.T.
(Beacon 34p + 4p V.A.T.)

Built and tested
incl. Beacon **£4.40** post free + 44p V.A.T.
Comprehensive instructions provided.

SONAX ELECTRONICS

SPENCER HOUSE,
BRETENHAM ROAD, EDMONTON,
LONDON, N.18.
Tel.: 01-807 5544 01-807 5999

Please send me: Kits Built and tested
 CBS SQ * decoder for the P. E. RONDO
 Phase locked loop decoder

I enclose cheque/postal order for £.....

Name

Address

(BLOCK CAPITALS PLEASE)


WW9

WW-073 FOR FURTHER DETAILS

Keep those
Contacts **CLEAN**

BY USING A

**DIACROM
SPATULA**



Manufactured in France
British Patents applied for

No other cleaner has all these advantages:—

1. Only 100% pure, natural diamond grains are utilised.
 2. Blades are treated with hard chrome to reinforce the setting of the diamond grains, to obviate loosening or breakaway during use. This process also prevents clogging of the diamonded surface by residues resulting from use.
 3. All diamonded blades are rectified to ensure an absolutely smooth surface by eliminating diamond grains which may rise above the surface. This eliminates all excessive scratching during use.
 4. All diamond grains are rigidly calibrated to ensure a perfectly uniform grain size of either 200, 300 or 400.
 5. The chrome gives a very weak co-efficient of friction and the rigidity of the nylon handle is calculated to permit proper utilisation and yet pliant enough to avoid undue pressures on highly delicate relays.
- Grain size 200, thickness 55/100 mm., both faces diamonded. For quick cleaning of industrial relays and switching equipment, etc.
 - Grain size 300, thickness 55/100mm., both faces diamonded. For smaller equipments, like telephone relays, computer relays, etc.
 - Grain size 400, thickness 25/100 mm., one face diamonded. For sensitive relays and tiny contacts. Two close contacts facing each other can be individually cleaned, because only one face of the spatula is abrasive.

Sole Distributors for the United Kingdom
SPECIAL PRODUCTS (DISTRIBUTORS) LTD

81 Piccadilly, London W1V 0HL. Phone: 01-629 9556

As supplied to the M.O.D., U.K.A.E.A., C.E.G.B. British Rail and other Public Authorities; also major industrial and electronic users throughout the United Kingdom.

WW—074 FOR FURTHER DETAILS

**If you want to be
in the
know**

about the U.K.'s
most Comprehensive Range of

PLANNED COMMUNICATION SYSTEMS

then place a tick in appropriate box, complete coupon and send to SNS Electronics Group, 851 Ringwood Road, Northbourne, Bournemouth BH11 8LN. We'll send you some interesting details by return. *I am interested in:*

- | | |
|--|---|
| <input type="checkbox"/> Executive Direct Speech Intercom Systems | <input type="checkbox"/> Automatic Dial Telephone Systems |
| <input type="checkbox"/> Heavy Duty and Industrial Direct Speech Systems | <input type="checkbox"/> Staff Location and Pocket Paging Schemes |
| <input type="checkbox"/> Push Button telephones and pocket paging | <input type="checkbox"/> Public Address Paging Systems |
| | <input type="checkbox"/> Other..... |

Name _____

Address _____



Please cut it out

WW—075 FOR FURTHER DETAILS

**From Goldring.
A new range of cartridges that ask a record
some searching questions.**

In every record there is stored a specific amount of reproduction capability.

And the purpose of any good cartridge is to release this potential to the fullest possible extent.

Now from Goldring comes a new range of cartridges that subject a record to a more searching inquisition than ever before.

The new 820 series.


In this series a whole range of new advances are introduced in materials and design, whilst

820 Super E. Performance characteristics:

Sensitivity @ 5 cm/sec — 1 kHz: 4mV. Separation @ 1 kHz: 25dB.

Recommended playing weight: 1.25 grammes.

Stylus point radius: .0003" x .0007". Frequency range: 10 Hz-25 kHz.



retaining the true transparency of sound and the true transduction techniques of earlier designs.

The small low-mass diamond point which is mounted on a new type of specially polished lightweight aluminium tube, combined with the new visco-elastic material used for the pivot pad, makes for greater tracking ability.

A special 'tie-wire' minimises fore and aft stylus movement, reducing non-linear distortion to a minimum.

There are three models in the range. The 820 with spherical stylus, and the 820 E and 820 Super E, both with bi-radial styli. Write for details.

The 820 series is capable of making the most of all that good records can offer now. And will keep pace with new developments as technical standards of recording continue to improve.

The new 820 series

The expert's cartridge by **Goldring** ©

Goldring Limited, 10 Bayford Street, Hackney, London E8 3SE. Telephone: 01-985 1152.

WW—076 FOR FURTHER DETAILS

REALISM IN SOUND FOR THE HOME CONSTRUCTOR

During the past 10 years, loudspeaker technology has advanced to a degree that it is no longer possible for the amateur to design and build a loudspeaker which matches the performance of a high quality commercial product. At one time, building a loudspeaker was simply putting a full range drive unit in a box of suitable size and shape. By present-day standards, a full range loudspeaker drive unit can no longer be considered in the high fidelity class.

The high fidelity loudspeaker started with the introduction of two-way systems, comprising bass and high-frequency drivers, and a simple frequency-dividing network. The dividing network was generally a coil in series with the bass driver, and a capacitor in series with the high-frequency driver. Although little attempt was made to ensure crossover at the best point in the frequency range, or the integration in respect of sensitivity, this was a considerable improvement over most single drive unit loudspeakers. It became apparent later, however, that the weaknesses of the single drive unit loudspeaker were still inherent to a degree in the two-unit system in respect of adequate frequency coverage. The relatively large and heavy diaphragm required for satisfactory bass response produces a poor performance above 1 kHz, and a high-frequency unit designed to have a satisfactory response to 15/20kHz is unsatisfactory below 3kHz. Most large bass drivers have a high-frequency resonance between 1kHz and 2kHz. The low-frequency resonance of high-frequency drivers is between 1kHz and 3kHz. These resonances produce transient colouration and an irregular response characteristic in the most important part of the total frequency spectrum. Optimum performance requirements thus necessitate the use of three or more drive units together with a sophisticated frequency dividing and integrating networks.

At the time of the introduction of multi-unit systems (between 1960 and 1965) drive unit design had not developed sufficiently to make it possible to produce a loudspeaker system covering the whole frequency range from 40Hz to 20kHz with a satisfactory angle of radiation using three drive units, and four-unit systems were common. Frequency crossover points were approximately 500Hz, 4kHz and 10kHz. With the introduction of the dome high-frequency driver and improvements in the mid-range driver, it is now possible to produce a three-unit system having a better performance than the four-unit system, using crossover frequencies of approximately 500Hz and 5kHz.

Drive unit design has now reached a very advanced state. The response characteristic obtainable is virtually flat over the desired range, in that the small variations, as measured, cannot be detected by any form of listening test. The greatest advance in recent years, however, has been the elimination of transient colouration due to standing waves on the diaphragm. Recent drivers have been designed on the concept of a transmission line to ensure perfect matching from the driving force at the coil to the terminating surround, thereby eliminating the source of termination reflections.

Recent further research by Arthur Radford has shown that the colouration which still exists in the finest forward facing (90° angle radiation) loudspeakers is due to standing wave generation between the radiation boundaries. It can be demonstrated that transient colouration is a function of the radiation angle at mid- and high-frequencies, and the wider the radiation angle the greater is the realism.

Components and designs are available for constructing loudspeakers from a small forward radiating loudspeaker to a 360° direct radiating (4 high-frequency drivers, 4 mid-range drivers, and 2-12" bass drivers coupled to an acoustic line) system.

You can now build a complete loudspeaker of your own styling which will outperform any commercial loudspeaker within its classification. Write for further details to:— Dept. W.W.


RADFORD ACOUSTICS LTD
Bristol BS3 2HZ

WW—077 FOR FURTHER DETAILS

cryston

AUDIO EQUIPMENT

SOUND MIXERS
for
ALL TYPES OF INSTALLATIONS



SOUND MODULES
full
Range Available


Telephone or Write
for
Further Details

CRYSLON ELECTRONICS LIMITED.
ROTHER STREET, STRATFORD-UPON-AVON, WARWICKS.
TEL: STRATFORD-UPON-AVON 4797.

WW—078 FOR FURTHER DETAILS

How much does Transit Damage cost you?

In damaged goods. In doubled delivery charges. It need not cost you a penny. Because it needn't happen. PROTECTOMUFFS are tough, padded, weather-proof, dustproof. They are tailored to fit your product. Slipped on in seconds by unskilled staff, they provide all the packing required. And because they are re-useable again and again and again, packing costs become a non-recurring item. Be like Hoover, Ferranti, Rediffusion — use Protectomuffs and show your customers you care.



PROTECTOMUFFS

TRADE MARK

To **JOHN EDGINGTON & CO. LTD.**

47 Old Woolwich Road, Greenwich, London SE10 9PU (01-858 7014-6)

Send me details of Protectomuffs


Name

Address

W.W. 2

WW—079 FOR FURTHER DETAILS

Purpose-built servo and actuator systems using standard components




Low Inertia DC motor
Typical precision gears


McLennan have considerable experience in the solution of actuator and servo problems using synchronous, stepping and D.C. motor techniques as well as solenoid-powered types. An important facet of our skill lies in purpose-designing around standard components for speed and economy of building.



Control Amplifier



Power Unit to feed up to 3 Servos



Gearhead with integral feed-back Potentiometer

The illustration shows a selection of modules from the McLennan standard range which are available as individual items or can be supplied engineered to custom-built systems.

Such a system could be complete in itself or form part of your own design.

Typical examples include:

- Camera positioning: Plotting Devices:
- Self-steering Systems: Signal-seeking Aerial Drives:
- Professional Tape Drives: Automated Production Lines.

Stimulation of output position or velocity may be by optical, radio, electrical, mechanical, pneumatic or hydraulic signals.




McLennan Engineering Ltd

Control Systems and Components

Kings Road, Crowthorne, Berkshire. Tel: Crowthorne 5757/8.

WW—080 FOR FURTHER DETAILS

METER PROBLEMS?



A very wide range of modern design instruments is available for 10/14 days' delivery.

Full Information from:

HARRIS ELECTRONICS (London)

138 GRAYS INN ROAD, W.C.1 Phone: 01/837/7937

WW—081 FOR FURTHER DETAILS

TEST PROBE

for logic circuits



- ★ High-Low Level Probe (2-colour indication)
- ★ Uses L.E.D.
- ★ Reverse Pole Protected
- ★ Very fast response
- ★ 50 nano seconds
- ★ Up to 12 MHz

Still available at **£5.50** EACH incl. P.P. + VAT
Quantity discount!

Pocket Size LED Applied
LOGIC TESTER
For use with DTL, TTL and other pulse circuits
Response frequency DC to 12 MHz



Associates Ltd.

Cricketfield Lane,

Bishop's Stortford, Herts.

Telephone: 0279-56347 Telex: 81675 JAYLAMPS STORT

WW—082 FOR FURTHER DETAILS

Don't just talk about it—DO something

QUADRAPHONICS

The September issue of Practical Electronics
now on sale introduces you to the —

RONDO system

Quadraphonics Par Excellence

Which gives you:-

- 4 x 20 watt power amplifier
- High quality preamplifier and control system with wide dynamic range
- AM/FM receiver of advanced design
- CBS/SQ Quadraphonic decoder

The PE RONDO is a total system incorporating the very latest semiconductor technology. It will be described with all constructional details in a series of articles starting in September. The receiver incorporates varicap FM tuning with i.c.i.f. amplifiers, quadrature detector and phase-locked loop stereo decoder together with a

unique new phase-locked loop synchrodyne AM mono tuner. Optional i.c. matrix decoders will be described including CBS/SQ and the logic enhanced version, together with others as they become available. Indeed, the very latest front/back, wave matching and variable blend logic—will be described in full.

PRACTICAL ^{20p}
ELECTRONICS

Place a regular order with your newsagent.

TPA SERIES - D

integrated circuit power amplifier



TPA 50 - D Specification

Power Output	100 watts rms into 4 ohms 65 watts rms into 15 ohms
Freq Response	± 0.1 dB 20Hz to 20KHz into 15 ohms. -1dB at 150KHz
Total harmonic distortion	Less than 0.04% at all levels up to 50 watts rms into 15 ohms
Input sensitivity	0dB to 100mV
Noise	-100dB
Rise time	2 μ seconds
Price	£53 plus V.A.T.

100V Line (C.T.) and balanced inputs available.

For further technical information contact:

H/E ELECTRONIC

CAMBRIDGE ROAD, MILTON, CAMBS
TELEPHONE CAMBRIDGE 65945/6/7

WW—083 FOR FURTHER DETAILS

Q

We didn't name our company Hy-Q for nothing! Our name is self evident to electronic engineers or course it means high quality too, and that's what we at Hy-Q Electronics offer

Backed by a continuous research and development program, we are now the largest manufacturers in the Southern Hemisphere of low and high frequency crystal units, encapsulated in glass, solder seal

and cold-weld holders. Our range of products includes both discrete component crystal filters and monolithic crystal filters for most communication applications.


Oscillators with output frequencies from 0.1 Hz through to 250 MHz are available from our standard range. We offer applications engineering advice on any of the above products. You name it, we've got it.

Hy-Q Electronics

P O Box 256
Frankston
Victoria, 3199
Australia
Phone: 783 9611
Telek: 31630
Cables: HYQUE
Melbourne

P O Box 29,
Pasir Panjang
Singapore, 5
Phone: 636477
Cables: HYQUESING
Telex: RS21427

WW—084 FOR FURTHER DETAILS



take good care of
your contacts with
ELECTROLUBE

- Contact Lubricants
 - Contact Cleaning Strips
 - Preclene
- Also Silicone Grease, Freezer,
Printed Circuit Lacquer

Electrolube Ltd. Slough, Bucks, England.
Tel: Slough (STD 0753) 25574


WW—085 FOR FURTHER DETAILS



W.H.M.
**WOW AND
FLUTTER
METER
(R.M.S.)
MODEL III
MK. II**

**SYDNEY HOUSE, 35 VILLIERS ROAD, WATFORD
WDI 4AL TEL: 38757**

WW—086 FOR FURTHER DETAILS



**CHECKMATE PROFESSIONAL
CROSSHATCH GENERATOR**

The unique test card edge enables the completely accurate alignment of colour and monochrome receivers without the need of a broadcast test pattern. The crystal derived patterns and waveforms make extensive use of digital i.c. logic. The stable and reliable 625 line high resolution patterns are crosshatch dot and white field, full 2:1 interlace with complete synchronising and blanking waveforms. Continuous tuning over all channels in each band B.N.C. video outputs into 75 ohms available for CCTV use on all models.

- Model CCH-1 UHF Bands IV & V £69.00
- Model CCH-V VHF Band 1 £70.00
- Model CCH-V2 VHF Band 11 £70.00
- Model CCH-V3 VHF Band 111 £70.00

U.K. Customers add VAT. Overseas Customers CIF at cost.

Send for further information from the sole agents:

**MANOR ENGINEERING,
The School House, Crookham Common,
Newbury, RG15 8EJ, England.
Telephone: Headley 487.
Telegrams: MANORENG, NEWBURY.**

WW—088 FOR FURTHER DETAILS

**TO SPARK YOUR
IMAGINATION!**
the
SPARKRITE
Electronic
Ignition Kit
only
£9.35

Kit comprises EVERYTHING
Case, cables, coil connectors,
Silicon grease,
8 page instruction leaflet.

Fascinating to build. Fantastic improvement to your car's performance. Complete Capacitive Discharge ignition system, fully proven, components fully guaranteed. Printed circuit design. All metalwork drilled ready. Fitted to car in 15 minutes when built.


- Sustained peak performance.
- Up to 20% fuel saving.
- Instant all-weather starting. Faster acceleration, higher top speed.
- Suitable for all engines up to 8 cyls.
- Longer spark plug life.
- Longer battery life.
- Contact breaker burn eliminated.
- Purer exhaust gas emission.

A new development from the manufacturers of Gunton ignition. Price: £9.35 inc. V.A.T. and postage. (12 volt only State Pos. or Neg. earth). Ready built unit also available £11.55 inc. V.A.T. and postage. GUARANTEED 5 YEARS.

ORDER NOW—send P.O./Cheque direct to:
ELECTRONICS DESIGN ASSOCIATES, Dept. WW9
82 Bath St., Walsall WS1 3DE. Phone: 33652

WW—087 FOR FURTHER DETAILS

EP1, EP2 (RED)
EP51, EP52 (GREEN)
**Seven Segment
Numeric Displays**
EP1, EP2 for RED



EP1 Red EP2 Red
Numeric Overflow one
Display & polarity

**EP51, EP52
for GREEN**



EP51 Green
Numeric
Display



EP52 Green
Overflow one
& polarity

PRICES (EACH)

Type	1-24	25-99	100 up
EP1	£3.55	£2.55	£2.24
EP2	£3.45	£2.50	£2.24
EP51	£5.40	£5.04	£4.68
EP52	£5.40	£5.04	£4.68

RASTRA ELECTRONICS LTD.
275-281 King Street - Hammersmith - London W6 9NF. Tel. 01-748 3143/2960. Telex 24443

WW—089 FOR FURTHER DETAILS



This is the D75

- Lightweight
- 50MHz bandwidth at 5mV/div
- 1mV/div at 15MHz
- 3% accuracy
- Mixed sweep
- Calibrated sweep delay
- Gated trigger
- Bright 8x10cm display

A new Dual Trace, 50MHz Portable Oscilloscope for £420

(Exclusive of V.A.T.)


Yes indeed! A 50 MHz dual-trace instrument costing you only £420. And it's portable too – the light-weight, comfortable-to-carry, take-it-anywhere kind of portable. Developed by engineers for engineers this newcomer from Telequipment offers unprecedented

value when compared with similar 50MHz instruments. The outstanding specification of the D75 includes a wide-range dual timebase incorporating sweep intensifying, delaying, mixed sweep and single-shot facilities, an 8 x 10cm CRT operating at

15 kV, and dual-trace operation in alternate and chopped modes with 5 mV/div all the way up to 50 MHz.

Write or telephone now for the specification and a demonstration, and prove for yourself that the D75 is the oscilloscope for you.

Tektronix U.K. Ltd.
Beaverton House, P.O. Box 69,
Harpenden, Herts.
Telephone: Harpenden 61251
Telex: 25559



Wireless World

Electronics, Television, Radio, Audio

Sixty-third year of publication

September 1973

Volume 79 Number 1455



This month's cover picture shows the inspection of colour phosphor dots on the faceplate of a Chromacolour television tube made by the Zenith Radio Corporation, U.S.A.

Contents

- 415 Electronics on the Factory Floor
- 416 A Homodyne Receiver by *J. W. Herbert*
- 420 Total Communications by *E. J. Gargini*
- 425 Motional Feedback
- 426 Books Received
- 427 News of the Month
 - Ultrasonic holography in medical diagnosis
 - New interference regulations
 - P.C.M. developments
- 429 Electronic Sound Synthesizer — 2 by *T. Orr and D. W. Thomas*
- 434 Announcements
- 434 H.F. Predictions
- 435 Circards — 9: Optoelectronics — Devices and Applications by *J. Carruthers, J. H. Evans, J. Kinsler & P. Williams*
- 437 Industrial Electronics — 5 by *Richard Graham*
- 439 An Approach to Audio Amplifier Design — 2 by *J. R. Stuart*
- 447 Experiments with Op-amps — 13, 14, 15 by *G. B. Clayton*
- 448 Raising Transmitter Valve Dissipation
- 449 Letters to the Editor
 - Audio amplifier design
 - Printed circuits the easy way
 - Radiating coaxial cables
- 452 Literature Received
- 453 Single Sideband Suppressed Carrier Generation by *A. J. Turner*
- 455 New Electrochromic Display
- 456 World of Amateur Radio
- 457 Multi-channel Tone Control by *J. R. Emmett*
- 459 Conferences and Exhibitions
- 460 Letter from America
- 461 Simple Facsimile or Teleprinter Signal Converter by *J. B. Tuke*
- 463 Sixty Years Ago
- 464 New Products
- A100 APPOINTMENTS VACANT
- A122 INDEX TO ADVERTISERS

In our next issue

(publication date September 17)

Digital voltmeter. A $3\frac{1}{2}$ -digit, dual-slope integrating voltmeter for alternating and direct voltage, with a sensitivity of 200mV full-scale. Uses filament-type seven-segment displays.

Multi-channel remote control. Uses logic devices to achieve proportional control of up to nine remote servos by means of a time-division multiplex link.



I.P.C. Electrical-Electronic Press Ltd
Managing Director: George Fowkes
Administration Director: George H. Mansell
Publisher: Gordon Henderson

© I.P.C. Business Press Ltd, 1973

Brief extracts or comments are allowed provided acknowledgement to the journal is given.

Price 20p. (Back numbers 40p.)

Editorial & Advertising offices: Dorset House, Stamford Street, London SE1 9LU.

Telephones: Editorial 01-261 8620; Advertising 01-261 8339.

Telegrams/Telex, Wiworld Bisnespres 25137 London. Cables, "Ethaworld, London S.E.1."

Subscription rates: *Home*, £4.35 a year. *Overseas*, 1 year £5; 3 years £12.50 (U.S.A. & Canada 1 year \$13, 3 years \$32.50) Student rates: Home 1 year £2.18, 3 years £5.55. Overseas, 1 year £2.50; 3 years £6.25 (U.S.A. & Canada 1 year \$6.50, 3 years \$16.25).


Distribution: 40 Bowling Green Lane, London EC1R 0NE. Telephone 01-837 3636.

Subscriptions: Oakfield House, Perrymount Rd, Haywards Heath, Sussex RH16 3DH. Telephone 0444 53281.

Subscribers are requested to notify a change of address four weeks in advance and to return envelope bearing previous address.

**EEV
POWER TUBES:
TETRODES &
TRIODES**

REPLACE WITH CARE, REPLACE WITH ONE OF OURS.



There are at least three reasons for this.

First, this is an EEV tube and EEV is one of the biggest tube makers in the world. When you replace with EEV, you know you are getting a tube that you can depend on.

Second, EEV tubes are very competitively priced.

Third, you'll find you get more than a good tube from EEV. Our service is quick, efficient, informed. We go to endless trouble to keep our customers out of trouble.

Ask any EEV customer, or try us for yourself. Write for details, or if you have a specific problem 'phone us at Chelmsford and ask for extension 428.

Ours	Theirs	Anode dissipation max. (kW)	Output power (kW)	Anode voltage max. (kW)	Frequency (MHz)	Filament ratings (V) (A)	
4CX1000A	4CX1000A	1.0	3.2	3.0	110	6.0	9.0
4CX1000K							
4CX1500B	4CX1500B	1.5	2.7	3.0	30	6.0	9.0
4CX5000A	4CX5000A CV8295	5.0	16	7.5	30/110	7.5	75
4CX10,000D							
4CX10,000D	4CX10,000D CV6184	10	16	7.5	30/110	7.5	75
4CX15,000A	4CX15,000A	15	36.5	10	110	6.3	160
4CX35,000C	4CX35,000C CV11107	35	82	20	30	10	300
BR1161							
BR1161	CV9343 RS726	35	100	14	10/30	11	155
Ours	Theirs	Anode dissipation max. (kW)	Output power (kW)	Anode voltage max. (kW)	Frequency (MHz)	Filament ratings (V) (A)	
CY1172	RS2002V	150	220	15	30	21	350
BW1184	YD1202	80	120	14.4	30	12.2	255
BW1185	YD1212	120	240	16.8	30	12.6	380
BY1161	RS826	60	120	14	10/30	11	155

EEV AND M-OV KNOW HOW.

ENGLISH ELECTRIC VALVE CO LTD, Chelmsford, Essex, England CM1 2QU. Tel: 0245 61777. Telex: 99103. Grams: Enelectico Chelmsford.



LAP 63

WW-090 FOR FURTHER DETAILS

Wireless World

Electronics on the factory floor

Editor:
TOM IVALL, M.I.E.R.E.

Deputy Editor:
PHILIP DARRINGTON

Technical Editor:
GEOFFREY SHORTER, B.Sc.

Assistant Editors:
BILL ANDERTON, B.Sc.
BASIL LANE

Drawing Office:
LEONARD H. DARRAH

Production:
D. R. BRAY

Advertisements:
G. BENTON ROWELL (*Manager*)
Phone 01-261 8339
G. J. STICHBURY
Phone 01-261 8037
KEITH NEWTON
Phone 01-261 8515
A. PETERS (*Classified Advertisements*)
Phone 01-261 8508 or 01-928 4597

The purpose of Richard Graham's series of articles "Industrial Electronics" is, as the author has stated, to exemplify the possibilities of electronics in industry. To quote from his first article in the March issue, "... modern, solid-state electronics has improved on processes in use a few years ago by virtue of its incredible speed, reliability, low power consumption, small size and, in most cases, improved accuracy". Readers interested in the techniques used to obtain particular improvements may not be aware that there is a strong commercial force behind most of this technology — the need for greater productivity. In most cases the cost of the electronic equipment must be justified by the reduction in manufacturing costs obtained by its use.

Productivity is a measure of production efficiency — of a country, an industry, a factory, a process or a machine. Because it is a measure of efficiency it is expressed as an output/input ratio. The best known example is labour productivity, where the input is measured in units of labour and the output in units of product value (that is, money). Here industrial electronics can help to increase the output/input ratio by a straightforward reduction of the labour input, either in number of workers or in the proportion of skilled, highly paid workers. Or electronics can help by reducing the requirement for middle management workers, by simplifying and making more predictable the processes involved — e.g. by data acquisition and processing.

Labour productivity seems to get most attention because in the highly developed countries labour is a relatively costly factor of production. Also it is an emotive term carrying suggestions of labour saving, redundancy, Luddism and disputes between managements and employees. Less well known is productivity of capital — measured as a ratio of product output to capital input — which shows the efficiency of utilization of capital investment. Here electronics helps by providing control and programming systems, automatic handling and feeding devices, or other techniques which reduce the idle time of machinery or allow industrial plant to operate at higher speeds. It can also help to reduce expenditure on stocks and factory floor area by providing automatic equipment to give faster and more continuous production and therefore reduce work in progress and requirements for large stocks. In addition factory space can be saved by reduction of the areas normally needed for operators.

There is a third type of productivity, which shows the efficiency of materials utilization and is measured as a ratio of product output to materials input. Electronic techniques can help to reduce materials requirements and wastage in processing by providing automatic programming, inspection and quality control techniques which result in more uniform product quality, fewer rejects or less scrap; hence there is a smaller materials input to obtain a required volume of output product within specification. Electronic inspection or measuring instruments that will determine quantities faster and more accurately than can human operators will reduce the product quantity that normally has to be given away to ensure that goods have guaranteed weight or volume.

With all these possibilities it is sad that electronics has been so much mistrusted on the factory floor. This attitude is gradually changing, but there are many prejudices and traditional policies in the organization of industry still to be overcome.

A Homodyne Receiver

by J. W. Herbert*

The purpose of this article is to bring to the attention of the home constructor an as yet rather uncommon reception technique for a.m. signals which has significant potential for enhancing the performance of most receivers be they for short wave or broadcast listening.

The problems of a.m. reception

The most common a.m. receiver circuit is the superheterodyne wherein the incoming signal is converted to some intermediate frequency before detection. Detection is usually by means of a diode-rectifier circuit which follows the i.f. stages. Other simpler receiver circuits are available to us however and these are shown in block form in Fig. 1 together with the superheterodyne.

The simplest of these receivers is the so called "crystal set". This name is a carry over from the early days of radio and as can be seen in Fig. 1 consists of an input tuned circuit feeding a diode

detector. The rectified a.m. signal is filtered to remove any radio frequency component and the output passed on to the audio amplifier. Such a receiver is not very sensitive or selective but these characteristics can be greatly improved through the use of tuned radio frequency (t.r.f.) stages ahead of the detector. Such a t.r.f. receiver, as it is known, is quite useful but reception is still limited by the selectivity characteristic and the additional amplification causes overload problems in the presence of strong stations on adjacent frequencies. In an attempt to overcome these problems (amongst others) the superhet receiver was employed. Through the use of a converter stage the desired signal is relocated in frequency to become what is known as the intermediate frequency. In the i.f. channel, through multiple stages, as much amplification and selectivity as desired can be provided and furthermore, this characteristic is applied to all signals tuned. In the days when this receiver was first developed, the process of frequency converting was sometimes termed "heterodyning" and in order to obtain great selectivity the i.f. was often

located at very low radio frequencies.

The superhet is by far the most common receiver configuration, particularly for telecommunications but like most systems exhibits its own peculiar set of disadvantages. These are significant when optimum reception of broadcast musical programmes is required by the audiophile. Bearing in mind the orders of audio frequency response, distortion and noise factors required in present day audio systems, the prime disadvantages of the superhet tuner may be summarized as follows.

- The superhet is the most complex receiver employing a number of separate stages (typically five), each with a separate role in the signal processing and incorporating multiple tuned circuits that must be aligned critically. Some of these are required to "track" each other as the receiver is tuned from station to station. This point alone makes the superhet the most expensive type of receiver.

- For optimum reception of programme, the receiver bandpass should be "flat" for 10kHz above and below the desired station carrier frequency as audio frequencies up to 10kHz are broadcast. If the receiver selectivity characteristic is such that the bandpass is less than 20kHz the treble frequencies broadcast will be lost in the receiver and/or the audio response will not be "flat". Bandpass restrictions usually occur in the selective i.f. and r.f. stages. Although this problem can be met with special block filtering in the i.f. and tracking bandpass couplers in the r.f. stages, the complexity, alignment and costs are very high. These techniques are therefore restricted to the most expensive tuners.

- The superhet generally employs a diode-rectifier type of detector stage (as does the crystal-set and t.r.f. receiver). There are two main reasons for this:

- it is simple and inexpensive,
 - the d.c. component in the output can be employed for automatic volume control purposes to stabilize receiver gain as station signal strengths vary.
- A prime disadvantage of this detector circuit is the high levels of harmonic distortion and intermodulation distortion it introduces to the recovered audio signal. For average levels of modulation percentage the diode introduces total harmonic distortion (t.h.d.) of typically 3% and at high modulation percentages 10% t.h.d. is not uncommon. These figures are based on valve receivers and are taken from reference 1. In order to reduce the diode detector t.h.d. the applied signal levels must have a large amplitude so that they operate mainly on the "linear" portion of the diode characteristic curve. Voltages up to 20 volts peak are not uncommon from the valve type i.f. but in the receivers of today valves are an exception. Transistorized stages, because of their much lower working voltages and circuit impedances, supply the detector diode with a signal that is restricted largely to the very non-linear diode

* Department of Electronic Engineering, Central Institute of Technology, Petone, N. Z.




Fig. 1. Broadcast receiver detector and demodulator systems.

"turn-on" characteristic. This comparison is illustrated in Fig. 2 and results in generally higher levels of t.h.d. in the receiver.

It would appear then that the superhet has very real design problems when employed as a broadcast tuner. To the audiophile, probably the most noticeable deficiency is the restricted audio bandwidth followed by distortion and noise. A typical r.f. stage in a tuner with input and output tuned circuits will be sufficiently selective to cut the outer limits of the broadcast stations' sidebands significantly (i.e. the passband is much less than 20kHz). By the time the i.f. channel has passed the signal, further degradation can be expected. In a typical broadcast tuner the overall passband is about 8 to 10kHz total giving audio output up to about 5kHz before severe treble roll-off.

These facts may help explain why some component retail stores still offer crystal set and simple t.r.f. tuners as an accessory. Due to their broad tuning characteristic (i.e. poor selectivity) they offer a generally noticeable improvement in reception quality primarily due to their ability to recover most of the audio spectrum broadcast. Their effectiveness is limited however by the signal detection circuits they employ.

Envelope detection of a.m. signals Any amplitude modulated carrier wave has a "modulation envelope" which corresponds to the original modulating (i.e. audio) signal. Fig. 2 illustrates the action of a typical diode-rectifier type detector and it can be seen that the rectified output signal consists largely of the original envelope waveform — hence the general title of envelope detector for this system. It should be realized that the principle of envelope detection applies to a host of other detector circuits such as grid-leak, class B, infinite impedance, etc. Now since the envelope detector output is dependent upon the amplitude only of the incoming r.f. signal, there is no differentiation between the frequencies in the input signal be they desired or undesired (i.e. adjacent channel) frequencies. This can be illustrated with the example of a t.r.f. type receiver tuning into a 600kHz station. Due to the (purposeful) poor selectivity the passband response is still good 30kHz away where another station is broadcasting on 570kHz. The two signals are therefore impressed on the rectifier circuit, their amplitude variations causing a change in diode output current, both modulations being passed on to the audio stages. It can be seen that the only way to reject the undesired and interfering 570kHz signal is to tune it out with greater selectivity. Assuming both signals were of same strength in the receiving antenna, in order to suppress the 570kHz signal by 40dB, two tuned circuits would be required with a working *Q* of about 100 each. The extent of the sideband cutting on the desired signal would be such that recovered audio frequencies at 3kHz would be suppressed by at least 6dB, rendering the receiver useless for musical programmes. Obviously then, receiver




Fig. 2. Diode detector characteristics and operation.

design using envelope detection must be compromised between achieving adequate selectivity and suppression of adjacent channel interference on one hand, and overall passband response for acceptable programme fidelity on the other.

Product detection of signals — the "synchrodyne" In search of a better "compromise" an engineer, D. G. Tucker produced a novel solution to the problem with his "synchrodyne" receiver in 1947. Tucker pointed out that if a broadcast signal is fed into a conventional superhet receiver in which the local oscillator feeding the converter stage is arranged to run at the *same* frequency as the incoming carrier, all of the side frequencies or sidebands associated with the signal carrier would appear as audio "beat-notes" in the converter output. This output then replaces the usual i.f. and in fact becomes the recovered audio signal. It is important to realize that in this case the incoming signal has not been detected as outlined previously, but rather has become displaced in the frequency spectrum to make it audible. Many readers will realize that this is the function of a so-called product demodulator in which the output signal

is a mathematical product of the incoming signal and local oscillator multiplied together through the action of the converter stage. Let us take the previous example of the two broadcast stations on 600kHz and 570kHz and see how they are processed by this type of receiver. Once again the 600kHz signal is tuned in and because of poor selectivity, the 570kHz signal is also presented to the product demodulator. The local oscillator mixes with the incoming signal and any differences in frequencies appear as "beat-notes" at the output. The normal sideband components contain modulating frequencies extending up to ± 10 kHz either side of the station carrier which has been tuned to zero-beat. The \pm signs represent the upper and lower sidebands both containing the modulation, but due to the operation of the product demodulator these two components appear as two audio signals in phase at the output. Thus they reinforce each other in the form of a single audio signal. Of interest however, is the presence of the 570kHz interfering signal. Assuming its bandwidth is also ± 10 kHz the lower frequency limit is 560kHz, the upper 580kHz. Since the receiver local oscillator is tuned to 600kHz, the interfering signal components will beat out with a frequency displacement locating them in the audio spectrum 20kHz to 40kHz. The interfering carrier would appear midway as a 30kHz whistle. The human ear cannot hear audio frequencies this high and furthermore it is easy to electronically filter the undesired frequencies, the interfering signal then, although present in the output, is inaudible.

With such a technique, receiver tuned circuit selectivity can obviously be reduced to prevent sideband cutting without fear of adjacent station modulations appearing as interference in the recovered audio signal. A second major advantage of the product demodulator is that since it is used to displace frequencies only, it introduces little distortion to the broadcast signal. Typical values are about 1% t.h.d. which is far less than the previously discussed envelope detector characteristic.

Unfortunately this receiver has several




Fig. 3. Block diagram of MC1330P i.c. demodulator.

problems which have largely precluded its use on a domestic basis. The prime objection is that in order to recover the audio free of phase distortion it is important that the local oscillator be not only synchronized to the station carrier but must also be in phase with it. Tucker (and others), have developed circuits which give synchronization, but for reliable operation the circuits are more complex and critical than the rest of the receiver and in a way destroy the apparent simplicity of the system. Another problem is the inconvenience of tuning a receiver that gives a piercing audio whistle as it is moved from station to station, although complex muting circuits have been devised. We can see however, that the synchronous-heterodyne or "synchrodyne" is an obvious title for this receiver. Despite its limitations the synchrodyne is used primarily by broadcasting stations as a high quality "off-air" monitor receiver and anyone who has heard one operating will testify favourably to its capabilities in this application.

In more recent times electronic technology has grown very rapidly and many new circuits and applications have appeared within the framework of modern telecommunications systems. Two signal detection systems with common features that have appeared are the synchronous demodulator and the coincidence detector. In these, suitable circuitry provides for a product demodulator in which the local

oscillator source is derived by extracting the incoming signal carrier only. The complexity of this arrangement is largely overcome through the use of integrated circuitry. In applying this concept to the synchrodyne type receiver it can be seen that employing a local oscillator is rather pointless as there is a perfect oscillator source in the received carrier wave. The problem is that it is amplitude modulated and of insufficient strength to use directly. If, however, it can be amplified and the a.m. stripped off, we have the ideal local oscillator source for product demodulation with the following features; it is inherently synchronized and phased to any station tuned in; no whistle or heterodyne will be encountered when tuning from station to station; thus the major disadvantages of the synchrodyne are overcome. Such a system once again effects frequency translation with the converter output or i.f. being one and the same as the audio signal. The base for the "same" is homo and the name "Homodyne" is therefore given to this inherently synchronized heterodyne receiver.

A homodyne receiver based on i.c.s.

Because of the wide bandwidth and low distortion capabilities of the synchronous demodulator, one version has appeared in i.c. form primarily for application as a video detector in colour TV receivers. The type number is a Motorola MC1330P² and a block diagram presentation is given

in Fig.3 to show the circuit functions. Tracing the a.m. signal from the input terminal (Pin 7), the signal is fed into an "i.f." amplifier which provides two output paths.

One of these leads to the signal port of a product demodulator, the other feeds into a buffer amplifier. This amplifies the signal and applies it to a pair of diodes in a shunt clipper circuit, where the a.m. variations are clipped off the carrier wave after which it appears as a train of square waves. The "square wave" carrier signal is then injected into an external tuned circuit (Pins 2 and 3) where the fundamental component is extracted to provide a sine wave signal for injection as a local oscillator source to the product demodulator. The product demodulator output consists of beat-notes due to the difference in frequency between the a.m. sidebands and reconstructed carrier, these being amplified and fed out on Pin 4. At this point a low pass filter can be employed to in effect set the pass band response of the overall demodulator. The electrical circuit for the MC1330P is shown in Fig.4 and this can be tied to the block diagram by inspection.

At this point a most useful by-product of this form of demodulation can be brought out. As stated earlier the output of this stage is the mathematical product of the a.m. signal and reconstructed carrier. Since the signal carrier and the reconstructed carrier are inherently in




Fig. 4. Circuit diagram of MC1330P.

synchronism and phase we can call each, when no modulation is present, $\sin A$. The product detector output then is:

$$\begin{aligned} &= \sin A \times \sin A \\ &= \sin^2 A \\ &= \frac{1}{2} - \frac{\cos 2A}{2} \end{aligned}$$

The output signal then, as far as the carrier is concerned, consists of two components: $\frac{1}{2}$ is a d.c. component whose amplitude varies in proportion to the signal strength. Since the following amplifier is d.c. coupled, the output d.c. level shifts in accordance with station signal strength giving an automatic gain control voltage which can be applied back to the previous r.f. stage. The term $\frac{\cos 2A}{2}$ is a second harmonic of the carrier

frequency. This is removed by filtering in the audio output circuit. This term can be significant however in connection with interference and this will be discussed later.

The circuit diagram, Fig. 5, shows how all of these features have been combined in a practical homodyne receiver circuit that tunes the broadcast band. The antenna input is tuned by one section of a permeability tuning unit to select the desired frequency and feeds the signal into Pin 2 of the r.f. amplifier. This is an i.c. type CA3028A (R.C.A.) (Ref.3) operating in the cascode mode, the output load being an r.f. choke and the capacitively coupled input of the MC1330P.

Leaving the interstage coupling untuned ensures that no sideband cutting occurs at this point in the circuit. The detector tuned circuit is tuned by the second ganged section of the permeability tuner which must be aligned to track the input tuned circuit for optimum results. The demodulator output circuit (Pin 4) is filtered by a $0.01\mu\text{F}$ bypass capacitor which introduces attenuation to frequencies above about 12kHz. The output circuit is also separately filtered and decoupled to pass the d.c. component back to Pin 7 of the r.f. stage CA3028A for a.g.c. purposes. With no signal input, Pin 4 is at about 5V and when a signal causes this voltage to fall to about 3V, the a.g.c. action is established.

Alignment is achieved with the following procedure.

1. Connect a voltmeter between Pin 4 of the MC1330P and earth. With no incoming signal and a 12V power supply this should read about 5 volts.
2. The receiver tuning range is set by the antenna tuned circuit whose adjustable slug and trimmer capacitor should be adjusted to achieve a satisfactory tuning range at the low and high frequency ends of the band respectively.
3. Tune in a signal from a known station (or use a signal generator) at the low frequency end of the band and adjust the demodulator tuned circuit slug for minimum d.c. output on Pin 4. Then tune a signal at the high frequency end of the band and adjust the demodulator trimmer capacitor for minimum d.c. output on Pin 4. These adjustments interact somewhat and should be done alternately until tracking is well established.




Fig. 5. Circuit of the complete homodyne broadcast tuner.

Conclusions

The prototype Homodyne tuner has been evaluated with suitable test equipment with the following results. Frequency response (-3dB points): at 600kHz, 20Hz to 12kHz; at 1,400kHz, 20Hz to 15kHz; total harmonic distortion at 1kHz with 50% modulation, approximately 5%; a.g.c. characteristic threshold $500\mu\text{V}$, range about 40dB and a.f. output level, 500mV pk-pk.

Although the sensitivity for a.g.c. threshold may seem poor, in practice, local broadcast stations generally produce a quite high field strength and within a 20 mile radius of five broadcast stations tested, the a.g.c. was effective using only a six foot length of wire as an aerial.

Because of the wide bandwidth capability of the tuner it could be prone to 10kHz whistles. These are usually caused by adjacent stations whose carrier is located only 10kHz apart from the desired station. Since local stations have frequency allocations to avoid this situation it normally should not be a problem. In addition, the relatively poor sensitivity coupled with a.g.c. action reduces the strength of distant stations sufficiently to render them ineffective at producing whistles.

At some locations close to the author's home, a faint 10kHz whistle could be heard on a station operating on 570kHz. Since the nearest other station carrier is on 980kHz there seemed to be no obvious explanation. It should be recalled however that the product demodulator multiplies the signals fed to its two input ports as outlined previously. The second harmonic of 570kHz is 1,140kHz and is produced within the product detector (i.e. the $\frac{\cos 2A}{2}$ term).

This coupled with poor receiver selectivity allowed another more local strong station operating on 1,130kHz to find its way to the detector. The frequency difference is of course 10kHz and this appeared in the audio output. The level of the interference at the most unfavour-

able locations is not of annoying strength but it is worth noting that this effect can occur and is one of the limitations of this particular receiver.

Much further development is possible with the homodyne receiver and in particular the MC1330P i.c. could be applied to communications receiver circuitry. For example, the existing "homodyne" tuner could be made suitable for long distance reception by tuning the interstage coupling (i.e. replace the r.f.c. with a tuned circuit). This would greatly increase the sensitivity. Also as suggested, for a.m. reception, provide switched audio filtering to provide variable selectivity. By link coupling a b.f.o. to the associated tuned circuit the MC1330P functions as an excellent c.w.-s.s.b. demodulator. This has been proved by the author but with this simple arrangement, the a.g.c. feature is lost. More work could be done here to solve that problem. Further, it seems possible that by employing the automatic fine tuning (a.f.t.) buffer-amplifier (Pin 1) and coupling it back to a tap on the tuned circuit, a self oscillating product demodulator would be obtained.

As it stands the MC1330P is quite an effective slope detector of f.m. signals but for best results should be preceded by limiting i.f. amplifier stages.

With these fields open to the amateur experimenter it is to be hoped that further developments and applications of both the homodyne principle and the MC1330P i.c. will appear in print before too long. Certainly those who construct the tuner described in this article will acquire an interesting and rewarding introduction to the homodyne receiver.

References

1. Radiotron Designers Handbook, Fourth Edition, Langford Smith, R.C.A., Harrison, N.J.
2. Linear Integrated Circuits Data Book, First Edition, Motorola Inc., 1971.
3. R.C.A. Solid State Data Book SSD201, R.C.A.
4. "Q" Inductance Specialists, Box 3018, Tauranga, N.Z.

Total Communications

Development of "interactive" two-way television from cable distribution: combination with telephone systems

by E. J. Gargini,* M.I.E. E., M.I.E.R.E.

Wired broadcasting using modern cable technology has made possible an interactive or two-way facility for television. By this is meant techniques for obtaining immediate responses from viewers via, for example, push-button generated signals, voice signals or, if necessary, television picture signals, all originated at the subscribers' premises.

There are two main methods of distribution in wired broadcasting: (1) the wideband v.h.f. and hybrid v.h.f./u.h.f. method with "stacked" carriers, in which the programme is selected by tuning the receiver in the home; and (2) the


h.f. multi-pair distribution method with a simpler, fixed-tuned receiver which is switched (in the home) to the required programme circuit. Interactive systems are being proposed and developed to suit both these branches of wired broadcasting technology.

Interactive systems using sequential signalling are being developed for combination with the wideband v.h.f. and u.h.f. coaxial distribution systems. These either use a portion of the spectrum at the low-frequency end of the cable carrying television signals or use a separate coaxial cable placed alongside the television distribution cable. Similar systems may be developed for the h.f. multi-pair technology, and these could either bring into use spare circuits or use a portion of the available spectrum of a cable circuit carrying television and sound signals.

There are, however, limitations which apply to these systems, coaxial, double coaxial or h.f. multi-pair, inasmuch as there is a practical limit to the number of programmes which can be brought into every home and also because the bandwidth available for each subscriber-originated signal is small. This introduces a delay in signalling a response. Because each returned signal must be "stacked" in frequency or time only a limited number of subscribers can originate wideband television transmissions at any moment. These limitations are inevitable because v.h.f. and h.f. wired networks follow a "spreading-tree" configuration. This, while being fundamentally two-way (in that downstream signals applied to the centre of a system travel out to all extremities and upstream return signals applied to all extremities travel to the centre), makes it necessary, in order to recognize particular signals sent from a particular extremity, to introduce frequency and/or time division multiplexing of all signals returned from subscribers' premises.

* Rediffusion Engineering Ltd. This article is a shortened version of a paper by Mr Gargini, "The Total Communication Concept for the Future", published in *The Royal Television Society Journal*, March/April 1973.

Fig. 1 Time-shared interactive computer controlled information television (TICCIT) system.



American v.h.f. communication systems

The Mitre Corporation, U.S.A., in their interim report entitled "Urban Cable Systems" (Nov. 1971)¹ point to the opportunity of making "revolutionary improvements in telecommunications for public uses" by providing an entirely new family of television related services to every home. The report is a quantitative study of the state of the art in equipment, software and programming, and includes a survey of the market possibilities for the new services.

A system is proposed for the District of Columbia, known as the Washington Cable Television Services system, to embrace an urban community of 700,000 people, and the design of this has been based on an analysis of the demographic, social, municipal and commercial characteristics of the District and the economic and service implications of these characteristics. The technical design of the two-way system, and kinds of services provided, are based on an experimental system Mitre have built and demonstrated in Reston, Virginia. The Mitre demonstration is of a number of one-way and

two-way services using the Mitre Time-shared, Interactive Computer-Controlled Information Television (TICCIT)² system on the Reston cable system: see Fig. 1. This diagram represents several interactive communication systems and summarizes the Mitre proposals for the Washington Cable Television System.

Fig. 2 is a block diagram of the subscriber's home terminal equipment for the Mitre TICCIT system. The tests at Reston at present do not include equipment to the detail shown in the diagram. The demonstration equipment is simpler and the telephone network is in fact used as part of the two-way system experiment. This diagram, however, indicates the requirement in home terminal complexity for the fully expanded Washington Cable Television double coaxial system design. The equipment includes: a set top converter, which must have the very high channel selectivity required for adjacent channel operation on a v.h.f. stacked carrier system when this deals with nearly thirty channels in the band 60-300MHz; an A/B switch to transfer the set-top converter from cable A to cable B for receiving the second group of up to thirty channels; and a modem unit for dealing with the two-way facilities proposed for the Washington network. This modem unit is shown, associated with peripheral equipment which includes a "frame snatcher" (see below), an unscrambler and print-out devices.

Mitre have recently announced that a solid state "frame-snatcher" which can

Table 1. Potential subscribers to wideband cable services: results of Howard University survey

Type of service	Type of system required	Percentage interested in specific service	Average fee they would pay
1 Improved off-the-air signals	1-way	68	\$/month 2.84
2 Special channels	1-way	63	2.18
3 New movies	1-way	75	2.67
4 Sport events	1-way	66	2.80
5 Educational services/CAI	2-way	71	2.22
6 Burglar alarm	2-way	68	2.86
7 Shopping aids	2-way	56	2.10
8 Subscriber polling	2-way	57	2.00

hold a page of alpha-numeric information will be available later at a price of about \$500. In operation the TICCIT computer will address sequential fields of alpha-numeric information to particular subscribers: a group of 3,000 subscribers could have this information up-dated every two minutes for every allocated television channel. The unscrambler unit is intended to provide security either for the subscriber when he calls for private data, i.e. bank statements, or for the programme originator when transmitting pay television signals. The print-out device can include facsimile or other forms of hard copy.

The services offered by the system include television programmes on child care, health care, educational courses of

all types, employment and housing, information on community meetings and locally originated television programmes. The system will cope with technical innovations such as computer-aided instruction, safety alarms, automatic meter readings and selective power control services. It also provides a basic network for automatic traffic control and public safety surveillance.

The Howard University in the U.S.A. conducted a market survey among householders to establish what services would interest potential subscribers and how much they would be prepared to pay for these services. Table 1 shows the results of this survey, based on 248 interviews with heads of households. Of all the families contacted, 85 per cent




Fig. 2 Subscriber's equipment for TICCIT system (see Fig. 1).

expressed an interest in cable television and a willingness to pay a monthly fee of at least one dollar per month for at least one service. The most popular service was new films at 75 per cent. The least popular was shopping aids at 56 per cent.

Although Mitre have shown the new film service as a one-way system, in any practical pay television system some means must be provided for subscribers to decide whether or not to accept a charge, and this implies that a two-way facility must be available.

Fig. 3, taken from the Mitre report, shows the total annual subscriber revenue per householder that would follow from the expected utilizations of different combinations of services. Quite obviously the system operator would be interested in obtaining maximum revenue from the system by charging higher subscriber fees, with a consequent reduction in utilization of the system to about 50 per cent. This, however, would make the meter reading capability of the system far less attractive to the gas, electricity and water undertakings, who would only take interest and subscribe to a system which almost entirely replaced the present manual system of meter reading.

American interest in "total communication" systems is not restricted to the Mitre proposals for Washington. The Theta Com organization, a Californian company, have produced a system known as the Subscriber Response System and are conducting tests in El Segundo. Fig. 4 outlines the main parameters of the system³. Sixteen television and f.m. broadcast sound channels are distributed from the source in the band 52-300 MHz and passed to off-air receivers via a highly selective channel converter. Digital information on a carrier of 50 MHz is passed from the local processing centre to all subscribers, and responses from

- (a) all 1-way plus all 2-way services
- (b) all 1-way services
- (c) single 1-way plus single 2-way service
- (d) single 1-way service




Fig. 3 Revenue as a function of penetration for various combinations of service.

subscribers and subscriber equipment are transmitted back to the processing centre in the band 6-30 MHz, together with up to three television signals originated by subscribers.

The frequency separation and message routing system is also shown in Fig. 4. The digital data rate for downstream and upstream data is 1 Mb/s, and compensating delays are provided at subscribers' terminals to reduce the effect of propagation delays on the network. It is claimed that this, combined with special programming techniques, permits a total basic interrogation and response time of less than 2.5 seconds for 50,000 subscribers. Systems which do not eliminate the effect of propagation delay on the interrogation response sequence must allow a time delay at least equal to twice the propagation time between the computer and the most remote subscriber, to avoid interference between responses from two subscribers. The time required to poll 50,000 subscribers would

increase (with 10-mile cable runs and without compensating delay) to 8 sec on the Subcarrier Response System.

The most extensive system concept, discussed in a report⁴ by the Sloan Commission of the Alfred P. Sloan Foundation, is one under test and being demonstrated by Vicom Industries Inc.⁵ This is intended to be a complete interactive digital system and has provision for controlling television channel use, data transmission and on-line interaction with the viewing audience by push-button keyboard response or by radio response, all these functions being controlled by a computer located at the "head" end. The outgoing command and control channel operates at a 1 Mb/s data rate and transmits 20-bit words at 40,000 words per second to the subscribers' terminals. These words are interpreted as either data for a terminal, commands to a terminal, or the "polling" of a terminal for a response. The terminal responds to every "poll" with its address and a single data character, and this returned information is sent at the 1 Mb/s rate used for the outgoing signal.

A key feature of the Vicom system is the control of who may view any channel. The converter is automatically disabled from the control centre whenever its channel selector is altered, and information about the new channel selector position is returned to the "head" end computer as a response to the next "poll". If the channel may be viewed by the subscriber a computer authorization signal is then transmitted which turns on the converter. The control of who views what is a requirement of pay television and of controlled group conferences.

The Vicom system also allows the chairman of a conference to control who says what by enabling or disabling the microphones of other subscribers on an individual basis. Anyone wishing to speak must indicate this by pushing a button.




Fig. 4 Subscriber response system.

Two channels are allocated in the Vicom system for the command and response functions. Downstream signals are sent in the 108-114 MHz band and the upstream channel is in the band 6-10 MHz. All data transmission is on a time division multiplex basis and a word is 20 one-microsecond bits. Modems are addressed at a rate which depends upon the particular action requested by a subscriber and is under the control of the head-end computer. The rate is between one and five per second for routine "polling", and for full screen displays of alpha-numeric information up to 5000 words per second can be transmitted to a single subscriber. Extensions to 30,000 words per second are possible.

The computer capital cost per subscriber based on 4000 subscribers is quoted⁴ as \$5-\$15 depending on the type of data service rendered. The present cost of a home terminal is estimated at \$265 and in large scale production about \$135. This home terminal comprises a keyboard entry unit with 12 momentary-contact keys, a microphone and a 25-channel converter that may be enabled and disabled under head-end control. Later models will include storage for up to 16 alpha-numeric characters which can be viewed on the television receiver. Provision is made for attaching a variety of peripheral devices such as television cameras, full screen alpha-numeric generators, hard copy printers and full keyboard typewriters.

Telecable Inc.⁶ have arranged for tests of the Vicom system in Overland Park, Kansas. The tests include home instruction for disabled children and home shopping demonstrations in co-operation with the Sears Roebuck company.

Central switching systems

The switched telephone system for point-to-point communication follows a "hub and spoke" network configuration and each circuit from the "hub", or exchange, is terminated at a particular subscriber's premises. There is thus no requirement, in general, for circuits to handle information from more than one network extremity, and thus no requirement for time division multiplexing at subscribers' premises.

What are called television switching centre systems are "hub and spoke" arrangements like the switched telephone network. Examples of these are the Dial-a-Program system — a development of the h.f. system in which the subscriber's selector switch is placed at a programme exchange and operated by a dial in the home — and a similar American system called Discade⁷ which employs coaxial cables. An important feature of the television switching centre system is that the television programmes made available at programme exchanges can be increased in number without modification of equipment in the home. It is, of course, necessary to increase the number of cable circuits linking exchanges, typically 10 per cent of the total cable route distance, and to add extra programme lines at the exchanges. But both these operations

entail no disturbance to the subscriber network or equipment, which is analogous to the expansion of telephone services. To complete the analogy, the television switching centre system has the important limitation, in common with the telephone, that the number of subscriber cable circuits (i.e. output lines provided) is a direct function of the number of subscribers that can be served, and a sufficient number must be installed at the outset to cater for future development.

American opinion on the relative merits of the tree structured "stacked" carrier system and the "hub and spoke" central switching system is varied. In the report by the Sloan Commission on cable communication entitled "On the cable — the television of abundance", the main advantages of the central switching system such as Dial-a-Program and Discade are given as:

- Almost complete immunity to the interference effects associated with the multiplexed v.h.f. system.
- The ability to use simplified tunerless television receivers.
- The better security of the system to unauthorized use, i.e. switching systems require connection somewhere of a physical device, whereas in the v.h.f. "stacked" carrier system the subscriber does not need a special physical device but only modification of the legally connected device he already has.
- The ability to provide a separate, full-bandwidth upstream channel from every subscriber.

On the other hand the Sloan Commission finds the main advantages of v.h.f. multiplexed systems to be:

- There is no "real estate" problem because the distribution amplifiers can be mounted on the poles which carry power distribution cables, transformers and the telephone network (a feature of most American towns), whereas in the Dial-a-Program system the local exchanges must be installed at the outset because they also house trunk repeating equipment, and in settled communities site acquisition can be difficult.
- For the moderate channel capacity considered necessary v.h.f. distribution systems are cheaper with respect to network and distribution equipment costs.

The Sloan Commission has also speculated on the future development of point-to-point video services and considers this would represent a major cost escalation of subscriber equipment by at least \$500 for the modulator and camera in large quantity production. They go on to quote a study by Complan Associates, which estimated the added capital cost of a complete nationwide narrow band (1 MHz) videophone service for 100 million subscribers to be \$3000 per subscriber — about five times the existing voice-grade telephone service — and that a high quality 6 MHz service would cost about \$12000 per subscriber. In both estimates "out of plant and local exchange costs" account for between one-third and half of the total. Thus a high quality, two-way videophone service would cost an amount just within that of a typical

c.a.t.v. head end dealing with 10,000 subscribers — at least \$4000 per subscriber and about 20 times more than v.h.f. stacked carrier systems. No estimate is given for the cost of a central switching system such as Dial-a-Program in this context but it would be substantially less.

It would be fanciful to imagine that wide-band, or for that matter narrow-band, videophone will have much application in the foreseeable future by the general public, because of cost. It is possible, however, for a wide-band videophone service to be developed for specialist applications such as "tele-medicine" and possibly at least within local communities.

Marlarkey Taylor and Associates of Washington, D.C., have produced a survey report distributed by the National Technical Information Services of the U.S. Department of Commerce entitled "Pilot projects for the broad band communication systems".⁸ The report considers the modification and addition to the tree-structured v.h.f.-c.a.t.v. system to achieve two-way communication and points to the difficulties and complexities of the home terminal equipment required in what they describe as "these party line systems". They consider that the type of communication contemplated does not even approach conversation or narrative, but since the computer is able to interrogate all subscribers in a very short time it is possible to send alpha-numeric messages using TWX or other codes. Also, with suitable computer programming, messages could be transmitted for subscriber communication. Mention is made in this report of work in the television receiver industry on television tuner design to suit the adjacent channel etc. requirements of c.a.t.v. systems dealing with more than 12 programmes per cable.

The report includes a cost comparison between double coaxial tree and Discade and Dial-a-Program hub systems, dealing with 24 channels to 5000 subscribers. This indicates that switched systems at this channel capacity cost about twice as much as tree systems. Off-air receivers were assumed as being used in both types of system and the comparison included no two-way facilities. The report, however, drew attention to the advantage of the switched system in that cheaper simplified receivers giving high quality pictures, not necessarily restricted to N.T.S.C. standards, could be used and that the remote switching feature permits maximum security for pay television etc. without the necessity for scrambling.

In the cost comparison all cabling was assumed to be carried overhead on messenger wire strung between utility poles. These poles also support the active equipment used in the v.h.f. tree distribution system. There is, however, a growing tendency to place networks underground in new communities and this would reduce the cost differential between the tree and hub systems.

It seems appropriate at this point to present the case for a central switching system and to list the facilities which appear to be of most value to a developing society. I believe that a

wired central switching system can overcome the natural barrier of the restricted capacity of radiated over-the-air broadcasting and make it possible to look forward to a future where television can be a selective medium in addition to a mass medium that is as open and unrestricted as the printed word. This argument leads directly to the requirement for a two-way visual communication system and for an electronic library or libraries capable of storing vast quantities of information in alpha-numeric form and dealing with a very large number of stationary or moving television pictures. All this information would have two main purposes: (1) education and instruction,⁹ and (2) entertainment and information.

Fig. 5 depicts the situation in education envisaged for the future. The pupil is not entirely taught by television but the role of television is certain to be much greater in the future.

Fig. 6 depicts a personal view of the ordering of services dealing with entertainment and information for the

future. The central base, labelled entertainment/community affairs resource centre, is in principle the central switching system. The diagram includes, in addition to the home, other access points shown as kiosks which might be placed in shopping areas. These kiosks may also find application in future transportation schemes in which the routing of public transport vehicles is controlled directly by public request.

A central switching system with all the facilities outlined in Figs. 5 and 6 must be economically viable. The user must pay for it, either indirectly by taxes and in purchasing advertised goods or services, or by direct billing. From the pay-television aspect of direct billing, the system must also have commercial security in the sense that the originator of a televised programme must be sure that only those who are prepared to accept a charge and pay are able to view the programme. It must also be possible for the head of the household to be secure in the sense that he can authorise the expenditure incurred and

what is to be watched — by turning, for example, a pay television key.

Some information and instruction must be restricted at the source, i.e. information intended for specialist users who require high security, such as bankers, stock-brokers, police and doctors. The system must therefore include a "programme denial" feature which cannot be bridged electronically by someone in the home.

A central switching system can meet these requirements.

(To be concluded)

References

1. W. F. Mason. "Urban Cable Systems — an interim report (M71-64)", Mitre Corporation, Washington, D.C., Nov. 1971. Also W. F. Mason and S. Polk, "Revolutionising home communications (new techniques for using computers with cable television) (M72-38)", Mitre Corporation, presented at the 1972 IEEE Intercon, 20th-23rd March 1972.
2. K. J. Stetten. "Ticcit: A delivery system designed for mass utilization (M71-56)", Mitre Corporation, Oct. 1971.
3. R. T. Callias. "Subscriber Response System (El Segundo Interim Test Report)", Hughes Aircraft Company, California, NCTA Convention, Chicago, 17th May 1972.
4. "On the cable — the television of abundance", Report of the Sloan Commission on cable communications.
5. "Classroom in the Home Via Cable" (Vicom system at Overland Park and the Mitre system at Reston), *Broadcast Management Engineering*, Oct. 1971.
6. *IEEE Spectrum*, Nov. 1971, p.47.
7. J. E. Ward. "The Ameco Discade System", Appendix A, Report of the Sloan Commission on Cable Communications, McGraw Hill, 1971, p.199.
8. "Pilot projects for the Broadband Communication Distribution System PB208 913 (Nov. 1971)", Marlarky Taylor and Associates, Washington, D.C., distributed by National Technical Information Services, U.S. Dept. of Commerce.
9. Prof. G. Pask. "Computer Assisted Learning and Teaching" (System Research Ltd), Proceedings of a seminar on computer based learning systems, Leeds University, 8th-12th Sept. 1969, published by the National Council for Educational Tech., London.




Fig. 5 Future educational service.




Fig. 6 Future entertainment and information service.

Motional Feedback Loudspeaker

Low frequency reproduction from a small enclosure

The principle of deriving a corrective electrical feedback signal from a moving loudspeaker cone has been known for some time¹. Several systems have been developed based on this principle and recently Philips have released information on a new "motional feedback" loudspeaker system (22RH532/00) which has been under development for several years. Comparative listening tests indicated that Philips have achieved a high degree of success with a controlled frequency response for the lower audio frequencies. The system, whose volume is a mere 15 litres (38 × 28.5 × 22cm external dimensions), is designed with a 12dB/octave low frequency cut-off at 35Hz.

Feedback principle

A loudspeaker cone does not always move in the pattern which its input signal intends. Distortion is generated — especially at low frequencies — by the resonant condition of the system and also by





Fig. 1. Block diagram of the method used for deriving a corrective signal from a speaker's movement.

Fig. 2. Circuitry in the Philips motional feedback system which is directly involved with the principle outlined in Fig. 1. Resistor * has a negative temperature coefficient.



the inability of the system to cope with the condition cone velocity \propto frequency² for a constant sound pressure level. If the motion of the cone can be sensed in some way to generate a current proportional to the speaker's acceleration, then this can be compared with the input signal and a corrective signal generated to force the cone to move in the manner originally dictated to it.

Fig.1 outlines the motional feedback system. Movement of the loudspeaker cone is transduced into an electrical analogue signal which is fed to an adder with the original input signal. The resultant signal is then compared with the current which flows through the loudspeaker voice coil and a corrective current is generated if the loudspeaker cone acceleration (proportional to the feedback signal) does not follow the input signal.

Several methods of deriving a feedback voltage from the speaker cone movement have been tried. A voltage may be derived from the displacement of the coil or from its velocity. Velocity feedback by means of an equivalent series inductance, or displacement feedback by means of capacitive variations have the disadvantage that a stationary reference point is required. This and other difficulties can be avoided by a device which measures the acceleration of the speech coil. The Philips system uses a PXE ceramic acceleration transducer — of the type used in ceramic pickup cartridges — which is clamped to the cone with the aid of two small rubber blocks. The element produces voltage which is proportional to the acceleration (inertial force) of the cone, and, provided the cone acts as a piston, the cone's acceleration is proportional to the acoustic oscillation. A drop of soldering tin is deposited on each side of the ceramic element to hold the attached wires in position. Connected to the output of the PXE transducer is an amplification and frequency correction stage. The resultant signal is fed back to the adding circuitry.

Circuit description

All crossover, power amplifiers and feedback circuitry for the three drive units in the Philips system is contained within the loudspeaker cabinet. The circuitry associated with the motional feedback loop and the bass driver power amplifier is shown in Fig.2. The input signal is taken from an 18dB/octave low pass filter and a 12dB/octave high pass filter, so that the band of frequencies fed to the bass unit circuitry is approximately 35 to 500Hz. This signal is fed to the adding circuitry (Tr_1), to which the feedback signal derived from the acceleration transducer is also applied. The latter arrives at the base of Tr_1 via R_2 and C_2 and the input signal does so via R_1 . The gain of the adding circuitry is approximately unity. A high-impedance ceramic crystal is matched to the feedback circuitry using a junction f.e.t., Tr_{10} . If the gate impedance of Tr_{10} is to be kept high, the drain-source voltage must not exceed a certain

value and to ensure this condition, a zener diode is used in conjunction with Tr_{11} . Before the feedback signal is fed to the adder stage, the amplitude response is corrected by the arrangement of Tr_{12} and Tr_{13} . Down to approximately 80Hz, the correction stage has a flat amplitude response, but below this the signal has a slope of 6dB/octave, the reason being that feedback at the resonant condition (also at about 80Hz) may cause the amplifier to become unstable.

The input signal is fed from the adder to a 40W amplifier (Tr_6-Tr_9) which drives an 8in bass unit. The signal which flows through the speaker voice coil is used to provide an input to the base of Tr_3 , which forms part of a differential amplifier with Tr_2 . The input to the base of Tr_2 is the sum of the input signal and the motional feedback signal. Thus the speaker's movement is compared with the driving signal and a corrective current is generated if necessary.

References

1. Klaassen, J.A. and de Koning, S.H., "Motional feedback with loudspeakers", *Philips Technical Review*, Vol.29, pp.148-157.

Books Received

Data Telecommunication by R. N. Renton gives an account of all techniques involved in interconnecting data systems and computers. It describes the various DATEL services recently introduced by the Post Office, special attention being devoted to error-detecting and error-correcting codes and to systems designed to combat errors due to transmission. The recently adopted CCITT/ISO/ASCII seven-unit code is presented. The essential line characteristics for satisfactory data transmission at various speeds are specified, full references being given to international (CCITT) standards. The important characteristics of national and international line circuits for data transmission are specified. Basic network plans for the U.K.'s STD system, and for worldwide telephone and telex exchange switching are illustrated with maintenance and fault testing procedures also fully covered. Although written for telecommunication engineers and students, this book will also be of interest to computer designers and users. Price £2.75. Pp.227. Sir Isaac Pitman and Sons Ltd, Pitman House, Parker Street, Kingsway, London WC2B 5PB.

Colour Television — Questions and Answers by J. A. Reddihough gives a simple, practical account of colour TV transmission and reception for the enthusiast, technician and service engineer. While the emphasis is on the techniques used in PAL colour receivers, the book necessarily begins by covering the principles of colour and the way in which a compatible colour signal is transmitted. The next sections deal with the shadowmask tube and the circuits needed to modulate it, and how the receiver decoder processes the composite transmitted waveform to produce the signals required by the shadowmask tube.

The final section is devoted to convergence circuits and the various convergence adjustments that are involved. Price 75p. Pp.108. Butterworth & Co. Ltd, 88 Kingsway, London WC2B 6AB.

Electrical Transducers for Industrial Measurement by P. H. Mansfield describes the principles of operation of the main types of instrument transducer for measuring a wide range of physical variables such as pressure, temperature, speed, flow, displacement, viscosity and density. Details of the range, accuracy, and linearity are given in each case. Since new applications for transducers are constantly being discovered, a useful inclusion is a "Measurements Method Chart" which shows methods for converting into an intermediate output and thence to a final electrical output of physical quantities that cannot be directly measured. To enable the reader to select the most suitable instrument for a specific purpose, a directory is included of transducer manufacturers or suppliers in the U.K., which lists readily available devices with their mode of operation. The book is a guide for engineers involved in instrumentation and control and to students taking degree or HND subjects in these courses. Price £4.40. Pp.281. Butterworth & Co. Ltd, 88 Kingsway, London WC2B 6AB.

Solid-State Circuits by G. J. Pridham provides an introduction to modern semiconductor theory and practice. It is a sequel to "Semiconductor Circuits" written by the author in conjunction with J. R. Abrahams, but while embodying certain features of that book it also lays considerable emphasis on field effect transistors and integrated circuits. The text is divided into three sections. The first is concerned with the basic physics of semiconductors, diodes and transistors and the construction and characteristics of devices including integrated circuits. The next section deals with the fundamental use of semiconductor devices in rectifier, amplifier and oscillator circuits. One chapter specifically deals with the high frequency use of transistors and in all examples, designs from device characteristics are included. The final section develops the a.c. equivalent circuits of transistors. Price £2.50 (hardback), £1.80 (limp). Pp.184. Pergamon Press Ltd, Headington Hill Hall, Oxford OX3 0BW.

Illustrations in Applied Network Theory by F. E. Rogers. Network theory has vital practical objectives: the analysis of given networks, or the synthesis of networks to fulfil given requirements. Though synthesis and analysis are converse in procedure, both are bound by the same circuit laws. This notion, together with duality, permeates the book in which a hundred numerical and algebraic illustrations exemplify practical circuit problems. Chapter headings include: general principles for passive and active network analysis; transient response and its correlation with frequency response; simplifying procedures, theorems and equivalences; power transfer and allied concepts; examples of non-linearity and the response of networks to non-sinusoidal waveforms and finally electronic amplifiers with feedback circuits. The book is primarily intended for the intermediate years of degree courses in electronic and communication engineering but it will also be of value to students following similar courses, such as HNC, HND and CEI. Price £5.00 (hardback), £2.50 (limp). Pp.228. Butterworth & Co. Ltd., 88 Kingsway, London WC2B 6AB.

News of the Month

Optional radio broadcasts

Hi-Low, standing for High Listener Option Radio, is a system of f.m. broadcasting proposed by David Williams of Matrix Enterprises for the transmission of two simultaneous sound broadcasts (see August "News" p.392 for tests made by the B.B.C. of the SCA-type system). One of the programmes can be in stereo and is compatible with standard receivers. The second programme is a time-shared sequence of items — the idea being that these items would be for minority groups within a wide audience receiving the compatible programme. The time-shared programme is accompanied by an electronic control signal which is made to change according to the kind of programme item which is being broadcast.

According to the technical information supplied in a pamphlet about the system prepared by Matrix Enterprises, the aim is as follows. The transmitter operates in the v.h.f. band and is frequency-modulated with a signal which may be considered as consisting of three components.

Component A is a sound signal conventionally prepared for v.h.f./f.m. broadcasting, and which may be a stereophonic signal encoded according to the pilot-tone system. Component B is a low-level 19kHz tone which is amplitude-modulated with one or more "key frequencies" of less than 1kHz. If component A is a stereophonic signal, the carrier frequency of component B serves as the stereo pilot tone. Component C is derived from a 76kHz frequency, phase locked to the fourth harmonic of the carrier of component B, and modulated by a single-sideband technique with a sound signal. The lower sideband is used, and the subcarrier suppressed, so that component C consists only of modulation sideband frequencies between 76kHz and about 60kHz. Different key frequencies, or combinations of frequencies, are transmitted in component B according to the programme content of the sound in component C.

In the receiver, the sound signal in component A is recovered conventionally. The 76kHz subcarrier is regenerated by quadrupling the 19kHz pilot tone, and a product detector used to recover the

sound signal in component C with high quality. Component B is monitored by a circuit which can be pre-set by the listener to respond to one or more key frequencies or frequency combinations. When such a frequency or combination is present, the audio circuitry of the receiver is switched to reproduce the sound from component C.

Ultrasonic holography in medical diagnosis

Workers in the Medical Engineering Department of Surgery at the Children's Hospital of San Francisco have recently produced some extraordinarily fine ultrasonic halograms using an immersion scanning technique for visualizing some internal organs of the human body. The basic technique of using ultrasonic holography has been used for the past twelve years but most of the early results proved disappointing. Three dimensional images of internal structures made without subjecting the patient to painful or hazardous procedures are the dream of every diagnostician.

The technique of the new system, manufactured by Holosonics Inc. of Richland, Washington, U.S.A., differs from optical holography in that the interference wave pattern cannot be recorded on film. It is recorded instead by making the sound beams impinge on a fluid surface which is disturbed according to the sound intensity pattern. This surface pattern is detected by coherent light from a laser and the reflected beam used for optical image reconstruction.

The Holosonics instrument employs a five-inch quartz crystal with a fundamental frequency of 1MHz as the ultrasound generator. Harmonics bringing the operating frequency up to 3.5 or 7MHz are used. The limb or organ to be investigated is immersed in the fluid between the crystal and the acoustic lens system. A reference beam is provided by a similar transducer. The depth of focus obtained is about 1cm. Images are recorded on film or on a videotape system.

Operated in the pulsed mode, the average sound intensity is about 20mW cm^{-2} . With pulses of 100 microsecond

duration at a repetition rate of 50Hz the peak intensity could exceed 4W cm^{-2} which is questionably high if reproductive organs are allowed into the beam, as they would be for the examination of the uterus.

This system seems to have neared the ideals of acoustic holography and may well prove to be valuable not only to medicine but in other applications of non-destructive testing.

Anti-skid control by micro-circuits

Two integrated circuits designed specifically for the automotive market have been announced by the Fairchild Camera and Instrument Corporation. Both are complex linear circuits developed over the past two years as "custom" circuits before being added to the standard product line. Typical applications include the control of anti-skid systems, fuel metering and the generation of either digital or analogue tachometer displays. Both are subsystems that will be used as components of larger automotive electronic systems.

The UA7350 includes a tachometer pulse generator, an operational amplifier and two comparators on a single chip, in a 16-pin dual-in-line package. The tachometer section produces fixed-width pulses at the zero crossings of a ground-referenced alternating current input signal.

The UA7351 is a triple operational amplifier, a general purpose circuit also specifically designed for automotive operation, with single 4- to 16-volt or dual 2- to 8-volt power supplies. The circuit contains three identical op amps on a single circuit chip in a 16-pin dual-in-line package.

New interference regulations

New regulations controlling interference from the ignition systems of internal combustion engines* have recently been introduced to Parliament by Sir John Eden, Minister of Posts and Telecommunications. They extend the frequency range controlled by the present regulations in order to give greater protection to the whole range of frequencies now used by television. They have been made after consultation with the Minister's advisory committee on wireless interference from ignition systems and come into force on October 1.

The existing Wireless Telegraph (Control of Interference from Ignition Apparatus) Regulations made in 1952 require assemblers, importers and users of ignition systems forming part of combustion engines (other than in aircraft) to ensure that the field strengths of electro-magnetic energy radiated at frequencies between 40MHz and 70MHz do not exceed specified limits. These regulations will still apply to ignition apparatus assembled in engines before 1 October 1973.

The new regulations which extend the frequency range to 250MHz conform

with the agreed international standards for radio interference suppression with which all vehicles manufactured on and after 1 October 1973, have to comply under the Motor Vehicles (Construction and Use) (Amendment) (No.4) Regulations 1972†.

*The Wireless Telegraphy (Control of Interference from Ignition Apparatus) Regulations 1973, SI No 1973/1217 published by HM Stationery Office.

†SI No 1972/1734 published by HMSO on behalf of the Department of the Environment.

U.S. "TV Time" system

Time-of-day information can be broadcast to one millionth of a second accuracy by a new system developed by the U.S. National Bureau of Standards at the Boulder, Colorado laboratories. Equipment at the broadcast station and complementary decoding equipment on the TV receivers allow information to be encoded and decoded to provide information in caption form on the screen. The aim is to provide accurate information to scientific and commercial institutions which need precise time and frequency data. The signals can be used to automatically reset electric clocks after a power failure and can help to analyse power failures on a continent-wide basis.

The primary standard of frequency and time is the N.B.S. atomic clock system which provides a time display accurate to a few thousandths of a second with

a possible accuracy to one millionth of a second using an optional high-accuracy decoder. A frequency reference at 1MHz, accurate to one part in 10^{11} , is also available at the receiver.

P.C.M. for the North

The B.B.C. has now completed a further stage in its p.c.m. sound distribution system, which will make it possible to start a full p.c.m. stereophonic service from the stations at Holme Moss and Belmont. These stations serve most of Lancashire, Yorkshire and Lincolnshire, and parts of the adjacent counties.

Test transmissions in stereo have begun from both stations but it may be necessary to revert to monophonic transmission on occasion, for essential engineering work. The new system will be used for Radio 1 (when that programme is transmitted on v.h.f.). Radio 2, Radio 3, and Radio 4, Radio 3 has been transmitted in stereo for some years, but it will be using the new p.c.m. system for the first time (See "News", Sept. 1972, page 411.)

Minicomputer on a card

A minicomputer, the Naked Mini/LSI, contained on a $15 \times 17 \times 1$ in printed circuit board has been introduced by Computer Automation. Contained on the card are a $1.6\text{-}\mu\text{s}$ central processing unit

(seven m.o.s. l.s.i. chips), memory storage and input/output logic interfaces, etc, making up a total weight of 4lb. The minicomputer is also available complete with chassis, control console, hexadecimal data-input keyboard and power supply, in which configuration it is known as the Alpha/LSI. Compared with Computer Automation's previous 16-bit minicomputers, their new machines cost half the price, occupy one-third the volume and offer functionally the same performance.

Radio 4 in the South-West

The B.B.C. has recently been authorized by the Ministry of Posts and Telecommunications to install five low-power transmitters in the south-west of England. These will broadcast the medium-wave Radio 4 service, including the locally produced magazine programme, news and weather reports which are at present transmitted on v.h.f. only.

The locations of the first four stations, together with their proposed wavelengths and the service dates which it is hoped to achieve are as follows:

Torquay	351 meters,	854kHz	Autumn 1973
Barnstaple	439 meters,	683kHz	Autumn 1973
Plymouth	206 meters,	1457kHz	Autumn 1973
Redruth	397 meters,	755kHz	Spring 1974

The Barnstaple service will replace the present one on 434 metres; the others will be additional to the existing Radio 4 medium-wave services.

Two geologists from the Polish Institute of Mining inspect three seismometers, with their attendant amplifier/modulators, which are part of a quantity of seismological recording equipment manufactured by Racal-Thermionic. The equipment has been adapted to accurately predict and locate potential "rock burst" activities — a mining phenomenon extremely dangerous to men and machinery underground.



TV deliveries in the U.K.

Deliveries of colour TV receivers to U.K. distributors have reached a total of 1,322,000 for the first half-year, a rise of 74% on the same period last year (761,000), according to the latest figures compiled by the British Radio Equipment Manufacturers' Association. Deliveries of monochrome sets for the first six months of this year were 765,000, a fall of 19% over 1972 (943,000 for the same period).

These are totals of U.K.-made and imported deliveries to the home market, including those to specialist rental and relay companies.

Briefly

The Sonex 1974 audio exhibition will move to the Post House Hotel, London Airport (Heathrow) and takes place from 29th to 31st March.

The U.S. Postal Service has issued a commemorative stamp for the 25th anniversary of the transistor — part of a series on the progress of electronics.

A Wireless World Annual is to be published for the first time later this year. Details will be announced shortly.

Electronic Sound Synthesizer: Part 2

Continuing the construction with descriptions of voltage control circuitry, reverberation and the exponential converter

by T. Orr,* B.Sc., and D. W. Thomas,† Ph.D., M.I.E.R.E.

The first part of this series of constructional articles (August issue) described the philosophy behind the design of the synthesizer and its capabilities as a musical or educational instrument. The series continues with constructional detail of the circuitry. Each basic modular unit is described in full, but the number of units employed can be varied to suit the constructor's needs.

Sweep frequency oscillator

By driving VCO_1 with a ramp, generated by VCO_2 (both described last month), it is possible to produce a sweep frequency oscillator capable of covering the entire audio spectrum in one sweep (Fig. 14). If the swept sinewave output of VCO_1 is then fed into a network, the amplitude-frequency response of that network can be rapidly determined. A three decade sweep is available and the peak to peak amplitude is virtually constant. However, the sinewave generated by VCO_1 is by no means pure, having a harmonic content of between 3 and 4%. This limits the resolution to a rather modest value, but even so, a reasonable representation of the network's frequency response can be obtained. (It is particularly useful for directly observing the effect of tone controls in audio amplifiers.) To display the amplitude-frequency response, the ramp drives both the oscillator VCO_1 , and an oscilloscope (in the x-direction), whilst the network response is displayed in the y-direction. The drive need not be a ramp; in fact any continuous function could be used.

Voltage controlled oscillator, VCO_3

This oscillator produces a sequence of steps, the amplitude of the steps being individually controllable. The number of steps in the sequence can be varied up to a maximum of six (Fig. 15) and a series of pulses is also available (1 to 1 mark/space ratio) each being coincident with the leading edge of each step. The oscillator is voltage controlled and has a pair of summing inputs. The frequency-voltage relationship is exponential and extends from subsonic frequencies to above 20kHz, all in one range.

The oscillator, which consists of a voltage controlled astable¹ driving a binary counter, is shown in block diagram form in Fig. 16.

Fig. 14. Using VCO_1 and VCO_2 as a sweep frequency oscillator.




Fig. 15. Functions provided by voltage controlled oscillator, VCO_3 .





Fig. 16. Block diagram of VCO_3 .

*Electronic Music Studios.
†University of Southampton.

The b.c.d. output is decoded into decimal form, attenuated by pots 1 to 6 and then summed. The length of the resulting sequential output can be modified by selectively resetting the binary counter. The circuit diagram of VCO_3 is given in Fig. 17. Transistors Tr_2 and Tr_3 are voltage driven and provide a current drive to the astable. The result is an exponential current-voltage relationship and an exponential frequency-voltage response.

The useful range of the control voltage applied to $Tr_{2,3}$ is a few hundred millivolts, and must be generated relative to $+V_{cc}$. Preset R_7 is adjusted so that the clock frequency produced is approximately 20kHz with the bias set at maximum. Also, when the bias is set to a minimum, preset R_{10} is adjusted so that the clock frequency is approximately 0.2Hz. Unfortunately, the effects of R_7 and R_{10} are interdependent and hence they must be set up iteratively until convergence is achieved on the desired settings.

The logic section is self explanatory;

however, the logic power supply must be decoupled with a $0.1\mu F$ capacitor. Note that this oscillator does not lend itself to construction on plug-in boards, as the edge connections required are exceptionally large.

Voltage controlled amplifier, $VCA_{1,2}$

The heart of this unit which performs the function of amplitude modulation is a linear four quadrant multiplier, the device being an integrated circuit, SG1495D. This device operates from a $+15V$ supply, and when used in the circuit shown in Fig. 18 can accept inputs of $\pm 5V$. The frequency response is greater than that required. The output is taken between two load resistors and a differential amplifier (IC_2) is required to remove the common mode signal. Design of the multiplier and differential amplifier is very nearly the same as that given in the applications sheet for the SG1495D but some component values have been modified and lower tolerances are used. A scale factor of 0.1 is employed.

The multiplier accepts two inputs, X and Y, and generates an output that is linearly proportional to the product XY. The X input is the audio signal V_{A1} , and the Y input is the output of the control circuit. This circuit is a voltage summer with inputs of V_{C1} , V_{C2} and a bias voltage. This arrangement is that of a "perfect" half wave rectifier, thus, when the sum of the control and bias signals goes negative, the output of IC_3 remains at 0V. Only when the sum is positive will an output (a control voltage) be produced. In this way, the control section has a threshold characteristic, this threshold occurring at 0V and being used as the reference level for zero output from the v.c.a. When long leads are used, parasitic oscillation may occur, but this can be suppressed by an RC network (C_1R_2).

Aligning the v.c.as

Four presets (Fig. 18) have to be aligned; these are R_{20} , R_{21} , R_{14} and R_8 . The first two are Y and X "offset adjust", the third is "gain" and the last is "output offset".




Fig. 17. Circuit diagram of VCO_3 .

Set X and Y to 0V making sure that the bias (R_{23}) is set at its most negative setting. Monitor the output of IC_2 and adjust the output offset (R_8) until it is at zero potential. Set X to +5V, but keep Y at 0V, and

adjust R_{20} , the Y "offset adjust" until the output is again at zero potential.

Set Y to +5V, set X to 0V, and adjust R_{21} , the X "offset adjust", until the output is once more at zero potential.




Fig. 18. Circuit diagram of voltage controlled amplifier $VCA_{1,2}$.

Now repeat the first step. The last preset to be adjusted is R_{14} , the gain control, which alters the scale factor of the generated output. The unit is now a functional v.c.a., and some amplitude modulation can be demonstrated. Also the audible and visible effect of varying the X and Y "offset adjust" can be observed.

Let VA_1 be a 1kHz sine wave and VC_1 be a 100Hz triangular wave. By varying the bias control, the product can be made to rise or fall above the reference level horizon (Fig. 19a).

If the sinewave and triangle are produced by VCO_1 and VCO_2 , then the output will also be one-sided as both of these signals are one-sided (Fig. 19b). If however, the signal VA_1 is alternating, then a double sided output will be produced.

The effects of misalignment of the X and Y "offset adjust" can now be observed. For the Y "offset adjust" the result is that the output is non-zero when the control voltage reaches the threshold level. The output may never reach zero or may even pass through zero and become inverted (Fig. 19c). The dynamic range of the v.c.a. is thus severely limited by errors in the setting of the Y "offset adjust". Misalignment of the X "offset adjust", results in the unwanted components of VC_1 , VC_2 and the bias appearing at the output, this being particularly disturbing when VA_1 is zero.

Voltage controlled filter

The v.c.f. is a bandpass filter with pre-settable Q factor and a variable (and voltage controllable) centre frequency. The circuit diagram of the v.c.f. is given in Fig. 20. The use of a multiplier makes the circuit appear rather complex; an alternative approach is to use f.e.t. modulators. The result would be a reduction in circuit complexity and cost, paid for at the expense of increased distortion and a loss of linearity of the centre frequency with respect to the control voltage.

The circuit operation is as follows. The sum of the bias and the input control voltage is squared and used to drive the multiplier. The transfer function of the square law generator is given in Fig. 21, transistor Tr_2 being designed to saturate when its collector reaches a potential of -5V. The multiplier is similar to VCA_1 and VCA_2 , but in this case forms part of the main loop with the two integrators. Integrator gains of 3.3×10^4 are used and the first integrator is limited by zener diodes D_{10} and D_{11} . If the output swing of this integrator were allowed its full range of movement, the maximum input of the multiplier would be exceeded, causing the loop to become unstable and then "hung-up". The Q factor can be modified by adjusting R_{22} and theoretically when the wiper of this pot is at 0V there is no damping term, and the loop becomes unstable. This situation may or may not occur, it being dependent on component imperfections and the way in which the circuit is constructed.

It was decided that this filter should not become oscillatory at high Q factor settings. Thus to eliminate this possible state, R_{23} has been included, the value of which is chosen to make the loop non-oscillatory




Fig. 19. (a) Variable threshold effect in aligning the v.c.as. (b) Waveform envelopes from VA_1 and VC_1 products. (c) Effects of misaligning the Y "offset adjust". See text for full explanation.




Fig. 20. Circuit of the voltage controlled filter.

throughout its ranges. The v.c.f. can be modified externally so that it forms a low distortion oscillator, but this will be described later. Other synthesizers tend to prefer the use of low pass v.c.fs, and this is easily achieved by taking the output from IC₄, the low pass output. In fact there is no reason why the bandpass and the low-pass outputs should not be simultaneously available.

Filter alignment


Careful adjustments of presets R₄₂, R₄₄ and R₃₅ are required, because the multiplier is part of a loop that can easily become unstable, particularly at low values of gain.

Break link A, Fig. 20, and align the multiplier using the method described for VCA₁ and VCA₂. Note that there is no "gain preset" to adjust. Replace link A and

monitor the output of IC₅. This potential may need to be zeroed by adjusting R₃₅, this offset being particularly large when the bias control is set at minimum. If the multiplier has been carefully aligned to give a maximum dynamic range, then a range in centre frequency of about one octave can be expected. Note that the multiplier's gain should not quite reach zero or (even worse) pass through it and hence change sign, as both of these states are unstable.

The v.c.f. is now functional and can be used to perform a variety of operations. The more common uses are to filter inputs such as white noise, producing various effects similar to wind, rain, jet engines etc.

The v.c.f. can be used as a low distortion oscillator (Fig. 22a). The Q factor and the bias are set at maximum and the control pot R₁₈ (Fig. 20) is increased so that the filter



* as in fig. 22

Fig. 21. Transfer function of the square law generator in Fig. 20.

just oscillates. The v.c.f. can now be swept throughout its range, producing a sine wave of virtually constant amplitude and of variable frequency (a 9.5 to 1 range was obtained). There is a 90-degree phase difference between the low-pass and band-pass output, sine and cosine waveforms being simultaneously available.

The v.c.f. can also be used as a notch filter (Fig. 22b). To set up the mixer, use a sine wave input and set the v.c.f. to the same frequency, with the *Q* factor at maximum. By varying pots *VA*₁ and *VA*₂, the input

and the bandpass output can be made to cancel out. The "notch" can then be swept throughout the v.c.f.'s range. This technique can be used to examine the harmonic content of any signal that lies within the frequency range of the v.c.f.

The v.c.f. is also useable as a spectrum analyser, measuring energy per hertz versus frequency (Fig. 22c). However, this is no more than a demonstration piece, due to the narrow range. Also, the sweep time must be rather long if a "high" resolution (i.e. high *Q* factor) is required, and the constant

bandwidth makes interpretation of results difficult.

Audio mixer and summer/inverter

The audio mixer is a three channel virtual-earth mixer, each channel having its own attenuator and being a.c. coupled. A master volume control determines the overall signal level at the output (Fig. 23).

Also, two direct coupled virtual-earth mixers are provided (Fig. 24). These both have three inputs, two having a fixed gain of -1 and one of -10, and are used for




Fig. 22. Using the voltage controlled filter as (a) a low distortion oscillator (b) a notch filter and (c) a spectrum analyzer.




Fig. 23. Three-channel virtual-earth a.c. coupled mixer circuit.




Fig. 24. Direct coupled virtual-earth mixer.




Fig. 25. Circuit of the reverberation unit. Resistors marked * are high stability metal oxide types.




Fig. 26. Circuit of the exponential converter. Two converters are included in the synthesizer.

signal processing, such as inversion, summing or amplification.

Reverberation unit

The reverberation unit consists basically of three sections; the driver, the springline reverberation unit and the equalised pickup amplifier (Fig. 25). The springline reverberation unit used was the "H242" obtainable from Henry's Radio. This unit is moderately inexpensive, but suffers from a loss of high frequency reverberation, dropping considerably at about 4kHz. However, a useful response can be obtained—enough in fact for this unit to be used in one of the commercially available synthesizers.

By operating switch S₁, a choice of the input signal plus reverberation, or just reverberation is available. Thus the reverberation can be separately controlled, by using a v.c.a. and/or a v.c.f., as well as being manually controllable (R₃). To reduce any microphonic effects, the HR42 unit should be mounted on a pair of rubber pillars.

Exponential converter

This unit has an exponential transfer function of the form,

$$V_{out} = \exp(V_{in} + \text{constant})$$

The base-emitter junction of transistor Tr₃, Fig. 26, is voltage driven, the collector current being monitored. The relationship between V_{BE} and I_C is very nearly exponential, modified by the fact that the voltage drive is imperfect and the value of V_{CE} (Tr₃) is changing. The suitable working range for the base emitter voltage of Tr₃ is from 0.5V to about 0.7V, a width of only 200mV. This requires that Tr₃ is biased to a V_{BE} of about 0.5V and that the control voltage drive is suitably attenuated, the bias being preset by adjusting R₉. As two exponential converters are included in the synthesizer, both should be adjusted so that their responses are matched.

The need for an exponential transfer

function is twofold. One, the subjective response to volume can be loosely described as "logarithmic". And two, the subjective response to a change in frequency is governed by the ratio of the two frequencies. Thus, frequency generation should be an exponential function of the control signal, if the control, from say a set of keyboards, is to be considered musically useful.

The construction of the synthesizer will be completed with a description of the sample and hold function, noise sources, waveform generator and power supply. All the synthesizer functions will then be linked via the patch panel, keyboards and joystick control. Details of i.c. pin connections will be given and also examples of the synthesizer's use.

Correction

In Fig. 13, a resistor R₁₀ of value 1kΩ should be inserted between the +15V supply and zener D₃.

(To be concluded)

Reference

I. D. T. Smith, "Multivibrators with Seven-decade Range in Period", *Wireless World*, February 1972, pp. 85-86.

Announcements

"Sound Studios and Recording" and "Broadcast Sound Reproduction" are two courses to be run during the Autumn and Spring terms 1973-74 at the Polytechnic of North London, Department of Electronic and Communications Engineering, Holloway Road, London N7 8DB.

The University of London, Department of Extra-Mural Studies is to hold a course of 22 meetings plus four visits on "Hi-Fi and the Science of Sound" at Callowland Adult Education Centre, Watford on Thursdays, 7.15 p.m.-9.15 p.m., beginning 11th October.

Information on part-time courses in electronics — including an R.A.E. course — at Plymouth College of Further Education can be obtained from E.H. Farrar, Head of the Department of Electrical Engineering, College of Further Education, Keyham Annexe, Keyham Road, Devonport, Plymouth, Devon.


Surrey Electronics, 24 The High Street, Merstham, Redhill RH1 3EA are producing a glass fibre p.c. board for M. Hartley Jones' "Frequency Shifter for Howl Reduction" circuit published in the July issue. The board is 90 x 140mm with a gold plated edge connector to mate with a 12-way 0.15in socket.

A course of nine Tuesday evening lectures on the "Engineering of High Fidelity Sound Systems" will be given from 6.30 p.m. to 8.30 p.m. at Cambridge College of Arts and Technology, Department of Engineering and Building, Collier Road, Cambridge CB1 2AJ commencing on 9th October. Information is also available on an R.A.E. course and morse practice evening also commencing in October.

H.F. Predictions for September

Seasonal changes will result in generally improved conditions in propagation. Long periods of subnormal days are unlikely. Ionospheric conditions are more favourable for the North Atlantic path and trans-equator-routes should be consistently workable above 20 MHz.

The period of the last sunspot cycle corresponding to current conditions was 1962. The solar index from then on did not rise above the present value of 25 until the beginning of 1966; by the end of 1966 it had risen above 60. The trough of sunspot minimum now upon us can therefore be expected to last until 1977.



Circards — 9

Optoelectronics: devices and applications

Twinkle twinkle little led, how I wonder if you're dead

by J. Carruthers, J. H. Evans, J. Kinsler & P. Williams*


Three aspects of the link between light and electronic circuitry are considered in this article: detection and measurement of light, generation of light from an electrically operated source, and use of light as an intermediary in some electronic process. Of the wide array of optoelectronic devices available a small number cover a wide range of requirements. More specialized components, such as semiconductor lasers, photomultipliers, must be left to a later series.

The electronics industry is seeing a production and pricing pattern in one family of optoelectronic devices reminiscent of the t.t.l. war at its fiercest. Light-emitting diodes have changed from an r & d novelty to a consumer component with great rapidity and are already falling to a price level comparable with the transistors used to drive them. They will replace filament and neon lamps for a wide variety of applications and it is on their characteristics that this series concentrates as far as light generation is concerned.

Light-emitting diodes are p-n junctions governed by the same rules as silicon diodes. The choice of materials is decided by the spectrum of light required while the efficiency can depend critically on doping levels. The most common materials are gallium arsenide and gallium phosphide (and other compounds) (Figs 1 & 2) with a current requirement of 5 to 50mA for normal brightness. The resulting p.d. is in the range 1 to 2V (Fig. 3) making the diodes compatible with both linear and digital circuits. Relative intensity of the lamp is an almost linear function of current over a wide range of currents (Fig. 4) falling at higher temperatures.

Response of the human eye is greatest in the yellow/green region of the spectrum, and the gallium arsenide-phosphide devices (Fig. 1) — which emitters peak in the red — appear less bright than otherwise comparable-efficiency yellow diodes. Nonetheless, economies of scale dictate the use of the lower-cost red l.e.ds for most applications.

Emission in other parts of the electromagnetic spectrum is possible with suitable materials including the highly specialized



Figs. 1 & 2. Materials used in light-emitting diodes are chosen to give the desired colour. Although GaAsP diodes are of comparable efficiency to GaP diodes, they appear brighter because eye response is greater in that region (Fig. 1, left).




Fig. 3. Light-emitting diodes have a p.d. of 1 to 2V for normal brightness levels, making them compatible with both linear and digital circuits.




Fig. 4. Lamp intensity is a linear function of current, except at higher temperatures (broken line).


semiconductor lasers with a very narrow spectral response. Pulsed operation with low duty-cycle high-current pulses gives the highest efficiency with such devices, and they find application in optical communication systems.

Solid-state light-sensitive devices are based either on p-n junctions (photodiode, photovoltaic cell, phototransistors) or polycrystalline materials (CdS photoconductive cells). Light falling on a p-n junction if of short enough wavelength generates hole-electron pairs. Current flows if the p-n junction is short-circuited (Fig. 5) or connected to a low-resistance load;

current is proportional to the intensity of light falling on the junction, and the terminal p.d. for a silicon diode may be up to about 0.5V (Fig. 6).

A specialized form of photodiode, the photovoltaic cell, is used as a power source. Selenium, or more commonly now silicon, is the material used and the cells are arranged to have a high surface area to maximize their light catchment. Although having non-linear characteristics, the simple maximum-power-transfer theorem gives a first order answer for the optimum load (Fig. 7) i.e. that load which maximizes the output power is

*All with Paisley College of Technology.



Figs. 5 & 6. In light-sensitive devices based on a p-n junction, current is a linear function of light intensity falling on the junction (Fig. 5, left). Open-circuit voltage can be as high as 0.5V with silicon photodiodes (Fig. 6, right).




Fig. 7. For selenium or silicon photo voltaic diodes maximum power is delivered for a load given by open-circuit voltage divided by short-circuit current.




Fig. 8. Photoconductive cells using cadmium sulphide normally have a non-linear light intensity solidus current characteristic although the voltage-current curve is linear.




Fig. 9. Because the spectral response of cadmium sulphide cells matches eye response they are widely used in photographic applications.

given by $R_{opt} = V_{oc}/I_{sc}$. The theorem applies to linear systems but gives reasonable results for some non-linearity.

Further increase in load resistance or illumination makes for little extra p.d. as it becomes comparable with the p-n junction barrier potential. In a phototransistor the collector-base junction is illuminated and the transistor amplifies the resulting current. Currents of 10mA and more are possible but the speed of response is slower than for the diode alone when reverse biased. This latter mode is the fastest with a separate d.c. supply providing a high field to sweep the carriers out of the junction. The limiting effect on speed of response is often the RC time constant of the external circuit particularly as the currents are low, forcing the use of large resistors where large voltage swings are needed. Any voltage swing up to the supply voltage may be obtained provided that the supply voltage does not exceed the diode reverse-breakdown voltage.

Any other semiconductor device or circuit using a p-n junction may in principle be made into an optoelectronic device with suitable packaging. Thus photothyristors can be obtained which are fired by an optical pulse, though they are presently restricted to relatively low-current applications e.g. for firing a higher power thyristor. In this case the photothyristor needs to have high voltage breakdown characteristics but can be a low-power device supplying pulses of a few tens of mA to the power device.

Photo-Darlington and other transistor combinations are equally feasible where higher output currents are desired in linear circuits, but in many cases it is equally simple to combine a photodiode or phototransistor with other conventional transistors. M.o.s. devices are very useful in optoelectronic circuits, with the threshold voltage varied by the light intensity. By adapting the m.o.s. processes, complex circuits have been recently produced by i.c. manufacturers, to provide outputs capable of driving small relays and switching at preselected light intensity.

Cadmium sulphide photoconductive cells have a very high resistance in the absence of light, with the resistance

falling rapidly with increasing light intensity (Fig 8). At all light intensities the device has a linear V/I characteristic, and for some devices the variation of conductance with light is itself almost linear. As the spectral response of CdS cells closely matches that of the human eye (Fig 9), they are used in photographic equipment. These cells have to be used with some external power supply, a.c. or d.c., as they do not generate any power. The advantage is that the power controlled in the load can be large enough to operate a wide range of lamps and relays.

A powerful tool for designers made possible by recent development is the photon coupler. This is typically an 8-pin dual-in-line package containing a light-emitting-diode tightly coupled, optically, to a silicon phototransistor. There is no electrical connection and breakdown voltages between the two sections of several kilovolts have been achieved. Similarly the capacitance coupling is small, and these devices are ideal for transmitting signals between circuits where direct electrical connection is impossible or inadvisable. Examples of such situations include firing of thyristors from grounded source and coupling between digital systems where ground noise is a problem.

Optoelectronics has passed the healthy infant stage and is developing into a mature branch of engineering where the choice is wide enough to encourage all designers to extend their skills.

How to get Circards

Order a subscription by sending £9 (U.K. price; £10.50 elsewhere) for a series of ten sets to:

Circards
J. Rider
IPC Business Press Ltd (Sundry Sales)
40 Bowling Green Lane
London EC1R 0NE.

Specify which set your order should start with if not the current one. One set (normally 12 cards) costs £1 U.K. and £1.15 elsewhere, postage included.

Topics covered in Circards are

- 1 active filters
- 2 switching circuits (comparators & Schmitts)
- 3 waveform generators
- 4 a.c. measurement
- 5 audio circuits (equalizers, tone control, filters)
- 6 constant-current circuits
- 7 power amplifiers (classes A, B, C, D)
- 8 astable circuits
- 9 optoelectronics: devices and applications

Subsequent issues will cover micropower circuits, logic gate circuits, wideband amplifiers, alarm circuits, digital counters, pulse modulators. Introductory articles in *Wireless World* indicate availability of Circards, which are normally ready for despatch on the 1st of the month, and the Circard concept was outlined in the October issue, pages 469/70.

Industrial Electronics

5. Weighing systems

by Richard Graham

Having discussed the reasons for the development of electronic weighing and looked at load cells in broad outline (July issue, p.353), one is now in a position to examine complete systems, with their benefits and advantages over mechanical weighing equipment.

First, though, there is one more type of weighing transducer which should be mentioned — the class of cell employing the linear variable differential transformer as its measuring element. This device, which is exemplified by the Hunting Engineering weigh cell shown in Fig. 1, is used chiefly for low weights (milligrammes to a few kilogrammes) and, especially when temperature-compensated, is extremely accurate and stable. High-speed check-weighing is a typical application. The sketch shows a load-carrying platform, which moves vertically against a precision, temperature-compensated spring, being constrained to vertical movement by two flexural pivot arms of specially developed, temperature-stable, spring steel. Moving with the platform assembly is the l.v.d.t. armature, the coils remaining stationary. A dash-pot (not shown) prevents oscillation. The output of the cell is a.c., but precision rectifier units are obtainable to fit inside the cell and the input to the l.v.d.t. is provided by a highly stable high-frequency oscillator.

The output signal provided by most strain-gauge load cells is of the order of 2mV per volt applied and, depending on the manner in which multiple cells are connected together, the output provided to the indicating and processing circuitry is usually around 5-15mV, a.c. or d.c. Alternating signals have been the usual type, but many firms are now tending to use a direct-voltage input to the cells, preferring to deal with drifts in the electronics rather than with cross-talk and quadrature signals in a.c.-fed systems.

Display

The type of instrumentation chosen depends to some extent on the display method preferred. Two schools of thought exist on this matter of readout: the protagonists of large dial displays with pointers, and the digital faction. Both methods of weight display have strong

points in their favour, and each has its own most appropriate sphere of activity, in common with the displays of other types of measuring equipment. Those in favour of digital readout point out its lack of ambiguity and ease of comprehension, but it must be admitted that this obtains only when the reading is static. On the other hand, the proponents of pointers on dials assert that the information can be assimilated more easily and, in some cases, even without the need to actually read the numbers — the position, or angle, of the pointer giving an adequate indication. If a hopper or vat is filling or emptying, the pointer

will follow and the instantaneous weight, can be seen. In this situation a digital display would be uncomfortable, to say the least. It is perhaps true to say, however, that a digital display is more compatible with complete systems which must interface with peripheral equipment such as printers, batching controllers and computing devices. A typical arrangement would be as shown in Fig. 2.

Dial indicator. A typical dial indicator is shown diagrammatically in Fig. 3, where it shows the weight borne by four load cells. The outputs of the cells are combined and amplified to a workable level, and




Fig. 1. The Hunting l.v.d.t. weighing cell.




Fig. 2. A possible configuration of a complete weighing system with ancillary recording and batching equipment. The batching controller detects coincidence between the digital output of the display unit and a preset number, and controls the hopper output.

form one input to a comparator. The comparator output drives a motor which rotates the pointer over the dial. On the same shaft is a high-quality potentiometer which rotates with the pointer and which drives the other input of the comparator with the voltage on its wiper. As the amplified signal from the load cells at the comparator varies, the motor, pointer and potentiometer shaft rotate until the voltage at the other input to the comparator equals that from the load cells. The pointer now indicates the weight. In practice problems occur with hunting, as in any servo system, and much of the electronics is concerned with achieving adequate sensitivity while retaining stability.

Digital indication. In essence, the electronic design of a digital weight indicator is identical with that of a digital voltmeter and is simply concerned with analogue-to-digital conversion. Several different methods of doing this exist, and have been adequately described many times. Dual-ramp integrators, ladder networks and voltage-to-frequency converters are used, and the availability of integrated a-to-d converters must have a significant effect on this type of equipment. One of the advantages of this digital type of display is that the signal itself is now digitized and is available for transmission to other equipment.

Applications

Containers. Perhaps the most common application of load-cell measurement is the weighing of the contents of large silos or vats. In place of levers and knife-edges (and imagine the problems associated with mounting a 500-ton silo in such a manner) it is only necessary to sit the container on three or four load cells arranged round its perimeter, and the rest is electronics. It is, of course, necessary to ensure that the load applied to the cells is truly vertical and that side loads due to thermal expansion are eliminated by "floating" mountings, and for this reason it is sometimes found necessary to "hang" the container from tension cells rather than resting it on the compression type. Mechanical connections to the

container must be arranged to exert the minimum resistance to load.

Weighbridges. Anyone who has seen below the load platform of a large mechanical weighbridge will readily understand the attraction of load cells for this application. The elimination or reduction in depth of the pit and the replacement of immoderately dimensioned levers with insignificant load-cells is not the only attraction however; the signal from the cells is easily transmitted to remote displays without the use of further levers, and a digitized signal is already in a form for input to other equipment for process control or data-collection.

Cranes. The mechanical way of weighing the load suspended from the hook of a crane is to suspend a complete weighing machine "in series" with the load, complete with its dial. Electronically, the method is to interpose a load cell somewhere between the gantry and the load (the exact position varies with manufacturer) and to lead the signal away to a fixed control and display console. The loads suspended from crane hooks are, in some cases, highly inimical to delicate mechanisms; molten metal, for instance, exudes fumes and quantities of heat: load cells are readily rendered relatively immune to this kind of treatment. It is also possible to arrange for the cell to provide an alarm signal which will indicate overload.

Belt-weighing. This is an application which has caused a certain amount of hair-tearing and teeth-gnashing until quite recently, and the accuracies obtained are still not much better than a claimed 1%. The essential information delivered by a belt weigher is the rate of flow of material over the belt (weight of a given amount \times speed) and the total amount conveyed.

In one example of belt weigher, designed by Philips, the belt produces a train of pulses, the frequency of which corresponds to the belt speed, by means of a slotted disc moving in the inductive feedback loop of an oscillator. The pulses are converted into a varying voltage

level in a frequency discriminator, the level becoming the input to the load cells, which bear the weight of a fixed length of belt. The cell output, therefore, is representative of the speed of flow multiplied by the weight (rate of flow). This signal is amplified to drive an indicator and is also applied to a frequency-to-voltage converter, the output of which (another train of pulses) is counted and totalized, thereby providing the "total" output.

A design was produced some time ago by Richard Sutcliffe Ltd, using l.v.d.ts as weight transducers, mounted on spring cantilevers which bear the load and which deflect linearly. A tachogenerator driven by the belt supplies the primary drive for the l.v.d.ts, the output of which is, again, speed times weight. This is indicated, as before, and gives rate of flow information. Integration to obtain "total" readout is performed by a watt-hour type of meter driven by the rate output, which has a perforated disc, with lamp and photocell mounted on its shaft. The pulses produced by the turning of the disc are counted to give the total.

These four applications probably account for the majority of load-cell weighing equipment in use, although many are in use in diverse other fields of activity. In medicine, for instance, it is used to measure minute variations in the weight of patients undergoing kidney dialysis. In this application, small variations are imposed on a static weight which is many times larger (the weight of the bed and patient), a constraint which requires considerable stability and resolution in the electronics as only a small portion of the transducer output can be used.

In conclusion, it can be said that load-cell weighing offers convenience in the design, construction and maintenance of large systems, ease of interfacing with data-handling equipment and a ready means of obtaining remote or multiple displays. Cost saving becomes apparent in larger systems, but even in the smaller systems, cheapness is sometimes traded for the other attractions.




Fig. 3. A dial indicator in basic form. Batching can be carried out either by using the analogue signal or by causing the pointer to actuate photo-cell or inductive trips.

Manufacturers of load cells and systems

W. & T. Avery Ltd., Smethwick, Warley, Wores. 021-558 1112/2161.
 Bofors Electronics Ltd, Orchard House, Cherry Orchard Road, Croydon. 01-686 9487.
 Davy-United Instruments Ltd, Darnall Works, Sheffield 9. Sheffield 49971.
 Electromechanisms Ltd, 218/221 Bedford Avenue, Slough, Bucks. Slough 27242.
 G.E.C.-Elliott Automation Ltd., Elstree Way, Borehamwood, Herts. 01-953 2030.
 Guest International Ltd, Redlands, Coulsdon, Surrey CR3 2HT. 01-668 7141.
 Hunting Engineering Ltd, Electrocontrols Division, Dallas Road, Bedford. Bedford 60181.
 Mangood Ltd, Polo Fields Estate, Panteg, Pontypool, Mon. NP4 5YJ. 04955/55112.
 Pye Ether Ltd, (Philips), Caxton Way, Stevenage, Herts SG1 2DG. 0438 4422.
 Transducers (CEL) Ltd, Trafford Road, Reading, RG1 8JH. 0734 580166.

An Approach to Audio Amplifier Design

2. Measurement of characteristics, transient considerations, transient intermodulation index.

by J. R. Stuart,*B.Sc.(Eng), M.Sc., D.I.C., M.I.E.E.

In the first part of this series the discussion of an approach to the design of audio systems led to consideration of some of the characteristics that are currently measured for evaluation purposes, and to some that are not, but could be.

It is easiest of course to measure systems in terms of deviations from the specified ideal, and here I have concentrated on measurements made with standard equipment. Discussion of the design of audio amplifiers has so far isolated the following parameters for examination, and an attempt has been made to apply a level of significance to each.

Steady state:

1. Frequency/amplitude and phase responses.
2. Steady-state harmonic and intermodulation distortions.
3. Specific waveform distortions e.g. crossover, clipping.

Transient:

1. Rise-time.
2. Stability.
3. Transient intermodulation distortions (t.i.d.).

Necessarily any discussion of these parameters is intimately involved with negative feedback design, and I return to this subject in this article.

Sensitivity of the ear to changes of slope around zero. The two distortion effects which, apart from serious overloading, seem to be the most objectionable to the ear are crossover and transient intermodulation distortion. Both effects can arise in any class AB or class B amplifier. The causes of both types of distortion are totally different and the designer can handle them independently. In general the values of these distortions are also independent of each other, but in the case of t.i.d. the presence of crossover distortion due to the gain deviation in the crossover region could aggravate the situation. It may be significant that both the distortions appear to have a similar subjective effect—possibly as both create a slope error (usually around the zero point)—although it may be an indirect consequence of these.

Measurement of amplifier open loop characteristics

In conventionally designed negative feedback audio amplifiers, and particularly in

power amplifiers, the open loop frequency response is normally determined by lag compensation applied to the loop, although in some cases transistor characteristics may dominate, e.g. when output transistors are operated in the common-emitter mode.

The problem of measuring the open-loop transfer characteristic is that usually the a.c. feedback loop is associated with d.c. feedback, and thus d.c. feedback is essential to the correct operation of the amplifier; also the measurement technique should not substantially alter the compensations and working conditions from those of closed-loop operation.

Figs. 11(a) and (b) show two common circuit configurations with all the usual lead and lag combinations. The technique proposed for measuring the forward characteristic is to divide R_f into three elements as shown in Fig. 11(c), and to use two by-pass tantalum capacitors C_a whose value is such that the attenuation between points A and B at the measuring frequency is at least 20dB more than the measured gain. As power amplifiers normally have a closed-loop gain of at least 20dB, the error in this measurement is likely to be less than 2dB. Note that this technique maintains fairly well the impedances at points A and B and

*Lecson Audio Ltd




Fig. 11 (a), (b). Two typical amplifier configurations used to establish methods of measuring open and closed loop circuit performance. (c) Substitution of feedback resistor R_f by test jig circuit.

does not interfere with the conservative compensation of C_x or the loading of C_y .

This connection, with careful attention paid to stray capacitances, will allow the measurement of open-loop gain and phase (compensated and uncompensated) and open-loop distortion.

Some transient considerations

At the end of the first part in this series, a list of conclusions leading to the avoidance of t.i.d. were given in terms of negative feedback-loop design considerations. To obtain the best reproduction from an amplifier, careful attention has to be paid to other transient distortion mechanisms which include waveform distortions like ringing and overshoot and low-frequency rumble effects.

One very interesting property of negative feedback loops is that whereas usually their action is to reduce distortion appearing at the output, waveforms inside the loop may be subject to very large amounts of distortion—much more than in the open-loop condition. I have quite often measured distortions within a loop $1000\times$ the output distortion when only 30dB of feedback is being used.

Low frequency transient effects can then arise if this distorted signal is able to change the d.c. working points of any stage in the amplifier, e.g. modify the average current in a decoupled stage as in Fig. 12. This is further aggravated, or may be induced, if the design allows the application of more d.c. than a.c. feedback. This is commonly done in an attempt to achieve an apparently high d.c. stability. In practice, small differences in the gain of the two halves of an amplifier can result in large very low frequency error signals being generated which can cause clipping or aggravate other distortions. The effect, which can be considered as a dynamic offset, is shown up by tone-burst testing.

Transient response, distortion and stability. The synthesis of a successful system, and of single-loop forward characteristics, relies heavily on judgements made in balancing the above three characteristics.

Curve 1 in fig. 13 is an uncompensated amplifier response shown as a Bode plot. Were this amplifier connected for a closed-loop gain of GdB it would be unstable. This is made more clear in the $j\omega$ -plane Nyquist plot of Fig. 14.

There are three important ways in which this amplifier may be stabilised. The first is to very conservatively compensate it to achieve unconditional stability by rolling off the gain at a very controlled -20dB/decade . This makes it necessary to introduce a dominant pole, sufficiently low in frequency, say at ω_c , to ensure that either the loop gain $A\beta$ has fallen to 0dB by the second open-loop breakpoint ω_β , or that it is possible to add some lead compensation to the original response—or the feedback network—to allow a little less drastic compensation. The results of these suggestions are illustrated as curves 2 and 3 in Figs. 13 and 14. One implication is that unless the designer can find more gain in the forward characteristic $A(s)$, or is prepared to add a

Fig. 12. Typical d.c. coupled amplifier.




Fig. 13. Bode plot of a typical uncompensated amplifier.




Fig. 14. Nyquist plot of amplifier example shown in Fig. 13.





Fig. 15. Loop gain characteristic of a marginally stable amplifier.






Fig. 16. An approximation to the ideal Bode loop gain characteristic.

zero to the feedback network at ω_β , then unconditional stability can only be achieved by accepting that the feedback will become inoperative at ω_β .

An alternative method is to accept a marginal stability and hence permit a loop gain characteristic $A(j\omega), \beta(j\omega)$ like that shown in Fig. 15. A characteristic of marginal stability is that such an amplifier may have a transient response which exhibits an overshoot or an oscillatory mode, and a peaking in the frequency response.

The third technique, of course, is to approximate to Bode's ideal loop gain characteristic as shown in Fig. 16. The first two cases will now be considered:

Unconditional stability. An amplifier whose ideal forward characteristic (see Fig. 16)

$$A(s) = A_o \cdot \frac{a_o}{s+a}$$

is connected as a feedback amplifier where $\beta(s) = \text{constant } \beta$. The closed loop gain $G(s)$ is given by

$$G(s) = \frac{aA_o}{s+a(1+A_o\beta)} \quad (1)$$

showing that the low frequency gain is reduced by the factor $(1+A_o\beta)$, along with noise and steady distortions, while the bandwidth has been increased to a $(1+A_o\beta)$. Here aA_o is the gain bandwidth product.

The response of this circuit to a step function, value p , is given by

$$o(s) = \frac{p}{s} \cdot \frac{aA_o}{s+a(1+A_o\beta)}$$

This gives by inverse Laplace transformation the output $o(t)$.

$$o(t) = \frac{pA_o}{1+A_o\beta} [1 - \exp-(a(1+A_o\beta)t)]$$

These are sketched in Fig. 17 along with the impulse response $\dot{o}(t)$ where $\dot{o}(t) = g(t)$. It can be seen that no overshoot or ringing is possible in this circuit, and this kind of step response is one which many audio designers try to achieve.

Marginal stability. This is the condition where $A(j\omega), \beta(j\omega)$ is arranged so that when $|A(j\omega), \beta(j\omega)| = 1$ there exists a phase margin, θ , such that $\pi/2 > \theta > 0$. (Note: for conditional stability the relationship could be $\pi/2 > \theta > -\pi/2$.)

The phase margin θ is determined from $\theta = \pi - \angle A(j\omega_1), \beta(j\omega_1)$. The most general open-loop response that can be used successfully for closed-loop gains ≥ 1 is the two-pole system shown in Fig. 15 and the open-loop response

$$A(s) = \frac{A_o \cdot a \cdot b}{(s+a)(s+b)}$$

When the loop is closed this gives the form:

$$G(s) = \frac{A_o \cdot a \cdot b}{s^2 + s(a+b) + ab(1+A_o\beta)} \quad (2)$$

The effect of negative feedback on the natural frequencies of this network is shown in the s -plane plot of Fig. 18. Notice that with sufficient feedback the two poles coincide at $s_o = \sqrt{(1+A_o\beta)ab}$.




Fig. 17. Response of an amplifier with ideal Bode plot of Fig. 15, to a step function.




Fig. 18. An s -plane plot showing the effect of negative feedback on the natural frequencies of the two pole system shown in Fig. 17.




Fig. 19. The peaking of frequency response as a result of the application of more feedback which, in turn, reduces damping.

The damping factor

$$\delta = \frac{1}{2Q} = \frac{a+b}{2\sqrt{(1+A_o\beta)ab}}$$

Note that the damping is inversely proportional to $\sqrt{1+A_o\beta}$ so, as would be expected, the application of more and more feedback reduces the damping, increases the peak in the closed-loop response and introduces an oscillatory mode to the step response for $\delta < 1$,* see Fig. 19 curves. This arises because the roots of the denominator of equation 2 become imaginary. Commonly used criteria to determine whether the transient response of such a circuit will be adequate are gain and phase margins, and the amount of peaking shown in the steady-state frequency response. To some extent, the values chosen depend upon gain and phase stability, and variability within the design, but rules of thumb suggest that $\delta \geq 1/\sqrt{2} \geq Q$, and suggest gain and phase margins of 15dB and 60°.

Reactive load conditions. One problem in the design of an audio power amplifier is that it may be expected to drive loads varying from pure inductance through resistance to pure capacitance, and may also be loaded with a tuned circuit.

So far as stability is concerned the inductive load does not concern us much† as it is assumed that the open-loop transfer characteristics referred to are measured or calculated under resistive loading.

Loading a practical amplifier with a pure capacitance, to simulate perhaps electrostatic loading, will result in the introduction of a new pole in the transfer function at ω_n . It can be seen from Fig. 20(a) that the effect of this on an unconditionally stable amplifier is that for $\omega_n, \omega_{n1} \ll \omega_a(1+A_o\beta)$ a ringing may appear in the closed loop step response, whereas little change will occur in the step response if $\omega_{n1} > \omega_a(1+A_o\beta)$.

In an amplifier of 2nd order response working into a resistive load, the effect of adding the pole $\omega_n < \omega_x$ can be to make the amplifier unstable; or for $\omega_n > \omega_x$ little change should be noted. See Fig. 20(b).

Capacitive load condition. One technique often used to ensure stability and/or freedom from overshoot into capacitive loads is to deliberately over compensate the open-loop response so that at no time does ω_n fall below the closed-loop cut-off frequency. This technique is unnecessarily punitive and will obviously result in a lower open-loop break-point.

Another technique is to modify the output circuit so that although ω_n can be $\ll \omega_x$, the change to the open-loop response is small, ensuring that at $|A(j\omega)| = \beta^{-1}$ the slope of $A(j\omega)$ is the same as in the resistive termination. Such a modification involves a resistor and inductor in series with the output. This is shown in Fig. 20(c).

The last technique to take account of this type of loading involves adding a zero to the

Fig. 20. Effect on single pole (a) and two pole (b) amplifiers of driving into a purely capacitive load. (c) Output circuit modification to improve stability with a capacitive load.




Fig. 21. Loop gain and phase characteristics of single pole amplifier.





Fig. 22. The projected effect on distortion of the amplifier loop characteristic.



*Critical damping

†Note: the inductive load is important when considering low frequency design.

feedback network; hence $\beta(s)$ is of the form:

$$\beta(s) = \frac{s+m}{m} \cdot \beta$$

This of course has the effect of adding a zero to the closed-loop transmission, and if m is chosen to be equal to ω_n for the largest value of capacitor load envisaged, say $2\mu\text{F}$, then the transient response and stability will not suffer provided $\omega_n > 50\text{kHz}$ (for an audio amplifier).

Phase response

Neglecting for the moment the example of an amplifier with a second order open-loop response, let us consider the responses of the

single pole example shown in Fig. 21 having its pole at ω_x . If we consider the closed-loop response of the system we can see that this also described the closed-loop responses where

$$\omega_o(\text{closed loop}) = (1 + A_o\beta)\omega_o$$

The specification for a high quality amplifier quoted in the first part of this series contained the suggestion that the amplifier as a whole should have phase tolerances of $\pm 10^\circ$. Given that a passive filter was shown to be desirable in the pre-amplifier, for transient distortion reasons, and that this will introduce a phase lag, it can be seen that the permissible phase shift in any one stage is small, and ideally -2°

at 20kHz in a typical system. Note that this and the requirements for stability apply equally to the low frequency design. An amplifier with a response of the form

$$G(s) = \frac{A_o \cdot a}{s + a(1 + A_o\beta)}$$

will have a phase shift of -2° at 20kHz for $\omega_x = \sin \omega_a(1 + A_o\beta) = 570\text{kHz}$ and -6° for $\omega_x = 200\text{kHz}$.

This result suggests that the phase requirement places fairly strict bounds on the gain-bandwidth product for any design; e.g., if we wish to have a phase lag of -2° at 20kHz and to use 40dB of feedback then the open-loop pole $\omega_a = 5.7\text{kHz min}$.

In the second order case the requirement for a given phase lag will be a greater open-loop -3dB bandwidth due to the more rapid open-loop phase shifts.

Distortion reduction

A point was made in the first part of this series that a weighted steady-state distortion of 0.1% at any frequency in the audio band was a good and sufficient goal at which to aim. In addition, general discussion of the mechanism of negative feedback loops produced three points:

1. The steady-state distortions, amenable to reduction by feedback, are not reduced for a signal of frequency ω_1 by the amount $(1 + A(j\omega_1)\beta(j\omega_1))$ but by an amount related to $(1 + A(jn\omega_1)\beta(jn\omega_1))$ for n , integer $\geq +2$. This accounts for any reduction of loop gain at harmonic frequencies and phase shifts at these frequencies.
2. The weighted steady distortions in an amplifier where $A(j\omega) = \text{constant}$, $\omega = 0$ to $\pm\infty$, will only reduce by the amount $(1 + A\beta)$ if the distortions are already small, so that $A\beta(v)$ has small limits; otherwise not only will the t.h.d. not reduce, but the weighted t.h.d. can be expected to reduce less, due to a changed harmonic structure being introduced.
3. It is likely that negative feedback will reduce the maximum unclipped output. Fig. 22 illustrates the expected effect of the loop characteristic on the distortion of an amplifier. Obviously the only two points the designer must carefully consider are the extremes of the range—as would be expected. The arguments of course apply equally to intermodulation distortion.

It can be seen that for any particular specification, e.g. $\gt 0.1\%$ weighted t.h.d. in the band 20Hz-22kHz, the open-loop gain and phase response will be an important consideration, a wider bandwidth giving a neater solution to the t.h.d. specification and making it necessary to obtain a given distortion characteristic, to use less low frequency gain and hence achieve better stability, and phase response.

System transient analysis

In analysing the transient performance of a system, that is pre-amplifier plus power amplifier, the power amplifier has been considered as having a first order open-loop response—or at least a second order response where $\omega_b \gg \omega_a$ (Fig. 15). This has been done for simplicity; however, the conclusions are general. Three conditions have been envisaged:




Fig. 23. Values of $\epsilon(\tau)$ plotted against damping factor for three different frequency response conditions.




Fig. 24. Model of performance as a function of input slew rate.




Fig. 25. Test signal used to probe incremental gain.

1. Pre-amplifier response declines at -6dB/octave above ω_1 .
 2. Pre-amplifier response declines at -12dB/octave above ω_1 .
 3. Pre-amplifier response is boosted by +6dB/octave above ω_2 and decays at -6dB/octave above ω_1 .
- In each case the power amplifier has an open-loop pole at ω_o and has a response

$$\frac{e_o}{e_1} = G(s) = \frac{A \cdot \omega_o}{s + \omega_o(1 + A\beta)}$$

The error signal ϵ is described by the relationship

$$\frac{\epsilon}{e_1} = K(s) = \frac{s + \omega_o}{s + \omega_o(1 + A\beta)}$$

Put $(1 + A\beta) = \alpha$ in case 1, then, the total input-output response is given by:

$$H(s) = A \cdot \frac{\omega_1}{(s + \omega_1)} \cdot \frac{\omega_o}{(s + \alpha\omega_o)}$$

and in response to step function value p , the output is given by:

$$e_o(s) = \frac{p}{s} \cdot \frac{A\omega_o\omega_1}{(s + \omega_1)(s + \alpha\omega_o)}$$

and the error signal:

$$\epsilon(s) = \frac{p}{s} \cdot \frac{(s + \omega_o)}{(s + \omega_o\alpha)} \cdot \frac{\omega_1}{s + \omega_1}$$

Taking partial fractions we deduce that

$$\frac{\epsilon(s)}{p} = \frac{1}{\alpha s} + \frac{\omega_1(1-\alpha)}{\alpha(\omega_o\alpha - \omega_1) [s + \omega_o\alpha]} + \frac{\omega_1 - \omega_o}{(\omega_o\alpha - \omega_1) [s + \omega_1]}$$

Setting $\omega_o/\omega_1 = \delta$ and $\omega_1 t = \tau$ and using the reverse Laplace transform we get

$$\epsilon(\tau) = \frac{p}{\alpha} \left[1 + \frac{(1-\alpha)}{(\alpha\delta - 1)} \cdot \exp(-\delta\alpha\tau) - \frac{\alpha(1-\delta)}{(1-\alpha\delta)} \exp(-\tau) \right] \quad (5)$$

By differentiating $\epsilon(\tau)$ and setting this signal to zero we get the stationary points. Other than at $\tau = 0, \infty$ there is a value of τ for which $\epsilon(\tau)$ is a maximum given by:

$$\tau = \frac{1}{(1-\alpha\delta)} \ln \frac{(-\delta)}{\delta(\alpha-1)} \quad (6)$$

The value of $\epsilon(\tau)$ for various values of α and δ are plotted in Fig. 23. A similar analysis shows for case 2,

$$\epsilon_2(\tau) = \frac{p}{\alpha} \left[1 + \frac{(1-\alpha)}{(1-\alpha\delta)} \exp(-\alpha\delta\tau) + \left\{ (\delta-1)\tau - \frac{1-\delta(2-\alpha\delta)}{(1-\alpha\delta)} \right\} \frac{\alpha}{1-\alpha\delta} \exp(-\tau) \right] \quad (7)$$

and for case 3

$$\epsilon_3(\tau) = \frac{p}{\alpha} \left[1 + \frac{(1-\alpha)}{(1-\alpha\delta)} \cdot \frac{(\alpha\delta - \phi)}{\phi(1-\alpha\delta)} \right] \exp(-\alpha\delta\tau) + \left\{ (\delta-1)(\phi-1) - \phi(\delta\phi-1) + \frac{(\delta-1)(\phi-1)}{(1-\alpha\delta)} \right\} \frac{\alpha}{\phi(1-\alpha\delta)} \exp(-\tau)$$

where $\phi = \omega_2/\omega_1$.

The values of $\epsilon(\tau)$ are also shown for cases 2 and 3 in Fig. 23. It is clear that the form of $\epsilon(\tau)$ allows quite large overshoots to occur in the feedback loop and these can have a peak value much larger than the steady state error signal for the highest frequency ω_1 . It is interesting to consider the reason for this, and once again the surprise can be traced back to the classical feedback model. In the open-loop amplifier, the time for the output to rise from 10% to 90% of the final value was given as $0.35/2\pi\omega_o$ sec. Now when the loop is closed, to achieve the original output level, instead of this condition, the effective input signal is increased in an attempt to increase the output slew-rate.

The classical theory breaks down here, because in a practical amplifier the following conditions will be obtained:




Fig. 26. Basic amplifier design produced to test transient distortion analysis.

- The amplifier will exhibit a time delay.
- The output slew-rate will not increase indefinitely in response to increased input signal level.
- In practice there will be a maximum slewing rate for the amplifier (S_{out} volts/sec) which is determined by the internal time constants and overload margins. At this point the relationship $S_{out} = AS$ totally breaks down.

This amounts to the feedback network being totally inoperative for a portion of the open-loop rise-time of the amplifier, which can in turn have three effects:

- The incremental gain of the amplifier is not controlled during this time.
- The resulting overshoot in $a(\tau)$ can overload the early stages of the amplifier, resulting in a 100% intermodulation during the rise time.
- The overshoot may, depending on the amplifier recovery characteristics, cause the amplifier to latch-up, resulting in an inter-modulation burst much longer than the rise-time. The burst is commonly several milliseconds in many commercial amplifiers, particularly if an amount of treble boost is applied as in case 3.

The transient distortion need not produce 100% i.m.d. since amplifiers tend to overload progressively. Fig. 24 is a model of performance as a function of the input slew rate S_{in} . The incremental gain will, of course, indicate the amplifier's ability to handle any other signal present before, during and after the transient. A useful test signal to probe this is shown in Fig. 25.

It will be remembered that the sensitivity of the ear to changes of slope was discussed earlier. It seems that there will be an equal likelihood of response to gain deviation in the vicinity of a transient as to disappearance of the incremental gain.

Transient intermodulation index

Transient distortion can be analysed statistically, the likelihood of such a distortion arising being dependent upon the probability that an overshoot will arise within the loop sufficient to cause a significant gain deviation. This can in turn be related to the product of two parameters, the transient intermodulation index (t.i.i.), which describes the maximum size of overshoot expected from the previous analysis, and the overload margins in the amplifier.

The transient intermodulation index has been proposed here to give a rough idea of the amplifier's susceptibility to this form of trouble, and has been normalised so that an amplifier considered to have a good quality, judged by listening experiments and having, say, 20kHz open-loop bandwidth with 40dB of feedback, is normalized to 0.1.

From the analysis it can be seen that the size of an overshoot could be approximately proportioned to F/δ where F is the feedback factor. The important thing to note here is that δ refers the signal bandwidth to the open-loop bandwidth and so this relationship can be applied to any stage in the amplifier.

An example: To test the analysis an amplifier was built as shown in Fig. 26. It is a very common circuit and there is nothing

Fig. 27. Graphical summary of steady state performance of amplifier design shown in Fig. 26.




Fig. 28. Transient response to the test amplifier to square wave test signals for a resistive 8 load and a 1 F capacitive load.





Fig. 29. Effect of combining a sine or square wave to demonstrate t.i.i.

special about the way the forward compensation has been applied. The dominant open-loop pole is set by C_1 and, as can be seen from the steady-state summaries in Fig. 27, the performance is nothing special. However, it is typical of the configuration which, due to device limitations, can never achieve the ultimate quality of alternative circuits.

Two experiments were carried out and in each case the input signal was passed through a network with a single pole at 44kHz. In the first a square wave was applied at 1kHz p.r.f. and 2μs rise and fall time and the error signal was measured for

20V peak to peak output. This waveform is shown in Fig. 28. Note that the overshoot is 350 x the steady-state error in the negative direction and that in the positive direction the error is clipped at 70 x the steady-state error.

Secondly, a 20kHz sine wave of 1V peak to peak was added to the input signal and, as Fig. 29 shows, a transient distortion occurred, which was considerably aggravated for both positive and negative excursions by the addition of a capacitive load.

Now obviously this can be much improved by increasing the overload margins of the first stage. Even when the situation



Listen. Philips have changed hiss into hush.

Whether the source of music is open-reel tape or cassette, hiss can be annoying during quiet passages.

The Dynamic Noise Limiter has been specially developed by Philips to solve this problem for you. Its ingenious circuits operate only during silent or quiet passages and when it can't be detrimental to the music. The DNL suppresses hiss without reducing the natural brilliance of reproduction. In fact it has the effect of actually increasing signal-to-noise ratio.


You connect the DNL unit N6720 between signal source and amplifier. It has 5-pin DIN 180° input and output sockets.

For a brochure on all Philips audio and recording accessories, write to Philips Electrical Ltd., Department SP, Century House, Shaftesbury Avenue, London WC2H 8AS.



PHILIPS
Simply years ahead.

WW—091 FOR FURTHER DETAILS



The big volume linear source

If you're in computers or consumer products, industrial or military, communications or automotive, one big linear source is really 'good news'.

With more than 40 new ICs in 1972 (and we don't include package or spec. variations), and many more to come this year, our commitment to linear is real — and complete:—

Voltage regulators. including the exciting new MC 1568, one of 7 unique Motorola designs, and the MC 7800 CP3 terminal series.

Op Amps. like the MC 3401 and MC 1456.

Multipliers. Motorola's are monolithic.

Interface IC's. A big range of sense amps, line drivers and receivers.

Consumer IC's. We're market leaders in US...

Comparators. such as MC 3302 quad.

Monolithic D/A and A/D converters. 6 and 8 bit, including the new 8 bit MC 1508.

You want quick delivery? Every device in this great and growing range is 'made in Europe' — and stocked by our distributors in Europe.

So telephone your Motorola distributor today. He's ready to deliver the big volume source to your doorstep.



MOTOROLA Semiconductors

Motorola Semiconductors Ltd., York House, Empire Way, Wembley, Middlesex. Telephone: 01-903 0944.
European manufacturing facilities at Toulouse and East Kilbride. Distributors: Celdis Ltd., Reading,
GDS(Sales) Ltd., Slough, Jermyn Industries, Sevenoaks, A. M. Lock & Co. Ltd., Oldham, Semicomps Ltd., Alperton.

WW—092 FOR FURTHER DETAILS

Experiments with operational amplifiers

Conversions between time and other variables

by G. B. Clayton,* B.Sc., F.Inst. P.

In instrumentation systems it is sometimes necessary to change a signal from one form into another. Conversions which involve time, for example voltage to time conversion or time to voltage conversion, can be performed using an operational integrator as the basis of the conversion circuit. The experimental circuits presented here show some of the ways in which operational amplifiers can be used for time conversions.

13. Pulse height to time conversion

A circuit which can be used to produce a time interval proportional to the height of a positive input pulse is shown in Fig. 13.1.

The amplifier is connected as an integrator. In the absence of an input pulse the output voltage of the amplifier is held at ap-

proximately zero by the negative feedback through diode D_3 . A positive input pulse causes capacitors C_1 and C_2 to charge, the output of the amplifier steps down and diode D_3 is reverse biased. If V_p is the height of the input pulse the output steps down by an amount $V_p \frac{C_1}{C_2}$. This output step is discharged at the integrator at a rate $\frac{E_{ref}}{C_2 R}$ volts/sec. The time for the output to charge up back to zero is thus

$$t = \frac{V_p \frac{C_1}{C_2}}{\frac{E_{ref}}{C_2 R}} = \frac{C_1 R}{E_{ref}} \cdot V_p$$

This time period is directly proportional to the height of the input pulse. Scaling may be set by choice of E_{ref} .

Circuit performance may be checked by applying input pulses of different amplitude and measuring charging times by observation of oscilloscope waveforms. The action of the circuit is illustrated by the typical waveforms in Fig. 13.2, which show the circuit response for input pulses of two different heights.




Fig. 14.1 Circuit for time to voltage conversion.

*Department of Physics, Liverpool Polytechnic




Fig. 13.1 Conversion of pulse height to time.




Fig. 13.2 Action of Fig. 13.1 circuit illustrated by input pulses of different heights. Pulse waveforms, 10V/div; integrator outputs, 1V/div; horizontal scale 1ms/div.




Fig. 14.2 Action of Fig. 14.1 circuit illustrated by negative-going rectangular-pulse gating signals of different widths. Rectangular waves, 5V/div.; ramp waveforms 2V/div.; horizontal scale 2ms/div.

Typical waveforms which may be observed in order to investigate the action of the circuit are shown in Fig. 14.2. The effect of two different gating periods is illustrated.

15. D.C. voltage to time conversion

A second amplifier, acting as a comparator, added to the circuit of Fig. 13.1 gives a system which may be used to produce a gate waveform of time period proportional to the magnitude of a d.c. voltage. The arrangement is illustrated in Fig. 15.1.

Positive reset pulses set the integrator output to approximately zero, and cause the comparator output to switch to its posi-

where E_o is the amplitude of the output ramp and t is the time period of the gating signal.

$$E_o = \frac{E_{ref}}{CR} \cdot t$$




Fig. 15.1 D.C. voltage to time conversion, achieved by adding a comparator to Fig. 13.1 circuit.




Fig. 15.2 Action of Fig. 15.1 circuit. Top trace shows positive reset pulses; middle trace, integrator output; bottom trace, comparator output. Vertical scale, 10V/div.; horizontal scale, 2ms/div.

tive level. At the end of a reset pulse the integrator output runs up linearly at a rate determined by E_{ref} and the integrator time constant CR . The comparator senses when the integrator output reaches a voltage level which is equal to the input voltage applied to the non phase inverting input terminal of the comparator, and the comparator output then switches to its negative saturation level. The time period of the positive part of the comparator output waveform is proportional to the input voltage, and is determined by the relationship

$$t = \frac{CR}{E_{ref}} \cdot e_i$$

Typical waveforms which may be observed in order to examine the action of the circuit are shown in Fig. 15.2. Accuracy and linearity of conversion can be checked by measuring the time periods for a range of values of e_i .

Note that the time period is proportional to the ratio e_i/E_{ref} so that if the reference voltage is replaced by a second input voltage the circuit then gives a time conversion proportional to the ratio of two input voltages.

In Fig. 15.1 the voltage e_i must be positive; it must also, of course, be less than the integrator positive output voltage swing. A circuit which provides conversion of either positive or negative input signals can be made if the integrator output is applied to two comparators. One comparator is used

to sense when the integrator output passes through zero, the other senses when it passes through a value equal to the input voltage. The time period between the transitions of the two comparators is then proportional to the magnitude of the input voltage. The sign of the input voltage is indicated by which comparator makes a transition first. Diode D_2 must be removed from the integrator to allow its output to be reset to a negative value. A system of this kind can be used as a basis for a simple ramp type d.v.m., the comparator transitions being used to generate start and stop pulses which are applied to a digital timer system.

Raising transmitter valve dissipation

In transmitting valves the maximum dissipation power of smooth, thin-walled copper anodes is in the region of 120 W/cm² and this no longer meets present-day design requirements. The Swiss firm Brown Boveri has recently developed a valve with a light-weight anode which is capable of dissipating over 350W/cm². This figure has been achieved by combining a number of different surface structures in the anode.

Normally the anodes of vapour-cooled valves are provided with structures such as fins and corrugations. The main task of the fins is to provide heat transfer into the water as the anode load increases, while a vapour film forms between them. The maximum dissipation power of a valve with this type of anode can be varied through a wide range by changing its

geometrical configuration (e.g. wall thickness, height of ribs, ratio of fin width to space between fins). The maximum dissipation power of light-weight structures with short fins and with a ratio of fin width to fin spacing of about 1:1 is in the region of 250W/cm². Brown Boveri made an attempt to raise this to over 300W/cm² by treatment of the anode surface in the gaps between the fins without having to use larger and bulkier fin configurations. Investigations were made into the effects of various small and micro-structures on the maximum dissipation power of a smooth, thin-walled copper anode. A transmitter triode with an output of up to 65kW was used as the specimen.

A rough surface increases heat transfer into the water because of improved bubble formation and higher bubble frequency. The maximum dissipation power also rises with increased surface roughness, so the dissipation was increased by 8 to 20% by means of sandblasting (depending on the grain size of the sand used). Highly porous surfaces can be produced by electrolytic plating processes. The maximum dissipation power of an anode plated with a 1mm thick layer of porous copper with an average pore diameter of several tenths of a millimetre was found to be 40% higher than that of a bare anode.

Investigations were also made of the long term behaviour of the maximum dissipation power of a valve, especially after a period of storage. A test was done on a tube with a sandblasted anode surface. Its maximum dissipation power was measured at intervals of several days during storage in normal atmosphere and was found to increase by about 20%. The increase is thought to be due to improved wetting, resulting from advanced oxidation at the copper surface.

The provision of fine structures of the order of millimetres at the anode surface also increases the maximum dissipation power in a similar fashion to micro-structures such as surface roughness or porosity. To investigate the effects of these fine structures, various cylindrical wire-mesh screens of different mesh sizes and wire thicknesses were fixed to the anode surface. A mesh configuration with a mesh width of 2mm enabled the maximum dissipation power to be raised by about 50% over anodes with smooth surfaces. The mesh was also fixed to the anode surface by a copper plating process to improve physical contact. With the anode surface thus prepared, and adding a porous copper layer, the maximum dissipation power was raised to 210W/cm². This is about twice that achieved with a bare anode and corresponds to the order of magnitude of the maximum dissipation power of finned anodes. A combined structure was made by fitting strips of wire mesh between the fins of a sandblasted double-fin anode and holding them in place by copper electroplating. The maximum dissipation power of this anode with an untreated smooth surface was 250W/cm² but, after the surface structure had been modified, this figure was found to have risen to 360W/cm².

Letters to the Editor

The Editor does not necessarily endorse opinions expressed by his correspondents

Frequency shift howl suppressor

I was interested in the description of the frequency shifter given by Dr Hartley Jones in the July issue of *Wireless World*, but there are a couple of points raised by the author with which I disagree.

Over the twelve years or so during which I have had occasion to use such a device I have not found any advantage in increasing the frequency shift by more than three hertz, two being often the optimum, and this has applied even in halls of moderate size. If more shift than this is employed the permissible degree of gain was not increased and the change in pitch in the reverberant sound was very obvious even on speech and quite unacceptable on music.

A further point is that the ear appears to accept a decreasing pitch fairly readily but regards an ascending one as definitely artificial and objectionable, even though the amount of shift is the same.

Finally, users should not always count on obtaining as great an improvement in gain as indicated, for with a well designed public address system I have found the possible gain increase when using a frequency shifter to be as low as 4dB. The use of the device does, however, considerably reduce the degree of coloration near howl-round.

H. D. Harwood,
B.B.C. Research Department,
Tadworth,
Surrey.

Audio amplifier design

I have read the further letter from Mr Stuart of Lecson Audio in your August issue, and I am somewhat surprised that so much of conjecture or personal opinion should be stated by Mr Stuart as matters of established fact.

However, to take the main points on which Mr Stuart has thrown down the gauntlet:

1. Transient intermodulation distortion

It has been known by audio amplifier designers for very many years that unsatisfactory results were frequently obtained if the input bandwidth to the power amplifier was excessive, and more recently this has focused attention on

the manner in which the amplifier responds to a transient input. A part of this problem was formerly analysed by Mr Ojala in his paper presented in 1970, and he coined the above term for this problem.

I will try to summarize Mr Ojala's argument with reference to the accompanying diagram.

If we take a feedback amplifier which consists of a chain of separate op-amp elements (for convenience I have shown three) of which, say, amplifier 3 is arranged to have the slowest response, and we apply a step-function input of sufficiently rapid rise time and sufficient magnitude, amplifier 1 will overload and produce severe intermodulation distortion in the transmitted signal, even when the magnitude of the input signal is within the normal input range of the amplifier, because the propagation delay of the main feedback loop is too long for the feedback to be effective in diminishing the magnitude of the applied signal — as seen by the first amplifier stage — during the transient condition.

This is a matter of practical concern in the design of transistor audio amplifiers, since the output transistors, represented by stage 3, will generally have a more sluggish response than the small signal voltage amplifier stages 1 and 2. Moreover, designers sometimes exacerbate this problem by choosing to stabilize the feedback loop by connecting a capacitor between the collector and base of the second voltage amplifier transistor, represented in my diagram by op-amp 2.

There are (at least) three solutions to this problem.

(a) To ensure that the propagation delay

through the whole system is very low, in comparison with the signal bandwidth. This is the approach favoured by Mr Ojala, but is expensive.

(b) To apply the loop stabilizing capacitor across stages 1 and 2, thereby ensuring that stage 1 does not run out of negative feedback under transient conditions. (This was what I referred to as a divided feedback loop.)

(c) To interpose an input bandwidth limiting circuit, which could well be in the pre-amplifier, to ensure that the rise time of the input signal does not exceed the handling capability of the amplifier.

I favour a combination of the last two methods and, in particular, I believe that the dissociation of the h.f. feedback capacitor from the amplifier output point helps to ensure that the amplifier is tolerant of unexpected reactive loads, even though one pays the price of a t.h.d. curve which worsens somewhat at the h.f. end. Since I also believe that it is better to put predictable tonal quality with unknown loudspeakers before refinement of paper spec. I remain content with this decision.


2. Noise output from "virtual earth" amplifiers.

Mr Stuart asks again how it should arise, if the "virtual earth" point appears to have a low noise impedance, that the noise output should rise when this is shunted by 47k Ω . Since Mr Stuart must know very well that the gain of a shunt feedback amplifier is determined by the ratio of the input and feedback limb impedances, and that, other things being equal the higher the gain the larger the noise output voltage, I had treated this as a rhetorical question.

Obviously, the "virtual earth" impedance is a notional thing which arises because of the feedback connection. Equally obviously, the gain of the system increases when the input limb is reduced from an impedance of infinity (o/c) to any lower value one chooses.

3. Effective bandwidth of R.I.A.A. equalized stages.

Mr Stuart says "of course the noise is calculated in a 20kHz bandwidth". May I suggest a simple experiment. If one takes a wideband feedback amplifier, of any input resistance value one likes, and measures the output noise with a 20kHz bandwidth, one will get a value which is in reasonable experimental agreement with the value predicted from



this bandwidth, the known gain of the circuit, and the thermal noise of the input elements. If now one connects across the feedback circuit the components necessary to provide the falling h.f. gain characteristic of the R.I.A.A. curve, the output noise will drop, simply because one has restricted the effective noise bandwidth. If this were not the case, the series feedback connection using an inductive input would be worse than it is.

J. L. Linsley Hood,
Taunton, Somerset.

Inverter for fluorescent tubes

I should like to point out a serious error in the article "An efficient inverter for fluorescent tubes" by K. C. Johnson in your August edition.

Mr Johnson recommends preheating the fluorescent tube by switching 12 volts across the heaters. However, as I have proved to my cost, 12 volts is more than sufficient to initiate a discharge across the ends of the heater. Since the current drawn by this discharge is limited solely by the winding resistance of the chokes (1Ω), a current of several amps immediately flows, resulting in the sad demise of the tube heaters.

To overcome this problem it is necessary to limit the available current to the heaters, and two resistors of ten ohms interposed between the second terminal of the tube heaters and the double pole switch contacts will achieve this, without seriously limiting the warm up capability of the tube.

D. G. Chappell,
Twickenham,
Middlesex.

V.A.T. and prices

Could I appeal to your advertisers to say either Including or Excluding V.A.T. ?

Those that do not make this clear cause unnecessary correspondence and create mistrust both by buyer and seller.

W. B. Henniker,
Henniker & Kerr,
Edinburgh.

Printed circuits the easy way

Mr J. Ferguson's tips on making printed circuits (July Letters) are very useful. If readers try fibre or nylon tipped pens other than the "Miracle Pen" Mr Ferguson recommends they should etch some test pieces first.

Platignum "Penline Nylon Tip" and fibre tip "Magic Marker", indian ink and vitrina outline black, all easy to draw with, do *not* resist the ferric chloride. Another first rate pen designed for this purpose is the "Decon Dals", easy to use but a bit expensive.

The 30 or 40 minutes etching time

can easily be filled in on other jobs, so that may not bother some people. It is important if using a flat dish to suspend the board copper side down in the etchant so that sediment falls away, and to slide the board in so as not to trap air bubbles. Small boards float without extra support.

I find this method good: the layout of components is planned using 0.1in squared paper. This is then transferred to typewriting paper, by pricking through the holes. On one side of the typewriting paper the components are drawn again and on the other side the printed circuit with any fibre tip pen. This might be repeated to rectify any errors or poor layout.

The laminated board is cut to shape and the copper cleaned. The paper pattern is cello-taped to the copper and the holes pricked into the copper surface with a cheap drawing compass. The paper removed, the holes are lightly centre punched, but not yet drilled. The circuit is now drawn on the copper with a suitable pen, and may be etched straight-away.

After etching and cleaning, the holes are quickly drilled with a Heathcraft Mini Drill which gives holes about 0.8mm, a suitable size for most component leads, though a few holes need a larger drill. Burrs can be removed by fine emery cloth to make soldering a trifle easier.

If any readers have not yet tried making these circuits I recommend them to try. With a little practice the finished result can give much more satisfaction than any other board construction method.
V. Rowe,
Salford.

Radiating coaxial cables

I read with interest the suggestion of Mr Guy Moore that an aerial design which enhanced the radial vector component and suppressed the transverse component of the radiating field might provide a solution to the problem of frequency congestion and interference in the medium wave band. Such a design would indeed enable local broadcasting coverage to be provided without the associated long distance interference outside the service area.

Interest in frequency conservation is increasing every year and several methods of confining radiated signals have been investigated to date. One of the most promising solutions is the application of

radiating coaxial cables, which not only confines the radiation to a defined area but has the added attraction of providing coverage in areas such as tunnels, mines and buildings which would be inaccessible by conventional methods.

Investigations into the operation of radiating cables in the absence of buildings or tunnel walls has yielded interesting results. Measurements were made on a length of radiating cable laid on the ground in an open area, and the results are shown in the graph. The cable was fed with a 1 watt source with the far end terminated in a matched load (50 ohms). The variation of field strength with perpendicular distance from the cable was then measured at the mid-point of the cable. At frequencies of 989kHz and 1502kHz the field variation was distinctly of an inverse r^{-4} nature. This was unaffected by either mounting the cable above the ground or burying it under the soil. The latter result is not surprising if in fact the radiation mechanism is a radial induction field and not a transverse electro-magnetic one.

Caution must be advised if this is attempted with a cable not designed to be buried, or one which radiates by electric field perturbation and not surface current transfer, as the presence of the moist earth will impede operation.


Working systems have been installed in a Scottish university and coverage was as predicted with no interference beyond the perimeter of the campus.

J. R. Avery,
Andrew Antenna Systems,
Lochgelly,
Fife.

Magnetic units

Although "Cathode Ray" and I agree on most points, he raises some questions in the August issue (p.332) that require an answer. First, the P.M.A. still issues literature in both SI and c.g.s. units. Internally a few people use SI but I suspect the majority prefer c.g.s. Personally, I use whichever is more convenient in the circumstances. We are still probably a little ahead of the world in the use of SI; only last week I was sent a book on rare-earth-cobalt magnets to review. It was written by two distinguished members of Bell Telephone Laboratories and was entirely in c.g.s. units, apart from a conversion table. I think it is much fairer to compare the speed of conversion from c.g.s. to SI units in magnetism with the speed of decimalization as a whole rather than with the decimalization of money, which is a rather special case.

Secondly, the magnetization or polarization is not just of importance to physicists interested in fundamentals. Certainly one can design a loudspeaker magnet without knowing anything but the B versus H demagnetization curve of the magnetic material, but the new rare-earth-cobalt magnets have been developed largely because they are needed for t.w.t.s in communication and other satellites. Two of these magnets can have almost identical



curves between remanence and the normal B coercivity point, yet one may have double the intrinsic coercivity of the other. The intrinsic coercivity is the demagnetizing force that reduces the polarization J (magnetization M) to zero. The magnet with the higher intrinsic coercivity would perform satisfactorily, the other one would be seriously demagnetized by the conditions under which it would have to operate. An engineer who allows some equipment to fail because he thinks the intrinsic demagnetization curve only concerns fundamental physicists is not very competent; and if the equipment happens to be in a satellite he is unlikely to keep his job. Other devices which may contain magnets for which the intrinsic curve is important are car wiper motors and domestic electricity meters.

May I take this opportunity of correcting a typographical error in my article? In some of the labels of the axes on the figures an unnecessary bracket has appeared in an inappropriate place, so that the symbols for mega ampere per metre have been printed as $M(\text{Am}^{-1})$ instead of MAm^{-1} .

Incidentally, it is internationally agreed that symbols for physical quantities should be written in sloping (italic) type, but those for units in upright type. Thus magnetization in mega ampere per metre should be in symbols M/MAm^{-1} . This convention has been followed in the text of my article, but not on the figures.

M. McCaig,
Permanent Magnet Association,
Sheffield.

Reflex circuits

I have been roused out of hibernation by M. G. Scroggie's very interesting article on his 50 years of authorship (August issue). As he describes me as "ubiquitous", may I add a historical footnote to his statement that P. G. A. H. Voigt wrote "one of the first expositions of dual or reflex circuits in the first issue of *Modern Wireless* (which I founded on 9 January 1923 and edited).

In point of fact, this type of circuit in various forms had been "exposed" frequently during ten years before 1923. I had done much to publicize it myself long before its incorporation in popular set designs and before the paper I read before the British Association in 1923. For example, in my book "Thermionic Tubes in Radio Telegraphy and Telephony", issued by the publishers of *Wireless World* in 1921, I give three examples. In Fig. 117 appears the standard reflex circuit. In describing it, I state: "A single valve may be used not only to amplify the high-frequency oscillators but also to magnify at the same time the rectified pulses obtained from a crystal detector. Many variations of the Fig. 117 circuit may be devised." I referred to Telefunken's British Patent 8821 (15 April 1913) which contains a double-amplification (reflex) circuit. On p.166 I describe a reflex circuit with reaction and state:

"A further development of the Fig. 128 circuit was to bring the detected current back into the grid circuit and so amplify it. This double-magnification circuit, which is exceedingly sensitive, is shown in Fig. 129." Later on I give in Fig. 205 a reflex circuit by Marius Latour. This is a reference to his British Patents 131092 (30 April 1917) and 132668 (17 Nov. 1917). The Marconi Company developed a ship's receiver using a reflex circuit with a single valve (the circuit appears in Fig. 124 of my book "Elementary Textbook on Wireless Vacuum Tubes" (published in 1922).

Over the formative years 1917 to 1920 *Wireless World* published thirteen of my articles on valve techniques. In Fig 14 of one entitled "The Valve as an Amplifier" appears a typical dual-amplification circuit with a full explanation. This issue is dated March 1918. I myself patented various forms of reflex circuit soon afterwards.

In view of the above selection of anticipations going back to 1913, I do not think that Voigt himself would have claimed in 1923 to have written "one of the first expositions".

May I take this opportunity of expressing the debt owed to Mr Scroggie by professionals and amateurs alike for his own brilliant and crystalline expositions which have enriched the literature of the subject for fifty years.

John Scott-Taggart,
Beaconsfield,
Bucks.

Audio amplifier design

After reading the J. R. Stuart "Approach to audio amplifier design" (August issue), I was left gasping for oxygen as I absorbed the philosophy of the new generation of amplifier designers. How can Stuart continue with the normal, every-day mundane matters of life (shopping for cheap beef, shouting at the missus etc.) while knowing at the same time that his brain—or even the inner-being that is known as "self"—is all the time functioning as $f(P, s, t, \tau, m, D)$. I must admit though that there is comfort in the fact that distortion $D\%$ reduces according to cost $\text{£}Z$ in the manner $a \exp [Q \cdot (D)^{-1}] + b \cdot D^{-2} + c \cdot D^{-1}$. I've memorized that for my next trip to the audio discount warehouse.

... but then I don't design amplifiers.

A. Bloomer,
Neasden.

Quantities and qualities

I am gratified to note that W. B. Broughton (August issue, p.385) has troubled to search for an alternative to my suggested "forbiddivity" to replace the quantity name "reciprocal permittivity". In fact, his designation, "restrictivity", was amongst about a dozen possibilities that I considered — including such monstrosities as "constrainitivity" — but for some reason which now escapes me I was then under the impression that res-

trictivity was a term already used in some obscure branch of science. However, since restrictivity (or whatever) has the SI unit metre per farad, it could have been most appropriately named "elasticity" (being given dimensionally by elastance multiplied by distance) had not elasticity been in practical use before capacitors. On closer examination of this naming problem, I now realize that my search for an *antonym* (not counterpart as suggested in August, since this is accepted as equivalent to synonym) was incorrect, the requirement being a *reciprocal*, which, until 1570, was taken to mean "inversely related". So, we are both off course, although I still regard forbid as an acceptable starting point, being synonymous with hinder and restrain; hardly indicators of absolute stoppage. Curiously, and as a precedent, the widely accepted reciprocal quantities impedance and admittance already exhibit an anomaly: does not "impede" suggest partial prevention whereas "admit" concedes total entry? At this juncture I may as well admit that all this discussion is merely a subtle manoeuvre to steer the SI authorities into giving the unit, metre per farad, the name baldock, symbol Ba!

In more serious vein and also referring to p.385, I am delighted that B. J. Shelley has drawn attention to the genius of Alan Dower Blumlein, since I tried to promote more widespread recognition by creating the B.K.S.T.S. memorial meeting concerning Blumlein's work that took place on May 1st 1968. For years — perhaps I should say decades — Mr Scroggie has been insisting that the "Miller integrator" should rightfully be called the "Blumlein integrator", and, apart from Blumlein's diverse and fundamental contributions to stereo techniques and 405 line TV developments, few electronic engineers know that he invented the transformer ratio arm bridge (Sept. 1928), the cathode follower (Sept. 1934; the forerunner of the emitter follower for those not brought up on thermionic devices) and the long-tailed pair (July 1936), to name just a few of the 128 patents in which his name appears, and the result of developments over only 15 years prior to his untimely accidental death in June 1942.

An insight into Blumlein's humility is revealed by his attitude to research and development. I know several pioneers who worked closely with him at E.M.I. on television in the mid 1930s and have heard many interesting anecdotes. For instance, when A.D.B. could not help the team directly under "panic" breakdown conditions he was not above making the tea!

The full story of Alan Blumlein's contribution to technical history will appear in the forthcoming biography by Mr F. P. Thompson, written in conjunction with Simon Blumlein, and anyone with information likely to be of value should write to Mr Thompson at 39, Church Road, Watford WD1 3PY, Herts, England.
R. N. Baldock,
Harrow,
Middlesex.

Literature Received

For further information on any item include the WW number on the reader reply card

ACTIVE DEVICES

Wall-charts (in striking variations on a theme of puce) have been produced setting out salient performance details of c.m.o.s. logic devices and germanium power transistors by Motorola Semiconductors Ltd, York House, Empire Way, Wembley, Middx. WW401

A range of studio recording equipment, including a modular system, reverberation equipment, signal processing equipment and a phase meter, is briefly described in a leaflet produced by Allen and Heath Ltd, Pembroke House, Campsbourne Road, Hornsey, London W.8. WW402

A wall chart giving salient performance figures of a selection of linear integrated circuits, including operational amplifiers, comparators and regulators has been sent to us by National Semiconductors (U.K.) Ltd, The Precinct, Broxbourne, Herts EN10 7HY. WW403

The design of logic systems using the 74 series of integrated circuits is well covered in TI's new publication "System 74". It offers advice on the loading and compatibility of the different groups of devices in the 74 family. Applications of t.t.l. and the problems of interfacing with other equipment are discussed and there is a section on memories. Texas Instruments Ltd, Manton Lane, Bedford. WW404

The Lock Distribution Electronic Components catalogue contains information on products from Motorola, Signetics, Thomson CSF, Dow Corning, Waycom and Electrosil and gives details of technical publications available and distribution centres of Lock Distribution, Neville Street, Middleton Road, Oldham OL9 6LF, Lancs. WW405

The 1973 Erie catalogue of electronic components incorporates the export and distributor stock catalogues. Components listed range from resistors and capacitors to thick film devices and semiconductors. Erie Electronics Ltd, South Denes, Great Yarmouth, Norfolk. WW406

We have received a leaflet on m.n.o.s. electrically reprogrammable memory elements, describing characteristics, mode of operation, typical circuits and future developments from General Electric Semiconductors Ltd, East Lane, Wembley, Middx. HA9 7PP. WW407

A catalogue listing semiconductors, including i.c.s, memories, m.o.s. devices, f.e.t.s and photo-electric devices, made by Fairchild, Mullard, Plessey and Lucas, has been produced by Gothic Electronic Components, Beacon House, Hampton Street, Birmingham 19. WW408

PASSIVE DEVICES

Resistors and capacitors and their more important performance characteristics are shown in tabular form on a large new wall-chart, sent to us by the Instrumentation and Control Electronics Division, Mullard Ltd, Mullard House, Torrington Place, London WC1E 7HD. WW410

A catalogue covering a wide range of passive components including terminals, coils and formers, capacitors, connectors and other small hardware is available from Cambion Electronic Products Ltd, Castleton, Nr. Sheffield, S30 2WR. WW411

We have received a short-form catalogue, describing collet knobs, relays, rotary and thumbwheel switches and many other passive components from Radiatron Components Ltd, 76 Crown Road, Twickenham, Middx. WW412

A catalogue describing eleven types of Melesco thermocouples, which contains a guide to the use of these devices and recommendations on maximum temperatures is available from International Combustion Ltd, Ashburton Road East, Trafford Park Industrial Estate, Manchester M17 1LA. WW413

A leaflet covering several ranges of miniature, rotary stud switches has been received from Highland Electronics Ltd, 33-41 Dallington Street, London EC1V 0BD. WW414

A catalogue detailing the Pohl range of cable clamps has been sent to us by C.T.L. Components Ltd, 223/243 Wimbledon Park Road, London S.W.18. WW415

A buyer's guide to the U.K. capacitor market, containing information on which types of capacitor are handled by over 100 firms, has been published by Eurolec, Little Waltham, Chelmsford CM3 3NU. Price 95p by post.

EQUIPMENT

Mobile microwave links TFH-TM210A (7GHz) and TM213 (13GHz), are described in a leaflet supplied by Thomson-CSF, Division Radiodiffusion Television, 100 Rue du Fosse Blanc, BP49, 92230 Gennevilliers, France. Specifications of the video and audio channels, multiplex telephony and power supply are included. WW416

Crystal oscillators — miniature, oven controlled, high stability and temperature compensated — crystal controlled clocks and a rubidium frequency standard are among products described in a leaflet from Oscilloquartz SA, CH-2002 Neuchatel 2/Suisse. WW417

Radiatron Ltd, 76 Crown Road, Twickenham, Middlesex TW1 3ET, has issued a four-page leaflet describing the range of mechanical, analogue and digital tachometer equipment that they market in the U.K. on behalf of Jaquet AG, Switzerland. WW418

The latest Servoscribe flatbed recorder range, which are 200µ V to 250V d.c. deflection instruments with a writing width of 200mm, using rolls or single sheets, is described in a leaflet available from Smith Industries, Ltd, Industrial Equipment Division, Waterloo Road, Cricklewood, London NW2 7UR. WW419

Colour picture monitors made by NV Cobar Barco, of Kortrijk, Belgium are described in three brochures available from the U.K. agents Crow of Reading Ltd, 79 London Street, Reading, Berks RG4 QDX. Each of the three types (of modular construction for ease of servicing) display RGB signals and PAL, Secam or NTSC-coded composite signals using the appropriate plug-in chrominance demodulator. The last two digits in the type number indicate the screen size in cm.

CTVM2/38 R W420

CTVM2/51 WW421

CTVM2/66 WW422

A single page date sheet for the DN-70 liquid nitrogen cooling unit is available from Oxford Instruments, Osney Mead, Oxford, OX2 0DX. WW423

"Cossor SSR Systems" is a booklet describing different types of secondary surveillance radar systems and fundamental performance requirements. Cossor Electronics Ltd, The Pinnacles, Harlow, Essex. WW424

A catalogue of electronic kits covers the subjects of audio, radio, laboratory and automotive equipment and also contains general product information

including calculators, metal locators, intercoms. Heath/ Schlumberger, Advertising/PR Services, Bristol Road, Gloucester GL2 6EE. WW425

A full range of high-fidelity sound reproduction equipment including tuner-amplifiers, amplifiers, turntables, speakers, mixers, etc., is described in a catalogue sent to us by Eagle International, Heather Park Drive, Wembley HAO 1SU. WW426

We have received a leaflet giving full technical information on the Response BM 104 10-channel studio mixer from Audio Applications Ltd, Kensington Barracks, Kensington Church Street, London W8 4EP. WW427

A new catalogue covering their range of electronic measuring instruments has been published by Keithley Instruments Ltd, 1 Boulton Road, Reading RG2 0NL. WW428

A leaflet describing photon counting systems for use in signal recovery from quantum detectors such as photomultipliers has been produced by Brookdeal Electronics Ltd, Market Street, Bracknell, RG12 1JU. WW429

A leaflet describing display and recording accessories for use with the Datalab 900 series of transient recorders is available from Data Laboratories Ltd, 28 Wates Way, Mitcham, Surrey CR4 4HR. WW430

GENERAL INFORMATION

A revised catalogue of Puratronic ultra-pure chemicals and metals used in the manufacture of electronic materials and devices has been sent to us by the Publicity Department, The Johnson Matthey Group, 78 Hatton Garden, London EC1P 1AE. WW431

We have received two publications from the British Standards Institute. 101 Pentonville Road, London N1 9ND.

"Electronic tube terminology" — group 06 of Part 1 of the glossary of terms common to electrotechnology. Price £2.00

Code of Practice for the reception of sound and television broadcasting — CP1020 : 1973. Price £2.00


A guide to the quality and reliability testing of resistors and capacitors, including a brief description of BS9000 and its relation to the C.E.C.C. system, has been received from the Instrumentation and Control Electronics Division, Mullard Ltd, Mullard House, Torrington Place, London WC1E 7HD. WW432

We have recently received a catalogue describing servicing instruments, tools and materials intended for the installation and maintenance of domestic equipment from Rank Radio International, Drayton Road, Borehamwood, Herts. WW433


Recently produced by Jermyn is a catalogue supplement describing a large variety of both active and passive components and assemblies, for which the firm is a distributor. Other services described include coil winding, component matching and sub-assembly work. The supplement can be obtained from Jermyn Distribution, Vestry Estate, Sevenoaks, Kent. WW434

We have received a catalogue containing information on calculators, large-scale i.c. chips for clocks and a receiver circuit, display devices and other components from Bywood Electronics, 181 Ebbens Road, Hemel Hempstead, Herts. WW435

We have received a leaflet listing books written for postgraduates studying electronics and published by Butterworth & Co. Ltd., 88 Kingsway, London WC2B 6AB. WW436



Shure makes the microphones, too.



To make life easier for the sound system installer, Shure offers an entire range of ingenious, low-cost circuitry devices. There are available modular "add-on" mixers, including a professional mixer, stereo mixer and a reverberation mixer. An Audio Control Centre is offered to shape response to match room acoustics, and our Level-Loc to control audio levels. In all, eight superb units are available to aid your work. Post the coupon today for a copy of our Microphone Circuitry catalogue.

Shure Electronics Limited
Eccleston Road, Maidstone ME15 6AU

Please send me full information on Shure Microphone Circuitry.

Name _____

Address _____



The Sinclair Cambridge... no other calculator is so powerful and so compact.

Complete kit-£29.95!

(INC.VAT)

The Cambridge – new from Sinclair

The Cambridge is a new electronic calculator from Sinclair, Europe's largest calculator manufacturer. It offers the power to handle the most complex calculations, in a compact, reliable package. No other calculator can approach the specification below at anything like the price – and by building it yourself you can save a further £14!

Truly pocket-sized


With all its calculating capability, the Cambridge still measures just $4\frac{1}{2}'' \times 2'' \times \frac{11}{16}''$. That means you can carry the Cambridge wherever you go without inconvenience – it fits in your pocket with barely a bulge. It runs on ordinary U16 batteries which gives weeks of life before replacement.

Easy to assemble

All parts are supplied – all you need provide is a soldering iron and a pair of cutters. Complete step-by-step instructions are provided, and our service department will back you throughout if you've any queries or problems.

The cost? Just £29.95!

The Sinclair Cambridge kit is supplied to you direct from the manufacturer – you can't get it anywhere else. Ready assembled, it costs £43.95 – so you're saving £14! Of course we'll be happy to supply you with one ready-assembled if you prefer – it's still far and away the best calculator value on the market.



Features of the Sinclair Cambridge

- * Uniquely handy package.
 $4\frac{1}{2}'' \times 2'' \times \frac{11}{16}''$, weight $3\frac{1}{2}$ oz.
- * Standard keyboard. All you need for complex calculations.
- * Clear-last-entry feature.
- * Fully-floating decimal point.
- * Algebraic logic.
- * Four operators (+, -, x, ÷), with constant on all four.
- * Constant acts as last entry in a calculation.
- * Constant and algebraic logic combine to act as a limited memory, allowing complex calculations on a calculator costing less than £30.
- * Calculates to 8 significant digits, with exponent range from 10^{-20} to 10^{79} .
- * Clear, bright 8-digit display.
- * Operates for weeks on four U16 batteries.
(Replacement set costs about 15p.)

A complete kit!

The kit comes to you packaged in a heavy-duty polystyrene container. It contains all you need to assemble your Sinclair Cambridge. Assembly time is about 3 hours.

Contents:

1. Coil.
2. Large-scale integrated circuit.
3. Interface chip.
4. Thick-film resistor pack.
5. Case mouldings, with buttons, window and light-up display in position.
6. Printed circuit board.
7. Keyboard panel.
8. Electronic components pack (diodes, resistors, capacitors, transistor).
9. Battery clips and on/off switch.
10. Soft wallet.



Actual size!




4 1/2 in long x 2 in wide x 1 1/16 in deep

This valuable book – free!

If you just use your Sinclair Cambridge for routine arithmetic – for shopping, conversions, percentages, accounting, tallying, and so on – then you'll get more than your money's worth.

But if you want to get even more out of it, you can go one step further and learn how to unlock the full potential of this piece of electronic technology.



How? It's all explained in this unique booklet, written by a leading calculator design consultant. In its fact-packed 32 pages it explains, step by step, how you can use the Sinclair Cambridge to carry out complex calculations like:

- Logs Tangents Currency conversion
- Sines Reciprocals Compound interest
- Cosines nth roots and many others...

sinclair

Sinclair Radionics Ltd, London Road, St Ives, Hunts.
Reg. no: 699483 England VAT Reg. no: 213 8170 88

Why only Sinclair can make you this offer

The reason's simple: only Sinclair – Europe's largest electronic calculator manufacturer – have the necessary combination of skills and scale.

Sinclair Radionics are the makers of the Executive – the smallest electronic calculator in the world. In spite of being one of the more expensive of the small calculators, it was a runaway best-seller. The experience gained on the Executive has enabled us to design and produce the Cambridge at this remarkably low price.

But that in itself wouldn't be enough. Sinclair also have a very long experience of producing and marketing electronic kits. You may have used one, and you've almost certainly heard of them – the Sinclair Project 60 stereo modules.

It seemed only logical to combine the knowledge of do-it-yourself kits with the knowledge of small calculator technology.

And you benefit!

Take advantage of this money-back, no-risks offer today

The Sinclair Cambridge is fully guaranteed. Return your kit within 10 days, and we'll refund your money without question. All parts are tested and checked before despatch – and we guarantee a correctly-assembled calculator for one year.

Simply fill in the preferential order form below and slip it in the post today.

Price in kit form: £27.23 + £2.72 VAT. (Total: £29.95)

Price fully built: £39.95 + £4.00 VAT. (Total: £43.95)

WW973

To: Sinclair Radionics Ltd, London Road,
St Ives, Huntingdonshire, PE17 4HJ

Please send me

a Sinclair Cambridge calculator kit at
£27.23 + £2.72 VAT (Total: £29.95)

a Sinclair Cambridge calculator ready built
at £39.95 + £4.00 VAT (Total: £43.95)

*I enclose cheque for £ _____, made
out to Sinclair Radionics Ltd, and crossed.

*Please debit my *Barclaycard/Access
account. Account number _____

*Delete as required.

Name _____

Address _____

PLEASE PRINT

Video from Bell & Howell

In the United Kingdom Bell & Howell Video means:-

Electrohome

Monitors

Grass Valley

Signal processing equipment

JVC Nivico

½in. EIAJ1 Video tape recorders and cameras

Thomson CSF

Specialised cameras and systems


Tamron

Prime and zoom lenses

and of course (in England and Wales) -

IVC

1in. colour and monochrome video recorders and cameras



New Thomson-CSF colour camera type THV 14 for studio use


Bell & Howell's team of video engineers can provide a video system to meet your needs.

For further information write to:-

Video Systems Division,
Bell & Howell A-V Ltd.

Freepost, Wembley, Middlesex, HAO 1BR

Or telephone: 01-902 8812 w w 7/73



BELL & HOWELL

Bell & Howell have
a team of engineers and
a world of equipment
at their fingertips

BELL & HOWELL 16MM PROJECTORS VIDEO CAMERAS OVERHEAD PROJECTORS VIDEO MONITORS BELL & HOWELL LANGUAGE MASTER SUPER 8 CAMERAS SOUND FILMSTRIP PROJECTORS
 CCTV SYSTEMS AUTO 8 PROJECTORS BELL & HOWELL 16MM CAMERAS SUPER 8/REGULAR 8 PROJECTORS VIDEO RECORDERS FILMSTRIP AND SLIDE PROJECTORS BELL & HOWELL

WW—095 FOR FURTHER DETAILS

www.americanradiohistory.com

Single Sideband, Suppressed Carrier Generation

Modification of the "third method", made possible by the use of integrated circuits

by A. J. Turner* M.Sc., G3UFP

Two distinct methods of generating a single sideband signal have found widespread use. These are known as the filter method and the phasing method. A third method has been described¹ but this has not found much favour. The purpose of this article is to try to resurrect some interest in the third method and present a new alternative made available by integrated circuits.

The principle of the filter method is shown in Fig. 1. The baseband signal is converted to a double sideband signal at an intermediate frequency, usually in the range 1-10MHz. A highly selective filter, usually quartz crystal or mechanical, is used to obtain a single sideband which is translated on to the transmission frequency by one or more stages of heterodyning using balanced modulators.

A block diagram of the phasing method is shown in Fig. 2. The baseband signal is applied to a wide-band phase shift network. The output from this and the unshifted signal are applied to a pair of balanced modulators. The translating carrier is also split into two quadrature components. When the output of the two balanced modulators are added, one set of sidebands add whilst the others cancel, leaving an s.s.b. signal.

Third method

A block diagram of this method is shown in Fig. 3 from which it can be seen that this method comprises both filtering and phasing techniques.

The third method offers the following advantages over the others: highly selective filters, which introduce a loss of quality, are not needed, nor are wideband phase shift networks which require careful design and very accurate component values if adequate sideband suppression is to be achieved. In addition, imperfections in filtering and phasing or in balanced modulators do not result in unwanted sidebands outside the bandwidth of the wanted sideband. This is important when channel conservation is an important reason for using a single sideband system. Before considering the suggested modification to the third method, a brief description of the principle of the original system is necessary.

Suppose the baseband input signal is speech which has frequency components between 300Hz and 3300Hz and the pilot frequency is 1800Hz. Each output of the first pair of balanced modulators then consists of two sidebands of translated speech, the upper between 2100Hz and 5100Hz and the lower between 0Hz and 1500Hz. The low pass filters, whose

transition region is between 1500Hz and 2100Hz where there is no energy, remove the upper sideband. The outputs from the second pair of balanced modulators each consists of an upper and lower sideband displaced about the translating carrier frequency. The two upper sidebands are in anti-phase.¹ The required single sideband may be obtained by adding or




Fig. 1. Filter method for the generation of an s.s.b. signal.




Fig. 2. Block diagram of the phasing method for s.s.b. signal generation.




Fig. 3. Block diagram of the third method of s.s.b. signal generation, which involves both filtering and phasing techniques.

* Hatfield Polytechnic

subtracting the outputs of the second balanced modulators.

Modified third method

The disadvantage with the third method is that both the pilot and translating frequency carriers must be accurately split into quadrature components. This is not too difficult to accomplish at the low frequency of the pilot carrier. However, in order to minimize the number of stages of frequency translation after the exciter, the translating input to the second balanced modulators must be at as high a frequency as possible. Ideally, it should be the desired transmission frequency. Generation of high frequency quadrature signals is usually accomplished by loosely coupled tuned circuits and at 1MHz this requires critical adjustment and layout of the circuit. The problem is worse at 10MHz and almost impossible at 100MHz. This problem may be overcome with the aid of digital integrated circuit techniques. Suppose we take a sine-wave oscillator whose frequency is four times that of the desired frequency of the translating input of the second balanced modulators. A conventional squaring circuit and RC differentiator may then be used to convert this to a positive going pulse train at the same frequency, as shown in Fig.4. Provided that the amplitude of the spikes is greater than about 3.5V this signal may be applied to the clock input of the circuit in Fig.5.

This is essentially a divide-by-four using two JK flip-flops. Its action may be understood from the following truth-table remembering that the flip-flops are "cross-coupled" so that $J \neq K$ and $J_1 = X_2$ whereas $J_2 = X_1$. The X output follows J on the next clock pulse.

Number of clock pulses	flip-flop 1.		flip-flop 2.	
	J_1	X_1	J_2	X_2
0	0	0	1	0
1	1	0	1	1
1	1	1	0	1
3	0	1	0	0
4	0	0	1	0
5	1	0	1	1
6	1	1	0	1
7	0	1	0	0
8 etc.	0	0	1	0

It can be seen from the above table that the X outputs are square-waves whose frequency is one quarter of the clock frequency. Moreover the output X_2 is delayed by one clock pulse compared with X_1 , so that the outputs form quadrature square waves. It is not necessary to convert these square-waves to sine-waves before application to the balanced modulators, indeed this would be difficult to do without introducing phase errors.

The reason for this is that a square-wave has energy at the fundamental frequency and odd harmonics only. So in the case of the first balanced modulators, the use of quadrature square-waves for the pilot carrier produces an output having sidebands between 0 and 1500Hz and between 2100 and 5100Hz as before. High frequency sidebands about odd multiples of the pilot frequency will also be produced, but these will be eliminated by the low-pass filters.




Fig. 4. Stages in the production of quadrature square-waves.




Fig. 5. Use of a t.t.l. i.c. to obtain quadrature square-waves.




Fig. 6. Block diagram of the modified third method of s.s.b. signal generation.

Quadrature square-waves, this time at a high frequency, may also be used for injection to the second balanced modulators so that a complete exciter may be made as shown in Fig.6. In practice, the modulator outputs are added using a tuned circuit and the exciter output is subsequently filtered and amplified before radiation. This filtering will remove high frequency components generated by the use of square-wave translating carriers.

However, there is a hidden advantage in using square-waves. As shown in Fig.7 the harmonic components of the quadrature

square-waves also form quadrature pairs. This means that the summing tank circuit may be tuned to a harmonic of the square-wave input and a true single sideband signal at that frequency will be obtained. This enables a higher transmission frequency to be reached without subsequent stages of translation.

The circuit of Fig.5 has been found to accept a clock-input of at least 4MHz and produce square-waves at 1MHz. By tuning to 3MHz or 5MHz higher frequency output is obtained. The use of higher harmonics is limited by their reduced amplitude. How-




Fig. 7. Harmonic components of the quadrature square-waves, which also form quadrature pairs.

ever, the 7473 referred to in Fig.5 is a slow device; even the 7472 edge-triggered flip-flop can offer a 50% increase in clock frequency.

The author is currently developing an exciter based on these principles using very high speed Shottky logic capable of

accepting a 100MHz clock input and producing s.s.b. on 25MHz with no stages of translation after the exciter. It is hoped that by using the third harmonic, s.s.b. on frequencies as high as 500MHz may be produced with only one stage of translation after the exciter. Since the

accurate tuning of circuits to obtain the quadrature signals is not required the output frequency may be varied by tuning the oscillator, no other tuning being necessary over a fairly large range of frequencies.

Conclusion

The modified third method, using quadrature square-waves for the translating and pilot carrier, offers all the advantages of the conventional third method. In addition, since it requires no adjustment and no inductors, except those in the filter and oscillators, and since the quadrature components are inherently accurate, its performance should be superior in terms of sideband suppression and reliability.

The use of harmonics can extend the frequency range that can be covered and minimizes the number of translation stages.

Integrated circuits have their effect on the balanced modulators also. The device SN56/76514 is a balanced modulator offering conversion gain which should enable a complete exciter using only six integrated circuits and two transistors for the oscillators to be built.

Reference

1. Weaver, D.K., "A third method for the generation and detection of single sideband signals," *Proc. I.R.E.* 1956 Vol. 44, Part 12, pp1703-1705.

New electrochromic display

A new type of display device which produces a purple display on application of electric charge has been developed at Philips Research Laboratories at Eindhoven. Displays using the principle — for which patents have recently been granted to Philips — offer long-term memory, low switching voltage and good contrast that is independent of viewing angle. Previous electrochromic displays, like those based on electro-plating, colour changes in pH indicators or metal oxide colour centres, have suffered from high power consumption, irreversibility and/or low speed.

The Philips display is based on a redox (oxidation-reduction) reaction of diheptylviologendibromide in water. This colourless organic compound can be reduced at a cell cathode on application of a p.d. greater than the redox potential into a purple radical ion that reacts with the bromine anion to form a compound insoluble in water that precipitates onto the cathode. Exceeding the redox potential reduces the viologen dye ion further to form an unstable product which imme-

diately reacts with the original ions to form the purple ion. The cathode deposit remains until the cell is reversed.

This is done by short-circuiting the electrodes (which is very slow at around 0.5s) or by applying the opposite polarity, giving an erasure time of 10 to 50ms. This simple way has a snag in that build-up can occur on the anode, effectively slowing the cell down on subsequent cycles. A solution is to use a third, reference, electrode — formed in the case of seven-bar displays by the two islands in a figure eight. This is placed in a feedback circuit in such a way that cell current is controlled so that the p.d. between reference electrode and cathode becomes zero. With this potentiostatic technique, which needs only a simple differential amplifier, current only flows when a coloured layer is on the cathode.

For a reflectance of 20%, writing time is about 15ms for a cell voltage of between $1 \pm 0.4V$. This value of reflectance is obtained with a charge density of $2mC/cm^2$, equivalent to about 100mW in the display we saw. Contrast ratio was

5:1, which could be increased by passing more charge, being quite independent of viewing angle. Typically, 1mJ of energy is required for a seven-bar numeral of $5 \times 10mm$, with no energy requirement during storage. The low switching power at low voltage makes such a display compatible with t.t.l., and i.g.f.e.t. (m.o.s.) technology.

Electrodes can be made of a metal or of the conducting, transparent oxides of tin or indium and deposited onto a glass plate. A second glass plate spaced 2mm from the front plate forms the cell, which is filled with an aqueous solution of the organic compound together with potassium bromide to increase conductivity. The cell needs to be hermetically sealed, oxygen leakage limiting storage life. Cells have been run over 10^5 cycles so far and the coloured ion shows no degradation after a year.

This organic cell shows a higher figure-of-merit (contrast/charge) than a similar, inorganic, electrochromic display using tungsten oxide, and being developed elsewhere, by a factor of 3 to 5.

World of Amateur Radio

Citizens to gain amateur frequencies?

A recent announcement by the American F.C.C. proposes that the frequency band 224 to 225 MHz (which at present forms part of the 220 to 225 MHz amateur band in Region 2) should be re-allocated to a new Class E Citizens' Radio Service. The new band would be divided into 40 channels each 25 kHz wide. In its combined inquiry and rulemaking notice the F.C.C. invites comments on these proposals by September 20 and states that it will reply to these by October 22; unless there are unexpected delays American manufacturers are expecting that the new Citizens' Band will be in operation next year, although F.C.C. states that it will establish enforcement procedures before any use of the band is permitted.

This move follows a long campaign by American firms and some users of the 27 MHz Citizens' Band to obtain more frequencies. The original C.B. facilities, introduced in 1945, were limited to u.h.f. and attracted little attention. But with the introduction of the 27 MHz allocation in the United States in 1958 the numbers began to grow rapidly; from about 49,000 in 1959 to 868,013 in 1971, though in this expansion many abuses of the facilities became apparent in what had originally been intended as a short-distance radio-communications service for fixed or mobile operation.

The new band, if implemented, is likely to further increase the antipathy of many amateurs towards Citizens' Band operation. They can point to the I.T.U. Radio Regulations which allocate, in Region 2, the entire 220 to 225 MHz to amateur and radiolocation services on an equal basis; the F.C.C. proposal to assign part of this to a non-amateur radio-communication service would thus appear to be in breach of the international regulations. European amateurs are not directly affected since this band is not available to amateurs in Region 1 but they will be concerned to note a further loss of frequencies by the amateur service.

25 years on "Two"

On September 1, 1948 part of the 144 to 146 MHz ("Two metre") band was released to amateurs in the U.K. for the first time as a result of the new frequency allocations made at the ITU Atlantic City conference in 1947. Within a few weeks, despite the temporary power restriction to

25 watts, contacts were being made by a small band of enthusiasts (most of whom had gained v.h.f. experience on the old 56 MHz band) with stations in Western Europe. For example Denis Heightman, G6DH at Clacton, made the first contacts with Holland, France and Belgium and one of the earliest long-distance contacts was between G5BY at Bolt Tail, South Devon and PAOPN in the west of Walcheran, Holland.

Since then this has become in the U.K. perhaps the most used of all amateur bands, with literally thousands of stations operating in almost all modes, including a.m., n.b.f.m., s.s.b., a.f.s.k. and slow-scan television. Contacts over distances of roughly 300 to 400 miles are accepted as being likely to occur during almost any period of concentrated activity, such as the many contests held on the band. The longest span ever covered on the band — 2540 miles between California and Hawaii — was almost certainly achieved by tropospheric ducting, and this propagation mode may have accounted for the contact between Australia and New Zealand in 1965. In Europe, a day still remembered was July 4, 1965 when one of the rare Sporadic E openings on this band resulted in many contacts with Yugoslavia, Hungary and even Rumania; The European record of 1387 miles was made on that day during a contact between Eire and Yugoslavia. The increase in Sporadic E openings on 70 MHz this year as we again approach a sunspot minimum suggests that further openings on 144 MHz may occur during the next few years.

Courses for potential amateurs

In September and October many courses covering the syllabus of the Radio Amateurs' Examination will be starting at various technical colleges, adult education centres and the like with a view to preparing students for the examination next May. A partial list of centres (based on information from the organizers or from the R.S.G.B.) is given below, but in other places it may prove worth enquiring locally since the list is unlikely to be complete.

London and Home Counties: Beckenham, Kent (Adult Education Centre); Chertsey, Surrey (Institute of Further Education); Cove, Hampshire (N. & W. Farnborough Further Education Centre) also Morse; High Wycombe, Bucks (College of Technology); Holloway, London (Shelburne

Youth Centre); Slough (College of Technology) also an "advanced" course for those who already have an amateur licence; Welwyn Garden City (Mid-Herts College of Further Education); Weybridge, Surrey (Brooklands Technical College).

Provinces: Bath, Somerset (City of Bath Technical College); Boston, Lincs (College of Further Education); Bridgnorth, Shropshire (College of Further Education) also Morse; Cannock, Staffs (Cannock Chase Technical College); Cheltenham, Glos. (North Gloucestershire College of Technology); Doncaster, Yorks (College of Technology); Knaresborough, Yorks (Adult Education Centre); Lichfield, Staffs (Lichfield School of Art and Evening Institute); Liverpool (Riversdale College of Technology); Peterborough, Hunts (Technical College); Sheffield, Yorks (King Edward VI School); Stafford (College of Further Education) and Morse.

National Field Day

Preliminary results — still subject to confirmation — of this year's National Field Day put the Surrey Radio Contact Club as overall winner, with Oxford & District Amateur Radio Club runner-up; Glenrothes club was third and also winner of the Scottish N.F.D. In the single-entry stations the B.B.C. club "Ariel Radio Group" (Langham) was top scorer with East Barnet as runner-up.

In brief

Ron Wilkinson, VK3AKC of Geelong, Victoria recently became the first Australian amateur to contact the United States through moonbounce on 1296 MHz. He used a 20ft diameter parabolic dish aerial which he and his wife built and tested in six months . . . Hilary Mathews, grand-daughter of the late John Clarricoats, G6CL, has been licensed as G8HCG. Her father, Peter Mathews is G3BPM . . . West German amateurs can now use 1815 to 1835 kHz (s.s.b. operation confined to top 3 kHz) . . . The M.P.T. has agreed to renew the experimental licence for the 144 MHz repeater station GB3PI for a further twelve months . . . A group of Australian amateurs recently recovered and tested an early Command (SCR283) airborne installation which had remained for over 30 years in tropical jungle in an Airacobra fighter plane that force-landed in 1942. The t.r.f. receiver was still in working order and the transmitter required only the replacement of block capacitors; the entire equipment has since been fully restored . . . A south-east counties h.f. convention is to be held at the Airport Hotel, Crawley, on Sunday, November 18 . . . A second Amateur Radio Retailers Association exhibition is to be held at Granby Halls, Leicester on October 25 to 27 . . . A mobile rally is being held at the Nettlewell Comprehensive School, Harlow on Sunday, September 23.

PAT HAWKER, G3VA

Multi-channel Tone Control

A five-channel unit using active band-pass filters

by J. R. Emmett*, B.Sc.

New ideas in tone controls have appeared in the last few years^{2,3} which improve or supplement bass and treble controls, which are usually of the Baxandall type.¹ If the function of these controls is clearly understood, a fairly flexible amplitude frequency response curve can be built up. However, an easier and more versatile method of building a desired response is to use a number of overlapping, variable gain, frequency channels, spaced evenly throughout the audio spectrum. By using linear slider potentiometers, the control panel presentation can be made to resemble a response against frequency graph. In this form the system is sometimes called a "graphic equalizer". The unit which will be described for construction has five channels with centre frequencies of 50Hz, 200Hz, 800Hz, 3.2kHz and 12.8kHz. The linear slider potentiometers used give a control range of ± 12 dB. The designed signal level for normal use is around 0dBm (approximately 800mV), a level matching most modern amplifier and recording equipment inputs.

Negative feedback system

The usual method of obtaining a multi-channel response is by using an LC band-pass filter and gain control for each channel. The range of inductance needed to cover the ten octaves or so of the audio band makes the filters expensive and unattractive. In addition, much trimming is normally needed to obtain a basically flat response, due to crossover interactions between channels.

Negative feedback methods offer many advantages, such as reduced noise and distortion and accurate gain setting using potentiometers of linear law. In the case of the multichannel system, the filter specification may be greatly relaxed, and trimming can normally be eliminated.

A block diagram of this type of system is given in Fig. 1. At the centre frequency of a channel, and assuming no interaction between channels

$$|V_{out}|/|V_{in}| = R_a/R_b$$

If a simple tuned circuit bandpass filter is used, in order to cross over evenly between channels the Q value should be $\sqrt{2^x/(2^x - 1)}$, where x is the channel spacing in octaves. In a negative feedback system this is not

critical and the value of Q can be raised to reduce the interaction, the penalty being a rise in noise at the crossover points. Error in the centre frequency of a filter has a similar effect; as a guide, approximately 1.5dB increase in noise is produced by 50% Q error, or 15% error in centre frequency.

At a first glance it would seem desirable to make the first and last filters low and high pass respectively, but in actual fact this response is produced in a negative feedback loop using only bandpass filters. The penalty is increased noise again, but this time well outside the audio range, assuming a reasonable choice of channel frequencies has been made. Using only bandpass filters simplifies the system since only one basic filter type is required. The design of this network will now be considered.

Active bandpass filter

In some systems there could be thirty or more channels, and since there is one filter circuit per channel, this must be designed as

Performance of the five-channel tone control

- 3dB bandwidth at 1V r.m.s. signal level, controls flat: 8Hz-30kHz
- distortion at 1V r.m.s. signal level, controls flat: 100Hz-0.05%
- 1kHz-0.05%
- 10kHz-0.05%
- clipping level, controls flat: 2.9V r.m.s.

economically as possible within the limits of the specification. Assuming no inductors are to be used for the reasons mentioned before, the number of active devices should be minimized, unless component tolerances can be relaxed by using more. Close tolerance capacitors can prove especially expensive.

A simple circuit that meets these requirements is the Wien bridge derivative⁴ shown




Fig. 1. Simple block diagram of the multi-channel negative feedback system.




Fig. 2. Example of a band-pass active filter.




Fig. 3. Band-pass filter using multiple feedback.

*University of Durham




Fig. 4. Circuit of the five-channel tone control unit. Only one of the filters and linear potentiometer is shown.




Fig. 5. Suggested power supply circuit using an integrated regulator.




Fig. 6. Alternative discrete component power supply.

in Fig. 2. The response follows the tuned circuit law

$$V_{out}/V_{in} = -H\omega_0(j\omega)/\omega_0^2 - \omega^2 + a\omega_0(j\omega)$$

where $a = 1/Q$, ω_0 is the resonant frequency and the gain of the voltage amplifier is

$$H = 1/3(6.5 - a)$$

The component values are $C_b = C_a/2$, $R_c = 2/\omega_0 C_a$, $R_d = R_c/3$ and $R_e = 2R_c$. The most desirable feature of this circuit is that R and C values are independent of Q , and ω_0 is independent of amplifier gain H . Unfortunately, the Q value becomes extremely sensitive to the value of H for $Q \geq 1$, and the margin of stability in such cases is narrow.


A circuit much more suited to this application⁵ consists of an inverting op-amp with multiple feedback loops (Fig. 3).

The response of this circuit is the same as before, but the component values are $C_c = C_d$, $R_f = 1/H\omega_0 C_c$, $R_h = 1/(2Q - H)\omega_0 C_c$ and $R_g = 2Q/\omega_0 C_c$. If $H = 2Q$, R_h can be left out and V_{out}/V_{in} at resonance becomes

$$V_{out}/V_{in} = -2Q^2 = R_g/2R_f.$$

The minus sign in this expression indicates a phase reversal, so the main amplifier in Fig. 1 will now need an in-phase gain to obtain an overall negative feedback relationship.

The above equations for this active filter circuit show that Q , passband gain and resonant frequency are determined solely by two identical capacitors and two resistors. The demands on the op-amp are not great, and a single bipolar transistor suffices for low Q values. The transistors are used in the circuits to follow to provide a high stage gain in addition to filtering. This reduces the noise contribution of the main amplifier, and so long as the gain is greater than the number of channels used, the dominant noise contribution is that due to the first transistor stage of the active filter. This means a signal to noise ratio of about 70dB,



Five slider potentiometer controls on the front panel can be set to represent the required amplitude frequency response.

Table 1

Channel frequency (Hz)	C_{4-13} ($\mu F \pm 10\%$)
50	0.22
200	0.056
800	0.015
3.2k	3,900p
12.8k	1,000p

which is better than most preamplifier inputs.

Practical circuit

The circuit is shown in Fig. 4. Only one filter is shown as the other four are identical, except for the values of C_x which are given in Table 1. An emitter follower Tr_1 provides a low impedance input source for the bank of control potentiometers, R_{49-53} . The fixed resistors R_{5-14} restrict the range of boost and cut to ± 12 dB. The active filter consists of a common emitter amplifier with a d.c. coupled emitter follower output. The Q value employed is unity and the passband gain at resonance should be approximately 28dB. The filter outputs are fed to the main amplifier through R_{40-44} which also provide the d.c. bias for this stage. Overall h.f. stability is obtained from the 6dB/octave roll-off provided by C_{15} and R_{45} .

The unit complete with power supply fits into a 16 x 11 x 11cm case without difficulty.





Fig. 7. Typical response curves of the five-channel unit.



Slider pots mounted on the front panel are shown at the top with the main p.c. board (centre), which carries the filter circuitry and input/output devices. The power supply is on a separate board (bottom).

Table 2
Modified filter component values for narrower channel spacing. For worst case component tolerance, channel spacing error is 30%.

Channel spacing (octaves)	Q	R_{15-19} (k Ω)	R_{20-24} (k Ω)	R_{30-34} (k Ω)	Tolerance
					C_{4-13}, R_{15-24} (%)
1	1.7	3.9	47	6.8	10
$\frac{1}{3}$	4.5	1.5	120	0.68	3

A suitable power supply circuit using a monolithic regulator is given in Fig. 5. An alternative discrete component version, with a "ring of two" constant current generator feeding a zener diode in parallel with the load is given in Fig. 6. Either unit offers a ripple level which is inaudible with the unit in operation.

A small point worth noting is that calibration of the potentiometers in linear dB steps does not strictly follow the mathematical law, although only 10% error is produced over a 12dB range.

More channels

The performance of the five channel unit is encouraging enough to consider expanding the controls in range and number. As for range of control, about ± 25 dB is the most that would normally be required, even for special effects. One can obtain this range by reducing the values of R_{5-14} down to 2.7k Ω . To make sure that the overload margin is maintained under all conditions, it may be necessary to increase the standing current in Tr_1 and Tr_{13} to provide sufficient drive voltage for the potentiometer bank. Transistors Tr_1 and Tr_{13} may then have to be types of a higher dissipation rating. The number and spacing of controls will depend chiefly on application, thirty controls of one third octave spacing being a reasonable limit. The filter circuits can remain the same as the five channel unit; modified resistor values for two higher values of Q are given in Table 2. Using these modified circuits does not significantly alter the capacitor values for a given frequency, which are given by the equation

$$C(\mu F) = 1(\omega_0 \sqrt{R_f \cdot R_g}) \approx 11.8/f_0(\text{Hz})$$

Components

Values for the power supply components are shown in Fig. 5 or Fig. 6.

Transistors
 Tr_{13} - BC212 All others BC109

Capacitors
 C_1 - 1 μ /10V C_{14} - 50 μ /10V
 C_2 - 10 μ /15V C_{15} - 0.005 μ
 C_3 - 10 μ /15V C_{16} - 10 μ /15V
 C_{4-8} } - C_x (see table 1)
 C_{9-13} }

Resistors

R_1 - 47k R_{30-34} - 10k
 R_2 - 47k R_{35-39} - 680
 R_3 - 100k R_{40-44} - 22k
 R_4 - 1k R_{45} - 100
 R_{5-9} } - 3.3k R_{46} - 10k
 R_{10-14} } - 3.3k R_{47} - 4.7k
 R_{15-19} - 6.8k R_{48} - 1k
 R_{20-24} - 27k * R_{49-53} - 10k lin
 R_{25-29} - 100k

*Slider pots are "Alp" type LV60 (mono) or LG60 (stereo). The cheaper Radiohm types are also suitable.

REFERENCES

1. Baxandall, P. J., "Negative Feedback Tone Control", *Wireless World*, Oct. 1952.
2. Ambler, R., "Tone-balance Control", *Wireless World*, March 1970.
3. Hutchinson, P. B., "Tone Control Circuit", *Wireless World*, Nov. 1970.
4. Sallen and Key, *Transactions I.R.E.*, CT-2 No. 1, March 1970.
5. Huelsman, L. P., "Theory and Design of Active RC Circuits", McGraw-Hill, 1968.

Conferences and Exhibitions

- 1973 European Microwave Conference**
Sept. 4-7 Brussels
(Dr. G. Hoffman, Secretary General, ST Pietersnieuwstraat 41, B-9000 Ghent, Belgium)
- LASER 73**
Sept. 4-7 Munich
(Munchener Messe- und Ausstellungsgesellschaft, Theresienhohe 13, Munich, Germany)
- Royal Television Society Convention**
Sept. 6-9 Cambridge
(Royal Television Society, 166 Shaftesbury Avenue, London WC2H 8JH)
- Solid State Devices Conference**
Sept. 10-11 Nottingham
(The Institute of Physics, 47 Belgrave Square, London SW1X 8QX)
- First National Quantum Electronics Conference**
Sept. 10-13 Manchester
(The Institute of Physics, 47 Belgrave Square, London SW1X 8QX)
- Physics of Semimetals and Narrow-gap Semiconductors**
Sept. 12-14 Cardiff
(Dr. J. Aubrey, Dept. of Applied Physics, UWIST, King Edward VII Avenue, Cardiff CF1 3NU)
- First Indian Electronics Trade Fair**
Sept. 15-17 Bombay
(Taj Mahal Inter-Continental Hotel, Division of Trade Fairs and Exhibitions, Apollo Bunder, Bombay 1, India)
- Switching and Signalling in Telecommunications**
Sept. 16-22 Birmingham
(I.E.E. Savoy Place, London WC2R 0BL)
- IEEE Electronics and Aerospace Systems Conference**
Sept. 17-19 Washington
(I.E.E.E., 345 East 47th Street, New York, N.Y. 10017, U.S.A.)
- Eleventh Modulator Symposium**
Sept. 18-19 New York
(I.E.E.E., 345 East 47th Street, New York, N.Y. 10017, U.S.A.)
- Electronic Prosthetics Conference**
Sept. 19-21 Lexington
(College of Engineering, University of Kentucky, Lexington, Kentucky 40506)

Letter from America

There were a number of firms making projection TV in England around the 1950s — Decca, Valradio, Ferranti and White-Ibbotson come to mind — and I am sure there were many others. However, the idea never really caught on and production ceased after a few years. Servicing posed some problems, but the big disadvantage was the fact that the picture could only be viewed under cinema conditions. After all there was only 6 watts to play with and even with cathode and grid tube-modulation, plus the use of efficient aluminium screens, the picture was not that bright. Now, with the advent of better projection tubes — colour of course — large screen projection TV might well be “an idea whose time has come”. Sony certainly think so and they have given some very impressive demonstrations recently. Henry Kloss of Advent also thinks so and his company will be marketing a system later this year. The early systems I mentioned all used a Schmidt optical system made by Philips. The aluminized mirror tended to collect dust and it was most difficult to clean without damaging the delicate surface. Henry Kloss also uses a Schmidt system but he has dealt with the problem very simply: *the whole thing is enclosed within the tube*. It does mean that the system has a fixed focus but the advantages of having the optical components free from dust and fingerprints more than compensates for this. Three tubes are used and the phosphors are deposited

on $\frac{1}{16}$ in aluminium substrates. As the full colour picture is formed by the superimposition of the three images coming from different places there will obviously be some distortion. The varied angles of projection cause a kind of “pincushion” effect and because two of the tubes are angled slightly for convergence, the height of two of the images varies from left to right; in other words, a “keystone” distortion. These deviations are corrected by applying a complex compensating waveform to the scanning circuits.

The screen measures just over $5\frac{1}{2}$ feet by 4 feet and is spherical in shape with a 5-inch depth in the centre. It is made of aluminium foil bonded to a supporting material and the surface is indented by a pattern formed during a rolling process. This pattern gives the effect of a multitude of tiny lenses which define the viewing angles as well as improving the efficiency. Compared to matt white paper, the overall gain of the screen is said to be about 10. The loudspeaker is housed in the projection unit and the sound is reflected from the screen. Expected price is about \$2500.

The Consumer Electronics Show was again held in Chicago's vast McCormick Exhibition hall and, predictably, quadraphonic sound was the main interest. Just as predictable — the majority of receivers had provision for both SQ matrix and CD-4 “discrete” records. One receiver from Onkyo had automatic switching. No details were available but I imagine

the normal mode of operation is SQ and the presence of the CD-4 30kHz carrier operates the switching. A few receivers had SQ and CD-4 decoders built-in but the majority offered SQ with provision for an external CD-4 unit. Harman-Kardon pioneered the method of 2-4 channel bridge switching whereby each pair of output stages are effectively connected in series for 2-channel operation but now many more receivers (Marantz, Rotel, Sony, Pioneer) are employing this technique. How much do these receivers cost? Well, a typical a.m./f.m. quadraphonic receiver giving some 40 watts per channel would cost between \$450 and \$600. Half that power would bring down the price to about \$299. The majority are fitted with some form of “joystick” balance control — some with visual indication using l.e.d.s. The most conservative guess would put quadraphonics with 20% of the market but it is growing rapidly. Glenburn-McDonald have just announced a new turntable featuring a wide-range phono cartridge and built-in CD-4 discriminator to sell under \$59. Very few CD-4 discs are available — only about 25 against 300 or more matrix types — but RCA promise a lot more by the end of the year.

JVC were showing their new quadraphonic cassette deck which has eight tracks on standard 0.15-inch tape. Two drive systems are employed; one for the reel and one for the capstan. With such a minute separation between tracks, crosstalk can be quite a problem but JVC claim that special phase shift and feedback circuits reduce crosstalk to a minimum. Actual figures quoted were 25dB (at 1kHz) — not as high as in conventional machines but acceptable enough for most purposes. Provision is made for CrO₂ tape and the JVC noise reduction system — ANRS — is built-in.

Eight-track tape is still immensely popular, especially for car use, and CBS recently introduced a 100-minute cartridge which can accommodate the double or triple “albums”. Why a single record is called an “album” is inexplicable.

Sales of electronic calculators have been increasing by leaps and bounds and there were a number of new ones to be seen at the Show. One was the Commodore; a “super-mini” unit measuring only $4\frac{1}{2}$ inches by $2\frac{1}{2}$ by $\frac{3}{4}$ inches deep, priced at \$39.95. It is a six-digit model with add, subtract, multiply and divide functions. TI had two new models, a 12-digit desk-top unit at \$179.95 and another 12-digit unit with memory at \$179.95. Casio were showing a new hand-held six-digit model costing \$59.95 with an eight-digit model priced at \$99.95. One sales manager said “before too long children are going to be carrying mini calculators to school like pencils”.

According to Leibniz “It is unworthy of excellent men to lose hours like slaves in the labour of calculation” True enough, but I am still a little uneasy at the implications!

G. W. Tillett.



First production cassette machine with eight-track, four-channel capability uses special circuitry to keep crosstalk to a minimum (–25dB at 1kHz). S/n ratio is quoted 48dB in the four-channel mode, presumably with JVC's noise reduction system.

Simple Facsimile or Teleprinter Signal Converter

by J. B. Tuke

The author describes here a simple and reliable signal converter unit suitable for driving both facsimile and teleprinter machines from the a.f. output of a communications receiver. Phase-lock-loop technique is used which has the ability to detect extremely weak frequency-shift keyed radio transmissions, under conditions of low signal/noise ratio, and eliminates the use of bulky and parameter restricting LC filter circuits which would be normally used.

To interface a communications receiver with either facsimile recording or teleprinter machines, a signal converter is required. Fundamentally the method of transmission for both systems are of the same type utilizing two level f.s.k. Different information rates and frequency shifts may be used depending on the transmission frequency and mode used.

Satellite transit predictions are broadcast via radio teleprinter and these being of immense value to stations equipped for the reception of weather satellite facsimile transmissions, the need for a converter or "terminal unit" which will deal with both forms of signals is evident.

Reception of f.s.k. signals

The facsimile transmission of a weather picture takes the form of a frequency shift keyed signal in which the r.f. carrier is on one of two frequencies according to whether a black or white part of the picture is being transmitted at that instant. It should be noted that with this type of signal there are no intermediate shades of grey — the signal is either black or white. Since almost all facsimile recording machines in use are amplitude operated devices, where no signal means black and maximum signal means white, the job of the converter will be to change the frequency variations of the transmitted signal into amplitude variations suitable for feeding into the picture recorder.

A teleprinter is, in almost all cases, operated by feeding reversing currents into the operating coil. The transmission is still f.s.k. — the two frequencies correspond to the "mark" and "space" characters of the Murray five unit code. In this case the converter or terminal unit must change the r.f. signal into output current "reversals". It does not require much imagination to see that if the facsimile converter can produce amplitude changes corresponding to frequency changes, it will require only a simple relay to further change these amplitude variations into reversing d.c.

The NE560B integrated circuit, provides

the basis for a simple terminal unit which can deal with both facsimile and radio teleprinter signals. This will permit both data systems to be decoded and driven from a conventional communications receiver. This Signetics i.c. is a "phase-locked-loop" device in which a local oscillator, in fact a voltage controlled oscillator or v.c.o., locks onto an incoming signal by means of an error voltage which is produced by a phase comparator. An example of operation using typical frequencies follows.

Suppose the v.c.o. is free-running at 1500Hz. If an input signal above this frequency, say 1600Hz, is applied to the equipment, the v.c.o. is locked to this frequency by the error voltage generated by the phase comparator. The v.c.o. therefore has the same frequency as the incoming signal but there will, of course, be a constant phase error between the two which is proportional to the v.c.o. control voltage. If the input frequency is now changed to some figure below the free-running frequency, say 1400Hz, the v.c.o. would shift to that figure generating, in the phase comparator, an error voltage of the reverse sign. In the i.c., the error voltage does not, in fact, reverse sign but changes the level around a mean d.c. or quiescent value. The relationship is illustrated diagrammatically in Fig. 1.

If the error signal derived from the




Fig. 1. Response of phase-lock-loop over locking range.

comparator is fed (after suitable buffering) to a Schmitt trigger, it may be arranged so that one signal frequency produces a voltage which switches the trigger on, while the other switches it off. If an amplitude modulated signal is required to operate the facsimile recorder, the Schmitt trigger may be made to key a tone oscillator. For teleprinter use, the trigger may be used to operate a suitable high speed relay, via a transistor driver, which can provide the current reversals required.

Practical considerations

In designing a practical unit using the scheme described above, the first item to consider is the frequency at which the i.c. is to function. It could be at the receiver i.f. but few equipments have accessible i.f. outputs. It is preferable therefore to operate in the a.f. range, making the unit compatible with any receiver having a b.f.o.

Any frequency shift transmission, when received with the b.f.o. switched on, results in two audio tones. The pitch of the tones produced will depend on the b.f.o. setting but if the signal is tuned sufficiently to one side of the i.f. centre frequency, the tones will always differ in frequency from each other by the degree of shift employed at the transmitter. On the h.f. bands, this is typically 800Hz while on the l.f. bands — below 150Hz — it is 300Hz. The NE560B is capable of following frequency shifts up to 30% of the operating frequency. If the shift is 800Hz, the lowest operating frequency is therefore around 2700Hz. It is inadvisable to design to maximum limits so that if the i.c. capability is reduced to 25%, the mean frequency will be 3200Hz. A shift of ± 400 Hz then represents a total of 25% and is comfortably within the working limits of the i.c. The tones to be fed to the i.c. are therefore 3600 and 2800Hz. These frequencies may be attenuated, to some extent, by top cut capacitors fitted in the receiver to reduce noise, so some component removal may be necessary in the receiver a.f. stages. It may also be necessary to adjust the b.f.o. coarse tuning control to ensure that a sufficiently high beat note is available.

The performance of the NE560B is governed very largely by the amplitude value of the input signal. The range over which the oscillator will lock, expressed as a percentage of the centre frequency, is

dependent, amongst other things, upon this parameter. It is very important consequently that the signal be properly conditioned before being fed to the i.c. This conditioning implies amplification and limiting and a convenient method of doing this here is to employ a CA3076 i.c. as a pre-amplifier. Although designed for r.f. use, there is no reason why this circuit cannot be used at lower frequencies provided the bypass capacitors are increased accordingly. The 3076 will limit adequately with an input exceeding some 50µV, and the amplitude of the output is determined by the value of the output resistor. A suitable figure is 51Ω, which provides 20mV of signal to drive the NE560B. The full circuit is shown in Fig.2.

The error voltage output from the phase-lock-loop, IC₂, is available in amplified form at pin 9. The recommended load to ground is in the order of 15kΩ and the use of a transistor as part of that load, as suggested in an application note from Signetics, changes the load impedance with signal, thereby providing some small amplification. The available voltage change, for ±10% change of frequency, is in the order of ±1V which is then used to operate the trigger circuit Tr₂ and Tr₃.

It is desirable that the trigger should operate with the minimum change of voltage, and the circuit shown will switch for a change of about 0.3V which means that if the Signetics i.c. will deliver a voltage of ±0.15V, the trigger will operate satisfactorily. Since about ±1V is expected, there is plenty of voltage change in hand and trigger operation will be absolutely clear-cut.

The degree of filtering prior to the trigger is quite critical and if C₁₂ is too low a value, the trigger will operate from the break-

through of input signal superimposed on the changing d.c. at pin 9, and if too high, very brief signals, such as exist in facsimile transmission, may not operate the trigger at all. The value shown is a compromise but if the unit is to be operated solely for teleprinter work, this may safely be doubled or even trebled.

Machine interfacing

For working into a facsimile machine, the trigger is used to operate a gate which keys a local oscillator. This is conveniently arranged as shown using an f.e.t., Tr₅, as a keyed amplifier. The trigger output is either +4 or +14V with the values shown and with the source of the f.e.t. held at +9V by zener diode D₃, it is either on or off according to the state of the trigger.

The local oscillator may be any convenient design, say a small phase-shift oscillator and buffer, running at about 2500Hz. The waveform must be reasonably pure as otherwise the facsimile amplifier-rectifier may not operate correctly.

When radio teleprinter reception is required, the simple driver circuit shown will operate a "type 7" receive teleprinter. The +4/+14V available from the Schmitt trigger is passed via a 6V zener diode D₂ and suitable current limiting resistor R₂₀ at the base of driver transistor Tr₄. At this point the signal appears as 0V or +6V and the transistor switches fully on or off. The resulting collector current operates a Siemens high speed relay, with the two 1000Ω coils connected in parallel instead of the more usual series arrangement. The relay contacts should be adjusted for a 0.002in gap and the setting of the spring tension is discussed in setting up below.

There are only 3 controls on the converter; tuning, lock-range and trigger. These only need adjustment when changing to different shift values. The tuning control R₈ determines the centre frequency to be used and the performance of the unit is degraded when the potentiometer is more than 2/3 of the way towards the h.f. end. Useful limits with the values shown are from 1000 to 4000Hz which is an adequate range for normal use. If very narrow shift is to be used, C₁₀ should be increased to lower the mean operating frequency to the desired figure.

The lock-range control R₇ can only reduce the bandwidth over which the i.c. can follow to below the 30% maximum figures quoted. In most cases it is left fully "open", i.e. maximum lock-range, but under conditions of small shift and interference it may be reduced to advantage. Unfortunately, this control also alters the centre frequency, to some extent, so adjustment under working conditions may become difficult.

The third control R₁₂ adjusts the off-set voltage of the trigger to match the steady voltage of the i.c. output.

Setting up

It is strongly advised that the unit be set up to the desired standards before being put into service. The controls are all, to some extent, interdependent and adjusting under working conditions is likely to have as much success as fiddling with the i.f. cores of a TV while watching the picture!

Initial setting up requires only an a.f. signal generator and a pair of high impedance headphones. A basic oscilloscope is handy for correct adjustment of the




Fig.2. Circuit diagram of terminal unit.

receiver b.f.o. and to indicate that the converter is "on the correct frequency".

Having determined the shift to be employed, proceed as follows: let us assume a shift of 800Hz. The mean operating frequency will be, say, 3200Hz. Connect the headphones between "test point" and earth and feed a 3200Hz signal from the signal generator to the converter input. Adjust the tuning control until a pure tone is heard from the phones. Adjust the signal generator, decreasing the frequency, until a rasping, low frequency beat note is heard. This is the l.f. limit of the phase-lock-loop and the frequency should be noted (e.g. 2900Hz). Now, increase the generator frequency until the rasping note is again heard (e.g. 3600Hz). A quick calculation will show that the centre frequency of the loop is $3600 + 2900$ or 3250Hz. Adjust the

2

tuning control to slightly lower the frequency and repeat the checks, as necessary, until the lock-range is symmetrical about the desired centre frequency.

If the lock-range is excessively wide for the shift to be used, the lock-range control should be advanced slightly and the tuning re-adjusted until the required range is achieved. Normally the lock-range should exceed the shift by about 5%, otherwise the slightest frequency drift in the phase-lock-loop or the receiver will cause faulty operation. Therefore, using the generator, set the required locking width. Set the signal generator back to the correct centre frequency and transfer the phones to the facsimile output terminal. Adjust the trigger offset control R_{12} to a point midway between trigger on and off. The trigger may "jitter" at this setting as it tries to follow the breakthrough of the 3200Hz. Now, increase the generator frequency to a point where the trigger is firmly on. Note this frequency. Similarly, reduce the signal frequency until the trigger is shut off. Again note this frequency. These frequencies will be typically ± 50 Hz around the centre frequency and adjustment should be made for symmetry about this point.

An oscilloscope may now be connected to the "test point" and some f.s.k. signals can now be fed into the input from a receiver. When the correct tuning point is obtained, a pattern similar to that shown in Fig.3. will result, together with correct trigger operation. Detuning the receiver will result in large "spikes" appearing on the picture (Fig.4) together with random operation of the trigger.

Once the signal is correctly tuned in, the trigger offset control may be shifted in either direction to produce optimum results. If the two incoming tones are absolutely correct, the adjustments made during the setting up procedure will be satisfactory. However, this state of perfection may not always exist and if the signals are off frequency (but inside the lock-range) then a slight adjustment to the offset control will ensure proper trigger operation. This control is not all that critical and may be adjusted under working conditions without difficulty.

There only remains the adjustment of the




Fig.3. Correct tuning for f.s.k. signal.




Fig.4. Incorrect tuning where one frequency is outside the locking range.

high speed relay for use with a printer. If IC_2 is temporarily removed from its socket, a positive-going square wave may be applied to the trigger via the "test point". This may conveniently be obtained via a small diode and resistor (acting as a polarity sensitive switch) from the a.f. signal generator.

A frequency of 25Hz should be used (corresponding to a maximum rate of 50 bauds) and the output from the high speed relay contact examined on an oscilloscope. If a double beam oscilloscope is used correctly in the chopped mode, the relay spring should be adjusted until the output waveform from the relay matches, as closely as possible, the input waveform from the signal generator. Once set, this should require no further adjustment.

The complete unit requires 15V d.c. (negative earth) and draws about 30mA. Supply stabilization is provided by zener diodes D_4 for IC_1 and D_5 for IC_2 .

Components may be mounted in any convenient fashion, p.c.b., Veroboard or on a plain sheet of copper laminate, as wiring is relatively non-critical.

Transmission information

Radio teleprinter and facsimile transmission data can be obtained from the World Met. Organization, Geneva or, for British transmissions, in publication 510 a, b & c, from H.M.S.O. One problem with h.f. facsimile is multipath transmission, giving rise to ghosting on pictures, so that choosing the optimum frequency becomes important. This effect is less noticeable on radio teleprinter signals due to the longer time constants and l.f. facsimile transmissions seldom suffer from this condition.

Components list

R_1	100 Ω	R_{13}	22k Ω
R_2	22k Ω	R_{14}	3.3k Ω
R_3	5.6k Ω	R_{15}	3.3k Ω
R_4	250 Ω	R_{16}	6.8k Ω
R_5	51 Ω	R_{17}	15k Ω
R_6	100 Ω	R_{18}	5.6k Ω
R_7	100k Ω pot	R_{19}	100k Ω
R_8	20k Ω pot	R_{20}	22k Ω
R_9	8.2k Ω	R_{21}	47k Ω
R_{10}	3.3k Ω	R_{22}	33 Ω
R_{11}	2.2k Ω	R_{23}	33 Ω
R_{12}	5k Ω pot	R_{24}	5.6k Ω

C_1	6.4 μ F	C_9	0.005 μ F
C_2	50 μ F	C_{10}	0.08 μ F
C_3	0.1 μ F	C_{11}	6.4 μ F
C_4	6.4 μ F	C_{12}	0.004 μ F
C_5	200 μ F	C_{13}	0.04 μ F
C_6	0.1 μ F	C_{14}	0.1 μ F
C_7	0.47 μ F	C_{15}	0.01 μ F
C_8	200 μ F	C_{16}	0.01 μ F

IC_1	RCA CA3076
IC_2	Signetics NE560B

Tr_1	BC108
Tr_2	BC108
Tr_3	BC108
Tr_4	2N2538
Tr_5	2N3819

D_1	1N914
D_2	BZY88 - C6V2 (6.2V zener)
D_3	BZY88 - C9V1 (9.1V zener)
D_4	BZY88 - C9V1 (9.1V zener)
D_5	BZY88 - C12 (12V zener)
D_6	0A91, AA215 or similar
D_7	2.7V zener diode

Sixty Years Ago

The "Questions and Answers" section of the 1913 *Wireless World* makes as fascinating reading today as it must have done sixty years ago. The attitude adopted by the resident oracle is somehow reminiscent of the non-nonsense approach of some of the more matriarchal women's magazines. This impression is enhanced by the omission of the readers' queries, causing one to speculate on the possibility that they were rather too intimate for public exhibition. For example, a reply to "W.P." of Lanark . . . "W.P. shows from his question that he had better study the instructional articles now appearing in THE WIRELESS WORLD before attempting experimental wireless". W.P. (Lanark) must have felt like throwing the whole thing up and cultivating prize haggis instead.

The same advice was peremptorily handed to J.F.W., who was told: "Size of helix, etc., has little to do with distance of transmission; height of aerial (which you do not even mention) has a great deal. Evidently you need to read the series of instructional articles very carefully before commencing work". . . Ah, well, back to the drawing board.

The oracular dispensation to J.W.T. was, perhaps, the most intriguing in that month's answers: "(1) Your diagram, though neat enough, is the most mysterious of all those we have received. No indication is given as to where the three terminals shown are connected with the tuning inductance or its sliders; no parts of the apparatus are labelled, and some of it is quite beyond our powers of guessing. Study the diagrams appearing in many places in THE WIRELESS WORLD, and learn how to represent what you want to represent. . . ."

Fighting words — people evidently needed thick skins as well as ingenuity to listen to what the wild waves were saying.

New Products

15MHz dual trace oscilloscope


The Meteronic Type 201 dual trace 15MHz oscilloscope offers a wide range of features in a portable instrument form. Plug-in time base and amplifier modules allow the user to select the configuration best suited to his needs and an internal voltage and time calibration signal is provided.

Sensitivity is 5mV/div at full bandwidth and the fastest sweep speed is 100ns/div. The t.t.l. trigger circuits operate to 20MHz and triggering may be from either channel or external. The display mode may be either A, B, A and B chopped or A and B alternate. A battery option is soon to be available. The instrument weighs 3.5kg and measures 111 × 260 × 222mm. The U.K. list price is £170. Meteronic Ltd, 114/116 Shipbourne Road, Tonbridge, Kent.

WW317 for further details

Temperature balance heat sinks

The Redpoint type 92DC heat sink available from Celdis is designed to take two TO92 case plastic transistors and is thus ideal for applications such as complementary pair amplifiers, strain gauge amplifiers, or any other circuit where two devices are to work in a balanced condition, a situation which is assisted when the case temperatures of the two devices change in the same way. The size of 92DC dual heat sink is $\frac{3}{4} \times \frac{3}{16} \times \frac{5}{16}$ in, with a green anodized finish, and a thermal rating of 80°C/W. Price is 7.9p each for quantities greater than 100. Similar dual




heat sinks for temperature balancing are the type 5DC/HA, providing a thermal rating of 50°C/W for use with TO5 transistors, and the 18DC/HA with the same thermal rating, but for use on TO18 transistors. Prices for these are 21.3p and 20p each respectively (for quantities again in excess of 100). Celdis Ltd, 37/39 Loverock Road, Reading, Berks, RG3 1ED.

WW311 for further details

Plastic connector for audio

A new connector has been introduced by Sealectro Ltd for use in audio equipment. Designed initially to meet stringent European safety regulations, the new connector, part number 300A003, has an all plastic body, three pins and a slide engagement. It is suitable for operation at up to 125 volts, 4 amps, and the socket contacts are recessed for complete safety.



The chassis socket is flange mounted and the free plug has an unusual cable grip providing a firm anchorage. Cables from 5.8-6.5mm diameter may be used. The mated length is 63mm and diameter 18mm. Sealectro Ltd, Walton Road, Farlington, Portsmouth, Hants PO6 1TB.

WW306 for further details

Belt driven turntable

Two new automatic record turntables have recently been introduced by Garrard. The Zero 100 SB is similar to the earlier Zero 100 (which has a pivoted head for tangential tracking), but is now a belt driven unit providing drive to a heavy



zinc die-cast platter. Also included is a record counter for monitoring stylus wear.

The 86 SB is a belt driven development of the earlier AP76 and is similar to the Zero 100 in most features except that a conventional pick-up arm is used. Main specifications common to both models are: motor — screened four-pole synchronous; drive — belt from two-step motor pulley; wow and flutter — typically 0.12 peak; rumble — 63dB; bias compensator on both models is calibrated for both conical and elliptical styli; stylus force — 0 to 3gm, minimum recommended $\frac{3}{4}$ gm. Garrard Engineering Ltd, Swindon, Wilts.

WW302 for further details

(Zero 100 SB. Price £54.83 + v.a.t.)

WW304 for further details

(86 SB. Price £40.31 + v.a.t.)

Magnetic probe

Available from Interskill Ltd, this magnetic probe (The Magniprobe) replaces the conventional test magnet. It is no larger than a fountain pen and has a clip for carrying in the pocket. Originally developed for the easy identification of nickel aluminium conductors in miniature thermocouples, it incorporates a pivoting needle which is claimed to be many times more sensitive to low magnetic energy than is any hand held magnet.

The applications of this instrument are said to be innumerable and include the checking, at all stages, of conductor polarity in complex thermocouple installations; checking changes of magnetic state in some alloys due to heat treatment


conditioning; checking the quality of screws and other inserts assembled in positions inaccessible to the conventional magnet; establishing the polarity of small unmarked magnets used with reed relays and similar devices and for extracting fine magnetic swarf from small holes.

List price is from £4-£5 according to the quantity required and single Magniprosbes for trial purposes are available at £5.50 including v.a.t. and carriage paid from Interskill Ltd, 121 Cambridge Road, Milton, Cambridge CB4 4AT.

WW314 for further details

Variable transformers

Designated the 20 and 30 series, the Mk II Regavolt units from Berco have several interesting features. A new design of rotor brush arm provides metal to metal clamping using non-corrosive resistant steels, the contact arm being manufactured in beryllium copper which is heat treated to ensure stabilized brush pressure throughout its working life. Very low torque is required for rotation 3.5N cm (5oz.in) and these units can also be supplied in "ganged" form.



The 20 series Regavolt is primarily designed for the aircraft industry and provides a stepless control of power from 0-120W on 120V, 400Hz supplies. The 30 series has many applications such as simple motor speed control for d.c. motors, heating and ventilation control systems and light dimming applications. Berco Controls Ltd, Baird Road, Enfield, Middx. EN1 1UA.

WW 307 for further details

TV sound channel pick-up

Since few TV sets are fitted with an audio output to connect to hi-fi amplifiers, Multitech Corp. have designed a device which will pick up the radiated i.f. from the TV set and demodulate it to provide a suitable audio feed for an amplifier. The probe is designed to be placed (using an adhesive Velcro pad) on the back or side of the television set at a point producing optimum signal-to-noise and the unit, battery powered or with a small mains adaptor fitted, will stand on the set-top. Several adaptations are possible as the basic unit contains a synthetic stereo decoder which can be exchanged for a true stereo decoder (Zenith pilot

Video-level meter



A new video-signal level meter was shown for the first time by Philips at this year's International Television Exhibition in Montreux and is available from Pye Unicam Ltd. Designed to perform signal-level measurements on composite TV signals, the PM 5548 is claimed to be the first instrument of its type available anywhere in the world.

A feature of this instrument is that it can accurately measure an instantaneous signal level at any point in a composite video-test signal to the very high accuracy of $0.1\% \pm 1$ digit. This measurement is displayed digitally on a four-digit display, the measurement range covers - 600mV to + 1400mV relative to the blanking level. Additionally, a b.c.d. output of the measured value is optionally provided for driving a printer or other remote device, and a d.c. output for recording purposes.

Complete operation of the PM 5548 is based upon use of sampling techniques, a sample being taken from the video-test signal and used as a means of gauging the appropriate signal-component level. Via front-panel controls, the width of this pulse, the line on which it is employed, and its position on that line

can be controlled. It is also possible for this sampling pulse to be applied over a number of adjacent lines (up to 50) and for the pulse width to be varied from 0.3 to 10μ s. Measurements can be made on any section of the TV signal (both monochrome and colour) including the blanking period and sync pulse.

A further feature of this instrument is that the sampling pulse can also be employed as a marker pulse. In this mode it shows, via a monitor or oscilloscope, exactly which area of the video-test signal is being sampled. This marker, which can be applied positively or negatively, is also available as a separate output for Z-modulation of, for example, an oscilloscope.

Apart from its use independently in TV studios, etc, the PM 5548 can also be employed in conjunction with Philips PM 5546 video calibration generator. This unit provides the high-accuracy signals needed to check and align monitors, encoders, decoders, mixers, and other video equipment. Pye Unicam Ltd, Cambridge CB1 2PX.

WW318 for further details.

tone) or an amplifier which will drive an inductive loop for hearing aids. Performance specification is as follows: a.m. rejection 50dB; 3dB gain bandwidth 200kHz; distortion, 0.5% at 1kHz for 25kHz deviation; frequency response, 20Hz to 20kHz ± 0.5 dB. output 250mV r.m.s. at 5k Ω Multitech Corp, Nybovej 1 — 2500 Valby, Denmark.

WW 320 for further details

Direct reading 30kV meter

Believed to be the only one of its kind available in the U.K., a 30kV meter from Brandenburg Ltd, provides a

compact and portable instrument with high accuracy. Operated by 9V internal batteries linked to a built-in checking facility, the meter is flashover and transient proof and measures only 178 x 114 x 127mm (7 x 4.5 x 5in). Accuracy is 1.0% f.s.d. over the meter's range of 0-30kV d.c. and the high input impedance of 30,000M Ω means that the current drawn under test of less than 1 μ A is unimportant.

Positive or negative ground is selected by a switch mounted on the front panel which also houses the clear 4.5in scale meter. Battery life is 800 hrs. Brandenburg Ltd, 939, London Road, Thornton Heath, Surrey.

WW 308 for further details

Digital tracking voltmeter

The VID Tracking Voltmeter from Gay of Milan and marketed by Lyons Instruments, is an instrument which, in addition to operation as a normal d.c. digital voltmeter, has a peak reading memory voltmeter capability with the ability to read "maximum" or "minimum".

A new "continuous conversion" principle is used in which the tracking voltmeter continuously follows the input signal, providing a steady state indication when the input is constant, and continuous updating when the input changes. When the input changes only the variation is digitised to cause an increase or decrease in the displayed value (and b.c.d. output) and hence this "tracks" the input signal.

As a conventional d.v.m., the tracking voltmeter provides accuracy of $\pm 0.05\%$ of reading, $\pm 0.02\%$ of range with automatic polarity indication on four ranges of $\pm 0.9999V$, $\pm 9.999V$, $\pm 99.99V$ and $\pm 999.9V$. The floating input provides an impedance of $10,000M\Omega$ on the $1V$ range and $1.1M\Omega$ on the other three.

The above specifications apply both for the normal mode and for the



"maximum" and "minimum" peak holding memory modes. In the "maximum" mode the polarity switch can select either positive or negative peaks, whilst in the "auto" polarity position the absolute peak value (greater of positive or negative) is displayed, the polarity indicator acting as a polarity memory.

The unique "minimum" mode features the capability to measure and store the minimum instantaneous value (see picture) of a varying d.c. voltage, for example a fast voltage drop.

The Gay Milano VID tracking voltmeter is only 180×50 mm panel size by 220mm deep. Weighing 1.8kg, it requires only 15VA mains power. Price is £250 duty free, £275 duty paid, including b.c.d. output and logic level remote control inputs. Lyons Instruments Ltd, Hoddesdon, Herts.

WW315 for further details


True r.m.s. analogue voltmeter

Datron Electronics have announced a true r.m.s. analogue voltmeter designated Type 1115 which utilises what is claimed to be an entirely new type of true root mean square sensing circuit for the measurement of both sinusoidal and non-sinusoidal waveforms. The circuitry used in the 1115 is reported to overcome the shortcomings of thermal r.m.s. to d.c. converters by directly computing the true r.m.s. value of an input signal. The instrument comprises a precision wideband preamplifier with a selectable

low pass filter, an r.m.s. computation circuit and a 3 pole integration filter having two selectable time constants. The instrument has a bandwidth of d.c. or 1Hz to 1MHz; 12 voltage ranges from 3mV to 1kV and an accuracy of 1% full scale below 100kHz. Crest factor is 10:1 (full scale) and the instrument will withstand a 1kV overload on all ranges.

Price £260. Datron Electronics Ltd, Hotblack Road, Norwich, Norfolk.

WW313 for further details



Mini-power supplies

Recently introduced by ITT Components Group Europe is the Powercard "Size Two" — the first major extension of the range of p.c.b.-compatible power supplies launched last year. The new Powercard is larger ($16 \times 10 \times 5.5$ cm) and provides 15W against $7\frac{1}{2}$ from the standard Powercards. This is sufficient to supply a full 19in rack shelf of i.cs in most applications. Foldback overcurrent protection is standard and the input voltage ratings are 99 to 132V or 198 to 264V a.c. at 48 to 65Hz. The six Powercard "Size Two" specification codes are:

PC500C	15/15	: 0.5A at ± 12 to $\pm 15V$ tracking o/ps.
PC500D	15/15	: two isolated 0.5A o/ps at 12 to 15V.
PC500E	5/15	: two isolated 0.5A o/ps at 5 to 6V and 12 to 15V.
PC1000A	15	: 1A o/p at 12 to 15V.
PC500F	30	: 0.5A o/p at 24 to 30V.
PC3000A	5	: 3A at 5V ranging to 2.5A at 6V.

ITT Components Group Europe, Rectifier Division, Edinburgh Way, Harlow, Essex.

WW301 for further details

Large-screen video monitor

The Electrohome range of video monitors marketed by Bell & Howell A-V now includes a new 23in model, the EVM-23 V5. Designed for applications where picture size is as important as quality, it is suitable for message displays at hospitals and airports, computer read-out terminals and educational television in classrooms and lecture theatres. A solid-state monochrome monitor, the EVM-23 V5 is built to professional standards and includes among its features, high video input impedance, external sync input and plug-in transistors for ease of service.

Provision is made for asynchronous operation and there is remote control for brightness and contrast adjustment.

Resolution is claimed to be greater than 1,000 lines in the central 80% of the display area, and picture brightness is 513.9cd/m² under 80% white field conditions. All primary and most secondary controls are on the front of the monitor and are protected by a lockable panel. Price, £141. Bell & Howell A-V Ltd, Alperton House, Bridgewater Road, Wembley, Middx HA0 1EG.

WW316 for further details

High speed water fuse

Industrial Instruments Ltd, announce the introduction of a water filled fuse holder suitable for experimental situations. There are many applications in power electronics where expensive, pure silver fuses are blown deliberately during testing. Some of these may cost several pounds each. The Transifuse is a way of reducing these costs to that of a piece of copper wire.

The water filled fuse has a sufficiently fast rupture period, provided suitable diameter wire is used, to ensure the



protection of the most expensive power semiconductors. Current rating is from 25 to 100A with up to 200A permitted intermittently. Voltages up to 415V a.c. or d.c., depending upon current capability are permissible. Price, one off £3.35 with reductions for larger quantities. Industrial Instruments Ltd, Stanley Road, Bromley, Kent, BR2 9JF.

WW 310 for further details

Film capacitors

The new ITW-Paktron Micromatic polypropylene (PP) and polyester (PT) film capacitors, in which the capacitor leads serve as winding mandrels, are available from ITW Ltd, Electronic Division, of Slough. These are thought to be the first capacitors to be manufactured using this technique which eliminates outside wrapping and separate lead attachments. In consequence, the capacitors have no mandrel hole left as in conventionally

wound capacitors and it is claimed that air or moisture cannot penetrate and the leads cannot loosen.

The electrode foils and lead wires are separated by three layers of dielectric, and no dielectric is in direct contact with either wire in the electrical field. This manufacturing process insures against voltage breakdown in the area of lead wire penetration. The PT polyester series covers the capacitance range 1000pF

to 150nF with tolerances of $\pm 10\%$ to $\pm 20\%$ and voltage ratings of 200-400V d.c.

Completely self encased, types PT and PP capacitors provide low inductance, high insulation resistance and a low dissipation factor; additionally, the type PP has a negative temperature coefficient. ITW Ltd, Electronic Division, 263 Farnham Road, Slough, SL2 1HA.

WW 319 for further details

Solid State Devices

Each section under the title of Solid State, is devoted to the new semiconductor products offered by one manufacturer or distributor. The type number and device title is given in bold type, followed by a brief description of features or application. The section is terminated with the address of the company together with reader reply card numbers associated with the device numbers or types.

Announced from Celdis Ltd:

MC14530, dual 5-input majority logic gate. This is a Motorola m.o.s. i.c. which sometimes is referred to as having "voting logic" since it makes decisions based upon the levels presented at its inputs. Eighteen different logic possibilities are permitted and the alternative of a number of simple or fewer complex logic functions are facilitated without resort to a high gate count. It is constructed for p and n channel enhancement mode devices and features single positive or negative power supply operation with a typical noise immunity of 45% v.d.d. and a fan out of 750.

MC10128, MC10129, dual bus driver/quad bus receiver. These are designed to interface with t.t.l. or I.B.M. level buses, enabling high speed mainframes to feed the slower t.t.l. peripheral equipment. Price of both devices for 100 up quantity is £0.712.

MC1408L-8, eight-bit digital to analogue converter. This device features a current mode output and will provide a linear product of an eight-bit digital word and an analogue input voltage. The relative accuracy is $\pm 19\%$ error maximum, settling time is typically 300ns, non-inverting digital inputs are t.t.l. and c.m.o.s. compatible, output voltage swing is from +0.5V to 5.0V and the multiplying input slew rate is 4.0mA/ms. Price is £3.101 each at 100 up rate.

MC12000 digital mixer/translator. Designed to produce an output frequency which is the difference between two input frequencies, this i.c. consists of a D flip-flop with t.t.l. to e.c.l. and e.c.l. to t.t.l. translators. Intended primarily for use as a prescaler in phase-locked loop applications where the v.c.o. frequency is greater than 10MHz and the tuning range is narrow, it provides a means of generating frequencies up to 250MHz without tuned circuits. The output frequency could be either a single fixed frequency or a series of programmable frequencies when used in conjunction with the MC4016 programmable Modulo-N decade counter. Price is £2.38 at 100 up rate.

MC1455P1 i.c. timing circuit. This circuit provides timing intervals from 1 μ s to 1hr simply by the selection of one external resistor and capacitor. In the astable mode, it will operate as an oscillator with the frequency and duty cycle determined by the selection of two external resistors and a capacitor. The output can drive t.t.l. logic and can either sink or source up to 200mA. Price at 100 up rate, £0.55.

MC7800 series fixed voltage regulators. These are available in seven groups of 5, 6, 8, 12, 15, 18 and 24 volts, each able to supply over 1A with adequate heat sinking. Price (100 up) is £0.872.

5082-4860 and 5082-4468 light emitting diodes. These are made by Hewlett-Packard and contain a built-in resistor which acts in a current limiting mode. This makes them suitable for direct driving from t.t.l. or other i.c. families. The 5082-4860 is 0.2in diameter and is panel mounted by black plastic clips (part 5082-4418) which are supplied free of charge if ordered with the l.e.ds. The 5082-4468 has a diameter of 0.125in

but has the same specification in other respects. Luminous intensity is 0.8mcd (typical) at a V_F of 5V with a wave length of 655nm. Response speed is 15ns. Price (100 up) is £0.35 each for both types.

KBS series rectifier bridges are made by G.I., and are epoxy encapsulated inside a hexagonal metal case which is stud-mounted. With a dimension of 0.55in across flats, the devices will rectify up to 2A with a case temperature of 50°C. Voltage selections are 50, 100, 200, 400 and 600V with typical 100 up prices for say the KBS005 (50V) of £0.312 each to the KBS06 (600V) at £0.412.

40967 and 40968 r.f. transistors from RCA are designed for use as u.h.f. class C amplifiers in low voltage mobile applications. They are rated for 2W and 6W power output respectively, at 470MHz and a 12.5V supply. Supplied in the RCA HF-44 package, the price at 100 up quantities is £3.16 and £4.02 each respectively. Celdis Ltd, 37/39 Loverock Road, Reading, Berks RG3 1ED.

WW 330 majority logic gate

WW 331 dual bus driver/quad bus receiver

WW 332 8-bit d/a converter

WW 333 digital mixer/translator

WW 334 i.c. timing circuit

WW 351 voltage regulators

WW 335 resistor — L.c.ds

WW 336 rectifier bridges

WW 337 r.f. transistors

S.010 d.c.-d.c. converter by IPL provides dual positive and negative rails up to 15V and operates from a single 5V, t.t.l. supply rail. The dimensions are 2.48 × 1.225 × 0.575in and has a 0.1in grid connection pins. No heat sinking is required for supply currents up to 40mA at 12V and 34mA at 15V. The transient response is 10μs to 0.1% and a 15mV pk-pk output ripple. Each individual output is preset by a single resistor and each output is isolated (up to 10¹⁰MΩ) from the input. Price £10 each.

S1724 variable 256-bit shift register. This i.c. is made by AMI and is electrically programmable from 2 to 257 bits. It features m.o.s.-t.t.l. compatible inputs and outputs without the need for external resistors and through the use of a push-pull output will sink 1.6mA. Capable of being operated up to 1MHz, the S1724 is supplied in a 14 lead d.i.l. package at a 100 up price of £8.75.

S1709 queuing buffer register by AMI contains thirteen parallel in-parallel out shift registers and the control logic necessary to achieve a first in-first out (SILO) memory configuration. External control signals allow the cascading of many register arrays and the S1709 may operate with independent input and output data rates. The i.c. is a low voltage threshold m.o.s. device and packaged in a 24 lead d.i.l. package. Cost is £8.69 (100 up).

HD-0165 keyboard encoder from Harris is a 16-line to four-bit parallel encoder intended for use with manual data entry devices such as calculators, typewriters, etc. In addition to the encoding function there is a strobe output and a key rollover output which energizes whenever two or more inputs are activated simultaneously. These are normally routed through the key switches to the +5V supply. Price of the 24 lead d.i.l. package is £3.22 (100 up).

AA2705 operational amplifier. This Harris i.c. is designed to dissipate 0.75mW with dual 5.5V rails and 2.25mW with dual 15V rails. Open loop gain is 2,000,000. Input offsets are 2.5nA and 1mV and the slew rate is 20V/μs. Common mode and power supply rejection ratio are both 80dB minimum and the device will deliver up to 22mA output current.

TS6AM6. Fetron. This Teledyne device is designed as a direct solid state valve replacement and will plug in to the 6AM6/EF91/Z77 pentode valve sockets, which it is intended to replace, without circuit modifications. Price (100 up) £4.70. GDS (Sales) Ltd, Michaelmas House, Salt Hill, Bath Road, Slough.

WW338 d.c./d.c. converter

WW339 256-bit register

WW340 buffer register

WW341 keyboard encoder

WW342 operational amplifier

WW343 Fetron

IR106 low power thyristor range. These devices offer a V_{RRM}/V_{DRM} range of 15 to 400V and are available in five different packages which allow for p.c.b. mounting.

IR140 and IR141 fast turn-off thyristor ranges. Conforming to the JEDEC 2N3649 and 2N3658 series respectively, these thyristors offer a maximum turn-off time of 15μs for the IR140 and 10μs for the IR141. The re-applied dv/dt is 200V/μs for both devices and they will operate at up to 4kHz without peak current capability being reduced. International Rectifier, Hurst Green, Oxted, Surrey.

WW344 low power thyristor range

WW345 fast turn-off thyristors

NSN-33 three-digit i.e.d. display is a pin for pin replacement for the Litronix DL33. Each digit in the NSN-33 is 0.125in high and is made up of seven segments and a right hand decimal point. Segment and decimal point anodes of the three digits are internally connected in parallel. Current drive is 1mA average per segment to a maximum of 8mA. Packaged as a 12 pin d.i.l., the digits are spaced on 0.2in centres for end-to-end stacking of 6, 9 or 12 or more digits. The NSN-133 is a modified version of the same display with a minus sign replacing the extreme left digit and

connected to pin 12 which is unused in the NSN-33. Displays are available in matched brightness sets.

NSL5027 high intensity i.e.d. This lamp has an intensity of 2.0mcd minimum at 10mA, a forward current (I_F) of 70mA d.c. and a reverse voltage of 3V with a power dissipation of 140mW. Price (100 up) is 60p.

LH0062 f.e.t. operational amplifier i.c.

The circuit contains a monolithic dual j.f.e.t. chip and a bipolar op-amp similar to the LM118. Typical offsets are 2mV and 1pA with an offset temperature coefficient of 5V/°C. Drifts are only 4μV and 0.1pA per week! No external components are required for operation and the i.c. offers a 15MHz bandwidth, 70V/μs slew rate and 1μs settling time to 0.1%. Feedforward compensation almost doubles the speed whilst an extra capacitor lowers the settling time. Gain is 100V/mV and noise currents are less than 0.1pA r.m.s.

MM5316 digital alarm clock. This is a completely self contained alarm clock circuit capable of driving fluorescent tubes or liquid crystal displays. It is a monolithic m.o.s. integrated circuit that employs both low threshold p-channel enhancement mode and ion implanted depletion mode devices. The timekeeping function is triggered either by a 50 or 60Hz input and the display format may be either 12 hrs with suppressed leading zeros and a.m. or p.m. indication or 24 hrs. Four possible display modes are offered, time in hours and minutes, minutes and seconds, alarm set time or sleep time, with outputs provided for display drives, alarm enable and sleep or timed radio turn-off. The device operates over an unregulated supply range of from 8 to 29V and is available in a 40 pin epoxy B package.

DM7575/DM8575 and DM7576/DM8576 programmable logic array. These arrays have 14 data inputs and 8 outputs. Each output provides a sum of product terms where each product term can contain any combination of 14 variables or their complements. The p.l.a. is intended for use as control logic in digital systems and features a typical delay of 90ns and dissipates about 550mW. The DM7575/DM8575 has a conventional totem-pole output and the DM7576/DM8576 has a passive pull-up output for use in systems requiring more than one p.l.a. The arrays are available in a 24 pin Epoxy B d.i.l. package for operation from 0°C to 70°C (DM8575 and DM8576) or a 24 pin ceramic d.i.p. for operation over -55°C to 125°C temperature range (DM7575 and DM7576). National Semiconductor (UK) Ltd, The Precinct, Broxbourne, Herts.

WW 346 i.e.d. display

WW347 high intensity i.e.d.

WW348 f.e.t. operational amplifier

WW349 alarm clock i.c.

WW350 programmable logic array

They pay by instalments.

When you're in the business of installing sound systems, you have one major problem.

If the equipment you install breaks down, you get the blame.

That's why the Millbank range results from an intense research and development programme.

Just so this won't happen. A comprehensive collection of high quality audio equipment designed to take on any job.

No matter how large, or how small. Great lookers.

With Havana front panels and anodised alloy handles.

And above all great workers.





In fact, Millbank equipment is as good as it sounds.

Which means guaranteed satisfaction every time.

For your customers.

For you.

And for us.



Get in touch. We'll send you full details of all you need to know.

Any way you look at it, it's a sound investment.

Millbank

It's got to be good.

Millbank Electronics Group, Uckfield, Sussex, TN22 1PS, England. Tel: UCK (0825) 4166. From Europe: 892-96 4166. Telex: 28604.

Manufacturers of specialist audio equipment for industrial and entertainment applications.

Sound mixers, tuners, sound systems, loudspeakers, tuner amplifiers, audio modules and amplifiers.





WW—096 FOR FURTHER DETAILS

Precision drilling made so easy...

adcola quickstar

COMPACT, PRECISION, HIGH FREQUENCY P.C.B DRILLING MACHINE

This Machine is a must for any P.C.B. Manufacturer, essential for pre-production runs, P.C. Board corrections and additions for manufacturers of prototype P.C. Boards.



For full details send to

ADCOLA PRODUCTS LIMITED, ADCOLA HOUSE, GAUDEN ROAD, CLAPHAM SW4 6LH. DEPT. WW6 MACHINE SALES
REG. No. 442762 V.A.T. No. 235-6153-72

NAME

ADDRESS

WW—097 FOR FURTHER DETAILS

Sinclair Project 60

New performance standards ... new safety margins

Such are the results of using a PZ8 Mk.3 to drive two Z.50 Mk.2 power amplifiers. Developed from the original Z.50, the Mk.2 has improved thermal stability, better regulated D.C. limiting to ensure more symmetrical output voltage swing with still less distortion at lower outputs and automatic transient overload protection. The PZ.8 Mk.3 is the most advanced power supply unit ever to be made at a reasonable price. It cannot be damaged by direct shorting, nor will it fail through overloading, because of an ingenious re-entrant current limiting principle used usually only in expensive laboratory equipment. Because output voltage is variable, the PZ8 Mk.3 makes a worthwhile alternative where PZ.5 and PZ.6 are recommended for Project 60 applications, particularly since this most powerful of all Sinclair supply units can be operated from a smaller mains transformer. Together, the Z.50 Mk.2 and PZ8 Mk.3 provide new standards of performance and reliability and these modules are compatible with earlier types in the Project 60 range.

Z.50 Mk.2 SPECIFICATIONS

Input impedance 100 K Ω
 Input (for 30w into 8 Ω) 400mV
 Signal to noise ratio, referred to full o/p at 30v HT 80dB or better
 Distortion 0.02% up to 20W at 8 Ω .
 See published curve
 Frequency response 10Hz to more than 200 KHz \pm 1dB
 Max. supply voltage 45v (4 Ω to 8 Ω speakers) (50v 15 Ω speakers only)

Min. supply voltage 9v
 Load impedance - minimum: 4 Ω at 45v HT
 Load impedance - maximum: safe on open circuit


£5.48 + V.A.T.
 54p

PZ.8 Mk.3 SPECIFICATIONS


Nominal working output 45V.
 Adjustable between 20 & 50V.

£7.98 + V.A.T.
 79p

Mains Transformer £5.98 + V.A.T. 59p



**Z.50
Mk 2**



**PZ8
Mk 3**

Other power supplies

In addition to the remarkable Sinclair PZ.8 Mk.III as described, there are two other power units available, which should be chosen according to their types in order to buy to best advantage. All are for operation from A.C. mains 240V.

PZ.5 30 volt, unstabilised **£4.98**
 + V.A.T. 49p

PZ.6 35 volt, stabilised (Not suitable for Super IC.12). **£7.98**
 + V.A.T. 79p

Guarantee

If, within 3 months of purchasing any product direct from Sinclair Radionics Ltd., you are dissatisfied with it, your money will be refunded at once. Many Sinclair appointed Stockists also offer this same guarantee in co-operation with Sinclair Radionics Ltd.

Each Project 60 module is tested before leaving our factory and guaranteed to work perfectly. Should any defect arise in normal use, we will service it at once and without any charge to you. A small charge may be made in those cases where damage arises through miss-use. No charge is made for postage by surface mail. Air Mail charged at cost.

Typical Project 60 applications

System	The Units to use	together with	Units cost
Simple battery record player	Z.50	Crystal P.U., 12V battery volume control, etc.	£5.48 + V.A.T. 54p
Mains powered record player	Z.50, PZ.5	Crystal or ceramic P.U. volume control, etc.	£10.46 + V.A.T. £1.04
12W. RMS continuous sine wave stereo amp. for average needs	2 x Z.50, Stereo 60; PZ.5	Crystal, ceramic or mag. P.U., F.M. Tuner, etc.	£25.92 + V.A.T. £2.59
25W. RMS continuous sine wave stereo amp. using low efficiency (high performance) speakers	2 x Z.50, Stereo 60; PZ.6	High quality ceramic or magnetic P.U., F.M. Tuner, Tape Deck, etc.	£28.92 + V.A.T. £2.89
80W. (3 ohms) RMS continuous sine wave de luxe stereo amplifier. (60W. RMS into 8 ohms)	2 x Z.50 Mk.2, Stereo 60; PZ.8 Mk.3 transformer	As above	£34.90 + V.A.T. £3.49
Indoor P.A.	Z.50 Mk.2, PZ.8 Mk.3 transformer	Mic., guitar, speakers, etc., controls	£19.44 + V.A.T. £1.94

A.F.U. (£5.98 + V.A.T. 59p) may be added as required.



the world's most advanced high fidelity modules

Q.16 high fidelity loudspeaker

The Q.16 employs original and by now well proven acoustic principles in which a special driver assembly is meticulously matched to a uniquely designed cabinet. In performance it comfortably stands comparison with very much more expensive loudspeakers. A solid teak surround is used with a special all-over cellular black foam front chosen both for its appearance and ability to pass all audio frequencies without masking.

Specifications

Construction: A sealed seamless sound or pressure chamber is used with internal baffle, and special high flux driver


Loading: Up to 44 watts RMS, into 8 ohms

Frequency response: From 60 to 16,000 Hz

Size and styling: 248 mm square x 120 mm deep (9 7/8" x 4 7/8") with neat pedestal base.



£7.70 + V.A.T. 77p



Stereo 60 pre-amp/control unit

Designed specifically for Project 60 systems, the Stereo 60 is equally suitable with any high quality power amplifier. Silicon epitaxial planar transistors used throughout ensure high signal-to-noise ratio and excellent tracking between channels. Input selection is by press buttons, with accurate equalisation on all input channels. The unit is easy to mount.

SPECIFICATIONS—Input sensitivities: Radio — up to 3mV. Mag. p.u. 3mV; correct to R.I.A.A. curve ± 1 dB; 20 to 25,000Hz. Ceramic p.u. — up to 3mV; Aux — up to 3mV. **Output:** 250mV. **Signal to noise ratio:** better than 70dB. **Channel matching:** within 1dB. **Tone controls:** TREBLE +12 to -12dB at 10KHz; BASS +12 to -12dB at 100Hz. **Front panel:** brushed aluminium with black knobs and controls. **Size:** 66 x 40 x 207mm.

Built, tested and guaranteed.

£9.98 + V.A.T. 99p

AFU filter unit


For use between Stereo 60 and two Z.30's or Z.50's in stereo formation. Cut off frequencies are continuously variable, with 12dB/octave cut in the rejection band. Two stages of filtering — rumble (high pass) and scratch (low pass). Amplitude and phase distortion are negligible. Supply voltage needed — 15–35V. H.F. cut-off (–3dB) 28KHz to 5KHz; L.F. (–3dB) 25Hz to 100Hz. For Project 60 or any good stereo system.

Built, tested and guaranteed

£5.98 + V.A.T. 59p



Super IC.12 Integrated circuit high fidelity amplifier



Having introduced Integrated Circuits to hi-fi constructors with the IC.10, which was the first time an IC had ever been made available for such purposes, we followed it with an even more efficient version, the Super IC.12. This needs very few external resistors and capacitors to make an exceedingly efficient high fidelity amplifier for pick-up, F.M. radio or small P.A. set up etc. The free 40 page manual supplied details many other applications which this remarkable IC make possible. The Super IC.12 is the equivalent of a 22 transistor circuit

contained within a 16 lead DIL package, and the finned heat sink is sufficient for all likely requirements. The Super IC.12 is also compatible with those Project 60 modules which would be used with the Z.50 and Z.30 amplifiers. Complete with free manual and printed circuit board.

SPECIFICATIONS

Output power: 6 watts RMS continuous (12 watts peak) into 6–8 Ω . **Frequency Response:** 5Hz to 100KHz ± 1 dB. **Total Harmonic Distortion:** Less than 1% (Typical 0.1%) at all output powers and frequencies in the audio band (28V). **Load Impedance:** 3 to 15 ohms. **Input Impedance:** 250 Kohms nominal. **Power Gain:** 90dB (1,000,000,000 times) after feedback. **Supply Voltage:** 6 to 28V. **Quiescent current:** 8mA at 28V. **Size:** 22 x 45 x 28mm including pins and heat sink.

Manual available separately 15p post free

With FREE printed circuit board and 40 page manual.

£2.98 + V.A.T. 29p Post free

Project 605



the simple way to build a Project 60 system without soldering

For the many audio enthusiasts anxious to build to high standards without too many involvements, there could be nothing better or simpler than Project 605. It offers the advantages of Project 60 and is absolutely complete down to the last piece of wire cut to length. Whilst not as powerful as assemblies using Z.50 power amplifiers, we know from experience that there are many for whom the specifications of Project 605 are ideal, particularly in relation to the environment in which it is required to be used. In Project 605 you have everything necessary to build a versatile Project 60 thirty watt high fidelity amplifier system suitable for all domestic requirements. The convenient pack includes two Z.30 power amplifiers, a Stereo 60 pre-amp control unit and the special Masterlink unit to and from which all input and output connections are made. For power a PZ.5 is provided. Building is particularly easy since all necessary leads are supplied colour coded, cut to length and terminated by contact clips which connect firmly to the modules. There is absolutely no soldering to be done. Complete with comprehensive, easy to follow instructions manual.

£29.95 + V.A.T. £2.99 Post free

Send coupon for leaflet

Please send leaflet and name and address of my nearest Sinclair stockist

Name _____

Address _____

SINCLAIR RADIONICS LTD., LONDON ROAD, ST. IVES, HUNTINGDON PE17 4HJ

ww1

sinclair

The Largest Selection of

BRAND NEW FULLY GUARANTEED DEVICES

AC107 0-22	AD162 0-37	BC148 0-11	BD138 0-44	BF185 0-33	MPP105 0-41	2G344 0-20	2N2917 0-24	2N3053 0-19	2N4059 0-11
AC113 0-22	AD161 0-37	BC149 0-13	BD137 0-50	BF188 0-44	OC10 0-39	2G345 0-18	2N2918 0-22	2N3054 0-51	2N4060 0-13
AC115 0-28	AD162 (MP)	BC150 0-20	BD138 0-55	BF194 0-13	OC20 0-70	2G371 0-18	2N2919 0-22	2N3055 0-55	2N4061 0-13
AC117K 0-22		BC151 0-22	BD139 0-61	BF195 0-13	OC22 0-42	2G373 0-18	2N2920 0-24	2N3091 0-16	2N4062 0-13
AC122 0-13	ADT140 0-55	BC152 0-19	BD140 0-66	BF196 0-16	OC23 0-48	2G377B 0-19	2N2921 0-22	2N3092 0-16	2N4063 0-19
AC125 0-19	AF114 0-27	BC153 0-31	BD155 0-88	BF197 0-16	OC24 0-62	2G374 0-19	2N2922 0-22	2N3092 0-16	2N4064 0-19
AC126 0-19	AF115 0-27	BC154 0-33	BD175 0-88	BF200 0-50	OC25 0-62	2G377 0-19	2N2923 0-22	2N3093 0-16	2N4065 0-19
AC127 0-18	AF116 0-27	BC155 0-37	BD177 0-72	BF202 0-05	OC26 0-28	2G378 0-18	2N2924 0-22	2N3094 0-16	2N4066 0-19
AC128 0-19	AF117 0-27	BC156 0-13	BD177 0-72	BF205 0-50	OC28 0-55	2G381 0-18	2N2925 0-22	2N3095 0-19	2N4067 0-19
AC132 0-16	AF118 0-39	BC159 0-13	BD178 0-72	BF208 0-66	OC29 0-55	2G382 0-18	2N2926 0-22	2N3096 0-19	2N4068 0-19
AC134 0-16	AF124 0-33	BC160 0-50	BD179 0-77	BF209 0-94	OC35 0-48	2G401 0-33	2N2927 0-22	2N3097 0-19	2N4069 0-19
AC137 0-16	AF125 0-28	BC161 0-55	BD180 0-77	BF292 0-61	OC36 0-55	2G411 0-33	2N2928 0-22	2N3098 0-19	2N4070 0-19
AC141 0-16	AF126 0-31	BC162 0-13	BD185 0-83	BF263 0-81	OC41 0-22	2G417 0-33	2N2929 0-22	2N3099 0-19	2N4071 0-19
AC144K 0-19	AF127 0-31	BC168 0-13	BD186 0-72	BF272 0-39	OC42 0-27	2N388 0-39	2N2930 0-22	2N3100 0-19	2N4072 0-19
AC142 0-16	AF139 0-33	BC169 0-13	BD187 0-77	BF271 0-33	OC44 0-17	2N388A 0-61	2N2931 0-22	2N3101 0-19	2N4073 0-19
AC142K 0-19	AF178 0-39	BC170 0-13	BD188 0-77	BF272 0-38	OC45 0-14	2N404 0-22	2N2932 0-22	2N3102 0-19	2N4074 0-19
AC151 0-17	AF179 0-55	BC171 0-16	BD189 0-99	BF273 0-39	OC70 0-11	2N404A 0-31	2N2933 0-22	2N3103 0-19	2N4075 0-19
AC154 0-22	AF180 0-55	BC172 0-18	BD190 0-93	BF274 0-38	OC71 0-11	2N524 0-46	2N2934 0-22	2N3104 0-19	2N4076 0-19
AC155 0-22	AF181 0-50	BC173 0-16	BD195 0-94	BF270 0-66	OC72 0-16	2N527 0-54	2N2935 0-22	2N3105 0-19	2N4077 0-19
AC156 0-22	AF186 0-50	BC174 0-16	BD196 0-94	BF275 0-30	OC74 0-16	2N598 0-46	2N2936 0-22	2N3106 0-19	2N4078 0-19
AC157 0-22	AF239 0-41	BC175 0-24	BD197 0-99	BF276 0-39	OC75 0-17	2N599 0-50	2N2937 0-22	2N3107 0-19	2N4079 0-19
AC158 0-22	AF239 0-41	BC176 0-24	BD198 0-99	BF285 0-33	OC76 0-17	2N696 0-14	2N2938 0-22	2N3108 0-19	2N4080 0-19
AC166 0-22	ASL103 0-72	BC178 0-21	BD199 0-105	BF286 0-24	OC77 0-28	2N697 0-15	2N2939 0-22	2N3109 0-19	2N4081 0-19
AC167 0-22	ASV26 0-72	BC179 0-21	BD200 1-05	BF287 0-27	OC81 0-17	2N698 0-27	2N2940 0-24	2N3110 0-19	2N4082 0-19
AC168 0-27	ASV27 0-33	BC180 0-27	BD205 0-88	BF288 0-24	OC82 0-17	2N699 0-39	2N2941 0-24	2N3111 0-19	2N4083 0-19
AC169 0-16	ASV28 0-33	BC181 0-27	BD206 0-88	BF289 0-24	OC82 0-17	2N708 0-08	2N2942 0-16	2N3112 0-19	2N4084 0-19
AC176 0-22	ASV29 0-28	BC182 0-11	BD207 1-05	BF290 0-24	OC82 0-17	2N708 0-08	2N2943 0-16	2N3113 0-19	2N4085 0-19
AC177 0-27	ASV30 0-28	BC182L 0-11	BD207 1-05	BF291 0-24	OC83 0-22	2N708 0-08	2N2944 0-16	2N3114 0-19	2N4086 0-19
AC178 0-31	ASV31 0-28	BC183 0-11	BDY20 1-10	BF292 0-24	OC83 0-22	2N708 0-08	2N2945 0-16	2N3115 0-19	2N4087 0-19
AC179 0-31	ASV32 0-28	BC183L 0-11	BF115 0-27	BF293 0-19	OC84 0-22	2N711 0-33	2N2946 0-16	2N3116 0-19	2N4088 0-19
AC180 0-19	ASV34 0-28	BC184 0-13	BF117 0-50	BF295 0-14	OC89 0-22	2N717 0-39	2N2947 0-16	2N3117 0-19	2N4089 0-19
AC180K 0-22	ASV55 0-28	BC184L 0-13	BF118 0-77	BF296 0-17	OC140 0-22	2N718 0-27	2N2948 0-16	2N3118 0-19	2N4090 0-19
AC181 0-19	ASV56 0-28	BC186 0-31	BF119 0-77	BF297 0-17	OC169 0-28	2N718A 0-55	2N2949 0-16	2N3119 0-19	2N4091 0-19
AC181K 0-22	ASV57 0-28	BC187 0-31	BF121 0-50	BF298 0-17	OC170 0-28	2N726 0-31	2N2950 0-16	2N3120 0-19	2N4092 0-19
AC187 0-24	ASV58 0-28	BC187L 0-31	BF123 0-55	BF299 0-17	OC171 0-28	2N727 0-31	2N2951 0-16	2N3121 0-19	2N4093 0-19
AC187K 0-22	ASZ21 0-44	BC208 0-12	BF125 0-50	BF326 0-17	OC200 0-28	2N743 0-22	2N2952 0-16	2N3122 0-19	2N4094 0-19
AC188 0-24	BC107 0-10	BC209 0-13	BF127 0-55	BF329 0-17	OC201 0-31	2N744 0-22	2N2953 0-16	2N3123 0-19	2N4095 0-19
AC188K 0-22	BC108 0-10	BC212L 0-12	BF152 0-61	BF329 0-17	OC202 0-31	2N814 0-18	2N2954 0-16	2N3124 0-19	2N4096 0-19
ACV17 0-28	BC109 0-11	BC213L 0-12	BF153 0-50	BF330 0-28	OC203 0-28	2N814 0-33	2N2955 0-16	2N3125 0-19	2N4097 0-19
ACV18 0-28	BC113 0-11	BC214 0-16	BF154 0-50	BF331 0-28	OC204 0-28	2N814 0-33	2N2956 0-16	2N3126 0-19	2N4098 0-19
ACV19 0-22	BC114 0-17	BC225 0-28	BF155 0-77	BF332 0-28	OC206 0-39	2N814 0-33	2N2957 0-16	2N3127 0-19	2N4099 0-19
ACV20 0-22	BC115 0-17	BC227 0-12	BF156 0-53	BF333 0-28	OC207 0-39	2N814 0-33	2N2958 0-16	2N3128 0-19	2N4100 0-19
ACV21 0-22	BC116 0-17	BCY30 0-27	BF157 0-61	BF334 0-28	OC208 0-44	2N1131 0-22	2N2959 0-16	2N3129 0-19	2N4101 0-19
ACV22 0-18	BC117 0-17	BCY30 0-27	BF158 0-61	BF335 0-28	OC209 0-44	2N1132 0-24	2N2960 0-16	2N3130 0-19	2N4102 0-19
ACV27 0-20	BC118 0-11	BCY31 0-29	BF159 0-68	BF336 0-28	OC210 0-44	2N1133 0-24	2N2961 0-16	2N3131 0-19	2N4103 0-19
ACV28 0-21	BC119 0-33	BCY32 0-33	BF160 0-44	BF337 0-28	OC211 0-44	2N1134 0-24	2N2962 0-16	2N3132 0-19	2N4104 0-19
ACV29 0-39	BC120 0-88	BCY33 0-34	BF161 0-44	BF338 0-28	OC212 0-44	2N1135 0-24	2N2963 0-16	2N3133 0-19	2N4105 0-19
ACV30 0-31	BC121 0-13	BCY34 0-28	BF162 0-44	BF339 0-28	OC213 0-44	2N1136 0-24	2N2964 0-16	2N3134 0-19	2N4106 0-19
ACV31 0-31	BC122 0-20	BCY70 0-18	BF164 0-44	BF340 0-28	OC214 0-44	2N1137 0-24	2N2965 0-16	2N3135 0-19	2N4107 0-19
ACV34 0-23	BC132 0-13	BCY71 0-20	BF165 0-44	BF341 0-28	OC215 0-44	2N1138 0-24	2N2966 0-16	2N3136 0-19	2N4108 0-19
ACV35 0-23	BC134 0-20	BCY72 0-16	BF167 0-24	BF342 0-28	OC216 0-44	2N1139 0-24	2N2967 0-16	2N3137 0-19	2N4109 0-19
ACV36 0-31	BC135 0-13	BCZ10 0-22	BF173 0-24	BF343 0-28	OC217 0-44	2N1140 0-24	2N2968 0-16	2N3138 0-19	2N4110 0-19
ACV40 0-19	BC136 0-17	BCZ11 0-28	BF176 0-34	BF344 0-28	OC218 0-44	2N1141 0-24	2N2969 0-16	2N3139 0-19	2N4111 0-19
ACV41 0-30	BC137 0-17	BCZ12 0-28	BF177 0-39	BF345 0-28	OC219 0-44	2N1142 0-24	2N2970 0-16	2N3140 0-19	2N4112 0-19
ACV44 0-39	BC139 0-44	BD121 0-28	BF178 0-33	BF346 0-28	OC220 0-44	2N1143 0-24	2N2971 0-16	2N3141 0-19	2N4113 0-19
AD130 0-42	BC140 0-33	BD123 0-72	BF179 0-33	BF347 0-28	OC221 0-44	2N1144 0-24	2N2972 0-16	2N3142 0-19	2N4114 0-19
AD140 0-53	BC141 0-33	BD124 0-66	BF180 0-33	BF348 0-28	OC222 0-44	2N1145 0-24	2N2973 0-16	2N3143 0-19	2N4115 0-19
AD142 0-53	BC142 0-33	BD125 0-65	BF181 0-33	BF349 0-28	OC223 0-44	2N1146 0-24	2N2974 0-16	2N3144 0-19	2N4116 0-19
AD143 0-43	BC143 0-33	BD132 0-68	BF182 0-44	BF350 0-28	OC224 0-44	2N1147 0-24	2N2975 0-16	2N3145 0-19	2N4117 0-19
AD149 0-55	BC145 0-50	BD133 0-72	BF183 0-44	BF351 0-28	OC225 0-44	2N1148 0-24	2N2976 0-16	2N3146 0-19	2N4118 0-19
AD151 0-37	BC147 0-11	BD135 0-44	BF184 0-28	BF352 0-28	OC226 0-44	2N1149 0-24	2N2977 0-16	2N3147 0-19	2N4119 0-19

FULL RANGE OF ZENER DIODES
VOLTAGE RANGE
 2-23V, 400mV (DO-7 Case) 15p ea. 14W (Top Hat) 20p ea. 10W (SO-10 Stud) 33p ea. All fully tested 5% tol. and marked. State voltage required.

10 amp POTTED BRIDGE RECTIFIER
 on heat sink.
100PIV. 99p each

NEW LINE
 Plastic Encapsulated
2 Amp. BRIDGE RECTS.
 250 RMS 30 short
 100V RMS 41p
 400V RMS 51p
 Size 15 mm x 6 mm.

UNIJUNCTION
 UT46. Eqt. 2N2646.
 Eqt. T1843. BEN3000
 30p each, 25-99 28p
 100 UF 22p.

CADMIUM CELLS
 ORP12 48p
 ORP60, ORP61 45p each

GENERAL PURPOSE NPN SILICON SWITCHING TRANS. TO-18
 SIM. TO 2N706/8. BSY-27/28/5A. A.I.I. usable devices no open short circuits. ALSO AVAILABLE in PNP Sim. to 2N2906, BCY70. When ordering please state preference NPN or PNP.

20	For	0-55
50	For	1-10
100	For	1-12
500	For	8-25
1000	For	14-30

SIL. G.P. DIODES 4p
 300mV 30 .30-1.85
 40V(Min.) 100 .1-55
 50V(Min.) 500 .5-50
 Full Tested 1,000-9.90
 Ideal for Organ Builders.

TRIACS
 VBOM 2A 6A 10A
 TO-5 TO-6 TO-18
 4p 8p 10p
 100 33 55 83
 200 55 66 99
 400 77 83 121

FOR USE WITH TRIACS
 BR100 (D32) 41p each

FREE
 One 50p Pak of your own choice free with orders valued \$4 or over.

BRAND NEW TEXAS GERM. TRANSISTORS
 Coded and guaranteed
 Pak No. 2G3713 OC71
 T2 8D1374 OC75
 T3 8D1216 OC81D
 T4 8D2381T OC82
 T5 8D2382T OC82
 T6 8D2344B OC44
 T7 8D2345B OC45
 T8 8D2378 OC78
 T9 8D2399A 2N1302
 T10 8D2417 2N1307
 All 55p each pak.

2N3055
 115 Watt SIL POWER NPN
 55p EACH.

120 VCR NIXIE DRIVER
 Transistor. Sim. BSN21 & C407. 2N1883
 FULLY TESTED AND
 CODED. NPN 120V 2-24
 19p each. TO-5 NPN
 25 up 17p each.

Sil. trans. suitable for P.E. Organ. Metal TO-18 Eqt. 2N3000 6p each. Any Qty.

NEW EDITION 1972

TRANSISTOR EQUIVALENTS BOOK. A complete cross reference and equivalents book 160 European, American and Japanese Transistors. Exclusive to BI-PAK 90p each.

KING OF THE PAKS Unequalled Value and Quality
SUPER PAKS NEW BI-PAK UNTESTED SEMICONDUCTORS

Satisfaction GUARANTEED in Every Pak, or money back.

Pak No.	Description	Price
U 1	120 Glass Sub-Min. General Purpose Germanium Diodes	0-55
U 2	60 Mixed Germanium Transistors AF/RF	0-55
U 3	75 Germanium Gold Bonded Sub-Min. like OA5, OA47	

- the lowest prices!

74 Series T.T.L. I.C.'S

BI-PAK STILL LOWEST IN PRICE FULL SPECIFICATION
GUARANTEED. ALL FAMOUS MANUFACTURERS



1			25			100+			1			25			100+					
SN7400	0-17	0-16	0-13	SN7450	0-17	0-16	0-13	SN74141	0-74	0-71	0-64	SN74141	0-74	0-71	0-64	SN74141	0-74	0-71	0-64	
SN7401	0-17	0-16	0-13	SN7451	0-17	0-16	0-13	SN74145	£1.65	£1.54	£1.43	SN74145	£1.65	£1.54	£1.43	SN74145	£1.65	£1.54	£1.43	
SN7402	0-17	0-16	0-13	SN7453	0-17	0-16	0-13	SN74150	£2.30	£2.27	£2.75	SN74150	£2.30	£2.27	£2.75	SN74150	£2.30	£2.27	£2.75	
SN7403	0-17	0-16	0-13	SN7454	0-17	0-16	0-13	SN74151	£1.10	£1.05	0-99	SN74151	£1.10	£1.05	0-99	SN74151	£1.10	£1.05	0-99	
SN7404	0-17	0-16	0-13	SN7460	0-17	0-16	0-13	SN74153	£1.32	£1.21	£1.05	SN74153	£1.32	£1.21	£1.05	SN74153	£1.32	£1.21	£1.05	
SN7405	0-17	0-16	0-13	SN7470	0-32	0-29	0-27	SN74154	£1.98	£1.87	£1.78	SN74154	£1.98	£1.87	£1.78	SN74154	£1.98	£1.87	£1.78	
SN7406	0-39	0-34	0-31	SN7472	0-32	0-29	0-27	SN74155	£1.54	£1.43	£1.32	SN74155	£1.54	£1.43	£1.32	SN74155	£1.54	£1.43	£1.32	
SN7407	0-39	0-34	0-31	SN7473	0-41	0-39	0-35	SN74156	£1.54	£1.43	£1.32	SN74156	£1.54	£1.43	£1.32	SN74156	£1.54	£1.43	£1.32	
SN7408	0-20	0-19	0-18	SN7474	0-41	0-39	0-35	SN74157	£2.09	£1.98	£1.87	SN74157	£2.09	£1.98	£1.87	SN74157	£2.09	£1.98	£1.87	
SN7409	0-20	0-19	0-18	SN7475	0-60	0-48	0-46	SN74160	£1.98	£1.87	£1.76	SN74160	£1.98	£1.87	£1.76	SN74160	£1.98	£1.87	£1.76	
SN7410	0-17	0-16	0-13	SN7476	0-44	0-43	0-42	SN74161	£1.98	£1.87	£1.76	SN74161	£1.98	£1.87	£1.76	SN74161	£1.98	£1.87	£1.76	
SN7411	0-28	0-27	0-26	SN7480	0-74	0-71	0-64	SN74162	£4.40	£4.13	£3.85	SN74162	£4.40	£4.13	£3.85	SN74162	£4.40	£4.13	£3.85	
SN7412	0-39	0-34	0-31	SN7481	£1.32	£1.27	£1.21	SN74163	£4.40	£4.13	£3.85	SN74163	£4.40	£4.13	£3.85	SN74163	£4.40	£4.13	£3.85	
SN7413	0-32	0-29	0-27	SN7482	0-96	0-95	0-94	SN74164	£2.43	£2.37	£2.31	SN74164	£2.43	£2.37	£2.31	SN74164	£2.43	£2.37	£2.31	
SN7416	0-48	0-44	0-42	SN7483	£1.21	£1.16	£1.05	SN74165	£2.48	£2.42	£2.37	SN74165	£2.48	£2.42	£2.37	SN74165	£2.48	£2.42	£2.37	
SN7417	0-48	0-44	0-42	SN7484	£1.10	£1.05	0-99	SN74166	£2.85	£2.58	£2.30	SN74166	£2.85	£2.58	£2.30	SN74166	£2.85	£2.58	£2.30	
SN7420	0-17	0-16	0-13	SN7485	£3.96	£3.85	£3.74	SN74174	£2.53	£2.42	£2.31	SN74174	£2.53	£2.42	£2.31	SN74174	£2.53	£2.42	£2.31	
SN7422	0-55	0-53	0-50	SN7486	0-34	0-34	0-33	SN74175	£1.76	£1.65	£1.54	SN74175	£1.76	£1.65	£1.54	SN74175	£1.76	£1.65	£1.54	
SN7423	0-55	0-53	0-50	SN7489	£6.05	£5.78	£5.50	SN74182	£2.75	£2.64	£2.53	SN74182	£2.75	£2.64	£2.53	SN74182	£2.75	£2.64	£2.53	
SN7425	0-55	0-53	0-50	SN7490	0-74	0-71	0-64	SN74187	£2.75	£2.64	£2.53	SN74187	£2.75	£2.64	£2.53	SN74187	£2.75	£2.64	£2.53	
SN7426	0-60	0-46	0-44	SN7491	£1.10	£1.05	0-99	SN74189	£2.20	£2.16	£2.14	SN74189	£2.20	£2.16	£2.14	SN74189	£2.20	£2.16	£2.14	
SN7427	0-50	0-46	0-44	SN7492	0-74	0-71	0-64	SN74181	£6.05	£5.50	£5.23	SN74181	£6.05	£5.50	£5.23	SN74181	£6.05	£5.50	£5.23	
SN7428	0-77	0-72	0-66	SN7493	0-74	0-64	0-64	SN74182	£2.20	£2.16	£2.14	SN74182	£2.20	£2.16	£2.14	SN74182	£2.20	£2.16	£2.14	
SN7430	0-17	0-16	0-13	SN7494	0-85	0-82	0-75	SN74184	£3.85	£3.58	£3.30	SN74184	£3.85	£3.58	£3.30	SN74184	£3.85	£3.58	£3.30	
SN7432	0-50	0-46	0-44	SN7495	0-85	0-82	0-75	SN74190	£2.15	£2.09	£2.04	SN74190	£2.15	£2.09	£2.04	SN74190	£2.15	£2.09	£2.04	
SN7433	0-88	0-83	0-77	SM7496	0-96	0-93	0-86	SN74191	£2.09	£2.04	£1.98	SN74191	£2.09	£2.04	£1.98	SN74191	£2.09	£2.04	£1.98	
SN7437	0-71	0-68	0-66	SN74100	£1.82	£1.76	£1.71	SN74192	£2.15	£2.09	£2.04	SN74192	£2.15	£2.09	£2.04	SN74192	£2.15	£2.09	£2.04	
SN7438	0-71	0-68	0-66	SN74104	£1.07	£1.04	0-97	SN74193	£2.20	£2.16	£2.14	SN74193	£2.20	£2.16	£2.14	SN74193	£2.20	£2.16	£2.14	
SN7440	0-17	0-16	0-13	SN74105	£1.07	£1.04	0-97	SN74194	£2.97	£2.86	£2.75	SN74194	£2.97	£2.86	£2.75	SN74194	£2.97	£2.86	£2.75	
SN7441	0-74	0-71	0-64	SN74107	0-44	0-42	0-40	SN74195	£2.20	£2.09	£1.98	SN74195	£2.20	£2.09	£1.98	SN74195	£2.20	£2.09	£1.98	
SN7442	0-74	0-71	0-64	SN74110	0-61	0-59	0-55	SN74196	£1.88	£1.87	£1.76	SN74196	£1.88	£1.87	£1.76	SN74196	£1.88	£1.87	£1.76	
SN7443	£1.43	£1.38	£1.32	SN74111	£1.38	£1.27	£1.21	SN74197	£1.93	£1.87	£1.76	SN74197	£1.93	£1.87	£1.76	SN74197	£1.93	£1.87	£1.76	
SN7444	£1.43	£1.38	£1.32	SN74116	£1.10	£1.05	0-99	SN74198	£6.05	£5.50	£4.95	SN74198	£6.05	£5.50	£4.95	SN74198	£6.05	£5.50	£4.95	
SN7445	£1.98	£1.95	£1.93	SN74119	£1.49	£1.38	£1.21	SN74199	£6.05	£5.50	£4.95	SN74199	£6.05	£5.50	£4.95	SN74199	£6.05	£5.50	£4.95	
SN7446	£1.07	£1.04	0-97	SN74121	0-44	0-41	0-38	3 Terminal Pos Volt Reg. TO.3												
SN7447	£1.20	£1.07	£1.05	SN74122	£1.54	£1.43	£1.21	Plastic O/P 1.5 Amps. uA7805												
SN7448	£1.10	£1.07	£1.05	SN74123	£3.08	£2.87	£2.86	5V. & uA7812 12V. £1.76 each.												

The AL50 HI-FI AUDIO AMPL 50W pk 25w (RMS)

0-1% DISTORTION! HI-FI AUDIO AMPLIFIER

- Frequency Response 15Hz to 100,000-1dB.
- Load—3, 4, 8 or 16 ohms. ● Supply voltage 10-35 Volts.
- Distortion—better than 0-1% at 1kHz.
- Signal to noise ratio 90dB.
- Overall size 63 mm x 105 mm x 13 mm.

Tailor made to the most stringent specifications using top quality components and incorporating the latest solid state circuitry conceived to fill the need for all your A.F. amplification needs.
FULLY BUILT—TESTED—GUARANTEED.

BRITISH MADE. only £3.58 each



STABILISED POWER

MODULE SPM80

£3.25



AP80 is especially designed to power 2 of the AL50 Amplifiers, up to 15 watt (r.m.s.) per channel simultaneously. This module embodies the latest components and circuit techniques incorporating complete short circuit protection. With the addition of the Mains Transformer MT80, the unit will provide outputs of up to 1.5 amps at 35 volts. Size: 63 mm x 105 mm x 20 mm. These units enable you to build Audio Systems of the highest quality at a hitherto unobtainable price. Also ideal for many other applications including: Disco Systems, Public Address, Intercom Units, etc. Handbook available, 10p.

TRANSFORMER BMT80 £2.15 p. & p. 25p

NUMERICAL INDICATOR TUBES

MODEL	CD66	GR116	3015F Minitron
Anode voltage (Vdc)	170min	175min	5
Cathode Current (mA)	2-3	14	8
Numerical Height (mm)	16	13	9
Tube Height (mm)	47	32	22
Tube Diameter (mm)	19	13	12 wide
I.C. Driver Rec.	BP41/14 141	BP41 or 141	BP47
PRICE EACH	£1.87	£1.70	£1.60

All indicators 0-9 + Decimal point. All side viewing. Full data for all types available on request.

STEREO PRE-AMPLIFIER TYPE PA100

Built to a specification and NOT a price, and yet still the greatest value on the market, the PA100 stereo pre-amplifier has been conceived from the latest circuit techniques. Designed for use with the AL50 power amplifier system, this quality made unit incorporates no less than eight silicon planar transistors, two of these are specially selected low noise NPN devices for use in the input stages. Three switched stereo inputs, and rumble and scratch filters are features of the PA100, which also has a STEREO/MONO switch, volume, balance and continuously variable bass and treble controls.


SPECIFICATION:

- Frequency response 20Hz—20kHz ±1dB better than 0-1%
- Harmonic distortion 1-25mV into 50KΩ
- Inputs: 1. Tape head 35mV into 50KΩ
- 2. Radio, Tuner 1-5mV into 50KΩ
- 3. Magnetic P.U. 1-5mV into 50KΩ
- All input voltages are for an output of 250mV.
- Tape and P.U. inputs equalised to RIAA curve within ±1dB from 20Hz to 20kHz.
- Bass control ±10dB at 20Hz
- Treble control ±15dB at 20kHz
- Filters: Rumble (high pass) 100 Hz
- Scratch (low pass) 8kHz
- Signal/noise ratio better than +65dB
- Input overload +26dB
- Supply -35 volts at 20mA
- Dimensions 292 x 82 x 35 mm

SPECIAL COMPLETE KIT COMPRISING 2 AL50's, 1 SPM80, 1 BMT80 & 1 PA100 ONLY £25.30 FREE p.&p. only £13.15

The STEREO 20

The 'Stereo 20' amplifier is mounted, ready wired and tested on a one-piece chassis measuring 20 cm x 14 cm x 5.5 cm. This compact unit comes complete with on/off switch, volume control, balance, bass and treble controls. Attractively printed front panel and matching control knobs. The 'Stereo 20' has been designed to fit into most turntable plinths without interfering with the mechanism or, alternatively, into a separate cabinet. Output power 20w peak Input 1 (Cer.) 300mV into 1M



£13.47 free p. & p.

INTEGRATED CIRCUIT PAKS


Manufacturers "Fall Outs" which include Functional and Part-Functional Units. These are classed as 'out-of-spec' from the maker's very rigid specifications, but are ideal for learning about I.C.'s and experimental work.

Pak No.	Contents	Price	Pak No.	Contents	Price	Pak No.	Contents	Price
UIC00	—12 x 7400	0-55	UIC46	—5 x 7448	0-55	UIC90	—5 x 7490	0-55
UIC01	—12 x 7401	0-55	UIC48	—5 x 7448	0-55	UIC91	—5 x 7491	0-55
UIC02	—12 x 7402	0-55	UIC50	—12 x 7450	0-55	UIC92	—5 x 7492	0-55
UIC03	—12 x 7403	0-55	UIC51	—12 x 7451	0-55	UIC93	—5 x 7493	0-55
UIC04	—12 x 7404	0-55	UIC53	—12 x 7453	0-55	UIC94	—5 x 7494	0-55
UIC05	—12 x 7405	0-55	UIC64	—12 x 7454	0-55	UIC95	—5 x 7495	0-55
UIC06	—8 x 7406	0-55	UIC70	—12 x 7450	0-55	UIC96	—5 x 7496	0-55
UIC07	—8 x 7407	0-55	UIC72	—8 x 7472	0-55	UIC99	—5 x 7490	0-55
UIC10	—12 x 7410	0-55	UIC73	—8 x 7473	0-55	UIC121	—8 x 74121	0-55
UIC20	—12 x 7420	0-55	UIC74	—8 x 7474	0-55	UIC141	—8 x 74141	0-55
UIC30	—12 x 7430	0-55	UIC76	—8 x 7476	0-55	UIC151	—8 x 74151	0-55
UIC40	—12 x 7440	0-55	UIC80	—5 x 7480	0-55	UIC164	—5 x 74164	0-55
UIC41	—5 x 7441	0-55	UIC81	—5 x 7481	0-55	UIC193	—5 x 74193	0-55
UIC42	—5 x 7442	0-55	UIC82	—5 x 7482	0-55	UIC198	—5 x 74198	0-55
UIC43	—5 x 7443	0-55	UIC83	—5 x 7483	0-55			
UIC44	—5 x 7444	0-55	UIC85	—5 x 7485	0-55			
UIC45	—5 x 7445	0-55	UIC86	—				



I.L.P. (Electronics) Ltd

100 WATTS!



- ★ NO EXTERNAL COMPONENTS
- ★ MECHANICALLY & ELECTRICALLY ROBUST
- ★ INTEGRAL HEATSINK
- ★ HERMETICALLY SEALED UNIT
- ★ ATTRACTIVE APPEARANCE
- ★ LOW COST
- ★ BRITISH BUILT

With the development of the HY200, ILP bring you the first COMPLETE Hybrid Power Amplifier.

COMPLETE: because the HY200 uses no external components!

COMPLETE: because the HY200 is its own heatsink!

By the use of integrated circuit technique, using 27 transistors, the HY200 achieves total component integration. The use of specially developed high thermally conductive alloy and encapsulant is responsible for its compact size and robust nature.

The module is protected by the generous design of the output circuit, incorporating 25amp transistors. A fuse in the speaker line completes protection.

Only 5 connections are provided, input, output, power lines and earth.

Output Power: 100 watts RMS; 200 watts peak music power

Input Impedance: 10K Ω

Input Sensitivity: 0Dbm (0.775volt RMS)

Load Impedance: 4-16 Ω

Total Harmonic Distortion: less than 0.1% at 100 watts typically 0.05%

Signal: Noise: Better than 75Db relative to 100 watts

Frequency response: 10Hz-50KHz \pm 1Db

Supply Voltage: \pm 45volts

APPLICATIONS: P.A., Disco, Groups, Hi-Fi, Industrial.

PRICE: £14.90 inc. VAT & P & P


Trade applications welcomed

DELIVERY FROM JULY 1st

CROSSLAND HOUSE · NACKINGTON · CANTERBURY · KENT

CANTERBURY 63218

IP I.L.P. (Electronics) Ltd



THE HY41

The HY41 supersedes the popular HY40 introduced by ILP last year. This highly improved module achieves true High Fidelity with a dramatic reduction in distortion (typically 0.05% at 1KHz into 8 ohms!) and is electronically and mechanically compatible with the HY40.

With this important improvement the HY41 retains all of the quality characteristics found in the earlier version and P.C. board, Resistor, Capacitors, Hardware Mountings and comprehensive manual are included in the basic kit. No further components are required to construct a complete power amplifier of extremely high performance sufficiently versatile to provide power not merely for Hi-Fi but also for public address systems and industry.

The free manual gives a full circuit diagram of the HY41 and its various applications including a complete stereo amplifier.

Like its predecessor the HY41 is based on conventional and proven circuit techniques developed over recent years.

OUTPUT POWER: British Rating 40 WATTS PEAK, 20 watts R.M.S. continuous.

LOAD IMPEDANCE: 4-16 ohms.

INPUT IMPEDANCE: 30K ohms at 1KHz.

VOLTAGE GAIN: 30db at 1KHz

TOTAL HARMONIC DISTORTION: less than 0.15% (typical 0.05%) at 1KHz.

FREQUENCY RESPONSE: 5Hz-50KHz \pm 1db.

SUPPLY VOLTAGE: + 22.5volts D.C.

SUPPLY CURRENT: 0.8 amps maximum.

PRICE: inc. comprehensive manual, P.C. board, five extra components and P. & P.:-

MONO: £5.39

STEREO: £10.78 This is inclusive of V.A.T. plus P. & P.

UNIQUE HYBRID PRE-AMPLIFIER

The HY5 has rapidly established a position in the WORLD as the sole hybrid pre-amplifier to contain all feedback and equalization networks within an integrated pre-amplifier circuit.

Supplied with the HY5 are two stabilizing capacitors and by the addition of volume, treble and bass potentiometers it is ready for use.

Internally the HY5 provides equalization for almost every conceivable input, the desired function is achieved by use of a multi-way switch or by direct interconnection.

Two distinctive features of the HY5 are its inbuilt stabilization circuit, allowing it to be run off any unregulated power supply from 16-25 Volts and a balance circuit which, when linked by a balance control to a second HY5, forms a complete stereo pre-amplifier.

Specifically and critically designed to meet exacting Hi-Fi standards, the HY5 combines extremely low noise with a high overload capability. When used in conjunction with the HY41 and PSU45 forms a completely integrated system.

INPUTS

Magnetic Pick-up (within \pm 1db RIAA curve)
2mV. 47K Ω

Tape Replay (external components to suit head). 4mV. 47K Ω

Microphone (flat) 10mV. 47K Ω

Ceramic Pick-up (equalized and compensatable) 20-2000mV. variable.

Tuner (flat) 250mV. 100K Ω

Auxiliary 1 250mV. 47K Ω

Auxiliary 2 2-20mV. 100K Ω

ACTIVE TONE CONTROLS (Baxendall)

Treble + 12db.

Bass + 12db.

INTERNAL STABILIZATION


Enables the HY5 to share an unregulated supply with the Power Amplifier.

SUPPLY VOLTAGE

16-25 volts

PRICE: MONO: £3.96

STEREO: £7.92 This is inclusive of V.A.T. plus P. & P.




SUPPLY CURRENT

6mA approx.

OVERLOAD CAPABILITY

better than 26db on most sensitive input infinite on tuner and auxl.

OUTPUT NOISE VOLTAGE: 0.5mV.



POWER SUPPLY PSU45

The versatile P.S.U.45 is designed to supply your HY41's +HY5's in stereo or mono format.

Specification

Input: 200-240 Volts.

Output: \pm 22.5 Volts at 2 amps.

Overall Dimensions: L. 7"; D. 3.8"; H. 3.1"

PRICE: £4.95 This is inclusive of V.A.T. plus P. & P.

Please note we reserve the right to substitute at our discretion updated versions of advertised designs where applicable

CROSSLAND HOUSE · NACKINGTON · CANTERBURY · KENT

CANTERBURY 63218

G.W.S. G.W.S. SMITH & CO (RADIO) LTD

AUDIOTRONIC MODEL ATM.1

Top value 1000 o.p.v. pocket multimeter.
Ranges: 0/10/50/250/1000V AC and DC. DC Current 0-1mA/100mA. Resistance 0/150k ohms. Decibels -10 to +22dB. Size 90 x 60 x 28mm. Complete with test leads.
£2.50. Post 15p.



LT401 MULTIMETER

New style 20,000 o.p.v. pocket multimeter.
5/25/50/1250/2500V D.C.
10/50/100/500/1000V A.C.
50µA/250mA. 6K/6 meg ohms. -20 to +22db.
£3.75. Post 20p.



MODEL TH-12

20,000 o.p.v. Overload protection. Slide switch selector.
0/25/2.5/10/50/250/1000V D.C.
0/10/50/250/1000V A.C.
0/50µA/25/250mA D.C.
0/3K/30K/300K/3 meg. -20 to +50db.
£4.97. Post 15p.



RUSSIAN 22 RANGE MULTIMETER

Model U437 10,000 o.p.v. A first class versatile instrument manufactured in U.S.S.R. to the highest standards. Ranges: 2/5/10/50/250/500/1000V D.C. 2.5/10/50/250/500/1000V A.C. D.C. Current 100 µA/1/10/100 mA/1A. Resistance 300 ohms/3/30/300K/3MΩ. Complete with batteries, test leads, instructions and sturdy steel carrying case.
Our Price £5.97. Post 25p.



MODEL PL436

20kΩ/Volt D.C. 8kΩ/Volt A.C. Mirror scale. 6/3/12/30/120/600V D.C. 3/30/120/600V A.C. 50/600µA/60/600 mA. 10/100K/1 Meg/10 meg Ω. -20 to +46db. £8.97. Post 12p.



MODEL 500

30,000 O.P.V. with overload protection. mirror scale. 0/5/2.5/10/25/100/250/500/1,000 v. D.C. 0/2.5/10/25/100/250/500/1,000 v. A.C. 0/50µA/5/50/500mA. 12 amp. D.C. 0/50K/5 meg/50 meg Ω.
£8.95. Post 25p.
Leather case £1.75.




U432 MULTIMETER

Extremely sturdy instrument for general electrical use. 667 o.p.v. 0/3/1.5/7.5/30/60/150/300/600/900 VDC and 750V. 0/3/1.5/7.5/30/60/150/300/600/900 VAC. 0/300µA/1.5/6/15/60/150/600mA/1.5/6 AMP. D.C. 0/1.5/6/15/60/150/600mA/1.5/6 AMP. A.C. 0/200/3/3K/30K Ω. Accuracy DC 1% AC 1.5%. Knife edge pointer, mirror scale. Complete with sturdy metal carrying case, leads and instructions. £9.50. Post 25p.



H10K1 MODEL 700X

100,000 O.P.V. Overload protection. Mirror scale. 3/6/1.2/1.5/3/6/12/30/60/120/300/600/1200 VDC. 1.5/3/6/12/30/60/150/300/600/1200 VAC. 15/30V A.C. 3/30/60/150/300 mA. 6/12 AMP DC. 2K/200 K/2 Meg/20 megohm. -20 to +63db.
£13.50. Post 20p.



MODEL C-7080 EN

Giant 6in. mirror scale. 20,000 o.p.v.
0/25/12.5/10/50/250/1000/5000V D.C.
0/2.5/10/10/50/250/1000/5000V A.C.
0/50µA/1/10/100/500mA/10 amp. D.C.
0/2K/200K/2 meg. -20 to +50 db.
£13.95. Post 35p.



KAMODEN 72.200 MULTITESTER

High sensitivity tester. 200,000 o.p.v. Overload protection. Mirror scale. Ranges: 0/0.6/3/30/120/600/1200V D.C.
0/3/12/60/300/11.20KV A.C.
0/6µA/1.2mA/120mA/600mA/12A D.C.
0/12A A.C.
-20 to +63dB.
0/2K/200K/2 meg/200 meg ohms.
£16.95. Post 30p.



370 WTR MULTIMETER

Features A.C. current ranges. 20,000 o.p.v.
0/5/2.5/10/50/250/500/1000 V DC
0/2.5/10/50/250/500/1000 V AC
0/50µA/1/10/100mA/1/10 Amp DC.
0/100MA/1/10 Amp AC.
0/5K/50K/500K/5MEG/50MEG. -20 + 62 db.
£15. Post 25p.



TMK LAB TESTER

100,000 O.P.V. 6 1/2 in. Scale Buzzer Short Circuit Check. Sensitivity -100,000 OPV D.C. 5K/Volt A.C. D.C. Volts: 5, 2.5, 10, 50, 250, 1,000V. A.C. Volts: 3, 10, 50, 250, 500, 1,000V. D.C. Current: 10, 100µA, 10, 100, 500mA, 2.5, 10 amp. Resistance: 1K, 10K, 100K, 10MEG, 100MEG. Decibels: -10 to +49 db. Plastic Case with carrying handle. Size 7 1/4 x 6 1/2 x 3 1/4. £18.95. P & P. 25p.



MODEL S-100TR MULTIMETER/TRANSISTOR TESTER

100,000 o.p.v. MIRROR SCALE/OVERLOAD PROTECTION.
0/12-6/3/12/30/120/600 V DC.
0/6/30/120/600 V. AC.
0/12/600µA/12/300MA/12 AMP. DC.
0/0.5/1 MEG/100 MEG. -20 to +50 db. 0-01 -2 mtd. Transistor tester measures Alpha, beta and Ico. Complete with batteries, instructions and leads. £13.50. Post 25p.



LB4 TRANSISTOR TESTER

Tests PNP or NPN transistors. Audio indication. Operates on two 1.5v batteries. Complete with all instructions etc. £4.50. Post 20p.



LB3 TRANSISTOR TESTER

Tests Ico and B. PNP/NPN. Operates from 9v battery. Complete with all instructions etc. £3.95. Post 20p.



KAMODEN HM.350 TRANSISTOR TESTER

High quality instrument to test Reverse Leak current and DC current Amplification factor of PNP, NPN, transistors, diodes, SCR's etc. 4in. x 4 1/2in. clear scale meter. Operates from internal batteries. Complete with instructions leads and carrying handle. £12.50 Post 30p.



MODEL 49A IN CIRCUIT TRANSISTOR TESTER

Checks true A.C. beta in/out. Checks Ico. Checks diodes in/out. Checks SCR etc. Beta HI 10-500. LO-20. Ico 0-5000µA. 220/240V. A.C. operation. £17.50. Post 25p.



KAMODEN HM.720B F.E.T. V.O.M.

Input impedance 10 meg. ohms. Ranges: 0/25/1/2.5/10/50/250/1000V D.C.
0/2.5/10/50/250/1000V A.C.
0/25µA/2.5/25/250 MA D.C. -20 to +62db
0/5K/50K/500K/5 meg/500 meg ohms.
£14.95. Post 30p.



T.E.40 HIGH SENSITIVITY A.C. VOLTMETER

10 meg. input 10 ranges: 0/1.03/1.1/3/13/10/30/100/300 v. R.M.S. 4 cps.-1.2 Mc/s. Decibels -40 to +50 dB. Supplied brand new complete with leads and instructions. Operation 250 v. A.C. £17.50 Carr. 25p.



TE-65 VALVE VOLTMETER

High quality instrument with 28 ranges. D.C. volts 1.5-1,500 v. A.C. volts 1.5-1,500 v. Resistance up to 1,000 megohms. 220/240V. A.C. operation Complete with probe and instructions. £17.50. Post 30p. Additions. Probes available: R.F. £2.12 H.V. £2.50.



MODEL U4311 SUB-STANDARD MULTI-RANGE VOLT AMMETER

Sensitivity 330 ohms/Volt A.C. and D.C. Accuracy -5% D.C. 1% A.C. Scale length 185mm.
0/300/750µA/1.5/3/7.5/15/30/75/150/300/750mA/1.5/3/7.5 Amp. D.C. 0/3/7.5/15/30/75/150/300/750mA/1.5/3/7.5 Amp. A.C.
0/75/150/300/750mV/1.5/3/7.5/15/30/75/150/300 750V. D.C.
0/750mV/1.5/3/7.5/15/30/75/150/300/650V. A.C. Automatic cut out. Supplied complete with test leads, manual and test certificates. £49. Post 50p



TMK MODEL 117 ELECTRONIC VOLTMETER

Battery operated. 11 meg input. 26 ranges. Large 4 1/2in. mirror scale. Size 5 1/2 x 4 1/2 x 2 1/2in. DC Volts 0.3-1200V. AC Volts 3-300V RMS. 8.0-800V. P-P. DC Current -12.2MA. Resistance up to 2000Ω ohm. Decibels -20 to +11 db. Complete with leads/instructions. £17.50. P & P. 20p.



MODEL L-55 FET V.O.M.

Input impedance 10 meg. ohms.
0/3/1.2/6/30/120/600V. D.C.
0/3/12/60/120/600V. A.C.
0/120µA/120mA. D.C.
0/1K/100K/10 meg/100 meg ohms. £15.97. Post 25p.



KAMODEN HMG-500 INSULATION RESISTANCE TESTER

Range 0-1000 Meg-ohms, 500 Volt. Battery operated. Wide range clear meter 4 1/2in. x 4 1/2in. Complete with deluxe carrying case, batteries, instructions. £19.95. Post 30p.



BELCO AF-5A SOLID STATE SINE SQUARE WAVE C.R. OSCILLATOR

Sine 18-200,000 Hz; Square 18-50,000 Hz
Output max. +10 dB (10 K ohms). Operation internal batteries. Attractive 2-tone case. 7 1/2in. x 5in. x 2in. Price £17.50 Carr. 17p.



CI-5 PULSE OSCILLOSCOPE

For display of pulsed and periodic waveforms in electronic circuits. VERT. AMP. Bandwidth 10MHz. Sensitivity at 100KHz V RMS/mm. 1-25; HOR. AMP. Bandwidth 500KHz. Sensitivity at 100KHz, V RMS/mm. 3-25; Preset triggered sweep 1-3.000µsec.; free running 20-200,000µsec in nine ranges. Calibrator pips. 220 x 360 x 430mm. 115-230V. A.C. operation. £39.00. Carr. paid.



TO-3 PORTABLE OSCILLOSCOPE 3in. TUBE

Y amp. Sensitivity. 1v p-p/CM. Bandwidth 1.5 cps -1.5 MHz. Input Imp. 2 meg Ω. 25 PF. X amp sensitivity. -9v p-p/KHz. bandwidth 1.5 cps-800 KHz. Input Imp. 2 meg Ω 20 PF. Time base. 5 ranges 10 cps-300 KHz. Synchronization. Internal/external. Illuminated. 140 x 115 x 130mm. Weight 15lbs. £20/240 V. A.C. Supplied brand new with handbook £47.50. Carr. 50p.



RUSSIAN CI-16 DOUBLE BEAM OSCILLOSCOPE

5 mcs Pass Band. Separate Y1 and Y2 amplifiers. Rectangular 5in. x 4in. C.R.T. Calibrated triggered sweep from 2 µsec. to 100 mill-sec. per cm. Free running time base 50-1 mcs. Built-in time base calibrator and amplitude calibrator. Supplied complete with all accessories and instruction manual. £87 Carr. paid.



MODEL AT201 DECADE ATTENUATOR

Frequency range: 0-200KHz. Attenuator: 0-11db, 0-1db. step. Impedance 600 ohms. Max. input power 30dbm. Size 180 x 90 x 55mm. £12.50. Post 37p.



ARF-300 AF/RF SIGNAL GENERATOR

All transistorised, compact, fully portable. AF sine wave 18Hz. to 220KHz. AF square wave 18Hz. to 100KHz. Output sine/square 10v. P-P. RF 100KHz. to 200 MHz. Output 1v. maximum. Operation 220/240V. A.C. Complete with instructions and leads. £29.95. Post 50p.



TE-20 DRF SIGNAL GENERATOR

Accurate wide range signal generator covering 120 Kc/s-500 Mc/s on 6 bands. Directly calibrated Variable R.F. attenuator, audio output. Xtal socket for calibration. 220/240V. A.C. Brand new with instructions. Size 140 x 215 x 170 mm. £17.50. Carr. 37p.



TE22 SINE SQUARE WAVE AUDIO GENERATORS

Sine: 20 cps to 200 kc/s. on 4 bands. Square 20 cps to 30 kc/s. Output impedance 5,000 ohms, 200/250 v. A.C. operation. Supplied brand new and guaranteed with instruction manual and leads. £17.50. Carr. 37p.



230V/240V SMITHS SYNCHRONOUS GEARED MOTORS

Built-in gearbox. All brand new and boxed. 30 RPH CW; 2 RPH CW; 20 RPH CW; 2 RPH ACW; 30 RRH CW. 50p each. Post 12p.



230 VOLT A.C. 50 c/s RELAYS

Brand new. 3 sets of changeover contacts at 5 amp rating. 50p each. Post 10p (100 lots £40). Quantities available.



MODEL TE-15 GRID DIP METER

Transistorised. Operates as Grid Dip, Oscillator, Absorption Wave Meter and Oscillating Detector. Frequency range 430Kc/s-280Mc/s in 6 coils. 500µA Meter. 9V. battery operation. Size 180 x 80 x 40mm. £15.00. Post 20p.



"YAMABISHI" VARIABLE VOLTAGE TRANSFORMERS

Excellent quality at low cost. All models—Input 230V. 50/60 c/s. Variable output 0-250V.

MODEL S-260 GENERAL PURPOSE BENCH MOUNTING

1 Amp	£7.00
2.5 Amp	£8.05
5 Amp	£11.75
8 Amp	£15.90
10 Amp	£22.50
12 Amp	£23.60
20 Amp	£24.00
25 Amp	£25.00
40 Amp	£29.50

MODEL S-260B

Panel Mounting.
1 Amp £7.00
2.5 Amp £8.05
Carriage and Packing Extra



AUTO TRANSFORMERS

0/115/230V. Step up or step down. Fully shrouded.	
80 W	£2.10 P. & P. 18p
150 W	£2.70 P. & P. 18p
300 W	£3.60 P. & P. 23p
500 W	£5.25 P. & P. 35p
1000 W	£7.50 P. & P. 35p
1500 W	£10.20 P. & P. 45p
2250 W	£17.25 P. & P. 50p
5000 W	£35.00 P. & P. £1

MCA. 220 AUTO-MATIC VOLTAGE STABILISER

Input 88-125 VAC or 176-250VAC. Output 120VAC or 240VAC. 200VA rating. £11.97. Carr. 50p.



ALL PRICES ARE EXCLUSIVE OF 10% V.A.T.



JOSTYKIT
WE ARE
APPOINTED
STOCKISTS
AT ALL
BRANCHES

HIGH QUALITY CONSTRUCTION KITS

- AF20 Mono Transistor Amplifier £4.80
 - AF30 Mono Transistor Pre-Amplifier £2.61
 - AF310 Mono Amplifier (for Stereo use two) £5.91
 - AT5 Automatic Light Control £2.58
 - AT30 Photo Cell Switching Unit £5.70
 - AT50 400 Watt Triac Light Dimmer Speed Control £4.80
 - AT55 1.300 Watt Triac Light Dimmer Speed Control £5.70
 - AT58 2.300 Watt Triac Light Dimmer Speed Control £6.90
 - AT60 Psychedelic Light Control, Single Channel £7.80
 - AT65 Psychedelic Light Control, 3 Channel £14.55
 - HF61 Medium Wave Transistor Radio £3.33
 - HF65 P.M. Transistor Transmitter £2.70
 - HF75 P.M. Transistor Receiver £2.88
 - HF10 F.M. Tuner Unit £15.81
 - HF25 De-Luxe P.M. Tuner Unit £24.12
 - HF30 Stereo Decoder for use with HF310 or HF25 £9.96
 - HF35 Aerial Amplifier for AM/FM Bands I, II and III £1.77
 - GP310 Stereo Pre-Amp to use with 2, AF310 £21.27
 - GU30 Tremolo Unit for guitars, etc. £7.50
 - NT10 12V Unstab. Professional Stabilized Power Supply 2 x 30 V, 2.2 amp. £12.51
 - NT30 Transistor Converter 12/15V, AC/DC to 6V, 7.5V, or 9V DC £4.50
 - NT310 Power Supply 240V AC to 2 x 18V DC at 2 amps. £4.80
 - NT315 Power Supply 240V AC to 4.5-15V DC, 500 mA £9.57
- Post and Packing 15p per kit
Complete with comprehensive, easy to follow instructions and covered by full guarantee.

RP.214 REGULATED P.S.U.

Solid state. Variable output 0-24V DC up to 1 amp. Dual scale meter to monitor voltage and current. Input 220/240V AC. Size 185 x 85 x 105mm. £8.97 Post 25p.



PS.200 REGULATED P.S.U.

Solid state. Variable output 5-20 volt D.C. up to 2 amp. Independent meters to monitor voltage and current. Output 220/240 V. A.C. Size 7 1/2" x 5 1/2" x 3 1/2". £19.95. Post 25p.



PS.1000B REGULATED P.S.U.

Solid state. Output 6-9 or 12 V. D.C. up to 3 amps. Meter to monitor current. Input 220/240 V. A.C. Size 4" x 3 1/2" x 6 1/2". £11.97. Post 25p.



240° WIDE ANGLE 1mA METERS
MW1-6 60mm. square £3.97
MW1-8 80mm. square £4.97
Post extra.



POWER RHEOSTATS
High quality ceramic construction. Windings embedded in vitreous enamel. Heavy duty brush wiper. Continuous rating. Wide range available ex-stock. Single hole fixing, jin. dia. shaft. Bulk quantities available.



25 WATT. 10/25/50/100/250/500/1000 ohms. 95p. P. & P. 10p.
50 WATT. 10/25/50/100/250/500/1000/2500 or 5000 ohms. £1.35. P. & P. 10p.
100 WATT. 1/5/10/25/50/100/250/500/1000 or 2500 ohms. £1.95. P. & P. 15p.

HAND HELD 2-WAY WALKIE TALKIES



100 mW. £24.95 Pair. Post 50p.
2 channel 300 mW. £52.50 Pair. Post 50p.
3 channel 1 watt. £71.25 Pair. Post 50p.

Battery operation. Volume and squelch controls. Call button and press to talk button. Telescopic aerial. Complete with carrying cases.

Note: Licence required in U.K.

SEW CLEAR PLASTIC PANEL METERS
USED EXTENSIVELY BY INDUSTRY, GOVT. DEPTS., EDUCATIONAL AUTHORITIES, etc.
Over 200 ranges in stock—other ranges to order. Quantity discounts available. Send for fully illustrated brochure.

TYPE SW.100 100 x 80mm

100µA	£3.95
100-0-100µA	£3.80
500µA	£3.70
1mA	£3.60
20V. D.C.	£3.60
50V. D.C.	£3.60
300V. D.C.	£3.60
1 amp. D.C.	£3.60
5 amp. D.C.	£3.60
300V. A.C.	£3.70
VC Meter	£4.30

TYPE SD.830 82.5mm x 110mm Fronts

10mA	£3.10
50mA	£3.10
100µA	£3.10
500µA	£3.10
1 amp.	£3.10
5 amp.	£3.10
10 amp.	£3.10
5V. D.C.	£3.10
10V. D.C.	£3.10
20V. D.C.	£3.10
50V. D.C.	£3.10
300V. D.C.	£3.10
15V. A.C.	£3.30
300V. A.C.	£3.30
5mA	£3.10
VC Meter	£3.50


TYPE SD.640 63.5mm x 85mm Fronts

50µA	£3.05
50-0-50µA	£3.05
100µA	£3.00
100-0-100µA	£3.00
200µA	£3.00
500µA	£2.95
1mA	£2.90
5mA	£2.90
10mA	£2.90
100µA	£2.90
500µA	£2.90
1 amp.	£2.90
5 amp.	£2.90
10 amp.	£2.90
5V. D.C.	£2.90
10V. D.C.	£2.90
20V. D.C.	£2.90
50V. D.C.	£2.90
300V. D.C.	£2.90
15V. A.C.	£3.00
300V. A.C.	£3.00
VC Meter	£3.15

TYPE SD.460 46mm x 59.5mm Fronts

50µA	£2.80
50-0-50µA	£2.80
100µA	£2.75
100-0-100µA	£2.75
200µA	£2.70
500µA	£2.65
1mA	£2.60
5mA	£2.60
10mA	£2.60
100µA	£2.60
500µA	£2.60
1 amp.	£2.60
5 amp.	£2.60
10 amp.	£2.60
5V. D.C.	£2.60
10V. D.C.	£2.60
20V. D.C.	£2.60
50V. D.C.	£2.60
300V. D.C.	£2.60
15V. A.C.	£2.70
300V. A.C.	£2.70
VC Meter	£2.80

"SEW" EDGWISE METERS TYPE P.E.70



3 17/32in. x 1 15/32in. x 2 1/2 in. deep.

50µA	£3.75
50-0-50µA	£3.60
100µA	£3.60
100-0-100µA	£3.50
200µA	£3.40
500µA	£3.20
1mA	£3.20
300V. A.C.	£3.25
VC Meter	£3.85

*** MOVING IRON— ALL OTHERS MOVING COIL**

Please add postage

TYPE MR.85P 4 1/2in. x 4 1/2in. fronts.

10mA	£3.90
50mA	£3.90
100µA	£3.90
500µA	£3.90
1 amp.	£3.90
5 amp.	£3.90
15 amp.	£3.90
30 amp.	£3.95
20V. D.C.	£3.90
50V. D.C.	£3.90
150V. D.C.	£3.90
300V. D.C.	£3.90
100µA	£4.40
50-0-50µA	£4.25
100µA	£4.25
100-0-100µA	£4.05
200µA	£4.05
500µA	£3.90
5000-500µA	£3.90
1mA	£3.90
1-0-1mA	£3.90
5mA	£3.90
10mA	£3.90
50mA	£3.90
100µA	£3.90
100-0-100µA	£2.95
500µA	£2.65
1mA	£2.50
5mA	£2.50
10mA	£2.50
50µA	£2.50
1 amp.	£2.50
5 amp.	£2.50
10V. D.C.	£2.50
20V. D.C.	£2.50
50V. D.C.	£2.50
300V. D.C.	£2.50
15V. A.C.	£2.60
300V. A.C.	£2.60
8 Meter 1mA	£2.60
VC Meter	£3.60
1 amp. A.C.*	£2.50
5 amp. A.C.*	£2.50
10 amp. A.C.*	£2.50
20 amp. A.C.*	£2.50
30 amp. A.C.*	£2.50

TYPE MR.52P 2 1/2in. square fronts.

50µA	£3.50
50-0-50µA	£3.05
100µA	£3.00
100-0-100µA	£2.95
500µA	£2.65
1mA	£2.50
5mA	£2.50
10mA	£2.50
50µA	£2.50
1 amp.	£2.50
5 amp.	£2.50
10V. D.C.	£2.50
20V. D.C.	£2.50
50V. D.C.	£2.50
300V. D.C.	£2.50
15V. A.C.	£2.60
300V. A.C.	£2.60
8 Meter 1mA	£2.60
VC Meter	£3.60
1 amp. A.C.*	£2.50
5 amp. A.C.*	£2.50
10 amp. A.C.*	£2.50
20 amp. A.C.*	£2.50
30 amp. A.C.*	£2.50

TYPE MR.65P 3 1/2in. x 3 1/2in. fronts

50µA	£3.70
50-0-50µA	£3.15
100µA	£3.15
100-0-100µA	£3.10
200µA	£3.05
500µA	£2.75
500-0-500µA	£2.60
1mA	£2.60
5mA	£2.60
10mA	£2.60
50µA	£2.60
100µA	£2.60
1 amp.	£2.60
5 amp.	£2.60
10 amp.	£2.60
15 amp.	£2.60
20 amp.	£2.60
30 amp.	£2.60
50 amp.	£2.60
5V. D.C.	£2.60
10V. D.C.	£2.60
20V. D.C.	£2.60
50V. D.C.	£2.60
150V. D.C.	£2.60
300V. D.C.	£2.60
500V. A.C.	£2.60
300V. A.C.	£2.60
500V. A.C.	£2.60
8 Meter 1mA	£2.60
VC Meter	£3.70
50µA A.C.*	£2.60
100µA A.C.*	£2.60
200µA A.C.*	£2.60
500µA A.C.*	£2.60
1 amp. A.C.*	£2.60
5 amp. A.C.*	£2.60
10 amp. A.C.*	£2.60
20 amp. A.C.*	£2.60
30 amp. A.C.*	£2.60

"SEW" EDUCATIONAL METERS

TYPE ED.107



Size overall 100mm x 90mm x 108mm.

A new range of high quality moving coil instruments ideal for school experiments and other bench applications. The meter movement is easily accessible to demonstrate internal working.

Available in the following ranges—
50µA £6.90
100µA £6.40
1mA £5.95
50-0-50µA £6.40
1-0-1mA £5.95
1A D.C. £5.95
5A D.C. £5.95
10V. D.C. £5.95
20V. D.C. £5.95
50V. D.C. £5.95
300V. D.C. £5.95
Dual range
500µA/5A D.C. £7.00
5V/50V. D.C. £7.00

TYPE MR.36P 1 21/32in. square fronts.

150µA	£2.25
200µA	£2.25
300µA	£2.25
500µA	£2.25
750µA	£2.25
1 amp.	£2.25
2 amp.	£2.25
5 amp.	£2.25
10 amp.	£2.25
3V. D.C.	£2.25
10V. D.C.	£2.25
15V. D.C.	£2.25
20V. D.C.	£2.25
50V. D.C.	£2.25
100V. D.C.	£2.25
150V. D.C.	£2.25
300V. D.C.	£2.25
500V. D.C.	£2.25
750V. D.C.	£2.25
15V. A.C.	£2.30
50V. A.C.	£2.30
150V. A.C.	£2.30
300V. A.C.	£2.30
500V. A.C.	£2.30
8 Meter 1mA	£2.30
VC Meter	£2.65

TYPE MR.45P 2in. square fronts.

50µA	£2.70
50-0-50µA	£2.65
100µA	£2.60
100-0-100µA	£2.60
200µA	£2.50
500µA	£2.45
500-0-500µA	£2.45
1mA	£2.40
5mA	£2.40
10mA	£2.40
50µA	£2.40
100µA	£2.40
500µA	£2.40
1 amp.	£2.40
5 amp.	£2.40
10V. D.C.	£2.40
20V. D.C.	£2.40
50V. D.C.	£2.40
300V. D.C.	£2.40
15V. A.C.	£2.40
300V. D.C.	£2.40
8 Meter 1mA	£2.40
VC Meter	£2.70
1 amp. A.C.*	£2.40
5 amp. A.C.*	£2.40
10 amp. A.C.*	£2.40
20 amp. A.C.*	£2.40
30 amp. A.C.*	£2.40

"SEW" BAKELITE PANEL METERS

TYPE MR.65 3 1/2in. square fronts.



1 amp.	£2.60
5 amp.	£2.60
15 amp.	£2.60
30 amp.	£2.60
50 amp.	£2.60
5V. D.C.	£2.60
10V. D.C.	£2.60
20V. D.C.	£2.60
50V. D.C.	£2.60
150V. D.C.	£2.60
300V. D.C.	£2.60
50V. A.C.*	£2.65
50V. A.C.*	£2.65
150V. A.C.*	£2.65
300V. A.C.*	£2.65
500µA A.C.*	£2.60
1 amp. A.C.*	£2.60
5 amp. A.C.*	£2.60
10 amp. A.C.*	£2.60
20 amp. A.C.*	£2.60
30 amp. A.C.*	£2.60
50 amp. A.C.*	£2.60
VC Meter	£3.85
100 mV D.C.	£2.90
500µA	£2.60
500-0-50µA	£2.60
100µA	£2.60
100-0-100µA	£3.00
500µA	£2.70
500-0-500µA	£2.70
1mA	£2.60
5mA	£2.60
10mA	£2.60
50µA	£2.60
100µA	£2.60
500µA	£2.60
1 amp.	£2.60
5 amp.	£2.60
10 amp.	£2.60
20 amp.	£2.60
30 amp.	£2.60
50 amp.	£2.60
50µA	£2.60
100µA	£2.60
500µA	£2.60
1 amp.	£2.60
5 amp.	£2.60
10 amp.	£2.60
20 amp.	£2.60
30 amp.	£2.60
50 amp.	£2.60
50µA	£2.60
100µA	£2.60
500µA	£2.60
1 amp.	£2.60
5 amp.	£2.60
10 amp.	£2.60
20 amp.	£2.60
30 amp.	£2.60
50 amp.	£2.60
50µA	£2.60
100µA	£2.60
500µA	£2.60
1 amp.	£2.60
5 amp.	£2.60
10 amp.	£2.60
20 amp.	£2.60
30 amp.	£2.60
50 amp.	£2.60
50µA	£2.60
100µA	£2.60
500µA	£2.60
1 amp.	£2.60
5 amp.	£2.60
10 amp.	£2.60
20 amp.	£2.

GWS C.W. SMITH & CO (RADIO) LTD

EMI LOUDSPEAKERS

Model 350. 1 1/2in. x 8in. with single tweeter/crossover. 20-20,000 Hz. 15 watt RMS. Available 8 or 15 ohms. £7-25 each. P. & P. 37p.
Model 450. 1 1/2in. x 8in. with twin tweeters/crossover. 55-13,000 Hz. 8 watts RMS. Available 8 or 15 ohms. £3-62 each. P. & P. 25p.

SPECIAL OFFER!

STEREO SPEAKERS

Matched pair of bookshelf speakers. De luxe teak veneered finish. Size 1 1/2in. x 9in. x 7 1/2in. 8 ohms. 8 watts RMS. 16 watts peak. Complete with DIN lead.

OUR PRICE **£12-95** Carr. 50p

HA-10 STEREO HEADPHONE AMPLIFIER

All silicon transistor amplifier operates from magnetic, ceramic or tuner inputs with twin stereo headphone outputs and separate volume controls for each channel. Operates from 9 v. battery. Inputs 5MU/100MU. Output 60mW.

OUR PRICE **£6-97** P. & P. 20p

MP7 MIXER PREAMPLIFIER

5 microphone inputs each with individual gain controls enabling complete mixing facilities. Battery operated. 9 1/2" x 5" x 3". Inputs Mics: 3 x 3mV 50K; 2 x 3mV 600 ohm. Phono mag. 4mV 50K. Phono ceramic 100mV 1 meg. Output 250mV 100K.

OUR PRICE **£8-97** P. & P. 20p

1021 STEREO LISTENING STATION

For balancing and gain selection of loudspeakers with additional facilities for stereo headphone switching. 2 gain controls, speaker on-off slide switch, stereo headphone sockets. 6in. x 4in. x 2 1/2in.

OUR PRICE **£2-25** P. & P. 20p

FM TUNER CHASSIS

6 TRANSISTOR HIGH QUALITY TUNER. SIZE ONLY 6in. x 4in. x 2 1/2in. 3 I.F. stages. Double tuned discriminator. Ample output to feed most amplifiers. Operates on 9 volt battery. Coverage 88-108 Mc/s. Ready built ready for use. Fantastic value for money.

OUR PRICE **£5-95** P. & P. 20p

STEREO MULTIPLEX ADAPTOR £4-97.

ALL PRICES ARE EXCLUSIVE OF 10% V.A.T.

ALSO SEE PREVIOUS PAGES

SH628 STEREO HEADPHONES



Outstanding value. Soft earpads, adjustable headband. 8-16 ohms. 20-20,000 Hz. Complete with lead and stereo plug.

OUR PRICE **£1-87** P. & P. 30p

LIGER LHO2S STEREO HEADPHONES



Lightweight headphones with padded earpieces. 4-16 ohms. 20-20,000 Hz. Complete with 6ft cord and plug.

OUR PRICE **£1-95** P. & P. 30p

TE1018 DE-LUXE MONO HIGH IMPEDANCE HEADSET



Sensitive magnetic headset with soft earpads. Impedance 2,600 ohms (d.c. 600 ohms). Frequency response 200-1000 Hz.

OUR PRICE **£2-25** P. & P. 30p

SDH8V MONO/STEREO HEADPHONES



Two way stereo/mono with volume controls. Padded headband. 4-16 ohms. 20-18,000 Hz. Complete with lead and stereo plug.

OUR PRICE **£4-97** P. & P. 30p

BH001 HEADSET AND BOOM MICROPHONE



Moving coil. Headphone imp. 16 ohms. Mike imp. 200 ohms. Ideal for language teaching, communications etc. Complete with leads and plugs.

OUR PRICE **£4-95** P. & P. 30p

DH.08S Stereo Headphones



De luxe model with unique 2 way mechanical units and volume controls. 8 ohms. 20-20,000 Hz. Complete with coil lead and stereo jack plug.

OUR PRICE **£7-97** P. & P. 30p

4-CHANNEL STEREO HEADPHONES



TTC G3600 - Soft vinyl covered head cushion and earphones. Each earpiece incorporates two 2" speaker units. Fitted 2/4 channel changeover switch. Impedance 4-16 ohm. Frequency response 20-20,000 Hz. Complete with 15ft. coiled lead fitted two stereo plugs.

OUR PRICE **£9-95** P. & P. 30p

EA41 REVERBERATION AMPLIFIER

Self contained, transistorised, battery operated. Simply plug in microphone, guitar, etc., and output into your amplifier. Volume control, depth of reverberation control. Beautiful walnut cabinet. 7 1/4 x 3 x 4 1/2in.

OUR PRICE **£7-50** P. & P. 15p

AUDIOTRONIC

Audiotronic Products are manufactured exclusively for the Audiotronic Group of Companies and as a member of the group we are pleased to offer you this fabulous range of high quality equipment. Made to our own specifications each item provides outstanding performance and reliability at a value for money price!

TAPE CASSETTE



Top Hi-Fi quality in library cases

Type	5	10	25
C60	£1-20	£2-53	£5-99
C90	£1-65	£3-62	£8-59
CR20	£2-59	£4-48	£10-63
CR60	£3-41	£6-72	£16-63
CR90	£4-63	£9-10	£23-80
TAPE HEAD CLEANER	30p each		

P. & P. 15p for 5; 10 and over post free.

8-TRACK BLANK TAPES

Type	1	5	10
40M	75p	£3-50	£8-50
60M	90p	£4-70	£8-90

P. & P. 5p.; 5 and over post free.

ACR.14 BATTERY/MAINS CASSETTE RECORDER

Portable twin track mono recorder with automatic recording level control. Built-in speaker. Earpiece socket. Input for radio or record player. Fast forward and rewind. Output 500mW. AC 220/240v. or 6v. DC operation. Complete with remote control microphone, mains lead, earpiece and batteries.

OUR PRICE **£10-50** P. & P. 50p

SPORTSMAN AM/FM PORTABLE RADIO MODEL AR.1000

5 wavebands covering AM 535-1065KHz. FM 88-107MHz. AIR 102-135MHz. PB 147-174MHz. WB 162.5MHz. Large horizontal slide dial with logging scale. Slider volume and squelch controls. 7 section telescopic aerial for FM. FM and built-in ferrite bar for AM. AFC. 3in. speaker. Earpiece socket. Green leatherette covered cabinet with metal side panels. Size 152 x 79 x 219mm. Battery/mains operation.

OUR PRICE **£11-50** P. & P. 35p

MULTIBAND RADIO AMB 500

5 wavebands covering MW 535-1605KHz and FM 88-175MHz. All transistor. Battery or mains operation. Built in aerial and 8 section telescopic aerial for aerial. Complete with batteries, shoulder strap and earpiece.


OUR PRICE **£6-95** P & P 35p

PORTABLE RADIO AMR-9000 GLOBAL AM/FM

10 wavebands covering: AM: 535-1605 KHz. LW: 150-380 KHz. MR 1.6-4 MHz. SW1: 5.9-18.9 MHz. SW2: 8.0-1.6 MHz. SW3: 16-24 MHz. PSB1: 30-50 MHz. PSB2: 148-174 MHz. FM 88-108 MHz. AIR: 108-136 MHz. Features time zone map and timing dial. Large clear scale. Telescopic aerial and built in aerial. AFC on FM. 6in. x 4in. speaker and personal earpiece. Battery/mains operation. Size: 345 x 133 x 305mm.

OUR PRICE **£36-00** P. & P. 50p

STEREO CASSETTE DECK ACD.660



A beautifully styled 4-track stereo deck with an outstanding specification offered at a remarkably low price. Incorporates a host of features including switchable noise filter, normal/chrome tape selector, twin VU meter, slider record/playback level controls, front panel headphone socket, recording indicator lamp, phono/Din line input sockets, 3.5 mm. mike input sockets etc., etc. Frequency response 100-8KHz (100-12KHz Cr02) S/N -45dB. Crosstalk -45dB. Separation -35dB. Noise limiter -6dB at 10KHz. Complete with phono connecting leads.

OUR PRICE **£39-50** P. & P. 50p

IN-CAR EQUIPMENT



ACP.8 8-TRACK PLAYER

Attractive black and silver finish. 12v. neg. earth slider controls for Volume, Tone and Balance. Channel selector button with red pilot lamp. Complete with speakers, mounting brackets and instructions.

OUR PRICE **£12-50** P. & P. 40p

ACR 3500 CAR RADIO

Manual tuning of Medium and Long waves. 12v. pos. or neg. earth. Complete with speaker, mounting brackets and instructions.

OUR PRICE **£6-50** P. & P. 50p

ACR1 PUSH BUTTON CAR RADIO

Push button tuning of one LW and five MW stations of your choice. 12v. pos. or neg. earth. Complete with speaker, mounting brackets and instructions.

OUR PRICE **£8-95** P. & P. 50p

ACA 5SE ELECTRIC CAR AERIAL

5 section. Fully automatic. 12v. DC. Extends to approx. 40in. Complete with switch, all leads and instructions.

OUR PRICE **£5-95** P. & P. 50p

STEREO HEADPHONES

LSH.20 Individual volume controls. Stereo mono switch. 8 ohms. 40-19,000 Hz. £3-50. P & P 30p.
LSH.40 Two way system. Individual volume controls. 8 ohms. 20-20,000 Hz. £6-95. P & P 30p.
LSH.50 Professional Quality Electrostatic. Complete with self powered amplifier and control unit with headphone/speaker selector. 4-32 ohms. 20-24,000 Hz. £15.95. P & P 30p.



DOLBY 'B' NOISE REDUCTION UNITS

Reduce tape hiss by 3dB at 600Hz. 6dB at 1200Hz and 10dB for all frequencies above 3000Hz. Size 16 1/2" x 8" x 3 1/2". AC 200/250v.

PROCESS TWO

For use with cassette and tape recorders. Freq. res. 30Hz-20KHz ± 2dB. Off tape monitoring. Switchable multiplex filter. Two Dolby calibration meters. S/N better than 70dB. Supplied with test cassette or tape as required.


OUR PRICE **£34-50** P. & P. 50p

PROCESS FOUR

For use with semi professional tape recorders. Freq. res. 30Hz-20KHz ± 2dB. S/N better than 70dB. Full source tape monitoring. Record/Replay metering. Switchable multiplex filter. Supplied with test tape.

OUR PRICE **£50-00** P. & P. 50p

AHP-8A 8-TRACK STEREO TAPE PLAYER



Incorporates built-in amplifiers giving 2 1/2-2 1/2 watts rms output. Push button track selector, illuminated track indicators, slider controls for volume, balance and tone. Attractive cabinet with black and silver trim. Output impedance 8 ohms. AC 220/240v.

OUR PRICE **£17-25** P. & P. 50p

AHP-8D 8-TRACK STEREO TAPE DECK



Can be used with most hi-fi amplifiers. Push button track selector and illustrated track indicators. Attractive cabinet with black and silver trim. Output level 750mV. AC 220/240v.

OUR PRICE **£11-95** P. & P. 50p

AUDIOTRONIC LA.1700 SYSTEM



17+17 watt amplifier. Garrard AP76, plinth and cover, G800 cartridge, pair of Wharfedale Linton 2 speakers and all leads.

OUR PRICE **£86-95** Carr. & Ins. £1-50

Matching LT1700 AM/FM Stereo Tuner £37-50.

SAVE UP TO 33 1/3% OR MORE! GWS

SINCLAIR PROJECT 60 PACKAGE DEALS



- 2 x Z30 Stereo 60/P/Z5 £18.95. P. & P. 37p.
- 2 x Z30/Stereo 60/P/Z6 £18.00. P. & P. 37p.
- 2 x Z50/Stereo 60/P/Z8 £20.25. P. & P. 37p.
- Transformer for PZ8 £3.65
- Active Filter Unit £4.45
- Pair of Q16 Speakers £10.70 P. & P. 50p.
- Project 60 FM Tuner £14.95 P. & P. 50p.
- Sinclair Project 605 £20.97. P. & P. 37p.

All other Sinclair Products in stock.
 2000 Amplifier £28.95. P. & P. 60p.
 3000 Amplifier £28.95. P. & P. 60p.
 2000/3000 Tuner £28.95. P. & P. 60p.
 Q930 Speaker £14.98. P. & P. 50p.

UNREPEATABLE OFFER!



NIKKO TRM50 STEREO AMPLIFIER

17+17 watts rms. Inputs for magnetic and crystal phone, tuner, tape etc. Dual stereo speaker outputs. Headphone socket. Full range of controls. (Rec. List Price £59.50.)

OUR PRICE £39.95 P. & P. 50p

PHILIPS IC361 AM/FM MAINS/PORTABLE RADIO WITH AFC

Covers LW, MW, FM, SW1, SW2 and 49 metre band. Fine tuning of SW and Pre set tuning of three FM stations. Bass, treble and volume/on/off controls. Press button wave change. Tuning/battery indicator. Tape/Gram input. Earpiece socket. AC 110-140v. or 6 x 1.5v. batteries. Size 14 1/2" x 9" x 3 1/2". approx. With mains lead and instructions. Rec. List Price £69.18.

OUR PRICE £39.95 P. & P. 50p.

SAVE OVER 50%



NANIMEX HRC 3061 CASSETTE RADIO

Record/Playback facilities plus slide rule tuning of AM 535-1620 KHz and FM 88-108 MHz. Slider volume controls. Built in condenser microphone plus separate hand/deck microphone. Telescopic aerial. Complete with earpiece, batteries and instructions. (Tape not supplied.) (Rec. List price £55.50).

OUR PRICE £22.75 P. & P. 50p

RECORD DECKS



- Carriage & Packing 50p
 B.S.R. McDONALD
 C114 Mini £3.95
 C129 Mono £5.50
 C137 £7.00
 610/TPD1 £13.95
 610 £10.55
 610/TPD1 £15.45
 710 £21.15
 810 £28.30
 710/810 Plinth and Cover £9.15
 MP60 £8.25
 MP60/G800 £10.90
 MP60/TPD1 £13.20
 MP60/TPD2 £11.25
 HT70 £11.60
 HT70/G800 £14.25
 HT70/TPD1 £16.55

- ONNOISSSEUR
 BD1 Kit £9.10
 BD1 Chassis £11.35
 BD1/SAU2/Plinth/Cover £27.60
 BD2/SAU2/Chassis £22.70
 BD2/SAU2/Plinth/Cover £28.20

- GARRARD
 1025T Stereo £4.95
 2025 T/C Stereo £6.35
 SP25 III £9.25
 SP25 III/Acos GP104 Ceramic £8.50
 SP25 III/G800 £10.85
 SP25/M75-6 £13.90
 AP76 £18.00
 GL65B £11.15
 SL72B £17.75
 GL85B £21.15
 401 £24.95
 ZERO 100 £34.10
 ZERO 100S £31.40

- GOLDRING
 G99 £18.99
 G101/P £18.99
 GL69/2 £15.75
 GL72 £20.97
 GL72/P £27.80
 GL75 £26.80
 GL75/P £34.40
 GL78/P £46.55
 GL85/P £59.55

- THORENS
 TD125/II £58.60
 TD125AB/II £58.65
 TD160C £43.40
 TD165 £41.70

RECORD DECK PACKAGES



- Carriage and Packing 75p
 Complete units with Stereo cartridge ready wired in plinth and cover.
 GARRARD
 2025 TC/TAHCD £10.85
 SP25 III/G800 £16.00
 SP25 III/M44-E £16.45
 SP25 III/M44-7 £16.10
 SP25 III/M35E £16.90
 SP25 III Module/M75-6 £19.45
 AP76/G800 £23.50
 AP76/G800E £25.95
 AP76/M44-E £24.85
 AP76/M44-7 £26.60
 AP76/M35E £23.65
 AP76/M75ED £31.70
 AE76/M75EJ £27.85
 AP76 Module M75-6 £29.10
 AP86 Module M75-6 £33.20
 ZERO 100B Module/M93E £44.15
 B.S.R. McDONALD
 210/RC7M £7.40
 MP60/G800 £16.00
 MP60/TPD1/G800 £16.80
 MP60/M44-7 £16.60
 HT70/TPD1/G800 £19.20

- GOLDRING
 G172/G800 £30.90
 G175/G800 £33.60
 G175/G800E £36.75

- GOODMANS
 TD100/G800 Teak £46.85
 TD100/G800 White £48.60
 LEAK
 Delta M75-6 £43.95
 GAI05/GP200 £13.80
 GAI80/GP200 Teak £19.50
 GA308/GP400 £32.75
 GA308 (Less cartridge) £23.95
 GA212/GP400 £48.05
 FLOBER
 PL12D (Less cartridge) £31.75
 PL13C (Less cartridge) £44.25
 PL14D (Less cartridge) £104.75
 PL15D (Less cartridge) £98.80
 PL61 (Less cartridge) £110.30
 PL435 (Less cartridge) £61.55
 THORENS
 TD160C/Ortofon M15E Super £66.85
 TD125 AB/11 M15E Super £104.25
 T165/Ortofon M15E Super £58.60
 WHARFEDALE
 Lin. on M44-7 Teak £23.70
 Lin. on M44-7 White £23.90

SUPER AKAI CASSETTE BARGAINS!



CS35 STEREO CASSETTE RECORDER

High quality cassette recorder with hysterless synchronous outer-rotor motor. Has pause control with lock and selector for conventional or Chromium Dioxide tape. 4 track record/playback. Volume and tone controls. Frequency response 40-16kHz (using CrO2 tape). Distortion better than 2%, wow and flutter better than 0.2% RMS. Complete with pair of matching Akai CS88 speakers. Rec. Price £96.10.

OUR PRICE £56.50 P. & P. 50p

ADM MICROPHONES

Normally £11.80 pair.
OUR PRICE £7.50
 Pair. P. & P. 25p

AKAI CS35D STEREO CASSETTE DECK

4 track record/playback deck. Accepts chrome/regular tape cassettes. Rec. Price £68.30.
OUR PRICE £44.45 P. & P. 50p

AA6300 AM/FM STEREO RECEIVER

20+20 watts rms. with inputs for magnetic and ceramic cartridge and tape. Bass, Treble, Volume and Loudness controls. Frequency range FM 88-108 MHz AM 535-1605 kHz. Headphone socket. (Rec. Price £117.46).



OUR PRICE £61.95 P. & P. 75p

- CASSETTE (P. & P. 50p)
 CS35D Deck £44.45
 CS85/C888 Speakers £56.50
 GXC40D Deck £57.20
 GXC40 Recorder/Receiver £59.05
 GXC45 Deck £78.25
 GXC45D Dolby Deck £83.55
 GXC46 Recorder £88.95
 GXC50D Deck £87.85
 GXC50D Dolby Deck £92.05
 GARRIDE (P. & P. 50p)
 CR81 Deck with amps. £65.40
 CR81D Deck £53.60
 CR81T Recorder/Receiver £92.75
 CR8088 4 channel Recorder £114.25
 CR8088 4 channel Recorder Teak (P. & P. 75p) £93.65
 4000DS Deck £59.95
 4000DS Dust Cover £3.95
 1721L Recorder £60.35
 X5000 Recorder £82.50
 X201D Deck £108.20
 GX200D Deck £128.95
 GX221D Deck £138.40
 GX280D Deck £196.50
 GX370 Deck £211.50

- TAPE/CASSETTE (P. & P. 75p)
 GX1900D Deck £144.50
 STEREO AMPLIFIERS (P. & P. 50p)
 AA5200 20+20 watt £61.75
 AA5800 30+30 watt £78.50
 AA5800 45+45 watt £117.50
 STEREO TUNERS (P. & P. 50p)
 AT750 AM/FM £80.50
 AT750 AM/FM £94.50
 4-CHANNEL UNIT (P. & P. 50p)
 881 Synthesiser £39.95
 SPEAKERS (P. & P. 50p)
 SW155 (each) £51.00
 STEREO HEADPHONES (P. & P. 30p)
 ASE 11 £4.75
 ASE 20 £7.30
 ASE 22 £8.25
 STEREO RECEIVERS (P. & P. 75p)
 AA8030 25+25 watt £92.50
 AA8080 40+40 watt £117.50
 AA8100S 2x36 or 4x18 watt £175.00
 AA8500 65+65 watt £150.50

SPECIAL GARRARD OFFERS!




STEREO 1025T
 1025T. 4 speed autochanger unit fitted with stereo ceramic cartridge.
OUR PRICE £4.95 Carr & Ins. 50p



SP25 III WITH ACOS GP 104
 SP25 MK III. 4 speed single record player fitted GP104 stereo ceramic cartridge.
OUR PRICE £8.50 Carr & Ins. 50p

ALBANY HOUSE AM 108 SYSTEM



8+8 watt amplifier, SP25 or MP60, plinth and cover, G800 cartridge, pair of Medway T138 speakers.
OUR PRICE £50.95 Carr £1.25

TRIO KA 2000A SYSTEM



16+16 watt amplifier, 6P25 or MP60 plinth and cover, G800 cartridge, pair of Denton 2 speakers and all leads.
OUR PRICE £67.50 Carr. £1.25

BSR 8 TRACK BARGAINS




TD8S STEREO TAPE CARTRIDGE DECK
 Connects to most stereo amplifiers (output 125 mV). Automatic/Manual programme selector.
OUR PRICE £12.70 P. & P. 50p
 TD88V (750mV) £15.20 (P. & P. 50p)

BSR 8 TRACK PLAYER CHASSIS

Famous BSR 8 track chassis as used in Model TD8S complete with silver and black escutcheon ready to fit into cabinet. Output 125mV. AC 240V. Overall size approx. 185x215x80mm.
OUR PRICE £8.95 P & P 50p

FERGUSON EXPORT MODELS



3408 Stereo Tuner Amplifier
 Covers FM 88-108 MHz. Five push button tuning scales. 8+8 watts rms. Inputs for stereo ceramic cartridge and tape, etc. Separate bass, treble, balance and volume controls.
OUR PRICE £31.50 Carr. 50p



3416 Stereo Tape Deck
 4 track. 7 1/2, 3 1/2, 1 1/2 i.p.s. Stereo/mono record/play. 7" reels. Inputs for dynamic mikes, radio, gram. Complete with cover.
OUR PRICE £41.95 Carr. 75p

LONDON'S LARGEST STOCKS INCLUDING PRODUCTS BY-

- ARMSTRONG
- CAMBRIDGE
- KEF-LUX-NIKKO
- SANSUI-SANYO
- SONY-TEAC
- TRANSCRIPTORS
- TRIO-UHER
- YAMAHA

Prices on request or send S.A.E. for full Discount List
ALL EQUIPMENT IS FULLY GUARANTEED AND COVERED BY 12 MONTHS FREE SERVICE!

G.W.S.MITH & CO (RADIO) LTD

- PERSONAL CALLERS WELCOME AT ANY OF OUR RETAIL BRANCHES
- | | |
|--|--|
| CENTRAL LONDON
257/8, Tottenham Court Rd, W.1.
Tel: 01-580 0670 | 311, Edgware Road, W.2.
Tel: 01-262 0387 |
| 10, Tottenham Court Rd, W.1.
Tel: 01-637 2232 | 382, Edgware Road, W.2.
Tel: 01-723 4194 |
| 27, Tottenham Court Rd, W.1.
Tel: 01-636 3715 | 152/3, Fleet Street, E.C.4.
Tel: 01-353 2833 |
| 87, Tottenham Court Rd, W.1.
Tel: 01-580 3739 | 378, Harrow Road, W.9.
Tel: 01-286 9530 |
| 21, Old Compton Street, W.1.
Tel: 01-437 9369 | 86, South Street, Romford.
Tel: Romford 20218 |
| 3, Lisle Street, W.C.2.
Tel: 01-437 8204 | SURREY
1046, Whitgift Centre, Croydon.
Tel: 01-681 3027 |
| 34, Lisle Street, W.C.2.
Tel: 01-437 9155 | 27, Eden Street, Kingston.
Tel: 01-546 7845 |
| 118, Edgware Road, W.2.
Tel: 01-723 9789 | 32, Hill Street, Richmond.
Tel: 01-948 1441 |
| 193, Edgware Road, W.2.
Tel: 01-723 6211 | |

ALL BRANCHES OPEN 9 a.m. - 6 p.m. MONDAY TO SATURDAY
 HEAD OFFICE and MAIL ORDER DEPARTMENT
 UNIT 4, THE HYDE INDUSTRIAL ESTATE, THE HYDE, LONDON NW9 6JJ
 TELEPHONE 01-205 3735

PRICES SUBJECT TO 10% VAT

Order with confidence by Post—but remember to add 10% VAT to total value of order including carriage and packing and send cash with order. PLEASE PRINT NAME & ADDRESS CLEARLY IN CAPITALS.



TELEPHONED ORDERS ACCEPTED FROM ACCESS and BARCLAYCARD HOLDERS
 CREDIT TERMS FOR PERSONAL CALLERS (on sales of £50 and over).

All prices correct at 20.7.73 but subject to change without notice. E. & O.E.

CONCORDE INSTRUMENT COMPANY

42 CRICKLEWOOD BROADWAY LONDON NW2

who now have franchise agreements with Siemens and Thomson-CSF wish to sell the following capacitors manufactured by NTK, and resistors manufactured by Erie :

Voltage	Quantity	Capacitance	Dimensions	Price	Voltage	Quantity	Capacitance	Dimensions	Price	
		F	D x L (mm)				μF	D x L (mm)		
6V	10,000	2,200	18.0 x 31.5	9.0p	25V	25,000	100	10.0 x 25.0	3.0p	
	11,700	3,300	18.0 x 40.0	11.0p		12,500	220	12.5 x 31.5	5.0p	
	7,720	4,700	22.4 x 40.0	13.0p		50,000	330	12.5 x 31.5	5.6p	
10V	20,000	33	6.3 x 16.0	2.5p	35V	35,200	470	18.0 x 31.5	6.0p	
	2,500	47	8.0 x 16.0	2.5p		23,650	1,000	18.0 x 40.0	10.0p	
	8,000	330	10.0 x 31.5	2.6p		37,500	100	12.5 x 31.5	3.3p	
10V	1,500	470	12.5 x 31.5	4.5p	15,000		220	12.5 x 31.5	6.0p	
41,000	1,000	12.5 x 31.5	5.5p	5,800	330		18.0 x 31.5	9.0p		
16V	21,000	2,200	18.0 x 40.0	10.0p	50V	15,000	470	18.0 x 40.0	9.3p	
	20,460	3,300	22.4 x 40.0	13.0p		15,000	1,000	22.4 x 40.0	12.0p	
	18,000	220	10.0 x 31.5	3.3p		2,000	3.3	6.3 x 16.0	3.0p	
	27,500	330	12.5 x 31.5	5.0p			6,200	220	18.0 x 40.0	8.8p
	23,760	470	12.5 x 31.5	5.6p						
1,500	2,200	22.4 x 40.0	14.0p							

Please note that the above prices are for quantities of 1,000. If you require any more than that, please telephone us on 01-452 0161

Erie Resistors

¼ WATT 10%					
RΩ	Quantity	RΩ	Quantity	RΩ	Quantity
135	20,983	390	28,000	470	3,550
560	24,000	1K5	4,000	3K9	2,600
18K	20,000	1M	22,550	2M2	2,000
2M7	35,700	3M9	2,600	5M6	3,000
10M	54,750	8AD			
PRICE: 50p per 100. (Subject to remaining unsold.)					
2 WATT 10%					
RΩ	Quantity	RΩ	Quantity	RΩ	Quantity
1K2	1,700	1K5	108,600	2K2	20,650
3K3	3,000	3K9	6,250	4K7	24,200
5K2	4,000	5K6	31,500	8K2	59,150
15K	5,150	18K	3,950	22K	6,000
47K	24,200	100K	2,000	120K	2,000
150K	13,300	330K	2,850	470K	23,400
2M2	48,300	3M3	550	5M6	3,150
8M2	250	10M	32,450	10AD	
PRICE: £1.00 per 100					

We also have large stocks of:

BC108
AD162
BD116

BC109
2N3055
SN7441

AD161
AF116
LP1175

PRICES SUBJECT TO QUANTITIES REQUIRED.

Concorde Instrument Company has the exclusive franchise for Scotland with Siemens covering their complete range of passive components, semiconductors and ferrites. The address of the Scottish office is:—

CONCORDE INSTRUMENT COMPANY
65 BATH STREET, GLASGOW, G2 2BX, SCOTLAND

Telephone : 041 332 4133/4
Please telephone 01 452 0161 for all enquiries regarding this offer

MAGNETIC HEADS P.O.A.

210028 RCA.....	9 TRACK	303462 RCA.....	7 TRACK
259019 RCA.....	7 TRACK	1215872 TYPE1301.....	7 TRACK
257124 RCA.....	8 TRACK	5007821 POTTER.....	7 TRACK
282812 RCA.....	8 TRACK	19467 EPSYLON.....	8 TRACK
303489 RCA.....	7 TRACK	76815/948 BURROUGHES	9 TRACK
73927 RCA.....	7 TRACK	652623DRI 12/101.....	12 TRACK
303464 RCA.....	7 TRACK	L651922 DRI FR3000.....	16 TRACK

TRANSISTORS & DIODES

2N457.....	75p	AF116.....	25p	2N356/OC139.....	25p
2N1545.....	50p	AF117.....	25p	Get110.....	20p
2N1542.....	50p	BC107.....	8p	2G106/2N711B.....	43p
2N1557.....	50p	BC108.....	8p	OA5.....	20p
2N1908.....	£6.00	BC109.....	8p	OA10.....	25p
2N3054.....	40p	OC35.....	40p	RAS508AF.....	50p
2N3055.....	45p	OC42.....	40p	800PIV.....	50p
2N3442.....	£1.02	OC71.....	12p	RAS310AF 1000v Av.	50p
2N3553.....	£1.00	CV7006/OC72.....	20p	1.5a 2 for 50p	
2N5322.....	50p	OC75.....	25p	STC Wire ended 400PIV	
AC125.....	20p	OC77.....	45p	1a 4 for 50p	
AC127.....	25p	OC83.....	25p	IN3193.....	13p
AC128.....	20p			IN3194.....	14p
AF115.....	25p			IN3255.....	20p

RCA PHOTOMULTIPLIER C31005B

Checked and tested..... £37.50

BRIDGE RECTIFIERS

1B40K05 50v 4a..... 95p

RECTIFIER STACKS

GEX541B1P2.....	£6.88
GEX541B1P1.....	£3.50
GEX541D2P1.....	£3.50
GEX541NB1P1F.....	£6.00
GEX541HP3F.....	£6.00
SX751N1B1P1F.....	£6.00

INTEGRATED CIRCUITS

MC3544.....	£1.10
MC353G.....	£2.00
MC358AG.....	£5.00
MC365G.....	£5.00
CA3020.....	93p
CA3021.....	£1.15
CA3028A.....	97p
CA3038A.....	£2.14
CA3055.....	£1.24
CA3085.....	78p
CD4035AE.....	£1.91
CD4017AE.....	£3.86

THYRISTORS

GE2N1774 200v. 5a.....	£1.20
CR1-021C 20v. 1a.....	25p
CR10-101B 100v.	
10a.....	£1.00
CR10-021 10a.....	£1.00
CR10-408 10a.....	£1.00
CR10-051 10a.....	£1.00
CR10-017 10a.....	£1.00
BTX-82-300R 300v.	
26a.....	£2.00
STC 3/40 400v. 3a.....	50p

CONNECTORS

McMurdo Red Range. Plug RP24.....	56p
McMurdo Red Range. SKT RS32.....	90p
Eng. Elect. Edge. 36 way 0.2mm.....	£1.00
Sylvania Edge. 48 way 0.1mm.....	pair £1.40
Ultra Gold-plated Contacts. 0.1mm Type 10M 54631263C 38 way.....	pair £2.00
20 way.....	pair £1.60

CAPACITORS

Daly Electrolytic 9000 uf 40v. 50p; Wego paper 4uf 400v 60p; Dubilier Metallised Paper Type 426 100uf 150v. DC 50p; R.I.C. type 1297 1.8uf 440v. AC 35p. TCC V13 Conol 3.1µf 1500VDC 50p

MOTORS

GE fractional 1/12 hp 230/250v 1ph 50c 2850rpm.....	£3.50 carr. 67p
E.E. 1/2hp 230v. 50c 1ph 50c. 1440rpm complete with cap 80/100uf 275v.....	£13.00
76813-393 Potter Instr. 110v. DC 4amp 0.2hp. Cont. flange mounting precision tape transport motor (£80 value).....	£25.00 incl. carr.

FANS, CENTRIFUGAL BLOWERS AND STARTERS

Airmax Type M1/Y3954 (3 blades) Cast Aluminium alloy impeller & casing (corresponds to current type 3965 7 1/2") 230v. 1ph 50c 2900rpm Class "A" insulation 425cfm free air weight 9 1/2lbs. incl. p.p. £21.00.
Woods Aerofoil short casing type "S" 2700rpm 220/250v 1ph 50c 6" plastic impeller incl. p.p. £11.50.
Woods Aerofoil Code 7.5 280K 200/250v. 1-0a 1ph 50c 2700rpm 7 1/2" impeller 14 blades incl. p.p. £13.50.

Service Electric Hi-Velocity Fans, suitable for Gas combustion Systems. Steam exhausting, Pneumatic conveying, Cooling Electronic equipment, Air blast for Oil burners. **Secomak** Model 365 (corresponds to 575) Airblast Fan, 440v 3ph 50c 0.75hp 2850rpm, continuous 160cfm 12 in. w.g. nett weight 44lb price incl. carr. £41.00. **Secomak** model 350 250v 1ph 50c 0.166hp, 2800 rpm continuous 50cfm 2 in. w.g. net weight 34lbs, price incl. carr. £26.00.

Air Controls type VBL4-200/250v 1ph 50c. 110cfm free air weight 7 1/2lbs price incl. p.p. £14.50.
William Allday Alcossa Two Stage Vacuum Pump Model HSPOB 8hp up to 29 in. mercury rpm 1420. E.E. 3 phase induction, motor 1/2hp cont. 220/250v. 380/440v. £21.00 incl. carr.
Gast MFG. Vacuum pump 0522-P702-R26X. Motor 110/120v. A.C. 1 ph. 60c 1725 rpm. Class E. Or as compressor 10psi int. or 15 psi cont. £25.00 incl. carr.


Where p.p. not advised add 10p per £ handling and post (in UK). Cash with order. Personal calls welcome. Open Mon-Wed. 9.30-5.00 Fri.-Sat. 9.30-5.00. Free Car Park adjacent.

PRICES SHOWN ARE EXCLUSIVE OF V.A.T.

W. & B. MACFARLANE

126 UXBRIDGE ROAD, HANWELL, LONDON W7 3SL

WW-108 FOR FURTHER DETAILS



TRANSFORMERS

MAINS ISOLATING SERIES
 Primary 200-250 Volts Secondary 240 Volts Centre Tapped (120V) and Earth Shielded
 ALSO AVAILABLE WITH 115/120V SECONDARY WINDING

Ref. No.	VA (Watts)	Weight lb oz	Size cm.	P & P
07	20	1 11	7.0 x 6.0 x 6.5	1.77 30
100	60	3 8	8.9 x 8.0 x 7.7	2.62 36
61	100	5 12	10.2 x 8.9 x 8.7	2.88 52
30	200	9 8	12.0 x 10.3 x 10.0	4.83 52
62	250	12 4	9.5 x 12.7 x 11.4	6.38 67
55	350	15 0	14.0 x 10.8 x 12.4	8.55 82
63	500	27 0	17.1 x 11.4 x 15.9	12.32 *
92	1000	40 0	17.8 x 17.1 x 21.6	22.70 *
128	2000	63 24	24.1 x 21.6 x 15.2	37.50 *
129	3000	84 0	21.6 x 21.6 x 10.3	58.67 *
190	6000	178 0	31.1 x 35.6 x 17.1	96.27 *

PLEASE NOTE
 NEW ADDRESS
 AS BELOW

440V 300VA ISOLATOR, Primary 440V Secondary 240V, Centre Tapped Screened and Shrouded, £10.37. P & P 67p.

AUTO RESISTOR (NOT ISOLATED)

Ref. No.	VA (Watts)	Weight lb oz	Size cm.	Auto Taps	P & P
113	20	1 11	7.3 x 4.3 x 4.4	0-115-210-240	0.93 22
64	75	1 14	7.0 x 6.4 x 6.0	0-115-210-240	1.82 30
4	150	3 0	8.9 x 6.4 x 7.6	0-115-200-220-240	2.20 36
66	300	6 0	10.2 x 10.2 x 9.5	" "	4.28 52
67	500	12 8	14.0 x 10.2 x 11.4	" "	6.35 67
84	1000	16 0	11.4 x 14.0 x 14.0	" "	11.54 82
93	1500	28 9	13.5 x 14.9 x 16.5	" "	16.72 *
95	2000	40 0	17.8 x 16.5 x 21.6	" "	21.82 *
73	3000	45 8	17.4 x 18.1 x 21.3	" "	29.70 *

TOTALLY ENCLOSED 115V AUTO TRANSFORMERS

115V 500 Watt totally enclosed auto transformer, complete with mains lead and two 115V outlet sockets. £8.63. P & P 67p
 Also available a 20 Watt version, £1.84. P & P 22p.

LOW VOLTAGE SERIES (ISOLATED)

PRIMARY 200-250 VOLTS 12 AND/OR 24 VOLT RANGE

Ref. No.	Amps.	Weight lb oz	Size cm.	Secondary Windings	P & P
111	0.5	0.25	12	0-12V at 0.25A x 2	0.93 22
213	1.0	0.5	12	0-12V at 0.5A x 2	1.11 22
71	2	1	13	0-12V at 1A x 2	1.46 22
18	4	2	14	0-12V at 2A x 2	2.04 36
70	6	3	12	0-12V at 3A x 2	2.46 42
108	8	4	5	0-12V at 4A x 2	2.73 52
72	10	5	6	0-12V at 5A x 2	3.23 52
17	16	8	7	0-12V at 8A x 2	4.99 52
115	20	10	11	0-12V at 10A x 2	6.35 67
107	30	15	16	0-12V at 15A x 2	11.73 82
226	60	30	34	0-12V at 30A x 2	21.57 *

30 VOLT RANGE

Ref. No.	Amps.	Weight lb oz	Size cm.	Secondary Taps	P & P
112	0.5	1 4	8.3 x 3.7 x 4.9	0-12-15-20-24-30V	1.11 22
79	1.0	2 0	7.0 x 6.4 x 6.0	" "	1.48 36
3	2.0	3 2	8.9 x 7.0 x 7.6	" "	2.21 36
20	4.0	4 6	10.2 x 8.9 x 8.6	" "	2.72 42
21	4.0	6 0	10.2 x 10.0 x 8.6	" "	3.23 52
51	5.0	6 8	12.1 x 10.0 x 10.2	" "	4.80 52
117	6.0	7 8	12.1 x 11.7 x 10.0	" "	6.20 67
88	8.0	10 0	14.0 x 10.2 x 11.4	" "	7.85 67
89	10.0	12 2	" "	" "	" "

50 VOLT RANGE

Ref. No.	Amps.	Weight lb oz	Size cm.	Secondary Taps	P & P
102	0.5	1 11	7.0 x 7.0 x 5.7	0-19-25-33-40-50V	1.46 30
103	1.0	2 10	8.3 x 7.3 x 7.0	" "	2.13 36
104	2.0	5 0	10.2 x 8.9 x 8.6	" "	3.96 42
105	3.0	6 0	10.2 x 10.2 x 8.3	" "	4.01 52
106	4.0	9 4	12.1 x 11.4 x 10.2	" "	5.31 52
107	6.0	12 4	12.1 x 11.1 x 13.3	" "	7.85 67
118	8.0	18 9	13.3 x 13.3 x 12.1	" "	10.25 97
119	10.0	19 12	16.5 x 11.4 x 15.9	" "	12.85 97

60 VOLT RANGE

Ref. No.	Amps.	Weight lb oz	Size cm.	Secondary Taps	P & P
124	0.5	2 4	8.3 x 9.5 x 6.7	0-24-30-40-48-60V	1.48 36
126	1.0	3 0	8.9 x 7.6 x 7.6	" "	2.06 36
127	2.0	5 6	10.2 x 8.9 x 8.6	" "	3.23 42
125	3.0	8 8	11.9 x 9.5 x 10.0	" "	4.92 52
123	4.0	10 6	11.4 x 9.5 x 11.4	" "	6.35 67
120	6.0	16 12	13.3 x 12.1 x 12.1	" "	9.20 82
122	10.0	23 2	16.5 x 12.7 x 15.5	" "	15.23 *

EQUIPMENT TRANSFORMER

REF 238 PRI 0240 SCREEN SEC 3-0 3V RMS at 200mA SIZE CM 2.8 x 2.6 x 2.0 WEIGHT 2oz £1.08 P & P 10p.

LEAD ACID BATTERY CHARGER TYPES

PRIMARY 200-250VOLT FOR CHARGING 6 OR 12VOLT BATTERIES

Ref. No.	Amps.	Weight lb oz	Size cm.	P & P
45	1.5	1 9	7.0 x 6.0 x 6.0	1.47 30
5	4.0	3 11	10.2 x 7.0 x 8.3	2.23 42
86	6.0	5 12	10.2 x 8.9 x 8.3	3.37 52
146	8.0	6 4	8.9 x 10.2 x 10.2	3.84 52
50	12.5	11 14	13.3 x 10.8 x 12.1	5.72 67

All ratings are continuous. Standard construction: open with solder tags and wax impregnation. Enclosed styles to order.

TRANSISTORS

TO MANUFACTURERS' FULL SPECIFICATIONS FOR EXAMPLE

BC107/108/109 10p each	2N 3055 68p each with mica and bushes	AD 161/162 60p pair with mica and bushes
------------------------	---------------------------------------	--

★ Quantity prices on application
 Also stocked: SEMICONDUCTORS • VALVES
 AVOMETERS • ELECTROSIL RESISTORS
 PLEASE ADD 10% FOR V.A.T.
 Carriage via B.R.S.

BARRIE electronics

3, THE MINORIES, LONDON EC3N 1BJ


TELEPHONE: 01-488 3316/8

NEAREST TUBE STATIONS: ALDGATE & LIVERPOOL ST.

WW-109 FOR FURTHER DETAILS

HART ELECTRONICS

Audio Kits



This is our Bailey/Burrows Stereo pre-amp front end. We think it is the best engineered kit of the best pre-amp circuit available, and there is a back end/tone control unit of similar advanced design to go with it which is only 1½" deep so it fits almost anywhere, but of course it's at its best in a Hart universal amplifier metalwork with a couple of Hart Bailey 30 watt power amps to keep it company. That's a recipe for real Hi-Fi with electronics you'll be too proud to cover up.

Also a delight to the connoisseur are our printed circuits and components for the Stuart tape circuits.

This is a most useful high quality circuit with the record, replay and bias functions on separate boards thus giving considerable versatility of use. For instance a stereo replay channel can be built for £6 for single speed use without external components or a switch may be added for multispeed operation.

Stuart reprints all three articles under one cover.

Price 30p. No V.A.T.

Penylan Mill, Oswestry, Salop.

Personal callers are always welcome, but please note we are closed all day Saturday

WE ARE SUPPLYING

Printed Circuit Boards, Components and Kits for the

D. O'N. WADDINGTON DIGITAL MULTIMETER

This most interesting project fulfils the long-felt want for a Digital Multimeter with the added bonus of counter/timer functions, all at a price which makes it extremely attractive to the amateur, educational or commercial user.

Please send 9" x 4" SAE for full details:

ATTENTION!

PLESSEY RADAR MARK V and MARK VII DISPLAY UNITS

The following brand new P.W. Boards are available at a fraction of their original cost.

OUR SPECIAL PRICE **£15.00 each**

Part No.	Part No.	Part No.	Part No.
12305/A	12292/A	687/1/00925/001	12048/A
12346/A	12458/A	12065/A	12047/A
12439/A	12344/A	12327/A	12551/NP/C EXT. Stalk
12459/A	12034/A	17126/A	12378/A
12447/A	12336/A	12961/A	12343/A
12235/A	12412/A	12482/A	12326/A
419-1-00647	12345/A	12970/A	687/1/01291
12100/A	12353/A	12972/A	12422/A
12962/A	12963/A	12338/A	12281/A
12436/A	12098/A	12339/A	META for MK VII
12184/A	12341/A	12487/A	687/1/00678
12187/A	12968/A	12325/A	687/1/00070

BROADFIELDS & MAYCO DISPOSALS,

21, LODGE LANE, N. FINCHLEY, LONDON, N12, 8JG, ENGLAND

Telephone: 01-445 2713 and 01-445 0749

C. T. ELECTRONICS 267 ACTON LANE, LONDON W4 5DG 01-994 6275

MAIL ORDER DEPT./REGISTERED OFFICE/COMPONENT COUNTER

TEST EQUIPMENT

Manufacturer	Type	Price (ex V.A.T.)
EMI 9524H	Photomultiplier	£8
Teletronix 551	Oscilloscope and B+G Plug-in	£300
Teletronix 53/54B	Plug-in	£20
Teletronix 53/54E	Plug-in	£20
Croydon Precision Instruments KBI	Kelvin Bridge Ohmmeter	£60
Vibro-Meter Corp. PBA-1/A	Bridge Supply and Indicator	£120
Muirhead 21-A	Varley/Wheatstone/Murray Bridge	£40
Emouzy	Electronic Multimeter	£15
E.I.L. 22B	Micouac Electronic Testmeter	£18
Marconi Mod. 12	AM/FM Signal Generator 35kHz-18.3MHz	£65
Cawkell S.O.I.	Storage Oscilloscope	from £75
Teletronix 551	Oscilloscope and 2 x G Plug-in	£300
Teletronix D, G	Plug-in units	ea.
Teletronix 536	X-Y Oscilloscope and 2 x B Plug-in	£300
Teletronix 661	Sampling scope and 5TA1 + 4S1 Plug-in	£450
Eddystone	Receiver 500-1000MHz	£275
Marconi TF 1100	Sensitive Valve Voltmeter	£28
Marconi TF428C	Valve Voltmeter	£18
Marconi TF899	Valve Millivoltmeter	£12
Marconi TF887A	Valve Voltmeter	£12
Marconi	H.F. Absorption Wattmeter 52 ohm 1W/70 ohm 25W	£12
Marconi TF1374	Precision Crystal Calibrator	£30
Pye	Scalamp Galvo	£20
Advance MG5-40	5V 40A Stabilised Power Pack	£70
Marconi TF894	Audio Tester	£50
Cossor RI09AD5	25W Transmitter	£60
Teletronix c 545	Oscilloscope and G Plug-in	£225
H.P. 614A	UHF Sig. Generator 750-2100MHz	£85
Cohn	D.C. Voltage Standard 10µV-1000V 6 decade	£525
Marconi TF1272	Transistor Test Set	£24
Solartron JM1067	Precision RMS Millivoltmeter 3mV-300V	£52
Solartron LM903	AC Converter-Voltmeter	£50
Cossor RI09 AB5 Mk. 3	Receiver	£50
Marconi TF144G	Standard Sig. Gen. 85kHz-25MHz	£35
Cambridge	Spot Galvo 430 ohm	£18
Teletronix B, G, D, H	Plug-ins	ea.
Advance PM48	Stabilised Power Pack 15-30V 3A	£23
E.M.I. WM16	Oscilloscope and 7/6 Diff. Amp.	£140
Baird & Tatlock	0.1% Wheatstone Bridge	£50
Sullivan	Standard Mica Capacitor 1md. 4 decade	£75
Cambridge L358113	Decade Bridge	£58
Teletronix 107	Square Wave Generator	£18
Avo FPSK	Oscilloscope Camera with Polaroid Attachment	£120
Marconi TF1041	Valve Voltmeter	£30
Sony PV-120VE	Broadcast Standard Videotape Recorder, 2in. tape; 625 line CCIR, 2 Audio Channels	£650
Marconi TF928	FM Deviation Meter 20-100MHz	£28
Solartron CD1220	Oscilloscope and CX1258 Diff. Plug-in	£150
Solartron OS103	LF Decade Oscillator .01-11kHz 0.009-10V 4 phase and square wave outputs	£85
Ediswan R666	L.F. Oscillator .15Hz-5kHz	£20
Marconi TF1165	Electronic Counter 7 digit 1MHz	£35
Sanders L026	Lab. Magnetic Amplifier	£40
B.P.L. LC100-C	Coil Comparator .1µH-100mH	£55
Roband V50/50	Stabilised Power Supply 0-500V 500mA	£50
A.P.T. 2445	Twin Stabilised Power Supply 0-100V 250mA	£38
Muirhead D-729	Phasemeter and P.S.U.	£80
Farnell TSV12/2	Transistor P.S.U. 0-12V 2A Metered	£10
Airmec 252	A.F. Signal Generator 30-300kHz bal./unbal.	£28
Marconi TF130	Vacuum Tube Voltmeter	£30
Honeywell IK100	D.C. Reference Standard	p.o.A.
Jerrold 900A	UHF/VHF Sweep Freq. Generator	p.o.A.
Advance DI/D	R.F. Signal Generator	£45
E.M.I.	14in. TV Monitor	p.o.A.
Wayne Kerr M121	AF Voltmeter	p.o.A.
E.M.I.	Magnetic Drum Delay Units (Studio Echo Units)	p.o.A.

This is just a sample list of Test Equipment available. We have hundreds of other items available. Enquiries welcome. Please telephone 01-994-6275.

LOW-COST OSCILLOSCOPES

Cossor 1035, D.B.
Cossor 1049 Mk. 3A, D.B.
Cossor 1049 Mk. 4, D.B.
Solartron AD557.
Solartron CD513.2.
Solartron CD523 S.2.
Solartron CD643.
Solartron CD643.2.
Solartron CD7115.2.

E.M.I. WM2.
WM3B.
WM7.
WN8.
WM16.
WM18.
WM26.

All prices and details on application phone 01-994-6275. Inspection welcome—call at warehouse.

STABILISED D.C. POWER PACKS (Brand New)

FARNELL IR 24/10 24V. 10 Amp.	£40
STE 234 30V. 1A. + 10V. 2A.	£38
COUTANT ED 200/12/12 5-30V. 2A. Dual supply	£45
ES 500/26 6-30V. 5A.	£35
HTD 60/150/150 Dual supply	£35
A.P.T. SCV 32 FI 150V. 1/2A.	£20

COMMUNICATIONS EQUIPMENT

POCKET V.H.F. F.M. RADIOTELEPHONE

Corror Type CC2/8 Mk. 2.
Fully transistorised transmitter/receiver available in two versions:—
Low band; Freq. range 71.5-104MHz, R.F. Output 500mV.
Complete with 1/4 wave whip aerial, combined microphone/loudspeaker and 13.3V. rechargeable nickel-cadmium DEAC battery.

Price £75 + v.a.t.

U.H.F. 2 watt FIXED RADIO LINK. 24V. dc./240V. ac. F.M. TRANSMITTER/Type CC RTX 4A Mk. 1
R.F. Output 2V at 450-470MHz.

RECEIVER/Type CCRR4A Mk. 1
Full Technical and operating data available. Prices and details on request.
Mains Power Pack for the above £12.00 each

I + I CARRIER EQUIPMENTS. Corror Type CC M2A.
Solid state multiplex installations designed for U.H.F. radio systems enabling 2 speech channels each with out of band signalling, if required or the equivalent in telemetry information, to be transmitted simultaneously over a radio system. Prices and details on request.

V.H.F. RADIOTELEPHONE BASE STATION. Corror Type CC 603 Transmitter. Simplex or duplex operation, local or remote control with talk through facilities, using double sideband a.m. modulation.

Low-band 71.5-104MHz, or High-band 156-174MHz. versions available.
R.F. Output power 25W. into 50 Ohms.
24V. dc. operation. Prices and details on request
OPTIONAL POWER SUPPLY Type CC 101 for type CC603 base station P.O.A.

SELECTIVE CALL SYSTEM. Coder Type CC 505/50 (50 way) or CC 505/100 (100 way). The Cossor selective call system may be used with any communication system where a base station is required to call any one or all of a number of sub-stations. Both versions available, all new and in original packing.

Price: 50 way £65 + v.a.t.
100 way £80 + v.a.t.

DECODERS £15 ea.

DEAC RECHARGEABLE BATTERY CASSETTES 13.4V (nom.) type B/SA 80351/108. Heavy duty encapsulated DEAC supply.
Size 3 1/2 x 2 1/2 x 1 1/2 in. Price £5 + v.a.t.

8-WAY BATTERY CHARGER Type CC 999. Charges up to 8 of the above battery cassettes. Price £25 + v.a.t.

12-WAY BATTERY CHARGER Type CC 999. Charges up to 12 of 13.4V. DEAC batteries. Metered battery condition check. Price £35 + v.a.t.

MICROPHONES

S. G. Brown Stick Microphone and Stand. Push-to-talk button. 300Ω. £5 complete.
S. G. Brown Hand-held with push-to-talk button. £8 each.

SPECIAL OFFERS

BRIDGE RECTIFIER. 6A. 100V. Motorola MDA952-2 65p.

POWER SUPPLY. 12V. 6.5A. Stabilised Power Supply. Contains 18.5V. 8.5A. sec. Transformer, 4 x 4000µF 25V. Mullard capacitors, 2 x 2N3055 on 2 Redpoint heatsinks, 12A., 120V. Bridge rectifier, stabilised p.c.b. + circuit diagram. The parts alone are worth the asking price of £13 each inc. carriage.

Send s.a.e. for free circuit diagram.

ELECTRONIC COMPONENTS BARGAIN COMPONENT PACKS

Pack No.

- 500 Carbon resistors, 1/4, 1/2, 1, 2 watt.
- 100 Electrolytic Condensers.
- 250 Ceramic, Polystyrene, Silver Mica, etc., Condensers.
- 250 Polyester, Polycarbonate, Paper, etc., Condensers.
- 25 Potentiometers, assorted.
- 250 High-stab. 1%, 2%, 5% resistors.
- 50 Assorted Tagstrips.
- 11b Assorted nuts, bolts, washers, spacers, etc.
- 25 Assorted switches, rotary, lever, micro, toggle, etc.
- 50 Preset Potentiometers.
- Trial mixed component pack £1.
- Jumbo mixed pack £5.

ALL COMPONENTS NEW AND UNUSED
£1 + 25p p.p. per pack, £5 for 5 packs p/free.

NOW OPEN:

AUDIO ACCESSORY SHOP
17 TURNHAM GREEN TERRACE, W.4.
HEADPHONES, MICROPHONES, SPEAKERS, etc., etc.

WAREHOUSE
20-24 BEAUMONT ROAD, W.4.
SURPLUS COMPONENTS, TEST EQUIPMENT, etc., etc.



DRILL CONTROLLER
New 1kW model.
Electronically changes speed from approximately 10 revs. to maximum. Full power at all speeds by finger-tip control. Kit includes all parts, case, everything and full instructions £1.65, plus 13p post and insurance. Made up model also available £2.48 plus 13p p. & p.

MIGHTY MIDGET

Probably the finest possible radio, as described in Practical Wireless, January 73. All electronic parts £2.20 post paid.

GOOD COMPANION I.C. VERSION



We can now offer these again in I.C. version using Ferranti ZN414 and Mullard AF Module 1172. Cabinet size approx. 11in. wide x 8in. high x 3in. deep. Complete assembly instructions, £5.33 plus 25p post and ins. Excellent tone wood cabinet.

I CHIP RADIO

Ferranti's latest device ZN414—gives results better than superhet. Supplied complete with technical notes and circuits £1.38 each. 10 for £11.11.

HI-Q TUNER COMPONENTS

For experimenting with the ZN414
Kit No. 1 Plessey Miniature Tuning Condenser with built in LW switch and 3in. Ferrit slab and litz wound MW coil 72p.


Kit No. 2 Air spaced tuning condenser 6in. ferrit rod litz wound MW and LW coils and wave change switch 94p.

Kit No. 3 Air spaced TC with slow motion drive 8in. ferrit rod with litz wound LW and MW coils and wave change switch £1.10.

Kit No. 4 Permeability tuner with fast and slow motion drive and LW loading coils and wave change switch 50p.

12 VOLT 1 1/2 AMP POWER PACK

This compact double-wound 230/240V mains transformer with full wave rectifier and 2000 mfd/50V smoothing. Price £2.20, plus 20p post & packing.



Heavy Duty Mains Power Pack. Output voltage adjustable from 15-40V in steps—maximum load 250W—that is from 6 amp at 40V to 13 amp at 15V. This really is a high power heavy duty unit with dozens of workshop uses. Output voltage adjustment is very quick—simply interchange push on leads. Silicon rectifiers and smoothing by 3,000mF. Price £6.33 plus 65p post.

MICRO SWITCH

5 amp changeover contacts. 11p each. 10 for 99p. 15 amp. S.P. Model 15p. changeover 17p. each



MAINS OPERATED SOLENOIDS

Model 772—small but powerful 1in. pull—approx. size 1 1/2 x 1 1/2 x 1 1/2in., 66p.
Model 4001—1in. pull. Size 2 1/2 x 2 x 1 1/2in. 83p.
Model T71—1 1/2in. pull. Size 3 x 2 1/2 x 2in. £1.98 plus 20p. post and insurance.



MAINS TRANSISTOR POWER PACK

Designed to operate transistor sets and amplifiers. Adjustable output 6v., 9v., 12 volts for up to 600mA (class B working). Takes the place of any of the following batteries: PP1, PP2, PP4, PP6, PP7, PP9, and others. Kit comprises: mains transformer rectifier, smoothing and load resistor condensers and instructions. Real snip at only £1.10 plus 20p postage.



TIME SWITCH

Smith's mains driven clock with 15 amp switch also notes showing how you can wake up with music playing, kettle boiling or come home to a warm house, warn off burglars, keep pets warm, halve your heating bill, etc. £2.25.

PRESSURE SWITCH

Containing a 15 amp. change over switch operated by a diaphragm which in turn is operated by air pressure through a small metal tube. The operating pressure is adjustable but is set to operate in approx. 10in. of water. These are quite low pressure devices and can in fact be operated simply by blowing into the inlet tube. Original use was for washing machines to turn off water when tub has reached correct level but no doubt has many other applications. £1.38.



EDUCATIONAL KITS—all with pictorial instructions

THIS BALANCE KIT FREE

Pictorial educational kits. Japanese made these are excellent value for money. We do not expect to be able to repeat this offer once stocks are sold. Brief description of each kit is given below and with 3 kits or more we give FREE an accurate 11 piece balance kit. Price of kits 44p each post paid. Special price for all 7 kits £3.00 with free balance kit.



KA2 Lens Kit. Eleven parts, including candle one concave lens, one convex lens, stage and slit frame, etc. Watch light rays bend as they pass through different lenses.

KA3 Water Pump Kit. Thirteen parts. Top of pump is transparent so that operating parts may be observed. Small parts are brightly coloured to be seen easily while working. Three types of pump may be made: Lift pump Force Pump and Force Pump with reservoir and nozzle.

KA4 Buzzer Kit. Eleven parts. Transparent covers allow the operation of buzzer to be seen. Illustrates and teaches how electromagnetism with an automatic switch results in an operating buzzer.

KA7 Electro-Magnet Kit. Fifteen parts, includes compass. Makes two electro-magnets, one with one layer of wire and one with several layers of wire. Picks up tacks, nails and any small parts showing how magnetism works.

KA8 Current and Resistance Kit. Twenty-nine parts, including bench and light bulb. Conduct interesting and educational projects to learn the application of "OHMS LAW" and see the difference in current and resistance with different types and lengths of wire.

KA9 Bell Kit. Eight parts, including bell and push button switch. Build a complete electric bell and see how the hammer is triggered to make the bell ring.

KA10 Morse Key buzzer and bell kit. 25 part kit, easy to construct, simple to operate.

THIS MONTH'S SNIP

SOLENOID OPERATED TAPE DECK

Solenoid operated (so could be remote controlled) tape deck—comprises: motor driven heavy but balanced flywheel which forms capstan. Tape drive is operated by no. 1 solenoid. Two more solenoids operate fast forward and fast reverse. Complete with tape spools record/play back head and erase head. Real bargain at £6.60.



For any lamp up to 250 watt. Mounted on switch plate to fit in place of standard switch. Virtually no radio interference. Price £3.35. Industrial model 5A £3.30

THYRISTOR LIGHT DIMMER

10 AMP DIMMER CONTROL

For the control of lighting on stage or in a studio or for control of portable equipment in workshops, etc. This has two 13 amp socket outlets each is controlled by a 5 amp solid state regulator. The overall length is 17in., width 3 1/2in. and depth 1 1/2in. In the end is fitted a master On/Off switch indicator, lamp and fuse. Price £8.25.

STANDARD WAFER SWITCHES

Standard size 1 1/4in. wafer—silver-plated 5 amp. contact, standard 1/2in. spindle 2in long—with locking washer and nut.

No. of Poles	2 way	3 way	4 way	5 way	6 way	8 way	9 way	10 way	12 way
1 pole	44p	44p							
2 poles	44p	44p							
3 poles	44p	44p							
4 poles	44p	44p							
5 poles	44p	44p	77p	77p	£1.04	£1.04	£1.04	£1.04	£1.60
6 poles	44p	77p	77p	77p	£1.04	£1.04	£1.04	£1.87	£1.87
7 poles	77p	77p	77p	£1.04	£1.32	£1.32	£1.32	£2.15	£2.15
8 poles	77p	77p	77p	£1.04	£1.32	£1.32	£1.32	£2.42	£2.42
9 poles	77p	77p	£1.04	£1.04	£1.60	£1.60	£1.60	£2.70	£2.70
10 poles	77p	77p	£1.04	£1.32	£1.60	£1.60	£1.60	£3.00	£3.00
11 poles	77p	£1.04	£1.04	£1.32	£1.87	£1.87	£1.87	£3.25	£3.25
12 poles	77p	£1.04	£1.04	£1.32	£1.87	£1.87	£1.87	£3.52	£3.52


DISTRIBUTION PLATES

Just what you need for work bench or lab. 4 x 13 amp sockets in metal box to take standard 13 amp fused plugs and on/off switch with neon warning light. Supplied complete with 6 feet of heavy cable. Wired up ready to work. £2.48 plus 25p P. & P.




CAPACITOR DISCHARGE CAR IGNITION

This system which has proved to be amazingly efficient and reliable was first described in the Wireless World about a year ago. We can supply kit of parts for an improved and even more efficient version (Practical Wireless, June). Price £5.55 plus 30p post. When ordering please state whether for positive or negative systems. Also available. Ready made ignition systems for 6v. vehicles. £5.78 plus 20p.



CENTRIFUGAL BLOWER


Miniature mains driven blower centrifugal type blower unit by Woods, powerful but specially built for quiet running—driven by cushioned induction motor with specially built 4 1/2" x 4". When mounted by its flange air is blown into the equipment but to suck air out mount it from the centre using a clamp, ideal for cooling electrical equipment, or fitting into a cooker hood, film drying cabinet or for removing flux smoke when soldering etc., etc. A real bargain at £2.05.



SPECIAL SUMMER OFFER

MULLARD UNILEX at Pre V.A.T. price

You want a good stereo system—well here's an offer you should not miss! The four Mullard modules all in original manufacturer's cartons and with original maker's guarantee. £7 the lot. Control unit with name plate and 4 spun aluminium faced control knobs £3. Total £10 post and V.A.T. paid. 2 Goodmans Speakers £3.



ELECTRIC TIME SWITCH

Made by Smiths these are A.C. mains operated. NOT CLOCKWORK. Ideal for mounting on rack or shelf or can be built into box with 13A socket. 2 completely adjustable time periods per 24 hours, 5 amp changeover contacts will switch circuit on or off during these periods. £2.75 post and ins., 23p. Additional time contacts 55p pair.

MULLARD AUDIO AMPLIFIERS

All in module form, each ready built complete with heat sinks and connection tags, data supplied.
Model 1153 500mW power output 72p.
Model 1172 750mW power output 94p.
Model EP9000 4 watt power output £1.60.
EP9001 twin channel or stereo Pre amp. £1.99.
10% discount if 10 or more ordered.



WINDSCREEN WIPER CONTROL

Very speed of your wiper to suit conditions. All parts and instructions to make. £2.48.



PAPST MOTORS

Est. 1/40th h.p. Made for 110-120 volt working, but two of these work ideally together off our standard 240 volt mains. A really beautiful motor, extremely quiet running and reversible. £1.85 each. Postage one 25p, two 33p, 250v. model £3.30.

HORSTMANN 24-HOUR TIME SWITCH

With 6 position programmer. When fitted to hot water systems this could programme as follows:—

Programme	Hot Water	Central Heating
0	Off	Off
1	Twice Daily	Off
2	All Day	Off
3	Twice Daily	Twice Daily
4	All Day	All Day
5	Continuously	Continuously

Suitable of course, to programme other than central heating and hot water, for instance, programme upstairs and downstairs electric heating or heating and cooling or tapel music and radio. In fact there is no limit to the versatility of this Programmer. Mains operated. Size 3in. x 3in. x 2in. deep. Price £3.85 as illustrated but less case.

TAPE PLAYBACK UNITS

Mains operated. Made by Redstone the famous "music in background people." These are complete units ready to work. They have a superior motor driven flywheel to control the tape through the capstan and also an even equally useful valve amplifier with E1.84 output. In a steel case with carrying handle. Two models offered, good as new £6.50 and somewhat used at £3.50. 70p carriage up to 200 miles then 50p per 100 miles extra.
90 minutes cassette. Plain 77p. Recorded £1.



NEW ITEMS THIS MONTH

LABORATORY INSTRUMENTS

Used but believed in good order—one only of each—on offer to highest bidder. EMI Parasonic wave analyser. 2x Beckman Universal Eput. Flmer Model 7360c. First Electronics Wave Meter 115RA. Mansons Proportional Owen and Xtal Osc RD140. Airmeq Millivolt Meter type 264. Marconi Magnification Meter TF 329G. Airmeq Frequency Meter Type 726. Sarton Laboratory Amplifier 15 c/s-350 kc/s Awa 51a. GEC Quartz Xtal Activity Test Set 2-20 mcs. Muirhead Phasemeter D729 BM. Muirhead Phasemeter D729 B8. Heath Kit R-C Bridge C34-ROA. Fluther Indicator. Metrix Standard Sig. Generato. 50 mcs/s. 50 mcs/s to 50 mcs.

METAL CHASSIS

14 gauge sheet steel—size approx. 7in. x 3 1/2in. x 1 1/2in deep. Cadmium plated punched in the centre to take 3 P.O. 300V type relays. There is also a removable cover over this section measuring 4 1/2in. long x 3 1/2in. x 2 1/2in. The chassis also has a few holes and could take a small transformer and/or valve holders and also come 1in. holes for controls, pots etc. This is an ideal chassis for making up a relay unit or similar. These are ex-equipment but in excellent condition and may have a few resistors etc. still attached. Price 40p each.

CLOCKWORK TIME SWITCH

For delaying the switching on for up to 12 hours. Being clockwork this is independent of the mains and is therefore useful for remote operation or for battery appliance. The front dial which is calibrated in hours is turned through the required revolution then after pre-set time double pole 15A switch operates. Made by Smiths. Price £1.65.

MAINS TRANSFORMER

Our Ref. MTJ1. Dimp through chassis—open construction. 240 v. Primary—9v. 1A. Secondary. Price 77p. each

MAINS TRANSFORMER

Our Ref. MTJ2. Farmek Neptune series. This is a totally enclosed construction, appropriate sit mounting and black enamelled. For 230/240V. Sec. 25.0-25v. at 50 mA. Idea for mounting on metal chassis mentioned above. Ex-equipment but unused. 77p each.

3 POST OFFICE TYPE 3000 RELAYS

Ex-equipment but guaranteed perfect—any not so would be changed.

1. Ref. REL J1. Has 6 sets of change-over contacts and 2000 ohm coil. 55p each.
2. Ref. REL J2. 2 pairs that close when relay energized and 2000-1000 ohm coil. Price 44p.
3. Ref. REL J3. 2 pairs contacts that close and 6.4 K ohm coil. 44p.

1 REV. PER MINUTE MOTOR WITH BEAR-BOX

Made by the famous Chamberlain & Hookham Ltd. These could be made to drive clock or similar. Really robust reliable unit. Price 99p each.

110 REV. PER MINUTE MOTOR WITH GEAR-BOX

Good American make. Operates from mains and will drive switch mechanism or other medium device. Size approx. 4 1/2in. x 3in. x 2 1/2in. with 4in. diameter drive shaft. Price £2.20.

12V. CAR BLOWERS

Units made by Delco. 6 blades 5in. dia. fan inside heavy cylinder. These have really powerful series wound motors giving a terrific air flow suitable for ventilating or heating a car, boat, caravan, etc. Price £2.20, plus 40p post and insurance. (Note these are intended for 12V. D.C. but can be run from A.C. up to 30V. The higher the voltage the more the air flow).

13 AMP. SWITCHED SOCKETS

By G.E.C. Standard type for fused plugs. Brown bakelite, 17p each or £1.50 for 10.

V.H.E. AMPLIFIERS

With built in mains power pack, these are valve amplifiers. are metal-cased and co-axial inputs and outputs. Optimum amplification at T.V. frequency. Useful also for re-building into another unit which needs a mains power pack. Price £2.75.

3 CORE MAROON COTTON COVERED FLEX

Very best makers but old coloured code. 6 amp.—23/36 x 100 yd. coil £2 plus 50p. 15 amp.—70/35 x 50 yd. coil £3.95 plus 50p post.

INDICATOR AUDIBLE WARNING

Add this audible warning device to car indicators or dash panel warning lights and your attention will be instantly drawn to the warning lamp kit. £1.20.

NIGHT LIGHT SWITCH

A simple control to dim a lamp. Kit £1.10.

GENERAL PURPOSE AMPLIFIER

An audio amplifier of reasonable quality for use with radio tuners—audio oscillators, record decks—electric guitars, etc. Kit £4.90.

HOME INTERCOM

Keep in touch with this simple, easily connected good quality two way intercom. Kit £4.00.

FLASHING LIGHT METRONOME

For use in the musical field and the laboratory—where an audible not on click could get lost or become annoying. Kit £1.40.

MINI ORGAN

A three octave, stylus operated organ—neatly and simply constructed on a printed circuit board. Kit £4.75.

RAIN ALARM II

Sounds an audible alarm as soon as the first rain drops fall. Kit £3.00.

CASSETTE AMPLIFIER

Boosts the output from cassette tape recorders and transistor radios. Kit £4.50.

AUDIO SIGNAL MIXER

Where you want to mix speech and music, and to fade them in and out—no tape enthusiast should be without this. Kit £3.90.

AUTO FAN

A thermostatic control for car engine fan, gives quicker warming up time, etc. Kit £2.35.

SLAVE FLASH

Photos taken with a single flash have a "flat" appearance—a second flash correctly positioned overcomes this. This unit encloses a second (or third) flash to be automatically triggered. Kit £1.85.


ELECTRONIC DOORBELL

Not in fact a bell but an electronic circuit that produces an unusual sound when the button is pressed. Kit £4.00.

Where postage is not stated then orders over £5 are post free. Below £5 add 20p. S.A.E. with enquiries please.

J. BULL (ELECTRICAL) LTD.

(Dept. W.W.) 7, Park Street, Croydon, CR0 1YD
Callers to 102/3, Tamworth Road, Croydon



MARCONI SIGNAL GENERATOR TYPE TF-144G: Freq. 85 Kc/s-25 Mc/s in 8 ranges. Incremental: $\pm 1\%$ at 1 Mc/s. Output: continuously variable 1 microvolt to 1 volt. Output Impedance: 1 microvolt to 100 millivolts, 10 ohms 100mV - 1 volt - 52.5 ohms. Internal Modulation: 400 c/s sine wave 75% depth. External Modulation: Direct or via internal amplifier. A.C. mains 200/250V, 40-100 c/s. Consumption approx. 40 watts. Measurements 29 x 12 $\frac{1}{2}$ x 10 in. Secondhand condition. £27.50 each, Carr. £1.50.

T.1509 TRANSMITTERS (FOR EXPORT ONLY): General-purpose HF communications transmitter for use in fixed or mobile ground stations. Hand or high-speed keying. Crystal or MO control, with temperature compensated MO circuit. CW, MCW and R/T. Frequency: 1.5 to 20 Mc/s. Modulation: 100% O/p/ut impedance: 50 ohms. Audio input: 600 ohms. Valves: Power Amplifier 2 x 813 and Modulator 2 x 813. Power requirements 200-250 volts a.c., 50 cycles. Power out put 300 watts. Dimensions 2ft. 6in. W. x 2ft. D. x 5ft. H. Weight: 800 lbs. Excellent condition, price £225.00 each.

AN/ARC-27 TRANSMITTER/RECEIVER (FOR EXPORT ONLY): Frequency 225-400 mc. 1750 channels 100 Kc apart with 18 preset channels. Modulation: am. Power output 9 watts. Receiver is superheterodyne. Max. output 2 watts. Antenna: 50 ohm impedance. Power requirements 24v d.c. Complete transmitter with operating cables, control box, headphones, microphone. Price £250.00 each secondhand, excellent condition.

POWER SUPPLY suitable for AN/ARC-27: 100 volts to 250 volts a.c. input. 24v d.c. output @ 41 amps fully smoothed. £45.00 each.

FREQUENCY METER BC-221: 125-20,000 Kc/s, complete with original calibration charts. Checked out, working order. £18.50 + £1.00 carr. BC-221 Unused as new condition complete with headset, spare valves, charts. £35.00 + £2.00 carr.

CT.52 MINIATURE OSCILLOSCOPE: Portable. Operates from 115V or 250V 50-60c/s; or 180V 500c/s. A small compact tropicalised instrument designed to meet requirements of radar and communication engineers and general electronic service. Measures 9 in. x 8 in. x 6 in. Time base 10c/s-40Kc/s. Y plate sensitivity 40V per cm. Tube 2 $\frac{1}{2}$ in. Frequency compensated amplifier up to 38dB gain. Bandwidth up to 1 Mc/s. Single sweep facilities. Complete with test leads, metal transit case. As new £27.50 each. Carr. £1.

TUNING UNIT: 24V geared motor driving double 25pf double spaced variable capacitor. One m/c relay and 2 other relays. £2.50 each 30p post, good condition.

UHF ASSEMBLY: (suitable for 1,000MHz conversion) including UHF valves: 2C42, 2C46, 1B40 (complete with associated capacitors and screening), 3 manual counters 0-999. Valves 6AL5 and 8 x 6AK5. £10.00 plus 60p post, good condition.

MODULATOR UNIT: complete with transformer and 2 x 807 valves mounted in 19 in. chassis x 8 in. high x 8 in. deep. £4.50 secondhand cond., or £6.50 new cond. Carriage £1.

RF UNIT: suitable for use with the above unit. Complete with 2 x 3E29 valves. Ideal for conversion to 4 metres. £5 secondhand cond., or £7.50 new cond. Carriage £1.

POWER SUPPLY UNIT PN-12A: 230V a.c. input 50-60 c/s. 513V and 1025V @ 420 mA output. With 2 smoothing chokes 9H, 2 Capacitors, 10Mfd 1500V and 10Mfd 600V. Filament Transformer 230V a.c. input. 4 Rectifying Valves type 5Z3. 2 x 5V windings @ 3 Amps each, and 5V @ 6 Amp and 4V @ 0.25 Amp. Mounted on steel base 19" W x 11" H x 14" D. (All connections at the rear.) Excellent condition £6.50 each, carr. £1.

AUTO TRANSFORMER: 230-115V, 50-60c/s, 1000 watts, mounted in a strong steel case 5" x 6 $\frac{1}{2}$ " x 7". Bitumen impregnated. £7 each, Carr. 75p. 230-115V, 50-60c/s, 500 watts. 7" x 5" x 5". Mounted in steel ventilated case. £4.00 each, Carr. 75p.

MODULATOR UNIT: 50 watt, part of BC-640, complete with 2 x 811 valves, microphone and modulator transformers etc. £7.50 each, 75p carr.

CATHODE RAY TUBE UNIT: With 3in. tube, Type 3EG1 (CV1526) colour green, medium persistence complete with nu-metal screen, £3.50 each, post 50p.

APN-1 INDICATOR METER, 270° Movement. Ideal for making rev. counter. £1.25, post 30p.

AIRCRAFT SOLENOID UNIT S.P.S.T.: 24V, 200 Amps, £2 each, 30p post.

DECADE RESISTOR SWITCH: 0.1 ohm per step. 10 positions. 3 Gang, each, 0.9 ohms. Tolerance $\pm 1\%$ £3 each, 25p post. 90 ohms per step. 10 positions, total value 900 ohms. 3 Gang. Tolerance $\pm 1\%$ £3.50 each, post 30p.

TF-1041B VALVE VOLTMETER: Measures 25mV to 300V, 20 c/s to 1500 Mc/s a.c. Also 10mV to 1000V d.c. Resistance 0.02 ohms to 500 Meg. ohms. Power requirements 200-250 volts a.c. Secondhand, excellent con. £35.00. Carr. £1.

VARIAC TRANSFORMERS: Input 115V, output 0-135V at 2 Amps. £3 each 75p post.

RACK CABINETS: (totally enclosed) for Std. 19 in. Panels. Size 6 ft. high x 21 in. wide x 16 in. deep, with rear door. £12 each, £2.50 Carr. OR 4 ft. high x 23 in. wide x 19 in. deep, with rear door. £8.50, each, £2 Carr.

INSTRUMENT CABINETS: 19" W. x 16" H. x 16" D. £5.00 + £1.25 carr. 19" W. x 10" D. x 5" H. £2.50 + £1.00 carr.

FUEL INDICATOR Type 113R: 24V complete with 2 magnetic counters 0-9999, with locking and reset controls mounted in 3in. diameter case. Price £2 each, 30p post.

TS-418/URM49 SIGNAL GENERATOR: Covers 400-1000MHz range. CW Pulse or AM emission. Power Range 0-120 dbm. £125 each. Carr. £1.50.

ALL U.K. ORDERS SUBJECT TO 10% VALUE ADDED TAX. THIS MUST BE ADDED TO THE TOTAL PRICE (including post or carriage).

TN/130/APR.9 UHF TUNING UNIT: Freq. 4300-7350MHz. IF Output 160MHz with bandwidth of 20MHz and is electrically tuned by a d.c. reversible motor. £27.50 each. Carr. £1.

APR-4 AM RADIO RECEIVER: 90-1000MHz. This receiver is suitable for monitoring and measuring frequencies as well as relative signal strength. Power Supply 115V 50c/s. £100 each. Carr. £2.

SIGNAL GENERATOR TS-497B/URR: (Boonton). Freq. 2-400 Mc/s in 6 bands. Internal Mod. 400 or 1000 c/s per sec. External Mod. 50 to 10,000 c/s per sec. External PM. Percent Mod. 0-30 for sine wave. Am or Pulse Carrier. O/p/ut Voltage 0.1-100,000 microvolts cont. variable. Impedance 50 Ω . Price: £85 each + £1.50 carr.

CLASS "D" WAVEMETER NO. 1 MK. II: Crystal controlled heterodyne frequency meter covering 2-8MHz. Power supply 6V d.c. Good secondhand cond. £7.50 each. Post 60p.

RCA TE-149 HETERODYNE WAVEMETER: V-cut, 1MHz crystal (0.005%). Accuracy better than 0.02%. Dial directly calibrated every 1KHz from 2.5-5MHz. Useful harmonics up to 20MHz. Provision for fitting internal dry batteries. "As new" complete with Manual and Spares. £14 each. Carr. 75p.

POWER UNIT TYPE 24: (for R.216 Receiver) A.C. operated 100-125V or 200-250V, 50c/s. "As new" £10 each. Carr. 75p.

ROTARY INVERTERS: TYPE PE.218E—input 24-28V d.c., 80 Amps. 4,800 rpm. Output 115V a.c. 13 Amp 400 c/s. 1 Ph. P.F.9. £17.50 each. Carr. £1.50.

POWER SUPPLY: 230V a.c. input; 3000V @ 2.5mA; 4v @ 1 Amp. 300-0-300 200mA; 6V @ 7 Amp; 6V @ 3 Amp. With smoothing capacitors etc. £10.00 each. £1.50 carr.

ACTUATOR UNIT: With 115V d.c. geared motor; o/p/ut 12.5 rpm; torque 16 ins. oz; reversible; microswitches and potentiometer. £3.50 ea. + 40p post.

DALMOTORS: 24-28V d.c. at 45 Amps; 750 watts (approx. 1hp) 12,000rpm. £5 each, 60p post.

MOTOR: 240V single phase, 2,400 rpm. 1/40 H.P. approx. Price £1.75 each, 30p post.

CONDENSERS: 30 mfd 600 v wkg. d.c., £3.50 each, post 50p. 10 mfd 600 v. 43p each, 25p post. 8 mfd 2500 v. £5 each, carr. 63p. 8 mfd 600 v. 43p each, post 15p. 8 mfd. 1% 300 v. D.C. £1.25, post 25p. 4 mfd 3000 v. wkg. £3 each, post 37p. 4 mfd 2000 v. £2 each, post 25p. 4 mfd 600 v., 2 for £1. 0.01 mfd MICA 2.5Kv, £1 for 5, post 10p. Capacitor 0.125 mfd, 27,000 v. wkg. £3.75 each, 50p post. 2.25 mfd 25 Kv. wkg. £20 each, £3 carr. 2 mfd 12.5 Kv wkg. TCC RL 7002-97 £8.50 each, carr. £1. 10 mfd 3 Kv wkg. 55°C. TCC oil filled £7.50 each, £1 carr. 5 x 1 mfd 3 Kv wkg. 55°C. £6.50 each, £1 carr. 12 mfd 1500v d.c. wkg. £3.50 each, 50p post.

CONTROL PANEL: 230 v. A.C., 24 v. D.C. @ 2 amps, £2.50 each, carr. 75p.

OHMITE VARIABLE RESISTOR: 5 ohms, 5 $\frac{1}{2}$ amps; or 40 ohms at 2.6 amps; 500 ohms, 0.55 amps. Price (either type) £2 each, 30p post each.

TX DRIVER UNIT: Freq. 100-156 Mc/s. Valves 3 x 3C24's; complete with filament transformer 230 v. A.C. Mounted in 19in. panel, £4.50 each, carr. 75p.

AR88 RECEIVER: List of spares, 5p.

TELEPRINTER EQUIPMENT, REPERFORATORS, READERS, and AUTO TRANSMITTERS ETC. Send for list, 5p.

REDIFON TELEPRINTER RELAY UNIT NO. 12: ZA-41196 and power supply 200-250V a.c. Polarised relay type 3SEITR. 80-0-80V 25mA. Two stabilised valves CV 286. Centre Zero Meter 10-0-10. Size 8in. x 8in. x 8in. New condition £7.50, Carr. 75p.

WESTON INDUSTRIAL THERMOMETER MODEL 221: 0-100°C. 3in. dia. scale. Accuracy 1%. Precision made coil within-coil structure. Changes in temperature cause a rotary action of the Helix turning the shaft to which the pointer is mounted. £2.80 each 30p post. Unused condition.

TRANSMITTER UNITS: Complete with 12V vibrator unit QQVO3-20A and 5 other valves with modulation transformer, etc. Two crystal controlled channels. Suitable for conversion to 2 metres. £5 + £1 carr.

THERMOCOUPLE METER: Scale 3-5 AE 2in. square flush mounting. £2.50 + 25p post.

TS 15C/AP FLUXMETER: Used to provide qualitative measurements of flux densities between pole faces of magnets. Range 1200-9600 gauss. $\pm 2\%$. S/hand good cond. £25 + 60p post.

SYNCHRO DISTORTION AND MARGIN TEST SET: (Onwood Type 4A2) S/hand excellent cond. £85 each. Carr. £2.

MASTER SYNCHRO TEST SET T.101031 (U.S.A.): 115 volts 400 c/s. S/hand cond. £15 each + £1 carr.

MAGSLIP TESTER NO. 2 MK. I: S/hand cond. £25 each + £1 carr.

SYNCHROS: and other special purpose motors available. Send for list. S.A.E.

PANORAMIC ADAPTOR TYPE ALA2: Suitable for use with APR-1, APR-4, and other Receivers having an I.F. frequency of 30 MHz. Will display signals up to 5 MHz either side of the received frequency. Power Supply 115V a.c. 400 c/s. Tube 3PB1 with nu-metal screen. £8.50 each. £1 carr. S/hand cond.

MURHEAD PAMETRADA WAVE ANALYSER D-489-D: Primarily used for the analysis of complex vibration waveforms, but will measure audio and power frequency waveforms from 19 c/s to 21 kc/s. Complete with power supply unit 230 volts 50 c/s. S/hand good cond. £82.50 + £2 carr.

D-652 L.F. MODULATOR: Suitable for use with the above Wave Analyser D-489-D enabling the analysis of low frequencies between 2 and 20 c/s. S/hand good cond. £25 each + £1. carr.

AUTOMATIC VIBRATION EXCITER CONTROL UNIT TYPE 1016 Manufactured by Bruel & Kjoer. 5-5000 c/s. per second. S/hand very good cond. £90 + £2 carr.

INSULATION TEST SETS: A.C. or D.C. 0-5 kV. £22.50. S/hand cond. AND 0-3 kV. Positive and negative outputs, fine and course control. £17.50. S/hand cond. Carr. both types £2.

INSULATION TEST SET: 0-10 kV negative, earth with amplifier provision for checking ionisation. 110/230V a.c. input. S/hand good cond. £30 + £1 carr.

BOONTON SIGNAL GENERATOR TYPE 202B A.M./F.M.: 54-216 MHz in three bands. Deviation 24, 80 and 240 kc/s. Attenuator is adjustable 0.1 Vv to 0.2V. As new condition. £175 + £2 carr.

AVO FIXED ATTENUATORS: 75 ohms. £2.50 + 20p post. New cond.

R.F. POWER METER: 0-30 watts S/hand good cond. £27.50 + £1 carr.

AVO VALVE TESTER AND CHARACTERISTIC METER: S/hand good condition. £35 each + £2 carr.

AVO VALVE TESTER MK. III: £30 + £2 carr.

If wishing to call at stores, please telephone for appointment.

W. MILLS

3-B TRULOCK ROAD, LONDON, N17 0PG
Phone: 01-808 9213 and Bedford 740605 (STD 0234).

BENTLEY ACOUSTIC CORPORATION LTD.

7A GLOUCESTER ROAD, LITTLEHAMPTON, SUSSEX. Tel. 6743
ALL PRICES SHOWN INCLUDE V.A.T.

0A2	0-33	6BC8	0-20	6L12(M)	0-50	12A7E	0-28	30P12	0-69	ARP3	0-35	EC53	0-49	N709	0-21	PY80	0-33	UY85	0-23	2N966	0-58	AF178	0-75	F8Y41A	25	OC23	0-42
0B2	0-33	6BE6	0-20	6L12	0-34	12A7F	0-20	30P16	0-31	ATP4	0-40	EC54	0-49	F630	0-40	PY81	0-25	U10	0-45	2N1766	0-55	AF180	0-58	G104	0-36	OC24	0-42
0Z4	0-44	6BG6G	1-05	6L18	0-49	12A7G	0-38	30P19	0-38	AZ1	0-40	EC86	0-59	PABCS8	0-40	PY82	0-25	U15/14	0-38	2N2147	0-94	AF186	0-61	G115	0-31	OC25	0-42
1A3	0-44	6BH6	0-70	6L21	2-00	12A7H	0-21	30P1	0-65	AZ31	0-40	EC88	0-59	U16	0-75	PY83	0-28	U16	0-75	2N2927	0-25	AF189	0-14	G116	0-31	OC26	0-66
1A5GT	0-49	6BK7A	0-80	6L22	0-30	12A7I	0-28	30P12	0-29	B319	0-29	ECC32	1-50	U17	0-35	PY88	0-31	U17	0-35	2N2369A	24	ASY27	0-47	G118	0-28	OC29	0-89
1A7GT	0-38	6BK7B	0-80	6L22	0-30	12A7J	0-28	30P13	0-29	B319	0-29	ECC32	1-50	U18/20	0-75	PC88	0-44	U18/20	0-75	2N2369A	24	ASY28	0-47	G118	0-28	OC35	0-35
1B3GT	0-49	6BQ5	0-23	6L22	0-30	12A7K	0-28	30P14	0-29	B319	0-29	ECC32	1-50	U19	1-73	PC88	0-44	U19	1-73	2N2369A	24	ASY29	0-47	G118	0-28	OC36	0-47
1C2	0-50	6BQ7A	0-50	6P1	1-75	12A7L	0-28	30P15	0-29	B319	0-29	ECC32	1-50	U22	0-39	PC88	0-44	U22	0-39	2N2369A	24	ASY30	0-47	G118	0-28	OC38	0-47
1G6	0-75	6BR7	0-90	6P15	0-23	12A7M	0-28	30P16	0-31	B319	0-29	ECC32	1-50	U25	0-65	PC88	0-44	U25	0-65	2N2369A	24	ASY31	0-47	G118	0-28	OC41	0-55
1H5GT	0-45	6BR8	0-75	6P28	0-70	12A7N	0-28	30P17	0-31	B319	0-29	ECC32	1-50	U26	0-65	PC88	0-44	U26	0-65	2N2369A	24	ASY32	0-47	G118	0-28	OC42	0-55
1L4	0-15	6BR7	1-40	6PL12	0-28	12A7O	0-28	30P18	0-31	B319	0-29	ECC32	1-50	U28	0-81	PC88	0-44	U28	0-81	2N2369A	24	ASY33	0-47	G118	0-28	OC43	0-55
1LD5	0-60	6BW6	0-50	6Q7G	0-44	12A7P	0-28	30P19	0-31	B319	0-29	ECC32	1-50	U33	1-50	PC88	0-44	U33	1-50	2N2369A	24	ASY34	0-47	G118	0-28	OC44	0-55
1LN5	0-60	6BW7	0-50	6Q7G	0-44	12A7Q	0-28	30P20	0-31	B319	0-29	ECC32	1-50	U35	0-83	PC88	0-44	U35	0-83	2N2369A	24	ASY35	0-47	G118	0-28	OC45	0-12
1NSGT	0-60	6BX6	0-23	6R7(M)	0-55	12A7R	0-28	30P21	0-31	B319	0-29	ECC32	1-50	U37	1-75	PC88	0-44	U37	1-75	2N2369A	24	ASY36	0-47	G118	0-28	OC46	0-17
1R5	0-28	6BY7	0-28	6R7(M)	0-55	12A7S	0-28	30P22	0-31	B319	0-29	ECC32	1-50	U40	0-80	PC88	0-44	U40	0-80	2N2369A	24	ASY37	0-47	G118	0-28	OC47	0-12
184	0-33	6BZ6	0-49	6R7(M)	0-55	12A7T	0-28	30P23	0-31	B319	0-29	ECC32	1-50	U45	0-78	PC88	0-44	U45	0-78	2N2369A	24	ASY38	0-47	G118	0-28	OC48	0-17
185	0-22	6C4	0-28	6S7(M)	0-38	12A7U	0-28	30P24	0-31	B319	0-29	ECC32	1-50	U49	0-90	PC88	0-44	U49	0-90	2N2369A	24	ASY39	0-47	G118	0-28	OC49	0-12
1U4	0-44	6C6	0-22	6S7(M)	0-38	12A7V	0-28	30P25	0-31	B319	0-29	ECC32	1-50	U50	0-30	PC88	0-44	U50	0-30	2N2369A	24	ASY40	0-47	G118	0-28	OC52	0-12
1U5	0-50	6C9	1-00	6S7(M)	0-38	12A7W	0-28	30P26	0-31	B319	0-29	ECC32	1-50	U57	0-24	PC88	0-44	U57	0-24	2N2369A	24	ASY41	0-47	G118	0-28	OC54	0-11
2D21	0-44	6CBA	0-40	6S7(M)	0-38	12A7X	0-28	30P27	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY42	0-47	G118	0-28	OC55	0-12
2D91	0-55	6C12	0-28	6S7(M)	0-38	12A7Y	0-28	30P28	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY43	0-47	G118	0-28	OC56	0-12
3A4	0-36	6C17	1-00	6S7(M)	0-38	12A7Z	0-28	30P29	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY44	0-47	G118	0-28	OC57	0-12
3B7	1-00	6CD8G	0-80	6S7(M)	0-38	12A7A	0-28	30P30	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY45	0-47	G118	0-28	OC58	0-12
3D6	0-18	6CDA	0-75	6S7(M)	0-38	12A7B	0-28	30P31	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY46	0-47	G118	0-28	OC59	0-12
3Q4	0-48	6CH4	0-55	6U7G	0-70	12A7C	0-28	30P32	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY47	0-47	G118	0-28	OC60	0-12
3Q5GT	0-55	6CL6	0-48	6V4	0-19	12A7D	0-28	30P33	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY48	0-47	G118	0-28	OC61	0-12
384	0-28	6CMA	0-80	6V6G	0-17	12A7E	0-28	30P34	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY49	0-47	G118	0-28	OC62	0-12
4C86	0-55	6CM7	0-75	6V6G	0-17	12A7F	0-28	30P35	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY50	0-47	G118	0-28	OC63	0-12
5C88	0-55	6CJ5	0-75	6V6G	0-17	12A7G	0-28	30P36	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY51	0-47	G118	0-28	OC64	0-12
5R4GY	0-70	6CW4	0-70	6V6G	0-17	12A7H	0-28	30P37	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY52	0-47	G118	0-28	OC65	0-12
5T4	0-30	6D3	0-60	6V6G	0-17	12A7I	0-28	30P38	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY53	0-47	G118	0-28	OC66	0-12
5U4G	0-30	6DE7	0-75	6V6G	0-17	12A7J	0-28	30P39	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY54	0-47	G118	0-28	OC67	0-12
5V4G	0-35	6DT6	0-75	6V6G	0-17	12A7K	0-28	30P40	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY55	0-47	G118	0-28	OC68	0-12
5Y3GT	0-30	6EW6	0-75	6V6G	0-17	12A7L	0-28	30P41	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY56	0-47	G118	0-28	OC69	0-12
5Z3	0-53	6E5	0-75	6V6G	0-17	12A7M	0-28	30P42	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY57	0-47	G118	0-28	OC70	0-12
5Z4G	0-34	6F1	0-70	6V6G	0-17	12A7N	0-28	30P43	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY58	0-47	G118	0-28	OC71	0-12
5Z4GT	0-38	6P6G	0-35	6V6G	0-17	12A7O	0-28	30P44	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY59	0-47	G118	0-28	OC72	0-12
8/3012	0-55	6F12	0-17	6V6G	0-17	12A7P	0-28	30P45	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY60	0-47	G118	0-28	OC73	0-12
6A8G	0-44	6F13	0-45	6V6G	0-17	12A7Q	0-28	30P46	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY61	0-47	G118	0-28	OC74	0-12
4A 7	0-15	6F14	0-40	6V6G	0-17	12A7R	0-28	30P47	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY62	0-47	G118	0-28	OC75	0-12
6A55	0-27	6F15	0-65	6V6G	0-17	12A7S	0-28	30P48	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY63	0-47	G118	0-28	OC76	0-12
6A11G	0-60	6F18	0-55	6V6G	0-17	12A7T	0-28	30P49	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY64	0-47	G118	0-28	OC77	0-12
6A18	0-28	6F24	0-80	6V6G	0-17	12A7U	0-28	30P50	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY65	0-47	G118	0-28	OC78	0-12
6AK5	0-27	6F25	0-51	6V6G	0-17	12A7V	0-28	30P51	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY66	0-47	G118	0-28	OC79	0-12
6AK6	0-60	6F26	0-28	6V6G	0-17	12A7W	0-28	30P52	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY67	0-47	G118	0-28	OC80	0-12
6AK9	0-30	6F28	0-60	6V6G	0-17	12A7X	0-28	30P53	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY68	0-47	G118	0-28	OC81	0-12
6AL5	0-12	6F32	0-30	6V6G	0-17	12A7Y	0-28	30P54	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY69	0-47	G118	0-28	OC82	0-12
6AM2A	0-55	6G6G	0-38	6V6G	0-17	12A7Z	0-28	30P55	0-31	B319	0-29	ECC32	1-50	U78	0-27	PC88	0-44	U78	0-27	2N2369A	24	ASY70					

BI-PRE-PAK

SUPPLIERS OF SEMICONDUCTORS TO THE WORLD



COMPLETE TELEPHONES
NORMAL HOUSEHOLD TYPE
AS SUPPLIED TO THE POST OFFICE
EX. G.P.O.

ONLY £1.05p
P & P 45p EACH



TELEPHONE DIALS

Standard Post Office type
Guaranteed in working order

ONLY 27½p
P & P 16½p EACH

TESTED AND GUARANTEED PAKS

- B79 **4** IN4007 Sil Rec diodes, 1.000 PIV lamp plastic **55p**
- B81 **10** Reed Switches 1" long ½" dia. High speed P.O. type **55p**
- B99 **200** Mixed Capacitors Approx quantity, counted by weight, P & P 15p. **55p**
- H4 **250** Mixed Resistors Approx quantity, counted by weight, P & P 15p. **55p**
- H7 **40** Wirewound Resistors Mixed types and values **55p**
- H9 **2** OCP71 Light Sensitive Photo Transistor **55p**
- H28 **20** OC200/1/2/3 PNP Silicon uncoded TO 5 can **55p**
- H30 **20** 1 Watt Zener Diodes, Mixed Voltages 6.8-43V. **55p**
- H35 **100** Mixed Diodes, Germ. Gold bonded etc. Marked and Unmarked. **55p**
- H38 **30** Short lead Transistors, NPN Silicon Planar types **55p**
- H39 **6** Integrated circuits, 4 Gates BMC 962, 2 Flip Flops BMC 945 **55p**
- H40 **20** BFY50/2, 2N696, 2N1613 NPN Silicon uncoded TO-5 **55p**
- H41 **2** Power Transistors Comp. Pair BD131/132 **55p**

UNMARKED UNTESTED PAKS

- B1 **50** Germanium Transistors PNP, AF and RF. **55p**
- B66 **150** Germanium Diodes Min. glass type **55p**
- B83 **200** Trans. manufacturers' rejects all types NPN, PNP, Sil. and Germ **55p**
- B84 **100** Silicon Diodes DO-7 glass equiv. to OA200, OA202 **55p**
- B86 **100** Sil. Diodes sub. min. IN914 and IN916 types **55p**
- H6 **40** 250mV Zener Diodes DO-7 Min. Glass Type **55p**
- H15 **30** Top Hat Silicon Rectifiers, 750mA Mixed volts **55p**
- H16 **15** Experimenters Pak of Integrated Circuits. Data supplied **55p**
- H17 **20** 3 Amp. Silicon Stud Rectifiers, Mixed volts **55p**
- H26 **40** NPN Silicon Trans. 2N3707-11 range, low noise amp **55p**
- H34 **15** Power Transistors, PNP, Germ NPN Silicon TO-3 Can. P & P 5p extra. **55p**

MAKE A REV COUNTER FOR YOUR CAR

The "TACHO BLOCK" This encapsulated block will turn any 0-1mA meter into a linear and accurate rev. counter for any car with normal coil ignition system.

£1.10 each



OVER 1,000,000 TRANSISTORS IN STOCK

We hold a very large range of fully marked, tested and guaranteed Transistors, Power Transistors, Diodes and Rectifiers at very competitive prices. Please send for Free Catalogue.

SILICON PLANAR PLASTIC TRANSISTORS

Unmarked, untested — factory clearance Audio, PNP, similar to ZTX500, 2N3702/3, BCY70 etc. Audio NPN, similar to ZTX300, 2N3708/9, BC107/8/9, BC168/9 etc. R.F. NPN and Switching NPN. Please state type of Transistor required when ordering. ALL AT 500 for £3.30. 1,000 for £5.50. 10,000 for £44.00.

OUR VERY POPULAR 4p TRANSISTORS FULLY TESTED & GUARANTEED

TYPE "A" PNP Silicon alloy, TO-5 can.
TYPE "B" PNP Silicon, plastic encapsulation.
TYPE "E" PNP Germanium AF or RF.
TYPE "F" NPN Silicon plastic encapsulation.
TYPE "G" NPN Silicon, similar ZTX300 range.
TYPE "H" PNP Silicon, similar ZTX500 range.

Various Types
8 RELAYS FOR £1.10
Post & Packing 27½p

Our famous P1 Pak is still leading in value for money.

Full of Short Lead Semiconductors & Electronic Components, approx. 170. We guarantee at least 30 really high quality factory marked Transistors PNP & NPN and a host of Diodes & Rectifiers mounted on Printed Circuit Panels. Identification Chart supplied to give some information on the Transistors.

Please ask for Pak **P.1. Only 55p**
11p P & P on this Pak.



A CROSS HATCH GENERATOR FOR £3.85

YES, a complete kit of parts including Printed Circuit Board. A four position switch gives X-hatch, Dots, Vertical or Horizontal lines. Integrated Circuit design for easy construction and reliability. This was a project in the September 1972 edition of Practical Television.

This complete kit of parts costs £3.85, post paid.

A MUST for Colour T.V. Alignment.

ELECTRONIC TRANSISTOR IGNITION

Now in kit form, we offer this "up to the minute" electronic ignition system. Simple to make, full instructions supplied with these outstanding features: Transistor and conventional switchability, burglar proof lock up and automatic alarm, negative and positive compatibility. This project is a "star" feature in the September edition of "Electronics Today International" magazine available from Aug. 10th. Our kit is recommended by the ETI magazine.

Complete kit including P & P £7.92.
Ready built and tested unit £3.02 EXTRA.

FREE CATALOGUE

for TRANSISTORS, RECTIFIERS, DIODES, INTEGRATED CIRCUITS AND FULL PRE-PAK LISTS



Plastic Power Transistors

NOW IN TWO RANGES

These are 40W and 90W Silicon Plastic Power Transistors of the very latest design, available in NPN or PNP at the most shatteringly low prices of all time. We have been selling these successfully in quantity to all parts of the world and we are proud to offer them under our Tested and Guaranteed terms.

RANGE 1 VCE Min. 15	1-12	13-25	26-50
HFE Min. 15			
40 Watt	22p	20p	18p
90 Watt	26½p	24½p	22p
RANGE 2VCE Min. 40			
HFE Min. 40			
40 Watt	33p	31p	29p
90 Watt	38½p	36½p	33p

Complementary pairs matched for gain at 3 amps, 11p extra per pair. Please state NPN or PNP on order.

INTEGRATED CIRCUITS

We stock a large range of I.C.s at very competitive prices (from 11p each). These are all listed in our FREE Catalogue, see coupon below.

METRICATION CHARTS now available.

This fantastically detailed conversion calculator carries thousands of classified references between metric and British (and U.S.A.) measurements of length, area, volume, liquid measure, weights etc.

Pocket Size 15p. Wall Chart 18p.

LOW COST DUAL IN LINE I.C. SOCKETS

14 pin type at 16½p each } Now new low profile type.
16 pin type at 18p each }

BOOKS

We have a large selection of Reference and Technical Books in stock.

These are just two of our popular lines:

B.P.1. Transistors Equivalents and Substitutes 40p, this includes many thousands of British, U.S.A., European and C.V. equivalents.

The 11ffe Radio Valve and Transistor Data Book, 9th Edition 75p. Post & Packing 23½p extra. Characteristics of 3,000 valves and tubes, 4,500 Transistors, Diodes, Rectifiers and Integrated Circuits. Send for lists of these English publications. N.B. No V.A.T. to pay on books.

BUMPER BUNDLES

These parcels contain all types of surplus electronic components, printed panels, switches, potentiometers, transistors and diodes, etc.

2 LBS IN WEIGHT FOR £1.10
Post and packing 27½p.

Please send me the FREE Bi-Pre-Pak Catalogue.

ALL PRICES INCLUDE 10% VAT

NAME

ADDRESS

MINIMUM ORDER 50p CASH WITH ORDER PLEASE. Add 11p post and packing per order. OVERSEAS ADD EXTRA FOR POSTAGE.

BI-PRE-PAK LTD

DEPT. B, 222-224 WEST ROAD, WESTCLIFF-ON-SEA, ESSEX
TELEPHONE: SOUTHEND (0702) 46344

Henry's

Your Complete Audio-Electronic Stores

BUILD THE TEXAN

20+20 WATT INTEGRATED I.C. STEREO AMPLIFIER

★ FREE TEAK CABINET with complete kits!
FEATURES. New slim design with 6-IC's IC Sockets, 10 silicon transistors, 4 rectifiers, 2 zeners. Special Gardeners low field slim line transformer. Fibre glass PC panel. Complete chassis work. **HIGH QUALITY & STABILITY ARE PREDOMINATE FEATURES**—DEVELOPED BY TEXAS ENGINEERS FOR PERFORMANCE—**RELIABILITY AND EASE OF CONSTRUCTION.**
FACILITIES. On/off switch indicator, headphone socket, separate treble, bass, volume and balance controls, scratch and rumble filters, mono/stereo switch, Input selector; Mag. P.U. Radio Tuner, Aux. Can be altered for Mic, Tape, Tape-head, etc. (Parts list Ref. 20 on request). Constructional details (ref no 21) 30p.



(As featured in "Practical Wireless" May to August 1972)
 ★ SLIM DESIGN WITH SILVER TRIM. Overall chassis size 14½" x 6" x 2" high.

P. & P. 45p.
COMPLETE WITH FREE TEAK CABINET
 Designer approved kit distributed by Henry's Radio Ltd.

SPECIAL KIT PRICE **£28.50**

LATEST EDITION CATALOGUE

AN ABSOLUTE MUST IN ELECTRONICS
LATEST EDITION! Fully detailed and illustrated covering every aspect of Electronics—plus data, circuits and information. 10,000 Stock lines at Special Low Prices and Fully Guaranteed.



PRICE **55p** Post Paid
 (40p FOR CALLERS)
PLUS 1 FIVE 10p VOUCHERS

For use with purchases

Send to this address—HENRY'S RADIO LTD. (Dept WW) 3 ALBEMARLE WAY, LONDON, E.C.1.—for catalogue by post only. All other mail to '303' and callers to '404' see below

VAT ALL PRICES ARE EXCLUSIVE OF 10% VAT WHICH MUST BE ADDED TO ALL ORDERS INC. CARR. PACKING. (NOTE: CATALOGUE IS NOT SUBJECT TO VAT).

BUILD A VHF/FM TUNER



BUILD THIS VHF FM TUNER
 5 TRANSISTORS 300 k/c/s BANDWIDTH, PRINTED CIRCUIT, HIGH FIDELITY REPRODUCTION, MONO AND STEREO
 A popular VHF FM Tuner for quality and reception of mono and stereo. There is no doubt about it—VHF FM gives the REAL sound. All parts sold separately. Free Leaflet No. 3 & 7. **TOTAL £6.97** p.p. 20p. Mk I Decoder Kit £5.97. Built IC Decoder £5.50

Tuning meter unit £1.75.
 Mains unit (optional) £1.00.
 Mains unit for Tuner and Decoder PS6/12 £3.25.
 Post 20p.

SINCLAIR PROJECT 60 MODULES—SAVE £££'s

Z30	£3.57	STEREO 60	£18.00
PZ6	£6.37	PZ5	£3.97
Z50	£4.37	PZ8	£4.77
Transformer for PZ8			£2.95
Active Filter Unit			£4.45
Stereo FM Tuner			£16.95
IC12	£1.80	Q16's pr	£15
		Post etc.	20p per item.

PACKAGE DEALS

2x230, Stereo 60,	PZ5	Post 25p
2x230, Stereo 60,	PZ6	£15.95
2x250, Stereo 60,	PZ8	£20.25
Transformer for PZ8		£2.95
PROJECT 605 KIT		£19.95

INTEGRATED CIRCUITS!! Why buy alternatives when you can buy the genuine article from us at competitive prices from stock?

BRANDED FROM TEXAS I.T.T. FAIRCHILD

Type	1/11	12/24	25/99	Type	1/11	12/24	25/99	Type	1/11	12/24	25/99
SN7400	20p	18p	16p	SN7451	20p	18p	16p	SN74160	£2.00	£2.40	£2.25
SN7401	20p	18p	16p	SN7452	20p	18p	16p	SN74161	£2.00	£2.40	£2.25
SN7402	20p	18p	16p	SN7453	20p	18p	16p	SN74162	£2.00	£2.40	£2.25
SN7403	20p	18p	16p	SN7454	20p	18p	16p	SN74163	£2.00	£2.40	£2.25
SN7404	20p	18p	16p	SN7460	20p	18p	16p	SN74164	£2.75	£2.30	£2.10
SN7405	20p	18p	16p	SN7470	30p	27p	25p	SN74165	£1.55	£1.47	£1.35
SN7406	30p	27p	25p	SN7472	30p	27p	25p	SN74166	£1.55	£1.47	£1.35
SN7407	30p	27p	25p	SN7474	40p	37p	35p	SN74167	£1.80	£1.70	£1.50
SN7408	20p	18p	16p	SN7475	55p	52p	50p	SN74168	£2.00	£2.40	£2.25
SN7409	45p	42p	35p	SN7476	45p	42p	38p	SN74169	£2.00	£2.40	£2.25
SN7410	20p	18p	16p	SN7480	80p	75p	67p	SN74170	£4.10	£3.25	£2.70
SN7411	23p	22p	20p	SN7481	£1.25	£1.15	£1.10	SN74171	£2.00	£1.75	£1.60
SN7412	42p	40p	35p	SN7482	37p	35p	30p	SN74172	£2.00	£1.75	£1.60
SN7413	30p	27p	25p	SN7483	£1.00	90p	85p	SN74173	£1.35	£1.27	£1.15
SN7416	30p	27p	25p	SN7484	90p	85p	80p	SN74174	£4.00	£3.50	£3.00
SN7417	30p	27p	25p	SN7486	45p	41p	38p	SN74175	£4.00	£3.50	£3.00
SN7420	20p	18p	16p	SN7490	75p	70p	65p	SN74176	£1.60	£1.35	£1.20
SN7422	45p	44p	40p	SN7491	£1.00	95p	90p	SN74177	£1.80	£1.35	£1.20
SN7423	45p	44p	40p	SN7492	75p	70p	65p	SN74178	£1.80	£1.35	£1.20
SN7425	45p	40p	35p	SN7493	75p	70p	65p	SN74179	£1.55	£1.30	£1.15
SN7427	42p	39p	35p	SN7494	80p	75p	70p	SN74180	£1.55	£1.30	£1.15
SN7428	50p	45p	42p	SN7495	80p	75p	70p	SN74181	£7.00	£6.00	£5.50
SN7430	20p	18p	16p	SN7496	£1.00	97p	85p	SN74182	£2.00	£1.50	£1.40
SN7432	45p	44p	40p	SN7497	£5.25	£5.50	£5.00	SN74183	£2.00	£1.50	£1.40
SN7433	70p	61p	44p	SN7498	£2.50	£2.30	£2.00	SN74184	£2.00	£1.50	£1.40
SN7437	65p	60p	50p	SN74104	£1.45	£1.35	£1.20	SN74185A	£2.40	£2.00	£1.80
SN7438	65p	60p	50p	SN74105	£1.45	£1.35	£1.20	SN74186	£1.95	£1.55	£1.75
SN7440	20p	18p	16p	SN74107	50p	45p	40p	SN74187	£1.95	£1.55	£1.75
SN7441	75p	72p	70p	SN74110	80p	70p	60p	SN74188	£2.00	£1.50	£1.40
SN7442	75p	72p	70p	SN74118	£1.00	95p	90p	SN74189	£2.00	£1.50	£1.40
SN7443	£1.00	95p	90p	SN74119	£1.90	£1.78	£1.65	SN74190	£2.00	£1.50	£1.40
SN7445	£2.00	£1.75	£1.60	SN74121	60p	55p	50p	SN74195	£1.85	£1.70	£1.60
SN7446	£2.00	£1.75	£1.60	SN74122	£1.35	£1.25	£1.10	SN74196	£1.50	£1.40	£1.30
SN7447	£1.75	£1.60	£1.45	SN74123	£2.70	£2.55	£2.47	SN74197	£1.50	£1.40	£1.30
SN7448	£1.75	£1.60	£1.45	SN74131	£1.00	95p	90p	SN74198	£4.00	£3.70	£3.35
SN7460	20p	18p	16p	SN74145	£1.50	£1.40	£1.30	SN74199	£4.00	£3.70	£3.35

PRICES OF 7400 SERIES ARE CALCULATED ON THE TOTAL NUMBER ORDERED REGARDLESS OF MIX. LARGER QUANTITY PRICES PHONE 01-402 4991

PA-DISCO-LIGHTING!!

UK's Largest Range—Write, phone or call in. Details and demonstrations on request.
 DJ30L 3 Channel sound to light unit, 3kw. £29.50
 DJ40L 3 Channel Mic. (Built-in) to light, 3kw. £38.75
 DJ70S 70 watt Disco amp/mixer £49.75
 DISCO AMP 100 watt amp/mixer £65.85
 DJ105S 30 watt Disco amp/mixer £52.25
 DJ700 70 watt Ant.-Feedback Quality Mic. £11.50
 DJ500 50 watt PA Amplifier £43.95
 DJ700 70 watt £52.75

DJ1000 100 watt £63.00
 DJ300 150 watt rms "Group" Valve Amplifier £86.00
Fibre Optics Lighting. Mics. Effects. Projectors. Spots. Dimmers—Stands. Mixers. Speakers. Everything for PA—Disco—Lighting. FREE Stock List Ref. No. 18.
 ● PORTABLE DISCOS—DETAILS ON REQUEST.
 ● CREDIT TERMS FOR CALLERS.

TRIACS

STUD WITH ACCESSORIES

Type	Volts P.I.V.	Price 1-11
3 AMP RANGE	100	85p
SC35A	100	85p
SC35B	200	79p
SC35D	400	85p

6 AMP RANGE (TO48)

SC40A	100	85p
SC40B	200	90p
SC40D	400	£1.00
SC40E	500	£1.20

15 AMP RANGE (TO48)

SC50A	100	£1.25
SC50B	200	£1.35
SC50D	400	£1.65
SC50E	500	£1.85
DIAC D32		25p

SILICON RECTIFIERS

WIRE ENDED PLASTIC

Type	P.I.V.	1-11	amp miniature
IN4001	50	6p	
IN4002	100	7p	
IN4003	200	8p	
IN4004	400	8p	
IN4005	600	10p	
IN4006	800	12p	
IN4007	1000	15p	

RECTIFIERS

NEW BRIDGE RECTIFIERS SMALL SIZE AND LOW COST

Type	Volts P.I.V.	Price 1-11	B1/20	200	30p
BO5/05	50	20p	B1/60	600	35p
BO5/10	100	25p			
ONE AMP TUBULAR					
W005	50	30p			
W01	100	35p			
B1/05	50	25p			
B1/10	100	25p			

RECTIFIERS

SILICON CONTROLLED RECTIFIERS

Type	Volts P.I.V.	Price 1-11	THREE AMP (TO48)	SEVEN AMP (TO48)	
CRS 1/05	50	25p	CRS 3/05	50	30p
CRS 1/10	100	30p	CRS 3/10	100	30p
CRS 1/20	200	30p	CRS 3/20	200	35p
CRS 1/40	400	35p	CRS 3/40	400	45p
CRS 1/60	600	45p	CRS 3/60	600	55p
			FIVE AMP (TO66)		
			CRS 5/400	400	60p

RECTIFIERS

SL4030D PLESSEY 3 WATT R.M.S. I.C.

Complete with 8 page Data Booklet and Circuits £1.50. (P.C. Board Stereo 60p; Heat Sink 14p).
 Also Sinclair IC12 £1.80. TH9013P—20 watt Power Amp Module £4.57.
 TH9014P-IC Preamp £1.50. Data/Circuits for above No. 42 10p.
 ZN414 RADIO IC £1.20.

FREE STOCKLIST

Ref. No. 36 Revised Regularly
 TRANSISTORS, IC's DIODES, TRIACS, BRIDGES, SCR'S ZENERS, LDRS
 This advert contains just a small selection of the thousands of devices kept in stock. Send for Stock List Today! Quantity prices! Phone: 01-402 4891.



LINEAR (O/P AMPS)

702C TO5	75p
709C TO99	35p
709C D.I.L.	35p
723C TO99	£1.00
723C D.I.L.	95p
725C (TO99)	£4.50
741C TO99	55p
741C D.I.L.	55p
747C TO99	£1.10
747C D.I.L.	£1.10
72741P D.I.L.	60p
72748P D.I.L.	60p

MINIATURE AMPLIFIER

5 transistor. 300mW o/p. Fitted volume and sensitivity control, 9 volt operated. £1.75 each P/P 15p.

TEST EQUIPMENT

SE250B	Pocket Pencil Signal Injector	£1.90
SE500	Pocket Pencil Signal Tracer	£1.50
THL33D	Robust 2K/Volt	£4.95
TE15	Grid Dip Meter 440 KHz-280 mHz	£13.45
500	30 K/V Multimeter	£9.25
200H	20 K/V Multimeter	£4.20
AF105	50 K/V Multimeter	£8.50
U4341	AC/DC Multimeter with transistor tester. Steel case	£10.50
TE20D	RF Generator 120KHz-500MHz	£16.50
TE22D	Audio Generator 20Hz-200KHz	£17.50
C1-5	3" Pulse Scope 10Hz-10mHz	£39.00
TE65	Valve Voltmeter 28 ranges	£17.50

ALL NOMBREX MODELS IN STOCK

"BANDSPREAD" PORTABLE MW/LW TUNER
 To build MW/LW Superhet Radio using Mullard RF/IF Module, 600mW o/p. Fibre glass cabinet. All parts £7.98. P. & P. 32p. (Battery 22p extra.)

ZENER DIODES

400 M/W 5/ Min. voltage. BZY 88 Range. All voltages 3.3-33 Volt. 10p each.	25+ 9p; 100+ 8p; 500+ 6.5p. Any one type. 1 1/2 Watt 5/ Wire Ends, Metall Case.	All voltages. 6.8-100 Volts. 20p ea. 25+ 18p; 100+ 16p; 500+ 12p. Any one type.	2 Watt 5/ Plastic. 2EZ Range. 6.8-33 Volts. 25p each. 3 Watt Plastic. Wire Ends. 5/.
--	---	---	--

7 SEG & NIXIE TUBES

(Post 15p per 1 to 6)
 XN3, XN13, GNE 0-9 side view with data, 85p.
 GNP-7, GNP-8 0-9 side view with decimal points and data, 85p.
 30SF 7 seg. £2 each, £7 per 4 with data.
 12 and 24 hour clock circuits. Ref. No. 31 15p.

ULTRASONIC TRANSDUCERS

Operate at 40kc/s up to 100 yds. Ideal remote switching and signalling. Complete with data and new I.C. circuits. PRICE PER PAIR £5.90. Post 10p.

QUALITY SLIDER CONTROLS

60mm stroke singles and ganged. Complete with knobs. 5kΩ, 10kΩ, 25kΩ, 100kΩ, 250kΩ, 500kΩ, 1 meg. Log and Lin. 40p each, 10kΩ, 25kΩ, 50kΩ, 100kΩ, 250kΩ, Log and Lin ganged, 60p each.

MARRIOT TAPE HEADS

4 TRACK MONO or 2 TRACK STEREO
 '17" High Impedance £2.00
 '18" Med. Impedance £2.90
 '36" Med.-Low Imp. £3.50
 Erase Heads for above 75p
 '63" 2 track mono—High Impedance £1.75
 '43" Erase Head for above 75p.

Henry's RADIO LIMITED

EDGWARE ROAD, W2

All stores within 200 yards—call in and see for yourself
 404-406 Electronic Components and Equipment 01-402 8381
 354-356 High Fidelity and Tape Equipment 01-402 5854
 309 PA-Disco-Lighting High Power Sound 01-723 6963
 303 Special offers and bargains store
 All mail to 303 Edgware Road, London W2 1BW
 Open: 9 am-6 pm 6 days a week

FOR THE STOCKS, THE DISCOUNTS AND THE SERVICE YOU NEED

ELECTROVALUE

Electronic Component Specialists

RESISTORS—10%, 5%, 2%

Code	Power	Tolerance	Range	Values available	1 to 9	10 to 99	100 up
C	1/20W	5%	82Ω-220KΩ	E12	9	8	7.5
C	1/8W	5%	4.75Ω-470KΩ	E24	1	0.9	0.75 nett
C	1/4W	5%	4.75Ω-10MΩ	E12	1	0.9	0.75 nett
C	1/2W	5%	4.75Ω-10MΩ	E24	1.2	1	0.9 nett
CO	1W	5%	4.75Ω-10MΩ	E12	2.5	2	1.6 nett
MO	1/2W	2%	105Ω-1MΩ	E24	4	3	2 nett
WW	1W	10% ± 1/20Ω	0.225Ω-3.9Ω	E12	7	7	6
WW	3W	5%	15Ω-10KΩ	E12	7	7	6
WW	7W	5%	15Ω-10KΩ	E12	9	9	8

Codes: C = carbon film, high stability, low noise.
MO = metal oxide, Electrofil TR5, ultra low noise.
WW = wire wound, Plessey.

Values:
E12 denotes series: 10, 12, 15, 18, 22, 27, 33, 39, 47, 56, 68, 82 and their decades.
E24 denotes series: as E12 plus 11, 13, 16, 20, 24, 30, 36, 43, 51, 62, 75, 91 and their decades.

Prices are in pence each for quantities of the same ohmic value and power rating. NOT mixed values. (Ignore fractions of one penny on total value of resistor order.)

TRANSISTORS BY SIEMENS AND NEWMARKET

2N3055 npn silicon power	60p
AC153K pnp germanium low power	32p
AC176K npn germanium low power	32p
AD161 npn germanium medium power	42p
AD162 pnp germanium medium power	40p
AF139 pnp germanium UHF	49p
BC107-13p; BC108-12p; BC109-13p	} npn
BC167-11p; BC168-10p; BC169-11p	
BC177-21p; BC178-19p; BC179-22p	
BC257-12p; BC258-11p; BC259-13p	
Standard groupings available.	
BD135 npn medium power	37p
BD136 pnp medium power	38p

DIODES

OA90, OA91, OA95 each 6p
OA200-9p; OA202-10p
Other semi-conductors
AC128-17p AF117-32p
BFY51-19p

Very many other types listed, described and illustrated in catalogue.

DIN CONNECTORS by Hirshmann 4A rating




2 way loudspeaker Socket	10p	Plug	12p
3 way audio Socket	10p	Plug	12p
5 way audio 180° Socket	12p	Plug	15p
5 way audio 240° Socket	12p	Plug	15p
6 way audio Socket	13p	Plug	15p

Lockable types, phono connectors, etc.


COVERS & HEATSINKS

T03 Transistor cover, clip-on 7p
HEATSINK
Type 6W1
Extruded aluminium
1°C/W,
undrilled 60p
drilled 78p



TOGGLE SWITCHES

1011C SPST toggle 19p; 409 DPDT toggle 28p. (These are chrome plated, 2.5A rating). 7201 Sub-miniature DPDT 250V a.c./2A 48p



TTL ICs

Part Number	Price
7400	20p
7401	20p
7402	20p
7403	20p
7404	25p
7405	20p
7408	25p
7409	25p
7410	20p
7413	35p
7420	20p
7430	20p
7440	20p
74141 (16)	99p
7442 (16)	87p
7443 (16)	£1.00
7444 (16)	£1.00
7447	£1.36
7450	20p
7451	20p
7453	20p
7454	20p
7466	20p
7470	33p
7472	30p
7473	36p
7474	36p
7475 (16)	60p
7476 (16)	45p
7480	68p
7482	87p
7483 (16)	£1.32
7485	£1.70
7486	35p
7490	60p
7491AN	£1.00
7492	70p
7493	65p
7495	87p
7496 (16)	£1.00
74100 (24)	£1.64
74104	65p
74107	52p
74121	48p
74190 (16)	£1.80
74191 (16)	£1.80
74192 (16)	£1.74
74193 (16)	£1.74

POTENTIOMETERS carbon type

long spindles. Double wipers for low noise.

SINGLE GANG P20 linear 100Ω to 2.2MΩ, 12p, JP20 Log, 4-7KΩ, to 2.2MΩ 12p.

DUAL GANG linear 4.7KΩ to 2.2MΩ, 42p; Dual gang log, 4.7KΩ to 2.2MΩ, 42p; Log/antilog, 10K, 22K, 47K, 1MΩ only 42p; Dual antilog, 10K only, 42p. Any of above types with 2A D.P. mains switch, 12p extra. Only decades of 10, 22 & 47 available in ranges quoted.

DUAL CONCENTRIC DP20 in any combination of P20 values, 60p; with switch, 72p.

SLIDER POTS. In values from 4K7Ω to 1MΩ, linear or log, 26p. Escutcheon, white, grey, black, 10p. Knobs, flat, grip type, in 7 colours, 5p each.

SKELETON PRE-SETS. Small high quality, type PR linear only: 100Ω, 220Ω, 470Ω, 1K, 2K2, 4K7, 10K, 22K, 47K, 100K, 470K, 1M, 2M2, 5M, 10MΩ. Vertical or horizontal mounting, 5p each.

NUTS, SCREWS, ETC. In lots of 100.

Nuts 2BA-41p; 4BA-28p; 6BA-26p.
Screws 1"-2BA-67p; 4BA-35p; 6BA-26p.
0.5"-2BA-50p; 4BA-23p; 6BA-19p.
Screws roundedhead, cheese headed or countersunk. Other sizes available. Also tags, washers, spacers, etc.



ELECTROLYTICS

µF	Prices in pence									
	3V	6.3V	10V	16V	25V	40V	63V	100V		
0.47							10	7		
1.0						10		7		
2.2					10		7	8		
4.7					10		7	8	7	
10					7	8	7	8	7	8
22				7	8	7	7	9	9	9
47	7		8	7	7	7	9	12		
100	8	7	7	7	7	9	11	19		
220	7	8	8	8	9	10	17	27		
470	8	9	9	10	12	17	24	43		
1000	10	12	12	17	20	24	40			
2200	14	17	22	25	36	40				
4700	25	28	37	41	54					
10,000	40	43								


Smallest size 3.7mm x 12mm. Largest size 25.5mm x 41mm. Full ranges of many other types of capacitors stocked.

ROTARY SWITCHES

Radiospares Miniature Makerswitch (in assembly kit form). Shaft 48p.
Wafers, MBB-2P5W, 1P 11W; BBM1P12W, 2P6W, 3P4W, 4P3W, 6P2W, each 32p.

Wavechange switches
1P12W, 2P6W, 3P4W, 4P3W, each 24p.

3 New Babani Books
BP.13 Electronic Novelties for the Motorist; BP.15 Constructor's Manual of Electronic Circuits for the Home; 200 Handbook of Electronic Musical Novelties; EACH 50p (no V.A.T.).



KNOBS

(for 0.25 shafts)




K.30/3
Solid aluminium
17mm.

F.14 skirt dia. 20mm. pack of 2	32p
F.13 skirt dia. 26mm. pack of 2	38p
F.12 skirt dia. 33mm. pack of 2	40p
F.19 engraved 20mm.—two	32p
F.18 engraved. 26mm.—two	38p
F.17 engraved. 33mm.—two	40p

Very many other types in stock—see Catalogue.



KB.4
Ribbed
Skirt dia. 20mm.
4 in pack. 40p



Minitron DIGITAL INDICATOR

TYPE 3015F Seven segment indicator compatible with standard logic modules and power supplies. Figs. 0-9 from well illuminated filament segments to give character of 9mm height plus decimal point. Power requirement 8mA from 5V D.C. per segment. A limited number of alphabetical symbols also available. In 16 lead DIL case. Suitable BCD decoder driver type FLL121T

DIL Socket: 16 lead 30p. No. 3015G showing + or - and fig. 1 and decimal point £2.00. nett

ZENER DIODES

Full range E24 values: 400mW: 2.7V to 36V, 14p each; 1W: 6.8V to 82V, 21p each; 1.5W: 4.7V to 75V, 48p each. Clip to increase 1.5W rating to 3 watts (type 266F) 4p.

SIEMENS THYRISTORS

0-8A 400V, 56p; 600V 70p. 3A 400V, 60p; 600V, 88p.

DE-SOLDER BRAID 6ft. nett 50p

S-DEC

Unsurpassed for "breadboard work" can be used indefinitely without deterioration. Components just push into plug holes and connect automatically. Slot for control panel. 70 holes. £1-80.

T-DEC

For more advanced work with 208 contacts in 38 rows. Will take one 16 lead carrier. £3-30. (Carriers supplied separately.)

BAXANDALL SPEAKER

As described originally in "Wireless World" and still one of the most brilliant designs in high quality low priced speakers. You save by assembling it yourself. 10 watts/15Ω. Complete kit £14.90+60p part carr. Equaliser components £2.00. Speaker unit £2.45.

No. 6 CATALOGUE SUPPLEMENT

of latest price adjustments and new items. S.A.E. for your copy.

MAINS TRANSFORMERS

MT3 30V/2A plus 4 taps £2-85
MT103 50V/1A+4 taps £2-55
MT104 50V/2A+4 taps £3-50
MT127 60V/2A+4 taps £3-80
13T05 13V/1A, CT £1-25
28T05 12+12; 2-0-2V/1A £1-60

U.S.A. CUSTOMERS

are invited to contact Electrovalue America, P.O. Box 27, Swarthmore, PA.

DISCOUNTS

Available on all items except those shown with NETT PRICES. 10% on orders from £5 to £15. 15% on orders £15 and over.

TERMS OF BUSINESS

All items are offered for sale in accordance with our standard terms of business, a copy of which is available on request. Prices subject to alteration without notice. Enquiries from quantity users invited.

PACKING & POSTAGE
FREE in U.K. For mail orders for £2 list value and under, there is an additional handling charge of 10p.

V.A.T.

Please add 10% to nett value of order to meet tax requirements.
Not applicable to overseas orders.

ELECTROVALUE LTD

(DEPT. WW.9), 28 ST. JUDES RD, ENGLEFIELD GREEN, EGHAM, SURREY, TW20 0NB
Hours: 9-5.30, 1.0 p.m. Saturdays.

Reg. offices at above address

Phone: Egham 3603 Telex 264475
Business Reg. No. 1047769

R.S.T. VALVE MAIL ORDER CO. Blackwood Hall, 16A Wellfield Road, London, SW16 2BS Tel: 01-677 2424 R.S.T.

VALVES

AZ31 0-55	BY802 0-40	EF98 0-75	EZ80 0-28	OA2 0-40	PD500 1-30	PY82 0-35	UCH42 0-70	1T4 0-30	6BR7 0-80	6U5G 1.00	12BH7 0-50	80 0-60
AZ41 0-60	ECH35 1.00	EF183 0-30	EZ81 0-29	OB2 0-40	PEN45D 1	PY83 0-35	UCH81 0-40	354 0-40	6V6GT 0-45	6V6GT 0-45	30C13 1.00	807 0-50
CB13L1 1.00	ECH42 0-35	EF214 0-35	EZ90 0-29	OZ4 0-45	75Z 0-75	PY500 1.00	UCL89 0-35	3Y4 0-48	6BW7 0-90	6X4 0-40	30C11 1.10	6080 1-75
CL33 1-50	ECH84 0-45	EL33 1-75	GY501 0-80	PC86 0-60	PFL2000-65	PY800 0-47	UCL89 0-35	5R4GY 0-75	6C4 0-35	6X5GT 0-45	30C18 0-90	6146 1-60
CY31 0-50	ECL80 0-45	EL34 0-50	GZ30 0-45	PC88 0-60	PL36 0-55	PY801 0-50	UCL89 0-35	5U4G 0-40	6C6 0-60	6C6 0-60	30F5 1-00	TUBES
DAP91 0-30	ECL82 0-35	EL41 0-75	GZ32 0-40	PC900 0-48	PL38 0-55	SP41 3-00	UF41 0-65	5V4G 0-50	6C86 0-60	7B7 0-70	30FL1 0-80	2AP1 4-00
DAP96 0-50	ECL84 0-45	EL42 0-65	GZ34 0-60	PC984 0-40	PL81 0-50	SP61 0-50	UF89 0-40	5Y3GT 0-45	6E5 1-00	7C5 1-13	30FL14 0-10	3BP1 3-50
DDC50 1-35	ECL86 0-40	EL44 0-65	H63 0-90	PC189 0-60	PL82 0-45	T41 1-00	UL41 0-65	5Z4G 0-45	6F23 0-75	7G6 0-75	30FL15 0-75	3DPLA 3-50
DF91 0-30	EL84 0-25	EL84 0-25	HL41DD	PCF80 0-30	PL83 0-45	U25 0-35	UL44 0-65	6J0L2 0-90	6JGT 0-40	7H7 0-70	30FL17 0-85	3F10 1-00
DF96 0-50	EL91 0-40	EL91 0-40	70	PCF86 0-80	PL84 0-40	U26 0-85	UY41 0-48	6AL5 0-22	6JGT 0-45	787 2-25	30P12 1-00	3FP7 1-50
DK91 0-45	EL95 0-35	EL95 0-35	HN309 1-50	PCF80 0-30	PL85 0-40	U191 0-75	UY85 0-40	6A05 0-42	6K6G 0-75	7Y4 0-75	30P19 0-95	3GP1 3-50
DK92 0-70	EL95 0-35	EL95 0-35	KT61 1-75	PCF80 0-30	PL86 0-45	U404 1-25	VP4B 1-25	6A87 0-85	6K7GT 0-35	12AC6 0-60	30P11 0-95	5BP1 4-00
DK96 0-60	EL95 0-35	EL95 0-35	KT66 2-35	PCF80 0-30	PL86 0-45	U401 1-78	VR75/30	6A76 0-38	6K8GT 0-50	12AD6 0-60	30PL13 1-10	5CP1 5-00
DL92 0-40	EL95 0-35	EL95 0-35	KT81 7(25)	PCF80 0-30	PL86 0-45	U401 1-78	VR75/30	6A76 0-38	6K8GT 0-50	12AE6 0-60	30PL14 1-25	5FP7 3-00
DL94 0-48	EL95 0-35	EL95 0-35	KT81 7(25)	PCF80 0-30	PL86 0-45	U401 1-78	VR75/30	6A76 0-38	6K8GT 0-50	12AT6 0-40	35L07 0-75	5G1 10-00
DL96 0-55	EL95 0-35	EL95 0-35	KT81 7(25)	PCF80 0-30	PL86 0-45	U401 1-78	VR75/30	6A76 0-38	6K8GT 0-50	12AT7 0-40	CV429 22-00	5G1 10-00
DM70 0-60	EL95 0-35	EL95 0-35	KT81 7(25)	PCF80 0-30	PL86 0-45	U401 1-78	VR75/30	6A76 0-38	6K8GT 0-50	12AU6 0-45	5E23 0-75	CV960 8-00
DY96 0-35	EL95 0-35	EL95 0-35	KT81 7(25)	PCF80 0-30	PL86 0-45	U401 1-78	VR75/30	6A76 0-38	6K8GT 0-50	12AU7 0-33	5E23 0-75	CV960 8-00
DY87 0-38	EL95 0-35	EL95 0-35	KT81 7(25)	PCF80 0-30	PL86 0-45	U401 1-78	VR75/30	6A76 0-38	6K8GT 0-50	12B6 0-45	5E23 0-75	DGT-16 10-00
	EL95 0-35	EL95 0-35	KT81 7(25)	PCF80 0-30	PL86 0-45	U401 1-78	VR75/30	6A76 0-38	6K8GT 0-50	12BE6 0-50	5E23 0-75	VCR1388 0-00

TRANSISTORS

1N21 0-17	2N3709 0-10	AF116 0-25	BF195 0-15	CR83/40	GJ7M 0-37	OA95 0-07	OC26 0-25	OC71 0-12	OC84 0-25	ORP60 0-40
1N23 0-20	2N3710 0-10	AF117 0-25	BF196 0-15	CR10B 3-30	R8100A0-20	OA200 0-07	OC28 0-60	OC72 0-20	OC123 0-65	ORP61 0-42
1N4001 0-07	2N3712 0-10	AF139 0-30	BF197 0-15	CR10C 1-10	MAT10 0-30	OA202 0-10	OC30 0-30	OC73 0-20	OC140 0-35	8X642 0-80
1N4002 0-08	2N3713 0-10	AF142 0-15	BF198 0-15	CR10D 0-10	MAT12 1-25	OA210 0-20	OC35 0-50	OC74 0-20	OC141 0-60	8X643 0-70
1N4003 0-10	2N3714 0-10	AF148 0-15	BF199 0-15	CR10E 0-10	MAT12 1-25	OA211 0-20	OC36 0-60	OC75 0-25	OC169 0-20	ZS21 0-15
1N4004 0-10	2N3715 0-10	AF152 0-15	BF200 0-15	CR10F 0-10	MAT12 1-25	OA212 0-20	OC37 0-60	OC76 0-25	OC170 0-25	ZS22 0-45
1N4005 0-10	2N3716 0-10	AF156 0-15	BF201 0-15	CR10G 0-10	MAT12 1-25	OA213 0-20	OC38 0-60	OC77 0-25	OC171 0-30	ZS21 0-15
1N4006 0-10	2N3717 0-10	AF160 0-15	BF202 0-15	CR10H 0-10	MAT12 1-25	OA214 0-20	OC39 0-60	OC78 0-25	OC172 0-30	ZS21 0-15
1N4007 0-10	2N3718 0-10	AF164 0-15	BF203 0-15	CR10I 0-10	MAT12 1-25	OA215 0-20	OC40 0-60	OC79 0-25	OC173 0-30	ZS21 0-15
1N4008 0-10	2N3719 0-10	AF168 0-15	BF204 0-15	CR10J 0-10	MAT12 1-25	OA216 0-20	OC41 0-60	OC80 0-25	OC174 0-30	ZS21 0-15
1N4009 0-10	2N3720 0-10	AF172 0-15	BF205 0-15	CR10K 0-10	MAT12 1-25	OA217 0-20	OC42 0-60	OC81 0-25	OC175 0-30	ZS21 0-15
1N4010 0-10	2N3721 0-10	AF176 0-15	BF206 0-15	CR10L 0-10	MAT12 1-25	OA218 0-20	OC43 0-60	OC82 0-25	OC176 0-30	ZS21 0-15
1N4011 0-10	2N3722 0-10	AF180 0-15	BF207 0-15	CR10M 0-10	MAT12 1-25	OA219 0-20	OC44 0-60	OC83 0-25	OC177 0-30	ZS21 0-15
1N4012 0-10	2N3723 0-10	AF184 0-15	BF208 0-15	CR10N 0-10	MAT12 1-25	OA220 0-20	OC45 0-60	OC84 0-25	OC178 0-30	ZS21 0-15
1N4013 0-10	2N3724 0-10	AF188 0-15	BF209 0-15	CR10O 0-10	MAT12 1-25	OA221 0-20	OC46 0-60	OC85 0-25	OC179 0-30	ZS21 0-15
1N4014 0-10	2N3725 0-10	AF192 0-15	BF210 0-15	CR10P 0-10	MAT12 1-25	OA222 0-20	OC47 0-60	OC86 0-25	OC180 0-30	ZS21 0-15
1N4015 0-10	2N3726 0-10	AF196 0-15	BF211 0-15	CR10Q 0-10	MAT12 1-25	OA223 0-20	OC48 0-60	OC87 0-25	OC181 0-30	ZS21 0-15
1N4016 0-10	2N3727 0-10	AF200 0-15	BF212 0-15	CR10R 0-10	MAT12 1-25	OA224 0-20	OC49 0-60	OC88 0-25	OC182 0-30	ZS21 0-15
1N4017 0-10	2N3728 0-10	AF204 0-15	BF213 0-15	CR10S 0-10	MAT12 1-25	OA225 0-20	OC50 0-60	OC89 0-25	OC183 0-30	ZS21 0-15
1N4018 0-10	2N3729 0-10	AF208 0-15	BF214 0-15	CR10T 0-10	MAT12 1-25	OA226 0-20	OC51 0-60	OC90 0-25	OC184 0-30	ZS21 0-15
1N4019 0-10	2N3730 0-10	AF212 0-15	BF215 0-15	CR10U 0-10	MAT12 1-25	OA227 0-20	OC52 0-60	OC91 0-25	OC185 0-30	ZS21 0-15
1N4020 0-10	2N3731 0-10	AF216 0-15	BF216 0-15	CR10V 0-10	MAT12 1-25	OA228 0-20	OC53 0-60	OC92 0-25	OC186 0-30	ZS21 0-15
1N4021 0-10	2N3732 0-10	AF220 0-15	BF217 0-15	CR10W 0-10	MAT12 1-25	OA229 0-20	OC54 0-60	OC93 0-25	OC187 0-30	ZS21 0-15
1N4022 0-10	2N3733 0-10	AF224 0-15	BF218 0-15	CR10X 0-10	MAT12 1-25	OA230 0-20	OC55 0-60	OC94 0-25	OC188 0-30	ZS21 0-15
1N4023 0-10	2N3734 0-10	AF228 0-15	BF219 0-15	CR10Y 0-10	MAT12 1-25	OA231 0-20	OC56 0-60	OC95 0-25	OC189 0-30	ZS21 0-15
1N4024 0-10	2N3735 0-10	AF232 0-15	BF220 0-15	CR10Z 0-10	MAT12 1-25	OA232 0-20	OC57 0-60	OC96 0-25	OC190 0-30	ZS21 0-15
1N4025 0-10	2N3736 0-10	AF236 0-15	BF221 0-15	CR10A 0-10	MAT12 1-25	OA233 0-20	OC58 0-60	OC97 0-25	OC191 0-30	ZS21 0-15
1N4026 0-10	2N3737 0-10	AF240 0-15	BF222 0-15	CR10B 0-10	MAT12 1-25	OA234 0-20	OC59 0-60	OC98 0-25	OC192 0-30	ZS21 0-15
1N4027 0-10	2N3738 0-10	AF244 0-15	BF223 0-15	CR10C 0-10	MAT12 1-25	OA235 0-20	OC60 0-60	OC99 0-25	OC193 0-30	ZS21 0-15
1N4028 0-10	2N3739 0-10	AF248 0-15	BF224 0-15	CR10D 0-10	MAT12 1-25	OA236 0-20	OC61 0-60	OC100 0-30	OC194 0-30	ZS21 0-15
1N4029 0-10	2N3740 0-10	AF252 0-15	BF225 0-15	CR10E 0-10	MAT12 1-25	OA237 0-20	OC62 0-60	OC101 0-30	OC195 0-30	ZS21 0-15
1N4030 0-10	2N3741 0-10	AF256 0-15	BF226 0-15	CR10F 0-10	MAT12 1-25	OA238 0-20	OC63 0-60	OC102 0-30	OC196 0-30	ZS21 0-15
1N4031 0-10	2N3742 0-10	AF260 0-15	BF227 0-15	CR10G 0-10	MAT12 1-25	OA239 0-20	OC64 0-60	OC103 0-30	OC197 0-30	ZS21 0-15
1N4032 0-10	2N3743 0-10	AF264 0-15	BF228 0-15	CR10H 0-10	MAT12 1-25	OA240 0-20	OC65 0-60	OC104 0-30	OC198 0-30	ZS21 0-15
1N4033 0-10	2N3744 0-10	AF268 0-15	BF229 0-15	CR10I 0-10	MAT12 1-25	OA241 0-20	OC66 0-60	OC105 0-30	OC199 0-30	ZS21 0-15
1N4034 0-10	2N3745 0-10	AF272 0-15	BF230 0-15	CR10J 0-10	MAT12 1-25	OA242 0-20	OC67 0-60	OC106 0-30	OC200 0-30	ZS21 0-15
1N4035 0-10	2N3746 0-10	AF276 0-15	BF231 0-15	CR10K 0-10	MAT12 1-25	OA243 0-20	OC68 0-60	OC107 0-30	OC201 0-30	ZS21 0-15
1N4036 0-10	2N3747 0-10	AF280 0-15	BF232 0-15	CR10L 0-10	MAT12 1-25	OA244 0-20	OC69 0-60	OC108 0-30	OC202 0-30	ZS21 0-15
1N4037 0-10	2N3748 0-10	AF284 0-15	BF233 0-15	CR10M 0-10	MAT12 1-25	OA245 0-20	OC70 0-60	OC109 0-30	OC203 0-30	ZS21 0-15
1N4038 0-10	2N3749 0-10	AF288 0-15	BF234 0-15	CR10N 0-10	MAT12 1-25	OA246 0-20	OC71 0-60	OC110 0-30	OC204 0-30	ZS21 0-15
1N4039 0-10	2N3750 0-10	AF292 0-15	BF235 0-15	CR10O 0-10	MAT12 1-25	OA247 0-20	OC72 0-60	OC111 0-30	OC205 0-30	ZS21 0-15
1N4040 0-10	2N3751 0-10	AF296 0-15	BF236 0-15	CR10P 0-10	MAT12 1-25	OA248 0-20	OC73 0-60	OC112 0-30	OC206 0-30	ZS21 0-15
1N4041 0-10	2N3752 0-10	AF300 0-15	BF237 0-15	CR10Q 0-10	MAT12 1-25	OA249 0-20	OC74 0-60	OC113 0-30	OC207 0-30	ZS21 0-15
1N4042 0-10	2N3753 0-10	AF304 0-15	BF238 0-15	CR10R 0-10	MAT12 1-25	OA250 0-20	OC75 0-60	OC114 0-30	OC208 0-30	ZS21 0-15
1N4043 0-10	2N3754 0-10	AF308 0-15	BF239 0-15	CR10S 0-10	MAT12 1-25	OA251 0-20	OC76 0-60	OC115 0-30	OC209 0-30	ZS21 0-15
1N4044 0-10	2N3755 0-10	AF312 0-15	BF240 0-15	CR10T 0-10	MAT12 1-25	OA252 0-20	OC77 0-60	OC116 0-30	OC210 0-30	ZS21 0-15
1N4045 0-10	2N3756 0-10	AF316 0-15	BF241 0-15	CR10U 0-10	MAT12 1-25	OA253 0-20	OC78 0-60	OC117 0-30	OC211 0-30	ZS21 0-15
1N4046 0-10	2N3757 0-10	AF320 0-15	BF242 0-15	CR10V 0-10	MAT12 1-25	OA254 0-20	OC79 0-60	OC118 0-30	OC212 0-30	ZS21 0-15
1N4047 0-10	2N3758 0-10	AF324 0-15	BF243 0-15	CR10W 0-10	MAT12 1-25	OA255 0-20	OC80 0-60	OC119 0-30	OC213 0-30	ZS21 0-15
1N4048 0-10	2N3759 0-10	AF328 0-15	BF244 0-15	CR10X 0-10	MAT12 1-25	OA256 0-20	OC81 0-60	OC120 0-30	OC214 0-30	ZS21 0-15
1N4049 0-10	2N3760 0-10	AF332 0-15	BF245 0-15	CR10Y 0-10	MAT12 1-25	OA257 0-20	OC82 0-60	OC121 0-30	OC215 0-30	ZS21 0-15
1N4050 0-10	2N3761 0-10	AF336 0-15	BF246 0-15	CR10Z 0-10	MAT12 1-25	OA258 0-20	OC83 0-60	OC122 0-30	OC216 0-30	ZS21 0-15
1N4051 0-10	2N3762 0-10	AF340 0-15	BF247 0-15	CR10A 0-10	MAT12 1-25	OA259 0-20	OC84 0-60	OC123 0-30	OC217 0-30	ZS21 0-15
1N4052 0-10	2N3763 0-10	AF344 0-15	BF248 0-15							

BRAND NEW SEMICONDUCTORS & COMPONENTS GUARANTEED

WE SUPPLY NEARLY ALL THE COMPONENTS FOR PROJECTS ADVERTISED IN THIS MAGAZINE

TRANSISTORS

2G301	0.15	2N3403	0.19	40316	0.50	BC121	0.23	BDY18	1.75	BSX61	0.42
2G302	0.15	2N3404	0.24	40318	0.92	BC125	0.15	BDY19	1.97	BSX76	0.15
2G303	0.25	2N3405	0.27	40360	0.46	BC126	0.20	BDY20	0.05	BSX77	0.20
2G306	0.30	2N3414	0.10	40361	0.43	BC132	0.50	BDY38	1.65	BSX78	0.25
2G309	0.30	2N3415	0.10	40389	0.46	BC134	0.11	BDY60	0.90	BSW70	0.28
2G345B	0.25	2N3416	0.15	40394	0.56	BC135	0.11	BDY61	1.25	BSY24	0.20
2G371	0.15	2N3417	0.21	40395	0.65	BC136	0.15	BDY62	1.00	BSY25	0.15
2G374	0.15	2N3570	1.25	40406	0.44	BC137	0.15	BF115	0.23	BSY26	0.20
2N174	1.40	2N3571	1.12	40407	0.33	BC140	0.34	BF117	0.43	BSY27	0.15
2N404	0.75	2N3572	0.97	40408	0.50	BC141	0.39	BF121	0.25	BSY28	0.15
2N456	0.75	2N3702	0.11	40409	0.52	BC142	0.24	BF122	0.27	BSY39	0.20
2N456A	0.75	2N3703	0.10	40410	0.53	BC143	0.21	BF125	0.25	BSY51	0.25
2N457A	0.80	2N3704	0.14	40411	2.00	BC144	0.24	BF152	0.20	BSY52	0.25
2N491	3.25	2N3705	0.10	40414	3.55	BC145	0.21	BF153	0.29	BSY53	0.25
2N696	0.15	2N3706	0.10	40414	3.55	BC147	0.12	BF154	0.16	BSY54	0.30
2N697	0.15	2N3707	0.09	40467	0.69	BC148	0.12	BF158	0.23	BSY56	0.79
2N698	0.25	2N3708	0.10	40468A	0.44	BC149	0.12	BF159	0.27	BSY65	0.15
2N699	0.29	2N3709	0.09	40600	0.69	BC153	0.18	BF160	0.23	BSY78	0.40
2N706	0.10	2N3710	0.12	40601	0.70	BC154	0.18	BF161	0.42	BSY79	0.40
2N706A	0.12	2N3711	0.09	40602	0.46	BC157	0.14	BF163	0.20	BSY790	0.45
2N708	0.13	2N3712	0.09	40603	0.58	BC158	0.14	BF166	0.35	BSY95A	0.39
2N709	0.40	2N3713	1.08	40604	0.56	BC159	0.14	BF167	0.21	BU104	1.42
2N711	0.30	2N3714	1.15	40636	1.10	BC160	0.37	BF173	0.24	BU105	2.25
2N718	0.21	2N3715	1.23	40673	0.70	BC167B	0.11	BF177	0.29	CI11	0.53
2N718A	0.30	2N3716	1.30	AC107	0.35	BC168B	0.13	BF178	0.35	D40N3	0.62
2N720	0.50	2N3773	3.00	AC115	0.16	BC168C	0.13	BF179	0.43	GET111	0.45
2N721	0.55	2N3779	3.15	AC117	0.20	BC169B	0.13	BF180	0.35	GET113	0.20
2N914	0.15	2N3790	2.20	AC117	0.20	BC169C	0.11	BF181	0.32	GET114	0.20
2N916	0.17	2N3791	2.06	AC121	0.13	BC170	0.11	BF182	0.40	GET115	0.50
2N918	0.30	2N3792	2.20	AC126	0.25	BC171	0.13	BF183	0.40	GET119	0.35
2N929	0.14	2N3794	0.10	AC127	0.20	BC172	0.11	BF184	0.17	GET120	0.15
2N930	0.14	2N3819	0.32	AC128	0.20	BC182	0.10	BF185	0.17	GET535	0.20
2N1090	0.23	2N3820	0.47	AC141K	0.30	BC182L	0.12	BF194	0.14	GET536	0.20
2N1091	0.24	2N3823	0.62	AC142K	0.25	BC183	0.09	BF195	0.17	GET538	0.20
2N1131	0.20	2N3824	0.75	AC151V	0.14	BC183L	0.09	BF196	0.15	GET873	0.12
2N1132	0.20	2N3826	0.23	AC152V	0.17	BC184	0.11	BF197	0.15	GET880	0.30
2N1302	0.16	2N3854	0.16	AC153	0.22	BC184L	0.11	BF198	0.15	GET883	0.20
2N1303	0.16	2N3854A	0.16	AC153K	0.25	BC186	0.25	BF199	0.18	GET887	0.20
2N1304	0.20	2N3855	0.16	AC154	0.20	BC187	0.25	BF200	0.40	GET890	0.22
2N1305	0.20	2N3855A	0.16	AC176	0.18	BC207	0.12	BF224J	0.14	GET895	0.25
2N1306	0.22	2N3856	0.16	AC176K	0.20	BC208	0.11	BF225J	0.19	TIP29A	0.49
2N1307	0.22	2N3856A	0.16	AC187K	0.20	BC212K	0.10	BF237	0.22	TIP30A	0.58
2N1308	0.25	2N3858	0.16	AC188K	0.26	BC212L	0.18	BF238	0.22	TIP31A	0.62
2N1309	0.37	2N3858A	0.16	AC188K	0.26	BC214L	0.21	BF244	0.16	TIP32A	0.74
2N1483	0.90	2N3859	0.16	AC188K	0.26	BC237	0.09	BF245	0.33	TIP33A	1.01
2N1507	0.24	2N3859A	0.16	AC188K	0.26	BC238	0.09	BF246	0.43	TIP34A	1.51
2N1613	0.20	2N3860	0.16	AC188K	0.26	BC239	0.09	BF247	0.49	TIP35A	2.90
2N1631	0.35	2N3866	0.70	AC188K	0.26	BC251	0.20	BF254	0.18	TIP36A	3.70
2N1637	0.36	2N3877	0.25	AC188K	0.26	BC252	0.18	BF255	0.17	TIP41A	0.79
2N1638	0.32	2N3877A	0.26	AC188K	0.26	BC253	0.23	BF257	0.41	TIP42A	0.90
2N1701	1.10	2N3900	0.20	AC188K	0.26	BC257	0.09	BF258	0.46	TIP2955	0.98
2N1702	2.15	2N3900A	0.21	AC188K	0.26	BC258	0.09	BF259	0.45	TIP3055	0.60
2N1711	0.22	2N3901	0.32	AC188K	0.26	BC259	0.13	BF270	0.25	ME0401	0.18
2N1893	0.34	2N3903	0.22	AD136V	0.96	BC261	0.20	BF272	0.53	ME0402	0.20
2N2102	0.30	2N3904	0.17	AD142	0.54	BC262	0.18	BF273	0.25	ME0404	0.13
2N2147	0.70	2N3905	0.21	AD143	0.45	BC300	0.42	BF457	0.53	ME0411	0.17
2N2148	0.94	2N3906	0.20	AD149V	0.66	BC301	0.34	BF458	0.85	ME0412	0.18
2N2192	0.40	2N4036	0.46	AD150	0.63	BC302	0.27	BF521A	2.30	ME0413	0.14
2N2192A	0.40	2N4037	0.40	AD161	0.45	BC303	0.54	BF528	2.00	ME1120	0.25
2N2193	0.40	2N4058	0.16	AD162	0.45	BC307	0.10	BF561	0.27	ME4001	0.09
2N2193A	0.61	2N4059	0.09	AD162	1.05	BC307A	0.10	BF598	0.28	ME4002	0.11
2N2194	0.27	2N4060	0.11	AF109R	0.40	BC308	0.09	BFW11	0.31	ME4003	0.14
2N2194A	0.30	2N4061	0.11	AF114	0.25	BC308B	0.09	BFW15	0.65	ME4101	0.10
2N2195	0.37	2N4062	0.11	AF115	0.25	BC309	0.10	BFX13	0.23	ME4103	0.11
2N2195A	0.18	2N4302	0.25	AF116	0.24	BC309A	0.10	BFX29	0.20	ME4104	0.10
2N2218A	0.30	2N4303	0.47	AF116	0.25	BC309B	0.10	BFX37	0.25	ME6102	0.16
2N2219	0.37	2N4916	0.20	AF117	0.20	BC327	0.24	BFX44	0.33	ME8002	0.17
2N2219A	0.51	2N4917	0.17	AF118	0.50	BC328	0.22	BFX63	2.48	ME8003	0.16
2N2220	0.20	2N4918	0.50	AF121	0.22	BC337	0.19	BFX68	0.68	MJ400	0.78
2N2221	0.20	2N4919	0.63	AF124	0.24	BC338	0.19	BFX84	0.24	MJ420	0.86
2N2221A	0.33	2N4920	0.71	AF125	0.20	BC339	0.43	BFX85	0.29	MJ421	0.88
2N2222	0.31	2N4921	0.50	AF126	0.19	BCY31	0.40	BFX86	0.24	MJ430	0.75
2N2222A	0.41	2N4922	0.55	AF127	0.20	BCY32	1.15	BFX87	0.28	MJ440	0.71
2N2368	0.11	2N4923	0.60	AF139	0.38	BCY33	0.34	BFX88	0.25	MJ480	0.75
2N2369	0.15	2N5172	0.12	AF170	0.25	BCY34	0.35	BFX89	0.45	MJ481	0.85
2N2369A	0.17	2N5174	0.22	AF172	0.25	BCY38	0.53	BFY10	0.35	MJ490	0.94
2N2646	0.50	2N5175	0.26	AF178	0.55	BCY39	1.05	BFY11	0.45	MJ491	1.10
2N2647	1.20	2N5176	0.32	AF179	0.65	BCY40	0.50	BFY17	0.90	MJ802	14.2
2N2711	0.12	2N5190	0.92	AF180	0.50	BCY42	0.15	BFY18	0.35	MJ901	2.65
2N2712	0.12	2N5191	0.96	AF186	0.40	BCY43	0.15	BFY19	0.35	MJ1001	2.34
2N2713	0.17	2N5192	1.24	AF200	0.35	BCY58	0.21	BFY20	0.50	MJ1800	1.88
2N2714	0.17	2N5193	1.01	AF211	0.55	BCY59	0.22	BFY29	0.40	MJ2500	2.92
2N2904	0.28	2N5194	1.10	AF239	0.41	BCY70	0.17	BFY37	0.20	MJ2501	3.25
2N2904A	0.25	2N5195	1.46	AF240	0.72	BCY71	0.22	BFY41	0.43	MJ2955	1.00
2N2905	0.33	2N5245	0.35	AF279	0.54	BCY72	0.13	BFY43	0.65	MJ3000	2.47
2N2905A	0.35	2N5457	0.35	AF280	0.54	BCY77	3.47	BFY50	0.22	MJ3001	2.79
2N2906	0.24	2N5458	0.33	AFY42	0.74	BCY88	2.40	BFY51	0.15	MJ3701	0.9
2N2906A	0.30	2N5459	0.33	AL102	0.75	BCY89	0.97	BFY52	0.20	MJ4502	4.44
2N2907	0.32	3N128	0.73	AL103	0.70	BCZ10	0.35	BFY53	0.15	MJ4502	4.44
2N2907A	0.33	3N138	1.65	ASY26	0.30	BCZ11	0.50	BFY56	0.34	MJ4502	4.44
2N2923	0.12	3N139	1.42	ASY28	0.36	BD115	0.75	BFY64	0.41	MJ4502	4.44
2N2924	0.12	3N140	0.92	ASY28	0.28	BD116	0.50	BFY75	0.40	MJ4502	4.44
2N2925	0.15	3N141	0.81	ASY29	0.36	BD121	0.75	BFY76	0.22	MJ4502	4.44
2N2926	0.15	3N142	0.58	ASY50	0.20	BD123	0.82	BFY77	0.24	MJ4502	4.44
Green	0.12	3N143	0.75	ASY55	0.35	BD124	0.67	BFY78	0.36	MJ4502	4.44
Yellow	0.10	3N152	0.92	AU103	1.25	BD130	0.57	BFY90	0.60	MJ4502	4.44
Orange	0.10	3N153	0.81	BC107	0.10	BD131	0.40	BRY39	0.30	MJ4502	4.44
2N3053	0.31	3N154	0.84	BC108	0.10	BD132	0.50	BSX19	0.13	MJE2901	1.56
2N3054	0.60	3N159	1.17	BC109	0.10	BD135	0.43	BSX20	0.14	MJE2955	1.65
2N3055	0.50	3N187	1.55	BC113	0.13	BD136	0.49	BSX21	0.20		
2N3390	0.20	3N200	2.49	BC114	0.12	BD137	0.55	BSX26	0.49		
2N3391	0.20	3N201	1.05	BC115	0.15	BD138	0.63	BSX27	0.34		
2N3391A	0.22	40050	0.78	BC116	0.15	BD139	0.71	BSX28	0.25		
2N3392	0.13	40251	0.81	BC116A	0						

COMPONENTS FOR W.W. AMPLIFIER DESIGNS

100W AMPLIFIER (FEB. 1972)	
Designer approved kit.	15-60
Semiconductor set	2-50
Resistors, capacitors, pots	1-30
F/Glass PCB	1-30
POWER SUPPLY (For 100W Amp.)	
Designer approved kit.	14-70
Semiconductors, Resistors, capacitors, pots, trans-formers, F/Glass PCB	14-70
30W BLOMLEY (New approach to class B)	
Semiconductor set	5-60
Resistors, capacitors, pots	1-85
F/Glass PCB	0-70
30W BAILEY (Single power rail)	
Transistor set	4-60
Resistors, capacitors, pots	1-45
F/Glass PCB	0-65
LINSLEY-HOOD CLASS A (Dec., 1970, circuit)	
Designer approved kit.	1-20
2N3055 pair, BC212L, 2N1711	1-80
Resistors, capacitors, pot	0-60
F/Glass PCB	0-60
LINSLEY-HOOD 20W CLASS AB	
Designer approved kit.	3-35
MJ481/491, MJ521, BC182L, BC212L, zener	2-20
Resistors, capacitors, pots	0-70
F/Glass PCB	0-70
Please state 8Ω or 15Ω	
REGULATED 60V POWER SUPPLY	
A 5 transistor series stabiliser, suitable for a pair of Bailey or Blomley amplifiers, featuring very effective S/C protection. All Semi/C's, R's, C's, F/Glass PCB	4-85
Power supplies for other amplifiers also available	
BAILEY/BURROWS PRE-AMP (Aug., 1971)	
Component Set: Mono	2-75
Component set: Stereo	6-35
Each component set comprises of all specified resistors, capacitors, transistors pots, including special balance control for stereo sets.	
Stereo F/Glass PCB	1-60
STUART TAPE RECORDER	
Set of stereo f/glass PCBs	2-70
Components sets on price list.	

'TEXAN' TEXAS INSTRUMENTS DESIGNED & APPROVED FULL KIT



£28.50 INCLUDES TEAK CASE

20 Watt per channel stereo amplifier designed by Richard Mann of Texas Instruments and published in Practical Wireless May-July 1972.

This low distortion (0.09% at 20W into 8 ohm), wide bandwidth (-3dB 5Hz-35KHz) design is offered as a Texas Instruments approved full kit (including all metalwork and Teak case for a total of £28.50 post paid. Full details in price list.

METALWORK SYSTEM

Designed to house Bailey, Blomley or Linsley Hood Class AB amplifiers with simple or regulated power supplies and Bailey Burrows pre-amp. Options of standard or hum reducing toroidal mains transformer.

TOROIDAL TRANSFORMER 60 volt 2 amp.

Max. height 2in. Suitable for our regulated power supply	£7.40
Simple clamp	£0.20
Magnetically screening clamp	£0.75

SEMICONDUCTORS

2N699	0-25	BC184L	0-11
2N1613	0-20	BC212L	0-12
2N1711	0-25	BC214L	0-14
2N2926G	0-10	BCY72	0-13
2N3053	0-15	BF257	0-40
2N3055	0-45	BF259	0-47
2N3442	1-20	BFR39	0-25
2N3702	0-11	BFR79	0-25
2N3703	0-10	BFY50	0-20
2N3704	0-10	BFY51	0-20
2N3705	0-10	BFY52	0-20
2N3706	0-09	MJ481	1-20
2N3707	0-10	MJ491	1-30
2N3708	0-07	MJ521	0-60
2N3709	0-09	MPSA05	0-30
2N3710	0-09	MPSA12	0-55
2N3711	0-09	MPSA14	0-35
2N3819	0-23	MPSA55	0-35
2N3904	0-17	MPSA65	0-35
2N3906	0-20	MPSA66	0-40
2N4058	0-12	MPSU05	0-60
2N4062	0-11	MPSU55	0-70
2N4302	0-60	SN72741P	0-58
2N5087	0-42	SN72748P	0-58
2N5210	0-54	THB11	1-10
2N5457	0-30	TIP29A	0-50
2N5830	0-30	TIP30A	0-60
40361	0-40	TIP31A	0-60
40362	0-45	TIP32A	0-70
BC107	0-08	TIP33A	1-00
BC108	0-08	TIP34A	1-50
BC109	0-08	TIP41A	0-74
BC125	0-15	TIP42A	0-90
BC126	0-15	TIP3055	0-60
BC182K	0-10	IB08T20	0-50
BC212K	0-12	IB40K20	1-40
BC182L	0-10	IN914	0-07
		IN916	0-07
		IS44	0-05
		IS920	0-10
		IS3062	0-25
		5B05	1-20


HI-FI NEWS 75 WATT AMPLIFIER

BY J. L. LINSLEY-HOOD

Published Nov. 1972 to Feb. 1973

DESIGNER APPROVED KIT

- ★ 75 WATTS PER CHANNEL
 - ★ BANDWIDTH (3dB) 3HZ-40KHZ
 - ★ DISTORTION LESS THAN 0.01%
 - ★ UNCONDITIONAL STABILITY
- COMPONENT PACKS



SLIMLINE STYLE CHASSIS DIMENSIONS: 17.0in. x 2.0in. x 12.0in. This slimline unit has been made practical by the use of a specially designed TOROIDAL TRANSFORMER and highly compact printed circuit boards which have been fully tested and approved by Mr. Linsley-Hood.

FREE TEAK CASE

Total cost of individually purchased packs: **£63.95**

WITH 75 WATT PER CHANNEL COMPLETE AMPLIFIER KITS

Cost of complete kit: **£56.60**
TRADE ENQUIRIES WELCOME

P.S. Full circuit description in handbook 30p

FOR FURTHER DETAILS PLEASE WRITE TO:

POWERTRAN ELECTRONICS

PORTWAY INDUSTRIAL ESTATE, ANDOVER : HANTS

MAIL ORDER ONLY POST FREE TO U.K. OVERSEAS AT COST

U.K. Orders Subject to 10% V.A.T. Surcharge

Pack		
1	Fibre glass printed circuit board for power amp.	£0.75
2	Set of resistors, capacitors, pre-sets for power amp. . .	£1.50
3	Set of semi-conductors for power amp. (highest voltage version)	£5.50
4	Pair of 2 drilled, finned heat sinks	£0.80
5	Fibre glass printed circuit board for pre-amp.....	£1.10
6	Set of low noise resistors, capacitors, pre-sets for pre-amp	£2.70
7	Set of low noise, high gain semi-conductors for pre-amp	£2.10
8	Set of potentiometers (including mains switch)	£1.55
9	Set of 4 push button switches, rotary mode switch	£3.10
10	Toroidal transformer complete with magnetic screen/housing primary: 0-117-234 V. secondaries: 33-0-33 V. 24-0-24 V., electrostatic screen	£9.15
11	Fibre glass printed circuit board for power supply	£0.55
12	Set of resistors, capacitors, secondary fuses, semi-conductors for power supply	£3.50
13	Set of miscellaneous parts including DIN skts., mains input skt. fuse holder, interconnecting cable, control knobs	£3.25
14	Set of metal workparts including silk screen printed fascia panel and all brackets, fixing parts, etc.	£6.30
15	Handbook, based on Hi-Fi News articles	£0.30
16	Teak cabinet	£7.35

2 each of packs 1-7 inclusive are required for complete stereo system.

Basic Component Set

Set of semi-conductors, resistors, capacitors, printed circuit boards for stereo power amp, pre-amp. and power supply.

£31.35

Handbook Included

New Branches BOLTON COVENTRY SUNDERLAND STOCKPORT DONCASTER opening Sept



HI-FI CENTRES LTD.

- BIRMINGHAM** 30-31 Gt. Western Arcade (Closed Wed.) Tel: 236 1279
- BOLTON** 23 Deansgate Tel: 33512
- BRADFORD** 10 North Parade (Closed Wed.)
- COVENTRY** 17 Shelton Square Tel: 25983
- DONCASTER** 19 Northgate (Closed Wed.)
- DERBY** The Spot, 25 Osaston Rd. (Closed Wed.) Tel: 41361
- DONCASTER** 3 Queensgate, Waterdale Centre.
- EDINBURGH** 101 Lothian Road (Closed Wed.)
- GLASGOW** 326 Argyle St. (Closed Tues.)
- HULL** 7 Whitefargate (Closed Thurs.)
- LEEDS** 5-7 County (Mecca) Arcade, Briggate (Closed Wed.) Tel: 28252
- LEICESTER** 32 High St. (Closed Thurs.)
- LIVERPOOL** 73 Dale St. (Closed Wed.)
- LONDON** 238 Edgware Rd., (Closed Thurs.)
- MANCHESTER** 60a Oldham St. (Closed Wed.)

MAIL ORDERS to:
106 HENCOCK LANE, LEEDS 13.
Terms C.W.O. or C.O.D. Postage 22p extra under £2. 33p extra over £2, or as stated. Trade supplied. S.A.E. with enquiries.

EXPORT ENQUIRIES WELCOMED BRANCHES OPEN ALL DAY SATURDAYS AND OPERATE A 5-DAY WEEK MAIL ORDERS NOT TO BE SENT TO SHOPS.

MIDDLESBRO 106 Newport Rd (Closed Wed.)
NEWCASTLE-ON-TYNE 24 Newgate Shopping Centre (Closed Wed.) Tel. 21469
NOTTINGHAM 19 Market St. (Closed Thurs.)
SHEFFIELD 13 Exchange St. (Closed Thurs.) Tel.: 20716

STOCKPORT 8 Little Underbank Tel. 480 0777 (Closed Thurs.)
SUNDERLAND 5 Market Square (Closed Wed.)

ALL PRICES INCLUDE VAT AND FULL LABOUR/MATERIAL GUARANTEES.
HUGE DISCOUNTS ON LEADING BRAND TAPE AND TURNTABLE UNITS

- AKAI GXC 40D Tape Unit** £62.95 (Rec Price £89.74). Carr. £1.
 - AKAI 4000DS Tape Unit** £68.95 (Rec Price £93.50). Carr. £1.
 - AKAI 1721L Tape Unit** £66.95 (Rec Price £93.87). Carr. £1.
 - AKAI CR81D Tape Unit** £58.95 (Rec Price £84.10). Carr. £1.
 - GOLDRING GL72 T/Table & P.U.** £27.70 (Rec Price £34.65). Carr. 75p.
- Also FREE with above GL72 Goldring G800 cartridge worth over £10
B.S.R. MACDONALD MP60 T/Table & P.U. £9.95 (Recom. Price £14.84). CREDIT TERMS AVAILABLE. MIN. DEPOSIT 10%. Carr. 40p.
- Above is only a selection of Discount Lines, also Leak, Wharfedale etc.

R.S.C. G66 MkII 6+6 WATT STEREO AMPLIFIER
High Quality Output. Rating I.H.F.M. Ind. Ganged Control to Bass Treble, Vol. and Balance. Solid state constr. employing 1 0 Trans plus diodes. Range 20-20,000Hz. Bass control \pm 12 dB Treble \pm 13 dB. Selector switch P.U. or Tape/Radio. Output for 3-15 ohm speakers. Standard 200-250v. 50 Hz mains operation. Attractive Black/Silver metal face plate and matching knobs.

COMPLETE KIT OF PARTS INC. FULLY WIRE PRINTED CIRCUIT £12.65 OR FACTORY BUILT IN TEAK VENEERED CABINET £16.50

FANE ULTRA HIGH POWER LOUDSPEAKERS
Power Rating R.M.S. continuous. 2 years guarantee. Carr. free

12" 'POP' 50 Watts	15" 'POP' 60 Watts	18" 'POP' 100 Watts
£11.99	£14.75	£25.95

Or Dep. £2 and 9 monthly Or Dep. £3.30 and 9 monthly Or Dep. £5.00 and 9 monthly payments £1.33 (Total £13.97) payments £1.50 (Total £15.00) payments £2.49 (Total £28.41) Pair suitable for all purposes. SUITABLE FOR BASS GUITAR, ELECTRONIC ORGAN, etc.

FANE MODE ONE HI-FI SPEAKER KIT
inc. 803 8" cmt. 303 Pres. Tweeter, Printed circuit, inductor, capacitor, cross-over, acoustic filling, panels, screws, etc. Post free Response ONLY £9.96 30-20,000 Hz

FANE SPEAKERS 'POP' 25/2
12" 25 WATT Dual Cone. 15 ohms NOT for Bass Guitar. £7.95 Or Dep. £1.25 and 9 monthly payments 69p (Total £9.20)

R.S.C. MAINS TRANSFORMERS
FULLY GUARANTEED. Insulated and impregnated where necessary. Primaries 200-250v. 50 Hz. Screened MIDGET CLASPED TYPE 2 1/2 x 9 1/2 x 2 1/2. 280v., 60mA, 6.3v. 2a. £1.10
280-0-280v., 60mA, 6.3v. 2a. £1.10
FULLY SHROUDED TYPED MOUNTING 280-0-280v., 60mA, 6.3v. 2a., 0-5-6.3v. 2a. £1.55
280-0-280v., 100mA, 6.3v. 4a., 0-5-6.3v. 2a. £2.45
300-0-300v., 100mA, 6.3v. 4a., 0-5-6.3v. 2a. £2.45
300-0-300v., 130mA, 6.3v. 4a., c.t., 6.3v. 1a. £2.85
For Mullard 510 Amplifier. £2.85
350-0-350v., 100mA, 6.3v. 4a., 0-5-6.3v. 2a. £2.45
350-0-350v., 150mA, 6.3v. 4a., 0-5-6.3v. 2a. £2.85
425-0-425v., 200mA, 6.3v. 4a., c.t., 5v. 2a. £2.45
425-0-425v., 200mA, 6.3v. 4a., 0-5-6.3v. 2a. £2.85
450-0-450v., 250mA, 6.3v. 4a., c.t., 5v. 2a. £2.80
TOP SHROUDED DROP-THROUGH TYPE 250-0-250v., 70mA, 6.3v. 2a., 0-5-6.3v. 2a. £1.49
250-0-250v., 100mA, 6.3v. 2a., 0-5-6.3v. 2a. £1.71
250-0-250v., 100mA, 6.3v. 2a., 6.3v. 1a. £1.75
350-0-350v., 80mA, 6.3v. 2a., 0-5-6.3v. 2a. £1.81
350-0-350v., 100mA, 6.3v. 4a., 0-5-6.3v. 2a. £2.45
350-0-350v., 150mA, 6.3v. 4a., c.t., 6.3v. 1a. £2.85
Suitable for Mullard 510 Amplifier
350-0-350v., 100mA, 6.3v. 4a., 0-5-6.3v. 2a. £2.45
350-0-350v., 150mA, 6.3v. 4a., 0-5-6.3v. 2a. £2.85
FILAMENT OR TRANSISTOR POWER PACK TYPES 6.3v. 1.5a. 55p; 6.3v. 2a. 60p; 6.3v. 3a. 85p; 6.3v. 6a. £1.45; 12v. 1a. 61p; 0-9-18v. 1a. £1.25; 0-12-25-25v. 2a. £1.95; 12v. 2a. or 24v. 1.5a. £1.50; CHARGE TRANSFORMERS 0-9-15v. 1a. £1.10; 2 1/2a. £1.25; 3a., £1.40; 5a., £1.60; 6a., £1.85; 8a., £2.20.
AUTO (Step UP/Step DOWN) Transformers 0-110/120v., 200-230-250v. 50-80 watts £1.25; 150w., £2.10; 250w., £3.00; 500w., £6.40
OUTPUT TRANSFORMERS Standard Pentode 5,000 Ω to 7,000 Ω to 3 Ω 55p Push-Pull 8 watts EL84 to 3 Ω or 15 Ω 95p Push-Pull 10 watts 6V6 ECL86 to 3, 5, 8 or 15 Ω £1.55 Push-Pull EL84 to 3 or 15 Ω 10-12 watts £1.50 Push-Pull Ultra Linear for Mullard 510, etc. £2.45 Push-Pull 15-15 watts, sectionally wound 6L6 KT66, etc., for 3 or 15 Ω £2.20 Push-Pull 20 watt high quality sectionally wound EL34, 6L6, KT66, etc. to 3 or 15 Ω £3.65

HI-FI SPEAKER ENCLOSURES
Teak veneer finish. Pleasing design. Acoustically lined. All sizes approx. £5.50
16 x 11 x 9 in. Pressurised. Excellent results with 8 in. Hi-Fi speaker. £6.50
19 x 10 1/2 x 9 in. Speaker. £6.75
10-in. speaker. 2 1/2 x 16 x 9 in. Ported. £6.75
£12 for high grade results with 12 in. Hi-Fi speaker and Tweeter. £7.95
2 1/2 x 16 x 9 in. Pressurised.

FANE 807T HIGH FIDELITY SPEAKER 8" 10 WATT
A full range unit to provide excellent sound quality in suitable enclosure. Roll P.V.C. cone surround and long throw voice coil to achieve very low fundamental resonance of 30 Hz. Tweeter cone extends high note response. Frequency range 25-15,000 Hz Imp. 3 or 8/15 Ω (state requirement). £3.70
REMARKABLE VALUE £4.95
MODEL 803T 8" 15w. with parasitic Tweeter. Response 25 Hz to 15 KHz. GAUSS 13,000 Imp 3 or 8-15 ohms. ONLY £4.95

BATTERY/MAINS CONVERSION UNITS
R.S.C. BM1 battery eliminator completely replaces 1.5v. and 90v. Radio batteries where normal 200-250v. AC mains is available. £4.15 Ready for use

HIGH FIDELITY SPEAKERS AUDIOTRINE RANGE
Heavy construction. Highly efficient ceramic magnets. Plastiflex cone surrounds. "D" indicates Tweeter cone providing frequency range up to 15 KHz. Exceptional performance at low cost.
HF 808T 8" 10W £2.98
HF 102D 10" 10W £3.30
HF 120. 12" 15W £4.95 Please state impedance
HF 120D 12" 15W £5.50
HF 125. 12" 15W £6.25
HF 125D 12" 15W £8.85 3 or 8-15 ohm.

HI-FI SPEAKER SYSTEMS
Audiotrine 121K. 12 in. 15 watt. 11,000 Gauss bass unit. Crossover unit and Tweeter. Smooth response and wide frequency range ensure realistic sound reproduction. Carr. 33p £6-50
Audiotrine 125K with extra sensitive 15,000 Gauss 12 in. speaker. £7-65

MARCONI TF 167 SIGNAL GENERATOR
Range: 15KHz to 30MHz. Output 0.4V to 4V at 13 or 75 ohm impedance with termination (supplied). Built in crystal check facility with handbook, £138 including carr.

MARCONI SIGNAL GENERATOR TF 801B/3/S. Range 12 Mc/s to 485 Mc/s. P.O.A. TF121 HETERODYNE UNIT. Frequency range: 2 Kc/s-100 Mc/s in seven ranges. P.O.A. TF134/2 COUNTER FREQUENCY METER with plug-in units up to 250 Mc/s. P.O.A. OA.494A/2 H.F. SPECTRUM ANALYSER with trolley and L.F. extension unit TM6448. Frequency range: 3-30 MHz in nine bands. Selectivity: 6, 30, 150 Hz at 3 dB. Spectrum width: 0-3 kHz and 0-30 kHz in two ranges. Sweep duration: 0.1, 0.3, 1, 3, 10 and 30 sec. and manual control.

TF 144N SIGNAL GENERATOR. Frequency range: 10 kHz-72 MHz. Stability: 0.002%. High discrimination, plus crystal calibrator. Good r.f. waveform at all frequencies. Protected thermocouple level monitor. Price and spec. on request.

A.P.T. CONSTANT CURRENT POWER SUPPLY MODEL 555
D.C. voltage: 0-500v (cont. var.) in 4 ranges. D.C. current: 0-450mA adjustable 0-350mA in 7 steps, 0-90mA in 9 steps and 2-13mA var. A.C. voltage 6.3v at 10A. £52 incl. carr.

L.F. RESOLVED COMPONENT INDICATOR TYPE WP 253/2 This instrument will indicate, by means of two centre-zero 6-in. scale meters, the resolved components of a signal voltage with respect to the applied reference energisation. Frequency range: nominal range 0.5 c/s to 1 Kc/s. Accuracy of indication: \pm 3% of full scale on all ranges £70

RACAL UNIVERSAL COUNTER/TIMER SA550 (CT488)
8 digit in-line read-out. Facilities include: direct frequency measurement up to 100MHz; pulse, period, ratio, time interval and totalling measurements. Input sensitivity variable from 300mV to 9V, three independent inputs, self-check etc. Full spec. and price on request.

JOHN CRICHTON Electronic Equipment
558, Kingston Road, Raynes Park, London, S.W.20

TEKTRONIX OSCILLOSCOPES TYPES:
515A, 524AD, 543, 545, 545A, 545B. Plug-in Units: CA, G, 1A1, 10A1. P.O.A.

QUANTIZATION DISTORTION TESTER. Utilises system power supply. Output level: Variable in 1 dB steps, from -50 to +2 dBm. Accuracy: \pm 0.2 dB at +2 dBm, \pm 0.5 dB incremental. Quantization distortion: 0 to -40 dB in 0.5 dB steps. Meter indication: True r.m.s. Input impedance: 600 Ω \pm 10% balanced.

AVO MODEL 3 VALVE TESTER
Enables comprehensive characteristics to be plotted, or measures valves on a simple good/bad basis. £55 incl. carr.

AVO CT 160 VALVE TESTER
As above but in portable valise form as illustrated. Price £85 incl. carr.

AVO TRANSISTOR ANALYSER CT 446. £70 incl. carr.

GALVANOMETER by "Weston" scale 0-100 M.C. F.S.D. 200 uA, round 2 1/2 in. £1.50 post paid.
Carriage extra for overseas orders. Inland V.A.T. add 10%. Please phone 01-540 9334

Wilkinsons RELAYS P.O. TYPE 3000 AND 600
BUILT TO YOUR SPECIFICATION. HIGHEST QUALITY AT COMPETITIVE PRICES WITH QUICK DELIVERY SERVICE. QUOTATIONS BY RETURN HOME AND OVERSEAS.

Post Office Type Uniselectors in stock 25 way double ended wipers & level all non-bridging 11 level 1 bridging 10 non-bridging.

GEARED MOTORS. Double reduction Worm Gear Unit by Parvalux, 200/240 volts A.C., 0.2 amps., 2 mfd. condenser, 12 r.p.m., 35 lbs./ins., two shafts 3/8 in. x 1 1/2 in., fitted with a 24 volt Magnetic Brake Clutch. £20 each.

MINIATURE BUZZERS
6-12 volts, with tone adjuster 25p each as illus. 15p each for lots of 50

HIGH SPEED COUNTERS £1.75 each with 4 figures. The following D.C. voltages are available 6 v., 12 v., 24 v., 50 v., or 110 v. Auxiliary contacts, normally open, 40p extra.

BURGESS TWO CIRCUIT MICROSWITCH. One Micro Switch, 25 amps up to 250 volts A.C. 15 amps up to 460 volts A.C. £2 per box of ten. £15 per 100

JACK PLUGS
2 point with screw on cover 15p each. Type 201 fitted 4 ft. 6 in. headphone cord 20p each. Belling Lee L356 Fuse Holders, 10p each.

L. WILKINSON (CROYDON) LTD., LONGLEY HOUSE, LONGLEY RD., CROYDON. CR9 3LH. Phone 01-884 0236. Grams: WILCO CROYDON
WW-111 FOR FURTHER DETAILS

Transistor TELEPHONE AMPLIFIER Our price ONLY £3.99

4-STATION INTERCOM £8.75

Increase efficiency of Office, Shop and Workshop with this **DELUXE TELEPHONE AMPLIFIER** which enables you to take down long telephone messages or converse without holding the handset. Just moisten the suction pad and stick it to one side of the telephone. A useful office aid. On/Off switch. Volume control. Operates on one 9v battery. Size 3in. x 4in. Ready to operate. Complete with battery. P & P 25p.

This NEW, versatile De Luxe 4-Station Transistorised Intercom (1 Master and 3 Subs) for desk or wall mounting can solve your communication problems instantly. Effective range 300ft. Call/talk/listen from Master to Subs and Subs to Master. With Selector switch. Ideally suitable for office, shop, home or surgery. Adaptable for Mains. Complete with three 86ft. connecting wires and accessories. On/Off switch volume control. P. & P. 44p.

WEST LONDON DIRECT SUPPLIES
169 KENSINGTON HIGH STREET, LONDON W8 6SN

SERVICE TRADING CO

MATSUNAGA VARIABLE VOLTAGE TRANSFORMERS

INPUT 230 v. A.C. 50/60

OUTPUT VARIABLE 0/260 v. A.C.

Carriage extra if not shown.
BRAND NEW. All types.

- 50 AMP
0-260 v. at 1 amp. (Post 50p) £7-00
- 0-260 v. at 2.5 amps (Post 60p) £8-05
- 0-260 v. at 5 amps (Post 75p) £11-75
- 0-260 v. at 10 amps. £22-50
- 0-260 v. at 15 amps. £25-00
- 0-260 v. at 20 amps. £49-00
- 0-260 v. at 37.5 amps. £82-00
- 0-260 v. at 50 amps. £98-00

Special discount for quantity

OPEN TYPE (Panel Mounting)

1 amp £7-00. Post 50p. 2½ amp £8-05. Post 60p.

L.T. TRANSFORMERS

All primaries 220-240 volts.	Price	Post
Type No. Sec. Taps		
1 30, 32, 34, 36 v. at 5 amps.	£4-70	45p
2 30, 40, 50 v. at 5 amps.	£6-90	60p
3 10, 17, 18 v. at 10 amps.	£5-00	50p
4 6, 12 v. at 20 amps.	£5-50	60p
5 17, 18, 20 v. at 20 amps.	£7-30	60p
6 6, 12, 20 v. at 20 amps.	£6-90	60p
7 24 v. at 10 amps.	£5-30	50p
8 4, 6, 24, 32 v. at 12 amps.	£7-20	60p
9 6 and 12 v. at 10 amps.	£3-80	40p

VENNER ELECTRIC TIME SWITCH

200/250 volt. Ex-GPO. Tested, perfect condition. Two ON, two OFF, every 24 hrs. at any manually pre-set time. Price: 15 amp. £3-85. 20 amp. £4-39. Also available with Solar Dial DN at dusk, DFF at dawn. Prices as above.



MOTOROLA MAC11/6 PLASTIC TRIAC 400 PIV 10 AMP

Now available EX STOCK supplied complete with full data and applications sheet. Price £1-05. Post 5p. Suitable Diac 20p.

240 V A.C. SOLENOID OPERATED FLUID VALVE

Will handle liquids or gases up to 7 p.s.i. Forged brass body, stainless steel core and spring. ½ in. b.s.p. Inlet/outlet. Precision made. British mfg. PRICE: £1-75. Post 25p. Special quotation for quantity. NEW in original packing.



FOOT SWITCH

Suitable for Motors, Drills, etc., etc. 5 amp. 250 Volt. Price 75p. Post 15p.



POWER RHEOSTATS

New ceramic construction, vitreous enamel embedded winding, heavy duty brush assembly, continuously rated.

- 25 WATT 10/25/50/100/250/500/1k/1.5k ohm 95p. Post 10p.
- 50 WATT 1/5/10/25/50/100/250/500/1k/1.5k/2.5k/3.5k/5k ohm £1-35. Post 10p.
- 100 WATT 1/5/10/25/50/100/250/500/1k/1.5k/2.5k/3.5k/5k ohm £1-95. Post 15p.

Black Silver Skirted knob calibrated in Nos. 1-9. 1½ in. dia brass bush. Ideal for above Rheostats. 22p ea.

UNISELECTOR SWITCHES - NEW

- 4 BANK 25 WAY FULL WIPER 25 ohm coil, 24 v. D.C. operation £6-90. Post 30p.
- 6 BANK 25 WAY FULL WIPER 25 ohm coil, 24 v. D.C. £7-90. Post 30p.
- 8 BANK 25 WAY FULL WIPER 24 v. D.C. operation £9-50. Post 40p.



'HONEYWELL' PUSH BUTTON, PANEL MOUNTING MICRO SWITCH ASSEMBLY

Each bank comprises of a change-over rated at 10 amps 240 volt A.C. Black knob 1 in. dia. Fixing hole ½ in. Prices: 1-bank 30p, 2-bank 40p, 3-bank 50p. (Illustrated) Inc. P. & P. Special quotes for quantities.



24 HOUR TIMER

Can be adjusted to give a switching delay of between ½ hr. to 24 hrs. Driven by 200/250v. A.C. synchronous motor, 15 amp. c/o contacts. Mfg. Greer Controls Ltd. Supplied with scale calibrated 0-10 (2 hours per division) Brand new. £1-75. Post 25p.



'HONEYWELL' LEVER OPERATED MICROSWITCH

15 amps 250 volt A.C. c/o contacts. NEW in maker's carton. Price 10 for £1-90. Post 15p.



STROBE! STROBE! STROBE!

* FOUR EASY TO BUILD KITS USING XENON WHITE LIGHT FLASH TUBES, SOLID STATE TIMING + TRIGGERING CIRCUITS, PROVISION FOR EXTERNAL TRIGGERING. 230-250v. A.C. OPERATION.

* EXPERIMENTERS "ECONOMY" KIT
Adjustable 1 to 30 Flash per sec. All electronic components including Xenon Tube + instructions £6-30. Post 30p.

* NEW INDUSTRIAL KIT
Ideally suitable for schools, laboratories etc. Roller lin printed circuit. Adjustable 1-80 f.p.s., approx. 1 output of Hy-Light. Price £10-50. Post 50p.

* HY-LIGHT STROBE
Designed for use in large rooms, halls and utilizes a silica tube, printed circuit. Speed adjustable 1-20 f.p.s. Light output greater than many (so called 4 Joule) strobes. Price £12-00. Post 50p.

* 'SUPER' HY-LIGHT KIT
Approx. 4 times the light output of our well proven Hy-Light strobe.
* Variable speed from 1-13 flash per sec.
* Reactor control circuit producing an intense white light. ONLY £20-00. Post 75p.

* ATTRACTIVE, ROBUST, FULLY VENTILATED METAL CASE for the Super Hy-Light Kit including reflector. £7-00. Post 60p.

* FOR HY-LIGHT STROBE incl. reflector, £4-75. Post 25p.

* 7-INCH POLISHED REFLECTOR. Ideally suited for above Strobe Kits. Price 55p. Post 15p.

RAINBOW STROBE FOUR LIGHT CONTROL MODULE

* Will operate four of our Hy-Light or Super Hy-Light Strobes in either 1, 2, 3, 4 sequence; 2+; or all together. Thoroughly tested and reliable. Complete with full connection instructions. Price: £18-00. Post 50p. Send S.A.E. for details.

COLOUR WHEEL PROJECTOR

* Complete with oil filled colour wheel, 100 watt lamp. 200/240V AC. Features extremely efficient optical system. £18-50. Post 50p.



6 INCH COLOUR WHEEL

* As used for Disco lighting effects, etc. Price £5-00. Post 30p.

BIG BLACK LIGHT

* 400 Watt. Mercury vapour ultra violet lamp. Extremely compact and powerful source of u.v. Innumerable industrial applications also ideal for stage, display, discos etc. P.F. ballast is essential with these bulbs. Price of matched ballast and bulb £16-00. Post £1. Spare bulb £7-00. Post 40p.




BLACK LIGHT FLUORESCENT U.V. TUBES

* 4ft. 40 watt. Price £5-50. Post 30p. (For use in standard bi-pin fluorescent fittings). MINI 9 inch 6 watt black light U.V. tube. £1-30. Post 15p. Complete ballast unit and holder for 9 in. tube £1-70. Post 25p.

ELECTRONIC ORGAN KIT

parts including speaker, etc., together with full instructions and 10 tunes. £3-25. Post 35p.




Easy to build, solid state Two full octaves (less sharps and flats). Fitted hardwood case, powered by two penlite 1½v. batteries. Complete set of

50 in 1 ELECTRONIC PROJECT KIT

50 easy to build Projects. No soldering, no special tools required. The Kit includes Speaker, meter, Relay, Transformer, plus a host of other components and a 56-page instruction leaflet. Some examples of the 50 possible Projects are: Sound level Meter, 2 Transistor Radio, Amplifier etc. etc. Price £8-80

HONEYWELL PROGRAMME TIMERS

240V. A.C. 5 r.p.m. motor. Each cam operating a c/o micro switch. Cams are individually variable, allowing innumerable combinations. Ideally suited for machinery control, automation etc. Also in the field of entertainment, for chaser lights, animated displays, etc. 15 cam model £5-75. Post 25p. 10 cam model £4-75. Post 25p.



SIMPLE 12 CAM PROGRAMMER with 4 adjustable cams and 8 that may be profiled to individual requirements. Available with 15 or 13 r.p.m. motor £3-50. Post 25p.

VAT

All prices are subject to 10% VAT. (10p in the £)

To all orders add 10% VAT to total value of goods including carriage/packaging.



INSULATED TERMINALS
Available in black, red, white, yellow, blue and green. New 10p each. Incl. P. & P. Minimum order 6.

METER BARGAIN

BALANCE/LEVEL METERS
100-0-100 Micro Amp. Size 1½ in. x 1½ in. x ½ in. Price only 70p. Post 5p.



AMMETERS NEW! 2½ in. FLUSH ROUND
available as D.C. Amps 1, 5, 15, 20 or A.C. Amps 1, 5, 10, 15, 20. Both types £1-85. Post 15p. 0-300V. A.C. £2-00. Post 15p.



RELAYS

SIEMENS PLESSEY, etc. MINIATURE RELAYS			
1	2	3	4
52 4-6 6M 60p*	700 12-24 2 c/o 60p*		
52 4-6 4 c/o 80p*	700 15-35 2c/oHD 70p*		
150 6-12 4 c/o 80p*	700 16-24 6 M 80p*		
185 8-12 6 M 60p*	700 20-30 6 c/o 80p*		
280 9-12 2 c/o 70p*	1250 24-36 4 c/o 60p*		
410 10-18 4 c/o 70p*	2500 36-45 6 M 80p*		
600 9-15 2 c/o 60p*	2400 30-48 4 c/o 50p*		
700 16-24 4MBZ 60p*	9000 40-70 2 c/o 50p*		
700 16-24 4 c/o 80p*	15k 85-110 6 M 50p*		

(1) Coil ohms; (2) Working d.c. volts; (3) Contacts; (4) Price HD=Heavy Duty. All Post Paid. (*including Base)

12 VOLT D.C. RELAY
Type 1: Three sets c/o contacts 5 amp. 75p. Post 5p. (Similar to Illustration below.)
Type 2: 4-8 volt 3 c/o HD, 67 ohm coil. 75p. Post 5p

SPECIAL OFFER.
700 ohm. 4 c/o Ex. new equipment. £50-00 per 100 incl. bases (minimum 100).

230 VOLT A.C. 'DIAMOND H' RELAYS (Unused)
Three sets c/o contacts rated at 5 amps. Price 55p Inc. P. & P. (100 lots £40-00). 24 volt A.C. 3 c/o 55p. Post 5p.



230 VOLT A.C. RELAYS
One set c/o contacts rated at 7.5 amps. Boxed. Price 50p. Post 5p.

MINIATURE RELAYS
9-12 volt D.C. operation. 2 c/o 500 M.A. contacts. Size only 1 in. x 1½ in. Price 60p. Post 5p.
30-36 v. D.C. operation. 2 c/o 500 M.A. contacts. 3,200 ohm coil. Size only 1x2x1½ in. 40p. Post 5p.

MINIATURE LATCHING RELAY
Mfg. by Clare-Elliott Ltd. (Type F) 2 c/o permanent latching in either direction. Coll 1150 ohm. 15-30 v. D.C. New 65p. Post 5p.

INSULATION TESTERS (NEW)

Test to I.E.E. Spec. Rugged metal construction, suitable for bench or field work, constant speed clutch. Size L. 8 in. W. 4 in., H. 6 in., weight 6 lb. 500 VOLTS, 500 megohms £28-00. Post 60p. 1,000 VOLTS, 1,000 megohms £34-00. Post 60p.



BLOWER UNIT

200-240 Volt A.C. BLOWER UNIT
Precision German built. Dynamically balanced, quiet, continuously rated, reversible motor. Consumption 60m.A. Size 120mm. dia. x 60mm. deep. Price £3-00. Post 30p.



230V FAN ASSEMBLY

Continuously rated, special sealed bearing, removable aluminium blades. Price 80p. Post 20p.



4 BANK 3 c/o PUSH BUTTON ASSEMBLY

Complete with black rectangular buttons. 5 units 85p. Post 15p. (5 units min.).




230V/240V SYNCHRONOUS COMPACT GEARED MOTORS.

Manufactured by either Sangamo, Haydon or Smith. Built-in gearbox. 3 RPH A/cw 20 RPH cw 2 RPH cw 6 RPH cw 12 RPH cw cw=Clockwise. A/cw=Anti-clockwise All at 83p



BODINE TYPE N.C.I. GEARED MOTOR

(Type J) 71 r.p.m. torque 10 lb. in. Reversible 1/70th h.p. cycle 38 amp. (Type 2) 28 r.p.m. torque 20 lb. in. Reversible 1/80th h.p. 50 cycle 28 amp. The above two precision made U.S.A. motors are offered in 'as new' condition. Input voltage of motor 115v A.C. Supplied complete with transformer for 230/240v A.C. input. Price, either type £4-84 or less transformer £2-75. These motors are ideal for rotating aerials, drawing curtains, display stands, vending machines, etc. etc.



PARVALUX TYPE SD2. 200/250 VOLT. A.C. D.C. HIGH SPEED MOTOR

Speed 9,000 r.p.m. approx. or 3,200 r.p.m. If used with built-in governor, or variable speed over a wide range if used in conjunction with our Dimmer Switch, illustrated below. PRICE: £1-75. Post 35p.



600 WATT DIMMER SWITCH

Easily fitted. Fully guaranteed by makers. Will control up to 600 watts of all lights except fluorescent at mains voltage. Complete with simple instructions. £2-75. Post 25p.



ALL MAIL ORDERS, ALSO CALLERS AT:

57 BRIDGMAN ROAD, CHISWICK, LONDON, W4 5BB. Phone: 01-995 1560
Closed Saturdays.

SERVICE TRADING CO.

SHOWROOMS NOW OPEN
AMPLE PARKING

PERSONAL CALLERS ONLY

9 LITTLE NEWPORT STREET, LONDON, WC2H 7JJ.
Tel.: 01-437 0576

400Hz HIGH FREQUENCY ROTARY CONVERTERS
 27.5V, 150A. Input, 115V, 400Hz 2500VA. output. Not new but in excellent condition; fitted with control box containing switchgear and voltage and frequency adjustment circuits. These are extremely small for their capacity only 16in. long and 13in. high overall including the control box which also carries the circuit diagram. £31.90 (C. Pd. U.K. Mainld.).
 Type 153 24-28V, D.C. input, output 115V, 3 phase, 750W, 400Hz, 0.8pF. £21.50 (C. Pd. U.K. Mainld.).
 Type 153A, 100-116V, D.C. input, output 115V, 3 phase 750W, 400Hz, 0.8pF. £23.50 (C. Pd. U.K. Mainld.).
 Type 8A, 24V, D.C. input, output 115V, 400Hz 3 phase 1-8 amps. £16.50 (C. Pd. U.K. Mainld.).
 Type 100A, 22.5-23.5V, D.C. input, output 115V, 400Hz 3 phase 150VA, 0.8pF. £16.50 (C. Pd. U.K. Mainld.).
 Type 100B, 22-28V, D.C. input, 115V, 3 phase 400Hz, 150VA, 0.8pF. £16.50 (C. Pd. U.K. Mainld.).
 Type 200, 25-28V, D.C. input, 115V, 1 phase 360W, 1600Hz. output. £15.50 (C. Pd. U.K. Mainld.).
 Type 200A, input 25-28V, D.C., 115V, 1 phase, 360VA, 1.0pF 1600Hz output. £18.50 (C. Pd. U.K. Mainld.).
 Type 7, 22-29V, D.C. input, 80V, 1 phase, 240VA, 1 pF, 1600Hz output. £13 (C. Pd. U.K. Mainld.).
 Type 2, 24V, D.C. input, 40 amps, 80V, A.C. 6.25 ohms, 5KVA, 1pF, 1.100Hz output. £33 (C. Pd. U.K. Mainld.).

FERROGRAPH RE7 PROFESSIONAL TAPE SPOOLS
 5 for £2.95 (P. Pd. U.K.).
SPECIAL OFFER OF REED RELAYS containing up to 4 make or break reed inserts. Parcel of 20 for £3.25, parcel of 50 for £6.85 (P. Pd. U.K.).

FULL RANGE of Mk. IV multiway and co-axial connectors always available to small and large users. Ex-stock delivery at extremely competitive prices.

AIRLITE TYPE 62 Aircrew Mic Headsets £7-15 (P. Pd. U.K.) We hold extremely large stocks of G.E.C., S.T.C. and Plessey **SEALED RELAYS** available for Ex-Stock Delivery.

TELEVISION MEASURING OSCILLOSCOPE Type TF 1277. Available to callers only, at our Lydd premises, Teaching Machines (U.S.I.) Auto-tutor Mark 2.

BECKMAN TYPE B Helipot dials, ex-units, but in excellent condition. £1-10 (P. Pd. U.K.).

AMPHENOL MICRODIALS type 1309, £5-50 (P. Pd. U.K.).
KENT CHRONALOGPRINT OUT UNIT (P.O.A.).
POST OFFICE TRANSFORMERS type 416A, 55p. (P. Pd. U.K.).

DIGITAL MEASUREMENTS LIMITED, Digital Voltmeter type DM 2003, A.C./D.C. to 1kV, three digit. £44. (C. Pd. U.K.).
MF (D.C.-1MHz) ATTENUATOR, Marconi TF2162. £17-50 (C. Pd. U.K.).
CAMBRIDGE INSTRUMENTS D.C. Potentiometers, three available, in excellent condition. (P.O.A.).
MARCONI INSTRUMENTS Transistorised 510MHz to 1MHz converter. £150 (C. Pd.).

ALL PRICES INCLUDE 10% V.A.T.

SPECIALIST STOCKISTS OF SERVOMOTORS, SYNCHROS, MAGSLIPS & CONNECTORS

Servo and Electronic Sales Ltd

Regd. Office: 45a HIGH STREET, ORPINGTON, KENT. (Telex No. 965265)

Post Orders and Technical enquiries to: "BAYS", HIGH ST., LYDD, KENT. Lydd 20252 (STD 0679)
 Or 67 LONDON ROAD, CROYDON, SURREY (Retail and Instrument Repairs). Phone: 01-688 1512
 V.A.T. Reg. No. 201-1296-23

200-250V MAINS TO 27V 500mA D.C. STABILISED
A.C. MAINS TO 27V D.C. POWER SUPPLY UNIT
A.C. MAINS/27V DC POWER SUPPLY UNIT (P. Pd. U.K.)
EACH £4.13

A.C. MAINS TO 27V D.C. POWER SUPPLY UNITS with circuit. These interesting 27v 0.5A units (will happily provide 700mA indefinitely) are built into an attractive grey-finished instrument case, provision being made for base or side mounting. Cable entry grommets are mounted in the base of the unit. The choke capacity smoothed output is solid state stabilised against variation in input voltage and output current, and input and output fuses with spares are fitted. The output operates a built-in S.P.C.O. relay to switch for instance an alarm circuit. There is adequate room for other equipment within the ventilated case, which is 12" x 10" x 6" deep.

VELDOYNE MOTOR GENERATORS AND D.C. SPLIT FIELD SERVO MOTORS in stock for various supply voltages.

OVER 300,000 IN STOCK!
Multiway and R.F. Connectors
 by twenty different companies!
 Send us your detailed requirements quoting Nato numbers if known. We are now on TELEX.

AERIAL DIRECTION INDICATING KIT
 This set comprises a pair of Magslips to provide remote indication of aerial azimuth and comprises a transmitter and receiver. The transmitter is directly coupled to the remote aerial and the receiver can be mounted at the control point, to provide immediate and continuous indication of aerial position. Supply voltage required is 50v, 50Hz and the price £6-33. (P.Pd.) including a pointer for the receiver. The suggested use of these items would include a mains operated, geared motor to drive the aerial, controlled from the position to which is fed back position information by the magslip link. Transformers to provide 50v 50Hz from 240v A.C. £2-15 each. (P.Pd.). Both +10% V.A.T.


MIL SYNCHROS AVAILABLE EX-STOCK
 In sizes 08, 11, 15, 16, 18 and 23 for 50, 60 and 400 Hz operation.
Synchro Control Transformers
 Synchro Control Transmitters
 Synchro Torque Transmitters and Receivers
 Synchro Resolvers

PLESSEY GROUND BASED U.H.F. GROUND/AIR TX/RX FOR EXPORT ONLY OR SALE TO LICENSED USERS.
 This equipment comprises:
 Single Channel Receiver 5820-99-932-5694.
 Single Channel Transmitter 5820-99-932-5688.
 Single Channel Amplifier 5820-99-932-5701.
 Power Unit for Amplifier 5820-99-932-5700.
 Cooler Unit 5820-99-932-3995.
 These assemble into a free standing rack unit providing U.H.F. communications over 225.0 to 399.9MHz, the TX/Amplifier unit giving 100 Watts R.F. output into 50 Ohms. We have sufficient of these units to form 12 complete installations with a number of spare sub-units. All are guaranteed new and unused. Full details on request.

GAS CHROMATOGRAPHY RESEARCH OVEN PV4051/4056
 A large capacity oven of low thermal mass for use between 35 and 350°C. Provides a forced air circulating system yielding 1000 changes of air per min. The oven has forced air cooled outer surfaces when the internal temperature is high. 210-250V, 50Hz, 2.6KW, £28.60. (C. Pd. England and Wales).

GAS CHROMATOGRAPHY OVEN/ANALYSER UNIT PV4050/4055
 A somewhat smaller unit than the previous item for use between 35 and 500°C. 600 changes per min. with cooled outer surface. Internal dimensions 20cm x 18cm high x 20cm deep. Max. heating rate 50-400°C in 6 mins. Max. cooling rate 400°C to 100°C in 4 mins. 210-250V, 50Hz, 2.6KW, £22.00. (C. Pd. England and Wales).
 Details of these three and other gas chromatography items are available—price 25p (C.W.O. only) refundable on making first purchase.

IONISATION AMPLIFIER PV4075
 A modern high grade low noise solid state amplifier to feed a potentiometric recorder. 18 Input ranges from 10⁻¹⁴ to 5 x 10⁻⁷A with 5 outputs of 1mV to 100mV. Linearity 0.1% f.s. Noise less than 0.5% f.s. at max. sensitivity. Back off facility. Dimensions 28 x 10 x 43 cm deep. With operating information £27.50. (C. Pd. U.K.)



DRY REED INSERTS
 Overall length 1.85" (Body length 1.1")
 Diameter 0.14" to switch up to 500 mA at up to 250V D.C. Gold clad contacts, 6p per doz.; £4-12 per 100; £30-25 per 1,000; £275 per 10,000. All carriage paid U.K.
 Heavy duty type (body length 2") diameter 0.22" to switch up to 1A. at up to 250V A.C. Gold clad contacts, £1-37 per doz.; £6-88 per 100; £52-25 per 1,000; £495 per 10,000. Changeover type £2-75 per doz. All carriage paid U.K.
 Operating Magnets 61p per doz.; £4-40 per 100; £38-50 per 1000. All carriage paid.

ELECTRONIC ORGAN DIVIDER BOARDS built to high industrial/computer spec. 5 octave set £15. Complete with connection data and oscilloscope details.

COPPER LAMINATE P.C. BOARD
 8 1/2 x 5 1/2 x 1/16 in. 12 1/2 p sheet, 5 for 50p
 11 x 6 1/2 x 1/16 in. 15p sheet, 4 for 50p
 11 x 8 x 1/16 in. 20p sheet, 3 for 50p
 16 1/2 x 4 x 1/16 in. (Fibreglass), 30p sheet.
 Offcut pack (smallest 4 x 2 in.) 50p 300 sq. in.
 P&P single sheet 4p. Bargain packs 10p

SPEAKERS AND CABINETS
E.M.I. 13 x 8 in. (10 watt) with two tweeters and cross-over 3/8/15 ohm models. £3-75. P.P. 25p.
E.M.I. 20 watt (13 x 8 in.) with single tweeter and "X-over" 20 Hz to 20,000 Hz. Ceramic magnet 11,000Gss. £8. P.P. 40p. 20 watt base unit only. £6. P.P. 40p.

CABINETS for 13 x 8 in. speakers manufactured in 1/2 in. teak-finished blockboard. Size 14 x 10 1/2 x 9 in. £5 ea. P.P. 40p.
20W. CABINET. 18 x 11 x 10 in. £6. P.P. 50p.

PRECISION A.C. MILLIVOLTMETER (Solartron) 1.5m.v. to 15v; 60db to 20db, 9 ranges. Excellent condition. £22.50. P.P. £1-50.

HIGH CAPACITY ELECTROLYTICS
 2,200µf, 100v. (1 1/2 x 4in.) 60p. 3,150µf, 40v. (1 1/2 x 4in.) 20p. 10,000µf, 25v. (1 1/2 x 4in.) 60p. 10,000µf, 100v. (2 1/2 x 4in.) £1. 12,000µf, 40v. (2 x 4in.) 75p. 16,000µf, 16v. (2 x 4in.) 60p. 21,000µf, 40v. (2 1/2 x 4in.) £1. Post and packing 5p.

MINIATURE UNISELECTORS (A.E.I. 2203A.), 3 bank, 12 position, non-bridging wipers. £4-25 ea. Brand new. Complete with base.

CD-1220 OSCILLOSCOPE, with dualtrace Plug-in. (CX1257) DC-24MHz. £125.
 Wide band Plug-in (CX1256) DC-40MHz, £25.

SOLARTRON OSCILLATOR (CO546) 25Hz-500KHz £50.
OVERLOAD CUT-OUTS. Panel mounting (1 1/2 x 1 1/2 x 1/2 in.) 800 M/A/1.8 amp/10 amp. 35p ea. P.P. 5p.

BULK COMPONENT OFFER. Resistors/Capacitors. All types and values. All new modern components. Over 500 pieces £2. (Trial order 100cps. 50p.) We are confident you will re-order

TWIN STABILISED POWER SUPPLIES (A.P.T.) +80v. @ 500 M/A. -80v @ 500 M/A (9 x 6 x 5 1/2 in.) New. £8-50 with spec. & circuit.

U.K. ORDERS 10% V.A.T. SURCHARGE

HIGH-SPEED MAGNETIC COUNTERS. 4 digit (non reset) 24v. or 48v. (state which) 4 x 1 x 1 in. 40p. P.P. 5p.



5 digit (non-reset) 6-12-24-48v. (state which) 75p. P.P. 5p.
 5 digit (Reset) 12v. £3. P.P. 5p.

TRANSFORMERS

L.T. TRANSFORMER. Prim. 240v. Sec. 24v. 1 1/2 amp. £1. P.P. 20p.
250 WATT ISOLATION TRANSFORMER. 240v. double wound. £3-25. P.P. 50p.
E.H.T. TRANSFORMER. Prim. 240v. Sec. 2.5-0-2.5 kV. 12 mA.; 7.5v. 1 amp. 2.5v. 2 amp. £2-50. P.P. 25p.
E.H.T. TRANSFORMER. Prim. 240v. Sec. 1800v. 50 mA. £2-50. P.P. 25p.
L.T. TRANSFORMER. (Shrouded) Prim. 200/250v. Sec. 20/40/60v. 2 amp. £2 ea. P.P. 40p.
L.T. TRANSFORMER (CONSTANT VOLTAGE). Prim. 200/240v. Sec. 1. 50v. at 2 amp. Sec. 2. 50v. at 100 mA £3. P.P. 50p.
L.T. TRANSFORMER. Prim. 110/240v. Sec. 2x32v. @ 4 amp. 20v. @ 5 amp.; 15v. @ 1.5 amp.; 7v. @ 2.5 amp. £3. P.P. 50p.
L.T. TRANSFORMER. Prim. 220/240v. Sec. 13v. 1.5 amp. 65p. P.P. 15p.
L.T. TRANSFORMER. Prim. 115/240v. Sec. 10-5v. at 1 amp. c.t. 28-0-28v. at 2 amp. shrouded type. £2. P.P. 40p

2500 watt. ISOLATION TRANSFORMER (CONSTANT VOLTAGE). Prim. 190-260v. 50Hz. Sec. 230v. at 10-9 amps. £30. Carr. £2.

H.D. STEP-DOWN TRANSFORMER. Prim. 200/240V Sec. 117v. at 19-8 amps. (2,300 watt). £22-50. Carr. £2.

H.T. TRANSFORMERS. Prim. 200/240V. Sec. 300-0-300v. 80 mA. 6.3v. c.t. 2 amp. £1-50 P.P. 40p. 350-0-350v. 60 mA. 6.3v. c.t. 2 amp. £1-50 P.P. 25p.

STEP-DOWN TRANSFORMERS: Prim. 22/240V. Sec. 115v. Double wound 500w. £5. P.P. £1. 700w. (with filters) £10. P.P. £1. 500w. (metal cased with socket output) and overload protection. £6-50.

AUTO-WOUND. 75W. £1. P.P. 25p. 300W. £1-50. P.P. 50p 750W. £6. P.P. £1.

L.T. TRANSFORMER. Prim. 110/240v. Sec. 0/24/40v. 1-5A. (Shrouded type). £1-50. P.P. 25p.

HT/LT TRANSFORMER Prim. 240v. (tapped) Sec. 1. 500-0-500v. 150 mA. Sec. 2. 31v. 5 amp. £2-75 P.P. 50p.

AUTOMATIC VOLTAGE STABILISER. (Claude Lyons) Input: 190-260v. Output 240v. ±15%. 12-4 K.V.A. £60.

PRECISION CAPACITANCE JIGS. Beautifully made with Moore & Wright Micrometer Gauge. Type 1. 18.5p. to 1.220pF £10 each Type 2. 9.5p. to 11.5pF. £6 each.

MULTICORE CABLE (P.V.C.).
 6 core (6 colours) 3 screened, 14/0048. 15p. yd. 100 yds. £12-50.
 24 core (24 colours) 20p. yd. 100 yds. £17-50.
 30 core (15 colours) 22p. yd. 100 yds. £18-50.
 34 core (17 colours) 25p. yd. 100 yds. £20.
 Minimum order 10 yds.

TELEPHONE DIALS (New) £1 ea.

RELAYS (G.P.O. '3000'). All types. Brand new from 37 1/2p ea. 10 up quotations only.
EXTENSION TELEPHONES (Type 706) New/Boxed. £5. 50p.
RATCHET RELAYS. (310 ohm) Various Types 85p. P.P. 5p.
UNISELECTORS (Brand new) 25-way 75 ohm. 8 bank 1/2 wipe £3-25. 10 bank 1/2 wipe £3-75. Other types from £2-25.



BLOWER FANS (Snail type) Type 1: Housing dia. 3 1/2 in. Air outlet 1 1/2 x 1 in. £2-25 P.P. 25p. Type 2: Housing dia. 6 in. Air outlet 2 1/2 x 2 1/2 in. £4. P.P. 50p. Both types 115/240v. A.C. (brand new).

"PAPST TAPE" MOTORS. (LZ. 20.50) New Boxed. £2. P.P. 25p.

RELAYS
SIEMENS/VARLEY PLUG-IN. Complete with transparent dust covers and bases. 2 pole c/o contacts 35p ea; 6 make contacts 40p ea.; 4 pole c/o contacts 50p ea. 6-12-24-48v types in stock.

12 VOLT H.D. RELAYS (3x2x1 in.) with 10 amp. silver contacts 2 pole c/o 40p ea.; 2 pole 3 way 40p. P.P. 5p.

24 VOLT H.D. RELAYS (2x2x2 1/2 in.) 10 amp. contacts. 4 pole c/o. 40p ea. P.P. 5p.

240V. A.C. RELAYS. (Plug-in type), 3 change-over 10 amp. contacts. 75p (with base). P.P. 5p.

SUB-MINIATURE REED RELAYS (1 in. x 1/2 in.) Wt. 1/2 oz. 1 make 3/12v. 40p. ea.

SILICON BRIDGES. 100 P.I.V. 1 amp. (3/4 x 1/2 x 1/2 in.) 30p. 200 P.I.V. 2 amp. 60p.

24 VOLT A.C. RELAYS (Plug-in). 3 Pole Change-over 60p. 2 Pole Change-over 45p.

PATRICK & KINNIE
 191 LONDON ROAD · ROMFORD · ESSEX
 ROMFORD 44473 RM7 9DD

TEKTRONIX STORAGE SCOPE type 564 with Time base and Y amplifier plug-ins £400. plug-in £250; with CA plug-in £280.

TEKTRONIX 545A Oscilloscope with L plug-in £250; with CA plug-in £280.

TEKTRONIX 526 Vectorscope £375.

TEKTRONIX 529 Waveform monitor £320.

TEKTRONIX 536 oscilloscope with T & CA plug-ins £325.

TEKTRONIX 524D OSCILLOSCOPE Works well but old £60.

TEKTRONIX 524D OSCILLOSCOPE. Exceptional condition. Designed for Colour TV £120.

TEKTRONIX RM17 OSCILLOSCOPE £130.

TEKTRONIX TIME MARKERS type 181 £35.

ROHDE & SCHWARZ SYNTHESIZER Model BN 444462. 30 HZ to 30 MHz. Size 30 X 23 x 17in. MUST GO. £175.

ROHDE & SCHWARZ DIAGRAPH Model ZDD BN 3562. Frequency 300-2400 MHz. In Fine Condition. This difficult to shift item priced to move at £75.

ROHDE & SCHWARZ VIDEOSCOPE BN 424101/2 £750.

ROHDE & SCHWARZ Analyser BN 48302 £175.

AMERICAN SWEEP GENERATOR type 452. Covers from 5 to 100 MHz. Has built in display and 101 DB Push Button RF Attenuator in one DB steps, plus Calibrated Marker Generator covering 5 to 100 MHz continuous. American Government Contract, so quality is high. Supplied for 240V 50 Hz operation with plugs and leads. Size 13½ x 9½ x 19in. Price £70 each. Carriage £1-50.

AMERICAN SWEEP GENERATOR type TRM 3 15 to 400 MHz. £300.

AMERICAN POWER UNITS STANDARD 240V 50 HZ Input 28V 40 AMP OUTPUT. Size 22 x 16 x 9in. Supplied in original transit case £25.

AMERICAN AM GENERATOR type 497. 4 to 400 MHz. Supplied with leads, etc., for 240V 50 HZ operation £35.

POLARAD GENERATORS MODEL MSG 2, 2150-4600 MHz and Model MSG 34, 4200-11,000 MHz. The pair £130 or £75 each.

SPECIAL WM 16 Oscilloscope. Dual Timebase. 5in. tube Main frame 40 MHz. Supplied with one single trace plug-in type 7/1, 7/5, 7/6. At give away price of £45. Tested, working.

***STILL at £42-50**
Solartron CD 711S.2 Double Beam Oscilloscope DC—9 mc/s; 3 mv/cm; trigger delay; crystal calibrator; 4" flat faced tube. In good working condition. Carr. £1-50.

SOLARTRON CD 523 Single Beam Oscilloscope 3db at 10 MHz; 1mV max sensitivity. DC coupled down to 1 vol. 4in. flat faced PDA tube. TB from 1 secs. per cm. to 0.1 microsecs. per cm. plus times 9 expansion £50.

MARCONI TF 144H GENERATOR. In Very Good Condition £120.

MARCONI TF 195M-0/40 KHZ Sine Wave Generator 0/40 Volts output Metered. These must go £7-25.

MARCONI TF 801A AM GENERATOR 10 to 310 MHz £45.

MARCONI TF 801B. AM SIGNAL GENERATOR. 12 to 470 MHz. In good working condition £90.

MARCONI TF 867 GENERATOR £90.

MARCONI TF 938 (CT44). Absorption Wattmeter 10mW to 6 Watts. Input impedance 2.5 ohms to 20K ohms. Freq. response flat at 20KHZ. Calibrated in volts and db. 5in. mirror backed meter £9-50. P. & P. 75p.

MARCONI VVM TF 1041 £22-50.

MARCONI VVM TF 1041B £30.

MARCONI TF 1066/2. AM Generator 450-1200 MHz £140.

MARCONI VVM TF 1300. Measures AC 50MV to 100V, 20 HZ to 300 MHz, DC 100MV to 300V. Ohms 50 to 5 Meg Ohm. In fine condition £17.

AVO TRANSISTOR AND DIODE TESTER TYPE CT 537. In superb condition, in original crates with full instructions, circuit diagram, etc. New price £250 Plus. **OUR PRICE £40 ea.** Carr. £1-25.

BRANDENBURG EHT P/U 0/30KV £55.

EDDYSTONE 770 U. UHF RECEIVER £80.

RACAL RA17 RECEIVER £230.

TELEQUIPMENT S51 Rack Mount Oscilloscope £35.

SOLARTRON VF 252. Millivolt meter £20.

HEWLETT PACKARD SIGNAL GENERATOR MODEL 608B £70.

TELONIC 100 to 250 MHz Sweep Generator. Up to 4 watts output £120.

SURFACE PROFILE MONITOR by G. V. PLANNER type SPM 10 with recorder unit. MINT £140.

SLOPED CASES size 9 x 7in. with 8in. slope, 15in. long, in Hammer Grey. Brand New boxed £1. Packing and postage 37p.

BRAND NEW AMERICAN HIGH VOLTAGE CAPACITORS. 0.15mfd 120KV working. £20 each. Carriage at cost.

MODERN TELEPHONES type 706. Two tone grey, £3-75 ea. The same but black, £2-75 ea. P. & P. 25p ea.

Also **TOPAZE YELLOW** £4-50 ea. P. & P. 25p.

STANDARD GPO DIAL TELEPHONE (black) with internal bell, 87p ea. P. & P. 50p. Two for £1-50. P. & P. 75p.

All telephones complete with bell and dial.

POTENTIOMETERS

COLVERN 3 watt. Brand new, 5; 10; 25; 500 ohms; 1; 2-5; 5; 10; 25; 50k all at 13p ea.

MORGANITE Special Brand new, 2-5; 10; 100; 250; 500K; 1 in. sealed, 17p ea.

BERCO 2½ Watt. Brand new, 5; 10; 50; 250; 500 ohms; 1; 2-5; 5; 10; 25; 50K all at 15p ea.

STANDARD 2 meg. log pots. Current type 15p ea.

INSTRUMENT 3 in. Colvern 5 ohm 35p ea.; 50k and 100K 50p ea.

BOURNS TRIMPOT POTENTIOMETERS. 10; 20; 50; 100; 200; 500 ohms; 1; 2; 2-5; 5; 10; 25K at 35p ea. ALL BRAND NEW.

RELANCE P.C.B. mounting: 270; 470; 500 ohms; 10K at 35p ea. ALL BRAND NEW.

ALMA precision resistors 100K; 400K; 497K; 998K; 1 meg—0.1% 27p ea.; 3-25k, 5-6k, 13k-0.1% 20p ea.

MULLARD ELECTROLYTICS
2200MFD 100V 10A (50°C)
BRAND NEW BOXED
70p each
10 off — 60p each
100 off — 45p each

RELAYS

S.T.C. Sealed 2 pole c/o 700 ohms (24V), 15p ea. 2,500 ohm (okay 24V) 13p ea. 6800 ohm coil 15p each.

POTTER & BRUMFIELD 24V 4 pole c/o min relays. Clear Plastic. Brand New. 50p ea. P. & P. 10p.

Varley VP4 Plastic covers 4 pole c/o 5K—30p ea. 15K—33p ea.

CARPENTERS polarised Single pole c/o 20 and 65 ohm coil as new 37p each. 14 ohm coil 33p each. 45 ohm coil 33p each.

TRANSFORMERS. All standard inputs.

STEP DOWN ISOLATING trans. Standard 240V AC to 55-0-55V 300W, £3 ea. P. & P. 35p.

Neptune Series. Multi 6-3 volts to give 48V at 3-5 amps etc. £3-50 incl. P. & P.

Large quantity LT, HT, EHT transformers and chokes.

3 TYPES ALL BRAND NEW HIGH QUALITY

(1) 3V 9 amp, 6V 9 amp, 12V 9 amp. Size 3½ x 4 x 5½in. £2 each. Packing and postage 47p.

(2) As above but 5-4 amp. Size 3½ x 3½ x 4½in. £1-50 each. Packing and postage 37p.

(3) 3V 1-8 amp, 9V 1-8 amp, 27V 1-8 amp. Size 3 x 3½ x 4½in. £1-50 each. Packing and postage 37p.

All above 3 types also have 0-17V ½ amp and 17-0-17 ½ amp. All windings are separate.

COLVERN TEN TURN POTS, ex eq. 100K at 60p each. Complete with dial £1-50 each. P. & P. 15p.

CAPACITOR PACK 50 Brand new components only 50p. P. & P. 17p.

POTS 10 different values. Brand new. 50p. P. & P. 17p.

COMPONENT PACK consisting of 5 pots various values, 250 resistors ½ and ¼ watt etc., many high stabs. All brand new. Fine value at 50p per pack. P. & P. 17p.

DELIVERED TO YOUR DOOR 1 cwt. of Electronic Scrap chassis, boards, etc. No Rubbish. FOR ONLY £3-50. N. Ireland £2 extra.

LOOSE LEAF BUNDERS. Blue plastic cover, 4 ring. Standard size. 4 for £1. P. & P. 35p. 25 for £5. Carr. £1.

P.C.B. PACK S & D. Quantity 2 sq. ft.—no tiny pieces 50p plus P. & P. 20p.

FIBRE GLASS as above £1 plus P. & P. 20p.

5 CRYSTALS 70 to 90kHz. Our choice, 25p. P. & P. 15p.

MOTOR, min. synchronous, size 1½ x 2 x 6in., 240V Operation 3-6 rpm, 25p each. P. & P. 5p.

TRIMMER PACK, 2 Twin 50/200 pf ceramic; 2 Twin 10/60 pf ceramic; 2 min strips with 4 preset 5/20 pf on each; 3 air spaced preset 30/100 pf on ceramic base. ALL BRAND NEW 25p the LOT. P. & P. 10p.

GRATICULES. 12 cm. by 14 cm. in High Quality plastic. 15p each. P. & P. 5p.

PANEL mounting lamp holders. Red or green. 9p ea. Miniature. **PANEL** mounting lamp with holders—10V 15MA 5p ea.

BECKMAN MODEL A. Ten turn po complete with dial. 100K 3% Tol 0.25%—only £2-13 ea.

FIBRE GLASS PRINTED CIRCUIT BOARD. Brand new. Single sided up to 2½" wide x 15" 3p per sq. in. Larger pieces 1p per sq. in. Double sided. Any size 1p per sq. in. Postage 10p per order.

INTEGRATED CIRCUIT test clip by AP inc. Gold Plated clip-on. Brand New individually boxed. £1-00 ea. P. & P. 10p.

DECADE DIAL UP SWITCH—5 DIGIT. Complete with escutcheon. Black with white figures. Size 4in. long x 1in. high x 1½in. deep. Ex-Plessey. £1-40 each. P. & P. 15p.

LIGHT EMITTING DIODES (Red) from Hewlett-Packard. Brand New 38p ea. Holder 1p ea. Information 5p.

FIVE moving coil meters £2 P. & P. 37p.

VISCONOL EHT CAPACITORS

Size 1x2½ ins.

0.05mfd 2.5kV 50p ea.
0.01mfd 5kV 40p ea.
0.001mfd 10kV 50p ea.

Size 2½x6½ ins.

0.05mfd 8kV 50p ea.

Size 1½x5½ ins.

0.01mfd 10kV 50p ea.
0.002mfd 15kV 65p ea.
0.0005mfd 20kV 60p ea.
0.1mfd 4kV 35p ea.

DUBILIER 0.1mfd 5 KV; 0.1mfd 7.5 KV; 0.25mfd 7.5 KV; 0.5mfd 5 KV all at 50p ea. P. & P. 15p.

PHOTOCELL equivalent OCP 71. 13p ea. Photo-resist type Clare 703. (TO5 Case). Two for 50p.

MULLARD OCP70 10p each.

MAKE YOUR SINGLE BEAM SCOPE INTO A DOUBLE WITH OUR NEW LOW PRICED SOLID STATE SWITCH. 2 HZ to 8 MHz. Hook up a 9 volt battery and connect to your scope and have two traces for ONLY £5-50. P. & P. 25p.

STILL AVAILABLE our 20 MHz version at £9-25. P. & P. 25p.

20HZ to 200KHZ SINE AND SQUARE WAVE GENERATOR

In four ranges. Wien bridge oscillator thermistor stabilised. Separate independent sine and square wave amplitude controls. 3V max sine, 6V max square outputs. Completely assembled P.C. Board, ready to use. 9 to 12V supply required. £7.35 each. P & P 25p. Sine Wave only £5.35 each. P & P 25p.

TRANSISTOR INVERTER

12V to 1.5 KV 2MA. Size 1½ x 2½ x 4in. Multi tapped secondary and output level control makes possible large range of voltage and current output combinations without modification. Very flexible unit at £2-95 each. P. & P. 25p.

NEW WIDE RANGE WOBBLULATOR

5 MHz to 150 MHz (Useful harmonics up to 1.5 GMZ) up to 15 MHz sweep width. Only 3 controls, preset RF level, sweep width and frequency. Ideal for 10-7 or TV IF alignment, filters, receivers. Can be used with any general purpose scope. Full instructions supplied. Connect 6-3V AC and use within minutes of receiving. All this for only £5-75. P. & P. 25p. Suitable miniature transformer for 240 Volt operation £1-25.

Unless stated—please add £1-50 carriage to all units.

VALUE ADDED TAX not included in prices—please add 10%

Official Orders Welcomed, Gov./Educational Depts., Authorities, etc., otherwise Cash with Order

Open 9 am to 6.30 pm any day (later by arrangement.)

CHILTM EAD LTD

7/9 ARTHUR ROAD, READING, BERKS. (rear Tech. College, Kings Road) Tel.: Reading 582605/65916

Samson's

(ELECTRONICS) LTD.

9 & 10 CHAPEL ST., LONDON, N.W.1
01-723 7851 01-262 5125

CURRENT RANGE OF BRAND NEW L.T. TRANSFORMERS FULLY SHROUDED (excepted) TERMINAL BLOCK CONNECTIONS. ALL PRIMARIES 220/240v.

Type No.	Sec.	Volt Taps.	Amps.	Price	Carr.
1A	25-33-40-50	..	15	£13.00	75p
1B	25-33-40-50	..	10	£11.00	50p
1C	25-33-40-50	..	5	£7.75	50p
1D	25-33-40-50	..	3	£7.75	50p
2A	4-16-24-32	..	12	£8.75	50p
2B	4-16-24-32	..	8	£7.60	50p
2C	4-16-24-32	..	4	£4.75	40p
2D	4-16-24-32	..	2	£3.20	30p
3A	24-30-36	..	10	£8.25	60p
3B	24-30-36	..	5	£6.25	40p
3C	24-30-36	..	2	£3.25	30p
4A	12-20-24	..	20	£10.95	75p
4B	12-20-24	..	10	£6.50	40p
4C	12-20-24	..	5	£4.35	30p
5A	3-12-18	..	20	£9.76	50p
5B	3-12-18	..	10	£6.00	45p
5C	3-12-18	..	5	£4.10	35p
6A	48-56-60	..	2	£4.10	35p
6B	48-56-60	..	1	£3.00	30p
7A	6-12	..	20	£7.50	50p
7B	6-12	..	10	£4.10	40p
7C	6-12	..	5	£2.75	30p
8A1	12-24-1	..	1	£2.10	25p
9A1	17-32-1	..	8	£7.00	45p
10A1	9-15-1	..	2	£2.10	25p
11A1	6-31	..	15	£4.10	30p

Note: By using the intermediate taps many other voltages can be obtained.

Example: No. 1 .. 7-8-10-15-17-25-33-40-50v.1
No. 2 .. 4-8-12-16-20-24-32v.
No. 5 .. 3-6-9-12-15-18v.

30-25-0-25-30v. 2a. with Screen £4.30, carr. 35p 36-0-36v. 5a. £9.40, carr. 50p. As recommended for Linsley Hood Amplifiers. 1

HEAVY DUTY UNSHROUDED TYPE 9 INCH FLYING LEADS ALL PRIMARIES 240v.

Type No.	Sec.	Volt Tap.	Amps.	Price	Carr.
1	24-30-36	..	20	£11.00	75p
2	12-20-24	..	30	£13.00	75p
3	3-12-18	..	30	£13.00	75p
4	6-12	..	50	£14.00	75p
5	20	..	30	£12.00	75p

DAVENSET ISOLATION TRANSFORMERS
Pri. 10-0-200-220-240v. Sec. 240v. Centre tapped 1.2kva. Conservatively rated. Size 8½ x 7 x 8½ ins. Wgt. 59 lbs. Open frame type, terminal connections. Fraction of maker's price. £17.00 carr. £1.00.

STEP DOWN 240/110v. AUTO TRANSFORMERS FOR AMERICAN EQUIPMENT. Fitted with 2 or 3 pin American sockets. All sizes from 80 to 2½kva. available. Send s.a.e. for list. American sockets, plugs, adaptors also available.

T.E.C. HEAVY DUTY ISOLATION TRANSFORMERS
Pri. 240v. Sec. 150v. 4kva. Size 9 x 8½ x 7 ins. Wgt. 70 lbs. £22.50 carr. £2.00.

RICH AND BUNDY. Pri. 220-230-240-250v. Sec. 265-270-275v. 1400 watts. Conservatively rated. Size 8 x 8 x 7 ins. Terminal block connections. £17.00 carr. £1.00.

440 VOLT S.P. TRANSFORMERS
No. 1 T.E.C. Pri. 380-400-415-440v. Sec. 33 60 amps. Size 9 x 9 x 8 ins. Terminal block connections. Conservatively rated. £20.00 carr. £2.00. No. 2 Davenset. Pri. 415-440-525v. Sec. 220v. 2kva. Size 9 x 8½ x 8 ins. £23 carr. £2.00. No. 3 Davenset. Pri. 380-400-415-440v. Sec. 110v. 6 amps. Size 6 x 6½ x 5½ ins. £8.50 carr. £1. No. 4 Davenset. Pri. 380-400-417-437v. Sec. tapped 110-270v. 0-15kva. Size 7 x 5½ x 5 ins. £6.50 carr. 75p. No. 5 Rich and Bundy. Pri. 380-400-420-440v. Sec. 240v. 40 watts. Size 4 x 4 x 4 ins. Terminal block connections. £2.50 carr. 50p. Drake. Pri. 440v. Sec. 220-240v. 100 watts. Shrouded. £3.25 postage 40p.

H.T. SMOOTHING CHOKES
Parmeko potted types. 5h. 500mA. £3.00 carr. 50p. 10h. 300mA. £2.00 carr. 30p. 10h. 180mA. £1.50 carr. 30p. 15h. 180mA. £2.00 carr. 50p. Swinging type 5h. 0.4a. 4h. 0.25a. £1.50 carr. 35p. 10h. 120mA. 75p carr. 25p. 15h. 75mA. 10h. 75mA. 50h. 25mA. 50p carr. 20p.

PARMEKO ISOLATION TRANSFORMERS
Pri. tapped. 100-110-200-220-230-240-250v. Sec. 115v. 13-5 amps. Conservatively rated, fully shrouded. Table top connections. Size 13 x 10 x 8½ ins. £32.50 carr. £2.00. Pri. tapped 200-210-220-230-240-250v. Sec. tapped 90-100-110-120v. 7-5 amps. Conservatively rated table top connections. Size 9 x 8 x 8 ins. £22.50 carr. £1.50.

ADVANCED COMPONENTS CONSTANT VOLTAGE TRANSFORMERS
Input 190-260v. Output 230v. 150 watts. Type 140A £7.00 carr. 75p. Output 28v. 8 amps open frame type £4.50 carr. 75p. Output 4v. 3 watts 75p carr. 25p. Output 240v. 30 watts enclosed type £1.50 carr. 35p.

SMITHS 12v. D.C. VEHICLE HEATER MOTORS
3 dia. length 4 ins. Spindle ½. Length 1½ ins. Very powerful £1 carr. 25p. With 8½ in. fan £1.25 carr. 25p. As above with twin turbo fans £1.50 carr. 35p.

CRESSALL TORVOLT VARIABLE TRANSFORMERS
Input 115v. Output 0-130v. 1.25 amp. Complete with calibrated dial and control knob. Size 2½ x 3½ ins. dia. £3.00 carr. 25p. Brand new.

VAT PLEASE ADD 10% TO ALL ORDERS. INC. CARR./PACKING.

WE HAVE OVER 3,000 SURPLUS HT AND LT TRANSFORMERS IN STOCK. ALSO A LARGE SELECTION OF HT AND LT CHOKES. FRACTION OF MAKER'S PRICE. LET US KNOW YOUR REQUIREMENTS.

AMOS 'C' L.T. TRANSFORMERS
Primaries 220-240v. Sec. 17.5v. 6a. £2.00 pp. 35p. Sec. 53.6v. 6a. £2.95pp. 40p. 18-0-18v. 5a. £2.95 pp. 40p.

WODEN Primaries 220-240v. Sec. 10v. 2a. fully shrouded £1.25 pp. 25p. Sec. Tapped 6-12v. 2a. fully shrouded £1.50 pp. 25p. 15v. 2a. TWICE OPEN FRAME TYPE. £1.75 pp. 30p.

SPECIAL OFFER OF MULTI TAPPED L.T. TRANSFORMERS VERY CONSERVATIVELY RATED
Gresham Pri. 200-220-240v. Sec. 29-5v. 2-6a. twice. 20v. 5a. twice 15v. 0-1a. four times. 'C' Core. Table top connections £8.95 carr. 75p.
Pri. 200-220-240v. Sec. 16-3v. 1a. twice. 10v. 1a. twice. 22-5-25-28-30v. 5a. 26-5v. 2-5a. 23-9v. 1a. 6-3v. 2a. 145-0-145v. 200 m/a 'C' Core. Table top connections £4.95 carr. 75p.
Pri. 200-220-240v. Sec. 20-21-22-23-24-25v. 6a. 20-21-22-23-24-25v. 3-5a., 18-19-20-21-22-23v. 2a., 11-12-13-14-16v. 0-5a. twice 100-0-100v. 150 m/a 'C' Core. T. top connections. £7.25 carr. £1.

PARMEKO H.T. TRANSFORMERS NEPTUNE POTTED TYPE
Type 1. Pri. 220-240v. Sec. 250-0-250v. 320mA. 7v. 6 amps. £3.25 carr. 50p. Type 2. Sec. 250-0-250v. 240mA. 6-3v. 10 amps. £2.75 carr. 50p. Type 3. 250-0-250v. 50mA. 6-3v. 1a. £1.25 carr. 35p. Type 4. 350-0-350v. 200mA. 6-4v. 6a. 5v. 3a. £3.00 carr. 50p. Type 5. 630-0-630v. 105mA. 5v. 4a. 5v. 2a. £3.00 carr. 50p. Type 6. 1875v. 60mA. 4-2kV. wkg. and 500v. 31mA. £3.75 carr. 50p. Type 7. Sec. tapped 760-700v. 50mA. 6-3v. 1-5a. £1.75 carr. 35p.

RELAYS
Omron 24v. A.C. or 12v. D.C. 2 7A CO contacts. Size 1½ x 1½ x 1 in. Single hole fixing. 45p. Postage 5p.
Miniature type 6-12v. D.C. 24v. A.C. 1 CO contact. Size 1½ x 1½ x 1 in. S. hole fixing. 35p. Postage 5p.
Keyswitch 240v. A.C. 1 7A CO contact. Size 2 x 1 x 1 ins. S. hole fixing. 45p. Postage 5p.
B and R. 240v. A.C. 3 CO 7A contacts. Size 1½ x 1½ x 1½ ins. S. hole fixing. 60p. Postage 5p.
Robinsons. 240v. A.C. 2 5A CO contacts. Size 2½ x 1½ x 1½ ins. S. hole fixing. 50p. Postage 5p. Special terms for qty. of 25.

WEYRAD

COILS AND I.F. TRANSFORMERS IN LARGE-SCALE PRODUCTION FOR RECEIVER MANUFACTURERS

- P.11 SERIES** 10 mm. x 10 mm. x 14 mm. Ferrite cores 3 mm. 472 kc/s operation. Single-tuned I.F.s and Oscillator Coils.
- P.55 SERIES** 12 mm. x 12 mm. x 20 mm. Ferrite cores 4 mm. 472 kc/s operation. Single-tuned I.F.s and Oscillator Coils.
- T.41 SERIES** 25 mm. x 12 mm. x 20 mm. Ferrite cores 4 mm. 472 kc/s operation. Double-tuned 1st and 2nd I.F.s and Single-tuned 3rd I.F. complete with diode and by-pass capacitor.

These ranges are available to manufacturers in versions suitable for most of the popular types of Transistors. The Oscillator coils can be modified to enable specific tuning capacitors to be used provided that bulk quantities are required.

OUR WINDING CAPACITY NOW EXCEEDS 50,000 ITEMS PER WEEK

On the most up-to-date and efficient machines backed by a skilled assembly labour force for all types of coils and assemblies.

WEYRAD (ELECTRONICS) LIMITED, SCHOOL ST., WEYMOUTH, DORSET

G. F. MILWARD

ELECTRONIC COMPONENTS

Wholesale/Retail: **369 Alum Rock Road, Birmingham B8 3DR. Tel. 021-327 2339**

Special Offer!!!—From Stock—New—Boxed—AND 60% Discount!

MULLARD ELECTROLYTIC CAPACITORS

071 and 072 Series



Type No.	Working Voltage Vdc.	Capacitance μ F	Max. Ripple Current at 50°C	Weight	Price
071 14472	10	4700	2.5 amps	1oz	15p
071 14682	10	6800	4 amps	1oz	17p
071 15332	16	3300	2.4 amps	1oz	15p
071 15472	16	4700	5.8 amps	1oz	17p
071 15682	16	6800	7.9 amps	1oz	17p
071 15103	16	10000	5.8 amps	1 1/2oz	22p
071 18222	63	2200	5.8 amps	3oz	30p
072 14113	10	11000 + 11000	10.6 amps	3oz	37p
072 14173	10	16500 + 16500	13.4 amps	4oz	49p
072 15752	16	7500 + 7500	10.5 amps	3oz	37p
072 15113	16	11000 + 11000	13.8 amps	4oz	49p
071 16222	25	2200	2.2 amps	1oz	15p
072 16502	25	5000 + 5000	9.6 amps	3 1/2oz	37p
072 16752	25	7500 + 7500	12.6 amps	4 1/2oz	49p
072 17342	40	3400 + 3400	9.1 amps	3 1/2oz	37p
072 17502	40	5000 + 5000	12.0 amps	4 1/2oz	49p
071 18681	63	680	2.1 amps	1oz	15p
072 18172	63	1650 + 1650	7.8 amps	3oz	37p

106 and 107 Series

106 14153	10	15000	7 amps	4oz	57p
106 15103	16	10000	7 amps	2 1/2oz	65p
106 16223	25	22000	17 amps	10oz	£1.12
106 17103	40	10000	12 amps	7 1/2oz	94p
106 18153	63	15000	28 amps	18oz	£1.79
107 10222	100	2200	10 amps	5 1/2oz	74p

Type No.	Voltage	Capacitance	Weight	Price
102 15163	16	16000	8oz	20p
104 90003	20	39000	16oz	30p
102 16802	25	6000	7oz	25p
104 17562	40	5600	5oz	25p
104 90001	45	20000	16oz	50p

A discount of 10% may be deducted from above prices on lots of 100 of any one type.

Please calculate the weight of your order and include appropriate postage.

Not over	Ordinary Parcels
1 1/2lb	16p
2lb	21p
4lb	29p
6lb	37p
10lb	47p
14lb	57p
18lb	67p
22lb	77p



SMALL ELECTROLYTICS

Ref. No.	Capacity μ f	Voltage	Price	Ref. No.	Capacity	Voltage	Price
H8/1		150v	4p	H7/4A	64uf	35v	5p
H8/2	2.2uf	25v	4p	H7/5	80uf	16v	4p
H8/2A	3.3uf	25v	4p	H7/6	100uf	25v	5p
H8/3	3uf	50v	4p	H7/6A	100uf	15v	4p
H8/3A	4uf	50v	4p	H7/7	100uf	25v	4p
H8/4	4.7uf	25v	4p	H7/8	125uf	16v	5p
H8/4A	5uf	64v	4p	H7/8A	100uf	35v	6p
H8/5	5uf	10v	4p	H7/9	100uf	63v	6p
H8/5A	5uf	150v	4p	H7/9A	125uf	4v	4p
H8/6	10uf	10v	4p	H7/10	125uf	25v	6p
H8/6A	10uf	70v	4p	H7/10A	160uf	2.5v	3p
H8/8	16uf	35v	4p	H7/11	160uf	25v	6p
H8/8A	16uf	16v	4p	H7/11A	150uf	16v	5p
H8/9	20uf	6v	2p	H7/13A	200uf	25v	8p
H8/9A	20uf	70v	4p	H7/14	220uf	50v	10p
H8/10	22uf	50v	4p	H7/14A	220uf	16v	6p
H8/10A	22uf	100v	4p	H7/15	220uf	25v	5p
H8/11	25uf	12v	4p	H7/15A	220uf	35v	10p
H8/11A	24uf	275v	4p	H6/1A	250uf	4v	3p
H8/12	32uf	15v	4p	H6/2			
H8/12A	30uf	10v	4p	H6/3A	320uf	2.5v	3p
H8/13	32uf	50v	4p	H6/4	320uf	10v	4p
H8/14	40uf	25v	5p	H6/4A	330uf	16v	5p
H8/14A	40uf	16v	4p	H6/5	330uf	25v	10p
H8/15	47uf	50v	4p	H6/5A	330uf	35v	15p
H8/15A	40uf	35v	4p	H6/7	400uf	15v	5p
H7/1	50uf	10v	3p	H6/8	470uf	25v	10p
H7/1A	50uf	50v	4p	H6/8A	470uf	35v	20p
H7/2	50uf	50v	4p	H6/9			
H7/2A	64uf	2.5v	2p	H6/9A	400uf	40v	20p
H7/3A	64uf	25v	4p	H6/10	750uf	12v	5p
H7/4	64uf	15v	4p	H6/13A	1000uf	25v	16p
				H5/2A	2200uf	16v	15p

NEW! NEW! NEW! NEW!

An aerosol spray providing a convenient means of producing any number of copies of a printed circuit both simply and quickly.

Method: Spray copper laminate board with light sensitive spray. Cover with transparent film upon which circuit has been drawn. Expose to light. (No need to use ultra-violet.) Spray with developer, rinse and etch in normal manner.

Light sensitive aerosol spray £1.00 plus
Developer and Etchant 50p postage

Copper-clad Fibre-glass Board—50p sq. ft. (max. 3' x 4')

NEWER THAN NEW!!!

Fibre Glass Board pre-treated with light-sensitive lacquer enabling you to produce prototype printed circuits within five minutes.

75mm x 100mm	33p
150mm x 100mm	66p
150mm x 200mm	£1.32
250mm x 200mm	£2.20
Epoxy-Resin	
75mm x 100mm	22p
100mm x 150mm	44p
150mm x 200mm	88p

VEROBOARD

2 1/2in x 1in x 0.15in	6p
3 1/2in x 2 1/2in x 0.15in	16p
3 1/2in x 3 1/2in x 0.15in	25p
5in x 2 1/2in x 0.15in	25p
5in x 3 1/2in x 0.15in	30p
17in x 3 1/2in x 0.15in	55p
17in x 3 1/2in x 0.15in	79p
3 1/2in x 2 1/2in x 0.1in	21p
3 1/2in x 3 1/2in x 0.1in	25p
5in x 2 1/2in x 0.1in	25p
5in x 3 1/2in x 0.1in	29p
Spot Face Cutter 38p. Pin Insert Tool 57p.	
Terminal Pins (0-1 or 0-15) 36 for 22p.	

MULLARD POLYESTER CAPACITORS

500,000 in STOCK!!!

.001uf	.0018uf	.0056uf	.015uf
.0012uf	.0022uf	.033uf	
.0015uf	.0027uf	.012uf	.082uf
20p dozen; 75p-100; £5-1,000; £40-10,000			
15uf	18uf	22uf	39uf
20p dozen; £1-100; £6-50-1,000; £50-10,000			

ERIE MONOLITHIC CERAMIC CAPACITORS

3p each; 24p dozen; £1.75 per 100

10pf	68pf	560pf
15pf	100pf	620pf
22pf	150pf	680pf
33pf	220pf	1,000pf
39pf	330pf	
47pf	470pf	

CLEARANCE CORNER

BAGS CONTAINING 1,000 ASSORTED DIODES, SILICON/GERMANIUM/ZENER. UNTESTED, BUT MAINLY O.K.

£1

MIXED COMPONENTS, ALL NEW, UNUSED, RESISTORS, CARBON/WIRE, POTS, DIODES, TRANSISTORS, CAPACITORS, ELECTROLYTIC/PAPER/CERAMIC/SILVER MICA. FANTASTIC VALUE. PRICE PER 2lb. MIXED BOX

£1

RECTIFIERS 1N4007 1200 peak volts, 30 amps peak current, 1 amp mean current. 100 for £7.50, 1,000 £50.

UNREPEATABLE BARGAIN BD112

TO3-NPN DIFFUSED SILICON PLANAR EPITAXIAL. V_{CEO} COLLECTOR TO BASE—80 VOLTS. V_{CE0} COLLECTOR TO EMITTER—60 VOLTS. V_{BE0} EMITTER TO BASE—5 VOLTS. 20 WATTS—2 AMPS—30 MHz. FEATURES HIGH CURRENT GAIN OVER WIDE RANGE OF COLLECTOR CURRENT

25p!
ONLY

REMEMBER! ALL GOODS PLUS 10% V.A.T.

G. F. MILWARD, Drayton Bassett, Tamworth, Staffs. Postage (minimum) per order 15p.

P. F. RALFE

10 Chapel St London N.W.1

Phone 01-723 8753

TELEVISION SWEEP GENERATOR

by Sweep systems type 505. Frequency coverage 450-940MHz. (Channels 15-80). Markers at 465/565/660/750/830 and 900MHz. Attenuated output in eight, five db steps and fine 0-10 db. Sweep width adjustable from 1-15MHz. The instrument is completely solid-state using varactor diodes and transistors throughout. Dims: 19 x 12 x 5ins. Wt.: 20lbs. Supplied in good working order, price **£59.50** + 50p carriage.



AERIAL CHANGE/OVER RELAYS of current manufacture designed especially for mobile equipments, coil voltage 12v., frequency up to 250MHz at 50 watts. Small size only, 2 in. x 1/2 in. Offered brand new, boxed. Price **£1.50**, inc. P.&P.

'ALCAD' Sealed rechargeable Nickel-cadmium batteries. Type W3.5, 1.2V at 3.5 Ah. Size as 'U2'. Offered new in packs supplying 12V, **£15**. Or separately at **£1.25**.

Automatic Constant current electronic battery chargers specially designed for nickel cadmium cells. Metered and fused. Up to twelve cells can be charged up to 750mA, variable 0-750mA. Size 7x6x5ins. Brand new units. Price each **£17**.

Smiths Ltd Weight indicators, self powered, measures 0 to 20 cwts in 1 cwt divisions on a 4" circular meter indicator, 30 feet of cable and heavy duty load cell use with bell crank or actual reading is 5 cwt for F.S.D. brand new units special price **£7.50** post 50p.

Cossor Electronic Invertors type CRA 200. A high quality device for producing a 115v 400HZ single phase output. Incorporating the following features: Input 23-28V D.C.
* Full overload protection.
* Sine wave output.
* Remote control facilities.
* Completely Solid State (Silicon transistors).
* Built to Aircraft specifications.
* 180VA of output continuous.
May be run in series operation for 3 phase requirements. Offered brand new boxed units. Price **£17.50** Carriage 50p.

AUDIO OSCILLATORS

AMERICAN TS-382/U

Covers 20 c/s-200 Kc/s in four ranges. Output voltage 1 micro volt to 10 v. in seven ranges. Built in calibrator. Sine wave O.P. is excellent over complete range. Supplied with transmit case, adaptors and circuits and transformer for 240 A.C. **£20**.

MINIATURE A.E.I. UNISELECTORS 12 position x 3 bank 250 ohm coils, 1 bridging and 2 non-bridging wipers available now—Type 2200A complete with bases. Price **£4**.

BRAND NEW DIGITAL PANEL VOLT METERS

10MV-1.99VV. 199 Measuring points. Input impedance 100Mohm. Automatic zeroing. Measurements: 155mm x 72mm x 72mm. List price was **£52.00**. OUR PRICE **£24.50**.

DIGITAL MEASUREMENT Type 2003 Digital Voltmeter. 3 1/2 Digit display. Measuring up to 1000 Volts. AS NEW **£65**.

Noise Generator Model CT-82

Range 15kHz to 160MHz very useful noise for factor measurements of receivers/wide band I.F. amplifiers etc., the instrument is directly calibrated in noise factor and displayed on panel meter, also output meter calibrated in db, for 115-250 vac operation offered in good used condition, small size low price only **£8 Carr. 50p**.

H. W. SULLIVAN STANDARD AIR SPACED CONDENSERS

Capacitance range 0 to 100 pf fully screened with engraved vernier subdivided into 100 equal divisions complete with vernier index and original manufacturers seal offered brand new, at only **£25** each.

BARGAIN OFFER—LOW VOLTAGE STABILISED POWER SUPPLIES

*Voltage Range 16-24V.

*Current Range to 6 Amps.

*Full over-voltage and Current protection.

*AC Ripple content better than 5mV. These PSUs are constructed to exacting standards and incorporate the very best of components and circuit design for long life and reliability. Employs Silicon transistors, thyristors, C-Core transformer etc. Offered in perfect condition, carefully checked before despatch. List price over **£125**. Our price only **£26.50**. Carriage **£1**.

POWER TUBE BASES for 4X250 T/X Valves etc. BASES ARE BRAND NEW AND BOXED COMPLETE WITH THE CERAMIC CHIMNEY. Only **£3.25** each p.p. 10p.

SCHOMANDL PRECISION FREQUENCY METER TYPE FDI WITH FDMI ADAPTOR

GPO approved equipment for Radio Telephone Marine servicing etc., offered in as new condition with calibration certificate.

G.E.C. Uniselectors, 8-banks, 25 position full wipe. 75 ohm coil. Not new but excellent working condition. Each **£2**.

Brand new GEC 3 banks of 25 position uniselectors with fitted suppressor. **£2.50** each.

SIX Level A.E.I. Uniselectors miniature plug in type 2216A coil 125 ohms. non-bridging wipers with index. 12 position 6 bank. Absolutely brand new in makers cartons sold complete with base. **£6.50**

CAMBRIDGE PORTABLE POTENTIOMETER type 44228. The ideal tool for checking thermocouples and auxiliary temperature measuring equipment. Accuracy $\pm 0.1\%$. BRAND NEW. **£75**.

TINSLEY type 4363D Vernier potentiometer. Good condition Price **£75**.

FRIGIDAIRE, AIR-CONDITIONING UNIT. Table-top model. 4 inch diameter pipe outlet. Complete and ready for use. Price **£125**.

WAYNE KERR type B521 Component bridge. Accurate measurement of LC & R. **£55**. Excellent order throughout.

TEKTRONIX OSCILLOSCOPES

Type 545A with 'CA' plug-in. (Or 'L'). DC—30MHz.

Type 561A with 3A1 and 3B3 units. DC—10MHz.

Type 535 with CA plug-in unit. DC—15MHz.

Type 551. Double-beam with L&G units. DC—27MHz.

Also available:

Dynamco D7100 with 1Y2 and 1X2 plug-ins. Portable, DC—30MHz.

Hewlett-Packard 175A, 1781 and 1755A plug-ins. DC—30MHz.

Marconi TF1300. s/b. DC-15MHz. **£75**.

Roband RO50A with 5G plug-in. DC—15MHz. Price **£125**.

Solartron CD1400. With two CX1441 and a CX1443 units.

Extremely sensitive instrument. Twin differential inputs.



SIGNAL GENERATORS

Marconi type TF801D. 10-485MHz. Excellent.

P.U.R.

Marconi type TF867. 15KHz-30MHz. **£150**.

Hewlett-Packard 616A. 1780-4000MHz. **£75**.

Advance C2H. Spot-frequency production-line test instrument. 12 freqs. in bands 500KHz-30MHz. **£25**.

Rohde & Schwarz U.H.F. 990-1900MHz. P.U.R.

Rohde & Schwarz SMAF. A.M. & F.M. 4-300MHz. FM Dev. 0-100KHz in 2 ranges. Fundamental-frequency generator ideal for radio-telephone test equipment. P.U.R.



MARCONI TEST EQUIPMENT. All items have been calibrated, reconditioned and guaranteed.

Wave Analyser **TF455E**. Frequency range 20Hz. **£105**.

TF893 Audio Wattmeter. Range 20Hz-35KHz. Power range 20uW-10W. Impedance 2.5 Ω to 20K Ω in 48 steps. Direct calibration in Watts and dbm. Price **£45**.

TF2600 Sensitive Valve Voltmeter 1mV f.s.d. to 300V f.s.d. Accuracy $\pm 1\%$. Offered as new, price **£55**.

TF1370A Wide-range oscillator 10Hz to 10Mz. Squarewave up to 100KHz. High output—up to 1MHz 31 Volts. 75,100 or 600 Ω output. List price pre VAT—**£308**. Offered as new at **£125**.

TF2162 MF attenuator. DC-1MHz. 0-111db attenuation in 1db steps. Impedance 600 ohms unbalanced. Price **£50**.

TF2163 U.H.F. Attenuator. DC-1 GHz. 0-142db in 1db steps. Z, 50 ohms. Max. power input 0.5W. As new Price **£75**.

TF801D/1 A.M. Signal Generator up to 470MHz.

TF1106 Noise Generator 1-200MHz. **£75**.

TF1041B Voltmeter. 300mV-300V. 20Hz-1500MHz. **£45**.

TF1301 Noise Gen. 200-1700MHz. 50 ohms. **£55**.

TF1099 20MHz Sweep Generator as new **£75**.

OA1094AHF Spectrum Analyser 100KHz-30MHz. As new.


TF1417 Counter, Frequency Meter 7 digits. Plus range extension unit TF1434/2 to 220MHz. As new.

JERROLD 900B Sweep Generator with SD8A sweep driver unit. V.H.F. and U.H.F. 0-1200MHz. centre frequency. 1, 10 and 100MHz markers. Built-in detector, attenuators etc. This instrument is probably the most comprehensive sweeper ever made. P.U.R.

ADVANCE AUDIO SIGNAL GENERATOR TYPE HI. 15Hz-50KHz in three ranges. Sine/square wave output. Supplied in first-class working condition. **£15**. Carriage **£1** each.

R216 V.H.F. AM/FM Communications receivers. Coverage 19-157MHz. Film scale dial 2 frequency crystal calibrator. Plus all other facilities. Complete with A.C. power supply connecting lead. Supplied in full working order in excellent secondhand condition.


PLEASE ADD 10% V.A.T. TO THE TOTAL AMOUNT WHEN ORDERING. INCORRECT AMOUNTS WILL CAUSE DELAY IN DESPATCH. THANK YOU.



"SLO-SYN" 3-HEAD SYNCHRONOUS STEPPING MOTOR

Type SS15. These fine motors are easily reversed, starting and stopping in less than 5° without electrical or mechanical braking. Simple relay circuit can be applied to give DC., to winding for a maximum holding torque of 300oz/in with 35v at 0.35amps through winding. For AC. (synchronous) operation at 120v., 50Hz. Speed 60 rpm at 60Hz., 72 rpm. STEPPING: Holding torque at 60 steps per second—100 oz/in. Can be wired to give 100 or 200 steps per revolution with accuracy of 0.1° per step non-cumulative. Torque characteristics can be modified by simple R.C. circuits. Dimensions: dia. 4", body length 4 1/2", spindle length 2 1/2" x 1/4" dia. Weight 6 1/2 lbs. BRAND NEW in maker's packing. Offered at less than 1/3 maker's price.

£13.75



FAN/BLOWER

Precision-built in Germany. Dynamically balanced mains unit (200/240) continuous rated reversible 60MA on run. Size: 5 1/2" dia. x 2 1/2" deep. Back plate is tapped for 4 fixing screws (supplied). Well under maker's price at £3. P. & P. 20p. Similar unit to above but 7 1/2" dia. x 3" deep. £4.50. P. & P. 25p.



SMITHS RINGER-TIMER

Reliable 15 minute times, spring wound (concurrent with time setting) 15x1min divisions, approximately 1/2 between divisions. Panel mounting with chrome bezel 3 1/2" dia. £1.30. 15p. P. & P.



GEARED MOTORS

"Parvalux" Reversible 100 rpm geared motor. Type SD14, 230/250V. AC., 22 lb/in. 1/2" spindle. 1st class condition. £7.50 each. 50p P. & P. Also limited number only as above, BRAND NEW. £12.50 each. 50p P. & P.

REVERSIBLE Parvalux type SD19. 240v. AC. 30rpm. 40 lbs/in. Variable angle drive shaft. ABSOLUTELY AS NEW. £6.30. P. & P. 50p.

SHADED POLE Mains motor. 1 1/2" x 1 1/2" x 2" high. Double ended 1/2" shaft projecting 1/2" each side of motor. £1. P. & P. 20p.

OPEN FRAME GEARED MOTORS

(Dural gear case) 240 AC., 28rpm. NEW HIGH TORQUE, approx. overall size: 3 1/2" x 3 1/2" x 2 1/2" spindle 1/2" dia. as illustrated. £2.70. P. & P. 30p. Similar to above, 19rpm. £2.70. P. & P. 30p. 110rpm with pressed steel gear case (similar to above but slightly smaller). £2.70. P. & P. 30p.




SPIT MOTOR

5rpm. 2 1/2" x 1 1/2" x 6 1/2" high. 240v. AC. Shaft 1/2" dia., 1 1/2" length with hexagon socket inside. £1.80. P. & P. 30p.

BRAND NEW "GRYPHON" BROOK REVERSIBLE MOTORS Type TE

230/250V. 50Hz. 1ph. 0.83hp. 1,380rpm 0.9amps at full load, 1/2" spindle. This is a superbly constructed, standard foot-mounted unit with the extra facility of reversal by remote switching. Weight 16lb. 10oz. Offered in original maker's packing at approx. half price! £4.50. Carr. 50p.



AMPEX 7.5v. DC MOTOR

This is an ultra precision tape motor designed for use in the AMPEX model AG20 portable recorder. Torque 450GM/CM. Stall load at 500ma. Draws 600ma on run. 600rpm ± speed adjustment. Internal AF/RF suppression. 1/2" dia. x 1 1/2" spindle, motor 3" dia. x 1 1/2". Original cost £16.50. OUR PRICE £3. P. & P. 25p. Large quantities available (special quotations). Mu-metal enclosure available. 75p each. FREE P. & P.

KLG SEALED TERMINALS Type TLS1 AA. Overall length 11/16", box of 100 £1.50. P. & P. 10p.

KNOWLE (U.S.A.) MINIATURE MICROPHONE CAPSULES Impedance approx. 200Ω, output 60 or 80 DB at 1 Kc. As used in deaf aids, bugging devices, etc. Size (60 DB) 7/32" x 5/32" x 1/4"; (80 DB) 2 1/4" x 5/32" x 3/8". Ex-equipment, all tested. £1.20 each. P. & P. FREE.


"CROUZET" MOTORS Type 965 115/240v. 50Hz. 48w. Stoutly constructed, 2 1/2" dia. x 3 1/2" long plus spindle 1" x 1/2" dia. Anticlock. £3 each. P. & P. 25p.

ELECTRO-TECH

Self selection components. Huge stocks much too numerous to mention here, come along and look for yourself!

OPEN: MON to SAT. 9.30-6pm.

SYNCHRONOUS AUTO-RESET PROCESS TIMER by LONDEX LTD.



Type IMP Mk. 2. BRAND NEW and boxed. These well known timers are already in wide use and are perfect for Industrial Electronic Timing, Research and for all machine control timing problems. Repetitive accuracy better than 0.5% of full scale setting. Two or more can be interconnected to give control of a series of processes. 230/250V. 50Hz, also available 60Hz. 15mins. full scale 15secs. per division. Driven by self-starting sync. motor. Contact rating 5amp at 250V. AC. Incorporates solenoid operated clutch, also lever actuated micro-switches. Normal price probably in excess of £16. Complete with multi-pin connector as illustrated. £6.50. P. & P. 25p.

MAINS SOLENOID

This little unit gives vertical lift of approximately 1" through hinged "elbow". Bracket incorporates 2 fixing screws. Length of arm 2 1/2". 240V AC. Pull at coil is approximately 1lb. £1. FREE P. & P. Special quotes for quantities.



SOLENOIDS by WESTOOL

240AC type MM6. 3lb. pull, 2 1/2" x 1 1/2" x 1 1/2". Travel 1". 85p each. P. & P. 10p.
240AC type MM4. 2lb. pull, 1 1/2" x 1 1/2" x 1". Travel 1/2" 60p each. P. & P. 10p. Quantity discounts; 10-50 10%. 50 upwards 25%



"DECCO" MAINS SOLENOID

Compact and very powerful. 16lb. pull. 1/2" travel which can be increased to 1" by removing captive-end-plate. Overall size: 2" x 2 1/2" x 2 1/2" high. £2. P. & P. 20p.




"DAVENSET" MAINS SOLENOID

1" travel, 8lbs. pull (approx.). Size: 2 1/2" long x 2 1/2" x 2" high. Similar in appearance to "SORENG". £1.50 P. & P. 20p.

MAINS SOLENOID by MAGNETIC DEVICES LTD.

A beautifully constructed solenoid at half normal price. A 2-sided bracket is incorporated for vertical or horizontal mounting. Size: 2" x 1 1/2" x 1 1/2". Pull is approximately 2lbs., plunger travel 1 1/2". Fixing eye takes up to 1/2" bolt, plunger non-captive. NEW in original maker's boxes. £1. P. & P. 20p. Large number available, special price for quantity.




7 DIGIT COUNTER by "Counting Instruments Ltd."

Non re-set, robust construction. 115V AC. £1.20. P. & P. 10p.



3 BANK MAINS COUNTER

NON RE-SET by "E.N.M. LTD." BRAND NEW. 6 digits per unit. Robust and neat. 200/240AC. £5.80. P. & P. 25p. Limited supply.



MAINS to 12 Volt D.C. POWER SUPPLY Unit Type J24

This is a compact and neat unit in a moulded plastic case giving out 12v at 600MA. A thermal cut-out is incorporated. Screw terminals on output. Complete with 6ft. mains lead. Size: 5 1/2" x 2 1/2" x 2 1/2" high. £1.80. P. & P. 20p.

"RE CIRK IT" Mains 10amp cut-out

by "Neimman Electric" Germany. Eliminates fuses. Size: 2" x 2 1/2" x 1 1/2" deep. 90p each. P. & P. 10p. 10 or more 70p each. P. & P. 20p.



UNLESS OTHERWISE STATED

all items are NEW and UNUSED. Postal or carriage charges are for Gt. Britain only. We welcome orders from established companies, educational depts., etc. All orders under £2.50. C.W.O., please. Company orders under £2.50. surcharge 60p. unless C.W.O.

PLUG-IN RELAYS

(PERSPEX ENCLOSED)

by SCHRACK

OCTAL (2c/o) 6 amp contacts at following voltages: 48 D.C., 60 D.C., 60 A.C., 110 D.C., 380 A.C. PRICE EACH 90p.


11 pin (3 c/o) 6 amp contacts: 12 A.C., 48 D.C., 48 A.C., 60 A.C., 60 D.C., 110 D.C., 115 A.C., 240 A.C. PRICE EACH £1.

RA and RN Series (4 c/o) 3 amp Gold Plated Contacts. Handsome modern construction 1/2" x 1/2" x 1 1/2" high. Following voltages: 6 A.C., 12 A.C., 24 A.C., 48 A.C., 48 D.C., 60 A.C., 110 D.C., 115 A.C., 120 A.C. PRICE EACH 80p.

Base sockets for all above types 10p. Please add 10p towards P&P on all orders.

From JAPAN. TAKAMISAWA Perspex enclosed relays. Type MO 30p. 24V. D.C. 500 ohms (4c/o). Complete with base socket. 80p. P. & P. 10p.

FINDER Perspex enclosed OCTAL (2c/o) RELAY 220v. AC. 90p. P. & P. 10p.



TANGENTIAL HEATER

Silently driven by shaded pole Mycalex motor, powerful and smooth running with aluminium impeller (outlet 5/8" x 1/2"). Mains voltage PLUS matching heater unit with spiral element. May be switched for 500 or 1,000w. £1.80. P. & P. 30p.

DOUGLAS TRANSFORMERS

Full range in stock, SAE or phone for list please.



SILVANIA MAGNETIC SWITCH

Now complete with reference magnet! A magnetically activated switch, vacuum sealed in a glass envelope. Silver contacts, normally closed. Rated 3amp at 120v. 1amp at 240v. Size: (approx.) 1 1/2" long x 1/2" dia. Ideal for burglar alarms, security systems etc., and where ever non-mechanical switching is required. 10 for £1.80; P & P 15p. 50 for £8; 100 for £15. FREE P. & P. over 10.

NORPLEX

The famous American fibre-glass copper-clad laminate. Finest quality with woven glass base of epoxy-resin. Excellent Mech. and Elec. conductive properties. Heat resistant, ideal for P.C.'s etc. THIS IS A SPECIAL PURCHASE AND ONLY AVAILABLE WHILE STOCKS LAST! Sizes: 12" x 12"; 24" x 12"; 24" x 24"; FULL SHEET 43" x 37" (11 sq. ft.). Single-sided Copper with thickness of 1/32", 3/64", 3/32". Also double-sided 1/32", 1/16", 3/32". £1 per sq. ft. Cut sizes (1-10 sq. ft.) 25p. P. & P. Full Sheet £8 each. Carr. £1 for 1st sheet plus 25p each additional sheet.


MINIATURE "LATCHMASTER" RELAYS

6, 12, or 24v. DC operation. One makes one break, contacts rated at 5amps at 30v. Once current is applied relay remains latched until input polarity is reversed. Manufactured for high acceleration requirements by SPERRY GYROSCOPE CO. Size: 1" length, 9/16" dia. (including mount). Please state vertical or horizontal mount and voltage. £1 each. P. & P. 10p.



"GOYEN" PRESSURE SWITCH

Incorporating differential adjustment between 2" and 12" water gauge (a max. of approx. 1/2 p.s.i.). A single pole change-over switch rated 15 amps. 250v. is actuated. Air inlet tube 1/4" dia. Projection 1/4". Overall size dia. 3 1/2", depth 2" plus 3/4" (air tube). £1.45. P. & P. 20p.



PYE MICROSWITCH

OTEHALL Type. This switch has a 1 1/2" x 15/32" dia. column plus 1/2" plunger—fractional travel actuates. 6 for £1 (Min. quantity). P. & P. 15p. Large stocks available.



PHILIPS SLOW-MOTION DRIVE

Comprising dual knob assembly, i.e., 1 1/2" dia. futed knob surmounting a similar one 1 1/2" dia. (Black). Depth from panel overall approx. 1 1/2". Beautifully balanced for 1/2" spindle. Approx. ratio 7.5 to 1. (Small knob). Direct drive large knob. Very neat in appearance. £1. FREE P. & P.

PANTON BOURNE TRIMPOTS

1k, 2k, 2.5k, 5k, 10k, 20k, 50k, 500k. Other trimmer pots in stock. RIL 10k MORGANITE 1k MEC200ohms (tubular) 50ohms. Any 3 for £1.10. FREE P. & P.

PLEASE ADD 10% FOR V.A.T. ON ALL PRICES SHOWN INCLUDING P & P

ELECTRO-TECH COMPONENTS LTD.

315/317, EDGWARE ROAD, LONDON, W2. Tel: 01-723 5667 01-402 5580

Trannies

1 Dockyard, Station Road,
Old Harlow, Essex.
Telephone: 37739
(Saturday callers welcome)

V A T

PRICES DO NOT
INCLUDE VAT
ADD
10% TO THE TOTAL

Our NEW 1973
Catalogue is now
available
BIGGEST YET 10p


74 Series TTL (National Semiconductors and I.T.T.) LOW PRICES, HIGH QUALITY

7400	16p	25	100+	7450	1	25	100+	74141	1	25	100+
7401	16p	14p	12p	7451	16p	14p	12p	74145	£1.50	£1.40	£1.30
7402	16p	14p	12p	7453	16p	14p	12p	74150	£3.00	£2.69	£2.53
7403	16p	14p	12p	7454	16p	14p	12p	74151	£1.00	97p	92p
7404	16p	14p	12p	7460	16p	14p	12p	74153	£1.20	£1.12	99p
7405	16p	14p	12p	7470	29p	26p	25p	74154	£1.80	£1.71	£1.60
7406	36p	32p	28p	7472	29p	26p	25p	74155	£1.40	£1.30	£1.20
7407	36p	32p	28p	7473	38p	36p	32p	74156	£1.40	£1.30	£1.20
7408	18p	17p	16p	7474	38p	36p	32p	74157	£1.90	£1.81	£1.72
7409	18p	17p	16p	7475	46p	45p	42p	74160	£1.80	£1.71	£1.60
7410	16p	14p	12p	7476	40p	39p	38p	74161	£1.80	£1.71	£1.60
7411	24p	19p	16p	7480	68p	63p	59p	74162	£4.00	£3.76	£3.60
7412	30p	25p	20p	7481	£1.20	£1.15	£1.09	74163	£4.00	£3.76	£3.60
7413	29p	27p	25p	7482	88p	87p	86p	74164	£2.20	£2.16	£2.10
7416	44p	40p	38p	7483	£1.11	£1.07	97p	74165	£2.28	£2.22	£2.17
7417	44p	40p	38p	7484	£1.01	96p	91p	74166	£3.55	£3.28	£3.06
7420	16p	14p	12p	7485	£3.00	£2.45	£2.10	74174	£2.33	£2.22	£2.11
7422	50p	48p	45p	7486	32p	31p	30p	74175	£1.66	£1.55	£1.44
7423	50p	48p	45p	7489	£4.49	£3.84	£3.38	74176	£2.55	£2.44	£2.34
7425	50p	48p	45p	7490	58p	48p	38p	74177	£2.55	£2.44	£2.34
7426	46p	42p	40p	7491	£1.00	95p	90p	74180	£2.05	£1.66	£1.44
7427	46p	42p	40p	7492	68p	65p	59p	74181	£5.55	£5.10	£4.83
7428	70p	65p	60p	7493	68p	65p	59p	74182	£2.05	£1.83	£1.66
7430	16p	14p	12p	7494	78p	75p	69p	74184	£3.55	£3.28	£3.06
7432	45p	42p	40p	7495	78p	75p	69p	74190	£2.00	£1.94	£1.89
7433	80p	76p	71p	7496	88p	85p	79p	74191	£1.92	£1.87	£1.91
7437	68p	62p	60p	74100	£1.65	£1.60	£1.56	74192	£2.06	£1.94	£1.89
7438	66p	62p	60p	74104	97p	95p	89p	74193	£2.05	£1.66	£1.44
7440	16p	14p	12p	74105	97p	95p	89p	74194	£2.77	£2.66	£2.55
7441	68p	65p	60p	74107	41p	39p	37p	74195	£2.05	£1.66	£1.44
7442	68p	65p	60p	74110	58p	54p	51p	74196	£1.83	£1.75	£1.66
7443	£1.30	£1.25	£1.19	74111	£1.25	£1.18	£1.12	74197	£1.83	£1.75	£1.66
7444	£1.30	£1.25	£1.19	74116	£1.00	95p	90p	74198	£5.55	£5.10	£4.83
7445	£1.80	£1.76	£1.73	74119	£1.35	£1.25	£1.14	74199	£5.55	£5.10	£4.83
7446	97p	94p	88p	74121	40p	38p	35p				
7447	97p	84p	70p	74122	£1.40	£1.30	£1.12				
7448	£1.00	97p	95p	74123	£2.78	£2.67	£2.61				



Volume Controls (AB45 Series)

We are now able to offer a full range of carbon potentiometers from stock.



Single gang less switch	1-49	50 plus
Log or Linear 1K to 2 meg.	12p	10p
Single gang with D.P. switch		
Log or Linear 5K to 2 meg.	24p	20p
Dual Gang less switch		
Log or Linear 5K or 2 meg.	40p	32p

(Devices may be mixed to qualify for price breaks)

Veroboard

2 1/2 x 31	15 matrix	1
2 1/2 x 5	17p	22p
3 1/2 x 5	22p	24p
3 1/2 x 5	22p	24p
3 1/2 x 5	28p	28p
2 1/2 x 17	60p	79p
3 1/2 x 17	81p	£1.05
Pin insertion tool	—	82p
Spot face cutter	52p	52p
42p	42p	42p
Pack of 36 pins.	20p	20p

Presets

Carbon skeleton presets.

Small high quality type (Linear only). All valves 100 ohms to 10 megohms.

1 watt	5p	4p
25 watt	6p	5p
1-49	50 plus	

Linear Integrated Circuits

709c DIL	1-49	50 plus	741c 14 Pin DIL	38p	31p
709c TO99	34p	29p	741c TO99	38p	31p
723c DIL	35p	30p	747c DIL	80p	68p
723c TO99	70p	55p	748c DIL	36p	31p
741c 8 Pin DIL	76p	58p	748c TO99	38p	32p
	34p				



Many other types available.

Silicon Rectifiers lamp miniature

Type	PIV	1-99	100 plus
IN4001	50	5p	3 1/2p
IN4002	100	5 1/2p	4p
IN4003	200	6p	5p
IN4004	400	6 1/2p	5 1/2p
IN4005	600	7 1/2p	6 1/2p
IN4006	800	9p	7 1/2p
IN4007	1000	10p	8p

Phone 37739 for IMMEDIATE despatch

Thyristors

1 AMP	50v.	1-49	50 plus
	50v.	20p	16p
	100v.	22p	18p
	200v.	30p	24p
	300v.	35p	28p
	400v.	40p	31p
3 AMP	50v.	44p	40p
	100v.	50p	45p
	200v.	60p	54p
	400v.	66p	58p
5 AMP	100v.	66p	—
	200v.	80p	—
	400v.	95p	—

400 mW Zener Diodes

BZ78 Series. 3.3 volt through to 33 volt.

1-49	50-99	100 plus
9p	8p	6-8p

TRANSISTORS DIODES

(Quantity discount 25 plus 15%, 100 plus 20%)

AC126	14p	BC147	13p	OC36	65p
AC127	14p	BC148	13p	OC44	10p
AC128	11p	BC149	13p	OC45	10p
AC176	12p	BC154	17p	OC70	12p
AC187	14p	BC157	17p	OC71	12p
AC188	14p	BC158	14p	OC72	14p
AD140	60p	BC159	14p	2N706	12p
AD149	60p	BC169	14p	2N926	10p
AD161	32p	BC182	12p	2N3055	49p
AD162	32p	BC183	12p	2N3702	13p
AF114	14p	BC184	12p	2N3704	13p
AF115	14p	BC212	12p	2N3819	30p
AF116	14p	BC213	12p	40361	31p
AF117	14p	BC214	14p	40362	36p
AF139	32p	BD131	89p	40636	76p
AF239	40p	BD132	69p	OA90	5p
BC107	10p	OC25	40p	OA91	5p
BC108	10p	OC28	52p	OA202	7p
BC109	10p	OC35	52p	IN4148	5p

(Many other types stocked)

Resistors

1 watt 5% carbon	1p	100 plus
1 watt 5% carbon	1p	7p
1 watt 10% carbon	2p	2p
range 10 ohms to 4.7 megohms.		
1 watt m/o 2%	3p	2-4p
range 10 ohms to 1 megohms.		

Transformers

12-24 volt

Secondary	Volts	Amps	Volts	Amps	Part No.	Price inc. P.I.P.
12	500mA	24	250mA	MT111	£1.20	
12	1	24	500mA	MT113	£1.26	
12	2	24	1	MT71	£1.89	

30 volt

Amps	Part No.	Secondary	12, 15, 20, 24 30v.	Price inc. P.I.P.
1	MT79			£2.02
2	MT3			£2.78
5	MT51			£5.21

50 volt

Amps	Part No.	Secondary	19, 25, 33, 40, 50 volts	Price inc. P.I.P.
1	MT103			£2.54
2	MT104			£3.75
4	MT106			£6.00

Many other types available. See our Catalogue.

General Purpose Miniature Electrolytic Capacitors

(MULLARD & ERIE)

4 VOLT	47µf	6p	4700µf	36p	40 VOLT	6.8µf	6p
	100µf	6p	10,000µf	60p		15µf	6p
	220µf	6p				33µf	6p
	330µf	6p				100µf	6p
	1000µf	12p				150µf	6p
	4700µf	27p				220µf	10p
6.3 VOLT	33µf	6p				470µf	18p
	68µf	6p				680µf	16p
	150µf	6p				1000µf	17p
	470µf	10p				1500µf	26p
	680µf	12p				2200µf	33p
	1000µf	16p				3300µf	34p
	1500µf	18p				6800µf	57p
	2200µf	20p					
	3300µf	25p					
	6800µf	36p					
10 VOLT	22µf	6p					
	47µf	6p					
	100µf	6p					
	220µf	7p					
	330µf	9p					
	470µf	9p					
	1000µf	12p					
	1500µf	18p					
	2200µf	23p					

(Quantity discount 15%—25 plus. 20%—100 plus. 25%—250 plus.)

MULLARD POLYESTER CAPACITORS C280 SERIES

250v. p.c. mounting 0.01µf, 0.015, 0.022, 3p; 0.033, 0.047, 0.068, 3 1/2p; 0.1, 4p; 0.15, 0.22, 5p; 0.33, 6 1/2p; 0.47, 8 1/2p; 0.68, 11p; 1.0, 13p; 1.5, 20p; 2.2µf, 24p.



MULLARD POLYESTER CAPACITORS C296 SERIES

400v. : 0.001, 0.0015, 0.0022, 0.0033, 0.0047, 2 1/2p; 0.0068, 0.01, 0.015, 0.022, 0.033, 3p; 0.047, 0.068, 0.1, 4p; 0.15, 6p; 0.22, 7 1/2p; 0.33, 11p; 0.47, 13p. 160v. : 0.01, 0.015, 0.

TELEPRINTER EQUIPMENT LIMITED

Sales . . . Rentals . . . New . . . Refurbished . . . Installation . . .
Maintenance . . . Overhauls . . . Spare Parts . . . Prompt Deliveries

CREED EQUIPMENT

TELEPRINTERS Models 7B, 54, 75, 444
PERFORATORS 7PN, 85/86, PR75, 25
TAPE READERS 6S4, 6S5, 6S6, 6S6M, 92, 35, 71, 72, 74
HIGH-SPEED TAPE WINDERS 80-0-80V POWER SUPPLY UNITS, etc.

TELETYPE CORP. EQUIPMENT

TELEPRINTERS 15, 19, 20, 28, 32, 33, 35
all configurations
PERFORATORS 14, 19, 28 LPR, RECEIVE & MONITOR GROUP CABINETS
TAPE TRANSMITTERS 14, 20, 28 LBXD & LXD TRANSMIT GROUPS, etc.

SIEMENS EQUIPMENT

TELEPRINTERS T100 and T-68 in various configurations
PERFORATORS T-LOCH 12, T-LOCH 15, A, B, D & F, etc.

OTHER EQUIPMENT

KLEINSCHMIDT, OLIVETTI, LORENZ, COCQUELET, BRITISH, AMERICAN,
CONTINENTAL, ARABIC and other layouts, 5-8 track.

SPECIAL EQUIPMENT

SOLID STATE MOTOR CONTROLS, MODEM INTERFACE UNITS, TARRIFF J
INTERFACE UNITS, TEST EQUIPMENT, COMPUTER INTERFACE UNITS, DEC.
PDP8 and others. SILENCE COVERS AND CABINETS, TELEPRINTER TABLES,
SIGNALLING RECTIFIERS AND CONVERTORS, TAPE HOLDERS.

WW-104 FOR FURTHER DETAILS

COMMUNICATION ACCESSORIES & EQUIPMENT LIMITED

G.P.O. TYPE COMPONENTS FOR PROMPT DELIVERY

JACK PLUGS—201, 310, 316, 309, 404, 420, 609, 610, 1603 — 3201
JACK STRIPS—310, 320, 510, 520, 810
JACK SOCKETS—300, 500, 800, B3 and B6 mountings, 19, 84A and 95A
PATCH PANELS & RACKS—made to specifications
LAMPS, SWITCHBOARD NO. 2, BALLAST PO 11, LAMP STRIPS, 10-way PO 19, 20-way PO 17, Lamp Caps, Holder No. 12
CORDS (PATCHING & SWITCHBOARD)—made to specifications
TERMINAL BLOCKS (DISTRIBUTION)—20-way up to 250-way
LOW PASS FILTERS—type 4B and PANELS, TELEGRAPH 71 (15 x 4B)
POLARISED TELEGRAPH RELAYS AND UNISELECTORS—various types and manufactures both P.O. and miniature
LINE TRANSFORMERS/RETARDATION COILS—type 48A, 48H, 49H, 149H, 3/16, 3/216, 3/48A, 3/43A, 48J, etc.
FUSE & PROTECTOR MOUNTINGS—8064 A/B 4028, H15B, H40 and individual 1/2
COILS—39A, 40A, 40E, etc.
P.O.-TYPE KEYS—1000 and PLUNGER TYPES 228, 279, etc.
EQUIPMENT RACKS AND CONSOLES—made to specifications
RELAY ADJUSTING TOOLS, TOOL BAGS FOR MECHANICS, TENSION GAUGES, ARMATURE ADJUSTERS, SPRING BENDERS ETC. VARIOUS SWITCHBOARD EQUIPMENT.

WW-105 FOR FURTHER DETAILS

MORSE EQUIPMENT LIMITED

The GNT Range of Automatic Morse Equipment is now manufactured in the U.K. and comprises complete equipment for Morse Training Schools and for Automatic Morse Transmission. Models available include:

KEYBOARD PERFORATORS for offline tape preparation
AUTOMATIC TAPE TRANSMITTERS with speeds up to 250 w.p.m.
MORSEINKERS specially designed for training, producing dots and dashes on tape
HEAVY DUTY MORSE KEYS
UNDULATORS for automatic record and W/T signals up to 300 w.p.m.
CODE CONVERTERS converting from 5-unit tape to Morse and vice versa
MORSE REPERFORATORS operating up to 200 w.p.m.
TONE GENERATORS and all Students' requirements
CREED, MORSE EQUIPMENT, PERFORATORS, REPERFORATORS, TRANSMITTERS, PRINTERS, MARCONI UG6 UNDULATORS, BUZZERS, ALDIS LAMPS, etc.

WW-106 FOR FURTHER DETAILS


77 AKEMAN STREET, TRING, HERTS., U.K.

Telephone: Tring 3476/8, STD: 0442-82 Telex 82362, Answerback: Batelcom Tring

THE NEW NELSON-JONES FM TUNER

PUSH-BUTTON VARICAP DIODE TUNING (6 Position)

Exclusive Designer Approved Kits



For the first time the Nelson-Jones Tuner is available as a **complete kit** with all Metalwork, Printed and anodised Front Panel and Teak veneered cabinet. A Six Position push-button unit is used with each pre-selector button fully tuneable with its own scale and pointer and incorporating AFC disable for fine tuning.

Provision is also made for a Stereo LED, Stereo Decoder, Internal PSU and Fine Tuning indication (Meter or LED type). Push-button switches are also used for Stereo Mute and Mains On/Off. All sockets, board standoffs and panel mounting fuse are supplied.

Our attention to detail is such that even our cabinets are veneered inside and out for minimum warp and attractive appearance.

The tuner is available in two gain versions, and our **alignment service** is available to customers without access to a signal generator.

Prices for complete kits start at **£23.75** (mono) plus p.p. 45p., and of course all components are available separately


Please send large SAE for our latest price lists which detail all of the many options and special low prices for complete kits. All our other products remain available e.g. **The Portus and Haywood Phase Locked Stereo Decoder Kit.**

PLEASE NOTE. Existing tuners are readily convertible and kits/parts are available for this purpose.

TEXAN AMPLIFIER. We have designed the tuner case and metalwork to match the Texan amplifier (see photograph).

Complete designer approved Texan kits are available at **£28.50** plus p.p. 45p including a Teak Sleeve.

V.A.T. Please add V.A.T. at 10% to all prices for U.K. orders.



INTEGREX LIMITED, P.O. Box 45, Derby, DE1 1TW

Phone Repton (028389) 3580

BEDFORD ELECTRONICS

2, GROVE PLACE
BEDFORD

OSCILLOSCOPES

TEKTRONIX 545. From £250.
TELEQUIPMENT 554U. Complete with internal battery. Unused £150.
TELEQUIPMENT D43 with amplifiers B & C. Excellent condition £80.

ADVANCE power supply Type PM16, continuously variable output voltage and current limit, SCR overvoltage protection. Regulation better than 0.02% no load to full load. Complete with manual. 0-7 volts 1 amp. As NEW £9.50 EACH.

Colvern 9 Digit SHAFT ENCODERS Type 31 CW9, 3" magstrip case. 512 divisions/360 degrees. Test sheet included, £6 each.

Salford Electrical MULTI TAPPED POTS. Elect. angle 340 Deg. Mech. angle 360 Deg. Resistance 150K 5% lin. 0.5% tapped every 10 Deg. £2.50 each.

Colvern TEN TURN POTS. 500R. 5% Lin. 0.1%. £1.25 each.

Veeder Root 6 digit counters. Type LR1643. Mech. reset, 24V. Recent manufacture. As new £3 each.

Pressure transducers KDG, Type TD216. 0-1200 P.S.I. Complete with calibration chart. £5 each.

FLUID LOGIC teaching sets. These well made teaching aids contain the following components mounted on an engraved panel within a polished wooden box, 2 bistable, 1 and, 3 or nor logic elements, 2 press transmitters, 2 press receivers, 2 pressure

regs. and gauges, 2 actuating cylinders and press. amplifiers, 4 position sensors. Supplied complete with all accessories. £37.50.

7/0076 P.T.F.E. Equipment wire to EL1930 £2 per 100yds. Please check availability before ordering.

BELLING LEE Pattern 102 units L654/P 21p, /S 28p, /C3 18p, /R3 18p; L655/P 26p, /S 38p, /C3 18p, /R3 18p; L656/P 35p, /S 55p, /C3 20p, /R3 20p; L657/P 47p, /S 72p, /C3 25p, /R3 23p. Discount for quantity.

THERMISTORS Type FS1, bead at tip of 1" glass tube, approx. 100K @ 25 C. 25p each.

CARPENTERS polarised relay SPCO 2 x 1000R, complete with base and retainer, as new. 45p each.

POT CORES LA1 or LA3. 40p each.

METERS, 3 1/2" diameter, sealed, 50-0-50 uA/1300R, £2.25 each. 1 mA/130R, £1.75 each.

BALL RACES Type RCL 1/4F. Flanged 1/2" bore 5/16" dia. Sealed packs, 25p each.

PANEL FUSE HOLDERS with indicator lamp. The cap of these 1 1/2" fuse holders is provided with an amber lens and min. flanged lamp-holder to allow a fuse failure neon to be fitted, bulb not included. 20p each.

MINIATURE THUMB WELL SWITCHES, matt black, BCD and complement, as new, 70p each.

**V.A.T.
PLEASE ADD 10% V.A.T.
TO ALL PRICES.**

**RING BEDFORD 51961 FOR AN APPOINTMENT TO VIEW
TEST EQUIPMENT**

WW-102 FOR FURTHER DETAILS

COLOMOR ELECTRONICS

SALE

To clear our stores of surplus stock we are holding a sale of equipment and Components at give-away prices. It is impossible to list all the goods, the selection below is but a brief indication of items and prices. There is something for everyone to come and see, but hurry, many items are "one off" only.

HEWLET PACKARD 5408 COUNTER £25—
MARCONI OA1094 SPECTRUM ANALYSER £35—
TF 144G £3—SIGNAL GENERATOR No. 1 £20—
SIGNAL GENERATOR No. 2 £12—
TF958VUM £12.50—TF 957 WATTMETER £10—
AR88 £20—B 42 £15—P.C.R. £3.50—
CR 100 £1—CT 160 VALVE TESTERS £15—
TF 899 VmVM £1.50—SQUARE PULSE GENERATORS £7—
B.F.'s £5—REG. H.T. POWER SUPPLIES £10—
DM 2004 DVM £17—BERKELEY COUNTER £15—
K/H PEN RECORDERS £7.50—
THOUSANDS OF BRAND NEW METERS FROM 30p.
LARGE METERS FROM 40p—
COMPONENTS, SWITCHES, CONTROL BOXES, TESTERS, etc., etc., etc.

SALE COMMENCES 15th SEPTEMBER and will last a few weeks only. **HOW TO GET THERE:—** In the premises of Unigate Dairy Depot, entrance off Cromwell Road Extension (Cedars Rd.) towards London, first left (Sutton Lane North, W.4.) first entrance on left. Or write to:—

COLOMOR (ELECTRONICS) LTD.
170, Goldhawk Road, London W.12
01-743 0899

UNIQUE OPPORTUNITIES

GENERATORS

MARCONI TF867 STANDARD SIGNAL GENERATOR



Carrier Frequency. Range: 15Kc/s-30Mc/s in 11 bands. Calibration Accuracy: $\pm 1\%$. Stability: After warm up the drift in a 10-minute period is, typically, less than 0.005% for carrier frequencies up to 3.2Mc/s and less than 0.01% from 3.2-2.30Mc/s. Output Voltage: 0.4 μ V-4V. Impedance: 75 ohms nominal for outputs from 2-4 v. 75 ohms for outputs from 4 μ V-2V. 13 ohms for outputs from 0.4 μ V-0.4V.

Accuracy: below 3Mc/s ± 0.25 dB or $\pm 0.1\mu$ V. 3-10Mc/s ± 0.5 dB or 0.0-2 μ V. 10-30Mc/s ± 1 dB or $\pm 0.5\mu$ V. Power Supply: 100-125V, 200-250V 40-100c/s. Dimensions: 18 in. high x 21 in. wide x 14 1/2 in. deep. Price £165.00

DOUBLE PULSE GENERATOR TYPE TF 1400/S
10 c/s-100 Kc/s. Complete with TM 6600. Pulse adjustable between 1.5 μ sec. before and up to 3,000 μ sec. **PRICE £145.00**

MARCONI A.M. SIGNAL GENERATOR TYPE TF801D

10-485Mc/s in five ranges. Output 0.1 μ V-1 Volt E.M.F. External Sine A.D. Frequency 30c/s-50Kc/s. **PRICE £195**

PHILIPS SQUARE WAVE GENERATOR MODEL GM2314

Range 15 c/s-200 Kc/s. Duration of square wave pulses between 0.75 μ sec and 40 m/sec. Square wave voltage 10V **PRICE £75.00**

AMPLITUDE MODULATOR TF1102

100Kc/s-300Mc/s Sine-wave from 20 c/s-15 Kc/s and 20 x/s-500Mc/s **£35.00**

MARCONI Type TF987/1 NOISE GENERATOR

1-200 Mc/s ± 0.5 DB **£20.00**

MARCONI TF2092 NOISE GENERATOR **£295.00**

MARCONI VHF SIGNAL GENERATOR TF 1145

450-1900 Mc/s **£295.00**

PHILIPS VIDEO GENERATOR GM2887 **£95.00**

WAYNE-KERR VIDEO NOISE GENERATOR **£75.00**

MARCONI H.F. CIRCUIT MAGNIFICATION METER TF886A

A direct reading Q Meter 15-170 Mc/s Magnification 60-7200 Q **£45.00**

MARCONI DISTORTION FACTOR METER TF142F

100 c/s-8 Kc/s 0.05%-50% Measures all spurious components up to 30Kc/s **£35.00**

MARCONI PULSE GENERATOR TF675E

Repetition Frequency 50c/s-50Kc/s 0.15-40 μ Sec **£35.00**

MARCONI WIDE RANGE R.C. OSCILLATOR TF130

Sine-waves 10c/s-Mc/s, square waves 10c/s-100Kc/s Direct outputs up to 31.6V. Attenuator with three impedances. **£120.00**

HETERODYNE UNIT TF1221

2Kc/s-100Mc/s **£45.00**

WAYNE-KERR NOISE GENERATOR CT410

A portable instrument for measuring the noise factor of radio receiving equipment, metric radar receivers, and radar wide-band i.f. amplifiers in the band 15KHz-160MHz. **£75.00**

MARCONI TYPE TF801A SIGNAL GENERATOR

Frequency range: 10MHz to 310MHz. O/P voltage: 0-100 db relative to 200 mV into 75ohm IV CW O/P available. Internal modulation: 400Hz, 1kHz and 5kHz to 80% sine or square. **£45.00**

ADVANCE TYPE D1/D SIGNAL GENERATOR

Frequency range: 10MHz-300MHz. O/P voltage: 1V-10mV. **£25.00**

KENT CHROMALOG 1 DIGITAL INTEGRATOR

For use with gas chromatography apparatus or anything with an output expressed as a varying direct voltage. Automatic print out and 0-10mA O/P to drive recorder. Offered in excellent condition. 3 month warranty and copy of handbook. Price **£150**. Carriage extra.



FANTASTIC VALUE IN OSCILLOSCOPES

TEKTRONIX 515	
524AD	£125
535A DC-30 Meg	£205 Main Frame
545	
545A	£295


HEWLETT PACKARD 185B Sampling Oscilloscope DC-1000 Meg complete with 187C Dual Trace AMP has 350 microsec. Rise time (1000 MC) **£395**

COSSOR CDU 110 Dual Channel Transistorised DC-25 MHz at 5mV/cm. 0.2 microsec. $-0.5 \pm 3\%$ 5X Magnification extends sweep speed to 40 nanosec./cm. Sweep delay 180 nanosec. **£249.50**

COSSOR CDU 120 Dual Channel fully transistorised 50 mV/cm to 10V DC-60 MHz. Rise time 6 nanosec. 1 mV/cm at 25 MHz. 0.1 microsec. **£349.50**

COSSOR CDU 150 Rugged Transistorised fully portable Dual Channel DC-35 MHz at 5mV/cm. As used by numerous government departments (c/f CT531) **£375**

COSSOR The very latest Cossor 4000 Dual beam. 55 MHz at 50mV/cm Trigger. SCOOP-ONE ONLY **£425**



TEKTRONIX 545. With delay time base **£295**

DYNAMCO DC-60 7100

1Y2 7100 1X2 Oscilloscope, Dual channel with sweep delay, suitable for computer maintenance and most laboratory applications 30MHz, 1mV 10ys to 5s delay. **BRAND NEW £295**

HEWLETT PACKARD 185B

Sampling Oscilloscope DC-1GC. Complete with 187C Dual Trace Amplifier. Has a 350 p.sec. rise time (1000MC) **£395**



MINITRON

K.G.M. Type 3015F 7 Segment display showing figures 0-9 plus decimal point. Character of 9mm height. In 16 DIL case. **NEW LOW PRICE £1.40**

SN7447N BCD Decoder Driver **£1.00**

SINE COSINE POTENTIOMETER 47K

Precision component by Pye. Model 2002. Manufactured to rigid Ministry specification. The assembly consists of three units mounted in one frame. Each unit contains two sine and two cosine potentiometer sections, the sliders being ganged together. Electrical connections, 2 end taps, slider and centre tap. Mechanical I.P.: 30 r.p.m. Max. torque: 3 1/2 oz.in. Dimensions: W. 6 1/2 in. H. 5 in. D. 7 1/4 in. Wt. 7 1/2 lbs. Carriage equipment. Good condition. Price **£5**. Carriage extra.



INFRA-RED SPECTROPHOTOMETER

A single beam instrument designed primarily to analyse the effluent from a gas chromatograph, however the fast response and fast scan capabilities make it suitable for fast reaction studies involving conventional gas, liquid, or solid samples. The wave length range is 2.5 to 14.5 microns. In excellent condition. Price **£175.00**

Beckman Type IR-102



TRANSISTOR TEMPERATURE CONTROLLER TYPE 990

Completely transistorised self-contained direct deflecting units for indicating and controlling temperature accurately over a wide range. Suitable where a signal can be converted into d.c. Sensitivity 10 ohms per MV. Minimum F.S.D. 8 MV. Cold junction compensation. Calibrated scale length 6.5", 0-800°C. Accuracy $\pm 1\%$. Front panel size 10" x 8 1/2", weight 1 1/2 lbs. Mains supply 100-260 V. Control switching and thermo-couple connections all at back of case. Price **£18.50** plus **£2.00** packing and carriage.

ASCOP DIGITAL ENCODERS

Type 504A-8-001 Price **£20**. Type EDD8G Price **£20**.

SYNCHROVERTER SWITCH TYPE G1280


BY ELLIOTT **PRICE £3**.

POWER SUPPLIES

POWER SUPPLIES, IBM EX-COMPUTER HIGHLY STABILISED, TRANSISTORISED LOW VOLTAGE POWER SUPPLIES.

These modular units incorporate overload protection on both INPUT and OUTPUT. Load regulation of 1% or better. Low ripple and fast response time. Input voltage 120-130 50 Hz. Available in the following types:

6 Volt 8 Amp	£21.00
8 Volt 12 Amp	£17.00
6 Volt 15 Amp	£20.00
12 Volt 4 Amp	£22.00
12 Volt 12 Amp	£22.00
12 Volt 20 Amp	£24.00
30 Volt 7 Amp	£19.00



A BARGAIN IN NEW POWER SUPPLIES. AT LESS THAN HALF MANUFACTURERS PRICES.

O/P Voltage 7.5V-9V. Max. load current 10 Amps. Max. ripple on full load approx. 60mV. p.p. Threshold current 10.5A. Overvolt protection. **OUR PRICE £12.50**

EX COMPUTER HIGH GRADE FULLY STABILISED POWER SUPPLIES

Input 200/250V.	
ADVANCE TYPE DC 207	20 Volts 9 Amps. 10 Volts 5 Amps. 10 Volts 3 Amps. 20 Volts 2 Amps.
ADVANCE TYPE DC 200	20 Volts 13 Amps. 10 Volts 5 Amps. 20 Volts 2.5 Amps.
ADVANCE TYPE DC 202	35 Volts 8 Amps. 24 Volts 4 Amps. 10 Volts 8 Amps.
ADVANCE TYPE DC 197	6 Volts 7.5 Amps. 6 Volts 11 Amps. 28 Volts 9 Amps.
WESTINGHOUSE Fully Fused Input 200/220/240/110	14 Volts 0.75 Amps. 20 Volts 4 Amps. 25 Volts 2.5 Amps. 30 Volts 0.75 Amps.
WESTINGHOUSE	6 Volts 7.5 Amps. 6 Volts 11 Amps. 28 Volts 9 Amps.

£18 EACH. P. & P. £2.

EVERSHED SAFETY OHMMETER

for testing the continuity and resistance of circuits, consists of a hand-driven generator and a direct reading ohmmeter. Range in ohms 0-4, 0-5, 0-10, 0-100, 0-300. **£10**

IGNITION TESTER

Ideal for garages, this brand new instrument is used to display all ignition faults. Supplied complete with instruction manual showing photographs of displays, making use very simple. Sold complete with isolating transfer for use on 240V 50Hz supply. Display cards also available for garages and other places wishing to advertise this equipment is in use. Made by British Physical Laboratories Ltd., originally for use on the Canadian market. **Price £75**

AVOMETERS

Model	Price	Model	Price
D	£14	40	£16
7	£19.50	47A	£16
8	£29.50	48A	£16
8X	£35		

NB. 47A and 48A are Admiralty versions of Model 40, the only difference being that the resistance ranges 0-1.2, 0-12 ohms, which are available on the Model 40 with the use of an external power supply are not available on the 47A and 48A. **CASES AND LEADS EXTRA**

PHILIPS VALVE VOLTMETER

Model GM6014 **PRICE £30.00**
Max. 300mV, 1000Hz-30MHz.

ADD 10% VAT TO ALL PRICES



ELECTRONIC BROKERS LIMITED

49/53 PANCRAS ROAD : LONDON NW1 2QB. Tel: 01-837 7781

to purchase some of the World's finest calibration instruments at savings of

33 1/3% AND MORE!

PEN RECORDERS

BRAND NEW MINIATURISED STRIP CHART RECORDER BY RUSTRAK



of America. This Recorder indicates the magnitude of applied currents or voltages by a continuous distortion-free line on pressure sensitive paper. Moving coil movement, scale calibrated 0.1 milliamp d.c. Internal resistance 100 ohms. Chart drive motor 240 V 50Hz. Chart speed 1" per hour. Complete with handbook. Price £35.00 plus £5.00 packing and carriage.

SINGLE PEN RECORDER



by Record Electrical. 3" chart, sensitivity 1 milliamp, chart speed 1" and 6" per hour. Size 8" x 11" x 6". Offered complete with pen assembly and spare chart. Listed at over £100—this month's special price due to bulk purchase... £39.50 plus £5.00 packing and carriage.

LEEDS & NORTHRUP STRIP CHART RECORDER

This well-known instrument is fitted with a Series 60 control unit servo amplifier 101041 BR EQ. Range: 5.571 to 18.855. Ref. junction 320F. Primary element: P1. P1.13% RH JMC. Response time: 5 secs. for f.s.d. Chart width: 7 in. Chart speed: 1 in. per hour. Power supply: 120V 50 Hz (auto-transformer available). Dimensions: Ht: 18", width 11", depth 12 1/2". Weight 51 lbs. PRICE £86.00

POTENTIOMETERS

TEN TURN 360° ROTATION

Res Ohms	Linearity Per cent	Manufacturers	Model	Price
100/100/100		Beckman	A.	£4.00
100	0.5	Beckman	A.S.	£2.00
200	0.5	Beckman	A.	£2.00
500	0.1	Beckman	S.	£2.50
500		Colvern	2501	£2.25
500		Foxes	PX4	£2.00
500		Colvern	2610	£2.50
500		Colvern	26/1000/11	£3.00
1000	1.0	Relcon	HEL107-10.	£2.25
1K		Relcon	HEL0710	£2.25
2K	0.5	Beckman	SA1101	£3.00
2K	0.25	Beckman	7216	£3.00
2K		Reliance	GP115	£2.00
2K		General Controls	GPA15/4	£2.00
5K		Relcon	07-10	£2.50
5K		Colvern	CLR2503	£3.00
10K	0.5	Beckman	A.	£3.00
10K	0.1	Beckman X.	A.	£3.50
10K	0.1	Colvern	CLR25/1001	£3.50
15K		Colvern	CLR2402	£3.00
18K		Beckman	A.	£3.00
25K	0.5	Helipot	SA J337	£3.00
29K	0.05	Beckman	SA1244	£4.50
30K		Colvern	2402	£1.50
30K		Beckman	SA95C	£3.00
30K		Beckman	A.85	£3.50
30K	0.5	Beckman	SA1692	£3.00
30K	0.25	Beckman	SA1679	£3.25
30K	1.0	Colvern	2402/1	£1.50
50K		Reliance	07-10	£2.25
50K		Colvern	07-5	£2.25
50K		Colvern	2503	£2.25
50K		Foxes	PX4	£2.25
50K	0.5	Beckman	A.	£3.00
50K	0.1	Beckman	A.	£3.50
100K/100K		Ford	A.	£5.00
100K	0.1	Beckman	A.	£3.50
100K	0.5	Beckman	A.	£3.00
100K		Colvern	2501	£2.25
100K		Colvern	2610	£2.50
298K	0.1	Beckman	8A3902	£3.50
300K	0.1	Beckman	A.	£3.50

THREE TURN 780° ROTATION

100/100	0.5	Beckman	C.	£3.00
100/100		Beckman	Type C	£3.00
300		Beckman	9303	£2.25
1K		Fox	PX2/H3	£2.25
10K	0.5	Beckman	C.55	£2.25
20K/20K	0.1	Beckman	C.S.	£3.00
10K/10K	0.1	Beckman	C.	£3.00
50K	0.5	Beckman	C.S.	£1.75

FIFTEEN TURN 5400° ROTATION

25K/25K		Beckman B.	10 watts	£6.50
46K/46K		Beckman B.	10 watts	£6.50

TWENTY TURN 7200° ROTATION

1 Meg.		General Controls	PXM130	£4.00
50K		Reliance		£2.00

156 TURN 56/60° ROTATION

460		Kevin Hughes	KTP0701	£9.50
-----	--	--------------	---------	-------

FIVE TURN 1800° ROTATION

200		Relcon	HEL07-05	£2.25
500		Colvern	F/11	£2.00
U1-5K		Colvern	CLR2505	£2.00
		Colvern	CLR2605	£2.00

FIVE-AND-A-HALF TURN

500		Colvern	2405	£2.00
-----	--	---------	------	-------

OUR STOCKS ARE CONSTANTLY CHANGING—PLEASE LET US KNOW YOUR EXACT REQUIREMENTS

COMPUTER ACCESSORIES

80 COLUMN HAND PUNCHES




Ideal for stock control, sales analysis, back-up in existing computer installations, DP training centres, schools, etc. New low cost model £59.50 plus carriage.

DE LUXE MODEL



incorporating tabulating mechanism. £79.50 plus carriage.

ELECTRIC HAND VERIFIER



£89.50 plus carriage.

All machines supplied with numeric keytops and dust-cover and covered by our three month guarantee. Delivery ex-stock. Optional extras alpha keytops and chip tray.

Special Computer Offer!

SAVE 75% OF LIST PRICE ON THIS DEC PDP SYSTEM

PDP-12C	4K CPU and Console
DF32	32K Disk and Control
DWO8A	1/0 Bus Level Converter
PC12 & PC05	High Speed Reader/Punch
BA12	Peripheral Expander
ASR33	Teletype
PT08C	Dual Channel Interface
KP12	Power Fail/Restart
AFO1A	A/D Converter/Multiplexer

• Fully maintained by DEC since new
• DEC maintenance available on resale
• Available in our showroom now
• Only three years old

Also available PDP 8F with ASR 33 £1150

TELETYPE PUNCH

BRPE High-speed punch. Self-contained, consists of punch unit, base, motor unit. For use in many data communication systems. Operating speeds up to 100 characters per second. (1100 words per minute). Available for punching 5, 6, 7, or 8 level codes, into 11" tape. Synchronous, parallel-wire input. £145



Models S110 and R82C, 17 char. per sec. Rebuilt, available from stock. £45.

ICT KEYBOARDS

In original packing—Numerical from £4.50

ICT KEYBOARDS

In original packing—Alpha-numeric Prices from £12.50

Magnetic Tape Transporters AMPEX TM4, TM2, TM7, FR300, IBM 7330, POTTER, ICL Magnetic Drums. From £75.

IBM PUNCH CARD EQUIPMENT FULLY GUARANTEED

024 Automatic alphanumeric keypunch	£340.00
026 Automatic alphanumeric printing keypunch	£820.00
036 Verifier features and operation same as 024, 026.	£380.00
082 Sorter 500 cards per minute are sorted.	£740.00

Carriage extra.

FREQUENCY CONVERTER MODEL B.40

50 KVA to 60 Hz power frequency converter. Fully overhauled. Specification: Prime Mover: Electric Motor Input: 220/380V 50Hz 3ph Output: 220V 60Hz 3ph at 50 KVA with PF of 0.8. PRICE £450.00

HEWLETT PACKARD DIGITAL RECORDER MODEL 565A

Data Entry, parallel to 11 columns, Print speed 5 lines per second. PRICE £85.00.

HEWLETT PACKARD SAMPLING OSCILLOSCOPE MODEL 185B

Including 187C. DC—100 Meg Hz. PRICE £395.00

PYE HIGH RESISTANCE OHMMETER MODEL 10B

Range from 0.3-20,000 Megohms in 4 ranges at 500V. Used for the measurement of components or circuits having high parallel capacitance. PRICE £20.00



MULLARD VALVE VOLTMETER MODEL E7555/2

PRICE £20.00

COLVERN DIGITAL CODERS (Shaft Digitisers)

Digital Coders are electromechanical devices, which give a unique parallel digital code output representing the angular position of the shaft. The current handling capacity is sufficient to operate relay decodes and indicators direct without intermediate stage of amplification. 3 size mag slip, 256 divisions, max. torque for reflected binary code 4.5 oz. ins. PRICE £10.00

WIDE RANGE OSCILLATOR TYPE 400C by DAWE

1 c/s-1,000 c/s. PRICE £35.00

FANS BY PLAINAIR

115V-3 Phase 400 c/s-11,000 rpm. Type 1PL41-234 PRICE £4.00

R.C. OSCILLATOR TYPE G432 by FURZEHILL

Square and sinewave. 250 Kc/s. PRICE £25.00

SPECIAL OFFER SPECTRUM ANALYSER HEWLETT PACKARD 8551B

10MHz-12GHz and 851B Extension to 40GHz. With W/G Mixers and very little used Ex Calibration Lab. £3,950.00.

VENNER 3334

Digital Frequency Meter 0-1MHz £45.00.



VENNER 3336

Digital Counter Six Digit 0-1MHz £55.00. With 15 Meg Counter extension for above £85.00.

DYNAMCO 2001



Digital Voltmeter 50µV-2KV 0.05% £175.00.

DYNAMCO type 2022S

Long scale D.V.M. and Ratiometer. The 2022 is a high accuracy long scale instrument operating on the potentiometric principle. It features a very high input impedance with exceptionally low current errors, an external scaling facility, seven operating modes and digital output.

Scale	39999
Range	10µV to 2kV
Resolution	1 part in 40,000
Accuracy Long term	±0.0025% of F.S.D.
	±0.01% of reading
 Optimum	±0.0025% F.S.D.
	±0.0025% of reading
Input impedance	>25,000 M ohm
C.M.R.	160 dB at DC
	120 dB at 50Hz

Typical £275.00

MEGGLER CIRCUIT TESTING OHMMETER

For Measuring conductor resistance. By Evershed and Vignale. £22.50.

BELL & HOWELL

5-12 and 18 Channel U.V. Recorder £395.00. 5-127 12 Channel £350.00.



ELECTRONIC BROKERS LIMITED
49/53 PANCRAS ROAD : LONDON NW1 2QB. Tel: 01-837 7781

ADD 10% VAT TO ALL PRICES

APPOINTMENTS VACANT


DISPLAYED APPOINTMENTS VACANT : £9.90 per single col. inch.
LINE advertisements (run-on) : 55p per line (approx. 7 words), minimum two lines.
BOX NUMBERS : 25p extra. (Replies should be addressed to the Box number in the advertisement,
 c/o Wireless World, Dorset House, Stamford Street, London, S.E.1.)
PHONE : Allan Petters on 01-261 8508 or 01-928 4597.
Classified Advertisement Rates are zero currently rated for this purpose of V.A.T.

Advertisements accepted up to
 12 p.m. Thursday, September 6th
 for the October issue subject to
 space being available.

Test Engineers meet the demands of advanced satellite technology

The exacting standards of satellite work and the diversity of our military communications and underwater weapons projects provides a stimulating environment for Test Engineers at the Applied Electronics Laboratories at Portsmouth.

You will be involved in a variety of interesting work including design investigation and calibration of complex electronic circuits covering digital, analogue, VHF and microwave equipment. The work is mainly concerned with one-off



prototypes, both detail and complete systems – it is closely allied to design.

We are looking for men with at least three years relevant experience. An HNC whilst desirable is not essential. Attractive salaries are offered dependent upon experience and qualifications. Relocation expenses will be met where appropriate.

Write with full details of career to date to Alan Barrett, Personnel Manager, Marconi Space and Defence Systems Limited, The Airport, Brown's Lane, Portsmouth PO3 5PH, quoting ref. LP/110/S

Marconi Space & Defence Systems

A GEC-Marconi Electronics Company

2948

SOUND ENGINEER

ITN have a vacancy for a Sound Engineer to maintain a wide variety of sound equipment, including sound mixing desks, film and tape recording machines, film projectors and associated equipment.

Applicants should be experienced in this field, and be prepared to work either a five day week or on a shift pattern.

Contributory Staff Pension Scheme. Free Life Insurance. Four weeks holiday. Subsidised staff restaurant.

Telephone: Personnel 01-637 3144

2947

ELECTRONIC ENGINEER

Recording Studio of major Record Company is looking for an Electronic Engineer with excellent knowledge of advanced transistor techniques and a degree of experience in the audio field. High qualifications essential.

POLYDOR RECORDS STUDIO
 LONDON 01-499 8686 ext 51

[2009

There is scope,
variety and
responsibility as a

Radio Technician

Join the National Air Traffic Services of the Civil Aviation Authority as a Radio Technician and you have the prospect of a steadily developing career in a demanding and ever expanding field.

ENTRANCE QUALIFICATIONS

You should be 19 or over, with at least one year's practical experience in telecommunications. Preference will be given to those having ONC or qualifications in Telecommunications.

Once appointed and trained, you will be doing varied and vital work on some of the world's most advanced equipment including computers, radar and data extraction, automatic landing systems, communications and closed circuit television.

Vacancies exist at locations near London (Heathrow), London (Gatwick) and Stansted Airports and for suitably qualified people at the Signals Training Establishment, Milton Keynes, Bucks.

Salary: £1383 (at 19) to £1836 (at 25 or over); scale maximum £2158 (higher rates at Heathrow). Some posts attract shift-duty payments. Promotion prospects are excellent and ample opportunity and assistance is given to study for higher qualifications.


To: Mrs Pat Norton, Civil Aviation Authority, Room 518, Aviation House, Kingsway, London WC2B 6NN.

Please send me application form for entry as Radio Technician.

Name _____

Address _____

ww/1



National Air Traffic Services

Installation Engineers

Our increasing order book makes it necessary to recruit Installation Engineers to work on a variety of assignments both installing and commissioning the complete range of the Company's products. The assignments, which may be in the U.K. or abroad, can range from independent long term maintenance tours to attachments to large teams involved in complete systems projects.

The range of Company products covers the whole spectrum of communication systems, but of particular interest would be engineers with experience in the following: Line-of-Sight, Tropospheric Scatter Systems, Message Switching, T.V. and Radio Broadcasting.

Microwave Development Engineering

High calibre engineers are required to join existing teams working on the development of microwave equipment for tropo scatter systems. Previous experience of designing UHF or SHF mixers and up-converters or similar microwave circuits is essential.

HF Communications Engineering

Vacancies also exist for engineers to join small teams currently developing a comprehensive "state of the art" HF Communications System. A minimum of 4 years' experience is required in the mixer, oscillator, amplifier or digital circuitry fields for high performance HF ISB receivers, transmitter drives and wide band amplifiers.

The successful applicants will probably already be working in these fields and be qualified to at least HND level. They will be expected to make an immediate contribution to the Company's current projects and are therefore unlikely to be under 25.

To remain in the forefront of communications technology, the Company operates forward looking personnel policies and pays competitive salaries. The practice of internal promotion further ensures opportunities for progress in both engineering, management and specialised fields of communication development.

Applications giving a summary of experience to date, age and qualifications should be addressed to: Huw Jones, Personnel Officer, Marconi Communication Systems Ltd., New Street, Chelmsford, CM1 1PL. Tel: Chelmsford 53221 Ext. 251.

**Marconi
Communication
Systems**
A GEC-Marconi Electronics Company

FLIGHT SIMULATOR ENGINEER


£2612 - £2666 + Shift Allowance

BEA British Airways require experienced Flight Simulator Engineers for shift duties at their Training Centre, Heston.

Qualifications required are a recognised engineering apprenticeship, or equivalent standard of training, and theoretical knowledge to HNC standard in electronic engineering.

Applicants with 3-5 years practical experience in analogue computing, digital computing and closed loop television, together with a knowledge of aircraft systems and principles of flight, are requested to write or phone for an application form to:-

Personnel Officer (Flight Operations), BEA — British Airways, Room 1119 Queens Building, London Heathrow Airport, Hounslow, Middlesex 2987
01-759 3131 ext. 2769



Receiver Technician

BBC requires a Technician in their Receiver Section at Balham. The duties include the overhaul, maintenance and installation of colour television and stereo receivers which are used for critical appraisal of technical quality and programme content. The Technician will be in direct contact with senior members of the public and the Corporation.

Candidates should have a good general education which must include a science subject and have, or be studying for, an appropriate technical qualification. They must have several years' experience in television and sound receiver servicing and should be physically fit and able to work at roof height. A good personality and the ability to be tactful when working under pressure is essential. Candidates must possess a current driving licence.

Applicants who do not satisfy the requisite qualifications will be considered if they are able to demonstrate exceptionally useful experience and satisfactory knowledge at a selection board.

From 1st October appointment will normally be made in the salary range £1803-£1989 according to qualifications and experience. Technicians can progress to a roof salary of £2565. Requests for application forms to **The Engineering Recruitment Officer, BBC, Broadcasting House, London W1A 1AA quoting reference no. 73.E.4170WW and enclosing addressed foolscap envelope. Closing date for completed application forms 14 days after publication.**

[2994



UNIVERSITY OF DURHAM
INSTITUTE OF EDUCATION
Colleges of Education

TECHNICIAN

Closed Circuit Television Recording Unit

A Technician is needed to assist the Senior Engineer in the maintenance and operation of a well-equipped Mobile Closed Circuit Television Recording Unit serving a number of College of Education in the area, and based at Neville's Cross College, Durham. Recordings are made throughout the County. Applicants should have a basic general knowledge of television techniques and equipment. Ability to drive is essential.

Salary: Local Authority Scale T5: £1,803 to £2,100 (due for early revision), with initial placing according to age and qualifications. Conditions of service will be those applicable in a College of Education. The appointment is tenable from 1st October 1973 or as soon as possible thereafter.

Applications, including the names of two referees should be sent to the Secretary, University of Durham, Institute of Education, 48 Old Elvet, Durham, not later than Friday, 14th September, 1973.

[2975

SPANISH COMMUNICATIONS EQUIPMENT MANUFACTURER

Has an immediate opening for
An experienced Design and Development Engineer for Audio Equipment, including Highly Professional Mixing Desks, Compressors, Limiters, Audio Monitoring Amplifiers, etc. Systems Experience is desirable.

Salary open.

Send resumé to:
NORTRON
Fernando el Católico, 63
Madrid 15
SPAIN

[2540

ENGINEERS

Thames Television have vacancies for Engineers at their Teddington Studios in Middlesex.

The successful applicants will assist with specific duties in our engineering complex, involving the maintenance and operation of video-tape, teletext, master control and central apparatus room equipment.

Applicants, aged between 20 and 30, should have general engineering experience, a basic knowledge of electronics and be educated to O.N.C. level or equivalent. Initiative and a keen interest in television engineering are essential personal characteristics.

The salary for this position will be in the range of £2,100 per annum to £3,000 per annum, depending upon experience. Other benefits include an excellent pension scheme, good restaurant facilities and an active sports and social club.

Written applications should be addressed to:
The Staff Relations Officer, Thames Television Limited

Teddington Lock
Teddington
Middlesex 2902

THAMES

Electronics Appointments Register

We can get you a better job than you can get yourself.

The best jobs don't necessarily appear in the sits. vac. columns.

They are often to be found in the Electronics Appointments Register.

Our individual approach gives you a wider choice—we have lots of jobs on our specialised registers and we may well have one tailor-made for you.

The service is absolutely free to you and completely confidential.

In effect we offer you the chance to find your ideal job, all for the cost of a phone-call.

So capitalise now on your specialised knowledge.

Call 01-734 6536, or fill in the coupon and we will send you an enrolment form by return of post.

Please send me details of how to enrol on one of your Appointments Registers:

Name _____

Address _____

Post to G.A.R. 76 Dean Street London W1 01-734 6536.

ww2

Graduate **A**ppointments **R**egisters

CHARING CROSS HOSPITAL (FULHAM)
Fulham Palace Road, Hammersmith, London,
W6 8RF.

ELECTRONICS TECHNICIAN —PATIENT MONITORING

Applications are invited for a post on the technical staff of this newly built and equipped hospital. The work involves the installation and maintenance of patient monitoring equipment on a new unit.

Applicants should have HNC or higher qualification with a minimum of three years experience, two of which should have been completed on similar work in the Health Service.

Salary on Physics Technicians grades scale £1209-£2076 plus London Weighting. 38-hour week, superannuable post. Excellent social/sport facilities including swimming pool, squash courts, bar, etc.

Applications to Mr. C. Hill, Personnel Department, telephone 01-748 2050 ext. 2992. Completed forms giving names of two referees should be returned by 3rd September, 1973.

[2914

C S L

EXPERIENCED REPAIR AND CALIBRATION ENGINEERS

EARN UP TO £2,700 P.A.
ATCSL

Our premium rates for non-standard working hours make these earnings possible without excessive overtime.

We are one of the leading Repair and Calibration Companies with a consistently good growth record and in the process of still further expansion.

We offer stimulating and rewarding work to Engineers with a sound knowledge of circuitry and with some experience of one or more types of equipment in the range d.c. to microwaves, analogue or digital.

To find out more about job opportunities in our Company contact

The Technical Manager,

CALIBRATION SYSTEMS LTD.
Blackwater Station Estate, Camberley, Surrey
Tel. Camberley 28121

2932

Electronics Engineers

lecture on computer servicing.

International Computers Limited, Europe's leading computer company, is looking for Electronics Engineers to teach the practicalities of computer servicing. At the largest training centre of its kind in Europe, ICL will first of all ground you in computer technology and education training, and then ask you to train customer engineers to such a standard that they will be able to maintain computers at optimum operational specification.

We are looking for a thorough electronics competence and the ability to put across your own first-rate knowledge. Ideally, you will have an HNC or Forces' training in electronic engineering and at least three years'

experience, preferably in digital electronics or computers.

You will be based at the training centres in either Letchworth, Herts or Feltham, Middlesex. Salaries will be good. ICL depends on talent and rewards it accordingly. You will be encouraged and expected to progress; your development could be throughout the ICL group.

For an application form, write to A. E. Turner, quoting reference WW463C at International Computers Limited, 85/91 Upper Richmond Road, Putney, London SW15 2TE.

International Computers



think computers--think ICL

UNIVERSITY OF BATH School of Engineering

Applications are invited from suitably qualified persons for a post in charge of the instrumentation service (research and teaching) in the School.

Research covers a wide range of activities in the fields of Applied Mechanics, Aerodynamics, IC Engines and Turbomachinery, Structures, Production and Fluid Power Systems, supported by up to date electronic equipment currently valued at approximately £150,000 including an on-line computing facility.

The undergraduate course involves a final year project which generally requires electronic support.

Experience in the fields of computer interfacing, data acquisition systems and general electronic instrumentation would be most relevant.

The salary offered for this appointment will be at a point in a range not exceeding £3,200.

Applications giving full particulars of age, experience, qualifications and present salary together with the names of three referees should be sent to Registrar (S), The University, Bath, BA2 7AY, quoting reference 73/112. [2979

BERRY'S RADIO

has vacancies for

- (a) SENIOR SALESMEN
- (b) SENIOR ENGINEERS

TOP RATES OF PAY

5-DAY WEEK ● PERMANENCY

Apply: Mr. K. (405-6231)
319 High Holborn, London WC1

[97

Storno

RADIO COMMUNICATION SYSTEMS

We have vacancies for:

SERVICE TECHNICIANS

based at Camberley, to work in a specialised Department dealing with miniaturised transmitter/receivers on fault diagnosis and correction. Technical experience of communications systems is an advantage.

FIELD SERVICE ENGINEERS

in the Greater London Area. Applicants should have experience in fault finding and testing of UHF/VHF radio equipment. Current driving licence essential, company vehicle provided.

The Company has much to offer those who are interested in the sophisticated, modern world of radiotelecommunications and who can demonstrate their ability in this field.

Please contact:

**The Personnel Officer,
STORNO LTD.,
Frimley Road, Camberley, Surrey.**

Telephone: 0276 29131

2924

UNIVERSITY COLLEGE LONDON

Audio Visual Unit TECHNICIANS

The Audio Visual Unit provides audio-visual equipment, facilities and expertise to all departments of the College, and operates a television studio equipped with Link cameras.

Senior Audio Visual Technician (Grade 5)

He will have overall responsibility for the running of the Unit, carry out first-line servicing of all equipment, participate in the design and presentation of television programmes and be responsible for the technical aspects of this work. Salary: in the range £2,056-£2,416 including London Weighting.

Audio Visual Technician (Grade 2B)

Duties will include operation of V.T.R.'s, T.V. cameras, sound mixers, audio tape recorders, film and slide projectors; routine maintenance. Salary: range £1,591-£1,846 including London Weighting.

Further details and application forms from: Personnel Officer (Technical Staff), (WW), University College London, Gower Street, WC1E 6BT.

[2963

University of Surrey Television Service

SENIOR ENGINEER

(Technician Grade 5 £1,881-£2,241)

The Television Service is an integral part of the Audio Visual Aids Unit which provides services for teaching and research illustration throughout the University. The television equipment includes a most versatile mobile control room handling three Plumbicon studio cameras and five others. The Senior Engineer will be responsible to the Chief Engineer/Operations Manager and will assist with the operation and maintenance of all CCTV equipment including IVC video-tape recorders and Philips Plumbicon cameras.

The minimum qualification is HNC in electronics or electrical engineering or an appropriate training in the BBC or a programme company. Experience in educational television is desirable.

Applications are invited immediately on forms which may be obtained from the Assistant Secretary (Personnel), University of Surrey, Guildford, Surrey. Previous applicants need not apply. Tel: Guildford 71281 Ext. 452.

Closing date: 3 September 1973. [2955

ELECTRONICS ENGINEER

Qualified Engineer required for interesting work on a wide range of devices and systems used by and for blind people.

A sound basic knowledge of analogue and digital techniques, together with several years experience in a field of design, development and maintenance is necessary. Some experience of light electro-mechanical devices would be an advantage.

Apply: Personnel Officer, The Royal National Institute for the Blind, 224 Gt. Portland Street, London W1N 6AA.

[2953

Devices

SERVICE ENGINEER (ELECTRONICS)

Required for a Company situated in a modern new factory in Welwyn Garden City, Hertfordshire. The position involving a variety of interesting duties associated with the servicing of electronic medical equipment.

Applicants should have some previous experience in electronic servicing and full product training will be given.

A company car will be provided which may be used for private use.

Write or telephone the following:—

**Personnel Manager,
Devices Instruments Ltd.,
Hyde Way,
Welwyn Garden City,
Herts.**

Tel: 28511 Ext. 18.

2956

Senior and Junior Electronic Engineers

Vacancies exist in our new Design Laboratories at Leicester for the following:

Engineers for Tape (cassette and cartridge) equipment, mainly 'in car' entertainment.

Engineers for Audio and radio equipment for the domestic market.

Electro-mechanical Design Draughtsmen.

Applicants will have several years experience of circuit design, preferably in the fields of audio equipment or electronic instrumentation and possess a degree or H.N.C. qualification or equivalent.

Salaries for the above posts are negotiable and will reflect the importance attached to the positions. Applicants are invited to write or telephone for an application form to:

**The Personnel Officer,
Decca Radio & Television
Golf Course Lane,
Hinckley Road,
Leicester.
Tel: 0533 872101.**

DECCA

Electronics Development Engineer

IMRC is a leading company involved in the design and supply of radio communications equipment to the merchant shipping industries of the world.

We require an engineer to join our development team working on new transmitter and receiver design projects.

Applicants should have a sound knowledge of circuit design for communications equipment and ideally will have spent some time working on projects in the M.F. and H.F. bands. They should be qualified to H.N.C., or degree standard, but ability and experience will be our major concern.

Please write, with brief details of your experience and qualifications, or telephone to:—

**Personnel Manager,
International Marine Radio Company Limited,
1 Peall Road, Croydon CR9 3AX.
Tel: 01-684 9771**

2864

ITT Marine

RADIO OFFICERS would you come ashore for £2,300 a year?

As a Radio Operator with the Post Office Maritime Service you can continue your career ashore in an interesting and expanding service. And earn over £2,000 a year, including compulsory pension contributions, at 25 years of age working only a 41-hour week of shift duties — with overtime this could rise to £2,300 and possibly more.

Post Office Radio Operators benefit from a shorter pay scale than sea-going officers. You have good opportunities for promotion to positions earning basic salaries of up to £3,290, and prospects of further advancement into Post Office Senior

Management.

To apply you need to be 21 or over and to hold a 1st class or General Certificate issued by the MPT or an equivalent certificate issued by a Commonwealth administration or the Irish Republic.

If you would like to know more, please write to the Inspector of Wireless Telegraphy, Post Office, IMTR/WTS1.1.3, Union House, St. Martin's-le-Grand, London EC1A 1AR. L 51

**Post Office
Telecommunications**

91

SPANISH COMMUNICATIONS EQUIPMENT MANUFACTURER

Applications are invited from qualified design engineers specialized on:

- a) Ground/Air Communications
- b) TV Colour Transmitters
- c) Side Band Transmitters

At least 5 years experience desirable. Company located in Madrid. Salary open.

Send resumé to:

NORTRON
Fernando el Católico, 63
Madrid 15
SPAIN

[2539

EAST AFRICAN POST & TELECOMMUNICATIONS ASSISTANT ENGINEERS

Required to undertake appropriate duties in the following fields based in Kenya or Tanzania:-

- (1) Radio Construction and Surveys
- (2) Radio Maintenance UHF/VHF Systems
- (3) Radio Construction Microwave Systems (Clerks and Works)

Candidates, over 25 years, must possess the City & Guilds Intermediate Certificate in Telecommunications and have at least 7 years' relevant experience.

Salary will be in the range of £2310 to £3110. A generous gratuity is also payable. Because of lower rates of Income Tax in Kenya, for example, the gross emoluments are roughly equivalent to a UK salary of 3450 to 4250 for a single man and £3600 to £4650 for a married man with 2 children.

Other benefits include: Subsidised Accommodation; Education Allowances; Free Family Passages; Holiday Visit Passages; Appointment Grant £100-£200 Normally Payable; 24 Month Tour.

The post described is partly financed by Britain's programme of aid to the developing countries administered by the Overseas Development Administration of the Foreign and Commonwealth Office.

For further particulars you should apply giving brief details of experience to:

crown agents

M Division, 4 Millbank, London SW1P 3JD, quoting reference number M2K/730669/WF.

[2985

Electronics Engineers up to £4,000

Many jobs which would suit you down to the ground - either in the U.K. or overseas - are never advertised. Yet it will cost you nothing whatever to give yourself the opportunity to be considered for them. Join the Lansdowne Appointments Register - used by hundreds of employers to select electronics engineers. You have nothing to lose, everything to gain - and it's all conducted in strict confidence. So post the coupon - find out exactly how you can make use of a service which is all the more valuable for being free!

To: The Registrar, Lansdowne Appointments Register, Design House, The Mall, London W5 5LS. Tel: 01-579 6585 (anytime - 24 hour answering service).

Please send me further details.

Name

Age (20-45 only)

Address

WW 20 / 8
Lansdowne
Appointments Register
2939

THEATRE PROJECTS SOUND LIMITED

a member company of the Theatre Projects Group which operates a recording studio, large sound equipment hire and consultancy business requires an

AUDIO ENGINEER

The successful applicant will take responsibility for the maintenance and development of equipment in the studio and dubbing complex and in the hire department. H.N.C. or degree in an appropriate subject is essential.

Salary will be in the range of £1,900-£2,300 depending on experience in this field.

Apply in writing to:
THEATRE PROJECTS SOUND LIMITED
10 LONG ACRE, LONDON, W.C.2
or telephone 01-836 1168

[2958]

UNIVERSITY OF BATH Educational Services Unit

TECHNICIAN

Closed Circuit Television

The successful applicant for this position will service the television and film equipment in the Unit, and would also be expected to assist in productions. Previous experience in television servicing and qualifications to O.N.C. or equivalent is desirable.

The starting salary will be within the range £1,416-£1,794 according to qualifications and experience.

Application forms and further particulars are available from The Registrar (S), University of Bath, Claverton Down, Bath BA2 7AY and should be returned as soon as possible quoting reference 73/99.

[2976]

The best young Engineers have computers in mind.

Are you aged 21 to 25?

Do you want a flying start to a career in computers? Here is your chance. Train as a Field Engineer with ICL, Europe's leading computer manufacturer.

Training

You will be given thorough training on ICL electronic equipment leading to computers.

Qualifications

You should be aged between 21 and 25 and be on your final year or have attained City & Guilds electronic certificates or an HNC in electronics. You should have completed an electrical engineering apprenticeship or have at least two years' industrial experience on electronics.

Job satisfaction

As an ICL Field Engineer you have a high degree of responsibility for a customer's installation. You need technical expertise, tact and personality. So you are important as a representative of ICL.

There are opportunities of starting with us in several areas in the UK. Get the full details now by completing and returning this coupon today.

To: Mr A E Turner, International Computers Limited, 85/91 Upper Richmond Road, Putney, London SW15 2TQ.

Please send me an application form for job openings in Field Engineering.

Name

Address

International
Computers



(WW8)

Microwave Engineers

Here is a unique opportunity to join one of the leading British Microwave Laboratories in the U.K. Due to increasing work load we require qualified engineers with up to three years relevant experience to work in the following areas:

- Aerial and Feeder System Design.
- Filters and Multiplexers.
- Semi-conductor applications.
- Microwave integrated circuits and sub systems.

We have a well equipped laboratory, which uses network analyser techniques, swept-frequency test benches and computer-aided design. In addition we have a fully equipped aerial site capable of dealing with a wide range of aerial problems from V.H.F. to Microwave.

Some vacancies also exist for new graduates.

Write or telephone, giving brief details of experience to: **Mr. J. Morrison, Personnel Officer, EMI Electronics Ltd., Victoria Road, FELTHAM, Middx. Tel. 01-890 3600 Extension 44.**



International leaders in Electronics.
Records and Entertainment.

MILLBANK ELECTRONICS GROUP

BELLBROOK ESTATE, UCKFIELD,
SUSSEX TN22 1PS
Tel: Uckfield (0825) 4166

DEVELOPMENT ENGINEER

Preferably with two to three years experience in the development of audio equipment. Must be capable of working on own initiative.

TEST ENGINEER

Experienced in the testing and servicing of audio power amplifiers, mixers and associated equipment.

INVENTORY CO-ORDINATOR

This position would be suitable for a person interested in component buying, stock control and stores handling. Previous experience in the latter desirable.

★ Salaries for the above Staff positions are negotiable depending on qualifications and experience.

ALL STAFF POSITIONS WITHIN THE GROUP CARRY FULL BENEFITS INCLUDING MEMBERSHIP OF PRIVATE MEDICAL SCHEME.

If you are interested please apply in writing enclosing curriculum vitae to Mr. Keith Goodsell—Production Manager.

[2962

The European Organisation for the Safety
of Air Navigation

EUROCONTROL

SEEKS

Computer and Display Systems Maintenance Engineers

for the new Air Traffic Control Centre
at Karlsruhe (Germany)

Qualifications and Experience: H.N.C. or equivalent with experience in the field of digital electronics.

Language ability: Candidates must have a good command of English and a basic knowledge of German. Some French and/or Dutch would be an advantage.

Age: 25 to 40 years.

The posts will involve shift work.

Salary, allowances and social security arrangements correspond to those of the European Communities.

Further particulars and application forms may be obtained from:

EUROCONTROL
Rue de la Loi, 72,
1040 Brussels,
BELGIUM

[2960

Radio and Electronic Interference



Internationally recognised for its work on electromagnetic interference problems, the ERA Industrial Applications Department undertakes an extensive programme of contract research, providing clients with, among other services, a wide variety of interference research and measurement facilities. The current research programme covers investigations on a wide range of electromagnetic interference topics but is primarily concerned with the interference characteristics of electrical and electronic equipment and systems from avionics to computers, and techniques of measurement.

We are now seeking to strengthen the existing team by the appointment of at least two additional engineers or physicists.

The successful applicants will possess a relevant degree or HNC with emphasis on electronic engineering or telecommunications. They must have a practical approach to problems and have an interest in, and preferably experience of, r.f. techniques. However those recently qualified with an interest in radio, electronics or communication will be considered. We will be looking for evidence of ability to write clear, concise technical reports.

Commencing salary will be assessed primarily on experience. All salaries are reviewed annually to match performance and ERA offers full scope for career development in a rapidly expanding field.

Company benefits include a contributory pension scheme, and re-location assistance where applicable.

Please write to, or telephone for application form:

Personnel Manager, Electrical Research Association, Cleeve
Road, Leatherhead, Surrey. Leatherhead 74151 2967

cadac

The company specialise in the design and production of sound control equipment for the recording industries.

With the continued expansion of the company, vacancies arise for the following:

SENIOR TEST ENGINEER TEST ENGINEERS

Applicants should have a theoretical knowledge of electronics and/or experience in studio engineering techniques and practices.

It would be preferable that the Senior Test Engineer has had studio experience.

Salaries by negotiation and to be commensurate with that of the position.

Apply to:

**Cadac (London) Ltd.,
Lea Industrial Estate,
Batford,
HARPENDEN
Herts.**

Tel: Harpenden (STD 05827) 64698

2925

T.V. Studio Engineer

The Road Transport Industry Training Board has in operation at its Wembley Headquarters, a three camera broadcast-quality colour television studio with full telecine and video recording facilities, which includes RCA TR 50 and 1" Helical Scan systems. We now wish to appoint an experienced studio engineer to join a small team working on the production of training and educational television programmes.

The applicant should not be less than 24 years of age and have a good working knowledge of the above equipment. Salary will be negotiable depending on qualifications and experience. Three weeks holiday, contributory pension and life assurance scheme.

Please send all relevant personal history stating how the above requirements are met, and quoting reference ZH.319, to:

**Mrs. H. M. Brown, Personnel Manager,
Road Transport Industry Training Board,
Capitol House, Empire Way,
Wembley, Middlesex, HA9 0NG.**



Installation Technician

**Capital Projects Department
London c.£2000**

The BBC Studio Capital Projects Department has a vacancy for an Installation Technician. The successful candidate will be employed on the provision of Television or Sound originating or recording equipment for both Studio and outside use.

He will assist Engineers in the preparation and requisitioning of schedules of equipment, preparation of installation information and the on site supervision, testing and commissioning of installations. An important part of his duties will consist of liaison with clerks-of-works, contractors, foremen, etc.

Applicants should have some years' experience of electronic test equipment, workshop and drawing office practice. An academic training to O.N.C. level or equivalent qualification is desirable, as is relevant experience of the manufacture, operation and maintenance of video, audio, recording or communications equipment.

The post is based in London but some travelling is required. Salary, according to experience, will be initially between £1908 and £2118, rising by annual increments to a maximum of £2805. These salaries are under review.

Requests for application forms to **The Engineering Recruitment Officer, BBC, Broadcasting House, London W1A 1AA**, quoting reference no. 73.E.4164/WW and enclosing addressed foolscap envelope.



Closing date for completed application forms 14 days after publication.

2949

OPPORTUNITIES IN DESIGN


Electronic Design Engineers

Cambridge Scientific Instruments require an engineer to join their electronics development group. His job will be the design and development of circuitry to be used in conjunction with electron optical instruments for which the Company is world famous. Due to the complex nature of these instruments, the scope of the work is varied, offering opportunities to work with many types of circuitry.

A knowledge of the application of digital and analogue integrated circuits is required and experience is desirable.

A competitive salary is offered dependent upon age and experience.

Applications should be addressed to:



**D. E. Pickett, Personnel Manager
Cambridge Scientific Instruments Limited,
Chesterton Road, Cambridge CB4 3AW.
Tel: 61199**

2903

SPANISH FIRM NEAR MADRID

is looking for design and development engineers with a minimum of three years of experience in the field of P.C.M. equipment to be used by the telephone industry.

Areas of interest are encoders and decoders, P.C.M. multiplexers and R.F. equipment to transmit P.C.M. data.

Salary open.

Send résumé to:

NORTRON
Fernando el Católico, 63
Madrid 15
SPAIN

2584

Are you interested in
**Communal Aerial Television
 Systems Work?**

Then read on further.....

Due to continued expansion, EMI Service, part of EMI's Electronics and Industrial Operations group of Companies, has the following vacancies for engineers at Hayes, Middlesex.

SERVICE ENGINEERS
 required for bench and field work on Communal Television Aerial equipment. Must be capable of diagnosing faults and repairing wide range of aerial amplifying and distribution equipment.

SYSTEMS PLANNING ENGINEERS
 for the planning of Communal Television Aerial installations. Previous experience required to be capable of producing practical plans from building details and subsequently setting to work after installation.

Attractive starting salaries. Contributory Pension Scheme. Assistance with removal expenses in appropriate cases.

WANT TO TAKE THINGS FURTHER
 then write or telephone for an application form to:
R. N. L. Black, Personnel Department, EMI Limited, 135 Blyth Road, Hayes, Middlesex. 01-573 3888, Ext 2887.



International leaders
 in Electronics, Records
 and Entertainment.

**University College Hospital
 Medical School.**
 Department of Clinical Pharmacology,
 Neuropsychology & Metabolism
 Research Unit,
 Friern Hospital, London, N.11.

**ELECTRONIC
 TECHNICIAN**

to assist in the setting-up and subsequent running of a new research laboratory. Some experience with recorders, E.C.G., E.E.G. and data processing equipment desirable.

Applicants should have a minimum of O.N.C. in electrical or electronic engineering or a similar equivalent qualification.

The salary is on the Whitley Council scale according to age and experience, commencing at £1335 + London Weighting.

Applications before 31st August.

[2906]

FIELD SERVICE ENGINEERS

You've experience of things electro-mechanical, you're properly trained, you work in London, and they still won't pay you more than £2,000 p.a.

Our clients will!

Ring David Hilton 01-637 0781

ATA SELECTION
 209b Gt. Portland Street
 London W.1.

[2928]

**Airline
 Radio Technicians**

We require fully-trained and high-skilled Radio Technicians to work on the repair and overhaul of radio/radar equipment at Heathrow Airport (London). A high standard of theoretical knowledge is essential and at least 5 years' experience in radio maintenance. An approved apprenticeship is desirable.

Starting pay is £36.74 per week, plus shift allowance.

Additional benefits include a contributory pension scheme, sports and social facilities and opportunities for concessional holiday air travel worldwide.

Applications giving details of age and experience, quoting reference 68/WW/BW to:

Manager Selection Services
BOAC
PO Box 10
Heathrow Airport (London)
Hounslow TW6 2JA

2966

**ST. BARTHOLOMEW'S HOSPITAL
 LONDON, E.C.1**

Applications are invited from

PHYSICISTS or

ELECTRONIC ENGINEERS

to work as a

RESEARCH ASSISTANT

in the

DEPARTMENT of NEUROLOGY

The successful applicant will be expected to develop and assist in the evaluation of further instrumentation required for research into voluntary control of muscle action. There will be close liaison with the Department of Medical Electronics and the research work undertaken may be considered for a higher degree.

The appointment will be on the scale £1,335—£1,761 plus £126 London Weighting. Applications with the names of two referees to Personnel Department, quoting reference R/3679/WW

[2989]

British airways

THE STOCK EXCHANGE
require an additional
**TELEVISION
SERVICE
ENGINEER**

to maintain information display systems.

Applicants must possess appropriate television and radio servicing certificates and must be able to prove their ability as competent Service Engineers by a suitable trade test.

An attractive starting salary is offered. In addition, there is a non-contributory pension scheme, 3 weeks holiday in a full year and Luncheon Vouchers.

Applications giving brief details of qualifications and experience should be sent to:

Personnel Officer,
Council of The Stock Exchange,
The Stock Exchange,
London EC2N 1HP

[2926]

**UNIVERSITY OF LIVERPOOL
SCHOOL OF EDUCATION**

**TECHNICIAN
(AVA and CCTV)**

Applications are invited for the above post to have overall responsibility for the AA and CCTV provision in the School.

Applicants should be qualified and experienced in the fields of electronics and Audio Visual Aids and be capable of working on their own initiative and supervising other technicians.

This is a new post with interesting possibilities of developing new forms of work in the field of Educational Technology.

Salary within a range up to £2,241 per annum according to qualifications and experience.

Further particulars and application forms may be obtained from the Registrar, The University, P.O. Box 147, Liverpool L69 3BX. Quote ref. RV/WW/80410.

[2952]

**HAMILTON COLLEGE OF
EDUCATION**

require a

**TELEVISION
ENGINEER
(COLOUR UNIT)**

to join a team engaged in the operation, maintenance and development of the College service. At present the service consists of a two channel colour mobile control room with distribution facilities within the College.

Experience in video tape recorders and/or colour cameras and monitors an advantage.

Normal colour vision and driving licence essential. Annual leave will be 4 weeks.

Salary will be in the range £1530 - £2100 (N.J.C. Grade IV, V and VI) depending on qualifications and experience. (Salary scales are at present under review).

Further information and application forms may be obtained from the College Secretary with whom completed applications must be lodged not later than Friday, September 7th, 1973.

College of Education,
Bothwell Road, Hamilton, Lanarkshire,
ML3 0BD.

[2992]

Electronics Test Engineers

Pye Telecommunications of Cambridge and Haverhill have immediate vacancies for Production Test Engineers. The work entails checking to an exacting specification VHF/UHF radio-telephone equipment before customer delivery; applicants must therefore have experience of fault finding and testing electronic equipment, preferably communications equipment. Formal qualifications while desirable, are not as important as practical proficiency. Armed service experience of such work would be perfectly acceptable. Pye Telecommunications is the world's largest exporter of radio-telephone equipment and is engaged in a major expansion programme designed to double present turnover during the next five years. There are, therefore, excellent opportunities for promotion within the company. Pye also encourages its staff to take higher technical and professional qualifications.

These are genuine career opportunities in an expansionist company, so write or telephone without delay for an application form to:

Mrs A E Darkin at
Cambridge Works, Elizabeth Way, Cambridge CB4 1DW.
Telephone: Cambridge 51351.
or Mrs C Dawe at
Colne Valley Road, Haverhill, Suffolk.
Telephone: Haverhill 4422.



Pye Telecommunications Ltd

A member of the Pye of Cambridge Group

96

WORK AS A RADIO TECHNICIAN

ATTACHED TO SCOTLAND YARD

You'd be based at one of the Metropolitan Police Wireless Stations. Your job would be to maintain the portable VHF 2-way radios, tape recorders, radio transmitters and other electronic equipment which the Metropolitan Police must use to do their work efficiently. We require a technical qualification such as the City & Guilds Intermediate (telecommunications) or equivalent.

Salary scale: £1415 to £1715 according to age from 21 to 25, to a maximum £2025 p.a. (plus a London Weighting Allowance of £175 or £90 p.a.).

Promotion to Telecommunication Technical Officer will bring you more.

For details of this worthwhile and unusual job write to: Metropolitan Police, Room 733 (RT/WW), New Scotland Yard, Broadway, London, SW1H 0BG, or telephone 01-230 3122 (24-hour service).

[2917]

Applications Engineer

Telecommunications

An unusually interesting new appointment is available with this growing international company for a young graduate engineer, familiar with telecommunications practice generally and in particular with cables and accessories used in telephone and telegraph systems. Design experience with a cable manufacturer and/or the Post Office would be ideal.

He will be based in the Company's newly formed Communications Products laboratory at Harlow, Essex. There will be considerable European involvement, including some travel, and knowledge of a second European language would be an asset.

His prime function will be to reconcile the Company's innovations in the telecommunications field with individual national specifications in Europe, in order to provide acceptable systems to users (primarily telephone authorities). Having interpreted customer needs he will devise and apply appropriate tests and where necessary adapt or modify products to meet them.

Working largely without supervision, he will need to think clearly and to express himself fluently - a practical man who can prepare engineering drawings and fit readily into a well experienced and professional European team.

There will be a good starting salary and a full range of employee benefits. Opportunities for career development are first class in this highly diversified organisation.

Write, in confidence, with concise details to:

D. J. Stuckey (Ref: GE)
3M United Kingdom Limited,
3M House,
Wigmore Street,
London W1A 1ET.



**Victoria Hospital,
Blackpool**

Medical Physics Technician Grade III

Required to work on his own initiative but as a member of the Regional Physics Department and in collaboration with the Engineer's Department and Clinical Departments at Victoria Hospital, Blackpool.

This is a new post and is backed by an experienced team of Technicians together with access to the facilities of the Regional Physics Laboratory at Christie Hospital, Manchester.

Duties will include the maintenance and servicing of patient orientated electronic and electro-medical equipment to ensure correct functioning and patient safety and will initially focus on equipment in the Departments of Cardio-Thoracic Surgery and Cardiology. There is scope for the expansion of duties and, depending on the interests and capabilities of the person appointed, some development work. There is a possibility of eventual promotion to a higher grade.

Applicants should hold O.N.C., H.N.C. on a higher qualification together with a minimum of either three years experience as a Medical Physics Technician IV or V or six years relevant technical experience.

Normally the starting salary will be £1,602 rising by seven annual increments to £2,076 (Phase II increase pending).

Application form and job description from:-

**HOSPITAL SECRETARY,
VICTORIA HOSPITAL,
WHINNEY HEYS ROAD,
BLACKPOOL, FY3 8NR.**

Closing date 24th August, 1973.

[2930



Opportunities in the **ELECTRONICS FIELD**

Men with analogue or digital qualifications/
experience seeking higher paid posts in:
TEST — SERVICE — DESIGN — SALES

Phone: Roger Pearce 01-629 7306 Ref. WW
NEWMAN APPOINTMENTS
360 Oxford Street, W.1.

2940

RADIO OFFICERS

**DO YOU HAVE PMG I PMG II MPT
2 YEARS OPERATING EXPERIENCE**

POSSESSION OF ONE OF THESE QUALIFIES YOU FOR CONSIDERATION FOR A RADIO OFFICER POST WITH COMPOSITE SIGNALS ORGANISATION.

On satisfactory completion of a 7-month specialist training course, successful applicants are paid on a scale rising to £2,527 pa; commencing salary according to age — 25 years and over £1807 pa. During training salary also by age, 25 and over £1350 pa with free accommodation.

The future holds good opportunities for established status, service overseas and promotion.

Training courses commence at intervals throughout the year. Earliest possible application advised.

Applications only from British-born UK residents up to 35 years of age (40 years if exceptionally well qualified) will be considered.

Full details from

Recruitment Officer, Government Communications Headquarters, Room A/1105 Priors Road, Oakley, Cheltenham, Glos GL52 5AJ, Telephone: Cheltenham 21491 Ext 2270

**UNIVERSITY COLLEGE
CARDIFF**

Technician required for

ELECTRON MUSIC STUDIO

in the Department of Physics.

Salary £1,728-£2,028 p.a.

Applications to the Registrar, University College, P.O. Box 78, Cardiff, CF1 1XL, no later than 30 September 1973. Please quote 0882.

[2942

**CHARING CROSS HOSPITAL
(FULHAM)**

Fulham Palace Rd., Hammersmith W6

**SENIOR
PHYSIOLOGICAL
TECHNICIAN**(Salary on scale £1,500-£1,953 p.a.
inclusive of London Weighting)**PHYSIOLOGICAL
TECHNICIAN**(Salary on scale £1,236-1,689 p.a.
inclusive of London Weighting)

required for Department of Patient Monitoring currently being established. The posts will be primarily concerned with intensive care patient monitoring, but the successful applicants will also be expected to work in the Department of Cardiology, E.E.G. and Respirology.

At least 4 'O' levels required together with relevant experience, or an O.N.C. in Physiological Measurement or Equipment.

Applications with full details of age, experience, and the names and addresses of two referees, to Miss Matthews, Personnel Department, quoting ref. 810.

[2936]

**London Borough of Hounslow
Education Department****TECHNICIAN**

full-time, required at Heston School for the Deaf, Vicarage Farm Road, Heston, to maintain teaching aids for the deaf in nine deaf units in other schools in the Borough and one at Hillingdon. The successful candidate must hold a current driving licence. Salary on grade T.4 £1,635-£1,908. Application forms from Director of Education, 88 Lampton Road, Hounslow, Middlesex. Closing date: 14th September, 1973. Tel.: 01-570 7728, Ext. 535.

[2909]

**BERKSHIRE
COLLEGE OF EDUCATION****AUDIO TECHNICIAN**

(Man or Woman)

to work in new Resources Centre. The person appointed should have an interest in sound recording and operation of tape recorders and should be able to carry out first line service. A general knowledge of language laboratories would be an advantage but instruction will be given. Salary Technical Grade III viz. £1311-£1530 p.a.

Application forms together with further particulars obtainable from the Senior Administration Officer, Berkshire College of Education, Bulmershe Court, Woodlands Avenue, Earley, Reading, RG6 1HY. To be returned as soon as possible.

[2910]

MARCONI INSTRUMENTS LIMITED**ELECTRONIC
TECHNICIANS**

are required to work on calibration, fault-finding and testing of telecommunications measuring instruments. The work is varied and will enable technicians with experience of r.f. circuits to broaden their knowledge of the latest techniques employed in the electronics and telecommunications industries by bringing them into contact with a wide range of the most advanced measuring instruments embracing all frequencies up to u.h.f.

Entrants may be graded as Test Technicians, Senior Test Technicians or Technician Engineers according to experience and qualifications. Our servicing and production programme, geared to our recognised export achievement, provides employment combined with prospects of advancement, not only within these grades, but into other technical and supervisory posts within the Company at Luton and St. Albans.

Salaries are attractive and conditions excellent. A Pension Scheme includes substantial life assurance cover provided by the Company. Assistance with removal may also be given in appropriate cases. Please write or telephone, quoting reference WW178 for application form to:



Mr. M. Leavens, Works Manager
Telephone: Luton 33866, or
Mr P. Elsip, Personnel Officer
Marconi Instruments Ltd
Longacres, St. Albans, Herts
Telephone: St. Albans 59292

Member of GEC-Marconi Electronics

THE QUEEN'S AWARD
TO INDUSTRY**SERVICE REPRESENTATIVE
FOR NUCLEONIC INSTRUMENTATION**

As a result of continued growth and internal movement of personnel, Tracerlab, manufacturer of Automatic Liquid and Gamma Scintillation Spectrometers etc., need further service representatives.

We require self-motivated men who can work independently and with initiative.

Experience with digital electronics is essential, age is unlikely to exceed 35 and a background in physics and chemistry might be an advantage.

The Company offers negotiable salary, superannuation scheme, an excellent incentive bonus that encourages close co-operation in sales and a company car.

MAKE THE CHANGE NOW

contact: **SALES MANAGER,
ICN TRACERLAB,
2, RIVERDENE INDUSTRIAL ESTATE,
MOLESEY ROAD, HERSHAM, SURREY.
Tel: Walton on Thames 44441**

[2993]

BOTSWANA ASSISTANT ENGINEERS

The following vacancies exist in the Posts & Telecommunications Department:-

GRADE I or II

Officers are required to instal open-wire carrier and VFT systems, VHF/UHF and micro-wave systems up to 300 channel capacity at 2GHz.

Candidates for **GRADE I** posts must possess the City and Guilds Telecommunications Final Certificate and for **GRADE II**, the Intermediate Certificate, or equivalent qualifications. For either grade, candidates must be aged 25-45 years and have had five years' experience, excluding training, of the above mentioned equipment. Experience of single channel HF and VHF systems is also required.

(Reference M2K/720470/WF)

Salary for the **GRADE I** post will be in the range of £2230 to £3190 according to experience. A substantial Gratuity is payable on completion of engagement. Because of lower rates of Income Tax in Botswana the gross emoluments are roughly equivalent to a UK salary of £3300 to £4400 for a single man and £3450 to £4750 for a married man with 2 children.

Similarly salary for the **GRADE II** posts will be in the range of £1860 to £2810 according to experience roughly equivalent to a UK salary of £2750 to £3900 for a single man and £2800 to £4100 for a married man with 2 children.

Other benefits include:- Subsidised Accommodation; Free Family Passages; Education Allowances; Holiday Visit Passages; Appointment Grant £100-200 Normally Payable; 24-36 Month Tour.

The post described is partly financed by Britain's programme of aid to the developing countries administered by the Overseas Development Administration of the Foreign and Commonwealth Office.

For further particulars you should apply, giving brief details of experience to:

crowns agents

M Division, 4 Millbank, London SW1P 3JD, quoting appropriate reference number

2912

ELECTRONICS ENGINEER

required for interesting development work on prototype circuit layouts, wiring, testing, and fault finding. Experience of modern integrated circuits, especially digital, is essential.

The work is varied and working conditions are excellent in a modern laboratory. A good salary is offered and there is a pension scheme with life assurance cover.

Apply in writing to
Managing Director/TM.,

L. OERTLING LTD.,

CRAY VALLEY WORKS, ST. MARY CRAY, ORPINGTON, KENT. BR5 2HA

[2991]

X-RAY FIELD ENGINEERS

Our current expansion programme now calls for experienced electro-mechanical engineers to support our existing field staff. They will become involved in a variety of interesting activities covering the installation, service and maintenance of diagnostic medical x-ray equipment in hospitals.

Progressive opportunities exist in a number of our branches including London, Cardiff, Birmingham, Ipswich, High Wycombe, Boreham wood, South East England and also overseas.

Applicants should be qualified to ONC or City & Guilds equivalent and previous experience in any of the following—X-ray engineering, closed circuit television, electronics or logic circuitry—would be a distinct advantage.

Good salaries and fringe benefits will be offered to the successful applicants and a company car will be provided as soon as an acceptable stage of proficiency in our product is reached.

For further details write or telephone, giving details of the area(s) in which you are interested, to:

P. B. Blackmore,
GEC MEDICAL EQUIPMENT LTD.,
East Lane, Wembley, Middx. Tel: 01-904 1288.

[2961]

London Borough of Brent
Amenities and
Works Department

QUALIFIED TRADESMEN

for

AURAL and VISUAL AIDS SECTION

of

Engineering Services Division
at Alperton, Wembley

Experience essential in the installation, maintenance and repair of radios, projectors, tape recorders, etc. in Educational Establishments. Wages £30.80 per 5-day/40-hour week.

Apply to:

Engineering Services Manager,
Alperton Lane, Wembley,

Middlesex, HA0 1DZ

Telephone 01-998 3456

[2970]

THE TAPE DUPLICATING CO. (GREAT BRITAIN) LIMITED

a subsidiary of METRO SOUND

Manufacturers of pre-recorded music cassettes and eight-track cartridges, requires at its Waltham Abbey, Essex, plant, an Engineer with experience in electronics and mechanical equipment to control the maintenance of a wide range of machinery involved in the high speed duplication and assembly of pre-recorded tapes.

Salary will be negotiable, commensurate with age and experience, plus fringe benefits.

Please write, giving personal details and previous experience, to:-

Personnel Officer,
Metrosound Audio Products Limited,
Audio Works, Cartersfield Road,
Waltham Abbey, Essex, EN9 1JF.

[2907]

QUEEN ELIZABETH COLLEGE
(University of London)

ELECTRONICS ENGINEER

required for the design, development and maintenance of electronic equipment.

Applicants will be expected to have H.N.C. or equivalent qualification and several years experience in both linear and digital electronic circuits and systems.

Salary scale (Grade 5 Technician), £2,056—£2,416 including London Weighting.

Application forms obtainable from Mr. R. E. Webb, Electronics Unit, Queen Elizabeth College, Campden Hill Road, London W8 7AH.

[2973]

SERVICE ENGINEER

LKB INSTRUMENTS LTD.

requires an additional engineer to be resident in the South London, S.E. England area for field servicing of their Scientific and Technical instruments installed in Academic, Medical and Industrial Laboratories.

The successful applicant will possess a sound basic knowledge of modern electronics and will preferably have some field experience, although this is not essential.

The Company is internationally renowned for the quality of its products and offers excellent working conditions including company car, pension scheme, superannuation and profit sharing bonus scheme.

Write for application form to:

The Service Manager,
LKB Instruments Limited,
232 Addington Road,
South Croydon, Surrey, CR2 8YD
[2996]

FOREMOST IN THE UNITED KINGDOM

IN CONSTANT TOUCH WITH EVERY EMPLOYER OF EXPERIENCED ELECTRONICS ENGINEERS

Our professional placement service is specialised, confidential and completely free

Phone us at any time or write quoting WW106



ELECTRONICS APPOINTMENTS LTD
4 DRYDEN CHAMBERS,
119 OXFORD STREET,
LONDON, W1R 1PA.
TEL: 01-434 1861

93

Electronic/Technician Engineer

A responsible position is available within the Company for a person to take charge and supervise a small but expanding group of technicians engaged in the servicing and maintenance of a wide range of modern electronic equipment including portable radio, T.V., Cassette recorders, digital calculators, etc.

A working knowledge of the principles of transistor and integrated circuits pertinent to the above apparatus is required and qualifications to HNC, HND, T.Eng, Final C & G or equivalent is desirable. However, academic qualifications are not essential and proven practical ability is regarded as more important for this position where an active participation in the work is necessary.

A salary in the region of £2,500 is envisaged for this position coupled with excellent conditions and benefits of the Company situated at Audenshaw, near Manchester.

Write or telephone for application form from the Personnel Department.

JONES SEWING MACHINE CO. LTD.
Shepley Street, Audenshaw, Nr. Manchester
[2957]

Components Sales Engineer

Car provided

Our outstanding success in the development and production of advanced test and measurement instrumentation, has enabled us to effect a degree of parallel diversification and to broach the rapid-growth area of the high-quality component market.

Consequently, we need a Sales Engineer of sufficient calibre to sell our range of RF microwave and Opto electronic components to OEM users.

He'll be covering just about one quarter of the UK, making regular personal visits to major customers and promoting both company and products through lectures, seminars, and exhibitions. He will assist the Distributor Sales force by training and joint visits, and will himself attend training programmes in Europe and the USA.

Aged between 25 and 35 with at least an HNC/HND in Electronic Engineering, he should have RF, microwave, component or semi-conductor sales/marketing experience. Previous involvement in technical sales to the TV and Radio industry would also be ideal. His experience and ability should make him a self starter capable of managing his area with minimum supervision.

We offer an excellent starting salary, a car, annual cash bonuses and other worthwhile benefits. We will also assist with removal expenses where it is necessary to re-locate.

Please ring Maureen Rowley, Personnel Administrator on Slough 35621 for an application form.

HEWLETT  PACKARD

224 Bath Road, Slough, Bucks.

SERVICE ENGINEER EXTRAORDINARY

We are seeking an unusual mixture to offer an exciting challenge, good prospects and pay. The service engineer sought should have both digital and analogue experience, mechanical aptitude and if possible knowledge of nuclear physics. He is to be based in the South East, responsible for after-sales service of liquid scintillation equipment.

Please reply in confidence to:

**MANAGING DIRECTOR
INTERTECHNIQUE LIMITED
COTTRELL HOUSE
53-63 WEMBLEY HILL ROAD, WEMBLEY HA9 8BE**

[2990]

ANTARCTIC EXPEDITION WIRELESS OPERATOR MECHANICS

required for British stations in Antarctica.

Applicants, preferably single and aged 22-30, should have experience of maintaining and operating SSB transmitters, receivers. Teleprinter experience desirable. Salary from £1442 per annum, all found overseas. Low income tax. Bonus for satisfactory service.

Applications to:

**British Antarctic Survey,
30 Gillingham Street,
LONDON, SW1V 1HY.
(01) 834 3687.**

[2905]

NEWCASTLE REGIONAL HOSPITAL BOARD

Regional Engineer's Electronics Section

Applications are invited for the following newly created posts in this increasingly important section of the Regional Engineer's Department.

I Main Grade Electronic Engineer

This post embraces electronic design/development work connected with the hospital building programme, Technical evaluation of electro-medical equipment, and calibration/maintenance of electronic installations, and services in hospitals throughout the five Northern Counties of England.

The successful applicant will be expected to exercise initiative, whilst working as a member of a team of Electronic Engineers.

A wide experience in the field of applied electronics is essential, preferably including medical or clinical laboratory equipment, together with administrative ability.

QUALIFICATIONS: Chartered Electronic Engineer, or Degree in Electronic Engineering/Physical Electronics.

SALARY: According to age, qualifications and experience, will be in the scale:
£1866 - £3760

II Electronic Technical Assistants

Two posts, which will be based at Newcastle upon Tyne, will involve electronic design and development work connected with the hospital buildings programme, and participation in electronic maintenance/calibration in hospitals.

Applicants must have wide experience in the practical applications of electronics.

QUALIFICATIONS: Grade I. E.R.E., or HND/HNC in Electronic/Engineering or Physical Electronics

SALARY: According to age, qualifications and experience, will be in the scale:
Technical Assistant Grade I—£2379 - £2892.

Applications, naming three referees, including details of age, present salary, education, experience etc., and indicating which post applied for should be addressed to the Secretary, Newcastle Regional Hospital Board, Benfield Road, Newcastle upon Tyne, NE6 4PY by 31st August.

[2954

ELECTROSONIC LTD., GREENWICH

PROJECT ENGINEER SALARY £1,800 — £2,200

A vacancy exists for a project engineer to work on lighting control projects. Some experience of systems engineering and installation work together with an understanding of power distribution and switching essential.

Electrosonic is a medium sized company specialising in world wide commercial lighting, audio and audio-visual systems.

Candidates should preferably hold H.N.C. and be within the 25-35 age group.

Apply to: **ELECTROSONIC LTD.,**
815 WOOLWICH ROAD, CHARLTON, LONDON SE7 8LT.
TELEPHONE: 01-855 1101

[3003

Research Assistant/ Demonstrators

Applications are invited from good Honours Graduates for posts of Research Assistant/Demonstrators for the following project:—

Electronic multi-channel telemetry systems for geophysical survey borehole probes

Application form and further particulars about these posts may be obtained from the Chief Administrative Officer, Trent Polytechnic, Burton Street, Nottingham NG1 4BU.

3002

TRENT

POLYTECHNIC

BOOKS

PRACTICAL BOOKS

World Radio and TV Handbook 1973.....	£3-00
Integrated Circuit Pocketbook, 282 pp.....	£2-65
Electronic Engineers Ref. Book, 1532 pp. illus.....	£7-90
Electronics Pocketbook, 314 pp. illus.....	£1-55
Foundations of Wireless and Electronics, 552 pp.....	£1-98
110 Integrated Circ. Proj. for the Home Cons.....	£1-35
110 Semiconductor Proj. for the Home Cons. 134 pp.....	£1-35
Integrated Circuit Engineering, 406 pp. illus.....	£11-30
Integrated Circuit Systems, 236 pp. illus.....	£3-85
Aerials (P) TV and FM Receiving Aerials, 112 pp. illus.....	95p
Loudspeakers and Loudspeaker Cabinets, 120 pp.....	95p
Radio Valves, 134 pp. illus.....	95p
Stereo Handbook, 150 pp. illus.....	£1-10
Transistors in Logical Circuits, 132 pp. illus.....	95p
Practical Oscilloscope Handbook, 118 pp. illus.....	£1-95
Principles of Feedback Design, 246 pp. illus.....	£1-35
Principles of Transistor Circuits, 318 pp. illus.....	£1-85
Ques. & Ans. on Electronics, 112 pp. illus.....	75p
Ques. & Ans. on Transistors, 96 pp. illus.....	75p
Radio & Electronic Laboratory Handbook, 628 pp.....	£4-95
Semiconductors: Basic theory & devices, 272 pp. illus.....	£2-85
Simplified Modern Filter Design, 193 pp. illus.....	£2-95
Telecommunications Pocketbook, 152 pp. illus.....	£1-35
Transistor Circuit Design Tables, 128 pp. illus.....	£2-85
Transistor Pocketbook 312 pp. illus.....	£3-15
Transistors for Technical Colleges, 210 pp. illus.....	£1-55
20 Solid state Projects for the home, 114 pp. illus.....	£1-10
Beginners Guide to Radio, 204 pp. illus.....	£1-10
Dictionary of Radio & TV, 380 pp. illus.....	£1-95
Everyman's Wireless Book, 368 pp. illus.....	£1-85
FM Radio Servicing Handbook 206 pp. illus.....	£3-15
Guide to Broadcasting Stations, 164 pp.....	85p
The Hi-fi and Taperecorder Handbook, 304 pp. illus.....	£2-15
Introduction to Radar and Radar Techniques, 136 pp.....	90p
Marine Radio Manual, 622 pp. illus.....	£4-25
The Practical Aerial Handbook, 232 pp. illus.....	£2-85
Practical Integrated Circuits, 144 pp. illus.....	£1-90
Practical TV Circuits, 376 pp. illus.....	£1-95
Practical Wireless Circuits, 192 pp. illus.....	£1-35
Practical Wireless Service Manual, 288 pp. illus.....	£1-65
Principles of Aerial Design, 182 pp. illus.....	£1-35
Principles of PAL Colour TV, 162 pp. illus.....	£1-35
Principles of TV Engineering, 188 pp. illus.....	£1-85
Ques. & Ans. on Audio, 194 pp. illus.....	75p
Ques. & Ans. on Colour TV, 108 pp. illus.....	75p
Radio and Audio Serv. Handbook, 284 pp. illus.....	£3-20
Radio and Electronic Handbook, 156 pp. illus.....	£1-35
Radio Valve and Transistor Data, 240 pp. illus.....	85p
Television Engineers Pocketbook, 304 pp. illus.....	£1-55
Television Servicing Handbook, 358 pp. illus.....	£2-95
Wireless Servicing Manual, 302 pp. illus.....	£1-65
How to make Walkie Talkies for licensed operation.....	45p
Handbook of Trans. Equivalents & substitutes.....	50p
Handbook of Transistor Circuits, 64 pp.....	50p
Sound and Loudspeaker Manual, 96 pp.....	55p
Practical Transistor Novelty Circuits, 64 pp.....	50p
Hi-fi, P.A., Guitar, Discotheque Ampl. Design Hand- book.....	85p
Electronic Novelties for the Car Owner.....	60p
2nd Book of Trans. Equivalents & Substitutes.....	85p
High Fidelity Loudspeaker Enclosures.....	50p
Radio Servicing for Amateurs.....	30p
Radio, T.V. and Electronics Data Book.....	30p
Transistor Circuits for Radio Controlled Models.....	50p
Modern Transistor Circuits for Beginners.....	50p
Manual of Transistor Audio Amplifiers.....	50p
Practical Car Radio Handbook.....	40p
1-2-3-4 Servicing Stereo Amplifiers, 240 pp. illus.....	£2-85
Transistor TV Servicing Guide, 128 pp. illus.....	£2-35
101 Ques. & Ans. about AM, FM, & SSB. illus.....	£1-90
99 Ways to improve your S.W. listening, 144 pp.....	£1-95
99 Electronic Projects, illus.....	£1-85
Radio Handbook, 960 pp. illus.....	£7-95
Transistorised Radio Control for Models.....	£2-85
Making and Using Electronic Oscillators, 128 pp.....	£2-15
Making and Repairing Transistor Radios, 128 pp.....	£1-15
ABC's of Hi-fi and Stereo.....	£1-40
ABC's of Electrical Soldering.....	£1-55
Making and Repairing Made Easy, illus.....	£1-45
Car Radio Servicing Made Easy, illus.....	£1-75
Electric Guitar Amplifier Handbook.....	£1-65
FM Multiplexing for Stereo.....	£1-65
Hi-fi Stereo Handbook.....	£2-25
Hi-fi Stereo Servicing Guide.....	£1-90
How to repair small Appliances.....	£1-35
Making and Repairing Transistor Radios, 128 pp.....	£1-25
Radio Spectrum Handbook, illus.....	£3-30
Servicing Digital Devices.....	£1-45
Tape Recording Servicing Guide.....	£1-95
Transistor Radio Servicing Made Easy, 144 pp.....	£1-85

WHEEL PUBLICATIONS (WWA)

41a Adelaide Grove, London W12 0JH.

Foreign and Commonwealth Office

has vacancies for
HAND MORSE

COMMUNICATORS

Candidates should produce evidence of sound knowledge of radio and electronic theory eg MPT (PMG) Grade I or C & G certificates.

Further particulars may be obtained from:-

**RECRUITMENT SECTION
COMMUNICATIONS DIVISION
FOREIGN & COMMONWEALTH OFFICE
HANSLOPE PARK, HANSLOPE,
MILTON KEYNES, MK19 7BH**

[3001

BOOKS



ESSENTIAL BOOKS!

THE THEORY OF GUIDED ELECTROMAGNETIC WAVES. R. Waldron. Marconi series. The most comprehensive book on this subject ever written. Conveys sufficient understanding of principles and mathematical methods enabling the reader to solve a wide range of problems. Embraces Basic Electromagnetic Theory, The Mathematics of Waveguide Theory, Transmission Lines, Elementary Theory of Waveguides, Cavity Resonators, Inhomogeneous and Anisotropic Waveguides. Over 500 pages. Published at £11.50. Special offer to W.W. readers. £7.75 post free.

PRINCIPLES OF ELECTRICITY AND MAGNETISM. A complete course on Electricity and Magnetism for the student, electronics engineer and technician who wishes to improve his knowledge of the subject. As recommended to technical colleges, universities and polytechnics. 532 pages. Hardback. Fully illustrated. 4 massive reprints. Published at £4.50. Special offer while stocks last £2.75. p.p. 25p.

PROBLEMS IN ELECTRONICS WITH SOLUTIONS. A must for the student, technician and electronics engineer. Contains 349 problems, answers and how they were arrived at. Includes all aspects of electronics, amplifiers, power supplies, computers, aerials, waveguides, transmission lines. 307 pages. Only 90p. p.p. 10p.

COSMIC RADIO WAVES. Start a new hobby — RADIO ASTRONOMY. This big book of 444 pages is an ideal handbook for the beginner and established enthusiast. Numerous photographs and illustrations. Published by the Oxford University Press. Price £2.50 p.p. 25p.

HOW TO MAKE WALKIE-TALKIE FOR LICENSED OPERATION. Only 40p. p.p. 10p.

THE GOVERNMENT SURPLUS WIRELESS EQUIPMENT HANDBOOK. Gives circuits data and illustrations, plus valuable information for British/USA receivers, transmitters, trans/receivers. With modifications to sets and test equipment. Latest impression £3.25 including postage.

DIRECTORY OF GOVERNMENT SURPLUS WIRELESS EQUIPMENT DEALERS. Gives details of surplus wireless equipment stores and dealers including addresses and equipment that they are likely to have available. A valuable book only 40p. p.p. 10p.

NEW BOOKS. Publication date for these three titles is Nov. 15th. Order now to avoid disappointment as the first impression of each is expected to be a sell-out.

MOBILE RADIOTELEPHONE EQUIPMENT HANDBOOK. Gives circuits data, and illustrations plus some valuable modifications for commercial radiotelephone equipment including PYE and other popular makes. £4 including postage.

HOW TO MAKE 2 & 4 METRE CONVERTERS FOR AMATEUR USE. 50p. p.p. 10p. **ADVANCED BOOK OF CRYSTAL SET DESIGNS.** 35p. p.p. 5p.

HANDBOOK OF TRANSISTOR EQUIVALENTS AND SUBSTITUTES. 40p. post free. **TRADE ENQUIRIES INVITED FOR THE ABOVE BOOKS FROM RADIO & ELECTRONIC SHOPS AND BOOKSELLERS.**

HI-FI, P.A., GUITAR & DISCOTHEQUE AMPLIFIER DESIGN HANDBOOK. 75p post free.

HANDBOOK OF SATELLITES AND SPACE VEHICLES. 457 pages. An impressive book of 457 pages. Includes chapters on communication in space. Published at £8.20. available at £6.50. post free.

GERALD MYERS (W.W.)
18 SHAFTESBURY STREET,
LEEDS LS12 3BT.

Bookseller & Publisher
 NEW SHOWROOM & TRADE COUNTER OPEN AT
 8 HARTLEYS YARD,
 OFF TOWN STREET,
 ARMLEY, LEEDS 12. (near White Horse Inn) CALLERS WELCOME.

TRAIN FOR SUCCESS WITH ICS

Study at home for a progressive post in Radio, TV & Electronics. Expert tuition for C & G (Telecoms Techn's Cert and Radio Amateurs') RTEB, etc. Many non-exam courses including Colour TV Servicing, Numerical Control and Computers. Also self-build kit courses—valve and transistor.

Write for FREE prospectus and find out how ICS can help you in your career. ICS, (Dept 734 T) Intertext House, London SW8. [3000]

RADIO AMATEURS COURSE—Tuesdays 7 to 9 pm. Tutor Mr. C. Duckling, two terms, begins 25th September, 1973. Fee £3 for City and Guilds Radio Amateurs' Examination. Class to be held at St. Paul's Centre, School Lane, Aldlstone, Surrey. Details of syllabus from Area Principal, Chertsey & Egham I.F.E., O'd Council Offices, Guildford Street, Chertsey, Surrey. [2916]

COURSES

North East London Polytechnic

Electrical Engineering

(Barking Precinct)

B Sc Electrical Engineering (CNA)

with Honours options. 4-years sandwich

HND Electrical & Electronic Engineering

with possibility of transfer to B Sc course.

3-years sandwich.

CEI Part 2 1-year full time or 3-years part time

Other part time courses include:-

HNC Electrical & Electronic Engineering

Electrical Technicians Parts 2 and 3

Telecommunication Technicians Part 3

Colour T.V. Servicing (evenings)

All the above courses are held at the Barking Precinct, Longbridge Rd., Dagenham.

Further details may be obtained from The Registrar Ref: JS102

North East London Polytechnic, Forest Rd., London, E17 4JB

Tel: 01-527 0933

2978

Middlesex Polytechnic

Microelectronics Centre Short Practical Courses 1973/74

These courses, which have become well-known and popular in previous years, are being offered again.

Integrated Circuit Technology

Thick Films

Hybrid Micro-electronics

Bipolar and MOS Circuits

Write now for full details and application form to Mrs. D. P. Linnell, Ref WW/9, Middlesex Polytechnic, Queensway, Enfield, Middlesex EN3 4SF or phone 01-804 8131.

2977

APPTS CONT.

ENGINEER

to service

ELECTRONIC ORGANS B & O AUDIO and C.T.V.

The work is interesting and varied, a Company vehicle is provided and there are vacancies in Birmingham and Manchester.

Telephone or write to:

W. Swan, Jnr. or Mr. D. C. Kay,
 SWAN'S,

84-86 Oldham Street, Manchester M4 1LF
 Tel: 061-236 6774

[2959]

ARTICLES FOR SALE

TEST EQUIPMENT

TF144G Sig. gen. 85kHz-25MHz in 8 ranges. From £12 in average condition to £22 in excellent condition (£2); 5MHz Crystal calibrator £6(£1); Field telephones complete in carrying case £2.50(50p). pair for £4.50(75p); Sig. gen. type 12/2 35kHz-18.3MHz in 8 bands, AM-FM-CW, 36" long dial, inbuilt crystal calibrator at 100kHz & 2MHz, 8 diff modulation frequencies. £55(£2); Tape amplifiers. 2x ECC83. ELB4, EZ80, 20uV i/p for 3 watts into 30hm o/p. £1.80(40p); or in case with 7x4" speaker & non-standard deck £3.30(£1.10 up to 200 miles. £1.30 over); Isotope developments EHT supply type 532D. Provides stable 0-3kV @ 5mA. brand new £44(£2); Assorted resistors in bulk: 500 £1.10(15p); 20,000 £27.50(£1.20); 100,000 £88(£2); Computer panels: 7lb £2.20(40p); 56lb £13.20(£1); High quality Panels, 12 for £2.20(30p); 100 for £46.50(75p); 1,000 £82(£3); 7lb Bargain parcels, contain hundreds of R's, C's, xtals, pots, switches, panels, etc. £1.80(40p); 56lb ditto £12(£1).

GREENWELD ELECTRONICS (W4), 24 Goodhart Way, W. Wickham, Kent, Shop at 21 Deptford Broadway, SE8. Tel: 01-692 2009. [3007]

ENAMELLED COPPER WIRE

S.W.G.	1lb Reel	1/2lb Reel
10-14	£1.27	72p
15-19	£1.27	72p
20-24	£1.30	75p
25-29	£1.38	83p
30-34	£1.43	88p
35-40	£1.54	91p

Please add 10% to all above prices to cover V.A.T. The above prices cover P. & P. in U.K. Supplied by **INDUSTRIAL SUPPLIES** 102 Parswood Road, Withington, Manchester M20 Tel: 061-224-3553

Electrolytic capacitors MFD/V 2,000/50, 2,500/50, 5,000/50, 10,000/50, 12,500/50, 50p each post paid. 5,000/70 4 1/2" x 2 1/2" 60p. Subminiature plug in Crystals for Radio Control 26.985 MHz and 27.025 MHz 70p each.

INCLUDE 10% V.A.T. **ELEKON ENTERPRISES**, 224a St. Paul's Road, Highbury Corner, London, N.1. Tel: 01-359 4224. [3010]

ARTICLES FOR SALE

For ££'s more profit just look at these prices!



Big Savings on Valves		Goods Price		Goods Price		Goods Price		Goods Price	
Type	Goods Price	Type	Goods Price	Type	Goods Price	Type	Goods Price	Type	Goods Price
DY 87	24p	PY 88	25.5p	AF 139	37p	BC 158	8p	BF 258	40p
DY 802	24p	PY 500A	54p	AF 178	43p	BC 159	12p	BF 337	28p
EB 91	14.5p	PY 800	24.5p	AF 180	40p	BC 173	18p	BFY 50	22p
ECC 82	25.5p	PC 900	22.5p	AF 181	40p	BC 178B	20p	BFY 52	20p
EF 80	27p	Semi-Conductors		AF 239	45p	BC 182L	12p	BSY 52	25p
EF 183	31.5p	AC 127	15p	BA 145	14p	BC 183L	12p	BY 126	11p
EF 184	31.5p	AC 128	12p	BC 107	10p	BC 214L	15p	BY 127	12p
EH 90	28.5p	AC 141K	30p	BC 108B	9p	BD 124	70p	E. 1222	30p
PCC 89	34p	AC 142K	30p	BC 109	11p	BD 131	45p		
PCC 189	35.5p	AC 151	20p	BC 113	22p	BF 115	20p		
PCF 80	29p	AC 154	18p	BC 116	22p	BF 160	20p		
PCF 86	35.5p	AC 155	16p	BC 117	20p	BF 167	19p		
PCF 801	39p	AC 156	19p	BC 125B	18p	BF 173	20p		
PCF 802	35p	AC 176	19p	BC 132	25p	BF 178	35p		
PCL 82	34p	AC 187	17p	BC 135	20p	BF 179	40p		
PCL 84	28.5p	AC 187K	20p	BC 137	25p	BF 180	30p		
PCL 85	32.5p	AC 188K	20p	BC 138	40p	BF 181	30p		
PCL 86	32.5p	AD 142	45p	BC 142	26p	BF 184	21p		
PFL 200	44.5p	AD 149	37p	BC 143	30p	BF 185	21p		
PL 36	49p	AD 161	34p	BC 147A	8p	BF 194	8p		
PL 84	22p	AD 162	34p	BC 147B	8p	BF 195	15p		
PL 504	1p	AF 114	22p	BC 148	8p	BF 196	20p		
PL 508	53.5p	AF 115	20p	BC 149	12p	BF 197	17p		
PL 509	86p	AF 116	20p	BC 153	20p	BF 200	25p		
		AF 117	22p	BC 154	20p	BF 218	35p		
		AF 118	42p	BC 157	10p	BF 224	35p		

EHT RECTIFIER TRAY ASSEMBLIES	
Type	Goods Price
1TH Decca Col.	£4.25
2TQ 1400 + 950 Mk II	£1.75
2TAK 1500 5 Stick	£1.90
2DAF 1500 3 Stick	£1.70
2HD 950 3 Stick M1	£1.65
TCQ Pye/Ekco	£3.35

12 MONTHS GUARANTEE

COLOUR TUBES	
Type	Goods Price
19" A49/191X C.C.R.T.	£38.70
20" 510DJ22 C.C.R.T.	£39.80

FULLY GUARANTEED



Valves packed individually subject to settlement Discount 5% of "Goods" content 7 days and 2% monthly.

New Price List from 28th April 1973

Combined Precision Components (Preston) Ltd.
194-200 North Road, Preston PR1 1YP
Telephone 55034 Telex No. 67129

"AGENTS FOR TOSHIBA"

PRICES SUBJECT TO 10% VAT

83

INTRODUCING OUR NEW AUDIO COMPRESSOR

High quality kit or assembled and tested ready to use.

SEND FOR DETAILS

PARTRIDGE ELECTRONICS

23-25, Hart Road, Benfleet, Essex SS7 3PB.
PHONE (STD 03745) 3256

ALSO

- Pre-Amps
- Auto-Fades
- Audio-Monitors
- Slider Faders
- Drivers
- V.E. Mixers
- V.V. Monitors
- Power Packs
- Control Panels
- Cabinets

"CUSTOM BUILT SYSTEMS"



You may purchase by telephone with Barclay or Access cards



2969

WANTED PLUGS AND SOCKETS

Plessey/Painton Mk. IV, Mk. VI, Mk. VII
UK-AN Multicon
H.D. Multicon
159 Series

Send lists to:

J. SALLIS,
Oatlands Farm, Brighton Road,
Shermanbury, Horsham, Sussex.
Tel: 710-515.

[2972

Trampus electronic

Add 10% VAT to prices. All Brand New & Money Back Guaranteed.

DIGITAL INDICATORS 7 seg. OP 5v Filament type & socket £1.45. LED TYPE 1/2 0-9 DP 14 pin DIL £2.45. 4 + £2.29 ea 6 + £2.19 ea 10 + £2.15 ea. 4 DIGIT LED OIL/magnifier £11.
LIGHT EMITTING DIODES & data 1/2 DIA type & panel clip RED 33p. GREEN 73p. TIL209 1/2 DIA red 25p. INFRA RED £1.10. Dpto isolator £2. TGS308 Gas/smoke detector £1.69. ULTRASONIC TRANSDUCERS £2.
INTEGRATED CIRCUITS with data if req.



ic digital clock

MDS/LSI chip. 28 pin. 4 or 6 digit. 12 or 24 hr at flick of switch. Chip with DIL socket £13. PCB £1.69 KITS. 4 digit £21.49. 6 digit £25. IC LITE SWITCH 11-20v 40 ma relay/VTL drive. Photo amplifier/divider 87p ea. 10 + 77p ea. Photo amp only 39p. IC DIGITAL VOLTMETER £12. DVM VP MPX £6. Data booklet 39p. 741 OIL 8 pin 28p. 709 19p. dfl 29p. 710 33p. 748 29p. REGULATORS 1/2A 5 to 20v £1.49. 723 57p. 555 TIMER 89p. ZN414 RECEIVER Ferranti £1.19. Dual Pre amp £1.67. 35W AF AMP £1.24. STEREO DECODER IC FOR FM TUNERS MC1310P £2.69. KIT £3.45.

790 TTL BRAND NEW 100 + LESS 10%

Gates 7400/1/2/3/4/5/10/20/30/40/50 etc 14p ea. 7413 27p. 7441 73p. 7447 99p. 7470. 7472 28p. 7473 7474 36p. 7475 60p. 7476 32p. 7490 59p. 7492 67p. 7480 69p. 7483 £1.10. 7486 37p. 7493 73p. 7494 83p. 7495 83p. 7496 89p. 74121 45p. 74141 99p. 74190/91/92/93 £2.39. 74195 £1.59. C MOS logic in new lists. DIL PLUGS/IC case 10mm high 16 pin 35p.

DIL SOCKETS low/high profile 8/14/16 pin 13p 100 + 10p ea. SEMICONDUCTORS 25 - less 10%. ZENERS. 82V88 400 mW 7p. IN4001 3p. IN914 3p. 50v 1A Bridge 23p. 2N3055 40p. BC107 8p. BC108 8p. BC109 8p. BC147/8/9 10p. BC167/8/9 13p. BC177/8/9 15p. BC182/3/4 10p. BC212/3/4 11p. BCY70/77 13p. BD131/2 55p. BFY50/51/52 13p. TIS43 UJT 24p. 2N706 11p. 2N2369 12p. 2N2926 8p. 2N3053 17p. 2N3055 40p. 2N3614 65p. 2N3702/3/4 5/6/7/8/9/10/11 All 9p. FETS 2N3819 27p. 2N3823 29p. 2N3866 UHF 59p. SCR's 400v 1A 23p. 4A 55p. TRANSFORMERS 1/2A 6 & 12v £1. CAPACITORS 25v 10. 50. 100 ul 5p ea. 50 + 4p ea. 22p to 0.1uf 3p. RESISTORS 1/2W 5% 1/2p ea. PRESETS 5p. CARBON POTS 12p ea. 0.001 40p. Switch + 12p.

FLUORESCENT LIGHTS 12VOLT £2.79

8 WATT with diffuser. on/off switch. Fully built 13" long TRIO and CODAR communications and Hi Fi retailers. ELECTRONIC ORGANS imported. full facilities from £67. ELECTRONIC CAR IGNITION KIT P&P capacitor type £6.67. VAT customers MUST ADD 10% (VAT) to above prices.
FREE CATALIST S.A.E. DATA SHEETS 8p ea. S.A.E. P&P 8p CWO to PD BOX 29, BRACKNELL, BERKS.

EDDYSTONE V.H.F. & U.H.F. COMMUNICATIONS RECEIVER TYPE 770R. 19 mc/s to 165 mc/s C.W. A.M. N.F.M. F.M. Mains. in as new condition, £95. carr. £3. 770U 150 mc/s to 500 mc/s F.M. or A.M., Mains. in as new condition, £95. carr. £3. RACAL UNIVERSAL COUNTER/TIMER SAS50 (CT488). 8 digit inline readout, £85. carr. £3. AVO MODEL 3 VALVE TESTER in wooden Transit Case, £17.50. carr. £2.50p. INDIVIDUAL POCKET DOSIMETERS. Latest Government Release Type 2A and 3, 11,000 available individually wrapped in boxes of 50. Also 300 Charging Units No 1 for above Dosimeters, individually boxed, both are absolutely Brand New, supplied one box of 50 Dosimeters with one Charger £14, p/p. £1. 25 and one Charger £9, p/p £1. Singly 50p, p/p 10p. Chargers £2.50, p/p 25p. Probable cost of one Dosimeter £10. Larger quantities by quotation.
MARCONI SIGNAL GENERATOR TYPE TF867 15KHZ-30MHZ. £75. carr. £3.
JOHNS RADIO
424 BRADFORD ROAD, BATLEY, YORKS.
Tel: Batley 7732

[35

NEW FROM ELBON

L.E.D.'s (Red Emitting) ideally suited for panel indicators
Price only. 33p each or £2.50 for 10

Light SENSITIVE SWITCHES

Two types available giving wide operating voltages:
LITE-IC2 11V-20V working -£1 each -£8.50 for 10
LITE-IC3 20V-30V working -£1 each -£8.50 for 10

Applications include: Relay, Triac or Logic Drive, automatic light switching and door control, beam/break detection - burglar alarm, batch counting and code reading.

BARGAIN PACK!

2 LITE-IC2, 2 LITE-IC3 and 5 LED's all for £5.00

ALL PRICES INCLUDE VAT, PACKING AND CARRIAGE

Please send C.W.O. to:

LITE-IC, ELBON,
SUMMERFIELD, THE CRESCENT, WEST WITTERING, SUSSEX

ELECTRONIC SUPPLIES TERMS C.W.O. P. & P.
 P.O. BOX 216 London, N.W2 7RH
 Sp. Orders above £2 post free. Discounts available. Trade quotations. List 3p

BC107	-10	OC45	-12	ME8002	-15
BC107B	-12	OC71	-12	ME8101	-15
BC108	-10	MA8003	-35	ME8102	-17
BC108A	-11	ME0401	-20	ME8001	-15
BC108B	-11	ME0402	-21	ME8002	-15
BC108C	-14	ME0403	-15	ME8003	-10
BC109	-10	ME0404-1	-15	ME9003	-10
BC109B	-14	ME0404-2	-17	MP8111	-35
BC109C	-15	ME0411	-19	MP8112	-46

ADD 10% V.A.T.

SITUATIONS VACANT

DEVELOPMENT ENGINEER. Circa £3,000. A large and successful retail company require a Development Engineer. He will be responsible for the technical standards of a group of products, bought from both home and abroad, including Hi-Fi, Rad.o, T.V. and Tape Recorders. The work will entail technical negotiations with manufacturers concerning quality and types of components used and, or, should be developed. Electronic technical problem solving ability and practical knowledge is essential. Applicants should have appropriate qualifications and, as important, relevant experience with a major manufacturer in the electronics/components industry. Location: Head Office in North London. Salary to be negotiated around £3,000 p.a. though this could be exceeded for a particularly qualified man; other conditions of work including holidays and pension scheme are excellent. Brief replies stating qualifications, experience and current salary to Box No. WW 2937.

GRADE 3 AUDIO TECHNICIAN with knowledge of modern electronics and mechanical systems associated with audio equipment required for Language Centre, UNIVERSITY OF KENT. The salary scale is £1,539-£1,794 p.a. Further particulars and application forms from Director, Language Centre, Cornwallis Building, The University, Canterbury, Kent, quoting reference T73/9. Closing date for completed applications—10 September 1973.

ROYAL POSTGRADUATE MEDICAL SCHOOL. Young Engineer with wide range of practical interests required to work on projects applying electronic and other engineering techniques to medicine. Qualifications C & G or ONC. Starting salary in range £1,473-£1,896 per annum according to qualifications and experience. 5-day week. Applications to the Secretary, Royal Postgraduate Medical School, Hammersmith Hospital, DuCane Road, London W12 0HS, quoting reference 8/104/WW.

SERVICE ENGINEER. An expanding International company has vacancies for Service Engineers to install and maintain photocopying machines in the London postal district. Applicants should have electrical/mechanical experience with the ability to work on own initiative. After full training they will join our highly skilled force of field engineers with own area. Excellent promotion prospects, good salary, expenses, car allowance and fringe benefits. Tel.: Mr. Howkins on 01-828 4300. Nashua Copycat Limited, Greycoat Place, London, SW10 1SF.

SERVICE ENGINEER for Audio Visual Aids equipment, particularly 16mm projectors. Burgess Lane & Co. Ltd., Thornton Works, Thornton Avenue, Chiswick, London, W.4. 994 5752.

HI-FI AUDIO ENGINEERS. We require experienced Junior and Seniors and will pay top rates to get them. Tell us about your abilities. 01-437 4607.

UNIVERSITY HOSPITAL OF SOUTH MANCHESTER. CHRISTIE HOSPITAL AND HOLT RADIUM INSTITUTE. MANCHESTER M20 9BX. REGIONAL PHYSICS DEPARTMENT. ELECTRONICS TECHNICIAN. There is a vacancy in the Physics Department based at the above hospital, for an ELECTRONICS TECHNICIAN Grade III. Salary scale £1,692 with 7 increments to £2,076. Phase II increase being negotiated. Minimum qualification ONC or equivalent with 3 years subsequent experience essential. The department is responsible for a wide range of equipment in this and other hospitals in the Region. and the applicant will form part of a team involved in maintenance and repair of existing equipment and in the production of prototype equipment. Application forms from the Hospital Secretary quoting reference 73/58 returnable as soon as possible.

SITUATIONS WANTED

ADAPTABLE installation and maintenance engineer, 39, returning UK in mid-September from navigational aid work requires post as Field or Bench Service Engineer, preferably in South West. Experienced in audio, RF, and pulse work, also mechanically competent. Box WW 2983.

ARTICLES FOR SALE

ARVAK ELECTRONICS. 3-channel sound-light converters, from £18. Strobes, £25. Rainbow Strobes, £132.—12A Bruce Grove, N17 6RA. 01-808 9096.

ADVANCE IMHz Timer Counter Type TC 2A; £42. Ekco Timer Counter, Type M5024; £28. Solartron LM 903 A.C. Voltmeter; £12. I.C.L. Power Supply adjustable between 4.5 & 8 Volts and with twin meters; £16. Sharp pocket calculator Type 811A with memory & 16 digit capacity, c/w charger; £68. Griffin & George Optical Spectrometer; £45. Hewlett Packard Series 3900 six speed tape loop unit; £75. Raymond Boulkes, Mead Cottage, Bletchingley, Surrey, Godstone 3106.

BUILD IT in a DEWBOX quality plastic cabinet 2 in. x 2 1/2 in. x any length. D.E.W. Ltd. (W.), Ringwood Rd., Fernwood, Dorset. S.A.E. for leaflet. Write now—Right now.

BROADCAST CAMERA CHANNEL—Marconi Mk. III working order. Also, CCTV Monitor 21in. 625 Line 1/10; several U/S vidicon cameras, from £1-Pye VDA £3; window generator, waveform monitor, EMI Stab amp. Wanted CCV type 2106/Z, EMI control panel 215, Mk. IV camera cable. Phone Mr. Summers. Cainsborough 2802/3940.

ECONOMISE ON SEMICONDUCTORS
 All Prices include VAT

LED red Hewlett Packard	1-1	10+	25+
709C Op Amp	8 or 14 pin DIL	32	30
723C Regulator	14 pin DIL	70	65
741C Op Amp	8 pin DIL	34	32
748C Op Amp	8 pin DIL	37	35
BC107	108	109	8
7400 02 03	17	7413	27
7404 05	18	7441	90
7410 20 30	17	7473	43
BC109C	9	BC212	11
BC177	13	BC214	11
BC178	13	BF244B	27
BC182	10	2N3055	47
BC184	10	IN914	5
TAD 100 Radio IC + IF Filter and Data	£1-60p.		
5% 1/3W High stability Carbon film resistors 10-1M	£12 values 1p each. 10 mixed 9p. 10 same 8p.		
P. & P. 5p. (UK). Return of Post Service. All goods new full spec. devices. All linear IC's include Data.			
10% Discount where priced not given. SAE enquiries.			

SILICON SEMICONDUCTOR SERVICES
 41 Dunstable Road, Causton, Luton, LU1 4AL

CONSTRUCTION AIDS—Screws, nuts, spacers etc., in small quantities. Aluminium panels punched to spec. or plain sheet supplied. Fascia panels etched aluminium to individual requirements. Printed circuit boards—masters, negatives and board, one-off or small numbers. Send 6p for list. Ramar Constructor Services, 29 Shelbourne Road, Stratford on Avon, Warwks.

COLOUR, UHF and TV SPARES. Colour and UHF lists available on request. New Philips G6 single standard convergence panels complete, incl. 16 controls, coils, P.B. switches, leads, etc. and circuit data £3.75, or with yoke £5.00, P/P 30p. New Colour Scan Coils, Mullard or Plessey sub convergence yoke and blue lateral, £10.00, P/P 40. Mullard AT1025/05 Convergence Yoke, £2.50, P/P 25p. Mullard or Plessey Blue Laterals, £1.25, P/P 10p. BRC 3000 type Scan Coils, £4.00, P/P 40p. Delay Lines DL20, £3.50, DLIE, DL1, £1.50, P/P 25p. Lum. Delay Lines, 50p, P/P 15p. EHT Colour Quadrupler for Bush Murphy CTV 25 111/174 series, £8.25, P/P 25p. EHT Colour Triplet ITT TH25/1TH suitable most sets, £2.00, P/P 25p. KB CVCI Dual Stand. convergence panels complete incl. 22 controls, £3.75, P/P 35p. CR1 Base Panel, £1.75, P/P 15p. Makers Colour surplus/salvaged Philips G8 panels part complete: Decoder incl. 1/C, £2.50, IF incl. 5 modules, £2.50, T. Base, incl. 1.00, P/P 25p. CRT base, 75p, P/P 15p. GEC 2040 panels, Decoder, £3.50, T. Base, incl. 1.00, RGB and Sound, £1.00, P/P 25p. Pye CT70 Colour LOPT assembly incl. EHT output and Focus Control, £3.50, P/P 35p. B9D valve bases 10p, P/P 6p. VARICAP TUNERS. UHF ELC 1043 NEW, £4.50, Philips VHF for Band I and 3, £2.85 incl. data. Salvaged VHF and UHF Varicap tuners, £1.50, P/P 25p. UHF TUNERS NEW, Transistorised, £2.85 or incl. slow motion drive, £3.85. 4 position and 6 pos. push-button transist., £4.95. UHF/VHF basic integrated tuners, £3.25, Cydon UHF valve tuners, £1.50. All tuners P/P 30p. Transist. UHF/VHF IF panels salvaged, £2.50 P/P 25p. MURPHY 600/700 series complete UHF Conversion Kits incl. tuner, drive assy., 625 IF amplifier, 7 valves, accessories housed in cabinet plinth assembly, £7.50 P/P 50p. SOBELL/GEC 405/625 Dual standard switchable IF amplifier and output chassis incl. cct., £1.50 P/P 35p. THORN 850 Dual standard time base panel, £1.00 P/P 35p. PHILIPS 625 IF amplifier panel incl. cct., £1.00 P/P 30p. VHF turret tuners AT17650 incl. valves for K.B. Featherlight, Philips 19TG170, GEC 2010, etc., £2.50. PYE miniature incremental for 110 to 830, Pam and Invicta, £1.95. A.B. miniature with UHF injection suitable K.B. Baird, Ferguson, 75p. New fireball tuners Ferguson, HMV, Marconi, £1.90 P/P all tuners 30p. Large selection LOPIS, Scan Coils, FOPIS available for most popular makes. PYE/LABEARG transist. Mast-head UHF Booster, £5.75, Power Unit, £4.65 P/P 30p or Setback battery operated UHF Booster, £4.65 P/P 30p. MANOR SUPPLIES, 172 WEST END LANE, LONDON, N.W.6 (No. 28, 59, 159 Buses or W. Hampstead Bakerloo and Brit. Rail). MAIL ORDER: 64 GOLDERS MANOR DRIVE, LONDON, N.W.11 Tel. 01-794 8751.

DIGITAL voltmeter chassis 0-1 V. 1/p. with manual complete working order using TTL etc., £19.50. Sperry Gyroscope Compass Type CL1A and CL2 (Marine) complete with detectors in working condition with circuits and details. 100UA meters 3 inch circular ex-ministry 4 for £1.00. 0-8 Amp AC/DC meters 6 inch circular 75p each. Barometric Altimeters MK19B Kelvin Hughes £15.00 each. Rate of Climb and descent indicators Kelvin Hughes MK3P £2.00. Sperry artificial Horizon 115V 400Hz 3ph. MK3C £5.00. Smith's Resol ers type ACP 200 26V/11.8V ex-equipment but long lived in good condition with mounting plate £2.50. Redifon flight simulation c/2 compass pilot indicator type A 269/1113 £15.00. Redifon Artificial Horizon type A35/1713 £10.00. Dh Link Tring Equipment: CL1A Compass simulator £10.00, parts also available. CL2 Master indicator £2.50. "M" type differential Servo Unit for master indicator £3.00. Kelvin "Link" Altimeters type KB 578/01 £8.00. Altitude Servo unit £5.00. Airspeed Indicator 60-600 KTS £5.00. Airspeed Servo unit £5.00. Air temp Indicator £1.50. Ambient temp indicator £1.50. Temperature Servo Unit £3.00. For further information S.A.E. 109 Bishops Court, Trumpington, Cambridge. Tel: Trumpington 3454.

FOR SALE. Tequipment Laboratory Oscilloscope. Timebase TD51. Comprehensive triggering and variable sweep delay, 500mV/cm BW 500 MHz. Y amp 1 Type G—Differential, DC-10M (500K at 2mV/cm); Y amp 2 Type J—Single IP, DC-25M (5Hz-100K at 1mV/cm). Unused since recent manufacturer's service and recalibration. £150. Allotrope Limited, 77 Wardour Street, London W.1, 01-437 1892.

MULLARD FERRITE BAR MAGNETS
 100 for £1.25 p.p 16p
MULLARD FERRITE CORES
 LA3 100 to 500 kHz, 50p
 LA4 10 to 30 kHz, 75p
 LA2 100 3 to 200 kHz, 50p
 Please include 10% V.A.T. MAIL ORDER ONLY
XEROZA RADIO,
 1 East Street, Bishops Tawton, Devon. [3012]

GEC METAL-CONE SPKR with/without cabinet, presence unit. 01-883 0748. [2938]
HEWLETT PACKARD 50, MHz Counter Model 5326C, current in 1973 catalogue, used twice, mint condition, with handbook. £285. Box WW 2982.

LARGE quantity test equipment receivers transceivers, meters, various P.S.U.'s; over 1,000 items for immediate disposal. S.A.E., plus 25p, refunded on purchase over £2.00. F.J.C., Comemill, Alvington, Glos. [2881]

LADDERS 8ft. 10in. closed—22ft. 6in. extended £15.64, delivered. Home Sales Ladder Centre, Haldane (Nortn), Halesfield (1), Telford, Shropshire. Tel. 0952 586644. [122]

OLIVETTI P203 PROGRAMMA—OFFICE COMPUTER TYPE RWRIER, four years old. Regularly maintained by manufacturers, now surplus to requirement. Excellent condition. Reasonable offers to Snirey Herridge, Midenhall (6038) 713631. [2922]

OSCILLOSCOPE TELEQUIPMENT type D52, dual trace. Like new, £85 o.n.o. Mr. Harris, 1 Clacton Road, London N17 6UG. Tel. 01-808 3655. [2921]

PLUMBICON TV camera tubes type 55875 brand new, K ystrons type VA-222A, K366A, KY366AU, KY366CDU, KY366BU. Pye Westminster radio-telephone type W25FM low band £100. Philips colour monitor type EL3560, suitable for spares, any offers. Colour monitor decoder units by leading British maker. Designed to BBC standards, units consist of chrominance module, P.A.L. filter and delay module, luminance module and encoded video input module. All units brand new and complete including edge connectors and service manual, £30. Also complete PAL/NTSC switchable decoder by same maker built in a 19in. Isep rack with power unit and sync separator, £75. Philips monitor decoder panels Type EL6818/50F PAL £20; NTSC £15. Advance stabilised power units type PM53, 0-15 volt at 10 amp. Brand new £35. Savage 60J watt audio amp. contains 12 x KT88's, no details. Offers, B. Bamber, 20 Wellington Street, Littleport, Cambs. Tel. 0353 860363. [2904]

PRINTED CIRCUIT BOARD large supplies of glass fibre available. 1/16 in single sided one ounce copper 2p per 3 sq. inches (under 1 ft). 75p per sq. ft. (over 1 ft). 1/16 in double sided one ounce copper 1p per sq. inch (under 1 ft). £1 per sq. ft. (over 1 ft). Please add 10p per sq. foot postage and packing. We can cut to your size at 1p per cut. Solid State Lighting, (Dept. WW), 47 Hercules Rd., Norwich NOR 66M. [116]

Articles For Sale—Continued
PRINTED Circuit Board in 6 widths: 2 in., 2 1/2 in., 3 in., 3 1/2 in., 4 in. and 5 in. x any length; 1/16 in. single-sided fibreglass, 2p per 3 sq. in. Double-sided 1p per sq. in. P & P 5p per order. SAE quotations for other sizes and quantity discounts.—J. Knopp, 11 Connaught Gardens, Baintree, Essex, CM7 6LY. Tel. Braintree 25254. [15]

RF Heaters for sale. One EMI 3KW RF output 3 phase supply. One Raydne 1KW complete with leads and work coils for valve and CRT work. Offers to Mariner Radar Ltd., "Bridleway", Camps Heath, Lowestoft, Suffolk. [2971]

SCOPES. Very special offer. All serviced by Tequipment, and in perfect condition. S43 single beam 15 Mc. bandwidth, £70. D43 double beam 15 Mc. bandwidth, £90. Phone 01-886 9666. [2943]

TELEVISION VALVES, any 10—80p; 50—£3. ECCR2, EY86/7, DY86/7, ECL80, EF80, EF85, EF183, EF184, PCC84, PCC88, PCC189, PC97, PC88/86, PCF80, PCF86, PCL82/84/85, PL36/504, PY800/801. ELECTRONIC MAILORDER LTD., Ramsbottom, Bury, Lancs. [2944]

TELEPRINTER Terminal Unit Type CV-89A/URA-8A, £45. Companion unit to above CM-22A/URA-8A Comparator, £15. Also matching MT-719/URA-8A Rack, £3. T.D.M.S. Unit Type 5AB. As new £8. Creed 7B/N4 Teleprinter in excellent condition. Mains motor £25. Morris, 3 Astley Road, Bradshaw, Nr. Bolton, Lancs. [2933]

TRANSISTORS AND VALVES. All new and tested: 2N3711 7.5p each, £6 per 100 (National Semiconductors). 2D21, 6AU6; 25p. 6AS6, 12AV7, 12BH7; 30p. 6SN7GT, 12BE6, CV6, UR3C; 35p. R17; 45p. E180F, 225DV; 75p. EL37; £1.10. 11E3, E1231, U19; £3.75. KR2A; £4. CV85; £6. Also new but store-soiled, tested: EF36, EF39, UR3C, 12BH7, 6BE6, R17, 35Z4, OZ4, 6K7G, EF50; 20p. KLL32, KT33C, TDD13C, 6BW6, 6K7GT, 12AH8; 30p. Many more. Enquiries welcomed. Lists S.A.E. please. R.F., "Down Barton", Woodham Road, WOKING, Surrey (Mail order only). Postage 15p. [2970]

VACUUM is our speciality. New and second-hand rotary pumps, diffusion outfits, accessories, coaters, etc. Silicone rubber or varnish outgassing equipment from £40. V. N. Barrett (Sales) Ltd., 1 Mayo Road, Croydon. 01-684 9917. [24]

VHF KIT 80-180 MHz receiver, tuner, converter. Transistorised, remarkable performance. £4 or s.a.e. for literature Johnssons (Radio), St. Martins Gate, Worcester, WR1 2DT. [13]

5-N Channel J FETs type 3819F for £1. Full spec. devices complete with circuit details for building voltmeter, timer, ohm-meter, etc. Send 10p for full list of fet's and other top quality transistors available at bargain prices. REDHAWK SALES LTD., 45 STATION ROAD, GERRARDS CROSS, BUCKS. MAIL ORDER ONLY.

60 kHz MSF Rugby and 75 kHz Neuchatel Radio Receivers. Signal and Audio outputs. Small, compact units. Two available versions £35 and £60, Toolex, Bristol Road, Sherborne (3211), Dorset. [21]

STUDIO ELECTRONICS
P.O. BOX No.18 HARLOW ESSEX CM18 6SH
Telephone: Harlow 25457

SPECIALISED KITS

**HIGH STANDARD
LOW FREQUENCY SOURCE**

(to article by J. M. Osborne, W.W. Jan. 73)

A Phase-Locked Loop designer approved kit to professional standards with Glass-Fibre P.C. Board, and all components including Hardware, case, etc. Full constructional details from the designer are included. Reference accurate to 2 parts in 10!!! Probably the most economic high precision signal source availableKit **£24.67**
Assembled and tested version..... **£32.15**
NE561B onlyeach **£4.88**

**CBS-SQ QUADRAPHONIC
IC DECODER**

To Motorola application for MC1312
as described by Geoffrey Shorter (W.W. March 73)

Our complete kit of professional quality components includes a glass-fibre edge connected printed circuit board and is absolutely complete, with full assembly and application notes.

As we also design and manufacture complete stereo and Quadraphonic systems, our wide applications experience is available to you to guarantee professional results.

Complete kit as described above **£8.80**
Assembled and tested production board..... **£12.10**
A full logic board also using MC1314/MC1315 will shortly be available, as will all CBS-SQ records. Send for details.

**PHASE-LOCKED-LOOP
STEREO DECODER**

To Motorola application for MC1310
as described in Wireless World, July 1972

1310 complete kit of professional quality including a glass-fibre edge connected printed circuit board and all components.

Complete kit which can be built in 1/2 hr. **£3.74**
Assembled and tested production board..... **£4.84**
MAZ404 Professional LED 61p extra if required. Economy LED (physically small) 37p extra if required. A current limiting resistor is supplied free upon request with all LEDs. Self powered and special versions are available to order.

NEW PRODUCTS

1. Two tone test oscillator 1 & 2kHz. ideal for SSB setting up. Battery powered professional quality kit **£6.75**
2. Squelch board for FM tuners. Simple add-on advanced circuitry for effective muting. Tuner powered kit **£5.34**.

SPECIALIST SERVICES

Suppliers of products by Radiospares, Eagle, TTC, Sonax, Teleradio and RSGB publications. We welcome enquiries, irrespective of size or nature. A full technical and after-sales-service is provided, with licensed radio amateurs on the technical staff.

Communications acknowledged normally by return.
MAIN DISTRIBUTORS FOR QUADRASONICS, THE PREMIER BRITISH QUADRAPHONIC SYSTEM.

**NO HIDDEN EXTRAS
ALL PRICES INCLUDE VAT,
CARRIAGE and INSURANCE**

PLEASE SUPPLY

enclosed.

KITS ASSEMBLED

CBS-SQ QUAD DECODER
PLL STEREO DECODER
L.F. SOURCE
TWO TONE OSC.
SQUELCH BOARD

NAME

ADDRESS

WW9

"W.W." HI-FI KITS

*** LINSLEY HOOD 15-20W AMPLIFIER**

July 1970 latest and ultimate design. Our kit personally tested and approved by the designer. O/P Tr's matched for spec'd performance. Metal-work now available ensures simple construction of amps. and power supply.

*** BAILEY PRE-AMP (AUG. 1971)**

Superbly engineered kit of this established low noise pre-amp. Uses RH & LH fibreglass PCBs enabling a stereo version to be built in 8 x 2 1/2 x 2 1/2 in. or 8 x 1 1/2 x 5 1/2 in. Basic metalwork ex-stock. Especially recommended to drive 15-20W AB amp.

AFTER-SALES SERVICE at reasonable cost.

REPRINTS of any "W.W." article at 30p } Inc'g p.p. (Stamps accepted)
DETAILED PRICE LISTS at 5p }
Inc'g above and other designs.

*** REFUND GUARANTEED ON ALL PARTS**

SPECIAL OFFER
2N3055 33p each 4 for £1-10
2N3054 22p each 3 for 55p

Unmarked, Tested and Guaranteed. Post and packing 10p per order. Send S.A.E. for list of other devices. See July 1972 advert.

**PERSONAL CALLERS WELCOME—AT OUR
RETAIL SHOP NOW OPEN**

A.1 FACTORS


**245, North Sherwood St.,
Nottingham NG1 4EQ**

Telephone: Nottingham (0602) 46051
Sole proprietor: Douglas de Havilland
(10 a.m.—12 Midnight 7 days/week)

**PRINTED CIRCUITS
& ELECTRONIC EQUIPMENT**

- LARGE & SMALL QUANTITIES
- FULL DESIGN & P.T.H. PROTOTYPE SERVICE
- ASSEMBLIES AT REASONABLE PRICES

for full details contact



**K. J. BENTLEY
& PARTNERS**

18 GREENACRES
ROAD, OLDHAM
Tel 061 624 0939

P O APPROVED

Quartz Crystal Units
ACCURATE RELIABLE

Private enquiries: send 5p in stamps for brochure

THE QUARTZ CRYSTAL CO. LTD.
Q.C.C. WORKS, WELLINGTON CRESCENT,
NEW MALDEN, SURREY. 01-942-0334 & 2988

**A DEXTER
DIMMASWITCH**

ALLOWS COMPLETE

LIGHTING CONTROL



The DEXTER DIMMASWITCH is an attractive Dimma unit which simply replaces the normal light switch. It is available as a complete "ready to install" unit or "simple to assemble" kit. Two models are available controlling up to 300W or 600W of all lights, except fluorescents, at mains 200-250V, 50Hz. All DEXTER DIMMASWITCH models have built-in radio interference suppression. 600 watt **£3.52** Kit form **£2.97**
300 watt **£2.97** Kit form **£2.42**

All plus 12p post and packing
Prices include VAT. Please send c.w.o. to:

DEXTER & COMPANY

**4 ULVER HOUSE
19 KING STREET
CHESTER CH1 2AH
Tel: 0244-25883**

AS SUPPLIED
TO H.M. GOVERNMENT
DEPARTMENTS, HOSPITALS,
LOCAL AUTHORITIES,
ETC.

BRAND NEW FULL SPEC. DEVICES

U.K. CUSTOMERS ADD 10% VAT TO TOTAL

MICROCIRCUITS: 709 24p; 710 36p; 723 51p; 741 (14 pin) 27p; 748 37p. **FET OP. AMP.** £1.62.
TRANSISTORS: 2N2926 (Brown) 6p; 2N3053 15p; 2N3055 35p; 2N3702 10p; 2N3704 10p; 2N3819 26p; 2N4058 12p; BC107A 8p; BC108B 8p; BC109B 8p; BC109C 8p; BCY70 15p; 8FY50/51/52 15p; OC44/45/71/72 12p; AF114/5/6/7 14p; AC126/7/8 12p.

ZENERS: BYZ88 Series 8p. **1 AMP. RECTIFIERS:** 50V 3p; 100V 4p; 200V 4p; 400V 5p; 800V 6p; 1000V 7p. **14 pin IC SOCKETS** 12p. **SOLDER-CONS** 1/2p per pin. **DALO PC PEN** 68p. 1/2W 5% Carbon Film Resistors, E12 values only: 10 of one value per 7p. Sub Min. Vertical Preset Pots (50mW) 100 ohms to 220K 4p each. **LED** with bush and data 26p.

ANTEX S. IRONS: 15W £1-70; 25W £1-75.

Prices at 2nd July. Check our list.

Discounts start at 10% for 10+ Semiconductors or one type.

JEF ELECTRONICS (W.W.) 9

York House, 12 York Drive, Grappenhall, Warrington, WA4 2EJ.

Mail Order Only. C.W.O. P. & P. 10p per order minimum, or at cost if more. List free. Satisfaction or your money back.

DEIMOS LTD

**TAPE RECORDERS FOR
RESEARCH, INDUSTRY AND
PROFESSIONAL AUDIO**

single and multichannel
SIMMONDS ROAD, WINCHEAP
CANTERBURY, KENT

0227-68597

WILMSLOW AUDIO

The firm for speakers!



Fane Pop 100 watt 18" 8/15 ohm.....	£21.45
Fane Pop 60 watt 15" 8/15 ohm.....	£12.26
Fane Pop 50 watt 12" 8/15 ohm.....	£10.17
Fane Pop 25/225 watt 8/15 ohm.....	£5.94
Fane Pop 15 12" 15 watt 8/15 ohm.....	£4.40
Fane 122/10a or 122/12.....	£9.90
Fane Crescendo 15" 8 or 15 ohm.....	£27.20
Fane Crescendo 12" 8 or 15 ohm.....	£24.50
Fane 8" d/cone 808T 8 or 15 ohm.....	£2.64
Fane 8" d/cone, roll surr. 807T 8 or 15 ohm	£3.16
Baker Group 25 3, 8 or 15 ohm.....	£6.00
Baker Group 35, 3, 8 or 15 ohm.....	£7.50
Baker De Luxe 12" d/cone.....	£9.62
Baker Major.....	£7.50
EMI 13 x 8, 3, 8 or 15 ohm.....	£2.25
EMI 13 x 8 type 150 d/cone, 3, 8 or 15 ohm	£2.58
EMI 13 x 8 type 450 t/w, 3, 8 or 15 ohm....	£3.85
EMI 13 x 8 type 350 8 ohm.....	£8.25
EMI 6 1/2" 93850 4 or 8 ohm.....	£2.80
Eiac 9 x 5 59RM 109 15 ohm.....	£2.53
Eiac 9 x 5 59RM 114 8 ohm.....	£2.53
Eiac 6 1/2" d/cone 6RM220 8 ohm.....	£2.59
Eiac 6 1/2" d/cone, roll surr. 6RM171 8 ohm..	£3.22
Eiac 4" tweeter TW4 8 or 15 ohm.....	£1.21
Celestion P58 for Unilux.....	£2.16
Celestion MF 1000 25 watt horn 8 or 15 ohm	£10.45
Eiac 5" 3 ohm.....	£1.75
Eiac 7 x 4" 3 or 8 ohm.....	£1.52
Eiac 8 x 5", 3, 8 or 15 ohm.....	£1.93
Wharfedale Bronze 8 RS/DD.....	£3.11
Wharfedale Super 8 RS/DD.....	£5.50
Wharfedale Super 10 RS/DD.....	£9.80
Goodmans 8P 8 or 15 ohm.....	£3.80
Goodmans 10P 8 or 15 ohm.....	£4.49
Goodmans 12P 8 or 15 ohm.....	£11.55
Goodmans 15P 8 or 15 ohm.....	£17.05
Goodmans 18P 8 or 15 ohm.....	£29.70
Goodmans Twinaxiom 8.....	£6.79
Goodmans Twinaxiom 10.....	£7.61
Goodmans Axent 100.....	£6.60
Eagle DT33 dome tweeter 8 ohm.....	£4.95
Eagle HT15 tweeter 8 ohm.....	£3.46
Eagle CT5 tweeter 8 ohm.....	£1.21
Eagle MHT10 tweeter.....	£3.30
Eagle CT10 tweeter.....	£1.92
Eagle Xovers CN23, 28, 216.....	£1.10
Kef T27.....	£4.67
Kef T15.....	£5.50
Kef B110.....	£6.16
Kef B200.....	£7.42
Kef B139.....	£10.72
Kefkit 2.....	£24.75
Richard Allan 12" d/cone 3 or 15 ohm.....	£2.20
Richard Allan 8" 3, 8 or 15 ohm.....	£2.27
10 x 6" 3, 8 or 15 ohm.....	£1.92
8 x 5" 3 or 8 ohm.....	£1.38
7 x 4" 3 or 8 ohm.....	£1.38
3" 8 ohm or 80 ohm.....	£0.65
2 1/2" 64 ohm.....	£0.65
Speaker matching transformer 3/8/15 ohm	£1.10
Adastra Hiten 10" 10 watt 8 or 15 ohm.....	£2.80
Adastra Top 20 12" 25 watt 8 or 15 ohm....	£6.32

STEPHENSPEAKER KITS AND CABINETS
Send for illustrated brochure and list of recommended speakers.

CAR STEREO SPEAKERS —ask for leaflet
PA/DISCO AMPLIFIERS: (carr. and ins. £1.00)
Baker 100 watt..... £46.00
Linear 30/40..... £25.00
Linear 40/60..... £30.00
Linear 80/100..... £50.00

FREE with speaker orders over £7—"Hi-Fi Loudspeaker Enclosures" book.
All units guaranteed new and perfect.
Prompt despatch
Carriage and insurance 25p per speaker
(Tweeters and Crossovers 15p each)
(All prices quoted inclusive of V.A.T.)

WILMSLOW AUDIO,
Dept WW,
Swan Works, Bank Square, Wilmslow,
Cheshire SK9 1HF.

WW-116 FOR FURTHER DETAILS

EX-COMPUTER STABILISED POWER SUPPLIES

RECONDITIONED, TESTED AND GUARANTEED

Ripple <10mV. Over-voltage protection on all except 24v. 7A. unit. 120-130v. 50 c/s input. Stepdown transformer to suit about £3.

Post & Packing £1-50

5-6v. 8A.....	£12	24v. 7A.....	£14
5-6v. 12A.....	£14	30v. 7A.....	£14
5-6v. 16A.....	£16		

PAPST FANS 4 1/2 x 4 1/2 x 2in. 100 cfm. £3-50 (28p).

PAPST FANS 6in. dia. x 2 1/2in. deep Type 7576 £5-00 (30p).

WOODS FANS 6in. Plastic rotor £6-00 (36p).

ELECTROLYTICS

25,000µ 25v., 20,000µ 30v., 5,000µ 90v., 35,000µ 15v., 3,000µ 150v., 8,000µ 55v., 4 1/2 x 3in. dia. 50p (15p).

68,000µ 16v., 4 1/2 x 2in. dia. 50p (12p).

15,000µ 15v., 10,000µ 35v., 4 1/2 x 2in. dia. 30p (10p).

2,000µ 25v., 15p.

EX-COMPUTER PC PANELS

2 x 4in., min. 35 transistors with data 50p (9p). 25 boards for £1 (25p).

PANELS WITH 4 POWER TRANSISTORS

SIM OC28 50p (9p).

QH Bulbs, 12v. 55w..... 50p (5p)

250 Mixed Resistors..... 60p (8p)

250 Mixed Capacitors..... 60p (8p)

200 SI Planar Diodes..... 50p (5p)

Microswitches..... 8 for 50p (8p)

Min. Glass Neons..... 12 for 50p (5p)

10-way Terminal Blocks..... 10 for 55p (5p)

Postage and package shown in brackets

Please add 10% VAT to prices

KEYTRONICS

Mail Order only.

44 EARLS COURT ROAD, LONDON, W.8

01-478 8499



'SERIES 7' — Studio Monitor Version
One of the world's finest Amplifiers.



GRAMPIAN REPRODUCERS LIMITED
Hanworth Trading Estate, Feltham, Middlesex.
Telephone: 01-894 9141.

CASH IMMEDIATELY AVAILABLE

for redundant and surplus stocks of radio, television, telephone and electronic equipment, or in component form such as meters, plugs and sockets, valves, transistors, semi conductors, capacitors, resistors, cables, copper wire, screws and nuts, speakers, etc.

The larger the quantity the better we like it.

BROADFIELDS & MAYCO DISPOSALS
21 Lodge Lane, London, N12.
Telephone: 01-445 2713 01-445 0749
Evenings: 01-958 7624

EXCLUSIVE OFFERS

INSTRUMENTATION TAPE RECORDER-REPRODUCERS and COMPUTER PERIPHERALS

AMPEX

FR-100B
1" 14 tracks 6 speeds
FR-600
1" and 1/2" 14 and 7 tracks 4 speeds Transistorised


I.B.M.

729
1/2" 7 tracks 6 speeds
MINCOM
CMP-100
1/2" 1" 7 tracks 6 speeds
E.M.I.

TD-1
1/2" 4 tracks 7 speeds
Several other smaller decks.

Full details on request.

Prices of above are from £150 to £700.



COMPUTER HARDWARE

80 col. CARD READER 600 c.p.m.
High speed line PRINTER 1000 l.p.m.
High speed TAPE READER 5 to 8 track 800 c.p.s.

TALLY 5 TO 8 TRACK TAPE READERS
ADDO 5 TO 8 TRACK TAPE PUNCHES

Prices on Application

FREE

40-page list of over 1,000 different items in stock available—keep one by you.

HIGHEST QUALITY 19" RACK MOUNTING CABINETS & RACKS

Our Ref.	Height in inches	Width in inches	Depth in inches	Rack Panel Space in ins.	Price
CB	76	22	20	70	£16 00
CD	69	21	13	68	£10 00
CE	82	22	24	77	£14 00
CF	87	23	26	80	£12 50
CH	83	24	30	75	£14 00
CJ	83	24	24	75	£13 00
CK	83	24	12	75	£10 00
CL	30	40	36	42	£12 50
CM	19	22	18	17	£5 00
CP	69	24	26	61	£13 00
CR	69	30	20	80	£24 00
CT	70	69	27	60	£25 00
CU	87	26	17	—	£20 00
CY	59	24	24	52	£20 00
CZ	64	22	26	58	£14 00
DA	86	22	26	80	£15 00
DB	53	22	22	47	£15 00
DC	64	22	27	37	£17 00
DE	52	40	24	81	£20 00
DF	75	22	26	68	£18 00
DH	70	23	24	122	£20 00
DK	85	22	26	79	£20 00
DL	54	24	19	69	£18 00
DP	74	24	24	66	£18 00
DK	14	21	12	10	£7 00
DS	69	30	20	63	£26 00
DT	84	24	22	90	£24 00

Also Consoles, twin and multi-way Cabinets.

OPEN RACKS

Our Ref.	Height in inches	Channel Depth	Rack Panel Space	Base Bolts	Price
RF	108	5	104	Bolts	£9 00
RD	80	8	77	24 inches	£8 00
RC	66	5	63	Bolts	£8 00
RE	78	7 1/2	70	Bolts	£7 00

Full details of all above on request.

We have a large quantity of "bits and pieces" we cannot list—please send us your requirements we can probably help—all enquiries answered.

- ★ Ferroglyph 30FN Tape Recorders £35 00
- ★ Ferroglyph G 200 Tape Recorders £27 00
- ★ Racal RA-17L Receivers £225 00
- ★ CV-157 Hoffman 18H, SSB Converters £160 00
- ★ National One Sixty Receivers 230 v. £24 00
- ★ 10 foot Triangular Lattice Mast Sections 6 inch sides £9 00
- ★ Casella Assmann Electric Hygrometers £24 00
- ★ Racal RA-17 Cabinets £14 00
- ★ Racal MA-150 Synthesizers £95 00
- ★ Racal MA-250 Decade Generators £125 00
- ★ Avo Geiger Counters, new £7 00
- ★ Servomex 2KVA Voltage Regulators £34 00
- ★ Solartron CD-1016 d/b Oscilloscopes £34 00
- ★ Double Co-axial Blowers 6 x 8 220 v. A.C. £8 00
- ★ Ampex S.E.10 Auto Degaussers £45 00
- ★ Uniselectors 10 bank 25 way full wipe £3 00
- ★ R.C.A. 5 element 420 mc/cps Yagi Beams £4 00
- ★ Haynes 500 watt 230 v./115v. Isolation Transformers £9 00
- ★ Bull 60 column Card Hand Punch £47 00
- ★ Multhead D.888 Analyzers £80 00
- ★ Laboratory Radio Interference Filters £2 00
- ★ Pye Sealamp Galvos £14 00
- ★ Cawkill Type 1471 Variable Filters £70 00
- ★ Zenith 3Kv Insulation Test Sets £14 00
- ★ Adwell large Drafting Tables with parallel motions £24 00
- ★ 54in. dia. Meteorological Balloons £1 50
- ★ Flann Microwave Attenuators 4/12 EMC £40 00

PLEASE ADD V.A.T. TO ABOVE

P. HARRIS ORGANFORD — DORSET
BH16 6ER
BOURNEMOUTH-65051

Guide to Broadcasting Stations

17th Edition

A new edition of a title which has sold more than 250,000 copies. The bulk of the book is devoted to lists of stations broadcasting in the long, medium, short and v.h.f. bands in both frequency and geographical alphabetical order. The book also contains useful information on radio receivers, aerials and earths, propagation, signal identification and reception reports.

1973 206 pp., illustrated
0 592 00081 8 75p

Illustrations in Applied Network Theory

F. E. Rogers

A hundred numerical and algebraic illustrations designed to exemplify practical circuit problems and introduce, in analysis, principles consistent with studies of synthesis that may be pursued later.

1973 240 pp., illustrated
0 408 70425 X cased £5.00
0 408 70426 8 limp £2.50

Obtainable through any bookseller or from

The Butterworth Group

88 Kingsway, London WC2B 6AB
Showroom: 4-5 Bell Yard, WC2.

A.R.R.L. RADIO AMATEUR HANDBOOK 1973

price £2-95

ELECTRONICS IN MUSIC by F. C. Judd. Price £3-30

TRANSMISSION SYSTEMS VOL. I by M. T. Hills. Price £4-95

MOS INTEGRATED CIRCUITS by American Micro Systems, Inc. Price £9

DESIGN OF MAN COMPUTER DIALOGUES by James Martin. Price £8-40

LASER THEORY by F. S. Barnes. Price £4

TRANSISTOR AUDIO AND RADIO CIRCUITS by Mullard. Price £1-95

THE MAZDA BOOK OF PAL RECEIVER SERVICING by D. J. Seal. Price £3-95

ELECTRONIC PUZZLES AND GAMES by M. Mandl. Price £1-30

WORLD RADIO AND TV HANDBOOK 73. Price £3-12

SCR MANUAL 5th EDITION by General Electric. Price £1-65

★ALL PRICES INCLUDE POSTAGE★

THE MODERN BOOK CO.

SPECIALISTS IN SCIENTIFIC & TECHNICAL BOOKS

19-21 PRAED STREET, LONDON, W2 1NP

Phone 723 4185
Closed Sat. 1 p.m.

TRANSFORMERS

DOUGLAS GUARANTEED (Prices include 10% VAT and P. & P.)

Output V. & Amps.	Ref. No.	Price
12V x 2 250 mA x 2	MT 111 CS*	£1 15
12V x 2 500 mA x 2	MT 213 CT*	£1 56
12V x 2 1A x 2	MT 71 AT*	£1 97
12V x 2 2A x 2	MT 18 AT	£2 70
12V x 2 3A x 2	MT 70 AT	£3 34
12V x 2 4A x 2	MT 108 AT	£3 74
12V x 2 5A x 2	MT 72 AT	£4 30

Output Amps.	Ref. No.	Price	Output Amps.	Ref. No.	Price
500 mA	MT 112 CT*	£1 47	1A	MT 21 AT	£4 02
1A	MT 79 AT*	£1 99	5A	MT 51 AT	£5 73
2A	MT 3 AT	£2 92	8A	MT 88 AT	£7 87
3A	MT 20 AT	£3 39	10A	MT 89 AT	£8 75

Output Amps.	Ref. No.	Price	Output Amps.	Ref. No.	Price
500 mA	MT 102 AT*	£1 92	3A	MT 105 AT	£4 98
1A	MT 103 AT	£2 67	4A	MT 106 AT	£5 50
2A	MT 104 AT	£3 93	5A	MT 107 AT	£6 11

Output Amps.	Ref. No.	Price	Output Amps.	Ref. No.	Price
500 mA	MT 124 AT*	£2 03	2A	MT 127 AT	£4 12
1A	MT 126 AT	£2 94	3A	MT 125 AT	£5 78

Power output	Winding tapped at	Ref. No.	Price
20 VA	0-115-210-240	XMT 113 CT	£1 22
75 VA	"	XMT 64 AT	£2 82
150 VA	0-115-200-920-240	XMT 4 AT	£2 85
200 VA	"	XMT 65 AT	£3 84
300 VA	"	XMT 66 AT	£5 06

SAFETY ISOLATORS. 105/120 V. or 200/240 V. In. 105/120 CT or 200/240 CT Out.

VA	Ref. No.	Price	VA	Ref. No.	Price
60	MT 149 AT*	£2 86	250	MT 152 AT*	£7 75
100	MT 150 AT*	£3 51	350	MT 153 AT*	£10 16
200	MT 161 AT*	£6 22	500	MT 154 AT*	£14 55

400 V. Output at 50 HZ. Ref. I73 AT Price
C-D Ignition system by R. M. Marston Esq.
Wireless World. £2-98

Sec. Output (r.m.s.)	Ref. No.	Price
3-0-3 V.	200 mA MT 238 CS*	£1 59
9-0-9	100 mA MT 18 CS*	£1 24
12-0-12	50 mA MT 239 CS*	£1 24
20-0-20	30 mA MT 241 CS*	£1 24
0-20 x 2	300 mA x 2 MT 214 CT*	£1 59
0-8-9 x 2	500 mA x 2 MT 207 CT*	£1 97
0-15-20 x 2	500 mA x 2 MT 205 AT*	£2 85
0-15-27 x 2	500 mA x 2 MT 203 AT*	£3 17
0-15-27 x 2	1A x 2 MT 204 AT*	£4 25
20-12-0-12-20	700 mA (d.c.) MT 221 AT*	£1 58

AT indicates open universal fixing with tags; CT is open U-clamp fixing with P.C. spalls; * with interwinding screen; † untapped 240V Primary; ‡ tapped at 210-240V; other Primaries tapped at 200-220-240V.

Over 200 types in stock through agents or direct. Send for lists.
DOUGLAS ELECTRONIC INDUSTRIES LTD., Direct Sales Dept.
Thames Street, LOUTH, Lincs. LN11-7AD

STEREO IC DECODER

HIGH PERFORMANCE PHASE LOCKED LOOP (as in 'W.W.' July '72)

MOTOROLA MC1310P EX STOCK DELIVERY SPECIFICATION

Separation: 40dB 50Hz-15kHz. Distortion: 0.3%
I/P level: 560mV rms. O/P level: 485mV rms per channel.
Input impedance: 50kΩ. Power requirements: 8-16V at 16mA

Will drive up to 75mA stereo 'on' lamp or LED.

KIT COMPRISES FIBREGLASS PCB (Roller tinned), Resistors, I.C., Capacitors, Preset Potm. & Comprehensive Instructions

LIGHT EMITTING DIODE (Red) Suitable as stereo 'on' indicator. For above with panel mounting clip and instructions

MC1310P only £2-77 plus p.p. 6p

NOTE
As the supplier of the first MC1310P decoder kit, of which we have sold literally thousands, our customers can benefit from our wide experience.

V.A.T. From April 1st add V.A.T. at the standard rate to all prices

FI-COMP ELECTRONICS
BURTON ROAD, EGGINTON, DERBY, DE6 6GY

CLASSIFIED Continued from p. 120

ARTICLES WANTED—Continued
WANTED, all types of communications receivers and test equipment.—Details to R. T. & I. Electronics, Ltd., Ashville Old Hall, Ashville Rd., London, E.11. Ley. 4986. [63]

WE PURCHASE

All types of Electronic Components and Test Equipment. Cash waiting:

TRANNIES

1 Dockyard, Station Road, Old Harrow, Essex.
Tel No. (027-96) 37739 [2934]

CAPACITY AVAILABLE

AIRTRONICS LTD., for Coil Winding—large or small production runs. Also PC Boards Assemblies. Suppliers to P.O., M.O.D., etc. Export enquiries welcomed 3a Walerand Road, London, SE13 7PE. Tel. 01-852 1706. [61]

BATCH Production Wiring and Assembly to sample or drawings. Deane Electricals, 19B Station Parade, Ealing Common, London, W.5. Tel: 01-992 8976. [20]

DESIGN, development, repair, test and small production of electronic equipment. Specialist in production of printed circuit assemblies. **YOUNG ELECTRONICS**, 54 Lawford Road, London, N.W.5. 01-267 0201. [29]

CAPACITY available to the Electronic Industry. Precision turned parts, engraving, milling and grinding both in metals and plastics. Limited capacity available on Mathy SP33 JIG BORER. Write for lists of full plant capacity to C.B. Industrial Engineering Ltd., 1 Mackintosh Lane, E.9 6AB. Tel. 01-985 7057 [14]

BATCH PRODUCTION

Repair and Test of Electronic Equipment. P.C. Board Assemblies.

LYNTON ELECTRONICS,
Lynton House, The Green,
Downham Market, Norfolk.
Phone 036 63 3719. [2927]

IC PRINTED CIRCUITS and electronic assemblies sub-contracted. Reasonable rates and fast turn round. **ATLANTAS HOLDING Co.**, 71 Cranleigh Avenue, North Berwick, East Lothian. Tel. (0620) 3395. [2908]

SMALL Batch Production, wiring, assembly, to sample or drawings. Specialist in printed circuit assemblies. D. & D. Electronics, 42 Bishopsgate, Harlow, Essex. Harlow 33018. [17]

SUB-CONTRACTORS. We have extra capacity available for any quantities on short notice assembly, cable forming. Design and manufacture of electronic equipments under customer's specification is also undertaken. Instrumentation Services, 23 Hallam Road, Clevedon, Somerset. Tel. 2322. [2896]

★
FOR
CLASSIFIED
ADVERTISING
RING
01-261 8508
★

COURSES

RADIO and Radar M.P.T. and C.G.L.I. Courses. Write: Principal, Nautical College, Fleetwood, FY7 8JZ. [25]

EDUCATION

CIE, AMSE, City & Guilds, etc. Thousands of exam successes. Postal courses in all branches of Engineering. Prospectus FREE. State subject of interest: BIET (Dept. ZL BWW 19), Aldermaston Court, Reading RG7 4PF. Accredited by CACC. [19]

NEW GRAM AND SOUND EQUIPMENT

GLASGOW.—Recorders bought, sold, exchanged; cameras, etc., exchanged for recorders or vice-versa.—Victor Morris, 343 Argyle St., Glasgow, C.2. [11]

RECEIVERS AND AMPLIFIERS—SURPLUS AND SECONDHAND

HRO Rx5s, etc., AR88, CR100, BRT400, G209, S640, etc., etc., in stock.—R. T. & I. Electronics, Ltd., Ashville Old Hall, Ashville Rd., London, E.11. Ley. 4986. [65]

SERVICE & REPAIRS

BRISTOL AND DISTRICT. Service to Hi Fi and electronic equipment. Public address installations. Stereo Centre, 309 Gloucester Road, Bristol. Tel: 0272 421395. [26]

EXPERIENCED ENGINEER offers field service facilities London area covering Electronic and Electro-Mechanical equipment—Box No. WW 2676.
SCRATCHED TUBES. Our experienced polishing service can make your colour or monochrome tubes as new again for only £2.75, plus carriage 75p. With absolute confidence sent to Retube Ltd., North Somercote, Louth, Lincs, or 'phone 0507-85 300. [27]
SIGNAL generators, oscilloscopes, output meters, wave voltmeters, frequency meters, multi-range meters, etc., etc., in stock.—R. T. & I. Electronics, Ltd., Ashville Old Hall, Ashville Rd., London, E.11. Ley. 4986. [64]

TENDERS

MANCHESTER EDUCATION COMMITTEE—Tenders are invited for the purchase of second-hand audio-visual aids equipment. Further details and forms of tender from Supplies Officer, Stores Department, New Cross, Manchester, M4 5ES, returnable by 21st September, 1973. [2965]

VALVES WANTED

WE buy new valves, transistors and clean new components, large or small quantities, all details, quotation by return.—Walton's, 55 Worcester St., Wolverhampton. [62]

**DUAL-CHANNEL
50 MHz PULSE GENERATOR**

At £240 in the U.K. the new Bradley 233 Pulse Generator represents real value for money. One of the new generation of precision instruments from Bradley Electronics, it's a true dual-channel instrument which provides full mixing facilities, both output and time, on both of its independent channels.

High performance features include eight PRF ranges, covering 0.5Hz to 50MHz, with pulse delays of 20ns to 1s and widths from 10ns to 1s.

Two independent outputs and two time channels provide exceptional flexibility and versatility. For example, each output can supply A and/or B pulse width ; square wave at internal PRF ; external width or d.c. level. In addition, the outputs can be summed by push-button and a baseline offset will provide any pulse amplitude from $\pm 0.5V$ to $\pm 10V$, from a 50Ω source. And, as a bonus, the B period oscillator can run independently of the A channel, so that the 233 is, in effect, two pulse generators in one case.

The 233 can be used to drive resistive or reactive loads of any magnitude. Seven operating modes include true dual-channel ; series or parallel delay ;


internal burst without an external signal ; output B gated by A width ; square wave ; external gating ; and, of course, single shot.

It's easy to operate, too. Both channels and major functions are selected by push-button while the square wave facility eliminates the need to adjust the delay and width controls during operation. There are also lights to indicate correct triggering.

To find out more about the new-generation Bradley 233 Pulse Generator, please telephone Ashley Stokes on extension 113 at 01-450 7811. Or write to him at the address below.

Our own BCS Certificate is available.

G & E BRADLEY LIMITED,
Electral House, Neasden Lane,
London, NW10 1RR
Telephone : 01-450 7811
Telex : 25583
A Lucas Company



WW-002 FOR FURTHER DETAILS

Multicore- the complete answer for printed circuit soldering.

Most printed circuit soldering problems can be avoided by using quality products and seeking quality advice. Naturally, we suggest ours. First, let's talk about quality products.


Extrusol and Multipure.

EXTRUSOL Extruded Bars and MULTI-PURE Cast Bars are made from specially processed ultra high purity solder. EXTRUSOL bars and pellets are protected by plastic film from the moment they are made to the moment they are used. And MULTI-PURE bars are probably the smoothest and brightest solder bars you will ever see.



Ersin Multicore Savbit.

This cored solder has countless uses. For instance, it avoids erosion of copper plating and wires as well as prolonging the life of soldering iron bits.



For full information on these or any other Multicore products, please write on your company's letterhead direct to: **Multicore Solders Limited**, Maylands Avenue, Hemel Hempstead, Hertfordshire HP2 7EP. Tel: Hemel Hempstead 3636. Telex: 82363.

Liquid Fluxes.

We have a whole family of them, so you're bound to find the right one for your job. One of our latest is Activated RESIN 366 flux, exceptionally fast but non-corrosive and non-conductive.

ROSIN BASE

ERSIN Flux No.	Type	Solids Content w/w	Specifications
0360	non-activated	38%	MIL-F-14256D Type R; DTD 599A
5381	mildly activated Chloride and Bromide free	25%	DIN 8527 F-SW 31
304D 304W	mildly activated Halide Free	10% 25%	MIL-F-14256D Type RMA; DTD 599A
PC. 21A	activated	38%	DIN 8527 Type F-SW 32 DTD 599A
PC. 25	activated	25%	DTD 599A; DIN 8527. F-SW 26
366	activated (extra fast)	38%	DTD 599A; DIN 8527. F-SW 26
366A-25	activated (extra fast)	25%	Meet DIN 8511 Type F-SW 26 and pass DTD 599A Corrosion Test
ORGANIC ACID			
PC. 101	water base	12%	Water soluble residues must be removed after soldering.
PC. 112	solvent base. fast drying	9.5%	
INORGANIC ACID			
ARAX	water base extremely active	40%	Used with most "very difficult to solder" metals. Not for electronics assembly joints.

Solderability Test Instrument.

Already used by major electronic companies throughout the world, this novel instrument saves production costs by controlling solderability of component leads which, unlike a printed circuit, cannot be assessed by a simple "immersion and inspection" test.

Multicore Soldering Chemicals.

We make a complete, compatible range to assist in soldering processes. They clean, protect and preserve.

